

Planned Agenda

- 1. NRC Introduction & Meeting Purpose:** *M. Srinivasan*
- 2. Overview of PNNL Research Project:** *S. Bruemmer*
- 3. Review of SCC Crack-Growth Test Systems:** *M. Toloczko*
- 4. Test Plans and Initial Test Results:** *Bruemmer, Toloczko*
- 5. Discussion of Programmatic Challenges:** *S. Bruemmer*
- 6. Opportunity for Public Questions/Comments**
- 7. Crack and Crack-Tip Observations on Alloy 600 and Alloy 182 CRDM Components:** *S. Bruemmer*



SCC Crack Growth System Design and Construction

*Mychailo Toloczko, John Keaveney
and Steve Bruemmer*

Pacific Northwest National Laboratory

Project Kick-Off Meeting
Richland, Washington

May 3, 2005

Research Supported by
U.S. Nuclear Regulatory Commission

Presentation Outline

- **CGR System Design Requirements and Decision**
- **Review and Assessment of CGR System**
 - Loadline & load control
 - Pressure & temperature control
 - Water chemistry control
 - DCPD measurement
 - System control & automation
- **Review and Assessment of Peripheral Systems**
 - Pre-cracking station
 - Ultra-high purity make-up water system
- **Construction & Assembly Status**

SCC Crack Growth System Essentials

- **Long term static loading with load control**
- **Water temperatures to 360°C (3000 psi)**
- **Circulating ultra pure water (18 Mohm-cm) with chemistry control for simulated BWR/PWR conditions**
- **In-situ, high-res. crack length measurement**
- **Active control of key system variables**
- **Continuous data acquisition**
 - load, crack length, temperature, water resistivity, oxygen content, ECP

Options for System Design

➤ **Design our own**

- Lengthy design cycle
- Unproven design
- Finding appropriate components

➤ **Purchase ready-made system**

- Few vendors
- System limitations (expandability, repairability)
- Potentially high cost

➤ **Base the design on an existing system**

- Fast design cycle
- Proven design
- Cost efficient to achieve project objectives

General Electric Global Research

- World leader for quantitative SCC crack-growth-rate testing of LWR materials and they have led key international round-robin test programs.
- 25 years of development and test system evolution, unmatched experience with ECP control and DCPD, unique control and data acquisition software.
- Pioneered ultra-high-purity, make-up water system (outlet resistivity better than 15 Mohm-cm) for BWR applications and for isolation of impurity effects
- Recent PWR experience (290-360°C, B/Li water) evaluating Ni-base alloys and stainless steels
- Peter Andresen and his team have advised in the construction of SCC crack-growth systems for many laboratories over the last 10 years.

Elements of G.E. SCC CGR System

➤ **CGR System**

- Loadline and loading
- Water system (flow, pressure, temperature, chemistry control)
- Temperature controller
- In-situ crack length measurement (DCPD)
- System control & data acquisition

➤ **Peripheral Systems**

- Pre-cracking station
- Ultra-high purity make-up water system

Features of G.E. Systems


- **Many parts are "off-the-shelf"**
 - Inexpensive
 - Most items are rebuildable
- **Full control over loading system, incl. const K**
- **State-of-the-art DC potential drop for crack length measurement**
- **Low pressure loop for chemistry control**
- **High pressure loop**
- **Careful attention to seal materials**
- **Mature software package for continuous system control and data acquisition**

PNNL Approach to SCC System Design


- **Subcontract with GE Global to enable rapid and cost effective construction of state-of-the-art crack-growth test systems**
- **Assess individual elements of the elements of the GE system design and components**
- **Determine where improvements are possible**
 - System layout
 - Major components
 - Wetted materials
- **Incorporate improvements into design and establish cost basis for complete system**

Evaluation of Loadline

- **Sturdy loadframe**
- **Selected servo-electric motor**
 - Excellent long term static loading & positioning
- **Four-bar cage to support upper pullrod & clevis**
- **One mechanical feed-through on autoclave base**
 - feed-through sealed with a virgin teflon seal good to $\sim 280^{\circ}\text{C}$
 - water pressure applies a load on pullrod
 - pressure load factored into total specimen load
- **Sufficient room for two 0.5T specimens**
- **Components are manually aligned using a special alignment rod**



SCC Water System Block Diagram




Evaluation of Water System

➤ **General features**

- 316L SS tubing and compression fittings
- Low-leaching seals (viton, virgin teflon)
- Low pressure loop for chemistry control
- High pressure loop
- All water runs through a demineralizer and submicron filter

Evaluation of Water System


- **Low pressure mixing loop**
 - **Glass column for dissolving gasses**
 - **Dissolved gas content controlled by partial pressure (bottle containing target gas & Ar) or by overpressure**
 - **Impurity reservoir with injection pump**
 - boron & lithium
 - sulfates
 - **Conductivity sensor**
 - measure water quality
 - control injection pump
 - **Other sensors such as pH, dissolved oxygen will be added**



Evaluation of Water System

➤ High pressure loop

- **Piston pump creates high pressure**
 - adjustable flow rate
- **Back pressure regulator**
 - pressure control
- **Pulsation damper**
 - less than 3 psi peak-to-peak
- **Water conductivity measured at end of high pressure loop**
 - measure of water purity
- **Water flows from top to bottom of autoclave**
 - minimizes stagnation



Evaluation of Water System

- **Cost effective, efficient design**
- **Very little to improve upon**
- **Upgraded conductivity sensors and meters**
 - temperature measurement, more analog outputs
- **Careful evaluation of pulsation damper specs**
- **Careful evaluation of seal materials in flow meter, back pressure regulators, pulsation damper, etc.**
- **Reduced length of heated tubing to improve purity of water entering the autoclave**

Evaluation of Temperature Control

➤ Heating


- Step 1: coaxial heat exchanger
- Step 2: preheater
- Step 3: autoclave heater

➤ Cooling

- Step 1: coaxial heat exchanger with incoming water
- Step 2: coaxial water cooler with building coolant



➤ Control: Temperature controllers for preheater and autoclave heater

➤ Will evaluate magnitude of temperature gradients in autoclave



Evaluation of Crack Length

- **Reversing DC potential drop Measurement**
 - compensates for work function between dissimilar metals
 - setup to read stabilized voltage
- **Reference potential**
 - compensate for temperature effects on resistivity
- **DCPD estimates crack length via existing calibration curve**
- **All DCPD data written to data file**



Evaluation of Data Acq. & System Control

➤ **Data acquisition**

- DCPD, reference voltage, applied current, water mixing loop conductivity, water outlet conductivity, autoclave water temperature, corrosion potential, dissolved oxygen
- **May add: water pressure logging, mixing loop water temperature logging**

➤ **PC used to control load on specimen**


- Inputs for load control include specimen crack length from DCPD and water pressure which is entered manually
- Constant K testing
- Cyclic K with variable hold time

➤ **Automatic shutdown**

- run-away crack
- system overtemperature

Evaluation of Make-up Water System

- **UV light kills organics**
- **Demineralizer for ions**
- **Submicron filter for particulates**
- **N₂ gas to displace oxygen**
- **18.18 Mohm-cm is the typical water resistivity (theoretical purity)**



Pre-cracking

- **Instron servo-hydraulic used for pre-cracking**
- **Crack length measured from DCPD**
- **GE software package controls the Instron and pre-cracking routine.**



Construction & Assembly Status

- **System #1 running continuously for 60 days**
 - Simultaneously oxidizing autoclave internals and performing a shakedown test on cold-worked 316 SS sample
 - Excellent system cleanliness with outlet resistivity better than 10 Mohm-cm and still rising
 - Excellent system performance
- **System #2 is 80% complete**
 - Completion expected by end of May
 - Oxidation and shakedown test will follow
- **System #3 is 30% complete**
 - Completion next fiscal year