

May 23, 2005

U.S. Nuclear Regulatory Commission
ATTN: Document Control Desk
Washington, D.C. 20555

Gentlemen:

In the Matter of) Docket No. 50-328
Tennessee Valley Authority)

**SEQUOYAH NUCLEAR PLANT (SQN) - UNIT 2 CYCLE 14 CORE OPERATING
LIMITS REPORT (COLR)**

In accordance with the SQN Unit 2 Technical Specifications
6.9.1.14.c, enclosed is the Unit 2 Cycle 14 COLR.

Please direct questions concerning this issue to me at
(423) 843-7170 or J. D. Smith at (423) 843-6672.

Sincerely,

Original signed by:

P. L. Pace
Manager, Site Licensing and
Industry Affairs

Enclosure

SEQUOYAH UNIT 2 CYCLE 14
CORE OPERATING LIMITS REPORT

REVISION 0

April 2005

Prepared by:

Originally Signed by T. D. Beu / 05/03/2005
Nuclear Fuel Design / Date

Verified by:

Originally Signed by John Strange / 05/03/2005
Nuclear Fuel Design / Date

Reviewed by:

Originally Signed by James F. Lemons / 05/03/2005
Nuclear Fuel Design Manager / Date

Originally Signed by R. S. Hawn / 05/04/2005
Reactor Engineering Supervisor / Date

Approved by:

Originally Signed by Heywood R. Rogers (# 6242) / 05/06/2005
PORC Chairman / Date

Originally Signed by D. A. Kulisek / 05/06/2005
Plant Manager / Date

Revision 0

Pages affected

Reason for Revision _____

SEQUOYAH UNIT 2 CYCLE 14

1.0 CORE OPERATING LIMITS REPORT

This Core Operating Limits Report (COLR) for Sequoyah Unit 2 Cycle 14 has been prepared in accordance with the requirements of Technical Specification (TS) 6.9.1.14.

The TSs affected by this report are listed below:

TABLE 2.2-1 $f_1(\Delta I)$ trip reset function for OT Δ T Trip (QTNL, QTPL) and rates of trip setpoint decrease per percent ΔI (QTNS, QTPS)

TABLE 2.2-1 $f_2(\Delta I)$ trip reset function for OP Δ T Trip (QPNL, QPPL) and rates of trip setpoint decrease per percent ΔI (QPNS, QPPS)

3/4.1.1.3	Moderator Temperature Coefficient (MTC)
3/4.1.3.5	Shutdown Rod Insertion Limit
3/4.1.3.6	Control Rod Insertion Limits
3/4.2.1	Axial Flux Difference (AFD)
3/4.2.2	Heat Flux Hot Channel Factor ($F_Q(X,Y,Z)$)
3/4.2.3	Nuclear Enthalpy Rise Hot Channel Factor ($F_{\Delta H}(X,Y)$)

2.0 OPERATING LIMITS

The cycle-specific parameter limits for the specifications listed in section 1.0 are presented in the following subsections. These limits have been developed using the NRC approved methodologies specified in TS 6.9.1.14.

The following abbreviations are used in this section:

BOL stands for Beginning of Cycle Life
ARO stands for All Rods Out
HZP stands for Hot Zero THERMAL POWER
EOL stands for End of Cycle Life
RTP stands for RATED THERMAL POWER

2.1 Moderator Temperature Coefficient - MTC (Specification 3/4.1.1.3)

2.1.1 The MTC limits are:

The BOL/ARO/HZP MTC shall be less positive than 0 $\Delta k/k/^\circ F$ (BOL limit). With the measured BOL/ARO/HZP MTC more positive than $-0.12 \times 10^{-5} \Delta k/k/^\circ F$ (as-measured MTC limit), establish control rod withdrawal limits to ensure the MTC remains less positive than 0 $\Delta k/k/^\circ F$ for all times in core life.

The EOL/ARO/RTP MTC shall be less negative than or equal to $-4.5 \times 10^{-4} \Delta k/k/^\circ F$.

SEQUOYAH UNIT 2 CYCLE 14

2.1.2 The 300 ppm surveillance limit is:

The measured 300 ppm/ARO/RTP MTC should be less negative than or equal to $-3.75 \times 10^{-4} \Delta k/k/^\circ F$.

2.2 Shutdown Rod Insertion Limit (Specification 3/4.1.3.5)

2.2.1 The shutdown rods shall be withdrawn to a position as defined below:

<u>Cycle Burnup (MWD/MTU)</u>	<u>Steps Withdrawn</u>
≥ 0	≥ 225 to ≤ 231

2.3 Control Rod Insertion Limits (Specification 3/4.1.3.6)

2.3.1 The control rod banks shall be limited in physical insertion as shown in Figure 1.

2.4 Axial Flux Difference - AFD (Specification 3/4.2.1)

2.4.1 The axial flux difference (AFD) limits (AFD^{Limit}) are provided in Figure 2.

2.5 Heat Flux Hot Channel Factor - $F_Q(X,Y,Z)$ (Specification 3/4.2.2)

$F_Q(X,Y,Z)$ shall be limited by the following relationships:

$$F_Q(X,Y,Z) \leq \frac{F_Q^{RTP}}{P} * K(Z) \quad \text{for } P > 0.5$$

$$F_Q(X,Y,Z) \leq \frac{F_Q^{RTP}}{0.5} * K(Z) \quad \text{for } P \leq 0.5$$

where P = Thermal Power / Rated Thermal Power

2.5.1 $F_Q^{RTP} = 2.50$

2.5.2 $K(Z)$ is provided in Figure 3.

SEQUOYAH UNIT 2 CYCLE 14

The following parameters are required for core monitoring per the Surveillance Requirements of Specification 3/4.2.2:

2.5.3 $NSLOPE^{AFD} = 1.11$

where $NSLOPE^{AFD} =$ Negative AFD limit adjustment required to compensate for each 1% that $F_Q(X,Y,Z)$ exceeds BQDES.

2.5.4 $PSLOPE^{AFD} = 1.49$

where $PSLOPE^{AFD} =$ Positive AFD limit adjustment required to compensate for each 1% that $F_Q(X,Y,Z)$ exceeds BQDES.

2.5.5 $NSLOPE^{f_2(\Delta I)} = 1.38$

where $NSLOPE^{f_2(\Delta I)} =$ Adjustment to negative OP Δ T $f_2(\Delta I)$ limit required to compensate for each 1% that $F_Q(X,Y,Z)$ exceeds BCDES.

2.5.6 $PSLOPE^{f_2(\Delta I)} = 1.64$

where $PSLOPE^{f_2(\Delta I)} =$ Adjustment to positive OP Δ T $f_2(\Delta I)$ limit required to compensate for each 1% that $F_Q(X,Y,Z)$ exceeds BCDES.

2.5.7 $BQNOM(X,Y,Z) =$ Nominal design peaking factor, increased by an allowance for the expected deviation between the nominal design power distribution and the measurement.

2.5.8 $BQDES(X,Y,Z) =$ Maximum allowable design peaking factor which ensures that the $F_Q(X,Y,Z)$ limit will be preserved for operation within the LCO limits, including allowances for calculational and measurement uncertainties.

2.5.9 $BCDES(X,Y,Z) =$ Maximum allowable design peaking factor which ensures that the centerline fuel melt limit will be preserved for operation within the LCO limits, including allowances for calculational and measurement uncertainties.

$BQNOM(X,Y,Z)$, $BQDES(X,Y,Z)$, and $BCDES(X,Y,Z)$ data bases are provided for input to the plant power distribution analysis codes on a cycle specific basis and are determined using the methodology for core limit generation described in the references in Specification 6.9.1.14.

2.5.10 The increase in $F_Q^M(X,Y,Z)$ for compliance with the 4.2.2.2.e Surveillance Requirements is defined as follows:

For cycle burnups < 3193 MWd/MTU	2.0%
For cycle burnups \geq 3193 MWd/MTU to \leq 5007 MWd/MTU	2.7%
For cycle burnups > 5007 MWd/MTU	2.0%

SEQUOYAH UNIT 2 CYCLE 14

2.6 Nuclear Enthalpy Rise Hot Channel Factor - $F_{\Delta H}(X,Y)$ (Specification 3/4.2.3)

$F_{\Delta H}(X,Y)$ shall be limited by the following relationship:

$$F_{\Delta H}(X,Y) \leq \text{MAP}(X,Y,Z) / \text{AXIAL}(X,Y)$$

2.6.1 $\text{MAP}(X,Y,Z)$ is provided in Table 1.

$\text{AXIAL}(X,Y)$ is the axial peak from the normalized axial power shape.

The following parameters are required for core monitoring per the Surveillance Requirements of Specification 3/4.2.3:

$$F_{\Delta HR^M}(X,Y) \leq \text{BHNOM}(X,Y)$$

$$\text{where } F_{\Delta HR^M}(X,Y) = F_{\Delta H}(X,Y) / [\text{MAP}^M / \text{AXIAL}(X,Y)]$$

$F_{\Delta H}(X,Y)$ is the measured radial peak at location X,Y.

MAP^M is the value of $\text{MAP}(X,Y,Z)$ obtained from Table 1 for the measured peak.

2.6.2 $\text{BHNOM}(X,Y)$ = Nominal design radial peaking factor, increased by an allowance for the expected deviation between the nominal design power distribution and the measurement.

2.6.3 $\text{BHDES}(X,Y)$ = Maximum allowable design radial peaking factor which ensures that the $F_{\Delta H}(X,Y)$ limit will be preserved for operation within the LCO limits, including allowances for calculational and measurement uncertainties.

2.6.4 $\text{BRDES}(X,Y)$ = Maximum allowable design radial peaking factor which ensures that the steady state DNBR limit will be preserved for operation within the LCO limits, including allowances for calculational and measurement uncertainties.

$\text{BHNOM}(X,Y)$, $\text{BHDES}(X,Y)$ and $\text{BRDES}(X,Y)$ data bases are provided for input to the plant power distribution analysis computer codes on a cycle specific basis and are determined using the methodology for core limit generation described in the references in Specification 6.9.1.14.

2.6.5 $\text{RRH} = 3.34$ when $0.8 < P \leq 1.0$

$\text{RRH} = 1.67$ when $P \leq 0.8$

where RRH = Thermal power reduction required to compensate for each 1% that $F_{\Delta H}(X,Y)$ exceeds its limit.

P = Thermal Power / Rated Thermal Power

SEQUOYAH UNIT 2 CYCLE 14

2.6.6 TRH = 0.0334 when $0.8 < P \leq 1.0$

TRH = 0.0167 when $P \leq 0.8$

where TRH = Reduction in OT Δ T K1 setpoint required to compensate for each 1% F Δ H(X,Y) exceeds its limit.

P = Thermal Power / Rated Thermal Power

2.6.7 All cycle burnups shall use a 2% increase in F Δ HM (X,Y) margin for compliance with the 4.2.3.2.d.1 Surveillance Requirement.

3.0 REACTOR CORE PROTECTIVE LIMITS

3.1 Trip Reset Term [$f_1(\Delta I)$] for Overtemperature Delta T-Trip (Specification 2.2.1)

The following parameters are required to specify the power level-dependent $f_1(\Delta I)$ trip reset term limits for the Overtemperature Delta-T trip function:

3.1.1 QTNL = -20%

where QTNL = Maximum negative ΔI setpoint at rated thermal power at which the trip setpoint is not reduced by the axial power distribution.

3.1.2 QTPL = +5%

where QTPL = Maximum positive ΔI setpoint at rated thermal power at which the trip setpoint is not reduced by the axial power distribution.

3.1.3 QTNS = 2.50%

where QTNS = Percent reduction in Overtemperature Delta-T trip setpoint for each percent that the magnitude of ΔI exceeds its negative limit at rated thermal power (QTNL).

3.1.4 QTPS = 1.40%

where QTPS = Percent reduction in Overtemperature Delta-T trip setpoint for each percent that the magnitude of ΔI exceeds its positive limit at rated thermal power (QTPL).

SEQUOYAH UNIT 2 CYCLE 14

3.2 Trip Reset Term [$f_2(\Delta I)$] for Overpower Delta-T Trip (Specification 2.2.1)

The following parameters are required to specify the power level-dependent $f_2(\Delta I)$ trip reset term limits for the Overpower Delta-T trip function:

3.2.1 QPNL = -25%

where QPNL = Maximum negative ΔI setpoint at rated thermal power at which the trip setpoint is not reduced by the axial power distribution.

3.2.2 QPPL = +25%

where QPPL = Maximum positive ΔI setpoint at rated thermal power at which the trip setpoint is not reduced by the axial power distribution.

3.2.3 QPNS = 1.70%

where QPNS = Percent reduction in Overpower Delta-T trip setpoint for each percent that the magnitude of ΔI exceeds its negative limit at rated thermal power (QPNL).

3.2.4 QPPS = 1.70%

where QPPS = Percent reduction in Overpower Delta-T trip setpoint for each percent that the magnitude of ΔI exceeds its positive limit at rated thermal power (QPPL).

SEQUOYAH UNIT 2 CYCLE 14

Table 1

Maximum Allowable Peaking Limits MAP(X,Y,Z)

AXIAL(X,Y)	ELEVATION (ft)	MAP(X,Y,Z)	AXIAL(X,Y)	ELEVATION (ft)	MAP(X,Y,Z)
1.1	2	1.9540	1.9	2	2.8169
	4	1.9494		4	3.1537
	6	1.9431		6	3.0026
	8	1.9337		8	2.8465
	10	1.9147		10	2.6987
1.2	2	2.1780	>1.9	2	2.5377
	4	2.1682		4	2.8412
	6	2.1543		6	2.7051
	8	2.1317		8	2.5644
	10	2.0855		10	2.4313
1.3	2	2.4025	2.2	2	2.6873
	4	2.3875		4	3.3150
	6	2.3672		6	3.1660
	8	2.3029		8	3.0227
	10	2.1902		10	2.7136
1.4	2	2.6264	2.6	2	2.6965
	4	2.6047		4	3.5807
	6	2.5629		6	3.5514
	8	2.4204		8	3.3102
	10	2.2893		10	2.9726
1.5	2	2.8525	3.0	2	2.9517
	4	2.8119		4	3.8016
	6	2.6771		6	4.1225
	8	2.5251		8	3.6877
	10	2.3839		10	3.3466
1.7	2	2.7765	3.5	2	3.1500
	4	3.0191		4	4.1097
	6	2.8610		6	4.1197
	8	2.7036		8	3.7296
	10	2.5528		10	3.4811

SEQUOYAH UNIT 2 CYCLE 14




FIGURE 1
Rod Bank Insertion Limits Versus
Thermal Power, Four Loop Operation

*Fully withdrawn region shall be the condition where shutdown and control banks are at a position within the interval of ≥ 225 and ≤ 231 steps withdrawn, inclusive.

Fully withdrawn shall be the position as defined below,

$$\frac{\text{Cycle Burnup (MWd/mtU)}}{\geq 0}$$

$$\frac{\text{Steps Withdrawn}}{\geq 225 \text{ to } \leq 231}$$

This figure is valid for operation at a rated thermal power of 3455 MWt when the LEFM is in operation.

If the LEFM becomes inoperable, then prior to the next NIS calibration, the maximum allowable power level must be reduced by 1.3% in power, and the rod insertion limit lines must be increased by 3 steps withdrawn until the LEFM is returned to operation.




FIGURE 2

**Axial Flux Difference Limits As
A Function of Rated Thermal Power**

This figure is valid for operation at a rated thermal power of 3455 MWt when the LEFM is in operation.

If the LEFM becomes inoperable, then prior to the next NIS calibration, the maximum allowable power level must be reduced by 1.3% in power, and the AFD limit lines must be made more restrictive by 1% in AFD until the LEFM is returned to operation.

SEQUOYAH UNIT 2 CYCLE 14




FIGURE 3

K(Z) - Normalized FQ(X,Y,Z) as a Function of Core Height