

ACTIONS (continued)

CONDITION	REQUIRED ACTION	COMPLETION TIME
<p>C. KHU or its required overhead emergency power path inoperable due to reasons other than Condition A.</p>	<p>C.1 Perform SR 3.8.1.3 for OPERABLE KHU.</p>	<p>1 hour if not performed in previous 12 hours</p> <p><u>AND</u></p> <p>Once per 7 days thereafter</p>
	<p><u>AND</u></p>	
	<p>C.2.1 Restore the KHU and its required overhead emergency power path to OPERABLE status.</p>	<p>-----NOTE-----</p> <p>An additional 96 hours can be added to the following completion times. This expires on August 27, 2005 @ 1058 hours</p> <p>-----</p> <p>72 hours</p> <p><u>AND</u></p> <p>72 hours from discovery of inoperable KHU</p>
	<p><u>OR</u></p>	
	<p>C.2.2.1 Energize both standby buses from LCT via isolated power path.</p>	<p>72 hours</p> <p><u>AND</u></p> <p>1 hour from subsequent discovery of deenergized standby bus</p>
<p><u>AND</u></p>		
<p>C.2.2.2 Suspend KHU generation to grid except for testing.</p>	<p>72 hours</p> <p><u>AND</u></p> <p>(continued)</p>	