MANUAL HARD COPY DISTRIBUTION
DOCUMENT TRANSMITTAL 2005-35884

USER INFORMATION:

GERLACH*ROSE M EMPL#:028401 CA#: 0363

Address: NUCSA2

Phone#: 254-3194

TRANSMITTAL INFORMATION:

TO: GERLACH*ROSE M 08/25/2005
LOCATION: USNRC
FROM: NUCLEAR RECORDS DOCUMENT CONTROL CENTER (NUCSA-2)
THE FOLLOWING CHANGES HAVE OCCURRED TO THE HARDCOPY OR ELECTRONIC MANUAL ASSIGNED TO YOU:

TSB2 - TECHNICAL SPECIFICATIONS BASES UNIT 2 MANUAL

REMOVE MANUAL TABLE OF CONTENTS DATE: 07/08/2005

ADD MANUAL TABLE OF CONTENTS DATE: 08/24/2005

CATEGORY: DOCUMENTS TYPE: TSB2
ID: TEXT 3.6.1.3
REMOVE: REV:1

ADD: REV: 2

CATEGORY: DOCUMENTS TYPE: TSB2
ID: TEXT LOES
REMOVE: REV:60

A001

ADD: REV: 61

UPDATES FOR HARD COPY MANUALS WILL BE DISTRIBUTED WITHIN 5 DAYS IN ACCORDANCE WITH DEPARTMENT PROCEDURES. PLEASE MAKE ALL CHANGES AND ACKNOWLEDGE COMPLETE IN YOUR NIMS INBOX UPON RECEIPT OF HARD COPY. FOR ELECTRONIC MANUAL USERS, ELECTRONICALLY REVIEW THE APPROPRIATE DOCUMENTS AND ACKNOWLEDGE COMPLETE IN YOUR NIMS INBOX.

Manual Name: TSB2

Manual Title: TECHNICAL SPECIFICATIONS BASES UNIT 2 MANUAL

Table Of Contents

Issue Date: 07/08/2005

Procedure Name	Rev	Issue Date	Change ID	Change Number
TEXT LOES	60	07/06/2005		
Title: LIST OF EFFECTIVE SECTIONS				
TEXT TOC	7	04/18/2005		
Title: TABLE OF CONTENTS				
TEXT 2.1.1	1	10/27/2004		
Title: SAFETY LIMITS (SLS) REACTOR CORE SLS				
TEXT 2.1.2	0	11/18/2002		
Title: SAFETY LIMITS (SLS) REACTOR COOLANT SYSTEM (RCS) PRESSURE SL				
TEXT 3.0	1	04/18/2005		
Title: LIMITING CONDITION FOR OPERATION (LCO) APPLICABILITY				
TEXT 3.1.1	1	03/24/2005		
Title: REACTIVITY CONTROL SYSTEMS SHUTDOWN MARGIN (SDM)				
TEXT 3.1.2	0	11/18/2002		
Title: REACTIVITY CONTROL SYSTEMS REACTIVITY ANOMALIES				
TEXT 3.1.3	1	07/06/2005		
Title: REACTIVITY CONTROL SYSTEMS CONTROL ROD OPERABILITY				
TEXT 3.1.4	2	07/06/2005		
Title: REACTIVITY CONTROL SYSTEMS CONTROL ROD SCRAM TIMES				
TEXT 3.1.5	1	07/06/2005		
Title: REACTIVITY CONTROL SYSTEMS CONTROL ROD SCRAM ACCUMULATORS				
TEXT 3.1.6	2	03/24/2005		
Title: REACTIVITY CONTROL SYSTEMS ROD PATTERN CONTROL				

CONTROLLED

Manual Name: TSB2

Manual Title: TECHNICAL SPECIFICATIONS BASES UNIT 2 MANUAL

TEXT 3.1.7 0 11/18/2002
Title: REACTIVITY CONTROL SYSTEMS STANDBY LIQUID CONTROL (SLC) SYSTEM

TEXT 3.1.8 0 11/18/2002
Title: REACTIVITY CONTROL SYSTEMS SCRAM DISCHARGE VOLUME (SDV) VENT AND DRAIN VALVES

TEXT 3.2.1 1 03/24/2005
Title: POWER DISTRIBUTION LIMITS AVERAGE PLANAR LINEAR HEAT GENERATION RATE (APLHGR)

TEXT 3.2.2 1 03/24/2005
Title: POWER DISTRIBUTION LIMITS MINIMUM CRITICAL POWER RATIO (MCPR)

TEXT 3.2.3 0 11/18/2002
Title: POWER DISTRIBUTION LIMITS LINEAR HEAT GENERATION RATE (LHGR)

TEXT 3.3.1.1 2 07/06/2005
Title: INSTRUMENTATION REACTOR PROTECTION SYSTEM (RPS) INSTRUMENTATION

TEXT 3.3.1.2 0 11/18/2002
Title: INSTRUMENTATION SOURCE RANGE MONITOR (SRM) INSTRUMENTATION

TEXT 3.3.1.3 0 11/22/2004
Title: OPRM INSTRUMENTATION

TEXT 3.3.2.1 1 02/17/2005
Title: INSTRUMENTATION CONTROL ROD BLOCK INSTRUMENTATION

TEXT 3.3.2.2 0 11/18/2002
Title: INSTRUMENTATION FEEDWATER - MAIN TURBINE HIGH WATER LEVEL TRIP INSTRUMENTATION

TEXT 3.3.3.1 2 07/06/2005
Title: INSTRUMENTATION POST ACCIDENT MONITORING (PAM) INSTRUMENTATION

TEXT 3.3.3.2 1 04/18/2005
Title: INSTRUMENTATION REMOTE SHUTDOWN SYSTEM

Manual Name: TSB2

Manual Title: TECHNICAL SPECIFICATIONS BASES UNIT 2 MANUAL

TEXT 3.3.4.1 0 11/18/2002
Title: INSTRUMENTATION END OF CYCLE RECIRCULATION PUMP TRIP (EOC-RPT) INSTRUMENTATION

TEXT 3.3.4.2 0 11/18/2002
Title: INSTRUMENTATION ANTICIPATED TRANSIENT WITHOUT SCRAM RECIRCULATION PUMP TRIP (ATWS-RPT) INSTRUMENTATION

TEXT 3.3.5.1 3 07/06/2005
Title: INSTRUMENTATION EMERGENCY CORE COOLING SYSTEM (ECCS) INSTRUMENTATION

TEXT 3.3.5.2 0 11/18/2002
Title: INSTRUMENTATION REACTOR CORE ISOLATION COOLING (RCIC) SYSTEM INSTRUMENTATION

TEXT 3.3.6.1 1 11/09/2004
Title: INSTRUMENTATION PRIMARY CONTAINMENT ISOLATION INSTRUMENTATION

TEXT 3.3.6.2 1 11/09/2004
Title: INSTRUMENTATION SECONDARY CONTAINMENT ISOLATION INSTRUMENTATION

TEXT 3.3.7.1 0 11/18/2002
Title: INSTRUMENTATION CONTROL ROOM EMERGENCY OUTSIDE AIR SUPPLY (CREOAS) SYSTEM INSTRUMENTATION

TEXT 3.3.8.1 1 09/02/2004
Title: INSTRUMENTATION LOSS OF POWER (LOP) INSTRUMENTATION

TEXT 3.3.8.2 0 11/18/2002
Title: INSTRUMENTATION REACTOR PROTECTION SYSTEM (RPS) ELECTRIC POWER MONITORING

TEXT 3.4.1 2 11/22/2004
Title: REACTOR COOLANT SYSTEM (RCS) RECIRCULATION LOOPS OPERATING

TEXT 3.4.2 0 11/18/2002
Title: REACTOR COOLANT SYSTEM (RCS) JET PUMPS

TEXT 3.4.3 0 11/18/2002
Title: REACTOR COOLANT SYSTEM (RCS) SAFETY/RELIEF VALVES (S/RVS)

Manual Name: TSB2

Manual Title: TECHNICAL SPECIFICATIONS BASES UNIT 2 MANUAL

TEXT 3.4.4 0 11/18/2002
Title: REACTOR COOLANT SYSTEM (RCS) RCS OPERATIONAL LEAKAGE

TEXT 3.4.5 0 11/18/2002
Title: REACTOR COOLANT SYSTEM (RCS) RCS PRESSURE ISOLATION VALVE (PIV) LEAKAGE

TEXT 3.4.6 1 04/18/2005
Title: REACTOR COOLANT SYSTEM (RCS) RCS LEAKAGE DETECTION INSTRUMENTATION

TEXT 3.4.7 1 04/18/2005
Title: REACTOR COOLANT SYSTEM (RCS) RCS SPECIFIC ACTIVITY

TEXT 3.4.8 1 04/18/2005
Title: REACTOR COOLANT SYSTEM (RCS) RESIDUAL HEAT REMOVAL (RHR) SHUTDOWN COOLING SYSTEM - HOT SHUTDOWN

TEXT 3.4.9 0 11/18/2002
Title: REACTOR COOLANT SYSTEM (RCS) RESIDUAL HEAT REMOVAL (RHR) SHUTDOWN COOLING SYSTEM - COLD SHUTDOWN

TEXT 3.4.10 0 11/18/2002
Title: REACTOR COOLANT SYSTEM (RCS) RCS PRESSURE AND TEMPERATURE (P/T) LIMITS

TEXT 3.4.11 0 11/18/2002
Title: REACTOR COOLANT SYSTEM (RCS) REACTOR STEAM DOME PRESSURE

TEXT 3.5.1 1 04/18/2005
Title: EMERGENCY CORE COOLING SYSTEMS (ECCS) AND REACTOR CORE ISOLATION COOLING (RCIC) SYSTEM ECCS - OPERATING

TEXT 3.5.2 0 11/18/2002
Title: EMERGENCY CORE COOLING SYSTEMS (ECCS) AND REACTOR CORE ISOLATION COOLING (RCIC) SYSTEM ECCS - SHUTDOWN

TEXT 3.5.3 1 04/18/2005
Title: EMERGENCY CORE COOLING SYSTEMS (ECCS) AND REACTOR CORE ISOLATION COOLING (RCIC) SYSTEM RCIC SYSTEM

TEXT 3.6.1.1 0 11/18/2002
Title: CONTAINMENT SYSTEMS PRIMARY CONTAINMENT

Manual Name: TSB2

Manual Title: TECHNICAL SPECIFICATIONS BASES UNIT 2 MANUAL

TEXT 3.6.1.2 0 11/18/2002
Title: CONTAINMENT SYSTEMS PRIMARY CONTAINMENT AIR LOCK

TEXT 3.6.1.3 1 05/20/2005
Title: CONTAINMENT SYSTEMS PRIMARY CONTAINMENT ISOLATION VALVES (PCIVS)

TEXT 3.6.1.4 0 11/18/2002
Title: CONTAINMENT SYSTEMS CONTAINMENT PRESSURE

TEXT 3.6.1.5 0 11/18/2002
Title: CONTAINMENT SYSTEMS DRYWELL AIR TEMPERATURE

TEXT 3.6.1.6 0 11/18/2002
Title: CONTAINMENT SYSTEMS SUPPRESSION CHAMBER-TO-DRYWELL VACUUM BREAKERS

TEXT 3.6.2.1 0 11/18/2002
Title: CONTAINMENT SYSTEMS SUPPRESSION POOL AVERAGE TEMPERATURE

TEXT 3.6.2.2 0 11/18/2002
Title: CONTAINMENT SYSTEMS SUPPRESSION POOL WATER LEVEL

TEXT 3.6.2.3 0 11/18/2002
Title: CONTAINMENT SYSTEMS RESIDUAL HEAT REMOVAL (RHR) SUPPRESSION POOL COOLING

TEXT 3.6.2.4 0 11/18/2002
Title: CONTAINMENT SYSTEMS RESIDUAL HEAT REMOVAL (RHR) SUPPRESSION POOL SPRAY

TEXT 3.6.3.1 1 04/18/2005
Title: CONTAINMENT SYSTEMS PRIMARY CONTAINMENT HYDROGEN RECOMBINERS

TEXT 3.6.3.2 1 04/18/2005
Title: CONTAINMENT SYSTEMS DRYWELL AIR FLOW SYSTEM

TEXT 3.6.3.3 0 11/18/2002
Title: CONTAINMENT SYSTEMS PRIMARY CONTAINMENT OXYGEN CONCENTRATION

Manual Name: TSB2

Manual Title: TECHNICAL SPECIFICATIONS BASES UNIT 2 MANUAL

TEXT 3.6.4.1 2 03/01/2005
Title: CONTAINMENT SYSTEMS SECONDARY CONTAINMENT

TEXT 3.6.4.2 2 01/03/2005
Title: CONTAINMENT SYSTEMS SECONDARY CONTAINMENT ISOLATION VALVES (SCIVS)

TEXT 3.6.4.3 2 11/09/2004
Title: CONTAINMENT SYSTEMS STANDBY GAS TREATMENT (SGT) SYSTEM

TEXT 3.7.1 0 11/18/2002
Title: PLANT SYSTEMS RESIDUAL HEAT REMOVAL SERVICE WATER (RHRSW) SYSTEM AND THE ULTIMATE HEAT SINK (UHS)

TEXT 3.7.2 1 11/09/2004
Title: PLANT SYSTEMS EMERGENCY SERVICE WATER (ESW) SYSTEM

TEXT 3.7.3 0 11/18/2002
Title: PLANT SYSTEMS CONTROL ROOM EMERGENCY OUTSIDE AIR SUPPLY (CREOAS) SYSTEM

TEXT 3.7.4 0 11/18/2002
Title: PLANT SYSTEMS CONTROL ROOM FLOOR COOLING SYSTEM

TEXT 3.7.5 0 11/18/2002
Title: PLANT SYSTEMS MAIN CONDENSER OFFGAS

TEXT 3.7.6 1 01/17/2005
Title: PLANT SYSTEMS MAIN TURBINE BYPASS SYSTEM

TEXT 3.7.7 0 11/18/2002
Title: PLANT SYSTEMS SPENT FUEL STORAGE POOL WATER LEVEL

TEXT 3.8.1 2 04/18/2005
Title: ELECTRICAL POWER SYSTEMS AC SOURCES - OPERATING

TEXT 3.8.2 0 11/18/2002
Title: ELECTRICAL POWER SYSTEMS AC SOURCES - SHUTDOWN

Manual Name: TSB2

Manual Title: TECHNICAL SPECIFICATIONS BASES UNIT 2 MANUAL

TEXT 3.8.3 0 11/18/2002
Title: ELECTRICAL POWER SYSTEMS DIESEL FUEL OIL, LUBE OIL, AND STARTING AIR

TEXT 3.8.4 0 11/18/2002
Title: ELECTRICAL POWER SYSTEMS DC SOURCES - OPERATING

TEXT 3.8.5 0 11/18/2002
Title: ELECTRICAL POWER SYSTEMS DC SOURCES - SHUTDOWN

TEXT 3.8.6 0 11/18/2002
Title: ELECTRICAL POWER SYSTEMS BATTERY CELL PARAMETERS

TEXT 3.8.7 0 11/18/2002
Title: ELECTRICAL POWER SYSTEMS DISTRIBUTION SYSTEMS - OPERATING

TEXT 3.8.8 0 11/18/2002
Title: ELECTRICAL POWER SYSTEMS DISTRIBUTION SYSTEMS - SHUTDOWN

TEXT 3.9.1 0 11/18/2002
Title: REFUELING OPERATIONS REFUELING EQUIPMENT INTERLOCKS

TEXT 3.9.2 0 11/18/2002
Title: REFUELING OPERATIONS REFUEL POSITION ONE-ROD-OUT INTERLOCK

TEXT 3.9.3 0 11/18/2002
Title: REFUELING OPERATIONS CONTROL ROD POSITION

TEXT 3.9.4 0 11/18/2002
Title: REFUELING OPERATIONS CONTROL ROD POSITION INDICATION

TEXT 3.9.5 0 11/18/2002
Title: REFUELING OPERATIONS CONTROL ROD OPERABILITY - REFUELING

TEXT 3.9.7 0 11/18/2002
Title: REFUELING OPERATIONS RESIDUAL HEAT REMOVAL (RHR) - HIGH WATER LEVEL

Manual Name: TSB2

Manual Title: TECHNICAL SPECIFICATIONS BASES UNIT 2 MANUAL

TEXT 3.9.8 0 11/18/2002
Title: REFUELING OPERATIONS RESIDUAL HEAT REMOVAL (RHR) - LOW WATER LEVEL

TEXT 3.10.1 0 11/18/2002
Title: SPECIAL OPERATIONS INSERVICE LEAK AND HYDROSTATIC TESTING OPERATION

TEXT 3.10.2 0 11/18/2002
Title: SPECIAL OPERATIONS REACTOR MODE SWITCH INTERLOCK TESTING

TEXT 3.10.3 0 11/18/2002
Title: SPECIAL OPERATIONS SINGLE CONTROL ROD WITHDRAWAL - HOT SHUTDOWN

TEXT 3.10.4 0 11/18/2002
Title: SPECIAL OPERATIONS SINGLE CONTROL ROD WITHDRAWAL - COLD SHUTDOWN

TEXT 3.10.5 0 11/18/2002
Title: SPECIAL OPERATIONS SINGLE CONTROL ROD DRIVE (CRD) REMOVAL - REFUELING

TEXT 3.10.6 0 11/18/2002
Title: SPECIAL OPERATIONS MULTIPLE CONTROL ROD WITHDRAWAL - REFUELING

TEXT 3.10.7 1 03/24/2005
Title: SPECIAL OPERATIONS CONTROL ROD TESTING - OPERATING

TEXT 3.10.8 1 03/24/2005
Title: SPECIAL OPERATIONS SHUTDOWN MARGIN (SDM) TEST - REFUELING

Section	Title	Revision
TOC	Table of Contents	7
B 2.0	SAFETY LIMITS BASES	
	Page TS / B 2.0-1	1
	Page TS / B 2.0-2	2
	Page TS / B 2.0-3	3
	Page TS / B 2.0-4	4
	Page TS / B 2.0-5	1
	Pages B 2.0-6 through B 2.0-8	0
B 3.0	LCO AND SR APPLICABILITY BASES	
	Pages B 3.0-1 through B 3.0-4	0
	Pages TS / B 3.0-5 through TS / B 3.0-7	1
	Pages TS / B 3.0-8 through TS / B 3.0-9	2
	Pages TS / B 3.0-10 through TS / B 3.0-12	1
	Pages TS / B 3.0-13 through TS / B 3.0-15	2
	Pages TS / B 3.0-16 and TS / B 3.0-17	0
B 3.1	REACTIVITY CONTROL BASES	
	Pages B 3.1-1 through B 3.1-4	0
	Page TS / B 3.1-5	1
	Pages TS / B 3.1-6 and TS / B 3.1-7	2
	Pages B 3.1-8 through B 3.1-13	0
	Page TS / B 3.1-14	1
	Pages B 3.1-15 through B 3.1-22	0
	Page TS / B 3.1-23	1
	Pages B 3.1-24 through B 3.1-27	0
	Page TS / B 3.1-28	2
	Page TS / 3.1-29	1
	Pages B 3.1-30 through B 3.1-33	0
	Pages TS / B 3.1.34 through TS / B 3.1-36	1
	Page TS / B 3.1-37	2
	Page TS / B 3.1-38	2
	Pages B 3.1-39 through B 3.1-51	0
B 3.2	POWER DISTRIBUTION LIMITS BASES	
	Pages TS / B 3.2-1 and TS / B 3.2-2	1
	Page TS / B 3.2-3	2
	Page TS / B 3.2-4	1
	Pages TS / B 3.2-5 and TS / B 3.2-6	3
	Page TS / B 3.2-7	2
	Pages TS / B 3.2-8 and TS / B 3.2-9	3
	Pages TS / B 3.2-10 through TS / B 3.2-17	1
	Page TS / 3.2-18	2
	Page TS / 3.2-19	1

CONTROLLED

Section	Title	Revision
B 3.3	INSTRUMENTATION	
	Pages TS / B 3.3-1 through TS / B 3.3-4	1
	Page TS / B 3.3-5	2
	Page TS / B 3.3-6	1
	Page TS / B 3.3-7	2
	Pages TS / B 3.3-8 through TS / B 3.3-11	2
	Page TS / B 3.3-12	2
	Page TS / B 3.3-13	1
	Page TS / B 3.3-14	2
	Pages TS / B 3.3-15 and TS / B 3.3-16	1
	Pages TS / B 3.3-17 and TS / B 3.3-18	2
	Pages TS / B 3.3-19 through TS / B 3.3-27	1
	Pages TS / B 3.3-28 through TS / B 3.3-30	2
	Page TS / B 3.3-31	1
	Page TS / B 3.3-32	3
	Page Ts / B 3.3-33	2
	Pages TS / B 3.3-34 through TS / B 3.3-43	1
	Pages TS / B 3.3-43a though TS / B 3.3-43i	0
	Pages TS / B 3.3-44 through TS / B 3.3-54	2
	Pages B 3.3-55 through B 3.3-63	0
	Pages TS / B 3.3-64 and TS / B 3.3-65	2
	Page TS / B 3.3-66	4
	Page TS / B 3.3-67	3
	Page TS / B 3.3-68	4
	Pages TS / B 3.3-69 and TS / B 3.3-70	3
	Pages TS / B 3.3-71	3
	Pages TS / B 3.3-72 through TS / B 3.3-75	2
	Page TS / B 3.3-75a	4
	Pages TS / B 3.3-75b and TS / B 3.3-75c	4
	Pages B 3.3-76 through TS / B 3.3-77	0
	Page TS / B 3.3-78	1
	Pages B 3.3-79 through B 3.3-91	0
	Pages TS / B 3.3-92 through TS / B 3.3-103	1
	Page TS / B 3.3-104	2
	Pages TS / B 3.3-105 and TS / B 3.3-106	1
	Page TS / B 3.3-107	2
	Page TS / B 3.3-108	1
	Page TS / B 3.3-109	2
	Pages TS / B 3.3-110 through TS / B 3.3-112	1
	Page TS / B 3.3-113	2
	Page TS / B 3.3-114	1
	Page TS / B 3.3-115	2
	Pages TS / B 3.3-116 through TS / B 3.3-118	2
	Pages TS / B 3.3-119 through TS / B 3.3-120	1
	Pages TS / B 3.3-121 and TS / B 3.3-122	2
	Page TS / B 3.3-123	1
	Page TS / B 3.3-124	2

Section	Title	Revision
	Page TS / B 3.3-124a	0
	Page TS / B 3.3-125	1
	Page TS / B 3.3-126	2
	Page TS / B 3.3-127	3
	Page TS / B 3.3-128	2
	Pages TS / B 3.3-129 through TS / B 3.3-131	1
	Page TS / B 3.3-132	2
	Pages TS / B 3.3-133 and TS / B 3.3-134	1
	Pages B 3.3-135 through B 3.3-137	0
	Page TS / B 3.3-138	1
	Pages B 3.3-139 through B 3.3-149	0
	Pages TS/ B 3.3-150 through TS / B 3.3-162	1
	Page TS / B 3.3-163	2
	Pages TS / B 3.3-164 through TS / B 3.3-177	1
	Page TS / B 3.3-178	2
	Page TS / B 3.3-179	3
	Page TS / B 3.3-179a	2
	Page TS / B 3.3-180	1
	Page TS / B 3.3-181	2
	Pages TS / B 3.3-182 through TS / B 3.3-186	1
	Pages TS / B 3.3-187 and TS / B 3.3-188	2
	Pages TS / B 3.3-189 through TS / B 3.3-191	1
	Pages B 3.3-192 through B 3.3-205	0
	Page TS / B 3.3-206	1
	Pages B 3.3-207 through B 3.3-220	0
B 3.4	REACTOR COOLANT SYSTEM BASES	
	Pages TS / B 3.4-1 and TS / B 3.4-2	1
	Pages TS / B 3.4-3 through TS / B 3.4-9	3
	Pages B 3.4-10 through B 3.4-14	0
	Page TS / B 3.4-15	1
	Pages TS / B 3.4-16 and TS / B 3.4-17	2
	Page TS / B 3.4-18	1
	Pages B 3.4-19 through B 3.4-28	0
	Page TS / B 3.4-29	1
	Pages B 3.4-30 through B 3.3-31	0
	Page TS / B 3.4-32	1
	Pages B 3.4-33 through B 3.4-36	0
	Page TS / B 3.4-37	1
	Pages B 3.4-38 through B 3.4-40	0
	Page TS / B 3.4-41	1
	Pages B 3.4-42 through B 3.4-48	0
	Page TS / B 3.4-49	2
	Page TS / B 3.4-50	1
	Page TS / B 3.4-51	2
	Pages TS / B 3.4-52 and TS / B 3.4-53	1
	Pages TS / B 3.4-54 and TS / B 3.4-55	2

Section	Title	Revision
	Pages TS / B 3.4-56 through TS / B 3.4-60	1
B 3.5	ECCS AND RCIC BASES	
	Pages TS / B 3.5-1 and TS / B 3.5-2	1
	Page TS / B 3.5-3	2
	Page TS / B 3.5-4	1
	Pages TS / B 3.5-5 and TS / B 3.5-6	2
	Pages TS / B 3.5-7 through TS / B 3.5-10	1
	Page TS / B 3.5-11	2
	Pages TS / B 3.5-12 through TS / B 3.5-14	1
	Pages TS / B 3.5-15 through TS / B.3.5-17	2
	Page TS / B 3.18	1
	Pages B 3.5-19 through B 3.5-24	0
	Page TS / B 3.5-25	1
	Pages TS / B 3.5-26 and TS / B 3.5-27	1
	Pages B 3.5-28 through B 3.5-31	0
B 3.6	CONTAINMENT SYSTEMS BASES	
	Page TS / B 3.6-1	2
	Page TS / B 3.6-1a	3
	Pages TS / B 3.6-2 through TS / B 3.6-5	2
	Page TS / B 3.6-6	3
	Pages TS / B 3.6-6a and TS / B 3.6-6b	2
	Page TS / B 3.6-6c	0
	Pages B 3.6-7 through B 3.6-14	0
	Page TS / B 3.6-15	3
	Pages TS / B 3.6-15a and TS / B 3.6-15b	0
	Page TS / B 3.6-16	1
	Page TS / B 3.6-17	2
	Page TS / B 3.6-17a	0
	Pages TS / B 3.6-18 and TS / B 3.6-19	1
	Page TS / B 3.6-20	2
	Page TS / B 3.6-21	3
	Pages TS / B 3.6-21a and TS / B 3.6-21b	0
	Pages TS / B 3.6-22 and TS / B 3.6-23	2
	Pages TS / B 3.6-24 and TS / B 3.6-25	1
	Page TS / B 3.6-26	2
	Page TS / B 3.6-27	3
	Page TS / B 3.6-28	6
	Page TS / B 3.6-29	3
	Page TS / B 3.6-29a	0
	Page TS / B 3.6-30	2
	Page TS / B 3.6-31	3
	Page TS / B 3.6-32	1
	Page TS / B 3.6-33	2
	Page TS / B 3.6-34	1
	Pages TS / B 3.6-35 through TS / B 3.6-37	2

Section	Title	Revision
	Page TS / B 3.6-38	1
	Page TS / B 3.6-39	4
	Pages B 3.6-40 through B 3.6-42	0
	Pages TS / B 3.6-43 through TS / B 3.6-50	1
	Page TS / B 3.6-51	2
	Pages B 3.6-52 through B 3.6-62	0
	Page TS / B 3.6-63	1
	Pages B 3.6-64 through B 3.6-70	0
	Page B 3.6-71	0
	Page TS / B 3.6-72	1
	Pages B 3.6-73 through B 3.6-76	0
	Page TS / B 3.6-77	1
	Pages B 3.6-78 through B 3.6-82	0
	Page TS / B 3.6-83	3
	Pages TS / B 3.6-84 and TS / B 3.6-85	2
	Pages TS / B 3.6-86 through TS / B 3.6-87a	1
	Page TS / B 3.6-88	3
	Page TS / B 3.6-89	1
	Page TS / B 3.3-90	3
	Pages TS / B 3.6-91 through TS / B 3.6-95	1
	Page TS / B 3.6-96	2
	Pages TS / B 3.6-97 and TS / B 3.6-98	1
	Page TS / B 3.6-99	2
	Page TS / B 3.6-99a	0
	Pages TS / B 3.6-100 and TS / B 3.6-101	1
	Pages TS / B 3.6-102 through TS / B 3.6-104	2
	Pages TS / B 3.6-105 and TS / B 3.6-106	1
B 3.7	PLANT SYSTEMS BASES	
	Pages TS / B 3.7-1 through TS / B 3.7-6	2
	Page TS / B 3.7-6a	2
	Pages TS / B 3.7-6b and TS / B 3.7-6c	0
	Page TS / B 3.7-7	2
	Page TS / B 3.7-8	1
	Pages B 3.7-9 through B 3.7-11	0
	Pages TS / B 3.7-12 and TS / B 3.7-13	1
	Pages TS / B 3.7-14 through TS / B 3.7-18	2
	Page TS / B 3.7-18a	0
	Pages TS / B 3.7-19 through TS / B 3.7-26	1
	Pages B 3.7-24 through B 3.7-26	0
	Pages TS / B 3.7-27 through TS / B 3.7-29	2
	Page TS / B 3.7-30	1
	Pages B 3.7-31 through B 3.7-33	0
B 3.8	ELECTRICAL POWER SYSTEMS BASES	
	Pages B 3.8-1 through B 3.8-4	0
	Page TS / B 3.8-5	1

Section	Title	Revision
	Page TS / B 3.8-6	1
	Pages B 3.8-7 and B 3.8-8	0
	Pages TS / B 3.8-9 through TS / B 3.8-11	1
	Pages B 3.8-12 through B 3.8-18	0
	Page TS / B 3.8-19	1
	Pages B 3.8-20 through B 3.8-22	0
	Page TS / B 3.8-23	1
	Page B 3.8-24	0
	Pages TS / B 3.8-25 and TS / B 3.8-26	1
	Pages B 3.8-27 through B 3.8-37	0
	Page TS / B 3.8-38	1
	Pages TS / B 3.8-39 through TS / B 3.8-55	0
	Pages TS / B 3.8-56 through TS / B 3.8-64	1
	Page TS / B 3.8-65	2
	Page TS / B 3.8-66	2
	Pages TS / B 3.8-67 through TS / B 3.8-68	1
	Page TS / B 3.8-69	2
	Pages B 3.8-70 through B 3.8-99	0
B 3.9	REFUELING OPERATIONS BASES	
	Pages TS / B 3.9-1 and TS / B 3.9-2	1
	Page TS / B 3.9-2a	1
	Pages TS / B 3.9-3 and TS / B 3.9-4	1
	Pages B 3.9-5 through B 3.9-30	0
B 3.10	SPECIAL OPERATIONS BASES	
	Page TS / B 3.10-1	1
	Pages B 3.10-2 through B 3.10-32	0
	Page TS / B 3.10-33	2
	Pages B 3.10-34 through B 3.10-38	0
	Page TS / B 3.10-39	2

TSB2 LOES
8/12/05

B 3.6 CONTAINMENT SYSTEMS

B 3.6.1.3 Primary Containment Isolation Valves (PCIVs)

BASES

BACKGROUND

The function of the PCIVs, in combination with other accident mitigation systems, is to limit fission product release during and following postulated Design Basis Accidents (DBAs) to within limits. Primary containment isolation within the time limits specified for those isolation valves designed to close automatically ensures that the release of radioactive material to the environment will be consistent with the assumptions used in the analyses for a DBA.

The OPERABILITY requirements for PCIVs help ensure that an adequate primary containment boundary is maintained during and after an accident by minimizing potential paths to the environment. Therefore, the OPERABILITY requirements provide assurance that primary containment function assumed in the safety analyses will be maintained. For PCIVs, the primary containment isolation function is that the valve must be able to close (automatically or manually) and/or remain closed, and maintain leakage within that assumed in the DBA LOCA Dose Analysis. These isolation devices are either passive or active (automatic). Manual valves, de-activated automatic valves secured in their closed position (including check valves with flow through the valve secured), blind flanges, and closed systems are considered passive devices. The OPERABILITY requirements for closed systems are discussed in Technical Requirements Manual (TRM) Bases 3.6.4. Check valves, or other automatic valves designed to close without operator action following an accident, are considered active devices. Two barriers in series are provided for each penetration so that no single credible failure or malfunction of an active component can result in a loss of isolation or leakage that exceeds limits assumed in the safety analyses. One of these barriers may be a closed system.

For each division of H_2O_2 Analyzers, the lines, up to and including the first normally closed valves within the H_2O_2

(continued)

BASES

BACKGROUND (continued)

Analyzer panels, are extensions of primary containment (i.e., closed system), and are required to be leak rate tested in accordance with the Leakage Rate Test Program. The H_2O_2 Analyzer closed system boundary is identified in the Leakage Rate Test Program. The closed system boundary consists of those components, piping, tubing, fittings, and valves, which meet the guidance of Reference 6. The closed system provides a secondary barrier in the event of a single failure of the PCIVs, as described below. The closed system boundary between PASS and the H_2O_2 Analyzer system ends at the process sampling solenoid operated isolation valves between the systems (SV-22361, SV-22365, SV-22366, SV-22368, and SV-22369). These solenoid operated isolation valves do not fully meet the guidance of Reference 6 for closed system boundary valves in that they are not powered from a Class 1E power source. However, based upon a risk determination, operating these valves as closed system boundary valves is not risk significant. These valves also form the end of the Seismic Category I boundary between the systems. These process sampling solenoid operated isolation valves are normally closed and are required to be leak rate tested in accordance with the Leakage Rate Test Program as part of the closed system for the H_2O_2 Analyzer system. These valves are "closed system boundary valves" and may be opened under administrative control, as delineated in Technical Requirements Manual (TRM) Bases 3.6.4. Opening of these valves to permit testing of PASS in Modes 1, 2, and 3 is permitted in accordance with TRO 3.6.4.

Each H_2O_2 Analyzer Sampling line penetrating primary containment has two PCIVs, located just outside primary containment. While two PCIVs are provided on each line, a single active failure of a relay in the control circuitry for these valves, could result in both valves failing to close or failing to remain closed. Furthermore, a single failure (a hot short in the common raceway to all the valves) could simultaneously affect all of the PCIVs within a H_2O_2 Analyzer division. Therefore, the containment isolation barriers for these penetrations consist of two PCIVs and a closed system. For situations where one or both PCIVs are inoperable, the ACTIONS to be taken are similar to the ACTIONS for a single PCIV backed by a closed system.

(continued)

BASES

BACKGROUND (continued)

The drywell vent and purge lines are 24 inches in diameter; the suppression chamber vent and purge lines are 18 inches in diameter. The containment purge valves are normally maintained closed in MODES 1, 2, and 3 to ensure the primary containment boundary is maintained. The outboard isolation valves have 2 inch bypass lines around them for use during normal reactor operation.

(continued)

BASES (continued)

APPLICABLE SAFETY ANALYSES

The PCIVs LCO was derived from the assumptions related to minimizing the loss of reactor coolant inventory, and establishing the primary containment boundary during major accidents. As part of the primary containment boundary, PCIV OPERABILITY supports leak tightness of primary containment. Therefore, the safety analysis of any event requiring isolation of primary containment is applicable to this LCO.

The DBAs that result in a release of radioactive material within primary containment are a LOCA and a main steam line break (MSLB). In the analysis for each of these accidents, it is assumed that PCIVs are either closed or close within the required isolation times following event initiation. This ensures that potential paths to the environment through PCIVs (including primary containment purge valves) are minimized. Of the events analyzed in Reference 1, the MSLB is the most limiting event due to radiological consequences. The closure time of the main steam isolation valves (MSIVs) is a significant variable from a radiological standpoint. The MSIVs are required to close within 3 to 5 seconds since the 5 second closure time is assumed in the analysis. The safety analyses assume that the purge valves were closed at event initiation. Likewise, it is assumed that the primary containment is isolated such that release of fission products to the environment is controlled.

The DBA analysis assumes that within the required isolation time leakage is terminated, except for the maximum allowable leakage rate, L_a.

The single failure criterion required to be imposed in the conduct of unit safety analyses was considered in the original design of the primary containment purge valves. Two valves in series on each purge line provide assurance that both the supply and exhaust lines could be isolated even if a single failure occurred.

The primary containment purge valves may be unable to close in the environment following a LOCA. Therefore, each of the purge valves is required to remain closed during MODES 1, 2, and 3 except as permitted under Note 2 of SR 3.6.1.3.1. In this case, the single failure criterion remains applicable to the primary containment purge valve

(continued)

APPLICABLE SAFEETY ANALYSIS (continued)

due to failure in the control circuit associated with each valve. The primary containment purge valve design precludes a single failure from compromising the primary containment boundary as long as the system is operated in accordance with this LCO.

Both H_2O_2 Analyzer PCIVs may not be able to close given a single failure in the control circuitry of the valves. The single failure is caused by a "hot short" in the cables/raceway to the PCIVs that causes both PCIVs for a given penetration to remain open or to open when required to be closed. This failure is required to be considered in accordance with IEEE-279 as discussed in FSAR Section 7.3.2a. However, the single failure criterion for containment isolation of the H_2O_2 Analyzer penetrations is satisfied by virtue of the combination of the associated PCIVs and the closed system formed by the H_2O_2 Analyzer piping system as discussed in the BACKGROUND section above.

The closed system boundary between PASS and the H_2O_2 Analyzer system ends at the process sampling solenoid operated isolation valves between the systems (SV-22361, SV-22365, SV-22366, SV-22368, and SV-22369). The closed system is not fully qualified to the guidance of Reference 6 in that the closed system boundary valves between the H_2O_2 system and PASS are not powered from a Class 1E power source. However, based upon a risk determination, the use of these valves is considered to have no risk significance. This exemption to the requirement of Reference 6 for the closed system boundary is documented in License Amendment No. 170.

PCIVs satisfy Criterion 3 of the NRC Policy Statement. (Ref. 2)

LCO

PCIVs form a part of the primary containment boundary. The PCIV safety function is related to minimizing the loss of reactor coolant inventory and establishing the primary containment boundary during a DBA.

The power operated, automatic isolation valves are required to have isolation times within limits and actuate on an

(continued)

BASES

LCO (continued)

automatic isolation signal. The valves covered by this LCO are listed in Table B 3.6.1.3-1.

The normally closed PCIVs are considered OPERABLE when manual valves are closed or open in accordance with appropriate administrative controls, automatic valves are in their closed position, blind flanges are in place, and closed systems are intact. These passive isolation valves and devices are those listed in Table B 3.6.1.3-1.

Purge valves with resilient seals, secondary containment bypass valves, MSIVs, and hydrostatically tested valves must meet additional leakage rate requirements. Other PCIV leakage rates are addressed by LCO 3.6.1.1, "Primary Containment," as Type B or C testing.

This LCO provides assurance that the PCIVs will perform their designed safety functions to minimize the loss of reactor coolant inventory and establish the primary containment boundary during accidents.

APPLICABILITY

In MODES 1, 2, and 3, a DBA could cause a release of radioactive material to primary containment. In MODES 4 and 5, the probability and consequences of these events are reduced due to the pressure and temperature limitations of these MODES. Therefore, most PCIVs are not required to be

(continued)

BASES

APPLICABILITY (continued)

OPERABLE and the primary containment purge valves are not required to be closed in MODES 4 and 5. Certain valves, however, are required to be OPERABLE to prevent inadvertent reactor vessel draindown. These valves are those whose associated instrumentation is required to be OPERABLE per LCO 3.3.6.1, "Primary Containment Isolation Instrumentation." (This does not include the valves that isolate the associated instrumentation.)

ACTIONS

The ACTIONS are modified by a Note allowing penetration flow path(s) to be unisolated intermittently under administrative controls. These controls consist of stationing a dedicated operator at the controls of the valve, who is in continuous communication with the control room. In this way, the penetration can be rapidly isolated when a need for primary containment isolation is indicated.

A second Note has been added to provide clarification that, for the purpose of this LCO, separate Condition entry is allowed for each penetration flow path. This is acceptable, since the Required Actions for each Condition provide appropriate compensatory actions for each inoperable PCIV. Complying with the Required Actions may allow for continued operation, and subsequent inoperable PCIVs are governed by subsequent Condition entry and application of associated Required Actions.

The ACTIONS are modified by Notes 3 and 4. Note 3 ensures that appropriate remedial actions are taken, if necessary, if the affected system(s) are rendered inoperable by an inoperable PCIV (e.g., an Emergency Core Cooling System subsystem is inoperable due to a failed open test return valve). Note 4 ensures appropriate remedial actions are taken when the primary containment leakage limits are exceeded. Pursuant to LCO 3.0.6, these actions are not required even when the associated LCO is not met. Therefore, Notes 3 and 4 are added to require the proper actions be taken.

A.1 and A.2

With one or more penetration flow paths with one PCIV inoperable except for purge valve leakage not within limit,

(continued)

BASES

ACTIONS

A.1 and A.2 (continued)

the affected penetration flow paths must be isolated. The method of isolation must include the use of at least one isolation barrier that cannot be adversely affected by a single active failure. Isolation barriers that meet this criterion are a closed and de-activated automatic valve, a closed manual valve, a blind flange, and a check valve with flow through the valve secured. For a penetration isolated in accordance with Required Action A.1, the device used to isolate the penetration should be the closest available valve to the primary containment. The Required Action must be completed within the 4 hour Completion Time (8 hours for main steam lines). The Completion Time of 4 hours is reasonable considering the time required to isolate the penetration and the relative importance of supporting primary containment OPERABILITY during MODES 1, 2, and 3. For main steam lines, an 8 hour Completion Time is allowed. The Completion Time of 8 hours for the main steam lines allows a period of time to restore the MSIVs to OPERABLE status given the fact that MSIV closure will result in isolation of the main steam line(s) and a potential for plant shutdown.

For affected penetrations that have been isolated in accordance with Required Action A.1, the affected penetration flow path(s) must be verified to be isolated on a periodic basis. This is necessary to ensure that primary containment penetrations required to be isolated following an accident, and no longer capable of being automatically isolated, will be in the isolation position should an event occur. This Required Action does not require any testing or device manipulation. Rather, it involves verification that those devices outside containment and capable of potentially being mispositioned are in the correct position. The Completion Time of "once per 31 days for isolation devices outside primary containment" is appropriate because the devices are operated under administrative controls and the probability of their misalignment is low. For the devices inside primary containment, the time period specified "prior to entering MODE 2 or 3 from MODE 4, if primary containment was de-inerted while in MODE 4, if not performed within the previous 92 days" is based on engineering judgment and is considered reasonable in view of the inaccessibility of the devices and other administrative controls ensuring that device misalignment is an unlikely possibility.

(continued)

BASES

ACTIONS

A.1 and A.2 (continued)

Condition A is modified by a Note indicating that this Condition is only applicable to those penetration flow paths with two PCIVs except for the H_2O_2 Analyzer penetrations. For penetration flow paths with one PCIV, Condition C provides the appropriate Required Actions. For the H_2O_2 Analyzer penetrations, Condition D provides the appropriate Required Actions.

Required Action A.2 is modified by a Note that applies to isolation devices located in high radiation areas, and allows them to be verified by use of administrative means. Allowing verification by administrative means is considered acceptable, since access to these areas is typically restricted. Therefore, the probability of misalignment of these devices, once they have been verified to be in the proper position, is low.

B.1

With one or more penetration flow paths with two PCIVs inoperable except for purge valve leakage not within limit, either the inoperable PCIVs must be restored to OPERABLE status or the affected penetration flow path must be isolated within 1 hour. The method of isolation must include the use of at least one isolation barrier that cannot be adversely affected by a single active failure. Isolation barriers that meet this criterion are a closed and de-activated automatic valve, a closed manual valve, and a blind flange. The 1 hour Completion Time is consistent with the ACTIONS of LCO 3.6.1.1.

Condition B is modified by a Note indicating this Condition is only applicable to penetration flow paths with two PCIVs except for the H_2O_2 Analyzer penetrations. For penetration flow paths with one PCIV, Condition C provides the appropriate Required Actions. For the H_2O_2 Analyzer penetrations, Condition D provides the appropriate Required Actions.

C.1 and C.2

With one or more penetration flow paths with one PCIV inoperable, the inoperable valve must be restored to

(continued)

ACTIONS

C.1 and C.2 (continued)

OPERABLE status or the affected penetration flow path must be isolated. The method of isolation must include the use of at least one isolation barrier that cannot be adversely affected by a single active failure. Isolation barriers that meet this criterion are a closed and de-activated automatic valve, a closed manual valve, and a blind flange. A check valve may not be used to isolate the affected penetration. Required Action C.1 must be completed within the 72 hour Completion Time. The Completion Time of 72 hours is reasonable considering the relative stability of the closed system (hence, reliability) to act as a penetration isolation boundary and the relative importance of supporting primary containment OPERABILITY during MODES 1, 2, and 3. The closed system must meet the requirements of Reference 6. For conditions where the PCIV and the closed system are inoperable, the Required Actions of TRO 3.6.4, Condition B apply. For the Excess Flow Check Valves (EFCV), the Completion Time of 12 hours is reasonable considering the instrument and the small pipe diameter of penetration (hence, reliability) to act as a penetration isolation boundary and the small pipe diameter of the affected penetrations. In the event the affected penetration flow path is isolated in accordance with Required Action C.1, the affected penetration must be verified to be isolated on a periodic basis. This is necessary to ensure that primary containment penetrations required to be isolated following an accident are isolated. The Completion Time of once per 31 days for verifying each affected penetration is isolated is appropriate because the valves are operated under administrative controls and the probability of their misalignment is low.

Condition C is modified by a Note indicating that this Condition is only applicable to penetration flow paths with only one PCIV. For penetration flow paths with two PCIVs and the H_2O_2 Analyzer penetration, Conditions A, B, and D provide the appropriate Required Actions.

Required Action C.2 is modified by a Note that applies to valves and blind flanges located in high radiation areas and allows them to be verified by use of administrative means. Allowing verification by administrative means is considered acceptable, since access to these areas is typically

(continued)

ACTIONS

C.1 and C.2 (continued)

restricted. Therefore, the probability of misalignment of these valves, once they have been verified to be in the proper position, is low.

D.1 and D.2

With one or more H_2O_2 Analyzer penetrations with one or both PCIVs inoperable, the inoperable valve(s) must be restored to OPERABLE status or the affected penetration flow path must be isolated. The method of isolation must include the use of at least one isolation barrier that cannot be adversely affected by a single active failure. Isolation barriers that meet this criterion are a closed and de-activated automatic valve, a closed manual valve, and a blind flange. A check valve may not be used to isolate the affected penetration. Required Action D.1 must be completed within the 72 hour Completion Time. The Completion Time of 72 hours is reasonable considering the unique design of the H_2O_2 Analyzer penetrations. The containment isolation barriers for these penetrations consist of two PCIVs and a closed system. In addition, the Completion Time of 72 hours is reasonable considering the relative stability of the closed system (hence, reliability) to act as a penetration isolation boundary and the relative importance of supporting primary containment OPERABILITY during MODES 1, 2, and 3. In the event the affected penetration flow path is isolated in accordance with Required Action D.1, the affected penetration must be verified to be isolated on a periodic basis. This is necessary to ensure that primary containment penetrations required to be isolated following an accident are isolated. The Completion Time of once per 31 days for verifying each affected penetration is isolated is appropriate because the valves are operated under administrative controls and the probability of their misalignment is low.

When an H_2O_2 Analyzer penetration PCIV is to be closed and deactivated in accordance with Condition D, this must be accomplished by pulling the fuse for the power supply, and either determinating the power cables at the solenoid valve, or jumpering of the power side of the solenoid to ground.

(continued)

BASES

ACTIONS

D.1 and D.2 (continued)

The OPERABILITY requirements for the closed system are discussed in Technical Requirements Manual (TRM) Bases 3.6.4. In the event that either one or both of the PCIVs and the closed system are inoperable, the Required Actions of TRO 3.6.4, Condition B apply.

Condition D is modified by a Note indicating that this Condition is only applicable to the H_2O_2 Analyzer penetrations.

(continued)

ACTIONS (continued)

E.1

With the secondary containment bypass leakage rate not within limit, the assumptions of the safety analysis may not be met. Therefore, the leakage must be restored to within limit within 4 hours. Restoration can be accomplished by isolating the penetration that caused the limit to be exceeded by use of one closed and de-activated automatic valve, closed manual valve, or blind flange. When a penetration is isolated, the leakage rate for the isolated penetration is assumed to be the actual pathway leakage through the isolation device. If two isolation devices are used to isolate the penetration, the leakage rate is assumed to be the lesser actual pathway leakage of the two devices. The 4 hour Completion Time is reasonable considering the time required to restore the leakage by isolating the penetration and the relative importance of secondary containment bypass leakage to the overall containment function.

F.1

In the event one or more containment purge valves are not within the purge valve leakage limits, purge valve leakage must be restored to within limits. The 24 hour Completion Time is reasonable, considering that one containment purge valve remains closed, except as controlled by SR 3.6.1.3.1 so that a gross breach of containment does not exist.

G.1 and G.2

If any Required Action and associated Completion Time cannot be met in MODE 1, 2, or 3, the plant must be brought to a MODE in which the LCO does not apply. To achieve this status, the plant must be brought to at least MODE 3 within 12 hours and to MODE 4 within 36 hours. The allowed Completion Times are reasonable, based on operating experience, to reach the required plant conditions from full power conditions in an orderly manner and without challenging plant systems.

(continued)

BASES

ACTIONS (continued)

H.1 and H.2

If any Required Action and associated Completion Time cannot be met, the unit must be placed in a condition in which the LCO does not apply. If applicable, action must be immediately initiated to suspend operations with a potential for draining the reactor vessel (OPDRVs) to minimize the probability of a vessel draindown and subsequent potential for fission product release. Actions must continue until OPDRVs are suspended or valve(s) are restored to OPERABLE status. If suspending an OPDRV would result in closing the residual heat removal (RHR) shutdown cooling isolation valves, an alternative Required Action is provided to immediately initiate action to restore the valve(s) to OPERABLE status. This allows RHR to remain in service while actions are being taken to restore the valve.

SURVEILLANCE REQUIREMENTS

SR 3.6.1.3.1

This SR ensures that the primary containment purge valves are closed as required or, if open, open for an allowable reason. If a purge valve is open in violation of this SR, the valve is considered inoperable. If the inoperable valve is not otherwise known to have excessive leakage when closed, it is not considered to have leakage outside of limits. The SR is also modified by Note 1, stating that primary containment purge valves are only required to be closed in MODES 1, 2, and 3. If a LOCA inside primary containment occurs in these MODES, the purge valves may not be capable of closing before the pressure pulse affects systems downstream of the purge valves, or the release of radioactive material will exceed limits prior to the purge valves closing. At other times when the purge valves are required to be capable of closing (e.g., during handling of irradiated fuel), pressurization concerns are not present and the purge valves are allowed to be open. The SR is modified by Note 2 stating that the SR is not required to be met when the purge valves are open for the stated reasons. The Note states that these valves may be opened for inerting, de-inerting, pressure control, ALARA or air quality considerations for personnel entry, or Surveillances that require the valves to be open. The vent and purge valves are capable of closing in the environment following

(continued)

SURVEILLANCE REQUIREMENTS

SR 3.6.1.3.1 (continued)

a LOCA. Therefore, these valves are allowed to be open for limited periods of time. The 31 day Frequency is consistent with other PCIV requirements discussed in SR 3.6.1.3.2.

SR 3.6.1.3.2

This SR verifies that each primary containment isolation manual valve and blind flange that is located outside primary containment and not locked, sealed, or otherwise secured and is required to be closed during accident conditions is closed. The SR helps to ensure that post accident leakage of radioactive fluids or gases outside the primary containment boundary is within design limits.

This SR does not require any testing or valve manipulation. Rather, it involves verification that those PCIVs outside primary containment, and capable of being mispositioned, are in the correct position. Since verification of valve position for PCIVs outside primary containment is relatively easy, the 31 day Frequency was chosen to provide added assurance that the PCIVs are in the correct positions.

Two Notes have been added to this SR. The first Note allows valves and blind flanges located in high radiation areas to be verified by use of administrative controls. Allowing verification by administrative controls is considered acceptable since access to these areas is typically restricted during MODES 1, 2, and 3 for ALARA reasons. Therefore, the probability of misalignment of these PCIVs, once they have been verified to be in the proper position, is low. A second Note has been included to clarify that PCIVs that are open under administrative controls are not required to meet the SR during the time that the PCIVs are open. This SR does not apply to valves that are locked, sealed, or otherwise secured in the closed position, since these were verified to be in the correct position upon locking, sealing, or securing.

SR 3.6.1.3.3

This SR verifies that each primary containment manual isolation valve and blind flange that is located inside

(continued)

BASES

SURVEILLANCE REQUIREMENTS

S R 3.6.1.3.3 (continued)

primary containment and not locked, sealed, or otherwise secured and is required to be closed during accident conditions is closed. The SR helps to ensure that post accident leakage of radioactive fluids or gases outside the primary containment boundary is within design limits. For PCIVs inside primary containment, the Frequency defined as "prior to entering MODE 2 or 3 from MODE 4 if primary containment was de-inerted while in MODE 4, if not performed within the previous 92 days" is appropriate since these PCIVs are operated under administrative controls and the probability of their misalignment is low. This SR does not apply to valves that are locked, sealed, or otherwise secured in the closed position, since these were verified to be in the correct position upon locking, sealing, or securing. Two Notes have been added to this SR. The first Note allows valves and blind flanges located in high radiation areas to be verified by use of administrative controls. Allowing verification by administrative controls is considered acceptable since the primary containment is inerted and access to these areas is typically restricted during MODES 1, 2, and 3 for ALARA reasons. Therefore, the probability of misalignment of these PCIVs, once they have been verified to be in their proper position, is low. A second Note has been included to clarify that PCIVs that are open under administrative controls are not required to meet the SR during the time that the PCIVs are open.

SURVEILLANCE REQUIREMENTS

SR 3.6.1.3.4

The traversing incore probe (TIP) shear isolation valves are actuated by explosive charges. Surveillance of explosive charge continuity provides assurance that TIP valves will actuate when required. Other administrative controls, such as those that limit the shelf life of the explosive charges, must be followed. The 31 day Frequency is based on operating experience that has demonstrated the reliability of the explosive charge continuity.

SR 3.6.1.3.5

Verifying the isolation time of each power operated and each automatic PCIV is within limits is required to demonstrate

(continued)

BASES

SURVEILLANCE REQUIREMENTS

S R 3.6.1.3.5 (continued)

OPERABILITY. MSIVs may be excluded from this SR since MSIV full closure isolation time is demonstrated by SR 3.6.1.3.7. The isolation time test ensures that the valve will isolate in a time period less than or equal to that assumed in the Final Safety Analyses Report. The isolation time and Frequency of this SR are in accordance with the requirements of the Inservice Testing Program.

SR 3.6.1.3.6

For primary containment purge valves with resilient seals, the Appendix J Leakage Rate Test Interval of 24 months is sufficient. The acceptance criteria for these valves is defined in the Primary Containment Leakage Rate Testing Program, 5.5.12.

The SR is modified by a Note stating that the primary containment purge valves are only required to meet leakage rate testing requirements in MODES 1, 2, and 3. If a LOCA inside primary containment occurs in these MODES, purge valve leakage must be minimized to ensure offsite radiological release is within limits. At other times when the purge valves are required to be capable of closing (e.g., during handling of irradiated fuel), pressurization concerns are not present and the purge valves are not required to meet any specific leakage criteria.

SR 3.6.1.3.7

Verifying that the isolation time of each MSIV is within the specified limits is required to demonstrate OPERABILITY. The isolation time test ensures that the MSIV will isolate in a time period that does not exceed the times assumed in the DBA analyses. This ensures that the calculated radiological consequences of these events remain within 10 CFR 100 limits.

(continued)

SURVEILLANCE REQUIREMENTS (continued)

SR 3.6.1.3.7

The Frequency of this SR is in accordance with the requirements of the Inservice Testing Program.

SR 3.6.1.3.8

Automatic PCIVs close on a primary containment isolation signal to prevent leakage of radioactive material from primary containment following a DBA. This SR ensures that each automatic PCIV will actuate to its isolation position on a primary containment isolation signal. The LOGIC SYSTEM FUNCTIONAL TEST in SR 3.3.6.1.5 overlaps this SR to provide complete testing of the safety function. The 24 month Frequency was developed considering it is prudent that some of these Surveillances be performed only during a unit outage since isolation of penetrations could eliminate cooling water flow and disrupt the normal operation of some critical components. Operating experience has shown that these components usually pass this Surveillance when performed at the 24 month Frequency. Therefore, the Frequency was concluded to be acceptable from a reliability standpoint.

SR 3.6.1.3.9

This SR requires a demonstration that a representative sample of reactor instrumentation line excess flow check valves (EFCV) are OPERABLE by verifying that the valve actuates to check flow on a simulated instrument line break. As defined in FSAR Section 6.2.4.3.5 (Reference 4), the conditions under which an EFCV will isolate, simulated instrument line breaks are at flow rates which develop a differential pressure of between 3 psid and 10 psid. This SR provides assurance that the instrumentation line EFCVs will perform its design function to check flow. No specific valve leakage limits are specified because no specific leakage limits are defined in the FSAR. The 24 month Frequency is based on the need to perform some of these Surveillances under the conditions that apply during a plant outage and the potential for an unplanned transient if the Surveillance were performed with the reactor at power. The representative sample consists of an approximate equal number of EFCVs such that each EFCV is tested at least once every 10 years (nominal). The nominal 10 year interval is based on other performance-based testing programs, such as Inservice Testing (snubbers) and Option B to 10 CFR 50, Appendix J. In addition, the EFCVs in the sample are representative of the various plant configurations, models, sizes and operating environments. This ensures that any potential common problem with a specific type or application of EFCV is

(continued)

SURVEILLANCE REQUIREMENTS

SR 3.6.1.3.9 (continued)

detected at the earliest possible time. EFCV failures will be evaluated to determine if additional testing in that test interval is warranted to ensure overall reliability and that failures to isolate are very infrequent. Therefore, testing of a representative sample was concluded to be acceptable from a reliability standpoint (Reference 7).

SR 3.6.1.3.10

The TIP shear isolation valves are actuated by explosive charges. An in place functional test is not possible with this design. The explosive squib is removed and tested to provide assurance that the valves will actuate when required. The replacement charge for the explosive squib shall be from the same manufactured batch as the one fired or from another batch that has been certified by having one of the batch successfully fired. The Frequency of 24 months on a STAGGERED TEST BASIS is considered adequate given the administrative controls on replacement charges and the frequent checks of circuit continuity (SR 3.6.1.3.4).

SR 3.6.1.3.11

This SR ensures that the leakage rate of secondary containment bypass leakage paths is less than the specified leakage rate. This provides assurance that the assumptions in the radiological evaluations of Reference 4 are met. The secondary containment leakage pathways and Frequency are defined by the Primary Containment Leakage Rate Testing Program. This SR simply imposes additional acceptance criteria. A note is added to this SR which states that these valves are only required to meet this leakage limit in MODES 1, 2, and 3. In the other MODES, the Reactor Coolant System is not pressurized and specific primary containment leakage limits are not required.

SR 3.6.1.3.12

The analyses in References 1 and 4 are based on the specified leakage rate. Leakage through each MSIV must be ≤ 100 scfh for anyone MSIV or ≤ 300 scfh for total leakage through the MSIVs combined with the Main Steam Line Drain Isolation Valve, HPCI Steam Supply Isolation Valve and the RCIC Steam Supply Isolation Valve. The MSIVs can be tested at either ≥ Pt (22.5 psig) or P_a (45 psig). Main Steam Line Drain Isolation, HPCI and RCIC Steam Supply Line Isolation Valves, are tested at P_a (45 psig). A note is added to this SR which states that these valves are only required to meet this leakage limit in MODES 1, 2, and 3. In the other

(continued)

BASES

SURVEILLANCE REQUIREMENTS

SR 3.6.1.3.12 (continued)

conditions, the Reactor Coolant System is not pressurized and specific primary containment leakage limits are not required. The Frequency is required by the Primary Containment Leakage Rate Testing Program. If leakage from the MSIVs requires internal work on any MSIV, the leakage will be reduced for the affected MSIV to ≤ 11.5 scfh.

SR 3.6.1.3.13

Surveillance of hydrostatically tested lines provides assurance that the calculation assumptions of Reference 2 are met. The acceptance criteria for the combined leakage of all hydrostatically tested lines is 3.3 gpm when tested at 1.1 P_a, (49.5 psig). The combined leakage rates must be demonstrated in accordance with the leakage rate test Frequency required by the Primary Containment Leakage Testing Program.

As noted in Table B 3.6.1.3-1, PCIVs associated with this SR are not Type C tested. Containment bypass leakage is prevented since the line terminates below the minimum water level in the suppression chamber. These valves are tested in accordance with the IST Program. Therefore, these valves leakage is not included as containment leakage.

This SR has been modified by a Note that states that these valves are only required to meet the combined leakage rate in MODES 1, 2, and 3, since this is when the Reactor Coolant System is pressurized and primary containment is required. In some instances, the valves are required to be capable of automatically closing during MODES other than MODES 1, 2, and 3. However, specific leakage limits are not applicable in these other MODES or conditions.

REFERENCES

1. FSAR, Chapter 15.
2. Final Policy Statement on Technical Specifications Improvements, July 22, 1993 (58 FR 39132).
3. 10 CFR 50, Appendix J, Option B.
4. FSAR, Section 6.2.
5. NEDO-30851-P-A, "Technical Specification Improvement Analyses for BWR Reactor Protection System," March 1988.

(continued)

BASES

REFERENCES (continued)

6. Standard Review Plan 6.2.4, Rev. 1, September 1975

7. NEDO-32977-A, "Excess Flow Check Valve Testing Relaxation," June 2000

(continued)

Table B 3.6.1.3-1
Primary Containment Isolation Valve
(Page 1 of 10)

Plant System	Valve Number	Valve Description	Type of Valve	Isolation Signal LCO 3.3.6.1 Function No. (Maximum Isolation Time (Seconds))
Containment Atmospheric Control	2-57-199 (d)	ILRT	Manual	N/A
	2-57-200 (d)	ILRT	Manual	N/A
	HV-25703	Containment Purge	Automatic Valve	2.b, 2.d, 2.e (15)
	HV-25704	Containment Purge	Automatic Valve	2.b, 2.d, 2.e (15)
	HV-25705	Containment Purge	Automatic Valve	2.b, 2.d, 2.e (15)
	HV-25711	Containment Purge	Automatic Valve	2.b, 2.d, 2.e (15)
	HV-25713	Containment Purge	Automatic Valve	2.b, 2.d, 2.e (15)
	HV-25714	Containment Purge	Automatic Valve	2.b, 2.d, 2.e (15)
	HV-25721	Containment Purge	Automatic Valve	2.b, 2.d, 2.e (15)
	HV-25722	Containment Purge	Automatic Valve	2.b, 2.d, 2.e (15)
	HV-25723	Containment Purge	Automatic Valve	2.b, 2.d, 2.e (15)
	HV-25724	Containment Purge	Automatic Valve	2.b, 2.d, 2.e (15)
	HV-25725	Containment Purge	Automatic Valve	2.b, 2.d, 2.e (15)
	HV-25766 (a)	Suppression Pool Cleanup	Automatic Valve	2.b, 2.d (35)
	HV-25768 (a)	Suppression Pool Cleanup	Automatic Valve	2.b, 2.d (30)
	SV-257100 A	Containment Radiation Detection Syst	Automatic Valve	2.b, 2.d, 2.f
	SV-257100 B	Containment Radiation Detection Syst	Automatic Valve	2.b, 2.d, 2.f
	SV-257101 A	Containment Radiation Detection Syst	Automatic Valve	2.b, 2.d, 2.f
	SV-257101 B	Containment Radiation Detection Syst	Automatic Valve	2.b, 2.d, 2.f
	SV-257102 A	Containment Radiation Detection Syst	Automatic Valve	2.b, 2.d, 2.f
	SV-257102 B	Containment Radiation Detection Syst	Automatic Valve	2.b, 2.d, 2.f
	SV-257103 A	Containment Radiation Detection Syst	Automatic Valve	2.b, 2.d, 2.f
	SV-257103 B	Containment Radiation Detection Syst	Automatic Valve	2.b, 2.d, 2.f
	SV-257104	Containment Radiation Detection Syst	Automatic Valve	2.b, 2.d, 2.f
	SV-257105	Containment Radiation Detection Syst	Automatic Valve	2.b, 2.d, 2.f
	SV-257106	Containment Radiation Detection Syst	Automatic Valve	2.b, 2.d, 2.f
	SV-257107	Containment Radiation Detection Syst	Automatic Valve	2.b, 2.d, 2.f
	SV-25734 A (e)	Containment Atmosphere Sample	Automatic Valve	2.b, 2.d
	SV-25734 B (e)	Containment Atmosphere Sample	Automatic Valve	2.b, 2.d
	SV-25736 A (e)	Containment Atmosphere Sample	Automatic Valve	2.b, 2.d
	SV-25736 B (e)	Containment Atmosphere Sample	Automatic Valve	2.b, 2.d
	SV-25737	Nitrogen Makeup	Automatic Valve	2.b, 2.d, 2.e

Table B 3.6.1.3-1
Primary Containment Isolation Valve
(Page 2 of 10)

Plant System	Valve Number	Valve Description	Type of Valve	Isolation Signal LCO 3.3.6.1 Function No. (Maximum Isolation Time (Seconds))
Containment Atmospheric Control (continued)	SV-25738	Nitrogen Makeup	Automatic Valve	2.b, 2.d, 2.e
	SV-25740 A (e)	Containment Atmosphere Sample	Automatic Valve	2.b, 2.d
	SV-25740 B (e)	Containment Atmosphere Sample	Automatic Valve	2.b, 2.d
	SV-25742 A (e)	Containment Atmosphere Sample	Automatic Valve	2.b, 2.d
	SV-25742 B (e)	Containment Atmosphere Sample	Automatic Valve	2.b, 2.d
	SV-25750 A (e)	Containment Atmosphere Sample	Automatic Valve	2.b, 2.d
	SV-25750 B (e)	Containment Atmosphere Sample	Automatic Valve	2.b, 2.d
	SV-25752 A (e)	Containment Atmosphere Sample	Automatic Valve	2.b, 2.d
	SV-25752 B (e)	Containment Atmosphere Sample	Automatic Valve	2.b, 2.d
	SV-25767	Nitrogen Makeup	Automatic Valve	2.b, 2.d, 2.e
	SV-25774 A (e)	Containment Atmosphere Sample	Automatic Valve	2.b, 2.d
	SV-25774 B (e)	Containment Atmosphere Sample	Automatic Valve	2.b, 2.d
	SV-25776 A (e)	Containment Atmosphere Sample	Automatic Valve	2.b, 2.d
	SV-25776 B (e)	Containment Atmosphere Sample	Automatic Valve	2.b, 2.d
	SV-25780 A (e)	Containment Atmosphere Sample	Automatic Valve	2.b, 2.d
	SV-25780 B (e)	Containment Atmosphere Sample	Automatic Valve	2.b, 2.d
	SV-25782 A (e)	Containment Atmosphere Sample	Automatic Valve	2.b, 2.d
	SV-25782 B (e)	Containment Atmosphere Sample	Automatic Valve	2.b, 2.d
	SV-25789	Nitrogen Makeup	Automatic Valve	2.b, 2.d, 2.e
Containment Instrument Gas	2-26-072 (d)	Containment Instrument Gas	Manual Check	N/A
	2-26-074 (d)	Containment Instrument Gas	Manual Check	N/A
	2-26-152 (d)	Containment Instrument Gas	Manual Check	N/A
	2-26-154 (d)	Containment Instrument Gas	Manual Check	N/A
	2-26-164 (d)	Containment Instrument Gas	Manual Check	N/A
	HV-22603	Containment Instrument Gas	Automatic Valve	2.c, 2.d (20)
	SV-22605	Containment Instrument Gas	Automatic Valve	2.c, 2.d
	SV-22651	Containment Instrument Gas	Automatic Valve	2.c, 2.d
	SV-22654 A	Containment Instrument Gas	Power Operated	N/A
	SV-22654 B	Containment Instrument Gas	Power Operated	N/A
	SV-22661	Containment Instrument Gas	Automatic Valve	2.b, 2.d
	SV-22671	Containment Instrument Gas	Automatic Valve	2.b, 2.d
Core Spray	HV-252F001 A (b)(c)	CS Suction	Power Operated	N/A
	HV-252F001 B (b)(c)	CS Suction	Power Operated	N/A
	HV-252F005 A	CS Injection	Power Operated	N/A
	HV-252F005 B	CS Injection	Power Operated	N/A
	HV-252F006 A	CS Injection	Air Operated Check Valve	N/A
	HV-252F006 B	CS Injection	Air Operated Check Valve	N/A
	HV-252F015 A (b)(c)	CS Test	Automatic Valve	2.c, 2.d (80)
	HV-252F015 B (b)(c)	CS Test	Automatic Valve	2.c, 2.d (80)
	HV-252F031 A (b)(c)	CS Minimum Recirculation Flow	Power Operated	N/A
	HV-252F031 B (b)(c)	CS Minimum Recirculation Flow	Power Operated	N/A

Table B 3.6.1.3-1 (continued)
Primary Containment Isolation Valve
(Page 3 of 10)

Plant System	Valve Number	Valve Description	Type of Valve	Isolation Signal LCO 3.3.6.1 Function No. (Maximum Isolation Time (Seconds))
Core Spray (continued)	HV-252F037 A	CS Injection	Power Operated (Air)	N/A
	HV-252F037 B	CS Injection	Power Operated (Air)	N/A
	XV-252F018 A	Core Spray	Excess Flow Check Valve	N/A
	XV-252F018 B	Core Spray	Excess Flow Check Valve	N/A
Demin Water	2-41-017 (d)	Demineralized Water	Manual	N/A
	2-41-018 (d)	Demineralized Water	Manual	N/A
HPCI	2-55-038 (d)	HPCI Injection	Manual	N/A
	255F046 (b) (c) (d)	HPCI Minimum Recirculation Flow	Manual Check	N/A
	255F049 (a) (d)	HPCI	Manual Check	N/A
	HV-255F002	HPCI Steam Supply	Automatic Valve	3.a, 3.b, 3.c, 3.e, 3.f, 3.g, (50)
	HV-255F003	HPCI Steam Supply	Automatic Valve	3.a, 3.b, 3.c, 3.e, 3.f, 3.g, (50)
	HV-255F006	HPCI Injection	Power Operated	N/A
	HV-255F012 (b) (c)	HPCI Minimum Recirculation Flow	Power Operated	N/A
	HV-255F042 (b) (c)	HPCI Suction	Automatic Valve	3.a, 3.b, 3.c, 3.e, 3.f, 3.g, (90)
	HV-255F066 (a)	HPCI Turbine Exhaust	Power Operated	N/A
	HV-255F075	HPCI Vacuum Breaker	Automatic Valve	3.b, 3.d, (15)
	HV-255F079	HPCI Vacuum Breaker	Automatic Valve	3.b, 3.d, (15)
	HV-255F100	HPCI Steam Supply	Automatic Valve	3.a, 3.b, 3.c, 3.e, 3.f, 3.g, (6)
	XV-255F024 A	HPCI	Excess Flow Check Valve	N/A
	XV-255F024 B	HPCI	Excess Flow Check Valve	N/A
	XV-255F024 C	HPCI	Excess Flow Check Valve	N/A
	XV-255F024 D	HPCI	Excess Flow Check Valve	N/A
Liquid Radwaste Collection	HV-26108 A1	Liquid Radwaste	Automatic Valve	2.b, 2.d (15)
	HV-26108 A2	Liquid Radwaste	Automatic Valve	2.b, 2.d (15)
	HV-26116 A1	Liquid Radwaste	Automatic Valve	2.b, 2.d (15)
	HV-26116 A2	Liquid Radwaste	Automatic Valve	2.b, 2.d (15)
Nuclear Boiler	241F010 A (d)	Feedwater	Manual Check	N/A
	241F010 B (d)	Feedwater	Manual Check	N/A
	241F039 A (d)	Feedwater Isolation Valve	Manual Check	N/A
	241F039 B (d)	Feedwater Isolation Valve	Manual Check	N/A
	241818 A (d)	Feedwater Isolation Valve	Manual Check	N/A
	241818 B (d)	Feedwater Isolation Valve	Manual Check	N/A

Table B 3.6.1.3-1 (continued)
Primary Containment Isolation Valve
(Page 4 of 10)

Plant System	Valve Number	Valve Description	Type of Valve	Isolation Signal LCO 3.3.6.1 Function No. (Maximum Isolation Time (Seconds))
Nuclear Boiler (continued)	HV-241F016	MSL Drain	Automatic Valve	1.a, 1.b, 1.c, 1.d, 1.e (10)
	HV-241F019	MSL Drain	Automatic Valve	1.a, 1.b, 1.c, 1.d, 1.e (15)
	HV-241F022 A	MSIV	Automatic Valve	1.a, 1.b, 1.c, 1.d, 1.e (5)
	HV-241F022 B	MSIV	Automatic Valve	1.a, 1.b, 1.c, 1.d, 1.e (5)
	HV-241F022 C	MSIV	Automatic Valve	1.a, 1.b, 1.c, 1.d, 1.e (5)
	HV-241F022 D	MSIV	Automatic Valve	1.a, 1.b, 1.c, 1.d, 1.e (5)
	HV-241F028 A	MSIV	Automatic Valve	1.a, 1.b, 1.c, 1.d, 1.e (5)
	HV-241F028 B	MSIV	Automatic Valve	1.a, 1.b, 1.c, 1.d, 1.e (5)
	HV-241F028 C	MSIV	Automatic Valve	1.a, 1.b, 1.c, 1.d, 1.e (5)
	HV-241F028 D	MSIV	Automatic Valve	1.a, 1.b, 1.c, 1.d, 1.e (5)
	HV-241F032 A	Feedwater Isolation Valve	Power Operated Check Valves	N/A
	HV-241F032 B	Feedwater Isolation Valve	Power Operated Check Valves	N/A
	XV-241F009	Nuclear Boiler EFCV	Excess Flow Check Valve	N/A
	XV-241F070 A	Nuclear Boiler EFCV	Excess Flow Check Valve	N/A
	XV-241F070 B	Nuclear Boiler EFCV	Excess Flow Check Valve	N/A
	XV-241F070 C	Nuclear Boiler EFCV	Excess Flow Check Valve	N/A
	XV-241F070 D	Nuclear Boiler EFCV	Excess Flow Check Valve	N/A
	XV-241F071 A	Nuclear Boiler EFCV	Excess Flow Check Valve	N/A
	XV-241F071 B	Nuclear Boiler EFCV	Excess Flow Check Valve	N/A
	XV-241F071 C	Nuclear Boiler EFCV	Excess Flow Check Valve	N/A
	XV-241F071 D	Nuclear Boiler EFCV	Excess Flow Check Valve	N/A
	XV-241F072 A	Nuclear Boiler EFCV	Excess Flow Check Valve	N/A
	XV-241F072 B	Nuclear Boiler EFCV	Excess Flow Check Valve	N/A
	XV-241F072 C	Nuclear Boiler EFCV	Excess Flow Check Valve	N/A
	XV-241F072 D	Nuclear Boiler EFCV	Excess Flow Check Valve	N/A
	XV-241F073 A	Nuclear Boiler EFCV	Excess Flow Check Valve	N/A

Table B 3.6.1.3-1 (continued)
Primary Containment Isolation Valve
(Page 5 of 10)

Plant System	Valve Number	Valve Description	Type of Valve	Isolation Signal LCO 3.3.6.1 Function No. (Maximum Isolation Time (Seconds))
Nuclear Boiler (continued)	XV-241F073 B	Nuclear Boiler EFCV	Excess Flow Check Valve	N/A
	XV-241F073 C	Nuclear Boiler EFCV	Excess Flow Check Valve	N/A
	XV-241F073 D	Nuclear Boiler EFCV	Excess Flow Check Valve	N/A
Nuclear Boiler Vessel Instrumentation	XV-24201	Nuclear Boiler Vessel Instrument	Excess Flow Check Valve	N/A
	XV-24202	Nuclear Boiler Vessel Instrument	Excess Flow Check Valve	N/A
	XV-242F041	Nuclear Boiler Vessel Instrument	Excess Flow Check Valve	N/A
	XV-242F043 A	Nuclear Boiler Vessel Instrument	Excess Flow Check Valve	N/A
	XV-242F043 B	Nuclear Boiler Vessel Instrument	Excess Flow Check Valve	N/A
	XV-242F045 A	Nuclear Boiler Vessel Instrument	Excess Flow Check Valve	N/A
	XV-242F045 B	Nuclear Boiler Vessel Instrument	Excess Flow Check Valve	N/A
	XV-242F047 A	Nuclear Boiler Vessel Instrument	Excess Flow Check Valve	N/A
	XV-242F047B	Nuclear Boiler Vessel Instrument	Excess Flow Check Valve	N/A
	XV-242F051 A	Nuclear Boiler Vessel Instrument	Excess Flow Check Valve	N/A
	XV-242F051 B	Nuclear Boiler Vessel Instrument	Excess Flow Check Valve	N/A
	XV-242F051 C	Nuclear Boiler Vessel Instrument	Excess Flow Check Valve	N/A
	XV-242F051 D	Nuclear Boiler Vessel Instrument	Excess Flow Check Valve	N/A
	XV-242F053 A	Nuclear Boiler Vessel Instrument	Excess Flow Check Valve	N/A
	XV-242F053 B	Nuclear Boiler Vessel Instrument	Excess Flow Check Valve	N/A
	XV-242F053 C	Nuclear Boiler Vessel Instrument	Excess Flow Check Valve	N/A
	XV-242F053 D	Nuclear Boiler Vessel Instrument	Excess Flow Check Valve	N/A
	XV-242F055	Nuclear Boiler Vessel Instrument	Excess Flow Check Valve	N/A
	XV-242F057	Nuclear Boiler Vessel Instrument	Excess Flow Check Valve	N/A
	XV-242F059 A	Nuclear Boiler Vessel Instrument	Excess Flow Check Valve	N/A
	XV-242F059 B	Nuclear Boiler Vessel Instrument	Excess Flow Check Valve	N/A

Table B 3.6.1.3-1
Primary Containment Isolation Valve
(Page 6 of 10)

Plant System	Valve Number	Valve Description	Type of Valve	Isolation Signal LCO 3.3.6.1 Function No. (Maximum Isolation Time (Seconds))
Nuclear Boiler Vessel Instrumentation (continued)	XV-242F059 C	Nuclear Boiler Vessel Instrument	Excess Flow Check Valve	N/A
	XV-242F059 D	Nuclear Boiler Vessel Instrument	Excess Flow Check Valve	N/A
	XV-242F059 E	Nuclear Boiler Vessel Instrument	Excess Flow Check Valve	N/A
	XV-242F059 F	Nuclear Boiler Vessel Instrument	Excess Flow Check Valve	N/A
	XV-242F059 G	Nuclear Boiler Vessel Instrument	Excess Flow Check Valve	N/A
	XV-242F059 H	Nuclear Boiler Vessel Instrument	Excess Flow Check Valve	N/A
	XV-242F059 L	Nuclear Boiler Vessel Instrument	Excess Flow Check Valve	N/A
	XV-242F059 M	Nuclear Boiler Vessel Instrument	Excess Flow Check Valve	N/A
	XV-242F059 N	Nuclear Boiler Vessel Instrument	Excess Flow Check Valve	N/A
	XV-242F059 P	Nuclear Boiler Vessel Instrument	Excess Flow Check Valve	N/A
	XV-242F059 R	Nuclear Boiler Vessel Instrument	Excess Flow Check Valve	N/A
	XV-242F059 S	Nuclear Boiler Vessel Instrument	Excess Flow Check Valve	N/A
	XV-242F059 T	Nuclear Boiler Vessel Instrument	Excess Flow Check Valve	N/A
	XV-242F059 U	Nuclear Boiler Vessel Instrument	Excess Flow Check Valve	N/A
	XV-242F061	Nuclear Boiler Vessel Instrument	Excess Flow Check Valve	N/A
RB Chilled Water System	HV-28781 A1	RB Chilled Water	Automatic Valve	2.c, 2.d (40)
	HV-28781 A2	RB Chilled Water	Automatic Valve	2.c, 2.d (40)
	HV-28781 B1	RB Chilled Water	Automatic Valve	2.c, 2.d (40)
	HV-28781 B2	RB Chilled Water	Automatic Valve	2.c, 2.d (40)
	HV-28782 A1	RB Chilled Water	Automatic Valve	2.c, 2.d (12)
	HV-28782 A2	RB Chilled Water	Automatic Valve	2.c, 2.d (12)
	HV-28782 B1	RB Chilled Water	Automatic Valve	2.c, 2.d (12)
	HV-28782 B2	RB Chilled Water	Automatic Valve	2.c, 2.d (12)
	HV-28791 A1	RB Chilled Water	Automatic Valve	2.c, 2.d (15)
	HV-28791 A2	RB Chilled Water	Automatic Valve	2.c, 2.d (15)
	HV-28791 B1	RB Chilled Water	Automatic Valve	2.c, 2.d (15)
	HV-28791 B2	RB Chilled Water	Automatic Valve	2.c, 2.d (15)
	HV-28792 A1	RB Chilled Water	Automatic Valve	2.c, 2.d (8)
	HV-28792 A2	RB Chilled Water	Automatic Valve	2.c, 2.d (8)
	HV-28792 B1	RB Chilled Water	Automatic Valve	2.c, 2.d (8)

Table B 3.6.1.3-1
Primary Containment Isolation Valve
(Page 7 of 10)

Plant System	Valve Number	Valve Description	Type of Valve	Isolation Signal LCO 3.3.6.1 Function No. (Maximum Isolation Time (Seconds))
RB Chilled Water System (continued)	HV-28792 B2	RB Chilled Water	Automatic Valve	2.b, 2.d (8)
RBCCW	HV-21313	RBCCW	Automatic Valve	2.c, 2.d (30)
	HV-21314	RBCCW	Automatic Valve	2.c, 2.d (30)
	HV-21345	RBCCW	Automatic Valve	2.c, 2.d (30)
	HV-21346	RBCCW	Automatic Valve	2.c, 2.d (30)
RCIC	2-49-020 (d)	RCIC Injection	Manual	N/A
	249F021 (b) (c) (d)	RCIC Minimum Recirculation Flow	Manual Check	N/A
	249F028 (a) (d)	RCIC Vacuum Pump Discharge	Manual	N/A
	249F040 (a) (d)	RCIC Turbine Exhaust	Manual	N/A
	FV-249F019 (b) (c)	RCIC Minimum Recirculation Flow	Power Operated	N/A
	HV-249F007	RCIC Steam Supply	Automatic Valve	4.a, 4.b, 4.c, 4.e, 4.f, 4.g (20)
	HV-249F008	RCIC Steam Supply	Automatic Valve	4.a, 4.b, 4.c, 4.e, 4.f, 4.g (20)
	HV-249F013	RCIC Injection	Power Operated	N/A
	HV-249F031 (b) (c)	RCIC Suction	Power Operated	N/A
	HV-249F059 (a)	RCIC Turbine Exhaust	Power Operated	N/A
	HV-249F060 (a)	RCIC Vacuum Pump Discharge	Power Operated	N/A
	HV-249F062	RCIC Vacuum Breaker	Automatic Valve	4.b, 4.d (10)
	HV-249F084	RCIC Vacuum Breaker	Automatic Valve	4.b, 4.d (10)
	HV-249F088	RCIC Steam Supply	Automatic Valve	4.a, 4.b, 4.c, 4.e, 4.f, 4.g (12)
	XV-249F044 A	RCIC	Excess Flow Check Valve	N/A
	XV-249F044 B	RCIC	Excess Flow Check Valve	N/A
	XV-249F044 C	RCIC	Excess Flow Check Valve	N/A
	XV-249F044 D	RCIC	Excess Flow Check Valve	N/A
Reactor Recirculation	243F013 A (d)	Recirculation Pump Seal Water	Manual Check	N/A
	243F013 B (d)	Recirculation Pump Seal Water	Manual Check	N/A
	HV-243F019	Reactor Coolant Sample	Automatic Valve	2.b (9)
	HV-243F020	Reactor Coolant Sample	Automatic Valve	2.b (2)
	XV-243F003 A	Reactor Recirculation	Excess Flow Check Valve	N/A
	XV-243F003 B	Reactor Recirculation	Excess Flow Check Valve	N/A
	XV-243F004 A	Reactor Recirculation	Excess Flow Check Valve	N/A
	XV-243F004 B	Reactor Recirculation	Excess Flow Check Valve	N/A

Table B 3.6.1.3-1
Primary Containment Isolation Valve
(Page 8 of 10)

Plant System	Valve Number	Valve Description	Type of Valve	Isolation Signal LCO 3.3.6.1 Function No. (Maximum Isolation Time (Seconds))
Reactor Recirculation (continued)	XV-243F009 A	Reactor Recirculation	Excess Flow Check Valve	N/A
	XV-243F009 B	Reactor Recirculation	Excess Flow Check Valve	N/A
	XV-243F009 C	Reactor Recirculation	Excess Flow Check Valve	N/A
	XV-243F009 D	Reactor Recirculation	Excess Flow Check Valve	N/A
	XV-243F010 A	Reactor Recirculation	Excess Flow Check Valve	N/A
	XV-243F010 B	Reactor Recirculation	Excess Flow Check Valve	N/A
	XV-243F010 C	Reactor Recirculation	Excess Flow Check Valve	N/A
	XV-243F010 D	Reactor Recirculation	Excess Flow Check Valve	N/A
	XV-243F011 A	Reactor Recirculation	Excess Flow Check Valve	N/A
	XV-243F011 B	Reactor Recirculation	Excess Flow Check Valve	N/A
	XV-243F011 C	Reactor Recirculation	Excess Flow Check Valve	N/A
	XV-243F011 D	Reactor Recirculation	Excess Flow Check Valve	N/A
	XV-243F012 A	Reactor Recirculation	Excess Flow Check Valve	N/A
	XV-243F012 B	Reactor Recirculation	Excess Flow Check Valve	N/A
	XV-243F012 C	Reactor Recirculation	Excess Flow Check Valve	N/A
	XV-243F012 D	Reactor Recirculation	Excess Flow Check Valve	N/A
	XV-243F017 A	Recirculation Pump Seal Water	Excess Flow Check Valve	N/A
	XV-243F017 B	Recirculation Pump Seal Water	Excess Flow Check Valve	N/A
	XV-243F040 A	Reactor Recirculation	Excess Flow Check Valve	N/A
	XV-243F040 B	Reactor Recirculation	Excess Flow Check Valve	N/A
	XV-243F040 C	Reactor Recirculation	Excess Flow Check Valve	N/A
	XV-243F040 D	Reactor Recirculation	Excess Flow Check Valve	N/A
	XV-243F057 A	Reactor Recirculation	Excess Flow Check Valve	N/A
	XV-243F057 B	Reactor Recirculation	Excess Flow Check Valve	N/A
Residual Heat Removal	HV-251F004 A (b) (c)	RHR – Suppression Pool Suction	Power Operated	N/A
	HV-251F004 B (b) (c)	RHR – Suppression Pool Suction	Power Operated	N/A
	HV-251F004 C (b) (c)	RHR – Suppression Pool Suction	Power Operated	N/A

Table B 3.6.1.3-1 (continued)
Primary Containment Isolation Valve
(Page 9 of 10)

Plant System	Valve Number	Valve Description	Type of Valve	Isolation Signal LCO 3.3.6.1 Function No. (Maximum Isolation Time (Seconds))
Residual Heat Removal (continued)	HV-251F004 D(b) (c)	RHR – Suppression Pool Suction	Power Operated	N/A
	HV-251F007 A (b) (c)	RHR – Minimum Recirculation	Power Operated	N/A
	HV-251F007 B (b) (c)	RHR – Minimum Recirculation	Power Operated	N/A
	HV-251F008	RHR – Shutdown Cooling Suction	Automatic Valve	6.a, 6.b, 6.c (52)
	HV-251F009	RHR – Shutdown Cooling Suction	Automatic Valve	6.a, 6.b, 6.c (52)
	HV-251F011 A (b) (d)	RHR – Suppression Pool Cooling	Manual	N/A
	HV-251F011 B (b) (d)	RHR – Suppression Pool Cooling	Manual	N/A
	HV-251F015 A	RHR – Shutdown Cooling Return/LPCI Injection	Power Operated	N/A
	HV-251F015 B	RHR – Shutdown Cooling Return/LPCI Injection	Power Operated	N/A
	HV-251F016 A (b)	RHR – Drywell Spray	Automatic Valve	2.c, 2.d (90)
	HV-251F016 B (b)	RHR – Drywell Spray	Automatic Valve	2.c, 2.d (90)
	HV-251F022	RHR – Reactor Vessel Head Spray	Automatic Valve	2.d, 6.a, 6.b, 6.c (30)
	HV-251F023	RHR – Reactor Vessel Head Spray	Automatic Valve	2.d, 6.a, 6.b, 6.c (20)
	HV-251F028 A (b)	RHR – Suppression Pool Cooling/Spray	Automatic Valve	2.c, 2.d (90)
	HV-251F028 B (b)	RHR – Suppression Pool Cooling/Spray	Automatic Valve	2.c, 2.d (90)
	HV-251F050 A	RHR – Shutdown Cooling Return/LPCI Injection	Air Operated Check Valve	N/A
	HV-251F050 B	RHR – Shutdown Cooling Return/LPCI Injection	Air Operated Check Valve	N/A
	HV-251F103 A (b)	RHR Heat Exchanger Vent	Power Operated	N/A
	HV-251F103 B (b)	RHR Heat Exchanger Vent	Power Operated	N/A
	HV-251F122 A	RHR – Shutdown Cooling Return/LPCI Injection	Power Operated (Air)	N/A
	HV-251F122 B	RHR – Shutdown Cooling Return/LPCI Injection	Power Operated (Air)	N/A
	PSV-25106 A (b) (d)	RHR- Relief Valve Discharge	Relief Valve	N/A
	PSV-25106 B (b) (d)	RHR- Relief Valve Discharge	Relief Valve	N/A
	PSV-251F126 (d)	RHR- Shutdown Cooling Suction	Relief Valve	N/A
	XV-25109 A	RHR	Excess Flow Check Valve	N/A
	XV-25109 B	RHR	Excess Flow Check Valve	N/A
	XV-25109 C	RHR	Excess Flow Check Valve	N/A
	XV-25109 D	RHR	Excess Flow Check Valve	N/A
RWCU	HV-244F001 (a)	RWCU Suction	Automatic Valve	5.a, 5.b, 5.c, 5.d, 5.f, 5.g (30)

Table B 3.6.1.3-1
Primary Containment Isolation Valve
(Page 10 of 10)

Plant System	Valve Number	Valve Description	Type of Valve	Isolation Signal LCO 3.3.6.1 Function No. (Maximum Isolation Time (Seconds))
RWCU (continued)	HV-244F004 (a)	RWCU Suction	Automatic Valve	5.a, 5.b, 5.c, 5.d, 5.e, 5.f, 5.g (30)
	XV-24411 A	RWCU	Excess Flow Check Valve	N/A
	XV-24411 B	RWCU	Excess Flow Check Valve	N/A
	XV-24411 C	RWCU	Excess Flow Check Valve	N/A
	XV-24411 D	RWCU	Excess Flow Check Valve	N/A
	XV-244F046	RWCU	Excess Flow Check Valve	N/A
	HV-24182 A	RWCU Return	Power Operated	N/A
	HV-24182 B	RWCU Return	Power Operated	N/A
SLCS	248F007 (a) (d)	SLCS	Manual Check	N/A
	HV-248F006 (a)	SLCS	Power Operated Check Valve	N/A
TIP System	C51-J004 A (Ball Valve)	TIP Ball Valves	Automatic Valve	7.a, 7.b (5)
	C51-J004 B (Ball Valve)	TIP Ball Valves	Automatic Valve	7.a, 7.b (5)
	C51-J004 C (Ball Valve)	TIP Ball Valves	Automatic Valve	7.a, 7.b (5)
	C51-J004 D (Ball Valve)	TIP Ball Valves	Automatic Valve	7.a, 7.b (5)
	C51-J004 E (Ball Valve)	TIP Ball Valves	Automatic Valve	7.a, 7.b (5)
TIP System (continued)	C51-J004 A (Shear Valve)	TIP Shear Valves	Squib Valve	N/A
	C51-J004 B (Shear Valve)	TIP Shear Valves	Squib Valve	N/A
	C51-J004 C (Shear Valve)	TIP Shear Valves	Squib Valve	N/A
	C51-J004 D (Shear Valve)	TIP Shear Valves	Squib Valve	N/A
	C51-J004 E (Shear Valve)	TIP Shear Valves	Squib Valve	N/A

(a) Isolation barrier remains filled or a water seal remains in the line post-LOCA, isolation valve is tested with water. Isolation valve leakage is not included in 0.60 L_a total Type B and C tests.
(b) Redundant isolation boundary for this valve is provided by the closed system whose integrity is verified by the Leakage Rate Test Program.
(c) Containment Isolation Valves are not Type C tested. Containment bypass leakage is prevented since the line terminates below the minimum water level in the Suppression Chamber. Refer to the IST Program.
(d) LCO 3.3.3.1, "PAM Instrumentation", Table 3.3.3.1-1, Function 6, (PCIV Position) does not apply since these are relief valves, check valves, manual valves or deactivated and closed.
(e) The containment isolation barriers for the penetration associated with this valve consists of two PCIVs and a closed system. The closed system provides a redundant isolation boundary for both PCIVs, and its integrity is required to be verified by the Leakage Rate Test Program.