

February 9, 2006

Mr. G. R. Peterson  
Vice President  
McGuire Nuclear Station  
Duke Energy Corporation  
12700 Hagers Ferry Road  
Huntersville, NC 28078

SUBJECT: MCGUIRE NUCLEAR STATION, UNITS 1 AND 2, REQUEST FOR ADDITIONAL INFORMATION RE: RESPONSE TO GENERIC LETTER 2004-02, "POTENTIAL IMPACT OF DEBRIS BLOCKAGE ON EMERGENCY RECIRCULATION DURING DESIGN-BASIS ACCIDENTS AT PRESSURIZED-WATER REACTORS" (TAC NOS. MC4692 AND MC4693)

Dear Mr. Peterson:

On September 13, 2004, the Nuclear Regulatory Commission (NRC) issued Generic Letter (GL) 2004-02, "Potential Impact of Debris Blockage on Emergency Recirculation During Design Basis Accidents at Pressurized-Water Reactors," as part of the NRC's efforts to assess the likelihood that the emergency core cooling system (ECCS) and containment spray system (CSS) pumps at domestic pressurized water reactors (PWRs) would experience a debris-induced loss of net positive suction head margin during sump recirculation. The NRC issued this GL to all PWR licensees to request that addressees (1) perform a mechanistic evaluation using an NRC-approved methodology of the potential for the adverse effects of post-accident debris blockage and operation with debris-laden fluids to impede or prevent the recirculation functions of the ECCS and CSS following all postulated accidents for which the recirculation of these systems is required, and (2) implement any plant modifications that the above evaluation identifies as being necessary to ensure system functionality. Addressees were also required to submit information specified in GL 2004-02 to the NRC in accordance with Title 10 of the *Code of Federal Regulations* Section 50.54(f). Additionally, in the GL, the NRC established a schedule for the submittal of the written responses and the completion of any corrective actions identified while complying with the requests in the GL.

By letter dated March 1, 2005, as supplemented by letter dated September 1, 2005, Duke Energy Corporation provided responses to the GL. The NRC staff is reviewing and evaluating your responses along with the responses from all PWR licensees. The NRC staff has determined that responses to the questions in the enclosure to this letter are necessary in order for the staff to complete its review. Please note that the Office of Nuclear Reactor Regulation's Division of Component Integrity is still conducting its initial reviews with respect to coatings. Although some initial coatings questions are included in the enclosure to this letter, the NRC might issue an additional request for information regarding coatings issues in the near future.

G. Peterson

-2-

Please provide your response within 60 days from the date of this letter. If you have any questions, please contact me at (301) 415-1345.

Sincerely,

*/RA/*

John Stang, Senior Project Manager  
Plant Licensing Branch II-1  
Division of Operating Reactor Licensing  
Office of Nuclear Reactor Regulation

Docket Nos. 50-369 and 50-370

Enclosure:  
Request for Additional Information

cc w/encl: See next page

G. Peterson

-2-

Please provide your response within 60 days from the date of this letter. If you have any questions, please contact me at (301) 415-1345.

Sincerely,

*/RA/*

John Stang, Senior Project Manager  
Plant Licensing Branch II-1  
Division of Operating Reactor Licensing  
Office of Nuclear Reactor Regulation

Docket Nos. 50-369 and 50-370

Enclosure:  
Request for Additional Information

cc w/encl: See next page

Distribution:

Public	BSingal, DORL DPR	RArchitzel
LPL2-1 r/f	WBateman	THaffera
RidsNrrDorlLplc	RidsNrrPMJHopkins	JLehning
RidsNrrLAMO'Brien	MMuprhy	HWagage
RidsNrrPMJStang	PKlein	SLu
RidsOgcRp	MYoder	JHannon
RidsAcrcAcnwMailCenter	MScott	
RidsRgn2MailCenter		

Accession No.: ML060370427

\*by email

NRR-088

OFFICE	LPL2-1/PM	LPL2-1/LA	DSS/SSIB	DCI/CSGB	LPL2-1/BC
NAME	JStang:ckg	MO'Brien	DSolorio*	EMurphy*	EMarinos
DATE	2/9/06	2/9/06	2/6/06	2/8/06	2/9/06

**OFFICIAL RECORD COPY**

McGuire Nuclear Station, Units 1 & 2

cc:

Ms. Lisa F. Vaughn  
Duke Energy Corporation  
526 South Church Street  
P. O. Box 1006  
Mail Code = EC07H  
Charlotte, North Carolina 28202

County Manager of Mecklenburg County  
720 E. Fourth St.  
Charlotte, NC 28202

Mr. C. Jeffrey Thomas  
Regulatory Compliance Manager  
Duke Energy Corporation  
McGuire Nuclear Site  
12700 Hagers Ferry Road  
Huntersville, NC 28078

Senior Resident Inspector  
c/o U.S. Nuclear Regulatory Commission  
12700 Hagers Ferry Road  
Huntersville, NC 28078

Dr. John M. Barry  
Mecklenburg County  
Department of Environmental Protection  
700 N. Tryon St  
Charlotte, NC 28202

Mr. Peter R. Harden, IV  
VP-Customer Relations and Sales  
Westinghouse Electric Company  
6000 Fairview Road, 12th Floor  
Charlotte, NC 28210

NCEM REP Program Manager  
4713 Mail Service Center  
Raleigh, NC 27699-4713

Ms. Karen E. Long  
Assistant Attorney General  
NC Department of Justice  
P.O. Box 629  
Raleigh, NC 27602

Mr. R.L. Gill, Jr., Manager  
Nuclear Regulatory Issues &  
Industry Affairs  
Duke Energy Corporation  
526 S. Church St.  
Mail Stop EC05P  
Charlotte, NC 28202

Division of Radiation Protection  
NC Dept of Environment, Health & Natural  
Resources  
3825 Barrett Dr.  
Raleigh, NC 27609-7721

Mr. T. Richard Puryear  
Owners Group (NCEMC)  
Duke Energy Corporation  
4800 Concord Road  
York, SC 29745

Mr. Henry Barron  
Group Vice President, Nuclear Generation  
& Chief Nuclear Officer  
P.O. Box 1006-EC07H  
Charlotte, NC 28201-1006

## GL 2004-02 RAI Questions

### **Plant Materials**

1. Identify the name and bounding quantity of each insulation material generated by a large-break loss-of-coolant accident (LBLOCA). Include the amount of these materials transported to the containment pool. State any assumptions used to provide this response.
2. Identify the amounts (i.e., surface area) of the following materials that are:
  - (a) submerged in the containment pool following a loss-of-coolant accident (LOCA),
  - (b) in the containment spray zone following a LOCA:
    - aluminum
    - zinc (from galvanized steel and from inorganic zinc coatings)
    - copper
    - carbon steel not coated
    - uncoated concrete

Compare the amounts of these materials in the submerged and spray zones at your plant relative to the scaled amounts of these materials used in the Nuclear Regulatory Commission (NRC) nuclear industry jointly-sponsored Integrated Chemical Effects Tests (ICET) (e.g., 5x the amount of uncoated carbon steel assumed for the ICETs).

3. Identify the amount (surface area) and material (e.g., aluminum) for any scaffolding stored in containment. Indicate the amount, if any, that would be submerged in the containment pool following a LOCA. Clarify if scaffolding material was included in the response to Question 2.
4. Provide the type and amount of any metallic paints or non-stainless steel insulation jacketing (not included in the response to Question 2) that would be either submerged or subjected to containment spray.

### **Containment Pool Chemistry**

5. Provide the expected containment pool pH during the emergency core cooling system (ECCS) recirculation mission time following a LOCA at the beginning of the fuel cycle and at the end of the fuel cycle. Identify any key assumptions.
6. For the ICET environment that is the most similar to your plant conditions, compare the expected containment pool conditions to the ICET conditions for the following items: boron concentration, buffering agent concentration, and pH. Identify any other significant differences between the ICET environment and the expected plant-specific environment.

7. For a LBLOCA, provide the time until ECCS external recirculation initiation and the associated pool temperature and pool volume. Provide estimated pool temperature and pool volume 24 hours after a LBLOCA. Identify the assumptions used for these estimates.

### **Plant-Specific Chemical Effects**

8. Discuss your overall strategy to evaluate potential chemical effects including demonstrating that, with chemical effects considered, there is sufficient net positive suction head (NPSH) margin available during the ECCS mission time. Provide an estimated date with milestones for the completion of all chemical effects evaluations.
9. Identify, if applicable, any plans to remove certain materials from the containment building and/or to make a change from the existing chemicals that buffer containment pool pH following a LOCA.
10. If bench-top testing is being used to inform plant specific head loss testing, indicate how the bench-top test parameters (e.g., buffering agent concentrations, pH, materials, etc.) compare to your plant conditions. Describe your plans for addressing uncertainties related to head loss from chemical effects including, but not limited to, use of chemical surrogates, scaling of sample size and test durations. Discuss how it will be determined that allowances made for chemical effects are conservative.

### **Plant Environment Specific**

11. Provide a detailed description of any testing that has been or will be performed as part of a plant-specific chemical effects assessment. Identify the vendor, if applicable, that will be performing the testing. Identify the environment (e.g., borated water at pH 9, deionized water, tap water) and test temperature for any plant-specific head loss or transport tests. Discuss how any differences between these test environments and your plant containment pool conditions could affect the behavior of chemical surrogates. Discuss the criteria that will be used to demonstrate that chemical surrogates produced for testing (e.g., head loss, flume) behave in a similar manner physically and chemically as in the ICET environment and plant containment pool environment.
12. For your plant-specific environment, provide the maximum projected head loss resulting from chemical effects (a) within the first day following a LOCA, and (b) during the entire ECCS recirculation mission time. If the response to this question will be based on testing that is either planned or in progress, provide an estimated date for providing this information to the NRC.

### **ICET 1 and ICET 5 Plants**

13. Results from the ICET #1 environment and the ICET #5 environment showed chemical products appeared to form as the test solution cooled from the constant 140 °F test temperature. Discuss how these results are being considered in your evaluation of chemical effects and downstream effects.

**Trisodium Phosphate (TSP) Plants**

- 14. (Not Applicable).
- 15. (Not Applicable).
- 16. (Not Applicable).

**Additional Non-Coatings Questions**

- 17. (Not Applicable).
- 18. (Not Applicable).
- 19. (Not Applicable).
- 20. (Not Applicable).
- 21. (Not Applicable).
- 22. (Not Applicable).
- 23. (Not Applicable).
- 24. (Not Applicable).

**Coatings**

Generic - All Plants

- 25. Describe how your coatings assessment was used to identify degraded qualified/acceptable coatings and determine the amount of debris that will result from these coatings. This should include how the assessment technique(s) demonstrates that qualified/acceptable coatings' remain in compliance with plant licensing requirements for design-basis accident (DBA) performance. If current examination techniques cannot demonstrate the coatings' ability to meet plant licensing requirements for DBA performance, licensees should describe an augmented testing and inspection program that provides assurance that the qualified/acceptable coatings continue to meet DBA performance requirements. Alternately, assume all containment coatings fail and describe the potential for this debris to transport to the sump.

Plant Specific

- 26. (Not Applicable).
- 27. (Not Applicable).
- 28. (Not Applicable).

29. (Not Applicable).
30. The NRC staff's safety evaluation (SE) addresses two distinct scenarios for formation of a fiber bed on the sump screen surface. For a thin bed case, the SE states that all coatings debris should be treated as particulate and assumes 100% transport to the sump screen. For the case in which no thin bed is formed, the staff's SE states that the coatings debris should be sized based on plant-specific analyses for debris generated from within the ZOI and from outside the ZOI, or that a default chip size equivalent to the area of the sump screen openings should be used (Section 3.4.3.6). Describe how your coatings debris characteristics are modeled to account for your plant-specific fiber bed (i.e. thin bed or no thin bed). If your analysis considers both a thin bed and a non-thin bed case, discuss the coatings debris characteristics assumed for each case. If your analysis deviates from the coatings debris characteristics described in the staff-approved methodology, provide justification to support your assumptions.
31. Was/will "leak before break" be used to analyze the potential jet impingement loads on the new ECCS sump screen?
32. You indicated that you would be evaluating downstream effects in accordance with WCAP 16406-P. The NRC is currently involved in discussions with the Westinghouse Owner's Group (WOG) to address questions/concerns regarding this WCAP on a generic basis, and some of these discussions may resolve issues related to your particular station. The following issues have the potential for generic resolution; however, if a generic resolution cannot be obtained, plant-specific resolution will be required. As such, formal RAls will not be issued on these topics at this time, but may be needed in the future. It is expected that your final evaluation response will specifically address those portions of the WCAP used, their applicability, and exceptions taken to the WCAP. For your information, topics under ongoing discussion include:
- ee. Wear rates of pump-wetted materials and the effect of wear on component operation
  - ff. Settling of debris in low flow areas downstream of the strainer or credit for filtering leading to a change in fluid composition
  - gg. Volume of debris injected into the reactor vessel and core region
  - hh. Debris types and properties
  - ii. Contribution of in-vessel velocity profile to the formation of a debris bed or clog
  - jj. Fluid and metal component temperature impact
  - kk. Gravitational and temperature gradients
  - ll. Debris and boron precipitation effects
  - mm. ECCS injection paths
  - nn. Core bypass design features
  - oo. Radiation and chemical considerations
  - pp. Debris adhesion to solid surfaces
  - qq. Thermodynamic properties of coolant
33. Your response to GL 2004-02 question (d)(viii) indicated that an active strainer design will not be used, but does not mention any consideration of any other active approaches



- (i.e., backflushing). Was an active approach considered as a potential strategy or backup for addressing any issues?
34. You stated that the containment walkdown for Unit 1 will be completed in accordance with Nuclear Energy Institute (NEI) 02-01 during the fall 2005 outage. Please discuss the plans to incorporate the results of this future containment walkdown into the sump design analyses.
  35. You stated that Microtherm® insulation (currently installed on portions of the reactor vessel heads) will be replaced, and that this replacement will reduce the postulated post-accident debris loading on the sump strainer. Please discuss the insulation material that will replace the Microtherm® insulation, including debris generation and characteristics parameters. Has the new insulation been evaluated in the debris generation, transport, head loss analyses and other sump design analyses?
  36. You did not provide information on the details of the break selection, ZOI and debris characteristics evaluations other than to state that the NEI and SE methodologies were applied. Please provide a description of the methodology applied in these evaluations and include a discussion of the technical justification for deviations from the SE-approved methodology.
  37. Has debris settling upstream of the sump strainer (i.e., the near-field effect) been credited or will it be credited in testing used to support the sizing or analytical design basis of the proposed replacement strainers? In the case that settling was credited for either of these purposes, estimate the fraction of debris that settled and describe the analyses that were performed to correlate the scaled flow conditions and any surrogate debris in the test flume with the actual flow conditions and debris types in the plant's containment pool.
  38. Are there any vents or other penetrations through the strainer control surfaces which connect the volume internal to the strainer to the containment atmosphere above the containment minimum water level? In this case, dependent upon the containment pool height and strainer and sump geometries, the presence of the vent line or penetration could prevent a water seal over the entire strainer surface from ever forming; or else this seal could be lost once the head loss across the debris bed exceeds a certain criterion, such as the submergence depth of the vent line or penetration. According to Appendix A to Regulatory Guide 1.82, Revision 3, without a water seal across the entire strainer surface, the strainer should not be considered to be "fully submerged." Therefore, if applicable, explain what sump strainer failure criteria are being applied for the "vented sump" scenario described above.
  39. What is the minimum strainer submergence during the postulated LOCA? At the time that the re-circulation starts, most of the strainer surface is expected to be clean, and the strainer surface close to the pump suction line may experience higher fluid flow than the rest of the strainer. Has any analysis been done to evaluate the possibility of vortex formation close to the pump suction line and possible air ingestion into the ECCS pumps? In addition, has any analysis or test been performed to evaluate the possible accumulation of buoyant debris on top of the strainer, which may cause the formation of

an air flow path directly through the strainer surface and reduce the effectiveness of the strainer?

40. Please provide a detailed description of the analyses/testing performed to evaluate the new strainer head loss.
41. Please describe, in detail, the analysis performed to determine the minimum water level, and explain how the water source from the ice condenser is determined.
42. Your September 2005 GL response stated that the design of the modified containment sump would accommodate the effects of debris loading as determined by the baseline evaluation, which was under review by Duke, and the ongoing refined evaluation for McGuire and that the evaluations use the guidance of NEI 04-07, "Pressurized Water Reactor Sump Performance Evaluation Methodology, Revision 0," dated December 2004. Please supplement your response after completing the review.