

3.4 REACTOR COOLANT SYSTEM (RCS)

3.4.9 Pressurizer

LCO 3.4.9 The pressurizer shall be OPERABLE with:

- a. Pressurizer water level  $\leq 65.1\%$  in MODES 1 and 2, or  $\leq 84\%$  in MODE 3; and
- b. Two groups of pressurizer heaters OPERABLE with the capacity of each group  $\geq 150$  kW with each group powered from a different safeguards power train.

APPLICABILITY: MODES 1, 2, and 3.

ACTIONS

CONDITION	REQUIRED ACTION	COMPLETION TIME
A. Pressurizer water level not within limit.	A.1 Be in MODE 3. <u>AND</u>	6 hours
	A.2 Fully insert all rods. <u>AND</u>	6 hours
	A.3 Place Rod Control System in a condition incapable of rod withdrawal. <u>AND</u>	6 hours
	A.4 Be in MODE 4.	12 hours
B. One required group of pressurizer heaters inoperable.	B.1 Restore required group of pressurizer heaters to OPERABLE status.	72 hours

**ACTIONS (continued)**

CONDITION	REQUIRED ACTION	COMPLETION TIME
C. Required Action and associated Completion Time of Condition B not met.	C.1 Be in MODE 3.	6 hours
	AND C.2 Be in MODE 4.	12 hours

**SURVEILLANCE REQUIREMENTS**

SURVEILLANCE	FREQUENCY
SR 3.4.9.1 Verify pressurizer water level is $\leq 65.1\%$ in MODES 1 and 2, or $\leq 84\%$ in MODE 3.	12 hours
SR 3.4.9.2 Verify capacity of each required group of pressurizer heaters is $\geq 150$ kW.	24 months