

April 17, 2006

Mr. J. A. Stall  
Senior Vice President, Nuclear and  
Chief Nuclear Officer  
Florida Power and Light Company  
P.O. Box 14000  
Juno Beach, Florida 33408-0420

SUBJECT: ST. LUCIE PLANT, UNIT 2 - UPCOMING STEAM GENERATOR TUBE  
INSERVICE INSPECTION (TAC NO. MD1084)

Dear Mr. Stall:

Inservice inspections of steam generator (SG) tubes play a vital role in assuring that adequate structural integrity of the tubes is maintained. As required by the plant Technical Specifications, reporting requirements range from submitting a special report, within 15 days following completion of each inservice inspection of SG tubes, that identifies the number of tubes plugged and/or repaired; to submitting a special report, within 12 months following completion of the inspection, that provides complete results of the SG tube inservice inspection. The special report containing the complete results shall include the following:

1. Number and extent of tubes inspected.
2. Location and percent of wall-thickness penetration for each indication of an imperfection.
3. Identification of tubes plugged and/or repaired.

A phone conference has been arranged with members of your staff to discuss the ongoing results of the SG tube inspections to be conducted during the St. Lucie Unit 2 refueling outage. This phone call will occur after the majority of the tubes have been inspected, but before the SG inspection activities have been completed.

Enclosed is a list of discussion points to be used in this phone conference. The staff plans to document a brief summary of the conference call, as well as any material that you may have provided to the staff in support of the call.

Sincerely,

**/RA/**

Brendan T. Moroney, Project Manager  
Plant Licensing Branch II-2  
Division of Operating Reactor Licensing  
Office of Nuclear Reactor Regulation

Docket No. 50-389

Enclosure: List of Discussion Points

cc w/encl: See next page

April 17, 2006

Mr. J. A. Stall  
Senior Vice President, Nuclear and  
Chief Nuclear Officer  
Florida Power and Light Company  
P.O. Box 14000  
Juno Beach, Florida 33408-0420

SUBJECT: ST. LUCIE PLANT, UNIT 2 - UPCOMING STEAM GENERATOR TUBE  
INSERVICE INSPECTION (TAC NO. MD1084)

Dear Mr. Stall:

Inservice inspections of steam generator (SG) tubes play a vital role in assuring that adequate structural integrity of the tubes is maintained. As required by the plant Technical Specifications, reporting requirements range from submitting a special report, within 15 days following completion of each inservice inspection of SG tubes, that identifies the number of tubes plugged and/or repaired; to submitting a special report, within 12 months following completion of the inspection, that provides complete results of the SG tube inservice inspection. The special report containing the complete results will include the following:

1. Number and extent of tubes inspected.
2. Location and percent of wall-thickness penetration for each indication of an imperfection.
3. Identification of tubes plugged and/or repaired.

A phone conference has been arranged with members of your staff to discuss the ongoing results of the SG tube inspections to be conducted during the St. Lucie Unit 2 refueling outage. This phone call will occur after the majority of the tubes have been inspected, but before the SG inspection activities have been completed.

Enclosed is a list of discussion points to be used in this phone conference. The staff plans to document a brief summary of the conference call, as well as any material that you may have provided to the staff in support of the call.

Sincerely,

**/RA/**

Brendan T. Moroney, Project Manager  
Plant Licensing Branch II-2  
Division of Operating Reactor Licensing  
Office of Nuclear Reactor Regulation

Docket No. 50-389

Enclosure: List of Discussion Points

cc w/encl: See next page

DISTRIBUTION:

PUBLIC	LPL2-2 r/f	RidsNrrDorlLpID	RidsNrrPMBMoroney	RidsNrrDciCsgb
RidsNrrLABClayton		RidsOgcRp	RidsAcrsAcnwMailCenter	
RidsRgn2MailCenter		KKarwoski, NRR	GMakar, NRR	
Adams Accession No.	ML060960106			NRR-106

OFFICE	PM:LPL2-2	LA:LPL2-2	BC:LPL2-2
NAME	BMoroney	BClayton	MMarshall
DATE	04/6/06	04/6/06	04/17/06

**OFFICIAL RECORD COPY**

STEAM GENERATOR TUBE INSPECTION DISCUSSION POINTS

PREPARED BY THE OFFICE OF NUCLEAR REACTOR REGULATION

FLORIDA POWER AND LIGHT COMPANY

SAINT LUCIE NUCLEAR PLANT UNIT 2

DOCKET NO. 50-389

The following discussion points have been prepared to facilitate the phone conference arranged with Florida Power & Light Company to discuss the results of the steam generator (SG) tube inspections to be conducted during the upcoming St. Lucie Nuclear Plant, Unit 2 refueling outage (SL2-16). This phone call is scheduled to occur toward the end of the planned SG tube inspection interval, but before the unit completes the inspections and repairs.

The staff plans to document a brief summary of the conference call as well as any material that is provided in support of the call.

1. Discuss any trends in the amount of primary-to-secondary leakage observed during the recently completed cycle.
2. Discuss whether any secondary side pressure tests were performed during the outage and the associated results.
3. Discuss any exceptions taken to the industry guidelines.
4. For each steam generator, provide a description of the inspections performed including the areas examined and the probes used (e.g., dents/dings, sleeves, expansion-transition, U-bends with a rotating probe), the scope of the inspection (e.g., 100 percent of dents/dings greater than 5 volts and a 20 percent sample between 2 and 5 volts), and the expansion criteria.
5. For each area examined (e.g., tube supports, dents/dings, sleeves, etc.), provide a summary of the number of indications identified to-date of each degradation mode (e.g., number of circumferential primary water stress corrosion cracking indications at the expansion transition). For the most significant indications in each area, provide an estimate of the severity of the indication (e.g., provide the voltage, depth, and length of the indication). In particular, address whether tube integrity (structural and accident induced leakage integrity) was maintained during the previous operating cycle. In addition, discuss whether any location exhibited a degradation mode that had not previously been observed at this location at this unit (e.g., observed circumferential primary water stress corrosion cracking at the expansion transition for the first time at this unit).
6. Describe repair/plugging plans.

Enclosure

7. Describe in situ pressure test and tube pull plans and results (as applicable and if available).
8. Provide the schedule for SG-related activities during the remainder of the current outage.
9. Discuss the following regarding loose parts:
  - what inspections are performed to detect loose parts
  - a description of any loose parts detected and their location within the SG
  - if the loose parts were removed from the SG
  - indications of tube damage associated with the loose parts
  - the source or nature of the loose parts if known
10. Discuss the results of any secondary side inspections.
11. Discuss any unexpected or unusual results.

Mr. J. A. Stall  
Florida Power and Light Company

cc:  
Senior Resident Inspector  
St. Lucie Plant  
U.S. Nuclear Regulatory Commission  
P.O. Box 6090  
Jensen Beach, Florida 34957

Craig Fugate, Director  
Division of Emergency Preparedness  
Department of Community Affairs  
2740 Centerview Drive  
Tallahassee, Florida 32399-2100

M. S. Ross, Managing Attorney  
Florida Power & Light Company  
P.O. Box 14000  
Juno Beach, FL 33408-0420

Marjan Mashhadi, Senior Attorney  
Florida Power & Light Company  
801 Pennsylvania Avenue, NW.  
Suite 220  
Washington, DC 20004

Mr. Douglas Anderson  
County Administrator  
St. Lucie County  
2300 Virginia Avenue  
Fort Pierce, Florida 34982

Mr. William A. Passetti, Chief  
Department of Health  
Bureau of Radiation Control  
2020 Capital Circle, SE, Bin #C21  
Tallahassee, Florida 32399-1741

Mr. C. Costanzo  
Acting Plant General Manager  
St. Lucie Nuclear Plant  
6351 South Ocean Drive  
Jensen Beach, Florida 34957

Mr. Terry Patterson  
Licensing Manager  
St. Lucie Nuclear Plant  
6351 South Ocean Drive  
Jensen Beach, Florida 34957

## **ST. LUCIE PLANT**

Mark Warner, Vice President  
Nuclear Operations Support  
Florida Power and Light Company  
P.O. Box 14000  
Juno Beach, FL 33408-0420

Mr. Rajiv S. Kundalkar  
Vice President - Nuclear Engineering  
Florida Power & Light Company  
P.O. Box 14000  
Juno Beach, FL 33408-0420

Mr. J. Kammel  
Radiological Emergency  
Planning Administrator  
Department of Public Safety  
6000 Southeast Tower Drive  
Stuart, Florida 34997

Mr. G. L. Johnston  
Acting Vice President  
St. Lucie Nuclear Plant  
6351 South Ocean Drive  
Jensen Beach, Florida 34957-2000

Mr. Bill Parks  
Acting Operations Manager  
St. Lucie Nuclear Plant  
6351 South Ocean Drive  
Jensen Beach, Florida 34957-2000