

SURVEILLANCE REQUIREMENTS

SURVEILLANCE		FREQUENCY
SR 3.7.5.1	Verify each AFW manual, power operated, and automatic valve in each water flow path, and in both steam supply flow paths to the steam turbine driven pump, that is not locked, sealed, or otherwise secured in position, is in the correct position.	31 days
SR 3.7.5.2	<p style="text-align: center;">NOTE</p> <p>Not required to be performed for the turbine driven AFW pump until 24 hours after \geq 650 psig in the steam generator.</p> <hr/> <p>Verify the developed head of each AFW pump at the flow test point is greater than or equal to the required developed head.</p>	In accordance with the Inservice Test Program.
SR 3.7.5.3	<p style="text-align: center;">NOTE</p> <p>Not applicable in MODE 4 when steam generator is relied upon for heat removal.</p> <hr/> <p>Verify each AFW automatic valve that is not locked, sealed, or otherwise secured in position, actuates to the correct position on an actual or simulated actuation signal.</p>	24 months
SR 3.7.5.4	<p style="text-align: center;">NOTES</p> <ol style="list-style-type: none"> 1. Not required to be performed for the turbine driven AFW pump until 24 hours after \geq 650 psig in the steam generator. 2. Not applicable in MODE 4 when generator is relied upon for heat removal. <hr/> <p>Verify each AFW pump starts automatically on an actual or simulated actuation signal.</p>	24 months
SR 3.7.5.5	Not used.	
SR 3.7.5.6	Verify the FWST is capable of being aligned to the AFW system by cycling each FWST valve in the flow path necessary for realignment through at least one full cycle.	24 months