

- (b) Pursuant to the Act and 10 CFR Part 70, to possess and use four (4) mixed oxide fuel assemblies in accordance with the RG&E's application dated December 14, 1979 (transmitted by letter dated December 20, 1979), as supplemented February 20, 1980 and March 5, 1980;
  - (3) Pursuant to the Act and 10 CFR Parts 30, 40, and 70 to receive, possess, and use at any time any byproduct, source, and special nuclear material as sealed neutron sources for reactor startup, sealed sources for reactor instrumentation and radiation monitoring equipment calibration, and as fission detectors in amounts as required;
  - (4) Pursuant to the Act and 10 CFR Parts 30, 40, and 70, to receive, possess, and use in amounts as required any byproduct, source, or special nuclear material without restriction to chemical or physical form, for sample analysis or instrument calibration or associated with radioactive apparatus or components; and
  - (5) Pursuant to the Act and 10 CFR Parts 30 and 70, to possess, but not separate, such byproduct and special nuclear materials as may be produced by the operation of the facility.
- C. This renewed license shall be deemed to contain and is subject to the conditions specified in the following Commission regulations in 10 CFR Part 20, Section 30.34 of Part 30, Section 40.41 of Part 40, Sections 50.54 and 50.59 of Part 50, and Section 70.32 of Part 70; and is subject to all applicable provisions of the Act and rules, regulations and orders of the Commission now or hereafter in effect; and is subject to the additional conditions specified below:
- (1) Maximum Power Level

Ginna LLC is authorized to operate the facility at steady-state power levels up to a maximum of 1775 megawatts (thermal).
  - (2) Technical Specifications

The Technical Specifications contained in Appendix A, as revised through Amendment No. 99, are hereby incorporated in the renewed license. The licensee shall operate the facility in accordance with the Technical Specifications.
  - (3) Fire Protection
    - (a) The licensee shall implement and maintain in effect all fire protection features described in the licensee's submittals referenced in and as approved or modified by the NRC's Fire Protection Safety Evaluation (SE) dated February 14, 1979 and

### 3.6 CONTAINMENT SYSTEMS

#### 3.6.6 Containment Spray (CS), Containment Recirculation Fan Cooler (CRFC), and NaOH Systems

LCO 3.6.6 Two CS trains, four CRFC units, and the NaOH system shall be OPERABLE.

-----  
- NOTE -  
-----

In MODE 4, both CS pumps may be in pull-stop for up to 2 hours for the performance of interlock and valve testing of motor operated valves (MOV) 857A, 857B, and 857C. Power may also be restored to MOVs 896A and 896B, and the valves placed in the closed position, for up to 2 hours for the purpose of each test.  
-----

APPLICABILITY: MODES 1, 2, 3, and 4.

#### ACTIONS

CONDITION		REQUIRED ACTION	COMPLETION TIME
A.	One CS train inoperable.	A.1 Restore CS train to OPERABLE status.	72 hours
B.	NaOH system inoperable.	B.1 Restore NaOH System to OPERABLE status.	72 hours
C.	Required Action and associated Completion Time of Condition A or B not met.	C.1 Be in MODE 3.	6 hours
		<u>AND</u> C.2 Be in MODE 5.	84 hours
D.	One or two CRFC units inoperable.	D.1 Restore CRFC unit(s) to OPERABLE status.	7 days
E.	Required Action and associated Completion Time of Condition D not met.	E.1 Be in MODE 3.	6 hours
		<u>AND</u> E.2 Be in MODE 5.	36 hours

CONDITION	REQUIRED ACTION	COMPLETION TIME
F. Two CS trains inoperable.  <u>OR</u>  Three or more CRFC units inoperable.	F.1 Enter LCO 3.0.3.	Immediately

#### SURVEILLANCE REQUIREMENTS

SURVEILLANCE		FREQUENCY
SR 3.6.6.1	Perform SR 3.5.2.1 and SR 3.5.2.3 for valves 896A and 896B.	In accordance with applicable SRs.
SR 3.6.6.2	Verify each CS manual, power operated, and automatic valve in the flow path that is not locked, sealed, or otherwise secured in position is in the correct position.	31 days
SR 3.6.6.3	Verify each NaOH System manual, power operated, and automatic valve in the flow path that is not locked, sealed, or otherwise secured in position is in the correct position.	31 days
SR 3.6.6.4	Operate each CRFC unit for $\geq 15$ minutes.	31 days
SR 3.6.6.5	Verify cooling water flow through each CRFC unit.	31 days
SR 3.6.6.6	Verify each CS pump's developed head at the flow test point is greater than or equal to the required developed head.	In accordance with the Inservice Testing Program
SR 3.6.6.7	Verify NaOH System solution volume is $\geq 3000$ gal.	184 days
SR 3.6.6.8	Verify NaOH System tank NaOH solution concentration is $\geq 30\%$ and $\leq 35\%$ by weight.	184 days
SR 3.6.6.9	Perform required CRFC unit testing in accordance with the VFTP.	In accordance with the VFTP
SR 3.6.6.10	Verify each automatic CS valve in the flow path that is not locked, sealed, or otherwise secured in position actuates to the correct position on an actual or simulated actuation signal.	24 months

SURVEILLANCE		FREQUENCY
SR 3.6.6.11	Verify each CS pump starts automatically on an actual or simulated actuation signal.	24 months
SR 3.6.6.12	Verify each CRFC unit starts automatically on an actual or simulated actuation signal.	24 months
SR 3.6.6.13	Verify each automatic NaOH System valve in the flow path that is not locked, sealed, or otherwise secured in position actuates to the correct position on an actual or simulated actuation signal.	24 months
SR 3.6.6.14	Verify spray additive flow through each eductor path.	5 years
SR 3.6.6.15	Verify each spray nozzle is unobstructed.	Following maintenance which could result in nozzle blockage