

3.4 REACTOR COOLANT SYSTEM (RCS)

3.4.15 RCS Leakage Detection Instrumentation

LCO 3.4.15 The following RCS leakage detection instrumentation shall be OPERABLE:

- a. The containment sump level and flow monitoring system;
- b. One containment atmosphere particulate radioactivity monitor; and
- c. One containment air cooler condensate monitoring system.

APPLICABILITY: MODES 1, 2, 3, and 4.

ACTIONS

CONDITION	REQUIRED ACTION	COMPLETION TIME
<p>A. Required containment sump level and flow monitoring system inoperable.</p>	<p>A.1 -----NOTE----- Not required until 12 hours after establishment of steady state operation. -----</p>	<p>Once per 24 hours</p>
	<p>Perform SR 3.4.13.1.</p> <p><u>AND</u></p> <p>A.2 Restore required containment sump level and flow monitoring system to OPERABLE status.</p>	

(continued)

ACTIONS (continued)

CONDITION	REQUIRED ACTION	COMPLETION TIME
<p>B. Required containment atmosphere particulate radioactivity monitor inoperable.</p>	<p>B.1.1 Analyze samples of the containment atmosphere.</p>	<p>Once per 24 hours</p>
	<p><u>OR</u></p>	
	<p>B.1.2 -----NOTE----- Not required until 12 hours after establishment of steady state operation. -----</p>	
	<p>Perform SR 3.4.13.1.</p>	<p>Once per 24 hours</p>
	<p><u>AND</u></p>	
<p>C. Required containment cooler condensate monitoring system inoperable.</p>	<p>B.2.1 Restore required containment atmosphere particulate radioactivity monitor to OPERABLE status.</p>	<p>30 days</p>
	<p><u>OR</u></p>	
	<p>B.2.2 Verify containment air cooler condensate monitoring system is OPERABLE.</p>	<p>30 days</p>
	<p>C.1 Perform SR 3.4.15.1.</p>	<p>Once per 8 hours</p>
<p><u>OR</u></p>		
<p>C.2 -----NOTE----- Not required until 12 hours after establishment of steady state operation. -----</p>		
<p>Perform SR 3.4.13.1.</p>	<p>Once per 24 hours</p>	

(continued)

SURVEILLANCE REQUIREMENTS

SURVEILLANCE		FREQUENCY
SR 3.4.15.1	Perform CHANNEL CHECK of the required containment atmosphere particulate radioactivity monitor.	12 hours
SR 3.4.15.2	Perform COT of the required containment atmosphere particulate radioactivity monitor.	92 days
SR 3.4.15.3	Perform CHANNEL CALIBRATION of the required containment sump level and flow monitoring system.	18 months
SR 3.4.15.4	Perform CHANNEL CALIBRATION of the required containment atmosphere particulate radioactivity monitor.	18 months
SR 3.4.15.5	Perform CHANNEL CALIBRATION of the required containment cooler condensate monitoring system.	18 months