

- (3) Pursuant to the Act and 10 CFR Parts 30, 40, and 70, to receive, possess, and use at any time any byproduct, source, and special nuclear material as sealed neutron sources for reactor startup, sealed sources for reactor instrumentation and radiation monitoring equipment calibration, and as fission detectors in amounts as required;
- (4) Pursuant to the Act and 10 CFR Parts 30, 40, and 70, to receive, possess, and use in amounts as required any byproduct, source, or special nuclear material without restriction to chemical or physical form for sample analysis or equipment and instrument calibration or associated with radioactive apparatus or components;
- (5) Pursuant to the Act and 10 CFR Parts 30 and 70, to possess but not separate, such byproduct and special nuclear materials as may be produced by the operation of the facility.

C. This renewed operating license shall be deemed to contain and is subject to the conditions specified in the following Commission regulations in 10 CFR Chapter I: Part 20, Section 30.34 of Part 30, Section 40.41 of Part 40, Sections 50.54 and 50.59 of Part 50, and Section 70.32 of Part 70; is subject to all applicable provisions of the Act and to the rules, regulations, and orders of the Commission now or hereafter in effect; and is subject to the additional conditions specified or incorporated below:

(1) Maximum Power Level

The licensee is authorized to operate the facility at steady state reactor core power levels not in excess of 3293 megawatts thermal.

(2) Technical Specifications

The Technical Specifications contained in Appendices A and B, as revised through Amendment No. 262, are hereby incorporated in the renewed operating license. The licensee shall operate the facility in accordance with the Technical Specifications.

For Surveillance Requirements (SRs) that are new in Amendment 234 to Facility Operating License DPR-33, the first performance is due at the end of the first surveillance interval that begins at implementation of the Amendment 234. For SRs that existed prior to Amendment 234, including SRs with modified acceptance criteria and SRs whose frequency of performance is being extended, the first performance is due at the end of the first surveillance interval that begins on the date the surveillance was last performed prior to implementation of Amendment 234.

## TABLE OF CONTENTS

<u>Section</u>	<u>Page No.</u>
1.0	USE AND APPLICATION..... 1.1-1
1.1	Definitions..... 1.1-1
1.2	Logical Connectors..... 1.2-1
1.3	Completion Times..... 1.3-1
1.4	Frequency..... 1.4-1
2.0	SAFETY LIMITS (SLs)..... 2.0-1
2.1	SLs ..... 2.0-1
2.2	SL Violations ..... 2.0-1
3.0	LIMITING CONDITION FOR OPERATION (LCO) APPLICABILITY..... 3.0-1
3.0	SURVEILLANCE REQUIREMENT (SR) APPLICABILITY ..... 3.0-4
3.1	REACTIVITY CONTROL SYSTEMS..... 3.1-1
3.1.1	SHUTDOWN MARGIN (SDM) ..... 3.1-1
3.1.2	Reactivity Anomalies..... 3.1-5
3.1.3	Control Rod OPERABILITY..... 3.1-7
3.1.4	Control Rod Scram Times..... 3.1-12
3.1.5	Control Rod Scram Accumulators..... 3.1-16
3.1.6	Rod Pattern Control ..... 3.1-20
3.1.7	Standby Liquid Control (SLC) System..... 3.1-23
3.1.8	Scram Discharge Volume (SDV) Vent and Drain Valves ..... 3.1-28
3.2	POWER DISTRIBUTION LIMITS..... 3.2-1
3.2.1	AVERAGE PLANAR LINEAR HEAT GENERATION RATE (APLHGR) ..... 3.2-1
3.2.2	MINIMUM CRITICAL POWER RATIO (MCPR)..... 3.2-3
3.2.3	LINEAR HEAT GENERATION RATE (LHGR) ..... 3.2-5
3.3	INSTRUMENTATION ..... 3.3-1
3.3.1.1	Reactor Protection System (RPS) Instrumentation ..... 3.3-1
3.3.1.2	Source Range Monitor (SRM) Instrumentation ..... 3.3-9
3.3.2.1	Control Rod Block Instrumentation ..... 3.3-15
3.3.2.2	Feedwater and Main Turbine High Water Level Trip Instrumentation..... 3.3-21
3.3.3.1	Post Accident Monitoring (PAM) Instrumentation..... 3.3-23
3.3.3.2	Backup Control System..... 3.3-27

(continued)

## 1.1 Definitions (continued)

---

**LOGIC SYSTEM  
FUNCTIONAL TEST**

A LOGIC SYSTEM FUNCTIONAL TEST shall be a test of all required logic components (i.e., all required relays and contacts, trip units, solid state logic elements, etc.) of a logic circuit, from as close to the sensor as practicable up to, but not including, the actuated device, to verify OPERABILITY. The LOGIC SYSTEM FUNCTIONAL TEST may be performed by means of any series of sequential, overlapping, or total system steps so that the entire logic system is tested.

**MINIMUM CRITICAL  
POWER RATIO (MCPR)**

The MCPR shall be the smallest critical power ratio (CPR) that exists in the core. The CPR is that power in the assembly that is calculated by application of the appropriate correlation(s) to cause some point in the assembly to experience boiling transition, divided by the actual assembly operating power.

**MODE**

A MODE shall correspond to any one inclusive combination of mode switch position, average reactor coolant temperature, and reactor vessel head closure bolt tensioning specified in Table 1.1-1 with fuel in the reactor vessel.

---

(continued)

### 3.3 INSTRUMENTATION

#### 3.3.1.1 Reactor Protection System (RPS) Instrumentation

LCO 3.3.1.1 The RPS instrumentation for each Function in Table 3.3.1.1-1 shall be OPERABLE.

APPLICABILITY: According to Table 3.3.1.1-1.

#### ACTIONS

-----NOTE-----  
Separate Condition entry is allowed for each channel.  
-----

CONDITION	REQUIRED ACTION	COMPLETION TIME
A. One or more required channels inoperable.	A.1 Place channel in trip.	12 hours
	<u>OR</u> A.2 -----NOTE----- Not applicable for Functions 2.a, 2.b, 2.c, or 2.d. ----- Place associated trip system in trip.	12 hours
B. -----NOTE----- Not applicable for Functions 2.a, 2.b, 2.c, or 2.d. ----- One or more Functions with one or more required channels inoperable in both trip systems.	B.1 Place channel in one trip system in trip.	6 hours
	<u>OR</u> B.2 Place one trip system in trip.	6 hours

(continued)

ACTIONS (continued)

CONDITION	REQUIRED ACTION	COMPLETION TIME
C. One or more Functions with RPS trip capability not maintained.	C.1 Restore RPS trip capability.	1 hour
D. Required Action and associated Completion Time of Condition A, B, or C not met.	D.1 Enter the Condition referenced in Table 3.3.1.1-1 for the channel.	Immediately
E. As required by Required Action D.1 and referenced in Table 3.3.1.1-1.	E.1 Reduce THERMAL POWER to < 30% RTP.	4 hours
F. As required by Required Action D.1 and referenced in Table 3.3.1.1-1.	F.1 Be in MODE 2.	6 hours
G. As required by Required Action D.1 and referenced in Table 3.3.1.1-1.	G.1 Be in MODE 3.	12 hours
H. As required by Required Action D.1 and referenced in Table 3.3.1.1-1.	H.1 Initiate action to fully insert all insertable control rods in core cells containing one or more fuel assemblies.	Immediately

## SURVEILLANCE REQUIREMENTS

### NOTES

1. Refer to Table 3.3.1.1-1 to determine which SRs apply for each RPS Function.
2. When a channel is placed in an inoperable status solely for performance of required Surveillances, entry into associated Conditions and Required Actions may be delayed for up to 6 hours provided the associated Function maintains RPS trip capability.

SURVEILLANCE		FREQUENCY
SR 3.3.1.1.1	Perform CHANNEL CHECK.	24 hours
SR 3.3.1.1.2	<p>-----NOTE----- Not required to be performed until 12 hours after THERMAL POWER <math>\geq</math> 25% RTP.</p> <p>Verify the absolute difference between the average power range monitor (APRM) channels and the calculated power is <math>\leq</math> 2% RTP while operating at <math>\geq</math> 25% RTP.</p>	7 days
SR 3.3.1.1.3	<p>-----NOTE----- Not required to be performed when entering MODE 2 from MODE 1 until 12 hours after entering MODE 2.</p> <p>Perform CHANNEL FUNCTIONAL TEST.</p>	7 days

(continued)

SURVEILLANCE REQUIREMENTS (continued)

SURVEILLANCE		FREQUENCY
SR 3.3.1.1.4	Perform CHANNEL FUNCTIONAL TEST.	7 days
SR 3.3.1.1.5	Verify the source range monitor (SRM) and intermediate range monitor (IRM) channels overlap.	Prior to withdrawing SRMs from the fully inserted position
SR 3.3.1.1.6	<p>-----NOTE----- Only required to be met during entry into MODE 2 from MODE 1. -----</p> <p>Verify the IRM and APRM channels overlap.</p>	7 days
SR 3.3.1.1.7	Calibrate the local power range monitors.	1000 MWD/T average core exposure
SR 3.3.1.1.8	Perform CHANNEL FUNCTIONAL TEST.	92 days
SR 3.3.1.1.9	<p>-----NOTES----- 1. Neutron detectors are excluded. 2. For Function 1, not required to be performed when entering MODE 2 from MODE 1 until 12 hours after entering MODE 2. -----</p> <p>Perform CHANNEL CALIBRATION.</p>	92 days

(continued)

SURVEILLANCE REQUIREMENTS (continued)

SURVEILLANCE		FREQUENCY
SR 3.3.1.1.10	Perform CHANNEL CALIBRATION.	184 days
SR 3.3.1.1.11	(Deleted)	
SR 3.3.1.1.12	Perform CHANNEL FUNCTIONAL TEST.	18 months
SR 3.3.1.1.13	<p>-----NOTE----- Neutron detectors are excluded. -----</p> <p>Perform CHANNEL CALIBRATION.</p>	18 months
SR 3.3.1.1.14	Perform LOGIC SYSTEM FUNCTIONAL TEST.	18 months
SR 3.3.1.1.15	Verify Turbine Stop Valve — Closure and Turbine Control Valve Fast Closure, Trip Oil Pressure — Low Functions are not bypassed when THERMAL POWER is $\geq 30\%$ RTP.	18 months
SR 3.3.1.1.16	<p>-----NOTE----- For Function 2.a, not required to be performed when entering MODE 2 from MODE 1 until 12 hours after entering MODE 2. -----</p> <p>Perform CHANNEL FUNCTIONAL TEST.</p>	184 days



Table 3.3.1.1-1 (page 1 of 3)  
Reactor Protection System Instrumentation

FUNCTION	APPLICABLE MODES OR OTHER SPECIFIED CONDITIONS	REQUIRED CHANNELS PER TRIP SYSTEM	CONDITIONS REFERENCED FROM REQUIRED ACTION D.1	SURVEILLANCE REQUIREMENTS	ALLOWABLE VALUE
1. Intermediate Range Monitors					
a. Neutron Flux - High	2	3	G	SR 3.3.1.1.1 SR 3.3.1.1.3 SR 3.3.1.1.5 SR 3.3.1.1.6 SR 3.3.1.1.9 SR 3.3.1.1.14	≤ 120/125 divisions of full scale
	5(a)	3	H	SR 3.3.1.1.1 SR 3.3.1.1.4 SR 3.3.1.1.9 SR 3.3.1.1.14	≤ 120/125 divisions of full scale
b. Inop	2	3	G	SR 3.3.1.1.3 SR 3.3.1.1.14	NA
	5(a)	3	H	SR 3.3.1.1.4 SR 3.3.1.1.14	NA
2. Average Power Range Monitors					
a. Neutron Flux - High, Setdown	2	3(b)	G	SR 3.3.1.1.1 SR 3.3.1.1.6 SR 3.3.1.1.7 SR 3.3.1.1.13 SR 3.3.1.1.16	≤ 15% RTP
b. Flow Biased Simulated Thermal Power - High	1	3(b)	F	SR 3.3.1.1.1 SR 3.3.1.1.2 SR 3.3.1.1.7 SR 3.3.1.1.13 SR 3.3.1.1.16	≤ 0.66 W + 71% RTP and ≤ 120% RTP(c)
c. Neutron Flux - High	1	3(b)	F	SR 3.3.1.1.1 SR 3.3.1.1.2 SR 3.3.1.1.7 SR 3.3.1.1.13 SR 3.3.1.1.16	≤ 120% RTP

(continued)

(a) With any control rod withdrawn from a core cell containing one or more fuel assemblies.

(b) Each APRM channel provides inputs to both trip systems.

(c) [0.66 W + 71% - 0.66 Δ W] RTP when reset for single loop operation per LCO 3.4.1, "Recirculation Loops Operating."

Table 3.3.1.1-1 (page 2 of 3)  
Reactor Protection System Instrumentation

FUNCTION	APPLICABLE MODES OR OTHER SPECIFIED CONDITIONS	REQUIRED CHANNELS PER TRIP SYSTEM	CONDITIONS REFERENCED FROM REQUIRED ACTION D.1	SURVEILLANCE REQUIREMENTS	ALLOWABLE VALUE
2. Average Power Range Monitors (continued)					
d. Inop	1,2	3(b)	G	SR 3.3.1.1.16	NA
e. 2-Out-Of-4 Voter	1,2	2	G	SR 3.3.1.1.1 SR 3.3.1.1.14 SR 3.3.1.1.16	NA
3. Reactor Vessel Steam Dome Pressure - High <sup>(d)</sup>	1,2	2	G	SR 3.3.1.1.1 SR 3.3.1.1.8 SR 3.3.1.1.10 SR 3.3.1.1.14	≤ 1055 psig
4. Reactor Vessel Water Level - Low, Level 3 <sup>(d)</sup>	1,2	2	G	SR 3.3.1.1.1 SR 3.3.1.1.8 SR 3.3.1.1.13 SR 3.3.1.1.14	≥ 528 inches above vessel zero
5. Main Steam Isolation Valve - Closure	1	8	F	SR 3.3.1.1.8 SR 3.3.1.1.13 SR 3.3.1.1.14	≤ 10% closed
6. Drywell Pressure - High	1,2	2	G	SR 3.3.1.1.8 SR 3.3.1.1.13 SR 3.3.1.1.14	≤ 2.5 psig
7. Scram Discharge Volume Water Level - High					
a. Resistance Temperature Detector	1,2	2	G	SR 3.3.1.1.8 SR 3.3.1.1.13 SR 3.3.1.1.14	≤ 50 gallons
	5(a)	2	H	SR 3.3.1.1.8 SR 3.3.1.1.13 SR 3.3.1.1.14	≤ 50 gallons

(continued)

- (a) With any control rod withdrawn from a core cell containing one or more fuel assemblies.
- (b) Each APRM channel provides inputs to both trip systems.
- (d) During instrument calibrations, if the As Found channel setpoint is conservative with respect to the Allowable Value but outside its acceptable As Found band as defined by its associated Surveillance Requirement procedure, then there shall be an initial determination to ensure confidence that the channel can perform as required before returning the channel to service in accordance with the Surveillance. If the As Found instrument channel setpoint is not conservative with respect to the Allowable Value, the channel shall be declared inoperable.

Prior to returning a channel to service, the instrument channel setpoint shall be calibrated to a value that is within the acceptable As Left tolerance of the setpoint; otherwise, the channel shall be declared inoperable.

The nominal Trip Setpoint shall be specified on design output documentation which is incorporated by reference in the Updated Final Safety Analysis Report. The methodology used to determine the nominal Trip Setpoint, the predefined As Found Tolerance, and the As Left Tolerance band, and a listing of the setpoint design output documentation shall be specified in Chapter 7 of the Updated Final Safety Analysis Report.

## SURVEILLANCE REQUIREMENTS

### NOTES

1. Refer to Table 3.3.2.1-1 to determine which SRs apply for each Control Rod Block Function.
2. When an RBM channel is placed in an inoperable status solely for performance of required Surveillances, entry into associated Conditions and Required Actions may be delayed for up to 6 hours provided the associated Function maintains control rod block capability.

SURVEILLANCE		FREQUENCY
SR 3.3.2.1.1	Perform CHANNEL FUNCTIONAL TEST.	184 days
SR 3.3.2.1.2	<p>-----NOTE----- Not required to be performed until 1 hour after any control rod is withdrawn at <math>\leq 10\%</math> RTP in MODE 2.</p> <p>-----</p> <p>Perform CHANNEL FUNCTIONAL TEST.</p>	92 days
SR 3.3.2.1.3	<p>-----NOTE----- Not required to be performed until 1 hour after THERMAL POWER is <math>\leq 10\%</math> RTP in MODE 1.</p> <p>-----</p> <p>Perform CHANNEL FUNCTIONAL TEST.</p>	92 days
SR 3.3.2.1.4	<p>-----NOTE----- Neutron detectors are excluded.</p> <p>-----</p> <p>Perform CHANNEL CALIBRATION.</p>	18 months

(continued)

## SURVEILLANCE REQUIREMENTS (continued)

SURVEILLANCE		FREQUENCY
SR 3.3.2.1.5	Verify the RWM is not bypassed when THERMAL POWER is $\leq 10\%$ RTP.	18 months
SR 3.3.2.1.6	<p>-----NOTE-----</p> <p>Not required to be performed until 1 hour after reactor mode switch is in the shutdown position.</p> <p>-----</p> <p>Perform CHANNEL FUNCTIONAL TEST.</p>	18 months
SR 3.3.2.1.7	Verify control rod sequences input to the RWM are in conformance with BPWS.	Prior to declaring RWM OPERABLE following loading of sequence into RWM
SR 3.3.2.1.8	<p>-----NOTE-----</p> <p>Neutron detectors are excluded.</p> <p>-----</p> <p>Verify the RBM:</p> <ul style="list-style-type: none"> <li>a. Low Power Range - Upscale Function is not bypassed when THERMAL POWER is <math>\geq 27\%</math> and <math>\leq 62\%</math> RTP.</li> <li>b. Intermediate Power Range - Upscale Function is not bypassed when THERMAL POWER is <math>&gt; 62\%</math> and <math>\leq 82\%</math> RTP.</li> <li>c. High Power Range - Upscale Function is not bypassed when THERMAL POWER is <math>&gt; 82\%</math> RTP.</li> </ul>	18 months

Control Rod Block Instrumentation  
3.3.2.1

Table 3.3.2.1-1 (page 1 of 1)  
Control Rod Block Instrumentation

FUNCTION	APPLICABLE MODES OR OTHER SPECIFIED CONDITIONS	REQUIRED CHANNELS	SURVEILLANCE REQUIREMENTS	ALLOWABLE VALUE
1. Rod Block Monitor				
a. Low Power Range - Upscale	(a)	2	SR 3.3.2.1.1 SR 3.3.2.1.4 SR 3.3.2.1.8	(e)
b. Intermediate Power Range - Upscale	(b)	2	SR 3.3.2.1.1 SR 3.3.2.1.4 SR 3.3.2.1.8	(e)
c. High Power Range - Upscale	(f),(g)	2	SR 3.3.2.1.1 SR 3.3.2.1.4 SR 3.3.2.1.8	(e)
d. Inop	(g),(h)	2	SR 3.3.2.1.1	NA
e. Downscale	(g),(h)	2	SR 3.3.2.1.1 SR 3.3.2.1.4	(i)
2. Rod Worth Minimizer	1(c),2(c)	1	SR 3.3.2.1.2 SR 3.3.2.1.3 SR 3.3.2.1.5 SR 3.3.2.1.7	NA
3. Reactor Mode Switch — Shutdown Position	(d)	2	SR 3.3.2.1.6	NA

- (a) THERMAL POWER  $\geq 27\%$  and  $\leq 62\%$  RTP and MCPR less than the value specified in the COLR.
- (b) THERMAL POWER  $> 62\%$  and  $\leq 82\%$  RTP and MCPR less than the value specified in the COLR.
- (c) With THERMAL POWER  $\leq 10\%$  RTP.
- (d) Reactor mode switch in the shutdown position.
- (e) Less than or equal to the Allowable Value specified in the COLR.
- (f) THERMAL POWER  $> 82\%$  and  $< 90\%$  RTP and MCPR less than the value specified in the COLR.
- (g) THERMAL POWER  $\geq 90\%$  RTP and MCPR less than the value specified in the COLR.
- (h) THERMAL POWER  $\geq 27\%$  and  $< 90\%$  RTP and MCPR less than the value specified in the COLR.
- (i) Greater than or equal to the Allowable Value specified in the COLR.

### 3.10 SPECIAL OPERATIONS

#### 3.10.8 SHUTDOWN MARGIN (SDM) Test - Refueling

- LCO 3.10.8      The reactor mode switch position specified in Table 1.1-1 for MODE 5 may be changed to include the startup/hot standby position, and operation considered not to be in MODE 2, to allow SDM testing, provided the following requirements are met:
- a. LCO 3.3.1.1, "Reactor Protection System Instrumentation," MODE 2 requirements for Functions 2.a, 2.d, and 2.e of Table 3.3.1.1-1;
  - b. 1. LCO 3.3.2.1, "Control Rod Block Instrumentation," MODE 2 requirements for Function 2 of Table 3.3.2.1-1, with the banked position withdrawal sequence (BPWS) requirements of SR 3.3.2.1.7 changed to require the control rod sequence to conform to the SDM test sequence,

OR

- 2. Conformance to the approved control rod sequence for the SDM test is verified by a second licensed operator or other qualified member of the technical staff;
- c. Each withdrawn control rod shall be coupled to the associated CRD;
- d. All control rod withdrawals during out of BPWS control rod moves shall be made in notch out mode;
- e. No other CORE ALTERATIONS are in progress; and
- f. CRD charging water header pressure  $\geq$  940 psig.

APPLICABILITY:    MODE 5 with the reactor mode switch in startup/hot standby position.

**SURVEILLANCE REQUIREMENTS**

SURVEILLANCE		FREQUENCY
SR 3.10.8.1	Perform the MODE 2 applicable SRs for LCO 3.3.1.1, Functions 2.a, 2.d, and 2.e of Table 3.3.1.1-1.	According to the applicable SRs
SR 3.10.8.2	<p>-----NOTE----- Not required to be met if SR 3.10.8.3 is satisfied. -----</p> <p>Perform the MODE 2 applicable SRs for LCO 3.3.2.1, Function 2 of Table 3.3.2.1-1.</p>	According to the applicable SRs
SR 3.10.8.3	<p>-----NOTE----- Not required to be met if SR 3.10.8.2 is satisfied. -----</p> <p>Verify movement of control rods is in compliance with the approved control rod sequence for the SDM test by a second licensed operator or other qualified member of the technical staff.</p>	During control rod movement
SR 3.10.8.4	Verify no other CORE ALTERATIONS are in progress.	12 hours

(continued)