



Westinghouse Electric Company
Nuclear Power Plants
P.O. Box 355
Pittsburgh, Pennsylvania 15230-0355
USA

U.S. Nuclear Regulatory Commission
ATTENTION: Document Control Desk
Washington, D.C. 20555

Direct tel: 412-374-6306
Direct fax: 412-374-5456
e-mail: sterdia@westinghouse.com

Your ref: Project Number 740
Our ref: DCP/NRC1783

November 1, 2006

Subject: AP1000 COL Standard Technical Report Submittal

In support of Combined License application pre-application activities, Westinghouse is submitting Revision 0 of AP1000 Standard Combined License Technical Report Number 70. This report completes and documents, on a generic basis, activities required for COL Information Item 18.9-1 in the AP1000 Design Control Document. Changes to the Design Control Document identified in Technical Report Number 70 are intended to be incorporated into FSARs referencing the AP1000 design certification or incorporated into the design certification using supplemental rulemaking if Part 52 is revised to permit revision of the design certification. This report is submitted as part of the NuStart Bellefonte COL Project (NRC Project Number 740). The information included in this report is generic and is expected to apply to all COL applications referencing the AP1000 Design Certification.


The purpose for submittal of this report was explained in a March 8, 2006 letter from NuStart to the U.S. Nuclear Regulatory Commission.

Pursuant to 10 CFR 50.30(b), APP-GW-GLR-040, Revision 0, "Plant Operations, Surveillance, and Maintenance Procedures," Technical Report Number 70, is submitted as Enclosure 1 under the attached Oath of Affirmation.

It is expected that when the NRC review of Technical Report Number 70 is complete, COL Information Item 18.9-1 will be considered complete for COL applicants referencing the AP1000 Design Certification.

Questions or requests for additional information related to the content and preparation of this report should be directed to Westinghouse. Please send copies of such questions or requests to the prospective applicants for combined licenses referencing the AP1000 Design Certification. A representative for each applicant is included on the cc: list of this letter.

Very truly yours,



A. Sterdis, Manager
Licensing and Customer Interface
Regulatory Affairs and Standardization

/Attachment

1. "Oath of Affirmation," dated November 1, 2006

/Enclosure

1. APP-GW-GLR-040, Revision 0, "Plant Operations, Surveillance, and Maintenance Procedures," Technical Report Number 70, dated October 2006.

cc:	S. Bloom	- U.S. NRC	1E	1A
	S. Coffin	- U.S. NRC	1E	1A
	G. Curtis	- TVA	1E	1A
	P. Grendys	- Westinghouse	1E	1A
	P. Hastings	- Duke Power	1E	1A
	C. Ionescu	- Progress Energy	1E	1A
	D. Lindgren	- Westinghouse	1E	1A
	A. Monroe	- SCANA	1E	1A
	M. Moran	- Florida Power & Light	1E	1A
	C. Pierce	- Southern Company	1E	1A
	E. Schmiech	- Westinghouse	1E	1A
	G. Zinke	- NuStart/Entergy	1E	1A

ATTACHMENT 1

“Oath of Affirmation”

ATTACHMENT 1

UNITED STATES OF AMERICA
NUCLEAR REGULATORY COMMISSION

In the Matter of:)
NuStart Bellefonte COL Project)
NRC Project Number 740)

APPLICATION FOR REVIEW OF
"AP1000 GENERAL COMBINED LICENSE INFORMATION"
FOR COL APPLICATION PRE-APPLICATION REVIEW

W. E. Cummins, being duly sworn, states that he is Vice President, Regulatory Affairs & Standardization, for Westinghouse Electric Company; that he is authorized on the part of said company to sign and file with the Nuclear Regulatory Commission this document; that all statements made and matters set forth therein are true and correct to the best of his knowledge, information and belief.



W. E. Cummins
Vice President
Regulatory Affairs & Standardization

Subscribed and sworn to
before me this 1st day
of November 2006.

COMMONWEALTH OF PENNSYLVANIA

Notarial Seal
Debra McCarthy, Notary Public
Monroeville Boro, Allegheny County
My Commission Expires Aug. 31, 2009

Member, Pennsylvania Association of Notaries

Notary Public

ENCLOSURE 1

APP-GW-GLR-040, Revision 0

Plant Operations, Surveillance, and Maintenance Procedures

Technical Report Number 70

AP1000 DOCUMENT COVER SHEET

TDC: _____ Permanent File: _____ APY: _____
 RFS#: _____ RFS ITEM #: _____

AP1000 DOCUMENT NO. APP-GW-GLR-040	REVISION NO. 0	Page 1 of 22	ASSIGNED TO
---------------------------------------	-------------------	--------------	-------------

ALTERNATE DOCUMENT NUMBER: _____ WORK BREAKDOWN #: GW

ORIGINATING ORGANIZATION: Westinghouse Electric Company

TITLE: **Plant Operations, Surveillance, and Maintenance Procedures**

ATTACHMENTS:	DCP #/REV. INCORPORATED IN THIS DOCUMENT REVISION:
CALCULATION/ANALYSIS REFERENCE:	

ELECTRONIC FILENAME	ELECTRONIC FILE FORMAT	ELECTRONIC FILE DESCRIPTION
COL070 Rev 0.doc	Microsoft Word	

(C) WESTINGHOUSE ELECTRIC COMPANY LLC - 2006

- WESTINGHOUSE PROPRIETARY CLASS 2
 This document is the property of and contains Proprietary Information owned by Westinghouse Electric Company LLC and/or its subcontractors and suppliers. It is transmitted to you in confidence and trust, and you agree to treat this document in strict accordance with the terms and conditions of the agreement under which it was provided to you.
- WESTINGHOUSE CLASS 3 (NON PROPRIETARY)

ORIGINATOR Mark G. Williams	SIGNATURE/DATE <i>Mark G. Williams</i> 10/26/06	
REVIEWERS V. Shkolnik	SIGNATURE/DATE <i>V. Shkolnik</i> 10/26/06	
VERIFIER S. W. Long	SIGNATURE/DATE <i>S. W. Long</i> 10/26/06	VERIFICATION METHOD Page by page
AP1000 RESPONSIBLE MANAGER F. L. Carpentino	SIGNATURE* <i>F. L. Carpentino</i>	APPROVAL DATE 10-26-2006

* Approval of the responsible manager signifies that document is complete, all required reviews are complete, electronic file is attached and document is released for use.

APP-GW-GLR-040
Revision 0

October 2006

AP1000 Standard Combined License Technical Report

Plant Operations, Surveillance, and Maintenance Procedures Revision 0

Westinghouse Electric Company LLC
Nuclear Power Plants
Post Office Box 355
Pittsburgh, PA 15230-0355

©2006 Westinghouse Electric Company LLC
All Rights Reserved

Plant Operations, Surveillance, and Maintenance Procedures

TABLE OF CONTENTS

1.0	INTRODUCTION.....	3
1.1	PURPOSE	3
1.2	DETAILED SCOPE FOR COL INFORMATION ITEMS 18.9-1 AND 13.5-1	4
1.3	PROJECT SCOPE.....	5
1.4	PROCEDURE STANDARDIZATION	5
1.5	CLOSURE OF COL INFORMATION ITEM 18.9-1	5
2.0	TECHNICAL BACKGROUND.....	6
2.1	OVERVIEW	6
2.2	INTEGRATED MASTER PLAN	6
2.3	LISTS OF DOCUMENTS.....	7
2.4	DESCRIPTION OF WORK BREAKDOWN STRUCTURE (WBS)	8
2.5	PROCEDURE DEVELOPMENT PROCESS	8
2.5	WRITER'S GUIDELINES	8
3.0	REGULATORY IMPACT.....	9
3.1	APPLICABLE SECTIONS OF THE NRC'S FINAL SAFETY EVALUATION REPORT	9
3.2	SEVERE ACCIDENT CHANGE CRITERIA	9
3.3	SECURITY.....	9
4.0	REFERENCES.....	10
5.0	DCD MARKUP.....	11

APPENDIX A LIST OF DOCUMENTS FOR EMERGENCY OPERATING PROCEDURES
(3 pages)

APPENDIX B LISTS OF DOCUMENTS FOR NORMAL OPERATING PROCEDURES
(NOPs) AND ABNORMAL OPERATING PROCEDURES (AOPs) (7 pages)

1.0 INTRODUCTION

1.1 Purpose

The primary purpose of this Technical Report is to close combined license (COL) Information Item 18.9-1 for "Procedure Development" which is delineated in Design Control Document (DCD) Section 18.9.1 (Reference 1). In addition, this Technical Report also supports future closure of COL Information Item 13.5-1, as delineated in DCD Table 1.8-2. This Technical Report will address these issues by describing methodology, criteria and schedules for procedure development. Methodology and criteria for procedure development is contained in the Westinghouse Writer's Guidelines for the Normal Operating and Two-Column Format Procedures which are available for NRC onsite review at Westinghouse's offices in Monroeville, Pennsylvania. The procedure guidance delineated in these Writer's Guidelines, which incorporates industry and regulatory standards for the development process and the human factors requirements for nuclear power plant procedures, provides the basis for generating the procedures necessary for the conduct of human factors evaluation work and plant operations. The list of procedures developed or planned for development is included in Appendices A and B, and their availability is delineated in Table 2.2 below. Following the successful and satisfactory review of the procedures delineated in Phases 1 and 2 of Table 2.2, it is anticipated that COL Information Item 18.9-1 will be closed.

In the DCD, COL Information Item 18.9-1 is delineated in Section 18.9.1, as is stated as follows:

"18.9.1 Combined License Information

See Section 13.5 for a discussion of the responsibility for procedure development."

This Technical Report also acknowledges the acceptance of the AP600 Emergency Response Guidelines (ERGs) as delineated in Section 18.9.3 of the AP1000 Final Safety Evaluation Report and addresses the development of procedures as required by DCD Section 13.5.1. Additional issues associated with COL Item 13.5-1 as delineated in DCD Table 1.8-2 will be addressed in future licensing submittals.

In the AP1000 DCD (Reference 1) Section 13.5.1, COL item "Plant Procedures", references WCAP-14690, Revision 1, "Designer's Input to Procedure Development for the AP600," issued June 1997, which provides common guidelines for the COL applicant developing plant operating procedures and includes information on the development and design of the AP1000 emergency response guidelines and emergency operating procedures. In the DCD (Reference 1) Section 13.5.1, the "Combined License Information Item" requires the COL applicant referencing the AP1000 Certified Design to address plant procedures, including the AP1000 ERGs and emergency operating procedures. While the emergency response guidelines have been prepared to support preparation of the emergency operating procedures, the emergency response guidelines do not need to be controlled or issued as COL deliverables.

COL Information Item 13.5-1 as delineated in Section 13.5.1 of the DCD reads as follows:

“13.5.1 Combined License Information Item

Combined License applicant referencing the AP1000 certified design will address plant procedures including the following:

- normal operation
- abnormal operation
- emergency operation
- refueling and outage planning
- alarm response
- maintenance, inspection, test, and surveillance
- administration
- operation of post-72-hour equipment”

As discussed below, addressing the procedural requirements indicated in Section 13.5.1 of the DCD for selected procedures needed for Human Factors efforts facilitates closure of COL Information Item 18.9-1.

1.2 Detailed Scope for COL Information Items 18.9-1 and 13.5-1

“Operating Procedures” comprise the Emergency Operating Procedures (EOPs), Normal Operating Procedures (NOPs), and Abnormal Operating Procedures (AOPs) as well as refueling and outage planning, alarm response, maintenance, inspection test and surveillance, and operating of post-72 hour equipment procedures. Section 2 further breaks down the scope of these procedure groups.

Writer’s Guidelines have been developed which control the preparation of NOPs and Two-Column Format Procedures. As preparation of the remaining procedures begins, such as maintenance and surveillance procedures, appropriate writer’s guidelines will similarly be prepared. The Writer’s Guidelines establish programmatic guidelines. Details of the content of FSAR 13.5 will be provided in a future submittal, along with additional information to close COL Information Item 13.5-1. COL Information Item 18.9-1 refers to Section 13.5 of the DCD for responsibility of procedure development and to facilitate procedure development for Human Factors engineering activities. The criteria and methodology for procedure development is described in this technical report and in Westinghouse Writer’s Guidelines, and Human Factors-related procedures have been developed or will be developed in accordance with these criteria/guidelines and the schedule in Table 2.2 of this technical report.

1.3 Project Scope

EOPs, NOPs, and AOPs per DCD Section 13.5 are being developed by Westinghouse (WEC). This technical report documents the development process. Selected EOPs, NOPs, and AOPs are being prepared with an initial emphasis on a selective set of operating procedures necessary to support Human Factors simulator testing and task analysis. In addition to these procedures, the project scope encompasses EOPs, and AOPs and those NOPs which support specific EOP operator control room actions.

1.4 Procedure Standardization

The overall goal is to develop procedures integrating industry best practices and standards. To facilitate these goals, Westinghouse has developed Writer's Guidelines in collaboration with the plant operator which incorporate industry and regulatory standards for the procedure development process and human factors requirements for nuclear power plant procedures. Industry Lessons Learned have been incorporated into the AP1000 Procedures Program, as delineated in Writer's Guidelines. In addition, standards and guidance from the NRC and industry organizations such as INPO and NEI have been incorporated into the program for procedure development. Finally, the AP1000 Procedure Program utilized specific experience and examples from a population of industry procedures and writer's guidelines as a starting point for the development of the program.

1.5 Closure of COL Information Item 18.9-1

This technical report:

- (1) does not result in any regulatory impacts,
- (2) does not affect severe accident criteria, and
- (3) will not alter security requirements.

The NRC will have the option to review AP1000 guidelines and procedures at the Westinghouse design office. Based on these reviews and the Westinghouse-NuStart programmatic process to prepare plant procedures as described in this technical report, the NRC is requested to consider this COL item closed.

2.0 TECHNICAL BACKGROUND

2.1 Overview

A project plan has been prepared to manage the writing, review, and approval of AP1000 operating procedures as related to COL Information Items 13.5-1 and 18.9-1. The plan uses a definition of tasks based on a work breakdown structure (WBS) for the procedure preparation process. The current plan is further described in Sections 2.2 through 2.5 below.

2.2 Integrated Master Plan

The highest level of the current WBS for procedures is the Integrated Master Plan for major deliverables as shown below. Except for EOPs as discussed previously, plant procedures will be draft revisions when prepared and will become final documents at the customer's plant site. The current WBS has organized the development of AP1000 Procedures into four phases as delineated in Table 2.2 below.

Phase 1: Development of 3 EOPs, 15 NOPs and 2 AOPs to support the second phase of Human Factors Testing for Control Room Design Finalization in the AP1000 Simulator.

Phase 2: Development of 20 additional EOPs, a set of 9 NOPs, and 1 Surveillance Test to support Operational Task Analysis (OSA-1) for the AP1000.

Phase 3: Development of the remaining procedures and guidelines. This includes 11 EOPs and supporting EOP documentation, 20 NOPs which support specific EOP operator control room actions, the remaining 43 of the 45 total AOPs, and the Post-72 Hour Procedures. In addition, and of lower priority, Phase 3 will include the development of the remaining 47 NOPs, which do not support specific EOP operator control room actions, as well as:

- Maintenance Guidelines,
- Surveillance Guidelines,
- Refueling and Outage Procedures,
- Alarm Response Guidelines,
- Administrative Guidelines, and
- Operation of Post-72 Hour Procedures.

Surveillance Guidelines also address inspection and testing procedural issues associated with surveillance testing. Phase 3 Procedure Activities are expected to occur after the COL Licensing Process and are dependent upon program funding and work priorities.

Table 2.2: Current Integrated Master Plan

Phase 1 Procedures --- WEC Engineering Office Human Factors/ Simulator Development Support	
◇ Emergency Operating Procedures (3 total)	Completed
◇ Draft Normal Operating Procedures (15 total)	Completed
◇ Draft Abnormal Operating Procedures (2 total)	Completed
Phase 2 Procedures --- WEC Engineering Office Operational Task Analysis (OSA-1) Support	
◇ Emergency Operating Procedures (20 total)	Completed
◇ Draft Normal Operating Procedures, (9 total)	Completed
◇ Draft Surveillance Test Procedures, (1 total)	Completed
Phase 3 Procedures and Guidelines --- WEC Engineering Office Remaining Procedures and Guidelines	
◇ Remaining Emergency Operating Procedures (11 total)	
◇ Draft Normal Operating Procedures which support specific EOP actions (20 total)	
◇ Draft Abnormal Operating Procedures (43 total)	
◇ Draft Post-72 Hour Procedures (estimate 15 total)	
◇ Remaining Draft Normal Operating Procedures (47 total)	
◇ Maintenance Guidelines (estimated 150 total)	
◇ Surveillance Guidelines (estimated 200 total)	
◇ Draft Refueling & Outage Procedures (estimated 50 total)	
◇ Alarm Response Guidelines (estimated 3000 total)	
◇ Administrative Guideline (1 total)	

2.3 Lists of Documents

Appendix A provides a list of documents for EOPs. Appendix B provides a list of documents for NOPs and AOPs. The Phase 1 and Phase 2 Procedures are available for NRC review at the Westinghouse offices in Monroeville, Pennsylvania at the Staff's convenience.

2.4 Description of Work Breakdown Structure (WBS)

The WBS has been developed using a three level model. The starting point is level 1 which comprises a list of the major procedure groups as noted in Table 2.2. Each procedure group is broken down into a level 2 list of procedures. Lastly, each procedure is defined by level 3 development subtasks. This approach follows industry standard project management methods, but incorporates some innovative techniques to monitor performance metrics. The goal of the project plan implementing this WBS is to continuously track the procedure deliverables to maintain high quality and to complete them on a schedule to support NRC and customer requirements.

2.5 Procedure Development Process

The procedure development process follows the requirements delineated in the applicable AP1000 Writer's Guidelines. As discussed in Section 1.2 above, the Writer's Guidelines establish programmatic guidelines for AP1000 Operating Procedure development as well as the process for the:

- Preparation of AP1000 Operating Procedures
- Review of AP1000 Operating Procedures
- Approval of AP1000 Operating Procedures

Personnel developing AP1000 Operating Procedures are qualified in accordance with classroom training and Computer-Based Training, which address:

- Procedure Writing
- The AP1000 Procedure Writer's Guidelines
- AP1000 Administrative Processes, and
- AP1000 Systems and Design

In addition, the AP1000 procedure development process incorporates applicable industry, NRC, INPO and NEI standards with respect to the qualifications of the procedure writers and the qualified users. These standards are incorporated explicitly or by reference in the applicable Writer's Guidelines.

2.6 Writer's Guidelines

The AP1000 Writer's Guideline for Two-Column Format, which addresses EOPs, AOPs and Alarm Response Procedures as well as the AP1000 NOP Writer's Guideline have been developed and are available for NRC review onsite at Westinghouse at the Staff's convenience.

3.0 REGULATORY IMPACT

3.1 Applicable Sections of the NRC's Final Safety Evaluation Report

Sections 13.5 and 18.9 are the portions of the NRC's FSER related to the COL Action covered by this report. However, these sections are not impacted by this Technical Report.

3.2 Severe Accident Change Criteria

There are no proposed departures from Tier 2 that would affect resolution of a severe accident issue identified in the DCD. Therefore no license amendment is required.

Normal Operating Procedures are executed within the established Technical Specifications.

Abnormal and Emergency Operating Procedures conform to industry standards and are written in compliance with the applicable regulatory requirements. These procedures provide the response to abnormal or accident conditions to bring the plant to a condition as prescribed by the Technical Specifications.

As such, there are no changes that have an impact on the Severe Accident Criteria.

3.3 Security

The closure of COL Information Item 18.9-1 will not alter barriers or alarms that control access to the protected areas of the plant. The closure of this COL Information Item will not alter requirements for security personnel. Therefore, the closure of this COL Information Item does not have an adverse impact on the security assessment of the AP1000.

4.0 REFERENCES

1. APP-GW-GL-700, Revision 15, AP1000 Design Control Document.
2. NUREG-1793, Final Safety Evaluation Report Related to Certification of the AP1000 Standard Design, September 2004.
3. NEI 04-01, Revision D, DRAFT Industry Guideline for Combined License Applicants Under 10 CFR Part 52, October 5, 2005.
4. SECY-05-0197, Review of Operational Programs in a Combined License Application and Generic Emergency Planning Inspections, Tests, Analyses, and Acceptance Criteria, Policy Issue Notation Vote, October 28, 2005.
5. APP-GW-GL-027, "Framework for AP1000 Severe Accident Management Guidance", Revision 0, April 2006. Alternate Document Number: WCAP-16335.

5.0 DCD MARKUP

A markup of Section 13.5 is not proposed at this time. A proposed markup of Section 13.5, including a statement that the process to manage the writing, review, and approval of AP1000 plant procedure is described in this Technical Report, will be included in a future submittal.

The following DCD markups identify how the AP1000 DCD will be modified for Section 18.9.1.

Revise Section 18.9.1 as follows:

18.9.1 Combined License Information

Completed. The process to manage the writing, review and approval of the AP1000 plant procedures is described in reference 2 below.

Add Reference 2 to Section 18.9.2 as follows:

18.9.2 References

2. APP-GW-GLR-040, "Plant Operations, Surveillance, and Maintenance Procedures," October 2006.

APPENDIX A

LIST OF DOCUMENTS FOR EMERGENCY OPERATING PROCEDURES

(3 pages including this page)

TABLE A-1**Listing of EOP Documents**

The following list shows EOP documents being developed as Phase 1 (Human Factors / Simulator Development Support), Phase 2 (Operational Task Analysis Support) and Phase 3 (Remaining Procedures and Guidelines)

NOTE: This list does not include estimated 12 Severe Accident Management Guidelines (SAMGs). This Technical Report does not address SAMG development. The structure of the AP1000 SAMGs has been developed and is available in Reference 5, APP-GW-GL-027.

Procedure Title	Procedure Number
<u>Emergency Operating Procedures -- Human Factors/ Simulator Development Support</u>	
<u>(Phase 1)</u>	
TOTAL 3 PROCEDURES	
1. E-O Reactor Trip or Safety Injection	APP-GW-GJP-201
2. E-3 SG Tube Rupture	APP-GW-GJP-204
3. ES-0.1 Reactor Trip Response	APP-GW-GJP-206
<u>Emergency Operating Procedures -- Operational Task Analysis (OSA-1) Support</u>	
<u>(Phase 2)</u>	
TOTAL 20 PROCEDURES	
1. E-1 Loss of Reactor or Secondary Coolant	APP-GW-GJP-202
2. E-2 Faulted SG Isolation	APP-GW-GJP-203
3. ECA-1.1 LOCA Outside Containment	APP-GW-GJP-205
4. ES-0.2 Natural Circulation Cooldown	APP-GW-GJP-207
5. ES-1.1 Passive Safety System Termination	APP-GW-GJP-208
6. ES-1.2 Post LOCA Cooldown and Depressurization	APP-GW-GJP-209
7. FR-C.1 Response to Inadequate Core Cooling	APP-GW-GJP-210
8. FR-C.2 Response to Degraded Core Cooling	APP-GW-GJP-211
9. FR-C.3 Response to Saturated Core Cooling	APP-GW-GJP-212
10. FR-H.1 Response to Loss of Heat Sink	APP-GW-GJP-213
11. FR-H.2 Response to Steam Generator Overpressure	APP-GW-GJP-214
12. FR-H.3 Response to Steam Generator High Level	APP-GW-GJP-215
13. FR-H.4 Response to Loss of Normal Steam Release Capabilities	APP-GW-GJP-216
14. FR-H.5 Response to Steam Generator Low Level	APP-GW-GJP-217
15. FR-I.1 Response to High Pressurizer Level	APP-GW-GJP-218
16. FR-I.2 Response to Low Pressurizer Level	APP-GW-GJP-219
17. FR-I.3 Response to Voids in Reactor Vessel	APP-GW-GJP-220

Procedure Title	Procedure Number
18. SDP-1 Response to Loss of RCS Inventory During Shutdown	APP-GW-GJP-231
19. SDP-2 Response to Loss of RNS During Shutdown	APP-GW-GJP-232
20. SDP-3 Response to High Containment Radiation During Shutdown	APP-GW-GJP-233

Remaining Emergency Operating Procedures – (Phase 3)

TOTAL 11 PROCEDURES

1. FR-P.1 Response to Imminent Pressurized Thermal Shock Conditions	APP-GW-GJP-221
2. FR-P.2 Response to Anticipated Pressurized Thermal Shock Condition	APP-GW-GJP-222
3. FR-S.1 Response to Nuclear Power Generation – ATWS	APP-GW-GJP-223
4. FR-S.2 Response to Loss of Core Shutdown	APP-GW-GJP-224
5. FR-Z.1 Response to High Containment Pressure	APP-GW-GJP-225
6. FR-Z.2 Response to Containment Flooding	APP-GW-GJP-226
7. FR-Z.3 Response to High Containment Radiation Level	APP-GW-GJP-227
8. FR-Z.4 Response to Low Containment Pressure	APP-GW-GJP-228
9. SDP-4 Response to Increasing Nuclear Flux During Shutdown	APP-GW-GJP-234
10. SDP-5 Response to Cold Overpressure During Shutdown	APP-GW-GJP-235
11. SDP-6 Response to Unexpected RCS Temperature Changes During Shutdown	APP-GW-GJP-236

APPENDIX B

**LISTS OF DOCUMENTS FOR NORMAL OPERATING PROCEDURES (NOPs) AND
ABNORMAL OPERATING PROCEDURES (AOPs)**

(7 pages including this page)

TABLE B-1

Listing of NOP Documents, Phase 1 to Phase 3 (Preliminary Data)

Procedure Title	Procedure Number
<u>Draft Normal Operating Procedures -- Human Factors/ Simulator Development Support (Phase 1)</u>	
TOTAL 15 PROCEDURES	
1. Steam Generator Blowdown System	APP-BDS-GJP-101
2. Component Cooling Water System	APP-CCS-GJP-101
3. Chemical and Volume Control System	APP-CVS-GJP-101
4. Feedwater System	APP-FWS-GJP-101
5. Main Steam System	APP-MSS-GJP-101
6. Main Turbine System	APP-MTS-GJP-101
7. Passive Containment Cooling System	APP-PCS-GJP-101
8. Passive Core Cooling System	APP-PXS-GJP-101
9. Reactor Coolant System	APP-RCS-GJP-101
10. Normal Residual Heat Removal System	APP-RNS-GJP-101
11. Steam Generator System	APP-SGS-GJP-101
12. Service Water System	APP-SWS-GJP-101
13. Normal Operation at 100% Power	APP-GW-GJP-101
14. Plant Shutdown and Cooldown from Mode 1 to Mode 3	APP-GW-GJP-102
15. Plant Cooldown from Mode 3 to Cold Shutdown	APP-GW-GJP-103
<u>Draft Normal Operating Procedures plus 1 Surveillance Test -- Operational Task Analysis (OSA-1) Support (Phase 2)</u>	
TOTAL 10 PROCEDURES	
1. Plant Cooldown from Mode 5 to Refueling Mode	APP-GW-GJP-104
2. Plant Heatup - from Refueling Mode to Mode 5	APP-GW-GJP-105
3. Plant Heatup – Mode 5 to Mode 4	APP-GW-GJP-106
4. Plant Heatup – Mode 4 to Mode 3	APP-GW-GJP-107
5. Plant Startup – Mode 3 to 2% Power	APP-GW-GJP-108
6. Plant Power Escalation from 2% to 100% Power	APP-GW-GJP-109
7. Secondary Plant Heatup and Startup	APP-GW-GJP-110
8. Inverse Count Rate Plot Procedure	APP-GW-GJP-111
9. Critical Rod Position/Boron Concentration Calculation	APP-GW-GJP-112

Procedure Title	Procedure Number
10. ADS Valve Surveillance Testing During Mode 5	APP-RCS-GJP-801
<u>Draft Normal Operating Procedures – Remaining NOPs (Phase 3)</u>	
TOTAL 20 PROCEDURES	
1. Auxiliary Steam Supply System	APP-ASS-GJP-101
2. Compressed and Instrument Air Systems	APP-CAS-GJP-101
3. Condensate System	APP-CDS-GJP-101
4. Condenser Tube Cleaning System	APP-CES-GJP-101
5. Turbine Island Chemical Feed System	APP-CFS-GJP-101
6. Condenser Air Removal System	APP-CMS-GJP-101
7. Condensate Polishing System	APP-CPS-GJP-101
8. Circulating Water System	APP-CWS-GJP-101
9. Diverse Actuation System	APP-DAS-GJP-101
10. Data Display and Procession System	APP-DDS-GJP-101
11. Standby Diesel and Auxiliary Boiler Fuel Oil System	APP-DOS-GJP-101
12. Storm Drains System	APP-DRS-GJP-101
13. Demineralized Water Treatment System	APP-DTS-GJP-101
14. Demineralized Water Transfer and Storage System	APP-DWS-GJP-101
15. Main AC Power System	APP-ECS-GJP-101
16. Non Class 1E DC and UPS System	APP-EDS-GJP-101
17. Communication Systems	APP-EFS-GJP-101
18. Special Process Heat Tracing System	APP-EHS-GJP-101
19. Plant Lighting System	APP-ELS-GJP-101
20. Fuel Handling and Refueling System	APP-FHS-GJP-101
21. Fire Protection System	APP-FPS-GJP-101
22. Gland Seal System	APP-GSS-GJP-101
23. Generator Hydrogen and CO2 Systems	APP-HCS-GJP-101
24. Heater Drain System	APP-HDS-GJP-101
25. Hydrogen Seal Oil System	APP-HSS-GJP-101
26. Class 1E DC and UPS System	APP-IDS-GJP-101
27. Incore Instrumentation System	APP-IIS-GJP-101
28. Main Turbine and Generator Lube Oil System	APP-LOS-GJP-101
29. Meteorological and Environmental Monitoring System	APP-MES-GJP-101
30. Plant Gas Systems	APP-PGS-GJP-101

Procedure Title	Procedure Number
31. Plant Control System	APP-PLS-GJP-101
32. Protection and Safety Monitoring System	APP-PMS-GJP-101
33. Primary Sampling System	APP-PSS-GJP-101
34. Potable Water System	APP-PWS-GJP-101
35. Gravity and Roof Drain Collection System	APP-RDS-GJP-101
36. Radiation Monitoring System	APP-RMS-GJP-101
37. Raw Water System	APP-RWS-GJP-101
38. Reactor System	APP-RXS-GJP-101
39. Sanitary Drainage System	APP-SDS-GJP-101
40. Spent Fuel Cooling System	APP-SFS-GJP-101
41. Seismic Monitoring System	APP-SJS-GJP-101
42. Special Monitoring System	APP-SMS-GJP-101
43. Secondary Sampling System	APP-SSS-GJP-101
44. Turbine Building Closed Cooling Water System	APP-TCS-GJP-101
45. Turbine Island Vents, Drains and Relief System	APP-TDS-GJP-101
46. Main Turbine Control and Diagnostics System	APP-TOS-GJP-101
47. Radiologically Controlled Area Ventilation System	APP-VAS-GJP-101
48. Nuclear Island Nonradioactive Ventilation System	APP-VBS-GJP-101
49. Containment Recirculation Cooling System	APP-VCS-GJP-101
50. Main Control Room Emergency Habitability System	APP-VES-GJP-101
51. Containment Air Filtration System	APP-VFS-GJP-101
52. Health Physics and Hot Machine Shop HVAC System	APP-VHS-GJP-101
53. Containment Hydrogen Control System	APP-VLS-GJP-101
54. Radwaste Building HVAC System	APP-VRS-GJP-101
55. Turbine Building Ventilation System	APP-VTS-GJP-101
56. Central Chilled Water System	APP-VWS-GJP-101
57. Annex/Aux Building Nonradioactive Ventilation System	APP-VXS-GJP-101
58. Hot Water Heating System	APP-VYS-GJP-101
59. Diesel Generator Building Heating and Ventilation System	APP-VZS-GJP-101
60. Gaseous Radwaste System	APP-WGS-GJP-101
61. Liquid Radwaste System	APP-WLS-GJP-101
62. Radioactive Waste Drain System	APP-WRS-GJP-101
63. Solid Radwaste System	APP-WSS-GJP-101
64. Waste Water System	APP-WWS-GJP-101

Procedure Title	Procedure Number
65. Main Generation System (Generator Portion)	APP-ZAS-GJP-101
66. Onsite Standby Power System	APP-ZOS-GJP-101
67. Excitation and Voltage Regulation System	APP-ZVS-GJP-101

TABLE B-2

Listing of AOP Documents (Preliminary Data)

Procedure Title	Procedure Number
<u>Draft Abnormal Operating Procedures -- Human Factors/ Simulator Development Support (Phase 1)</u>	
TOTAL 2 PROCEDURES	
1. Rapid Plant Shutdown	APP-GW-GJP-301
2. Steam Generator Tube Leak	APP-GW-GJP-304
<u>Draft Abnormal Operating Procedures – Remaining Procedures and Guidelines (Phase 3)</u>	
TOTAL 43 PROCEDURES	
1. Emergency Boration	APP-GW-GJP-302
2. Acts of Nature	APP-GW-GJP-303
3. Fire Emergency Response	APP-GW-GJP-305
4. Evacuation of Control Room	APP-GW-GJP-306
5. Remote Shutdown	APP-GW-GJP-307
6. Loss of Control Room Air Conditioning	APP-GW-GJP-308
7. Toxic Gas	APP-GW-GJP-309
8. Security Events	APP-GW-GJP-310
9. CEA and Control System Malfunctions	APP-GW-GJP-311
10. Loss of Flux Indication or Flow Streaming	APP-GW-GJP-312
11. Uncontrolled Cooldown	APP-GW-GJP-313
12. Fuel Handling Incident	APP-GW-GJP-314
13. High Radioactivity	APP-GW-GJP-315
14. Loss of Containment Integrity	APP-GW-GJP-316
15. Loss of Component Cooling Water	APP-GW-GJP-317
16. Condensate System Malfunctions	APP-GW-GJP-318
17. CVCS Leak	APP-GW-GJP-319
18. Loss of Circulating Water	APP-GW-GJP-320
19. Loss of DDS	APP-GW-GJP-321
20. Generator Malfunctions	APP-GW-GJP-322
21. Loss of 6.9 kV, 4160 Volt or 480 Volt Bus Power	APP-GW-GJP-323
22. Loss of the ERF, QSPDS or Security Computer	APP-GW-GJP-324

Procedure Title	Procedure Number
23. Reset of Engineered Safeguards	APP-GW-GJP-325
24. Feedwater System Malfunctions	APP-GW-GJP-326
25. Startup Feedwater System Malfunctions	APP-GW-GJP-327
26. Feedwater Heater/Extr Steam System Malfunctions	APP-GW-GJP-328
27. Loss of Instrument Air	APP-GW-GJP-329
28. Loss of Defense-In-Depth Electrical Power	APP-GW-GJP-330
29. Loss of Plant DC Power and/or Batteries	APP-GW-GJP-331
30. Turbine Trip without a Reactor Trip	APP-GW-GJP-332
31. Turbine Malfunctions	APP-GW-GJP-333
32. Loss of Turbine Auxiliary Water Cooling	APP-GW-GJP-334
33. Loss of PLS	APP-GW-GJP-335
34. Loss of PMS	APP-GW-GJP-336
35. Passive RHR Heat Exchanger Leak	APP-GW-GJP-337
36. Passive Cooling System Malfunctions/Alignments	APP-GW-GJP-338
37. Emergency Fill of Makeup Tanks	APP-GW-GJP-339
38. Reactor Coolant Leak	APP-GW-GJP-340
39. Reactor Coolant System High Activity	APP-GW-GJP-341
40. Reactor Coolant Pump Malfunctions	APP-GW-GJP-342
41. Loss of Normal Residual Heat Removal	APP-GW-GJP-343
42. Loss of Spent Fuel Pool Cooling	APP-GW-GJP-344
43. Loss of Service Water	APP-GW-GJP-345