

---

# **November 14, 2006 Meeting With NRC**

## **Overview of the August 29, 2006 Plant Hatch Alternative Source Term Submittal**



# ***Agenda***

---

- ◆ **Introduction**
- ◆ **Scope**
- ◆ **Design Basis Accident Modeling**
- ◆ **Polestar Methods of Activity Removal**
- ◆ **Crediting of Turbine Building HVAC**
  - ◆ **Passive Ventilation Study**
  - ◆ **Ductwork Description and Seismic Verification**
  - ◆ **Air Supply and Seismic**
  - ◆ **Power Supply and Seismic**
- ◆ **Standby Liquid Control System Assessment**
- ◆ **Technical Specification Changes**
- ◆ **Conclusion**

# ***Introduction***

---

- ◆ **Purpose of Alternative Source Term (AST) NRC Submittal**
  - ◆ Address Control Room Habitability GL 2003-01
  - ◆ Address Hatch unique MCR location inside Turbine Building
  - ◆ Replace by May 31, 2010 interim licensing basis of 110 cfm MCR unfiltered inleakage (based on potassium iodide)
  
- ◆ **AST provides the margin needed to bound 15 cfm (5 cfm actual inleakage plus 10 cfm for ingress/egress)**
  - ◆ AST based limiting MCR unfiltered inleakage 115 cfm (10 cfm for ingress/egress)
  - ◆ Considers the impact of additional identified secondary containment bypass paths (0.9% increases to 2%)
  - ◆ Considers bypass paths that go thru turbine building
  - ◆ MCR/TSC Atmospheric Dispersion Factors updated with ARCON96 based on 3 years of data

# Scope – AST Mitigating Features

- ◆ Full scope AST submittal – all 4 BWR DBAs analyzed
  - ◆ LOCA is limiting DBA for main control room (MCR) inleakage
  - ◆ FHA requires no mitigating features
- ◆ Remaining mitigating feature (not listed below) is use of sodium pentaborate for suppression pool pH control post-LOCA

Mitigating Feature	LOCA (fuel damage)				MSLB (no fuel damage)			CRDA (fuel damage)		
	MCR	TSC	EAB/ LPZ Ground	EAB/ LPZ Elev.	MCR	TSC	EAB/ LPZ	MCR	TSC	EAB / LPZ
Drywell sprays and natural deposition	✓	✓	✓	✓						
MSIV leakage deposition in steam lines & condenser	✓	✓	✓							
Secondary containment bypass leakage deposition in condenser	✓									
TB fan starting at 8 hr at a rate of 15,000 cfm	✓				✓			✓		

# ***Scope - Seismic***

---


- ◆ **AST submittal includes 3 types of seismic evaluations and supporting EPRI report**
  - ◆ Unit 1 Main Steam Isolation Valve Alternate Leakage Treatment Path
  - ◆ Units 1 and 2 Seismic Verification of Potential Secondary Containment Bypass Leakage Paths Terminating at the Main Condenser
  - ◆ Units 1 and 2 Seismic Verification of the Turbine Building Exhaust Ductwork
    - Application of EPRI Technical Report 1007896 titled “Seismic Evaluation Guidelines for HVAC Duct and Damper Systems”

# ***DBA Dose Modeling – Overview***


---

- ◆ **Objective is to determine the maximum MCR inleakage without exceeding the dose limit of 5 rem TEDE**
  - ◆ LocaDose computer program is used to calculate doses for LOCA, CRDA, MSLB, and FHA based on the methodology of Regulatory Guide 1.183
- ◆ **For MCR dose calculations, activity is released into the turbine building for three of the accidents (LOCA, CRDA, MSLB)**
  - ◆ Since the activity concentration within the turbine building is higher than outside, all the MCR inleakage is assumed to be from the turbine building
  - ◆ Since FHA release is not into the turbine building, MCR inleakage is assumed to be from outside
  - ◆ For all accidents, TSC and offsite doses are calculated assuming no holdup in turbine building
- ◆ **Maximum MCR inleakage is determined to be 115 cfm for LOCA, 155 cfm for CRDA, 150 cfm for MSLB, and unlimited for FHA**
  - ◆ TSC and offsite doses are within acceptance criteria

# DBA Dose Model for LOCA - MCR






# DBA Dose Model for LOCA – TSC & Offsite




8


# DBA Dose Model for FHA




# DBA Dose Model for CRDA – MCR





# DBA Dose Model for CRDA – TSC & Offsite



# DBA Dose Model for MSLB – MCR



# DBA Dose Model for MSLB – TSC & Offsite



# ***Polestar Methods for Activity Removal***

---

## **◆ Polestar Methods**

- ◆ Credit for activity removal by DW spray and sedimentation in steam lines/main condenser (if open pathway to main condenser can be assured and steam lines/main condenser are seismically rugged)
- ◆ STARNAUA for aerosol removal by sedimentation and spray
- ◆ Credit for aerosol impaction in MSIV leakage pathway (DF of 2 at first closed MSIV)
- ◆ Assumption that elemental iodine will adsorb onto surface of dispersed aerosol (i.e., elemental iodine removal rate that of aerosol except not greater than  $\lambda = 20$  per hour)
- ◆ pH calculated using STARpH
- ◆ DF for elemental iodine calculated on basis of pH = 8.3 at 24 hours (end of spray removal period for elemental iodine) - no DF limit for particulate

# ***Polestar Methods for Activity Removal***

---

- ◆ **History and precedent for use of the STARNAUA computer code**
  - ◆ AP-600/AP-1000
    - AP-600: first application of STARNAUA for aerosol activity removal
    - Extensive NRC review with Sandia Nat'l Lab (Dr. Powers) as NRC contractor
  - ◆ Perry – first application of AST to an operating plant – reviewed by RES
  - ◆ Columbia – STARNAUA results used to justify modified NRC methods for steam line deposition to account for drywell spray credit
  - ◆ Oyster Creek (currently under review)
    - Close parallel to Hatch
    - No control room filtration whatsoever – 14,000 cfm outside air
- ◆ **Credit for drywell spray accepted on VY and Columbia**
- ◆ **Credit for removal in steam lines and main condenser accepted on VY and Browns Ferry (but not using STARNAUA)**

## ***Polestar Methods for Activity Removal***

	DW Spray	Main Cond	STARNAUA	NRC SE
AP-600/1000 <sup>1</sup>			X	X
Perry	X <sup>2</sup>		X	X
BFN		X		X
VY	X	X		X
Columbia	X		X <sup>3</sup>	X <sup>4</sup>
Oyster Creek	X		X	
Hatch	X	X	X	

**1: Advanced PWR (passive plant). 2: MkIII containment uses containment spray, not DW spray. 3: Used to adjust documented NRC-RES acceptance basis for Perry to account for DW spray. 4: SE completed by Dose Assessment Branch.**

# ***Polestar Methods for Activity Removal***

---

## **◆ STARNAUA Inputs**

- ◆ Initial aerosol size distribution and mass based on fuel melt experiments
- ◆ Spray flow (one pump) and fall height - 33% reduction to account for local impingement and drywell structures below spray pattern
- ◆ Spray droplet size increased to account for one pump
- ◆ Spray starts 15 minutes after start of accident (13 minutes after start of release with high radiation in drywell – same basis as VY/Columbia)
- ◆ DW thermal-hydraulic conditions (pressure/temperature/rh) from MAAP4
- ◆ Steam line temperature assumed same as normal operation

## **◆ Conservative aerosol impaction DF of 2 based on compilation of experimental data and models for inertial impaction filters**

- ◆ Aspiration efficiency = 50% (very high for expected leak path conditions)

# ***Polestar Methods for Activity Removal***

---

## **◆ Modeling of Steam Lines**

- ◆ Leak path could actually plug and reduce or eliminate gaseous release as well as particulate release (not credited)
- ◆ Aerosol leakage from drywell reduced by a factor of 2 for steam line STARNAUA cases
- ◆ Size distribution taken from output of STARNAUA DW spray case
- ◆ Same process repeated for downstream steam line control volumes and for main condenser control volume (except for factor of 2 reduction in leaked mass)
- ◆ Only horizontal projection of steam lines credited for aerosol deposition
- ◆ Elemental iodine deposition in steam lines not credited except for DF of 2 at inlet (treated as deposited on aerosol at inlet to main steam lines but not in steam lines due to superheat and potential for re-evolution)


# ***Polestar Methods for Activity Removal***

---

- ◆ **STARpH used for suppression pool pH calculation**
- ◆ **Previously applied to**
  - ◆ Perry
  - ◆ Oyster Creek
  - ◆ Hope Creek and Salem
  - ◆ Browns Ferry
  - ◆ Waterford 3
  - ◆ Columbia
- ◆ **pH = 8.3 at 24 hours**
- ◆ **pH greater than 7 for full 30 days (no iodine re-evolution in containment considered)**

## *Dose Methodology Wrap-up*

---




# ***Passive Ventilation Study of Turbine Building***

---


- ◆ **Observation that commercial/industrial structures typically “breathe” naturally at 2-10 volumes per day (sometimes as much as 1 volume per hour but large buildings tend to be less)**
- ◆ **Function of**
  - ◆ Wind speed (external pressure magnitude)
  - ◆ Wind direction (pressure distribution)
  - ◆ Façade effective leakage area and building openings
  - ◆ Inside vs. outside temperature (stack effect) ignored in study
- ◆ **CpCalc+ code developed by Politecnico di Torino (Turin, Italy) for the EU used to obtain pressure distribution**
  - ◆ Expressed as Cp (multiplier for dynamic pressure)
- ◆ **Effective leakage area = mean value for concrete panel construction = 4 cm<sup>2</sup>/m<sup>2</sup> from NISTIR 6585**


# Passive Ventilation Study of Turbine Building


- ◆ Variability in passive ventilation rate based on Hatch site-specific wind speed/direction
- ◆ Passive rates appear comparable to forced 15,000 cfm rate used in dose analysis
  - ◆ 5<sup>th</sup> %tile: 3300 cfm
  - ◆ 10<sup>th</sup> %tile: 4900 cfm
  - ◆ 20<sup>th</sup> %tile: 7000 cfm
  - ◆ 40<sup>th</sup> %tile: 10700 cfm
- ◆ Includes effect of partially-opened railroad bay doors
- ◆ Supports 70 cfm unfiltered inleakage




# TURBINE BUILDING HVAC CONFIGURATION








# TURBINE BUILDING HVAC CONFIGURATION





# ***Seismic Verification of TB HVAC***

---

## **◆ Scope:**

- ◆ Seismic verification of required portions of exhaust HVAC ductwork including supports & anchorage to assure structural and pressure integrity
- ◆ Seismic verification of associated dampers, filters, and fans to assure structural and pressure integrity

## **◆ Methodology:**

- ◆ Primarily based on earthquake experience & similar in concept to the SQUG GIP seismic verification of raceway systems
- ◆ EPRI Technical Report 1007896 “Seismic Evaluation Guidelines for HVAC Duct & Damper Systems” April 2003
  - Peer reviewed by Dr. Robert P. Kennedy February 2004


# ***Seismic Verification of TB HVAC cont.***

---

## **◆ Methodology cont'd:**

- ◆ Seismic verification performed by two SQUG Seismic Capability Engineers meeting required experience and training requirements
- ◆ Methodology includes
  - documentation & applicability reviews
  - detail in-plant seismic walkdowns using screening criteria
  - identification of potential failure modes (outliers)
  - analytical review of bounding sample of duct runs and supports/anchorage
  - resolution of outliers by further analysis or plant mods
  - documentation
  - independent peer review of the Hatch seismic verification
- ◆ SQUG GIP used for seismic verification of associated Equipment, e.g., fans.


# SERVICE AND INSTRUMENT AIR FLOWPATH (UNIT 2)




## ***Turbine Building HVAC Air Supply***

---

- ◆ The air for all Turbine Building HVAC dampers is supplied by interruptible instrument air. Failures can occur by:
  - ◆ A break in the compressed air system.
  - ◆ A mechanical or electrical failure.
  - ◆ A major air dryer failure.
- ◆ Procedural guidance will be implemented to prevent cross-tie operation should an accident occur on one unit.
- ◆ A single failure in any unit can result in complete loss of both exhaust trains on the affected unit.
- ◆ Modifications to supply non-interruptible air to the Turbine Building HVAC dampers will be implemented by the end of 2009.
- ◆ No single failures exist that would impact both unit's Turbine Building exhaust capability.





## ***Turbine Building HVAC Power Supplies***

---

- ◆ **No common power supplies exist through the start-up auxiliary transformers which would result in loss of both units' Turbine Building HVAC system.**
- ◆ **A single failure in any unit can result in complete loss of both exhaust trains on the affected unit.**
- ◆ **The only common mode issue that would affect both units is a seismic event.**
- ◆ **Unit 2 and Unit 1 Electrical MCCs will be walked down during the 2007 and 2008 outages and seismically evaluated.**

## ***Diesel Generator Loading***

---

- ◆ Diesel generator loading is approaching its rating limits.
- ◆ Calculations show current KW loading above continuous ratings for some scenarios.
- ◆ Operators would be forced to make hard choices and be more selective in load reductions.
- ◆ Adding Turbine Building fan motors will require the diesel generators to operate within their overload rating.
- ◆ Operating in the overload rating reduces the life of the machine.
- ◆ *The operators should not be required to make hard choices to remove safety related pumps from service in order to load the Turbine Building fans on the safety related buses.*

## ***Standby Liquid Control System Assessment***

---

- ◆ **SLC function is control of the pH in the suppression pool following a design-basis LOCA.**
- ◆ **SLC assessed to confirm reliability to perform its AST function per NRC review guidelines, “Guidance on the Assessment of a BWR SLC System for pH Control.”**
  - ◆ SLC pumps and valves are powered from the standby AC power supply and from separate buses.
  - ◆ SLC is seismically qualified in accordance with Reg. Guide 1.29 and App. A to 10 CFR Part 100.
  - ◆ SLC is incorporated into the plant’s ASME Code ISI and IST Programs.
  - ◆ SLC is incorporated into the plant’s Maintenance Rule Program.
  - ◆ SLC meets 10 CFR 50.49.
    - Environmental conditions are considered mild environment for SLC components.
    - SLC associated cables are environmentally qualified.
  - ◆ Although SLC is subject to a single failure, non-redundant active components are reliable to perform the AST function.
    - Injection check valves are shown to be highly reliable.
    - Although SLC initiation control switch failure is unlikely, it is located in the Main Control Room which is continually manned with provisions in place for manual SLC initiation.

# ***Technical Specification Changes***

---

- ◆ **AST implementation includes the following key technical specification changes:**
  - ◆ Standardize MSIV total allowed leakage rates between units at 100 scfh
  - ◆ DEI-131 specific activity of reactor coolant revised from 4.0  $\mu\text{Ci/gm}$  to 2.0  $\mu\text{Ci/gm}$
  - ◆ Add secondary containment bypass leakage to Unit 1 and increase value for Unit 2 (2% for both units)
  - ◆ Add drywell spray Technical Specification
  - ◆ TS Bases changes to reflect AST

# ***Conclusion***

---

◆ **Open Discussion**

◆ **Questions**