



UNITED STATES
NUCLEAR REGULATORY COMMISSION
REGION I
475 ALLENDALE ROAD
KING OF PRUSSIA, PENNSYLVANIA 19406-1415

November 29, 2006

Docket No. 03013022
Control No. 139454

License No. 44-00728-13

Frances Carr
Vice President for Research and Dean of Graduate Studies
University of Vermont
004 Rowell Building
Radiation Safety Office
106 Carrigan Drive
Burlington, VT 05405

SUBJECT: UNIVERSITY OF VERMONT, LICENSE AMENDMENT, CONTROL NO. 139454

Dear Mr. Carr:

This refers to your license amendment request. Enclosed with this letter is the amended license.

Please review the enclosed document carefully and be sure that you understand and fully implement all the conditions incorporated into the amended license. If there are any errors or questions, please notify the U.S. Nuclear Regulatory Commission, Region I Office, Licensing Assistance Team, (610) 337-5239, so that we can provide appropriate corrections and answers.

An environmental assessment for this action is not required, since this action is categorically excluded under 10 CFR 51.22(c)(14).

Current NRC regulations and guidance are included on the NRC's website at www.nrc.gov; select **Nuclear Materials; Medical, Academic, and Industrial Uses of Nuclear Material**; then **Toolkit Index Page**. Or you may obtain these documents by contacting the Government Printing Office (GPO) toll-free at 1-888-293-6498. The GPO is open from 7:00 a.m. to 8:00 p.m. EST, Monday through Friday (except Federal holidays).

Thank you for your cooperation.

Sincerely,

Original signed by Thomas K. Thompson

Thomas K. Thompson
Senior Health Physicist
Commercial and R&D Branch
Division of Nuclear Materials Safety

Enclosure:
Amendment No. 14

F. Carr
University of Vermont

2

cc:
Keddy G. Bharathan, Radiation Safety Officer

DOCUMENT NAME: C:\FileNet\ML063340292.wpd

SUNSI Review Complete: TThompson

After declaring this document "An Official Agency Record" it will be released to the Public.

To receive a copy of this document, indicate in the box: "C" = Copy w/o attach/encl "E" = Copy w/ attach/encl "N" = No copy

OFFICE	DNMS/RI	N	DNMS/RI	DNMS/RI			
NAME	TThompson /TKT/						
DATE	11/29/06						

OFFICIAL RECORD COPY

MATERIALS LICENSE

Pursuant to the Atomic Energy Act of 1954, as amended, the Energy Reorganization Act of 1974 (Public Law 93-438), and Title 10, Code of Federal Regulations, Chapter I, Parts 30, 31, 32, 33, 34, 35, 36, 39, 40, and 70, and in reliance on statements and representations heretofore made by the licensee, a license is hereby issued authorizing the licensee to receive, acquire, possess, and transfer byproduct, source, and special nuclear material designated below; to use such material for the purpose(s) and at the place(s) designated below; to deliver or transfer such material to persons authorized to receive it in accordance with the regulations of the applicable Part(s). This license shall be deemed to contain the conditions specified in Section 183 of the Atomic Energy Act of 1954, as amended, and is subject to all applicable rules, regulations, and orders of the Nuclear Regulatory Commission now or hereafter in effect and to any conditions specified below.

Licensee		In accordance with application dated September 11, 2006,	
1. University of Vermont Radiation Safety Office		3. License number 44-00728-13 is amended in its entirety to read as follows:	
2. 004 Rowell Building 106 Carrigan Drive Burlington, Vermont 05405		4. Expiration date May 31, 2015	
		5. Docket No. 030-13022 Reference No.	
6. Byproduct, source, and/or special nuclear material	7. Chemical and/or physical form	8. Maximum amount that licensee may possess at any one time under this license	
A. Any byproduct material with atomic numbers 2 through 83	A. Any	A. Not to exceed 300 millicuries per radionuclide and 1 curie total	
B. Any byproduct material with atomic numbers 84 through 95	B. Any	B. Not to exceed 1 millicurie per radionuclide and 10 millicuries total	
C. Hydrogen 3	C. Any	C. 1 curie	
D. Cobalt 60	D. Sealed source (ORNL)	D. 3 curies	
E. Americium 241	E. Any	E. 5 millicuries	
9. Authorized use:			
A. through E Research and development as defined in 10 CFR 30.4; animal studies; teaching and training of students.			

CONDITIONS

10. Licensed material may be used only at the licensee's facilities located at University of Vermont's campuses in Burlington, Vermont; South Burlington, Vermont; and Colchester, Vermont.

**MATERIALS LICENSE
SUPPLEMENTARY SHEET**License Number
44-00728-13Docket or Reference Number
030-13022

Amendment No. 14

11. A. Licensed material shall be used by, or under the supervision of, individuals designated in writing by the Radiation Safety Committee.

B. The Radiation Safety Officer for this license is Keddy G. Bharathan.
12. A. Sealed sources shall be tested for leakage and/or contamination at intervals not to exceed six months or at the intervals specified in the certificate of registration issued by the U.S. Nuclear Regulatory Commission under 10 CFR 32.210 or under equivalent regulations of an Agreement State.

B. Notwithstanding Paragraph A of this Condition, sealed sources designed to primarily emit alpha particles shall be tested for leakage and/or contamination at intervals not to exceed 3 months.

C. Each sealed source fabricated by the licensee shall be inspected and tested for construction defects, leakage, and contamination prior to any use or transfer as a sealed source.

D. In the absence of a certificate from a transferor indicating that a leak test has been made within the intervals specified in the certificate of registration issued by the U.S. Nuclear Regulatory Commission under 10 CFR 32.210 or under equivalent regulations of an Agreement State, prior to the transfer, a sealed source received from another person shall not be put into use until tested and the test results received.

E. Sealed sources need not be tested if they contain only hydrogen-3; or they contain only a radioactive gas; or the half-life of the isotope is 30 days or less; or they contain not more than 100 microcuries of beta- and/or gamma-emitting material or not more than 10 microcuries of alpha-emitting material.

F. Sealed sources need not be tested if they are in storage and are not being used; however, when they are removed from storage for use or transferred to another person and have not been tested within the required leak test interval, they shall be tested before use or transfer. No sealed source shall be stored for a period of more than 10 years without being tested for leakage and/or contamination.

G. The leak test shall be capable of detecting the presence of 0.005 microcurie (185 becquerels) of radioactive material on the test sample. If the test reveals the presence of 0.005 microcurie (185 becquerels) or more of removable contamination, a report shall be filed with the U.S. Nuclear Regulatory Commission in accordance with 10 CFR 30.50(c)(2), and the source shall be removed immediately from service and decontaminated, repaired, or disposed of in accordance with Commission regulations.

H. Tests for leakage and/or contamination, including leak test sample collection and analysis, shall be performed by the licensee or by other persons specifically licensed by the U.S. Nuclear Regulatory Commission or an Agreement State to perform such services.

I. Records of leak test results shall be kept in units of microcuries and shall be maintained for 5 years.

**MATERIALS LICENSE
SUPPLEMENTARY SHEET**License Number
44-00728-13Docket or Reference Number
030-13022


Amendment No. 14

13. Sealed sources or detector cells containing licensed material shall not be opened or sources removed from source holders by the licensee.
14. The licensee shall conduct a physical inventory every six months, or at other intervals approved by the U.S. Nuclear Regulatory Commission, to account for all sources and/or devices received and possessed under the license. Records of inventories shall be maintained for 5 years from the date of each inventory and shall include the radionuclides, quantities, manufacturer's name and model numbers, and the date of the inventory.
15. In addition to the possession limits in Item 8, the licensee shall further restrict the possession of licensed material at a single location to quantities below the limits specified in 10 CFR 30.72 which require consideration of the need for an emergency plan for responding to a release of licensed material.
16. Licensed material shall not be used in or on human beings.
17. The licensee shall not use licensed material in field applications where activity is released except as provided otherwise by specific condition of this license.
18. Experimental animals, or the products from experimental animals, that have been administered licensed materials shall not be used for human consumption.
19. A. Detector cells containing a titanium tritide foil or a scandium tritide foil shall only be used in conjunction with a properly operating temperature control mechanism which prevents the foil temperatures from exceeding that specified in the certificate of registration referred to in 10 CFR 32.210.
B. When in use, detector cells containing a titanium tritide foil or a scandium tritide foil shall be vented to the outside.
20. The licensee is authorized to transport licensed material in accordance with the provisions of 10 CFR Part 71, "Packaging and Transportation of Radioactive Material."
21. The licensee is authorized to hold byproduct material with a physical half-life of less than 120 days for decay-in-storage before disposal without regard to its radioactivity if it:
 - A. Monitors byproduct material at the surface before disposal and determines that its radioactivity cannot be distinguished from the background radiation level with an appropriate radiation detection survey meter set on its most sensitive scale and with no interposed shielding; and
 - B. Removes or obliterates all radiation labels, except for radiation labels on materials that are within containers and that will be managed as biomedical waste after they have been released from the licensee; and

**MATERIALS LICENSE
SUPPLEMENTARY SHEET**License Number
44-00728-13Docket or Reference Number
030-13022

Amendment No. 14

- C. Maintains records of the disposal of licensed materials for 3 years. The record must include the date of disposal, the survey instrument used, the background radiation level, the radiation level measured at the surface of each waste container, and the name of the individual who performed the disposal.
22. Radioactive waste possessed under this license shall be stored in accordance with the statements, representations, and procedures included with the licensee's waste storage plan described in the letter dated November 18, 2004.
23. Except as specifically provided otherwise in this license, the licensee shall conduct its program in accordance with the statements, representations, and procedures contained in the documents, including any enclosures, listed below. The U.S. Nuclear Regulatory Commission's regulations shall govern unless the statements, representations, and procedures in the licensee's application and correspondence are more restrictive than the regulations.
- A. Application dated August 26, 2004 (ML042520108)
B. Letter with attachments dated November 18, 2004 (ML043420341)



For the U.S. Nuclear Regulatory Commission

Date November 29, 2006

By

Original signed by Thomas K. Thompson

Thomas K. Thompson
Commercial and R&D Branch
Division of Nuclear Materials Safety
Region I
King of Prussia, Pennsylvania 19406