

SURVEILLANCE REQUIREMENTS (continued)

SURVEILLANCE		FREQUENCY
SR 3.1.7.7	Verify each pump develops a flow rate $\geq 41.2$ gpm at a discharge pressure $\geq 1320$ psig.	In accordance with the Inservice Testing Program
SR 3.1.7.8	Verify flow through one SLC subsystem from pump into reactor pressure vessel.	24 months on a STAGGERED TEST BASIS
SR 3.1.7.9	Verify all heat traced piping between storage tank and pump suction valve is unblocked.	24 months  <u>AND</u>  Once within 24 hours after piping temperature is restored to $\geq 70^{\circ}\text{F}$
SR 3.1.7.10	Verify sodium pentaborate enrichment is $\geq 25$ atom percent B-10.	Prior to addition to SLC tank