

SURVEILLANCE REQUIREMENTS (continued)

SURVEILLANCE		FREQUENCY
SR 3.6.1.3.4	Verify the isolation time of each power operated and each automatic PCIV, except MSIVs, is within limits.	In accordance with the Inservice Testing Program
SR 3.6.1.3.5	<p>-----NOTE----- Only required to be met in MODES 1, 2, and 3. -----</p> <p>Perform leakage rate testing for each primary containment purge valve with resilient seals.</p>	In accordance with the Primary Containment Leakage Rate Testing Program
SR 3.6.1.3.6	Verify the isolation time of each MSIV is ≥ 3 seconds and ≤ 5 seconds.	In accordance with the Inservice Testing Program
SR 3.6.1.3.7	Verify each automatic PCIV actuates to the isolation position on an actual or simulated isolation signal.	18 months

(continued)