

## REACTIVITY CONTROL SYSTEMS

### ROD DROP TIME

#### LIMITING CONDITION FOR OPERATION

---

---

3.1.3.4 The individual full-length (shutdown and control) rod drop time from the fully withdrawn position shall be less than or equal to 2.7 seconds from beginning of decay of stationary gripper coil voltage to dashpot entry with:

- a.  $T_{avg}$  greater than or equal to 500°F, and
- b. All reactor coolant pumps operating.

APPLICABILITY: MODES 1 and 2.

#### ACTION:

- a. With the drop time of any full-length rod determined to exceed the above limit, restore the rod drop time to within the above limit prior to proceeding to MODE 1 or 2.
- b. With the rod drop times within limits but determined with three reactor coolant pumps operating, operation may proceed provided THERMAL POWER is restricted to less than or equal to 65% of RATED THERMAL POWER with the reactor coolant stop valves in the nonoperating loop closed.

#### SURVEILLANCE REQUIREMENTS

---

---

4.1.3.4 The rod drop time of full-length rods shall be demonstrated through measurement prior to reactor criticality:

- a. For all rods following each removal of the reactor vessel head, and
- b. Deleted
- c. At least once per 24 months.

## PLANT SYSTEMS

### 3/4.7.9 AUXILIARY BUILDING FILTER SYSTEM

#### LIMITING CONDITION FOR OPERATION

---

---

3.7.9 Two independent Auxiliary Building Filter Systems shall be OPERABLE.

APPLICABILITY: MODES 1, 2, 3, and 4.

ACTION:

With one Auxiliary Building Filter System inoperable, restore the inoperable system to OPERABLE status within 7 days or be in at least HOT STANDBY within the next 6 hours and in COLD SHUTDOWN within the following 30 hours. In addition, comply with the ACTION requirements of Specification 3.6.6.1.

#### SURVEILLANCE REQUIREMENTS

---

---

4.7.9 Each Auxiliary Building Filter System shall be demonstrated OPERABLE:

- a. At least once per 31 days on a STAGGERED TEST BASIS by initiating, from the control room, flow through the HEPA filters and charcoal adsorbers and verifying a system flow rate of 30,000 cfm  $\pm 10\%$  and that the system operates for at least 10 continuous hours with the heaters operating;
- b. At least once per 24 months or following painting, fire, or chemical release in any ventilation zone communicating with the system by:
  - 1) Verifying that the cleanup system satisfies the in-place penetration and bypass leakage testing acceptance criteria of less than 0.05% and uses the test procedure guidance in Regulatory Positions C.5.a, C.5.c, and C.5.d of Regulatory Guide 1.52, Revision 2, March 1978,\* and the system flow rate is 30,000 cfm  $\pm 10\%$ ;
  - 2) Verifying, within 31 days after removal, that a laboratory analysis of a representative carbon sample obtained in accordance with Regulatory Position C.6.b of Regulatory Guide 1.52, Revision 2, March 1978,\* shows the methyl