



ELECTRIC POWER  
RESEARCH INSTITUTE

# **Pre-Emptive Weld Overlay Project MRP-169 Summary/Status NDE Considerations**

Pete Riccardella & Bud Auvil  
Structural Integrity Associates

Jack Spanner & Carl Latiolais  
EPRI

May 30, 2007  
MRP/PWROG Mitigation Briefing to NRC RES

# Presentation Overview


---

- MRP-169 Summary
- PWOL Mockup / Residual Stress Measurements
- RAI Questions and Response Plan
- Inspection Considerations


# MRP-169 Design Requirements

- Structural Sizing
- Residual Stress Improvement
- Inspectability Considerations
- Fatigue and Crack Growth Considerations
- Leak Before Break

# PWOL Design Concepts (as Defined in MRP-169)



## Full Structural Overlay



## Optimized Overlay

# PWOL Design Requirements: Residual Stress Improvement

- Weld overlay improves residual stress condition
  - Nozzle-specific analyses required to demonstrate that PWOL reverses residual stress field producing compressive residual stresses (both axial and hoop) in original pipe wall
  - Initial unfavorable residual stress state assumed in DMW due to ID weld repair during plant construction
  - Prior experimental work has validated residual stress analysis techniques (EPRI Reports NP-7103-D and NP-7085-D)
- Recent MRP PWOL Mockup project confirmed residual stress improvement on typical PWR nozzle geometry


# PWOL Design Requirements: Fatigue Considerations

- Fatigue Crack Growth
  - Assume initial flaw  $\geq$  thresholds of the NDE techniques used on the nozzles
    - For PDI qualified, pre-WOL inspection (10% thru wall typically assumed)
    - For nozzles not inspected pre-WOL, start with flaw depth = post-WOL inspection depth (50% or 75% thru wall as applicable)
  - Apply residual stresses plus all design basis loading conditions, including flow stratification transients where applicable (e.g.. NRC Bulletin 88-01 for surge nozzles)
  - Demonstrate that flaw doesn't grow to design basis flaw for PWOL in time interval to next inspection or end of design life\*
- Fatigue Usage
  - Demonstrate acceptable fatigue usage for overlay geometry in accordance with ASME Section III requirements to end of design life\*

\* - including license renewal where applicable

# PWOL Design Requirements: Inspectability Considerations

- WOL length and other design details often need to be adjusted (increased) to accommodate inspection requirements
  - WOL plus outer 25% or 50% of original nozzle thickness, encompassing PWSCC material + 1/2" on either side of weld
  - Inspectability of adjacent welds also needs to be considered



# Typical Overlay Design/Analysis Results

**From  
Structural  
Sizing**

Nozzle	WOL Thickness (in.)		Minimum Length (in.)
	Optimized Structural	Full Structural	
Pressurizer Spray	0.21	0.292	4.28
Pressurizer Surge	0.21	0.427	6.27
RCS Hot Leg	0.48	1.05	11.30

**Required for  
Resid. Stress &  
Inspectability**


Nozzle	WOL Thickness (in.)	WOL Length (in.)
Pressurizer Spray	0.30	7.19
Pressurizer Surge	0.44	9.81
RCS Hot Leg	0.48	11.60




# PWOL Mockup / Residual Stress Measurements

- A PWOL mockup was fabricated simulating a PWR surge nozzle, including:
  - Ferritic Nozzle, Tapered SS Safe-end & SS Pipe
  - Two welds + ID repair
  - Alloy-52 WOL
- Design and Residual Stress Analyses Performed
- Residual Stresses Measured before and after WOL application


# PWOL Mockup Drawing



# PWOL Mockup Finite Element Model




# ID of Mockup Showing 90° Weld Repair & XRD Measurement Locations



# Residual Stress Results


## Axial: Pre-Overlay





# Residual Stress Results

## Axial: Post-Overlay

**ID Surface Axial Stress**  
Post-Overlay Analysis vs. Measurements




**ID Weld Repair**



# Residual Stress Results

## Hoop: Pre-Overlay


**ID Surface Hoop Stress**  
Pre-Overlay Analysis vs. Measurements





# Residual Stress Results

## Hoop: Post-Overlay

**ID Surface Hoop Stress**  
Post-Overlay Analysis vs. Measurements



**ID Weld Repair**





# MRP-169 – NRC Request for Additional Information (RAI)

- Thirty (30) questions
  - General comments (4)
  - Inspections (8)
  - Leak Before Break (2)
  - Fatigue (2)
  - Weld Overlay Effectiveness (3)
  - Stress Analysis (6)
  - Example Analysis (1)
  - Clarifications (4)
- Draft initial RAI ‘plan of attack’ and ‘overarching issues summary’ provided to MRP in early May ‘07
- MRP conference call held in early May ‘07 to obtain concurrence on RAI response approach and project schedule

## MRP-169 – NRC RAI Project Schedule

Timeframe	Milestone
Early June '07	Draft Final Responses for MRP Review and Comment
Early July '07	MRP Comment Resolution Close-Out and NRC (Draft) RAI Response Submittal
TBD	MRP/NRC Staff Meeting to Present and Discuss Draft RAI Responses
TBD	Finalize and Submit RAI Responses
TBD	Revise and Resubmit MRP-169 for SER

# Summary of Overarching Issues

- Inconsistencies in Post Overlay ISI Requirements
  - MRP-169 vs. MRP-139 vs. (draft) Code Cases N-740-1 and N-754
  - Optimized WOL provides stress improvement plus structural and PWSCC resistance functionality. Therefore:
    - MRP-139, Cat. B (not Cat. C) should apply if pre-WOL inspection is conducted, found clean and optimized WOL applied;
    - MRP-139, Cat. F (not Cat. G) should apply if pre-WOL inspection is not conducted, or found cracked and optimized WOL applied;
    - Technical basis statement to be developed to support position (similar to MRP-139, Section 6) and formal 'interim guidance' obtained to reconcile with MRP-139
  - MRP does not endorse the 25% sampling approach for future WOL inservice inspections addressed by Code Case N-740
  - MRP-139/-169 5-year subsequent inspection requirement to be maintained rather than 1<sup>st</sup> or 2<sup>nd</sup> outage subsequent inspection requirement of Code Case N-740

# Summary of Overarching Issues (Cont'd)

- Optimized Overlays for Repair as well as Mitigation
  - Repairs for nozzle welds with cracks of a prescribed thru-wall and circumferential dimension substantiated by design analysis
  - Allowance akin to that defined for MSIP (30% TW, 10% circumferential)
  - May permit use of Optimized WOL without pre-inspection
- Additional Qualification for Exams from ID Surface
  - Preserve option of ID exams for Optimized WOL subsequent inspections
  - Requires further PDI qualification of ID exam for detection and sizing of potential cracks in the compressive region of weld overlaid DMW
  - Mockup samples being developed for this purpose

# Summary of Overarching Issues (Cont'd)

- LBB Re-Analysis Requirement
  - Impact of WOL on LBB analyses must be evaluated (from technical and licensing standpoint)
- Fatigue Crack Growth Evaluation Period
  - Section III fatigue usage computations, the evaluation period is to the end of plant life, including license renewal where applicable
  - Fatigue crack growth evaluation is based on next scheduled exam

# Conclusion/Summary

- MRP-169 will provide licensing basis for Optimized or reduced thickness WOLs
- Clear path for resolution of NRC RAI has been established
  - NRC approval requested consistent with first hot leg applications in Fall 2008
- Application of Optimized WOL as a repair (vs. mitigation measure) is defensible based on its design basis and regulatory precedent for MSIP/IHSI
- Interim MRP-139 guidance will be developed for Optimized WOL Category assignments

# Inspection Considerations

- Project Overview
- Phase I – 2006
  - Objectives
  - Results
- Phase II – 2007
  - Objectives
  - Planned activities
  - 2007 Mitigation Objectives & Workscope
- Phase III - 2008
  - Proposed activities
  - NDE Qualifications and Reporting
- Summary

# Project Overview

- **Closure of Inspection Gaps**
- **NDE of upper 50% of base material for optimized overlays**
- **NDE of weld Overlay (WOL) over Cast SS**
- **Address tapered surface examinations and configurations**
- **Address configurations requiring non-standard overlays**
- **Residual stress measurements to confirm model**



# Project Overview

- **Project is accomplished through three phases**
  - **Phase I**
    - **MRP funded in 2006 targeting the Pressurizer nozzles**
  - **Phase II**
    - **MEOG funded for 2007 targeting large diameter components**
  - **Phase III**
    - **NDE Center funds in 2008**
    - **NDE Technique development**
    - **Documentation**
    - **Demonstration**
    - **Incorporation into ASME Code**

# Pre-Emptive Weld Overlay Project – Phase I 2006

- Funded by MRP - 2006
- Objectives;
  - Pressurizer locations with and without WOL
  - Pressurizer locations with and without Cast SS safe-ends
  - Validation of Hot Isostatic Pressure (HIP) flaw process on Cast SS
  - NDE of upper 50% of base material
- Results
  - Mock ups complete (Full structural)
  - Additional NDE analysis is being performed to validate results
  - HIP process modifications will be considered for Phase II
  - 75% deep flaws were not detected
    - Detected flaws which extend into WOL
  - Current qualified PDI techniques are invalid on Cast SS w/ WOL
  - NDE techniques and Equipment modifications are needed
    - Working with vendors to improve

# Phase I Mock up Summary

			Without WOL	With WOL
System	NSSS	Location	# of Mock ups reqd	# of Mock ups reqd
PZR	CE	Surge	0	1
PZR	CE	Spray	0	1
PZR	CE	Safety/Relief	2	2
Hot Leg	CE	Surge Line	0	0

# Pre-Emptive Weld Overlay Project – Phase II 2007

- Funded by MEOG - 2007
- Objectives;
  - Locations include; RCP Inlet/Outlet, Shut down Cooling, Drain Nozzles, Safety Injection
    - With and without WOL
    - FSWOLs and OWOLs to be evaluated
  - Locations with Cast SS include; Surge, Safety/Relief, RCP, Safety Injection & Shutdown cooling
  - Validation of HIP process on heavy wall Cast SS
  - NDE of upper 50% of base material
- Planned activities
  - Analyze configuration data
  - Finalize sample design
  - Fabricate samples
  - Stress and weld dilution measurements
  - Perform QA and establish UT fingerprint baseline data
  - Document limitations and develop resolution plans

# Phase II Mock up Summary

			Without WOL	With WOL
System	NSSS	Location	# of Mock ups reqd	# of Mock ups reqd
Hot Leg	CE	Shutdown Cooling	1	1
Hot Leg	CE	Drain Nozzles	2	2
Cold Leg	CE	RCP In / Out	1	1
Cold Leg	CE	Safety Injection	0	0
Cold Leg	CE	Letdown/Drain Nz	0	0
Cold Leg	CE	Charging Inlet / Spray	2	2

12 Total

# Mitigation Objectives 2007

- Mitigation Project Objectives
  - Include required design attributes
  - Hold points are set to allow collection of the required measurements needed to support design
  - Assure welding processes used were consistent with the current industry practices and planned applications in the field
  - Provide information to complete finite element analysis for large thick pipes

# 2007 Mitigation Work Scope

- Information needed for design and welding of large diameter thick cast components
  - Overlay design
    - Optimized overlay design
    - Full structural overlay design
  - Verification of Stress Profile
  - Dilution Measurements
    - Verification of Cr (%) (first 2 layers)
  - Shrinkage Data (per weld layer)
- Reporting and Data Collection

# Pre-Emptive Weld Overlay Project – Phase III 2008

- Funded by EPRI (NDE) – 2008
  - Proposed activities include:
    - Additional technique development
    - Project documentation – 2007 results
    - Complete demonstration activities
    - Integrate results into ASME code



# 2008 NDE Qualifications & Report

- Work Scope
  - Develop Code criteria and relief requests needed to qualify NDE procedures for the examination of PWOL's
  - Develop and qualify examination procedures to address pre-emptive weld overlays
  - Develop and qualify examination procedures to examine overlays that cover cast SS components
  - Document stress/strain data, which will be used to support the design and application of pre-emptive weld overlays for large diameter, thick components

# Summary

- **Review of configuration data has indicated that additional mock-ups are needed to close inspection gaps**
  - **Unique configurations**
    - Including tapers
    - Thickness/diameter changes
  - **Cast Components**
  - **Overlays**
- **Mitigation Committee needs additional data to support both;**
  - **Full structural overlays of thick components**
  - **Optimized overlays of thick components**