

(1) Maximum Power Level

PSEG Nuclear LLC is authorized to operate the facility at a steady state reactor core power level not in excess of 3459 megawatts (one hundred percent of rated core power).

(2) Technical Specifications

The Technical Specifications contained in Appendices A and B, as revised through Amendment No. 283, are hereby incorporated in the license. The licensee shall operate the facility in accordance with the Technical Specifications.

(3) Deleted Per Amendment 22, 11-20-79

(4) Less than Four Loop Operation

PSEG Nuclear LLC shall not operate the reactor at power levels above P-7 (as defined in Table 3.3-1 of Specification 3.3.1.1 of Appendix A to this license) with less than four (4) reactor coolant loops in operation until safety analyses for less than four loop operation have been submitted by the licensees and approval for less than four loop operation at power levels above P-7 has been granted by the Commission by Amendment of this license.

(5) PSEG Nuclear LLC shall implement and maintain in effect all provisions of the approved fire protection program as described in the Updated Final Safety Analysis Report, and as approved in the NRC Safety Evaluation Report dated November 20, 1979, and in its supplements, subject to the following provision:

PSEG Nuclear LLC may make changes to the approved fire protection program without prior approval of the Commission only if those changes would not adversely affect the ability to achieve and maintain safe shutdown in the event of a fire.

3/4.3 INSTRUMENTATION

3/4.3.1 REACTOR TRIP SYSTEM INSTRUMENTATION

LIMITING CONDITION FOR OPERATION

3.3.1.1 As a minimum, the reactor trip system instrumentation channels and interlocks of Table 3.3-1 shall be OPERABLE.

APPLICABILITY: As shown in Table 3.3-1.

ACTION:

As shown in Table 3.3-1.

SURVEILLANCE REQUIREMENTS

4.3.1.1.1 Each reactor trip system instrumentation channel shall be demonstrated OPERABLE by the performance of the CHANNEL CHECK, CHANNEL CALIBRATION and CHANNEL FUNCTIONAL TEST operations during the MODES and at the frequencies shown in Table 4.3-1.

4.3.1.1.2 The logic for the interlocks shall be demonstrated OPERABLE prior to each reactor startup unless performed during the preceding 92 days. The total interlock function shall be demonstrated OPERABLE at least once per 18 months during CHANNEL CALIBRATION testing of each channel affected by interlock operation.

4.3.1.1.3 The REACTOR TRIP SYSTEM RESPONSE TIME of each reactor trip function shall be verified to be within its limit at least once per 18 months. Neutron detectors are exempt from response time testing. Each verification shall include at least one logic train such that both logic trains are verified at least once per 36 months and one channel per function such that all channels are verified at least once every N times 18 months where N is the total number of redundant channels in a specific reactor trip function as shown in the "Total No. of Channels" column of Table 3.3-1.

Page Left Blank Intentionally

Page Left Blank Intentionally

INSTRUMENTATION

3/4.3.2 ENGINEERED SAFETY FEATURE ACTUATION SYSTEM INSTRUMENTATION

LIMITING CONDITION FOR OPERATION

=====

3.3.2.1 The Engineered Safety Feature Actuation System (ESFAS) instrumentation channels and interlocks shown in Table 3.3-3 shall be OPERABLE with their trip setpoints set consistent with the values shown in the Trip Setpoint column of Table 3.3-4.

APPLICABILITY: As shown in Table 3.3-3.

ACTION:

- a. With an ESFAS instrumentation channel trip setpoint less conservative than the value shown in the Allowable Values column of Table 3.3-4, declare the channel inoperable and apply the applicable ACTION requirement of Table 3.3-3 until the channel is restored to OPERABLE status with the trip setpoint adjusted consistent with the Trip Setpoint value.
- b. With an ESFAS instrumentation channel inoperable, take the ACTION shown in Table 3.3-3.

SURVEILLANCE REQUIREMENTS

4.3.2.1.1 Each ESFAS instrumentation channel shall be demonstrated OPERABLE by the performance of the CHANNEL CHECK, CHANNEL CALIBRATION and CHANNEL FUNCTIONAL TEST operations during the MODES and at the frequencies shown in Table 4.3-2.

4.3.2.1.2 The logic for the interlocks shall be demonstrated OPERABLE during the automatic actuation logic test. The total interlock function shall be demonstrated OPERABLE at least once per 18 months during CHANNEL CALIBRATION testing of each channel affected by interlock operation.

4.3.2.1.3 The ENGINEERED SAFETY FEATURES RESPONSE TIME of each ESFAS function shall be verified to be within the limit at least once per 18 months. Each verification shall include at least one logic train such that both logic trains are verified at least once per 36 months and one channel per function such that all channels are verified at least once per N times 18 months where N is the total number of redundant channels in a specific ESFAS function as shown in the "Total No. of Channels" Column of Table 3.3-3. The provisions of Specification 4.0.4 are not applicable to MSIV closure time testing. The provisions of Specification 4.0.4 are not applicable to the turbine driven auxiliary feedwater pump provided the surveillance is performed within 24 hours after the secondary steam generator pressure is greater than 680 psig.

Page Left Blank Intentionally

Page Left Blank Intentionally

Page Left Blank Intentionally

Page Left Blank Intentionally

Page Left Blank Intentionally