



UNITED STATES
NUCLEAR REGULATORY COMMISSION
REGION II
230 PEACHTREE STREET, N.W. SUITE 1217
ATLANTA, GEORGIA 30303
NOV 15 1977

Centelli
50-390
391

In Reply Refer To:

RII:JPO

50-438, 50-439

50-259, 50-260

50-296, 50-518

50-519, 50-520

50-521, 50-553

50-554, 50-327

50-328, 50-390

50-391, 50-566

50-567

Tennessee Valley Authority
Attn: Mr. Godwin Williams, Jr.
Manager of Power
830 Power Building
Chattanooga, Tennessee 37401

Gentlemen:

Enclosed is a supplement (IE Bulletin No. 77-05A) to IE Bulletin No. 77-05 which requires action by you with regard to your power reactor facility(ies) with an operating license or a construction permit.

Should you have questions regarding this Bulletin or the actions required of you, please contact this office.

Sincerely,

Jack O'Reilly for
James P. O'Reilly
Director

Enclosures:

1. IE Bulletin No. 77-05A
2. List of IE Bulletins
Issued in 1977

AD ?
60

cc: J. E. Gilleland
Assistant Manager of Power
830 Power Building
Chattanooga, Tennessee 37401

W. W. Aydelott, Project Manager
Bellefonte Nuclear Plant
P. O. Box 2000
Hollywood, Alabama 35752

Stan Duhan
400 Commerce Street
E4D112
Knoxville, Tennessee 37902

J. G. Dewease, Plant Superintendent
Box 2000
Decatur, Alabama 35602

R. T. Hathcote, Project Manager
Hartsville Nuclear Plant
P. O. Box 2000
Hartsville, Tennessee 37074

G. G. Stack, Project Manager
Sequoyah Nuclear Plant
P. O. Box 2000
Daisy, Tennessee 37319

J. M. Ballentine
Plant Superintendent
Sequoyah Nuclear Plant
P. O. Box 2000
Daisy, Tennessee 37319

T. B. Northern, Jr.
Project Manager
Watts Bar Nuclear Plant
P. O. Box 2000
Spring City, Tennessee 37381

NUCLEAR REGULATORY COMMISSION
OFFICE OF INSPECTION AND ENFORCEMENT
WASHINGTON, D. C. 20555

November 15, 1977

IE Bulletin 77-05A

ELECTRICAL CONNECTOR ASSEMBLIES

Description of Circumstances:

This Bulletin is a supplement to IE Bulletin 77-05, issued November 8, 1977, and the two documents should be considered together.

Bulletin 77-05 described the failure, under test conditions, of a general type of electrical connector. The tests were intended to simulate post-LOCA conditions, therefore the action requested in the Bulletin focused on the qualification of electrical connectors for use inside containment.

Since issuance of Bulletin 77-05, our attention has been called to circumstances which indicate that the scope of the action requested should be expanded and therefore the response to Bulletin 77-05 should reflect the expanded scope.

Electrical connectors should be qualified to perform their intended function after having been subjected to accident conditions if they are contained in a system whose function is to mitigate that accident.

The location of the connectors that must be qualified is not limited to those inside containment.

Action To Be Taken By Licensees and Permit Holders:

1. Actions requested by Bulletin 77-05 should be expanded to include all connectors in safety systems which are required to function to mitigate an accident where the accident itself could adversely affect the ability of the system to perform its safety function. The examination is not to be limited to only LOCA's nor to areas only within containment.
2. Responses should be provided within 30 or 60 days, as appropriate, of the date of this supplement.

Approved by GAO, B180225 (R0072); clearance expires 7-31-80. Approval was given under a blanket clearance specifically for identified generic problems.

IE Bulletin 77-05A
November 15, 1977

LISTING OF IE BULLETINS
ISSUED IN 1977

Bulletin No.	Subject	Date Issued	Issued To
77-05	Electrical Connector Assemblies	11/8/77	All PWR Power Reactor Facilities with an Operating License (OL) or Construction Permit (CP)
77-04	Calculational Error Affecting the Design Performance of a System for Controlling pH of Containment Sump Water Following a LOCA	11/4/77	All PWR Power Reactor Facilities with an Operating License (OL) or Construction Permit (CP)
77-03	On-Line Testing of the W Solid State Protection System	9/12/77	All W Power Reactor Facilities with an Operating License (OL) or Construction Permit (CP)
77-02	Potential Failure Mechanism in Certain W AR Relays with Relays with Latch Attachments	9/12/77	All Holders of Operating Licenses (OL) or Construction Permits (CP)
77-01	Pneumatic Time Delay Set Point Drift	4/29/77	All Holders of Operating Licenses (OL) or Construction Permits (CP)