

ACTIONS

CONDITION	REQUIRED ACTION	COMPLETION TIME
C. (continued)	C.3 Verify MSIV and non-return check valve in the affected flowpath are closed and the MSIV is de-activated.	Once per 7 days
D. Required Action and associated Completion Time of Condition C not met.	D.1 Be in MODE 3.	6 hours
	<u>AND</u> D.2 Be in MODE 4.	12 hours

SURVEILLANCE REQUIREMENTS

SURVEILLANCE	FREQUENCY
SR 3.7.2.1 -----NOTE----- Only required to be performed in MODE 1. ----- Verify closure time of each MSIV is within limits.	In accordance with the Inservice Testing Program
SR 3.7.2.2 -----NOTE----- Only required to be performed in MODE 1. ----- Verify each MSIV actuates to the isolation position on an actual or simulated actuation signal.	18 months
SR 3.7.2.3 Verify each main steam non-return check valve can close.	In accordance with the Inservice Testing Program