

SUBJECT: TMI-2 ACTION PLAN ITEM I.G.1 - SPECIAL LOW POWER TESTING

NUREG-0737 "Clarification of TMI Action Plan Requirements" and NUREG-0694 "TMI Related Requirements for New Operating Licenses", Item I.G.1, calls for the implementation of "a special low power testing program approved by NRC to be conducted at power levels no greater than 5 percent for the purposes of providing meaningful technical information beyond that obtained in the normal startup test program and to provide supplemental training". Some PWR applicants have committed to a series of natural circulation tests. To date such tests have been performed at the Sequoyah 1, North Anna 2, and Salem 2 facilities. Based on the success of the programs at these plants, the staff has concluded that augmented natural circulation training should be performed for all future PWR operating licenses. This is to be implemented by including descriptions of natural circulation tests in your FSAR (Chapter 14 - Initial Test Program). If they are not already included in your FSAR, the natural circulation tests and associated training should be included either by modifying existing or adding new test descriptions in accordance with Regulatory Guide 1.70, Paragraph 14.2.12. The tests should fulfill the following objectives:

Training

Each licensed reactor operator (RO or SRO who performs RO or SRO duties, respectively) should participate in the initiation, maintenance and recovery from natural circulation mode. Operators should be able to recognize when natural circulation has stabilized, and should be able to control saturation margin, RCS pressure, and heat removal rate without exceeding specified operating limits.

Testing

The tests should demonstrate the following plant characteristics: length of time required to stabilize natural circulation, core flow distribution, ability to establish and maintain natural circulation with and without

OFFICE							
SURNAME					•••••••	•••••••••	•••••
	8106 2	30099	•••••				•••••••••••••••••••••••••••••••••••••••
NRC FORM 318 (10/80) NRCM 0240 OFFICIAL RECORD COPY *US							

H. G. Parris

(**b**)

JUN 16 1981

. . .

onsite and offsite power, the ability to uniformly borate and cool down to hot shutdown conditions using natural circulation, and subcooling monitor performance.

If these tests have been performed at a comparable prototype plant, they need be repeated only to the extent necessary to accomplish the above training objectives.

Procedure Validation

The tests should make maximum practical use of written plant procedures to validate the completeness and accuracy of the procedures.

The natural circulation tests require a source of actual or simulated decay heat. The tests may be performed during initial startup using nuclear heat to simulate decay heat, or may be performed later in the initial fuel cycle when actual decay heat is adequate to permit meaningful testing. If the test objectives are not compromised, pump heat during forced circulation operation could provide an acceptable source of simulated decay heat (e.g., the Lossof-Onsite and Offsite A/C Test performed at North Anna 2).

Applicants who perform a natural circulation boron-mixing and cooldown test to demonstrate compliance with Branch Technical Position RSB BTP 5-1 may use that test to accomplish some or all of the above training and testing objectives.

This guidance is provided for all PWR OL applicants and supersedes that dated November 14, 1980. Regulatory Guide 1.68 and/or the Standard Review Plan will be revised at a future date to include natural circulation testing and the associated training. OL applicants should submit test descriptions in accordance with Regulatory Guide 1.70, Paragraph 14.2.12, as part of their FSAR or an amendment thereto. Detailed test procedures should be made available for NRC review 60 days prior to scheduled test performance (see Regulatory Guide 1.68, Appendix B). When required by 10 CFR 50.59, a safety analysis must be prepared and distributed in accordance with the requirements stated therein.

Sincerely,

Robert L. Tedesco, Assistant Director for Licensing Division of Licensing

cc: See next page

OFFICE	L:LB#4./		ADRE			
SURNAME	Tkenvon:eb	EAdensam	RTesesco			 •••••
BATE	6/10/81	6/1 1/81	6/ <i>5</i> /81			
NRC FORM	318 (10/80) NRCM (9240	OFFICIAL	RECORD C	OPY	 ★ USGPO: 1980—329-824

Mr. H. G. Parris Manager of Power Tennessee Valley Authority 500A Chestnut Street Tower II Chattanooga, Tennessee 37401

cc: Herbert S. Sanger, Jr., Esq. General Counsel Tennessee Valley Authority 400 Commerce Avenue E11B33 Knoxville, Tennessee 37902

> Mr. W. Luce Westinghouse Electric Corporation P. O. Box 355 Pittsburgh, Pennsylvania 15230

Mr. David Lambert Tennessee Valley Authority 400 Chestnut Street Tower II Chattanooga, Tennessee 37401

Mr. J. F. Cox Tennessee Valley Authority 400 Commerce Avenue, W9D207 Knoxville, Tennessee 37902

Resident Inspector/Watts Barr NPS c/o U. S. Nuclear Regulatory Commission Rt. 2 - Box 300 Spring City, Tennessee 37831

Mr. David Ormsby Tennessee Valley Authority 400 Chestnut Street, Tower II Chattanooga, Tennessee 37401