

2.6.8 Containment Building Ventilation System

1.0 Description

The containment building ventilation system (CBVS) controls the Containment Building temperature, humidity and air change rate for personnel comfort, personnel safety, and equipment protection during normal plant operation. The CBVS provides cooling, heating, and ventilation for the Containment Building to remove equipment heat, and heat generated from other sources. The CBVS also provides heat to maintain a minimum temperature in the building. The CBVS provides a minimal air change rate for the building and controls the building pressurization to reduce spreading of contamination.

The CBVS provides the following safety related functions:

- Upon receipt of a containment isolation signal, the CBVS provides automatic isolation of the containment atmosphere by quick closure of the system containment isolation valves.
- CBVS low flow purge exhaust to iodine filtration trains.

The CBVS provides the following non-safety related functions:

- Containment full flow purge supply and exhaust during outages.
- Containment low flow purge supply for containment entry during normal plant operation.
- Internal filtration to reduce radioactive contamination inside the equipment compartment.
- Supply of cool air to the reactor pit area to prevent concrete degradation.
- Containment cooling to maintain ambient conditions.

2.0 Arrangement

2.1 The functional arrangement of the CBVS is as shown in the Figure 2.6.8-1—Containment Building Ventilation System Functional Arrangement

2.2 The location of CBVS equipment is as listed in Table 2.6.8-1—Containment Building Ventilation System Containment Isolation Valves Mechanical Design, and Table 2.6.8-2—Containment Building Ventilation System Equipment Mechanical Design.

3.0 Mechanical Design Features

3.1 Equipment listed in Table 2.6.8-1 as ASME Code Section III, is designed and tested in accordance with ASME Code Section III.

3.2 Equipment listed in the Table 2.6.8-2 as ASME AG-1 is designed, inspected and tested per ASME AG-1.

- 3.3 Equipment listed in Tables 2.6.8-1 and 2.6.8-2 perform the functions listed in Tables 2.6.8-1 and 2.6.8-2.
- 3.4 Equipment identified as Seismic Category I in Tables 2.6.8-1 and 2.6.8-2 can withstand a design basis seismic load without loss of safety function as listed in Tables 2.6.8-1 and 2.6.8-2.

4.0 Displays and Controls

- 4.1 Displays listed in Table 2.6.8-3—Containment Ventilation System Equipment I&C and Electrical Design are retrievable in the main control room (MCR) and the remote shutdown station (RSS) as listed.
- 4.2 The CBVS equipment controls that are provided in the MCR and RSS are as listed in Table 2.6.8-3.
- 4.3 Actuators listed as being controlled by a priority actuator control system (PACS) module in Table 2.6.8-3 are controlled by a PACS module.

5.0 Electrical Power Design Features

- 5.1 The equipment designated as Class 1E in Table 2.6.8-3 are powered from the Class 1E division as listed in Table 2.6.8-3 in a normal feed condition.
- 5.2 Motor operated dampers listed in Table 2.6.8-3 fail to the position as shown in Table 2.6.8-3 on loss of power.

6.0 Environmental Qualifications

- 6.1 Electrical drivers for equipment listed in Table 2.6.8-3 for harsh environment can perform the safety function in Tables 2.6.8-1 and 2.6.8-2 following exposure to the design basis environments for the time required.

7.0 Equipment and System Performance

- 7.1 The CBVS maintains a negative pressure in the Containment Building relative to the environment when the CBVS low flow purge subsystem is operating.

8.0 Inspections, Tests, Analyses and Acceptance Criteria (ITAAC)

The inspections, tests, analyses, and acceptance criteria (ITAAC) for the CBVS are specified in Table 2.6.8-4—Containment Ventilation System ITAAC.

Table 2.6.8-1—Containment Building Ventilation System Containment Isolation Valves Mechanical Design

Equipment Description	Equipment Tag Number⁽¹⁾	Equipment Location	ASME Code Section III	Function	Seismic Category
Containment Isolation Valve	30KLA10AA001	Fuel Building	Yes	Close	I
Containment Isolation Valve	30KLA10AA003	Reactor Building	Yes	Close	I
Containment Isolation Valve	30KLA30AA002	Fuel Building	Yes	Close	I
Containment Isolation Valve	30KLA30AA003	Reactor Building	Yes	Close	I
Containment Isolation Valve	30KLA20AA003	Fuel Building	Yes	Close	I
Containment Isolation Valve	30KLA20AA001	Reactor Building	Yes	Close	I
Containment Isolation Valve	30KLA40AA002	Fuel Building	Yes	Close	I
Containment Isolation Valve	30KLA40AA001	Reactor Building	Yes	Close	I

1) Equipment tag numbers are provided for information only and are not part of the certified design.

Table 2.6.8-2—Containment Building Ventilation System Equipment Mechanical Design (2 Sheets)

Equipment Description	Equipment Tag Number ⁽¹⁾	Equipment Location	ASME AG-1 Code	Function	Seismic Category
<u>Reactor Pit Cooling Fans</u>					
Reactor Pit Cooling Fan	30KLA65AN001	Reactor Building	Yes	Run	I
Reactor Pit Cooling Fan	30KLA66AN001	Reactor Building	Yes	Run	I
Reactor Pit Cooling Fan	30KLA65AN002	Reactor Building	Yes	Run	I
Reactor Pit Cooling Fan	30KLA66AN002	Reactor Building	Yes	Run	I
<u>Low Flow Purge Exhaust</u>					
Motor operated dampers	30KLA21AA004 30KLA22AA004	Fuel Building	Yes	Open	I
Electric Heaters	30KLA21AH005 30KLA22AH005	Fuel Building	Yes	On	I
Prefilters	30KLA21AT001 30KLA22AT001	Fuel Building	Yes	N/A	I
Upstream HEPA filters	30KLA21AT002 30KLA22AT002	Fuel Building	Yes	N/A	I
Carbon Adsorbers	30KLA21AT003 30KLA22AT003	Fuel Building	Yes	N/A	I
Downstream HEPA filters	30KLA21AT004 30KLA22AT004	Fuel Building	Yes	N/A	I
Motor operated dampers	30KLA21AA007 30KLA22AA007	Fuel Building	Yes	Open	I
Exhaust Fans	30KLA21AN001 30KLA22AN001	Fuel Building	Yes	Run	I
Backdraft Dampers	30KLA21AA003	Fuel Building	Yes	N/A	I

Table 2.6.8-2—Containment Building Ventilation System Equipment Mechanical Design (2 Sheets)

Equipment Description	Equipment Tag Number ⁽¹⁾	Equipment Location	ASME AG-1 Code	Function	Seismic Category
	30KLA22AA003				
Motor operated dampers	30KLA21AA001 30KLA22AA001	Fuel Building	Yes	Close	I
<u>Internal Filtration Train</u>					
Motor operated damper	30KLA50-AA002	Reactor Building	Yes	Open	I
Electric Heater	30KLA50-AH001	Reactor Building	Yes	On	I
Prefilter	30KLA50-AT001	Reactor Building	Yes	N/A	I
Upstream HEPA filters	30KLA50-AT002	Reactor Building	Yes	N/A	I
Carbon Adsorber	30KLA50-AT003	Reactor Building	Yes	N/A	I
Downstream HEPA filters	30KLA50-AT004	Reactor Building	Yes	N/A	I
Motor operated damper	30KLA50-AA004	Reactor Building	Yes	Open	I
Manual dampers	30KLA51AA006 30KLA52AA006	Reactor Building	Yes	Open	I
Recirculation Fans	30KLA51AN001 30KLA52AN001	Reactor Building	Yes	Run	I
Backdraft Dampers	30KLA51AA007 30KLA52AA007	Reactor Building	Yes	N/A	I

1) Equipment tag numbers are provided for information only and are not part of the certified design.

**Table 2.6.8-3—Containment Building Ventilation System Equipment I&C and Electrical Design
(2 Sheets)**

Equipment Description	Equipment Tag Number ⁽¹⁾	Equipment Location	IEEE Class 1E Source	Failure Position	EQ – Harsh Env.	PACS	MCR / RSS Displays	MCR / RSS Controls
Reactor Pit Cooling Fan	30KLA65AN001	Reactor Building	Division 1	N/A	Yes	Yes	On-Off / On-Off	Run-Stop / Run-Stop
Reactor Pit Cooling Fan	30KLA66AN001	Reactor Building	Division 4	N/A	Yes	Yes	On-Off / On-Off	Run-Stop / Run-Stop
Reactor Pit Cooling Fan	30KLA65AN002	Reactor Building	Division 1	N/A	Yes	Yes	On-Off / On-Off	Run-Stop / Run-Stop
Reactor Pit Cooling Fan	30KLA66AN002	Reactor Building	Division 4	N/A	Yes	Yes	On-Off / On-Off	Run-Stop / Run-Stop
Low Flow Purge Exhaust								
Motor operated damper	30KLA21AA004	Fuel Building	Division 1	Close	Yes	Yes	Position / Position	Open-Close / Open-Close
Motor operated damper	30KLA22AA004	Fuel Building	Division 4	Close	Yes	Yes	Position / Position	Open-Close / Open-Close
Electric Heater	30KLA21AH005	Fuel Building	Division 1	N/A	Yes	Yes	On-Off / On-Off	Start-Stop / Start-Stop
Electric Heater	30KLA22AH005	Fuel Building	Division 4	N/A	Yes	Yes	On-Off / On-Off	Start-Stop / Start-Stop
Motor operated damper	30KLA21AA007	Fuel Building	Division 1	Close	Yes	Yes	Position / Position	Open-Close / Open-Close
Motor operated	30KLA22AA007	Fuel Building	Division 4	Close	Yes	Yes	Position /	Open-Close /

**Table 2.6.8-3—Containment Building Ventilation System Equipment I&C and Electrical Design
(2 Sheets)**

Equipment Description	Equipment Tag Number ⁽¹⁾	Equipment Location	IEEE Class 1E Source	Failure Position	EQ – Harsh Env.	PACS	MCR / RSS Displays	MCR / RSS Controls
damper							Position	Open-Close
Motor operated dampers	30KLA21AA001	Fuel Building	Division 1	Close	Yes	Yes	Position / Position	Open-Close / Open-Close
Motor operated dampers	30KLA22AA001	Fuel Building	Division 4	Close	Yes	Yes	Position / Position	Open-Close / Open-Close
Motor operated damper	30KLA50AA002	Reactor Building	N/A	Close	Yes	Yes	Position / Position	Open-Close / Open-Close
Electric Heater	30KLA50AH001	Reactor Building	N/A				On-Off / On-Off	Start-Stop / Start-Stop
Motor operated damper	30KLA50AA004	Reactor Building	N/A	Close	Yes	Yes	Position / Position	Open-Close / Open-Close
Recirculation Fans	30KLA51AN001	Reactor Building	N/A	N/A	Yes	Yes	On-Off / On-Off	Run-Stop / Run-Stop
Recirculation Fans	30KLA52AN001	Reactor Building	N/A	N/A	Yes	Yes	On-Off / On-Off	Run-Stop / Run-Stop

1) Equipment tag numbers are provided for information only and are not part of the certified design.

**Table 2.6.8-4—Containment Building Ventilation System ITAAC
(3 Sheets)**

Reference Section Number	Commitment Wording	Inspection, Analysis or Test	Acceptance Criteria
2.1	The functional arrangement of the CBVS is as shown on Figure 2.6.8-1.	Inspections of the as-built system will be conducted.	The as-built CBVS conforms to the functional arrangement as shown in Figure 2.6.8-1.
2.2	Equipment shown on Figures 2.6.8-1, 2.6.8-2 and 2.6.8-3 is located as listed in Tables 2.6.8-1 and 2.6.8-2.	An inspection will be performed of the location of the equipment listed in Tables 2.6.8-1 and 2.6.8-2.	The equipment listed in Tables 2.6.8-1 and 2.6.8-2 is located as listed in Tables 2.6.8-1 and 2.6.8-2.
3.1	The CBVS equipment listed as ASME Code Section III in Table 2.6.8-1 has been designed, inspected, and tested per ASME Code Section III.	Analyses will be performed and inspections will be conducted of the as-built components listed in Table 2.6.8-1.	The CBVS equipment listed in Table 2.6.8-1 has been designed, inspected, and tested in accordance with ASME Code Section III.
3.2	The CBVS equipment listed as ASME AG-1 Code in Table 2.6.8-2 has been designed, inspected, and tested in accordance with ASME AG-1.	Analyses will be performed and inspections will be conducted of the as-built components listed in Table 2.6.8-2.	The CBVS equipment identified in Table 2.6.8-2 has been designed, inspected, and tested in accordance with ASME AG-1.
3.3	Equipment listed in Tables 2.6.8-1 and 2.6.8-2 can perform the function listed in Tables 2.6.8-1 and 2.6.8-2 under system design basis conditions.	Tests and analyses or a combination of tests and analyses will be performed.	The as-installed equipment change position as listed in Tables 2.6.8-1 and 2.6.8-2 under design basis conditions.
3.4	Equipment identified as Seismic Category I in Tables 2.6.8-1 and 2.6.8-2 can withstand a design basis seismic load without loss of	a) Inspections will be performed of the equipment identified as Seismic Category I in Tables 2.6.8-1 and 2.6.8-2.	a) The equipment designated as Seismic Category I in Tables 2.6.8-1 and 2.6.8-2 is installed as designed.

**Table 2.6.8-4—Containment Building Ventilation System ITAAC
(3 Sheets)**

Reference Section Number	Commitment Wording	Inspection, Analysis or Test	Acceptance Criteria
	safety function as listed in Tables 2.6.8-1 and 2.6.8-2.	b) Type tests, tests, analyses or a combination of tests and analyses will be performed on the equipment designated as Seismic Category I in Tables 2.6.8-1 and 2.6.8-2.	b) The equipment designated as Seismic Category I in Tables 2.6.8-1 and 2.6.8-2 can withstand a design basis seismic load without loss of safety function.
4.1	Displays listed in Table 2.6.8-3 are retrievable in the MCR and RSS as listed.	Inspections will be performed for the existence or retrieve-ability of the displays in the MCR and the RSS as listed in Table 2.6.8-3.	a) The displays listed in Table 2.6.8-3 as being retrieved in the MCR can be retrieved in the MCR. b) The displays listed in Table 2.6.8-3 as being retrieved in the RSS can be retrieved in the RSS.
4.2	Controls exist in the MCR and the RSS as identified in Table 2.6.8-3.	Test will be performed for the existence of control signals from the MCR and the RSS to the equipment listed in Table 2.6.8-3.	a) The controls listed in Table 2.6.8-3 as being in the MCR exist in the MCR. b) The controls listed in Table 2.6.8-3 as being in the RSS exist in the RSS.
5.1	The components designated as Class 1E in Table 2.6.8-3 are powered from the Class 1E division as listed in Table 2.6.8-3 in a normal feed condition.	Testing will be performed for the components designated as Class 1E in Table 2.6.8-3 by providing a test signal in each normally aligned division.	The test signal provided in the normally aligned division is present at the respective Class 1E component identified in Table 2.6.8-3.
5.2	Motor operated dampers listed in Table 2.6.8-3 will fail to the position as shown in Table 2.6.8-3 on loss of power.	Testing will be performed for the motor operated dampers listed in Table 2.6.8-3 to verify the position of dampers on loss of power.	Following loss of power, the motor operated dampers listed in Table 2.6.8-3 fail to the position as shown in Table 2.6.8-3.
6.1	Electrical drivers for equipment listed in Table 2.6.8-3 for harsh environment can perform the safety function in Tables 2.6.8-1	a) Type tests, tests, analyses or a combination of tests and analyses will be performed to demonstrate the ability of	a) The Class 1E equipment listed for harsh environment in Table 2.6.8-3 can perform the function listed in Tables

**Table 2.6.8-4—Containment Building Ventilation System ITAAC
(3 Sheets)**

Reference Section Number	Commitment Wording	Inspection, Analysis or Test	Acceptance Criteria
	and 2.6.8-2 following exposure to the design basis environments for the time required.	<p>the equipment listed for harsh environment in Table 2.6.8-3 to perform the function listed in Tables 2.6.8-1 and 2.6.8-2 for the environmental conditions that could occur before and during a design basis accident.</p> <p>b) For equipment listed for harsh environment in Table 2.6.8-3, an inspection will be performed of the as-installed Class 1E equipment and the associated wiring, cables and terminations.</p>	<p>2.6.8-1 and 2.6.8-2 before and during design basis accidents for the time required to perform the listed function.</p> <p>b) Inspection concludes that the as-installed Class 1E equipment and associated wiring, cables, and terminations as listed in Table 2.6.8-3 for harsh environment conform with the design.</p>
7.1	The CBVS maintains a negative pressure in the Containment Building relative to the environment when the CBVS low flow purge subsystem is operating.	Tests will be performed on the capability of the system to maintain a negative pressure in the Containment Building relative to the environment.	The CBVS maintains a negative pressure in the Containment Building relative to the environment when the CBVS low flow purge subsystem is operating.