

3.7 PLANT SYSTEMS

3.7.4 Control Center Air Conditioning (AC) System

LCO 3.7.4 Two control center AC subsystems shall be OPERABLE.

APPLICABILITY: MODES 1, 2, and 3.
During movement of recently irradiated fuel assemblies in the secondary containment.

During operations with a potential for draining the reactor vessel (OPDRVs).

ACTIONS

CONDITION	REQUIRED ACTION	COMPLETION TIME
A. One control center AC subsystem inoperable.	A.1 Restore control center AC subsystem to OPERABLE status.	30 days
B. Two control center AC subsystems inoperable.	B.1 Verify control room area temperature <90°F.	Once per 4 hours
	<u>AND</u> B.2 Restore one control center AC subsystem to OPERABLE status.	72 hours
C. Required Action and associated Completion Time of Condition A or B not met in MODE 1, 2, or 3.	C.1 Be in MODE 3.	12 hours
	<u>AND</u> C.2 Be in MODE 4.	36 hours

ACTIONS (continued)

CONDITION	REQUIRED ACTION	COMPLETION TIME
<p>D. Required Action and associated Completion Time of Condition A not met during movement of recently irradiated fuel assemblies in the secondary containment or during OPDRVs.</p>	<p>-----NOTE----- LCO 3.0.3 is not applicable -----</p>	
	<p>D.1 Place OPERABLE control center AC subsystem in operation.</p>	<p>Immediately</p>
	<p><u>OR</u></p> <p>D.2.1 Suspend movement of recently irradiated fuel assemblies in the secondary containment.</p>	<p>Immediately</p>
	<p><u>AND</u></p> <p>D.2.2 Initiate action to suspend OPDRVs.</p>	<p>Immediately</p>

(continued)

