



DETAIL 3
TYPICAL COVER SYSTEM, TOP OF CELL




DETAIL 2
TYPICAL COVER SYSTEM, CELL SIDE SLOPES




DETAIL 1
TYPICAL DISPOSAL CELL LINER SYSTEM

NOTES:


1. ROCK MULCH - Angular sandy gravel and cobbles with median particle size of 3.7 inches on south and east slopes, 3.0 inches on north and west slopes, and layer thickness of 9 inches.
2. PERIMETER APRON ROCK - Angular gravel and cobbles with median particle size of 7.5 inches and layer thickness of 24 inches.
3. EROSION PROTECTION FILTER - Gravel and sand with maximum particle size of 3.0 inches.
4. TOPSOIL - Approved material obtained from within facility boundary.
5. SOIL COVER - Gravelly clay to silty clay obtained from within facility boundary.
6. RANDOM FILL - Clean sandy gravel used for subgrade fill, with top surface rolled with vibratory roller or compactor.
7. DISPOSED MATERIALS - Materials from site cleanup operations, placed in lifts to minimize void spaces and rolled (where necessary) with vibratory roller or compactor.
8. BASE SYNTHETIC LINER - 60-mil nominal thickness HDPE, smooth surface on both sides, seamed and tested to form continuous liner.
9. SUBGRADE FILL - Granular material with maximum particle size of 6 inches.
10. CLAY LINER - Silty clay compacted to 95 percent of Standard Proctor density and within 2 percent of Standard Proctor optimum moisture content. Material obtained from within facility boundary.
11. LINER BEDDING AND COVER MATERIAL - Granular material with maximum particle size of 1.0 inches. Liner cover material placed in one lift to form a layer 1.5 ft. thick.
12. UPPER SURFACE OF DISPOSED MATERIALS - The upper surface of disposed materials shall be rolled with a drum roller or rubber-tired equipment.
13. COVER SYNTHETIC LINER - 60-mil nominal thickness HDPE, textured surface on both sides, seamed and tested to form continuous liner.
14. LEACHATE COLLECTION PIPE - 6-inch diameter blank HDPE pipe. Pipe perforated within inside toe of perimeter berm.
15. LEAK DETECTION PIPE - 4-inch diameter blank HDPE pipe. Pipe perforated 20 ft. inside of perimeter berm.
16. BASE SUBGRADE SURFACE - Compacted random fill, excavated soil surface, natural soil subsurface, or clean concrete or asphalt surface, forming base for subgrade fill.
17. STORMWATER LINER - 40-mil nominal thickness HDPE (or approved equivalent), smooth surface on both sides, seamed along stormwater berm.




DETAIL 4
CELL PERIMETER BERM AND COVER SYSTEM



DETAIL 6
CELL INTERIOR BERM



DETAIL 5
CELL PERIMETER BERM AND STORMWATER RETENTION BERM




DETAIL 7
FILTERED RAFFINATE SLUDGE CELL
(CONSTRUCTED ONLY IF FILTERED SLUDGE IS DISPOSED ON SITE)

No.	DESCRIPTION	BY	CHKD.	APPROVED	DATE
A	ISSUED FOR PERMITTING	CLS			12/02
B	UPDATED LINER SYSTEM	CLS			8/03
C	DISPOSAL CELL CONSTRUCTION PLAN	CLS			2/04
D	MODIFIED FROM SETTLEMENT AGREEMENT	CLS			3/05
E	MODIFIED FROM NRC REVIEW	CLS			1/06
F	MODIFIED FROM NRC REVIEW FOR EROSION PROTECTION	CLS			1/07
G	MODIFIED FROM NRC REVIEW FOR EROSION PROTECTION	RTS			12/07

REVISIONS	DWG No.	DRAWING TITLE

DESIGNERS	ENGINEERING RECORD	BY	DATE
	PRELIMINARY DESIGN	CLS	12/02
	CELL OPERATIONS	DAS	2/04
	ODEQ MODIFICATIONS	CLS	9/04
	NRC REVIEW	RTS	1/07

PREPARED BY



consulting
scientists and
engineers

Fort Collins, CO
970 223-9600

PREPARED FOR



SEQUOYAH FUELS
A GENERAL ATOMICS COMPANY

TITLE

DISPOSAL CELL DETAILS

D-03

PROJECT: 100734	DATE: DECEMBER 2007	DRAWING REVISION
SCALE: AS SHOWN	ACAD FILE: STIE-11-REV-G	11