

3.7 PLANT SYSTEMS

3.7.4 Control Room Emergency Ventilation (CREV) System

LC0 3.7.4 The CREV System shall be OPERABLE.

-----NOTE-----
The main control room envelope (CRE)
boundary may be opened intermittently
under administrative control.

APPLICABILITY: MODES 1, 2, and 3,
During movement of recently irradiated fuel assemblies in
the secondary containment,
During operations with a potential for draining the reactor
vessel (OPDRVs).

ACTIONS

CONDITION	REQUIRED ACTION	COMPLETION TIME
A. CREV System inoperable in MODE 1, 2, or 3 for reasons other than Condition B.	A.1 Restore CREV System to OPERABLE status.	7 days
B. CREV system inoperable due to inoperable CRE boundary in MODE 1, 2, or 3.	B.1 Initiate action to implement mitigating actions.	Immediately
	<u>AND</u> B.2 Verify mitigating actions ensure CRE occupant exposures to radiological, chemical, and smoke hazards will not exceed limits.	24 hours
	<u>AND</u> B.3 Restore CRE boundary to OPERABLE status.	90 days

(continued)

ACTIONS (continued)

C. Required Action and associated Completion Time of Condition A or B not met in MODE 1, 2, or 3.	C.1 Be in MODE 3. <u>AND</u> C.2 Be in MODE 4.	12 hours 36 hours
D. CREV System inoperable during movement of recently irradiated fuel assemblies in the secondary containment or during OPDRVs. <u>OR</u> CREV System inoperable due to an inoperable CRE boundary during movement of recently irradiated fuel assemblies in the secondary containment or during OPDRVs.	-----NOTE----- LC0 3.0.3 is not applicable. ----- D.1 Suspend movement of recently irradiated fuel assemblies in the secondary containment. <u>AND</u> D.2 Initiate action to suspend OPDRVs.	Immediately Immediately

SURVEILLANCE REQUIREMENTS

SURVEILLANCE		FREQUENCY
SR 3.7.4.1	Operate the CREV System for ≥ 10 continuous hours with the heaters operating.	31 days
SR 3.7.4.2	Perform required CREV filter testing in accordance with the Ventilation Filter Testing Program (VFTP).	In accordance with the VFTP
SR 3.7.4.3	Verify the CREV System actuates on a manual initiation signal.	24 months
SR 3.7.4.4	Perform required CRE unfiltered air inleakage testing in accordance with the Control Room Envelope Habitability Program.	In accordance with the Control Room Envelope Habitability Program