

CONTAINMENT SYSTEMS

SURVEILLANCE REQUIREMENTS (Continued)

- b. By verifying the developed head of each containment spray pump at the flow test point is greater than or equal to the required developed head when tested pursuant to Specification 4.0.5.
- c. At least once per 18 months by verifying each automatic containment spray valve in the flow path that is not locked, sealed, or otherwise secured in position, actuates to the correct position on an actual or simulated actuation signal.
- d. At least once per 18 months by verifying each containment spray pump starts automatically on an actual or simulated actuation signal.
- e. By verifying each spray nozzle is unobstructed following activities that could cause nozzle blockage.

4.6.2.1.2 Each containment air recirculation and cooling unit shall be demonstrated OPERABLE:

- a. At least once per 31 days by operating each containment air recirculation and cooling unit in slow speed for ≥ 15 minutes.
- b. At least once per 31 days by verifying each containment air recirculation and cooling unit cooling water flow rate is ≥ 500 gpm.
- c. At least once per 18 months by verifying each containment air recirculation and cooling unit starts automatically on an actual or simulated actuation signal.