

## GENERAL INFORMATION CONTENTS

1. GENERAL DESCRIPTION
  - 1.1 Location and Arrangement of Structures, Systems, and Components of the Geologic Repository Operations Area
    - 1.1.1 Physical Characteristics of Repository Site and Environs
      - 1.1.1.1 Site Location and Geography
      - 1.1.1.2 Site Geology and Hydrology
      - 1.1.1.3 Meteorology and Climatology
    - 1.1.2 Surface Facilities
      - 1.1.2.1 Major Surface Design Features
      - 1.1.2.2 Surface Facilities to Be Dismantled Prior to Decommissioning and Closure
    - 1.1.3 Subsurface Facilities
      - 1.1.3.1 Major Subsurface Design Features
      - 1.1.3.2 Subsurface Facilities to Be Dismantled prior to Closure
    - 1.1.4 Plans to Restrict Access to and Regulate Land Uses around the Geologic Repository Operations Area
    - 1.1.5 Radiological Monitoring and Plans for Mitigation of Radiological Impacts Associated with Construction and Operations
      - 1.1.5.1 Radiological Monitoring
      - 1.1.5.2 Plans for Mitigation of Radiological Emergency Events
  - 1.2 General Nature of the Geologic Repository Operations Area Activities
    - 1.2.1 Waste Forms to Be Disposed
    - 1.2.2 Routine Operations
    - 1.2.3 Inspection and Testing of Waste Forms and Waste Packages
    - 1.2.4 Waste Retrieval Requirements
    - 1.2.5 Repository Closure
    - 1.2.6 Uses of the Geologic Repository Operations Area for Purposes Other than Disposal of High-Level Radioactive Waste
    - 1.2.7 Plans for Emergency Responses
  - 1.3 Basis for U.S. Nuclear Regulatory Commission Exercise of its Licensing Authority
  - 1.4 GENERAL REFERENCES AND MATERIALS INCORPORATED BY REFERENCE
    - 1.4.1 General References
    - 1.4.2 Materials Incorporated by Reference
  - 1.5 GENERAL REFERENCES
2. PROPOSED SCHEDULES FOR CONSTRUCTION, RECEIPT, AND EMPLACEMENT OF WASTE
  - 2.1 Phased Construction Schedule
    - 2.1.1 Initial Operating Capability
      - 2.1.1.1 Infrastructure
      - 2.1.1.2 Initial Handling Facility
      - 2.1.1.3 Canister Receipt and Closure Facility 1, Panel 1, Initial Aging

---

**CONTENTS (Continued)**

- 2.1.1.4 Wet Handling Facility
      - 2.1.1.5 Additional Facilities Supporting Initial Operation
    - 2.1.2 Full Operating Capability
      - 2.1.2.1 Receipt Facility
      - 2.1.2.2 Canister Receipt and Closure Facilities 2 and 3, Additional Aging
    - 2.2 Schedule for Waste Receipt and Emplacement
    - 2.3 GENERAL REFERENCES
  - 3. PHYSICAL PROTECTION PLAN
    - 3.1 Description and Schedule for Implementation
    - 3.2 General Performance Objectives
    - 3.3 Protection Goal and Strategy
    - 3.4 Security Organization
    - 3.5 Physical Barrier Subsystems
    - 3.6 Access Control Subsystems and Procedures
    - 3.7 Detection, Surveillance, Alarm Subsystems, and Procedures
    - 3.8 Communication Subsystem
    - 3.9 Equipment Operability and Compensatory Measures
    - 3.10 Safeguards Contingency Plan
    - 3.11 Reporting of Safeguards Events
    - 3.12 Records Retention
    - 3.13 GENERAL REFERENCES
  - 4. MATERIAL CONTROL AND ACCOUNTING PROGRAM
    - 4.1 Material Balance, Inventory, and Record-Keeping Procedures
      - 4.1.1 Program Provisions and Requirements
      - 4.1.2 Item Accounting and Physical Inventories
      - 4.1.3 Quality of Physical Inventories
      - 4.1.4 Periodic Program Assessment
      - 4.1.5 Procedures
      - 4.1.6 Collusion Protection Program
      - 4.1.7 Records
    - 4.2 Reports of Accidental Criticality or Loss of Special Nuclear Material
    - 4.3 Material Status Reports
    - 4.4 Nuclear Material Transfer Reports
    - 4.5 GENERAL REFERENCES
  - 5. SITE CHARACTERIZATION
    - 5.1 Site Characterization Activities
      - 5.1.1 Site Studies Prior to Development of the Site Characterization Plan
      - 5.1.2 Performance Allocation
      - 5.1.3 Overview of the Site Characterization Plan
-

**CONTENTS (Continued)**

- 5.1.4 Role of the Semiannual Site Characterization Progress Reports
- 5.1.5 Description of Pre-Site Characterization and Site Characterization Activities that Resulted in Site Recommendation
  - 5.1.5.1 Geology
  - 5.1.5.2 Hydrology
  - 5.1.5.3 Thermal Testing and Near Field Geochemical Characteristics
  - 5.1.5.4 Geotechnical Properties
  - 5.1.5.5 Meteorology and Climatology
  - 5.1.5.6 Reference Biosphere
- 5.1.6 Testing and Monitoring Activities Conducted After the Conclusion of Site Characterization
  - 5.1.6.1 Geology
  - 5.1.6.2 Hydrology
  - 5.1.6.3 Thermal Testing and Near Field Geochemical Characteristics
  - 5.1.6.4 Geotechnical Properties
  - 5.1.6.5 Meteorology and Climatology
  - 5.1.6.6 Air Mass Loading
- 5.2 Summary of Site Characterization Results
  - 5.2.1 Overview of the Geology of the Yucca Mountain Site
    - 5.2.1.1 Physical Setting of the Repository Site
    - 5.2.1.2 Stratigraphy
    - 5.2.1.3 Structural Framework
      - 5.2.1.3.1 Faults
      - 5.2.1.3.2 Fractures
    - 5.2.1.4 Geotechnical Properties of Stratigraphic Units
    - 5.2.1.5 Tectonic Setting
      - 5.2.1.5.1 Geomorphic Processes and Erosion Rates
      - 5.2.1.5.2 Seismicity and Seismic Hazard
        - 5.2.1.5.2.1 Probabilistic Seismic Hazard Analysis Process
        - 5.2.1.5.2.2 Probabilistic Seismic Hazard Analysis Results
      - 5.2.1.5.3 Volcanism and Volcanic Hazard
        - 5.2.1.5.3.1 Location of Basaltic Volcanism in the Yucca Mountain Region
        - 5.2.1.5.3.2 Probabilistic Volcanic Hazard Analysis Process
        - 5.2.1.5.3.3 Probabilistic Volcanic Hazard Analysis Results
    - 5.2.1.6 Geologic FEPs Used to Estimate Postclosure Performance
    - 5.2.1.7 Potential Geologic Hazards during the Preclosure Phase
    - 5.2.1.8 Developments in Geologic Data and Models During Site Characterization

---

**CONTENTS (Continued)**

- 5.2.2 Overview of the Hydrology of the Yucca Mountain Site
  - 5.2.2.1 Hydrogeologic Features of the Yucca Mountain Site
  - 5.2.2.2 Summary of Regional Groundwater Flow System
    - 5.2.2.2.1 Regional Framework
    - 5.2.2.2.2 Regional Hydrogeology
  - 5.2.2.3 Site Hydrology and Conceptual Models
    - 5.2.2.3.1 Unsaturated Zone Hydrostratigraphy and Hydrology
      - 5.2.2.3.1.1 Unsaturated Zone Conceptual Model
    - 5.2.2.3.2 Saturated Zone Hydrostratigraphy and Hydrology
      - 5.2.2.3.2.1 Saturated Zone Conceptual Model
  - 5.2.2.4 Present Climate and Controlling Influences
  - 5.2.2.5 Water Quality and Water Use
  - 5.2.2.6 Water Budget
  - 5.2.2.7 Surface Water Hydrology
  - 5.2.2.8 Hydrologic Features and Processes Used to Estimate Postclosure Performance
  - 5.2.2.9 Potential Hydrologic Hazards during the Preclosure Phase
  - 5.2.2.10 Developments in Hydrologic Data and Models during Site Characterization
- 5.2.3 Geochemical Characteristics of the Yucca Mountain Site
  - 5.2.3.1 Hydrochemistry of Unsaturated and Saturated Zones
  - 5.2.3.2 Radionuclide Transport in the Unsaturated and Saturated Zones
    - 5.2.3.2.1 Solubilities of Key Radionuclides
    - 5.2.3.2.2 Radionuclide Sorption in the Saturated and Unsaturated Zones
  - 5.2.3.3 Colloid-Facilitated Transport
  - 5.2.3.4 Near-Field and In-Drift Chemistry and Hydrology
    - 5.2.3.4.1 Coupled Processes in the Near-Field Environment
    - 5.2.3.4.2 Thermal-Hydrologic-Chemical Processes
    - 5.2.3.4.3 Thermal Hydrology in Repository Host Rock
    - 5.2.3.4.4 In-Drift Chemistry
  - 5.2.3.5 Geochemical Processes and Features Used to Estimate Postclosure Performance
  - 5.2.3.6 Developments in Geochemical Data and Models During Site Characterization
- 5.2.4 Overview of Geotechnical Properties of the Yucca Mountain Site
  - 5.2.4.1 Geotechnical Investigations
  - 5.2.4.2 Engineering Properties of Soil and Rock
    - 5.2.4.2.1 Soil Material Properties for Surface Facilities
    - 5.2.4.2.2 Rock Material Properties for Subsurface Facilities

**CONTENTS (Continued)**

- 5.2.4.3 Geotechnical Features and Processes Used to Estimate Postclosure Performance
  - 5.2.4.4 Geotechnical Data from Exploratory Excavations
  - 5.2.5 Overview of the Meteorology and Climatology of the Yucca Mountain Site
    - 5.2.5.1 Present Climate and Controlling Influences
    - 5.2.5.2 Description of Local and Regional Meteorological Program Results
      - 5.2.5.2.1 Local and Regional Precipitation Characteristics
      - 5.2.5.2.2 Local Temperature Ranges and Extremes
      - 5.2.5.2.3 Humidity and Evaporation
      - 5.2.5.2.4 Lightning Characteristics and Frequency
      - 5.2.5.2.5 Local Wind Characteristics, Including Tornadoes
      - 5.2.5.2.6 Atmospheric Stability
    - 5.2.5.3 Paleoclimatology
      - 5.2.5.3.1 Sequence and Nature of Past Climates
        - 5.2.5.3.1.1 Evidence for Chronology of Climatic Sequences: Devils Hole
        - 5.2.5.3.1.2 Additional Evidence for Climatic Sequences and Evidence for Past Climates: Owens Lake Basin
      - 5.2.5.4 Forecast Timing and Sequence of Future Climates for Use in the TSPA
      - 5.2.5.5 Paleoclimatology and Climate-Related Processes Used to Estimate Postclosure Performance
      - 5.2.5.6 Developments in Meteorology and Climate Data and Models during Site Characterization
  - 5.2.6 Overview of Reference Biosphere and the RMEI
    - 5.2.6.1 Location and Lifestyle of the RMEI
    - 5.2.6.2 Summary of Biosphere Pathways
    - 5.2.6.3 Summary of Biosphere Dose Conversion Factors
    - 5.2.6.4 Biosphere FEPs Used to Estimate Postclosure Performance
    - 5.2.6.5 Developments in Biosphere Data and Models during Site Characterization
- 5.3 GENERAL REFERENCES

## **SAFETY ANALYSIS REPORT CONTENTS**

### **1. REPOSITORY SAFETY BEFORE PERMANENT CLOSURE**

#### **1.1 SITE DESCRIPTION AS IT PERTAINS TO PRECLOSURE SAFETY ANALYSIS**

##### **1.1.1 Site Geography**

###### **1.1.1.1 Repository Boundaries**

- 1.1.1.1.1 Site
- 1.1.1.1.2 Controlled Area
- 1.1.1.1.3 General Environment
- 1.1.1.1.4 Geologic Repository Operations Area
- 1.1.1.1.5 Control Points

###### **1.1.1.2 Natural Features**

###### **1.1.1.3 Man-Made Features**

###### **1.1.1.3.1 Nevada Test Site**

- 1.1.1.3.1.1 Defense Program
- 1.1.1.3.1.2 Waste Management Program
- 1.1.1.3.1.3 Environmental Restoration Program
- 1.1.1.3.1.4 Nondefense Research and Development Program
- 1.1.1.3.1.5 Work for Others Program
- 1.1.1.3.1.6 Miscellaneous New Missions and Facilities
- 1.1.1.3.1.7 Missile Launches

###### **1.1.1.3.2 Airspace and Related Facilities and Activities**

- 1.1.1.3.2.1 Nevada Test Site Airspace
- 1.1.1.3.2.2 Nevada Test and Training Range
- 1.1.1.3.2.3 Military Training Routes and Areas
- 1.1.1.3.2.4 R-2508 Complex
- 1.1.1.3.2.5 R-2508 Complex Peripheral Areas
- 1.1.1.3.2.6 Low- and High-Altitude Routes and Area Navigation Routes

###### **1.1.1.3.3 Military, Federal, and Civilian Airports and Airfields**

- 1.1.1.3.3.1 Military Airports and Airfields
- 1.1.1.3.3.2 Federal Airports and Airfields
- 1.1.1.3.3.3 Civilian Airports and Airfields

###### **1.1.1.3.4 Roads**

###### **1.1.1.3.5 Railroads**

###### **1.1.1.3.6 Potentially Hazardous Commercial Operations and Manufacturing Centers**

- 1.1.1.3.6.1 Commercial Rocket Launch and Retrieval
- 1.1.1.3.6.2 Bureau of Land Management Activities
- 1.1.1.3.6.3 Mining Activities

###### **1.1.1.3.7 Transmission Lines**

##### **1.1.2 Regional Demography**

**CONTENTS (Continued)**

- 1.1.2.1 Demographic Study Area
- 1.1.2.2 Population Centers
- 1.1.2.3 Population Projections
- 1.1.3 Local Meteorology and Regional Climatology
  - 1.1.3.1 Meteorological Monitoring
    - 1.1.3.1.1 General Site Exposure and Monitoring Stations
    - 1.1.3.1.2 Local Instrument Exposure
    - 1.1.3.1.3 Meteorological Sensors
    - 1.1.3.1.4 Onsite Data Recording
    - 1.1.3.1.5 Instrument Surveillance
    - 1.1.3.1.6 Data Acquisition and Reduction
  - 1.1.3.2 Data Summary
    - 1.1.3.2.1 Precipitation
    - 1.1.3.2.2 Wind Speed
    - 1.1.3.2.3 Temperature
    - 1.1.3.2.4 Atmospheric Humidity
    - 1.1.3.2.5 Solar Radiation
    - 1.1.3.2.6 Barometric Pressure
  - 1.1.3.3 Atmospheric Dispersion Characteristics
  - 1.1.3.4 Atmospheric Stability
  - 1.1.3.5 Meteorological Summary
  - 1.1.3.6 Severe Weather Characteristics
    - 1.1.3.6.1 Tornadoes
    - 1.1.3.6.2 Thunderstorms and Lightning Strikes
    - 1.1.3.6.3 Sandstorms
    - 1.1.3.6.4 Snowfall
- 1.1.4 Regional and Local Surface and Groundwater Hydrology
  - 1.1.4.1 Surface Water Hydrology
    - 1.1.4.1.1 Regional Surface Water Hydrology
    - 1.1.4.1.2 Local Surface Water Hydrology
      - 1.1.4.1.2.1 Flooding Potential
      - 1.1.4.1.2.2 Potential Water and Debris Flows from Slopes above the North Portal
  - 1.1.4.2 Groundwater Hydrology
    - 1.1.4.2.1 Regional Groundwater Flow System
    - 1.1.4.2.2 Water Use in the Region
    - 1.1.4.2.3 Local Groundwater Hydrology
  - 1.1.4.3 Hydrologic Engineering Studies for Surface Facilities
    - 1.1.4.3.1 Probable Maximum Precipitation Determination

---

**CONTENTS (Continued)**

- 1.1.4.3.2 Probable Maximum Flood Flow Characteristics
- 1.1.5 Site Geology and Seismology
  - 1.1.5.1 Site Geology
    - 1.1.5.1.1 Site Stratigraphy
    - 1.1.5.1.2 Site Structural Geology
      - 1.1.5.1.2.1 Extension
      - 1.1.5.1.2.2 Timing of Deformation
    - 1.1.5.1.3 Fractures
      - 1.1.5.1.3.1 Fracture Characteristics of Lithostratigraphic Units of the Repository Horizon
      - 1.1.5.1.3.2 Fractures Associated with Faults
      - 1.1.5.1.3.3 Fracture Hazard Summary
    - 1.1.5.1.4 Subsurface Conditions at the Surface Geologic Repository Operations Area
  - 1.1.5.2 Site Seismology
    - 1.1.5.2.1 Historical Seismicity of the Yucca Mountain Region
      - 1.1.5.2.1.1 Characteristics of the Recorded Seismicity in the Southern Great Basin
      - 1.1.5.2.1.2 Seismicity in the Vicinity of Yucca Mountain
    - 1.1.5.2.2 Quaternary Paleoseismic Data
    - 1.1.5.2.3 Vibratory Ground Motion Information
    - 1.1.5.2.4 Probabilistic Seismic Hazard Analysis
      - 1.1.5.2.4.1 Results of the Probabilistic Seismic Hazard Analysis
    - 1.1.5.2.5 Ground Motion Input Evaluation
      - 1.1.5.2.5.1 Conditioning of Ground Motion Hazard at the Reference Rock Outcrop
      - 1.1.5.2.5.2 Site-Response Modeling
        - 1.1.5.2.5.2.1 Site Amplification Factors
        - 1.1.5.2.5.2.2 Vertical-to-Horizontal Ratios
      - 1.1.5.2.5.3 Development of Site-Specific Hazard Curves
      - 1.1.5.2.5.4 Development of Design Response Spectra
      - 1.1.5.2.5.5 Development of Design Time Histories
      - 1.1.5.2.5.6 Development of Strain-Compatible Material Properties
    - 1.1.5.2.6 Ground Motion Inputs
      - 1.1.5.2.6.1 Surface Geologic Repository Operations Area Ground Motion Inputs
      - 1.1.5.2.6.2 Repository Block Ground Motion Inputs
      - 1.1.5.2.6.3 Summary of Ground Motions
      - 1.1.5.2.6.4 Adequacy of Site-Response Model Inputs
    - 1.1.5.2.7 Seismic Design Data for Preclosure Facilities



**CONTENTS (Continued)**

- 1.1.5.2.7.1 Design Methodology for Preclosure Facilities
- 1.1.5.2.7.2 Development of Seismic Design Data
- 1.1.5.2.7.3 Depth to the Reference Rock Outcrop Conditions and Comparison of the 2004 and Current Base-Case  $V_S$  Profiles
- 1.1.5.3 Geotechnical Properties and Conditions
  - 1.1.5.3.1 Underground Facilities
    - 1.1.5.3.1.1 Subsurface Conditions
    - 1.1.5.3.1.2 Rock Properties Used in Subsurface Design Analyses
      - 1.1.5.3.1.2.1 Geotechnical Characterization of Nonlithophysal and Lithophysal Rock Masses
      - 1.1.5.3.1.2.2 Mechanical Properties of Nonlithophysal and Lithophysal Rocks
        - 1.1.5.3.1.2.2.1 Intact Rock Properties
        - 1.1.5.3.1.2.2.2 Rock Mass Strength of Nonlithophysal Rock
        - 1.1.5.3.1.2.2.3 Rock Mass Strength of Lithophysal Rocks
        - 1.1.5.3.1.2.3 Thermal Properties of the Rock Mass
        - 1.1.5.3.1.2.4 In Situ Stress Conditions
      - 1.1.5.3.1.3 Dynamic Properties
        - 1.1.5.3.1.3.1 Seismic Velocity Profiles
          - 1.1.5.3.1.3.1.1 Seismic Velocities from Spectral Analysis of Surface Wave Surveys near the Crest of Yucca Mountain
          - 1.1.5.3.1.3.1.2 Seismic Velocities from Spectral Analysis of Surface Wave Surveys in the ESF Main Drift
          - 1.1.5.3.1.3.1.3 Seismic Velocities from Downhole Seismic Surveys
          - 1.1.5.3.1.3.1.4 Seismic Velocities from Vertical Seismic Profiling Surveys
  - 1.1.5.3.2 Surface Facilities
    - 1.1.5.3.2.1 Surface Conditions
    - 1.1.5.3.2.2 Seismic Velocity Profiles
    - 1.1.5.3.2.3 Density and Relative Density
    - 1.1.5.3.2.4 Shear Strength of Alluvium
    - 1.1.5.3.2.5 Poisson's Ratio
    - 1.1.5.3.2.6 Dynamic Shear Modulus and Damping Ratio
      - 1.1.5.3.2.6.1 Test Program from 2000 and 2001 on Specimens from Boreholes at the Surface Geologic Repository Operations Area
      - 1.1.5.3.2.6.2 Test Program on ESF Specimens
        - 1.1.5.3.2.6.2.1 2004 through 2006 Resonant Column and

**CONTENTS (Continued)**

- Torsional Shear (Fixed-Free) Testing of Tuff Samples
        - 1.1.5.3.2.6.2.1.1 Dynamic Properties in the Small-Strain Range ( $\gamma < 0.001\%$ )
        - 1.1.5.3.2.6.2.1.2 Dynamic Properties in the Large-Strain Range ( $\gamma > 0.001\%$ )
        - 1.1.5.3.2.6.2.2 2004 through 2006 Free-Free Laboratory Testing of Tuff Samples
        - 1.1.5.3.2.6.3 Normalized Shear Modulus and Damping for Design
        - 1.1.5.3.2.7 Liquefaction Potential
- 1.1.6 Igneous Activity
  - 1.1.6.1 Location of Volcanism in the Yucca Mountain Region
    - 1.1.6.1.1 Characteristics of Basaltic Volcanism in the Yucca Mountain Area
    - 1.1.6.1.2 Simultaneous Seismic Activity and Volcanic Eruption
  - 1.1.6.2 Probabilistic Volcanic Hazard Analysis
  - 1.1.6.3 Potential Hazard from Ash Fall
- 1.1.7 Site Geomorphology
  - 1.1.7.1 Geomorphic Information and Tectonic Activity
    - 1.1.7.1.1 Geomorphic Information Related to Faulting
    - 1.1.7.1.2 Geomorphic Information Related to Volcanism
  - 1.1.7.2 Variability in Quaternary Processes
    - 1.1.7.2.1 Erosion and Deposition in the Present Climate
    - 1.1.7.2.2 Potential for Future Erosion and Deposition at Yucca Mountain
- 1.1.8 Geochemistry
  - 1.1.8.1 Introduction
  - 1.1.8.2 Geochemical Composition of Subsurface Waters
  - 1.1.8.3 Geochemical Conditions in the Preclosure Emplacement Drift Environment
  - 1.1.8.4 Geochemical Alteration to Host-Rock Properties Environment
    - 1.1.8.4.1 Potential Geochemical Alteration Due to Heating
    - 1.1.8.4.2 Potential Geochemical Alteration Due to Other Processes
    - 1.1.8.4.3 Summary of Effects from Preclosure Geochemical Alteration on Host-Rock Properties
- 1.1.9 Land Use, Structures and Facilities, and Residual Radioactivity
  - 1.1.9.1 Previous Land Uses within the Land Withdrawal Area
    - 1.1.9.1.1 Mining Claims
    - 1.1.9.1.2 MX Missile
    - 1.1.9.1.3 Army Ballistics Research Laboratory Test Range

**CONTENTS (Continued)**

- 1.1.9.1.4 Borehole USW G-3
- 1.1.9.1.5 Concrete Batch Plant
- 1.1.9.2 Previous Land Uses in the Vicinity of the Proposed Land Withdrawal Area
  - 1.1.9.2.1 X-Tunnel
  - 1.1.9.2.2 Nevada Test Site Nuclear Testing
- 1.1.9.3 Location and Description of Existing Man-Made Structures or Facilities
  - 1.1.9.3.1 Mining Facilities
  - 1.1.9.3.2 Yucca Mountain Facilities Within the Land Withdrawal Area
    - 1.1.9.3.2.1 North Portal Pad
    - 1.1.9.3.2.2 South Portal Pad
    - 1.1.9.3.2.3 Subdock Equipment Storage Area
    - 1.1.9.3.2.4 Rock Storage Area
    - 1.1.9.3.2.5 Topsoil Storage Area
    - 1.1.9.3.2.6 Borrow Pit
    - 1.1.9.3.2.7 Water Supply System
    - 1.1.9.3.2.8 Surface Sanitation System
    - 1.1.9.3.2.9 Waste Management Facility (Nonradioactive)
    - 1.1.9.3.2.10 Terrestrial Ecosystems Yard
    - 1.1.9.3.2.11 Heliport
    - 1.1.9.3.2.12 Lower Muck Yard
    - 1.1.9.3.2.13 Gate 510 (Guard Station 510)
    - 1.1.9.3.2.14 Communications System
- 1.1.9.4 Identification of Residual Radiation
- 1.1.10 General References
- 1.2 SURFACE FACILITY STRUCTURES, SYSTEMS, AND COMPONENTS AND OPERATIONAL PROCESS ACTIVITIES
  - 1.2.1 Surface Operations Overview
    - 1.2.1.1 Overview of Transportation Casks, Waste Packages, and Canisters
      - 1.2.1.1.1 Transportation Casks
      - 1.2.1.1.2 Waste Forms
      - 1.2.1.1.3 Waste Packages
      - 1.2.1.1.4 Transportation, Aging, and Disposal Canister System
    - 1.2.1.2 Major Surface Facility Structures and Systems
    - 1.2.1.3 Overview of Operations
    - 1.2.1.4 Loading Plans
      - 1.2.1.4.1 Waste Package and Transportation, Aging, and Disposal Canister Loading Plan

---

**CONTENTS (Continued)**

- 1.2.1.4.2 Loading Options
  - 1.2.1.4.2.1 Transportation Cask Type
  - 1.2.1.4.2.2 Waste Form Type
  - 1.2.1.4.2.3 Waste Form Criticality Control
  - 1.2.1.4.2.4 Waste Form Thermal Power
  - 1.2.1.4.2.5 Waste Form Condition
- 1.2.1.4.3 Loading Records
- 1.2.1.4.4 Controls
- 1.2.1.5 Phased Operation and Construction Activities
  - 1.2.1.5.1 Separation of Construction Work Areas from Operating Areas
  - 1.2.1.5.2 Geologic Repository Operations Area—Area-Wide Systems
  - 1.2.1.5.3 Startup and Operations
  - 1.2.1.5.4 Construction-Related Hazards
- 1.2.1.6 General References
- 1.2.2 Surface Facilities Structural, Mechanical Handling Equipment, and Heating, Ventilation, and Air-Conditioning System Design
  - 1.2.2.1 Structural Design
    - 1.2.2.1.1 Structural Design Description
    - 1.2.2.1.2 Operational Processes
    - 1.2.2.1.3 Safety Category Classification
    - 1.2.2.1.4 Procedural Safety Controls to Prevent Event Sequences and Mitigate Their Consequences
    - 1.2.2.1.5 Design Bases and Design Criteria
    - 1.2.2.1.6 Design Methodologies
      - 1.2.2.1.6.1 Wind and Tornado Design
        - 1.2.2.1.6.1.1 Design Basis Wind
        - 1.2.2.1.6.1.2 Design Basis Tornado
        - 1.2.2.1.6.1.3 Determination of Forces on Structures
        - 1.2.2.1.6.1.4 Missile Impact Load
      - 1.2.2.1.6.2 Water Level (Flood) Design
        - 1.2.2.1.6.2.1 Flood Elevations
        - 1.2.2.1.6.2.2 Flood Protection
      - 1.2.2.1.6.3 Seismic Design
        - 1.2.2.1.6.3.1 Seismic Design Input
          - 1.2.2.1.6.3.1.1 Design Response Spectrum
          - 1.2.2.1.6.3.1.2 Design Time History
          - 1.2.2.1.6.3.1.3 Damping Values
        - 1.2.2.1.6.3.2 Structural Design Approach for Seismic
          - 1.2.2.1.6.3.2.1 Soil–Structure Interaction

**CONTENTS (Continued)**

- 1.2.2.1.6.3.2.2 Soil Model
- 1.2.2.1.6.3.2.3 Structural Model for CRCF, WHF, and RF
- 1.2.2.1.6.3.2.4 Structural Model for IHF and Aging Pads
- 1.2.2.1.6.3.3 Summary of Results
  - 1.2.2.1.6.3.3.1 Structural Responses
  - 1.2.2.1.6.3.3.2 Overall Shears
  - 1.2.2.1.6.3.4 Seismic Analysis of Systems and Components
- 1.2.2.1.6.4 Snow and Ice Design
- 1.2.2.1.6.5 Volcanic Ash Design
- 1.2.2.1.7 Consistency of Materials with Design Methodologies
- 1.2.2.1.8 Structural Design Codes and Standards
- 1.2.2.1.9 Structural Load Combinations
  - 1.2.2.1.9.1 Design Loads
  - 1.2.2.1.9.2 Load Combinations
    - 1.2.2.1.9.2.1 Reinforced Concrete Structures
    - 1.2.2.1.9.2.2 Structural Steel Design Load Combinations
    - 1.2.2.1.9.2.3 Overturning and Sliding
  - 1.2.2.1.10 Structural Design for Construction of the Surface Facilities
- 1.2.2.2 Mechanical Handling Equipment Design
  - 1.2.2.2.1 Mechanical Handling Equipment Description
  - 1.2.2.2.2 Operational Processes
  - 1.2.2.2.3 Safety Classification
  - 1.2.2.2.4 Procedural Safety Controls to Prevent Event Sequences or to Mitigate Their Consequences
  - 1.2.2.2.5 Design Bases and Design Criteria
  - 1.2.2.2.6 Design Methodologies
  - 1.2.2.2.7 Consistency of Materials with Design Methodologies
  - 1.2.2.2.8 Mechanical Handling Equipment Codes and Standards
  - 1.2.2.2.9 Mechanical Handling Equipment Load Combinations
    - 1.2.2.2.9.1 Design Loads
    - 1.2.2.2.9.2 Load Combinations
      - 1.2.2.2.9.2.1 Overhead Cranes, Canister Transfer Machine, and Spent Fuel Transfer Machine
      - 1.2.2.2.9.2.2 Jib Cranes
      - 1.2.2.2.9.2.3 Special Lifting Devices
      - 1.2.2.2.9.2.4 Cask Transfer Trolley and Waste Package Transfer Trolley
- 1.2.2.3 HVAC Systems Design
  - 1.2.2.3.1 HVAC Description
  - 1.2.2.3.2 Operational Processes

**CONTENTS (Continued)**

- 1.2.2.3.3 Safety Category Classification
- 1.2.2.3.4 Procedural Safety Controls to Prevent Event Sequences or to Mitigate Their Consequences
- 1.2.2.3.5 Design Bases and Design Criteria
- 1.2.2.3.6 Design Methodologies
- 1.2.2.3.7 Consistency of Materials with Design Methodologies
- 1.2.2.3.8 HVAC Codes and Standards
- 1.2.2.3.9 HVAC Load Combinations
  - 1.2.2.3.9.1 Design Loads
  - 1.2.2.3.9.2 Load Combinations
- 1.2.2.4 Regulatory Guidance and Other Design Codes and Standards
- 1.2.2.5 General References
- 1.2.3 Initial Handling Facility
  - 1.2.3.1 Initial Handling Facility Description
    - 1.2.3.1.1 Facility Description
      - 1.2.3.1.1.1 Cask Preparation Area (Room 1012)
      - 1.2.3.1.1.2 Canister Transfer Area (Room 2005)
      - 1.2.3.1.1.3 Waste Package Closure Area (Rooms 2002, 2004, and 2006)
      - 1.2.3.1.1.4 Waste Package Loadout Room (Room 1005)
      - 1.2.3.1.1.5 Canister Transfer Machine Maintenance Area (Room 1009)
      - 1.2.3.1.1.6 Waste Package Positioning Room (Room 1006)
    - 1.2.3.1.2 Operational Processes
      - 1.2.3.1.2.1 Cask Handling
      - 1.2.3.1.2.2 Canister Transfer
      - 1.2.3.1.2.3 Waste Package Closure
      - 1.2.3.1.2.4 Waste Package Loadout
    - 1.2.3.1.3 Safety Category Classification
    - 1.2.3.1.4 Procedural Safety Controls to Prevent Event Sequences or Mitigate Their Effects
    - 1.2.3.1.5 Design Bases and Design Criteria
    - 1.2.3.1.6 Design Methodologies
    - 1.2.3.1.7 Consistency of Materials with Design Methodologies
    - 1.2.3.1.8 Design Codes and Standards
    - 1.2.3.1.9 Design Load Combinations
  - 1.2.3.2 Mechanical Handling Systems
    - 1.2.3.2.1 Cask Handling Subsystem
      - 1.2.3.2.1.1 Subsystem Description

**CONTENTS (Continued)**

- 1.2.3.2.1.1.1 Subsystem Functions
- 1.2.3.2.1.1.2 Subsystem Location and Functional Arrangement
- 1.2.3.2.1.1.3 Subsystem and Components
  - 1.2.3.2.1.1.3.1 Cask Preparation Subsystem
  - 1.2.3.2.1.1.3.2 Waste Package Preparation Subsystem
- 1.2.3.2.1.2 Operational Processes
  - 1.2.3.2.1.2.1 Cask Preparation Subsystem
  - 1.2.3.2.1.2.2 Waste Package Preparation Subsystem
- 1.2.3.2.1.3 Safety Category Classification
- 1.2.3.2.1.4 Procedural Safety Controls to Prevent Event Sequences or Mitigate Their Effects
- 1.2.3.2.1.5 Design Bases and Design Criteria
- 1.2.3.2.1.6 Design Methodologies
- 1.2.3.2.1.7 Consistency of Materials with Design Methodologies
- 1.2.3.2.1.8 Design Codes and Standards
- 1.2.3.2.1.9 Design Load Combinations
- 1.2.3.2.2 Canister Transfer Subsystem
  - 1.2.3.2.2.1 Subsystem Description
    - 1.2.3.2.2.1.1 Subsystem Functions
    - 1.2.3.2.2.1.2 Subsystem Location and Functional Arrangement
    - 1.2.3.2.2.1.3 Subsystem and Components
  - 1.2.3.2.2.2 Operational Processes
  - 1.2.3.2.2.3 Safety Category Classification
  - 1.2.3.2.2.4 Procedural Safety Controls to Prevent Event Sequences or Mitigate Their Effects
  - 1.2.3.2.2.5 Design Bases and Design Criteria
  - 1.2.3.2.2.6 Design Methodologies
  - 1.2.3.2.2.7 Consistency of Materials with Design Methodologies
  - 1.2.3.2.2.8 Design Codes and Standards
  - 1.2.3.2.2.9 Design Load and Combinations
- 1.2.3.2.3 Waste Package Closure Subsystem
- 1.2.3.2.4 Waste Package Loadout Subsystem
  - 1.2.3.2.4.1 Subsystem Description
    - 1.2.3.2.4.1.1 Subsystem Functions
    - 1.2.3.2.4.1.2 Subsystem Location and Functional Arrangement
    - 1.2.3.2.4.1.3 Subsystem and Components
  - 1.2.3.2.4.2 Operational Processes

---

**CONTENTS (Continued)**

- 1.2.3.2.4.3 Safety Category Classification
- 1.2.3.2.4.4 Procedural Safety Controls to Prevent Event Sequences or Mitigate Their Effects
- 1.2.3.2.4.5 Design Bases and Design Criteria
- 1.2.3.2.4.6 Design Methodologies
- 1.2.3.2.4.7 Consistency of Materials with Design Methodologies
- 1.2.3.2.4.8 Design Codes and Standards
- 1.2.3.2.4.9 Design Load and Combinations
- 1.2.3.3 Process Systems
  - 1.2.3.3.1 Cask Cavity Gas Sampling Subsystem
  - 1.2.3.3.2 Water Collection Subsystem
- 1.2.3.4 Initial Handling Facility Heating, Ventilation, and Air-Conditioning Systems
  - 1.2.3.4.1 System Description
    - 1.2.3.4.1.1 System Functions
    - 1.2.3.4.1.2 System Location and Functional Arrangement
    - 1.2.3.4.1.3 Systems and Components
  - 1.2.3.4.2 Operational Processes
  - 1.2.3.4.3 Design Codes and Standards
- 1.2.3.5 General References
- 1.2.4 Canister Receipt and Closure Facility
  - 1.2.4.1 Canister Receipt and Closure Facility Description
    - 1.2.4.1.1 Facility Description
      - 1.2.4.1.1.1 Cask Receipt Area
        - 1.2.4.1.1.1.1 Transportation Cask Vestibule and Annex (Rooms 1036 and 1036A)
        - 1.2.4.1.1.1.2 Site Transporter Vestibule (Room 1027)
      - 1.2.4.1.1.2 Cask Preparation Room (Room 1026)
      - 1.2.4.1.1.3 Cask Unloading Rooms (Rooms 1023 and 1024)
      - 1.2.4.1.1.4 Canister Transfer Room (Room 2004)
      - 1.2.4.1.1.5 Waste Package Positioning Rooms (Rooms 1018 and 1019)
      - 1.2.4.1.1.6 Waste Package Closure Room (Room 2007)
      - 1.2.4.1.1.7 Waste Package Loadout Room (Room 1015) and Waste Package Loadout Vestibule (Room 1014)
    - 1.2.4.1.2 Operational Processes
      - 1.2.4.1.2.1 Cask Handling
      - 1.2.4.1.2.2 Canister Transfer
      - 1.2.4.1.2.3 Waste Package Closure
      - 1.2.4.1.2.4 Waste Package Loadout



**CONTENTS (Continued)**

- 1.2.4.1.3 Safety Category Classification
- 1.2.4.1.4 Procedural Safety Controls to Prevent Event Sequences or Mitigate Their Effects
- 1.2.4.1.5 Design Bases and Design Criteria
- 1.2.4.1.6 Design Methodologies
- 1.2.4.1.7 Consistency of Materials with Design Methodologies
- 1.2.4.1.8 Design Codes and Standards
- 1.2.4.1.9 Design Load Combinations
- 1.2.4.2 Mechanical Handling System
  - 1.2.4.2.1 Cask Handling Subsystem
    - 1.2.4.2.1.1 Subsystem Description
      - 1.2.4.2.1.1.1 Subsystem Functions
      - 1.2.4.2.1.1.2 Subsystem Location and Functional Arrangement
      - 1.2.4.2.1.1.3 Subsystem and Components
        - 1.2.4.2.1.1.3.1 Cask Preparation Subsystem
        - 1.2.4.2.1.1.3.2 Waste Package Preparation Subsystem
    - 1.2.4.2.1.2 Operational Processes
      - 1.2.4.2.1.2.1 Cask Preparation Subsystem
      - 1.2.4.2.1.2.2 Waste Package Preparation Subsystem
    - 1.2.4.2.1.3 Safety Category Classification
    - 1.2.4.2.1.4 Procedural Safety Controls to Prevent Event Sequences or Mitigate Their Effects
    - 1.2.4.2.1.5 Design Bases and Design Criteria
    - 1.2.4.2.1.6 Design Methodologies
    - 1.2.4.2.1.7 Consistency of Materials with Design Methodologies
    - 1.2.4.2.1.8 Design Codes and Standards
    - 1.2.4.2.1.9 Design Load Combinations
  - 1.2.4.2.2 Canister Transfer Subsystem
    - 1.2.4.2.2.1 Subsystem Description
      - 1.2.4.2.2.1.1 Subsystem Functions
      - 1.2.4.2.2.1.2 Subsystem Location and Functional Arrangement
      - 1.2.4.2.2.1.3 Subsystem and Components
    - 1.2.4.2.2.2 Operational Processes
    - 1.2.4.2.2.3 Safety Category Classification
    - 1.2.4.2.2.4 Procedural Safety Controls to Prevent Event Sequences or Mitigate Their Effects
    - 1.2.4.2.2.5 Design Bases and Design Criteria
    - 1.2.4.2.2.6 Design Methodologies

**CONTENTS (Continued)**

- 1.2.4.2.2.7 Consistency of Materials with Design Methodologies
- 1.2.4.2.2.8 Design Codes and Standards
- 1.2.4.2.2.9 Design Load and Combinations
- 1.2.4.2.3 Waste Package Closure Subsystem
  - 1.2.4.2.3.1 Subsystem Description
    - 1.2.4.2.3.1.1 Subsystem Functions
    - 1.2.4.2.3.1.2 Subsystem Location and Functional Arrangement
    - 1.2.4.2.3.1.3 Subsystem and Components
  - 1.2.4.2.3.2 Operational Processes
  - 1.2.4.2.3.3 Design Codes and Standards
- 1.2.4.2.4 Waste Package Loadout Subsystem
  - 1.2.4.2.4.1 Subsystem Description
    - 1.2.4.2.4.1.1 Subsystem Functions
    - 1.2.4.2.4.1.2 Subsystem Location and Functional Arrangement
    - 1.2.4.2.4.1.3 Subsystem and Components
  - 1.2.4.2.4.2 Operational Processes
  - 1.2.4.2.4.3 Safety Category Classification
  - 1.2.4.2.4.4 Procedural Safety Controls to Prevent Event Sequences or Mitigate Their Effects
  - 1.2.4.2.4.5 Design Bases and Design Criteria
  - 1.2.4.2.4.6 Design Methodologies
  - 1.2.4.2.4.7 Consistency of Materials with Design Methodologies
  - 1.2.4.2.4.8 Design Codes and Standards
  - 1.2.4.2.4.9 Design Load and Combinations
- 1.2.4.3 Process Systems
  - 1.2.4.3.1 Cask Cavity Gas Sampling Subsystem
    - 1.2.4.3.1.1 Subsystem Description
      - 1.2.4.3.1.1.1 Subsystem Functions
      - 1.2.4.3.1.1.2 Subsystem Location and Functional Arrangement
      - 1.2.4.3.1.1.3 Components
    - 1.2.4.3.1.2 Operational Processes
    - 1.2.4.3.1.3 Design Codes and Standards
  - 1.2.4.3.2 Water Collection Subsystem
    - 1.2.4.3.2.1 Subsystem Description
    - 1.2.4.3.2.2 Operational Processes
    - 1.2.4.3.2.3 Design Codes and Standards

**CONTENTS (Continued)**

- 1.2.4.4 Canister Receipt and Closure Facility Heating, Ventilation, and Air-Conditioning Systems
  - 1.2.4.4.1 System Description
    - 1.2.4.4.1.1 System Functions
    - 1.2.4.4.1.2 System Location and Functional Arrangement
    - 1.2.4.4.1.3 Systems and Components
  - 1.2.4.4.2 Operational Processes
  - 1.2.4.4.3 Safety Category Classification
  - 1.2.4.4.4 Procedural Safety Controls to Prevent Event Sequences or Mitigate Their Effects
  - 1.2.4.4.5 Design Bases and Design Criteria
  - 1.2.4.4.6 Design Methodologies
  - 1.2.4.4.7 Consistency of Materials with Design Methodologies
  - 1.2.4.4.8 Design Codes and Standards
  - 1.2.4.4.9 Design Load Combinations
- 1.2.4.5 General References
- 1.2.5 Wet Handling Facility
  - 1.2.5.1 Wet Handling Facility Description
    - 1.2.5.1.1 Facility Description
      - 1.2.5.1.1.1 Cask Receipt Area
        - 1.2.5.1.1.1.1 Transportation Cask Vestibule (Room 1001)
        - 1.2.5.1.1.1.2 Site Transporter Vestibule (Room 1023)
      - 1.2.5.1.1.2 Cask Preparation Area (Room 1016)
      - 1.2.5.1.1.3 Canister Transfer Area
    - 1.2.5.1.2 Operational Processes
      - 1.2.5.1.2.1 Cask Handling
      - 1.2.5.1.2.2 Spent Nuclear Fuel Assembly Transfer
      - 1.2.5.1.2.3 Dual-Purpose Canister Cutting
      - 1.2.5.1.2.4 Transportation, Aging, and Disposal Canister Closure
      - 1.2.5.1.2.5 Canister Transfer
      - 1.2.5.1.2.6 Pool
    - 1.2.5.1.3 Safety Category Classification
    - 1.2.5.1.4 Procedural Safety Controls to Prevent Event Sequences or Mitigate Their Effects
    - 1.2.5.1.5 Design Bases and Design Criteria
    - 1.2.5.1.6 Design Methodologies
    - 1.2.5.1.7 Consistency of Materials with Design Methodologies
    - 1.2.5.1.8 Design Codes and Standards
    - 1.2.5.1.9 Design Load Combinations

**CONTENTS (Continued)**

- 1.2.5.2 Mechanical Handling System
  - 1.2.5.2.1 Cask Handling Subsystem
    - 1.2.5.2.1.1 Subsystem Description
      - 1.2.5.2.1.1.1 Subsystem Functions
      - 1.2.5.2.1.1.2 Subsystem Location and Functional Arrangement
      - 1.2.5.2.1.1.3 Subsystem and Components
    - 1.2.5.2.1.2 Operational Processes
    - 1.2.5.2.1.3 Safety Category Classification
    - 1.2.5.2.1.4 Procedural Safety Controls to Prevent Event Sequences or Mitigate Their Effects
    - 1.2.5.2.1.5 Design Bases and Design Criteria
    - 1.2.5.2.1.6 Design Methodologies
    - 1.2.5.2.1.7 Consistency of Materials with Design Methodologies
    - 1.2.5.2.1.8 Design Codes and Standards
    - 1.2.5.2.1.9 Design Load Combinations
  - 1.2.5.2.2 Spent Nuclear Fuel Assembly Transfer Subsystem
    - 1.2.5.2.2.1 Subsystem Description
      - 1.2.5.2.2.1.1 Subsystem Functions
      - 1.2.5.2.2.1.2 Subsystem Location and Functional Arrangement
      - 1.2.5.2.2.1.3 Subsystem and Components
    - 1.2.5.2.2.2 Operational Processes
    - 1.2.5.2.2.3 Safety Category Classification
    - 1.2.5.2.2.4 Procedural Safety Controls to Prevent Event Sequences or Mitigate Their Effects
    - 1.2.5.2.2.5 Design Bases and Design Criteria
    - 1.2.5.2.2.6 Design Methodologies
    - 1.2.5.2.2.7 Consistency of Materials with Design Methodologies
    - 1.2.5.2.2.8 Design Codes and Standards
    - 1.2.5.2.2.9 Design Load Combinations
  - 1.2.5.2.3 Dual-Purpose Canister Cutting Subsystem
    - 1.2.5.2.3.1 Subsystem Description
      - 1.2.5.2.3.1.1 Subsystem Functions
      - 1.2.5.2.3.1.2 Subsystem Location and Functional Arrangement
      - 1.2.5.2.3.1.3 Subsystem and Components
        - 1.2.5.2.3.1.3.1 Dual-Purpose Canister Cutting Subsystem
    - 1.2.5.2.3.2 Operational Processes
    - 1.2.5.2.3.3 Safety Category Classification

**CONTENTS (Continued)**

- 1.2.5.2.3.4 Procedural Safety Controls to Prevent Event Sequences or Mitigate Their Effects
- 1.2.5.2.3.5 Design Bases and Design Criteria
- 1.2.5.2.3.6 Design Methodologies
- 1.2.5.2.3.7 Consistency of Materials with Design Methodologies
- 1.2.5.2.3.8 Design Codes and Standards
- 1.2.5.2.3.9 Design Load Combinations
- 1.2.5.2.4 Transportation, Aging, and Disposal Canister Closure Subsystem
  - 1.2.5.2.4.1 Subsystem Description
    - 1.2.5.2.4.1.1 Subsystem Functions
    - 1.2.5.2.4.1.2 Subsystem Location and Functional Arrangement
    - 1.2.5.2.4.1.3 Subsystem and Components
      - 1.2.5.2.4.1.3.1 TAD Canister Closure Subsystem
  - 1.2.5.2.4.2 Operational Processes
  - 1.2.5.2.4.3 Safety Category Classification
  - 1.2.5.2.4.4 Procedural Safety Controls to Prevent Event Sequences or Mitigate Their Effects
  - 1.2.5.2.4.5 Design Bases and Design Criteria
  - 1.2.5.2.4.6 Design Methodologies
  - 1.2.5.2.4.7 Consistency of Materials with Design Methodologies
  - 1.2.5.2.4.8 Design Codes and Standards
  - 1.2.5.2.4.9 Design Load Combinations
- 1.2.5.2.5 Canister Transfer Subsystem
  - 1.2.5.2.5.1 Subsystem Description
    - 1.2.5.2.5.1.1 Subsystem Functions
    - 1.2.5.2.5.1.2 Subsystem Location and Functional Arrangement
    - 1.2.5.2.5.1.3 Subsystem and Components
  - 1.2.5.2.5.2 Operational Processes
  - 1.2.5.2.5.3 Safety Category Classification
  - 1.2.5.2.5.4 Procedural Safety Controls to Prevent Event Sequences or Mitigate Their Effects
  - 1.2.5.2.5.5 Design Bases and Design Criteria
  - 1.2.5.2.5.6 Design Methodologies
  - 1.2.5.2.5.7 Consistency of Materials with Design Methodologies
  - 1.2.5.2.5.8 Design Codes and Standards
  - 1.2.5.2.5.9 Design Load Combinations
- 1.2.5.3 Process Systems

**CONTENTS (Continued)**

- 1.2.5.3.1 Cask Cavity Gas Sampling Subsystem
- 1.2.5.3.2 Pool Water Treatment and Cooling System
  - 1.2.5.3.2.1 System Description
    - 1.2.5.3.2.1.1 System Functions
    - 1.2.5.3.2.1.2 System Location and Functional Arrangement
    - 1.2.5.3.2.1.3 Components
      - 1.2.5.3.2.1.3.1 Pool Water Treatment Subsystem
      - 1.2.5.3.2.1.3.2 Pool Water Cooling Subsystem
      - 1.2.5.3.2.1.3.3 Boric Acid Makeup Subsystem
      - 1.2.5.3.2.1.3.4 Pool Water Makeup Subsystem
      - 1.2.5.3.2.1.3.5 Leak Detection Subsystem
    - 1.2.5.3.2.1.4 Maintenance Considerations
  - 1.2.5.3.2.2 Operational Processes
  - 1.2.5.3.2.3 Design Codes and Standards
- 1.2.5.3.3 Cask Decontamination Subsystem
  - 1.2.5.3.3.1 Subsystem Description
    - 1.2.5.3.3.1.1 Subsystem Functions
    - 1.2.5.3.3.1.2 Subsystem Location and Functional Arrangement
    - 1.2.5.3.3.1.3 Components
  - 1.2.5.3.3.2 Operational Processes
  - 1.2.5.3.3.3 Design Codes and Standards
- 1.2.5.3.4 Cask Cooling and Filling Subsystem
  - 1.2.5.3.4.1 Subsystem Description
    - 1.2.5.3.4.1.1 Subsystem Functions
    - 1.2.5.3.4.1.2 Subsystem Location and Functional Arrangement
    - 1.2.5.3.4.1.3 Components
  - 1.2.5.3.4.2 Operational Processes
  - 1.2.5.3.4.3 Design Codes and Standards
- 1.2.5.3.5 Transportation, Aging, and Disposal Canister Drying and Inerting Subsystem
  - 1.2.5.3.5.1 Subsystem Description
    - 1.2.5.3.5.1.1 Subsystem Functions
    - 1.2.5.3.5.1.2 Subsystem Location and Functional Arrangement
    - 1.2.5.3.5.1.3 Components
  - 1.2.5.3.5.2 Operational Processes
  - 1.2.5.3.5.3 Design Codes and Standards
- 1.2.5.3.6 Water Collection Subsystem

**CONTENTS (Continued)**

- 1.2.5.4 Shielded Transfer Cask
  - 1.2.5.4.1 System Description
    - 1.2.5.4.1.1 System Functions
    - 1.2.5.4.1.2 System Location and Functional Arrangement
    - 1.2.5.4.1.3 System and Components
  - 1.2.5.4.2 Operational Processes
    - 1.2.5.4.2.1 Aging Facility Operations
    - 1.2.5.4.2.2 Wet Handling Facility Operations
  - 1.2.5.4.3 Safety Category Classification
  - 1.2.5.4.4 Procedural Safety Controls to Prevent Event Sequences or Mitigate Their Effects
  - 1.2.5.4.5 Design Bases and Design Criteria
  - 1.2.5.4.6 Design Methodologies
  - 1.2.5.4.7 Consistency of Materials with Design Methodologies
  - 1.2.5.4.8 Design Codes and Standards
  - 1.2.5.4.9 Design Load Combinations
- 1.2.5.5 Wet Handling Facility Heating, Ventilation, and Air-Conditioning System
  - 1.2.5.5.1 System Description
    - 1.2.5.5.1.1 System Functions
    - 1.2.5.5.1.2 System Location and Functional Arrangement
    - 1.2.5.5.1.3 System and Components
  - 1.2.5.5.2 Operational Processes
  - 1.2.5.5.3 Safety Category Classification
  - 1.2.5.5.4 Procedural Safety Controls to Prevent Event Sequences or Mitigate Their Effects
  - 1.2.5.5.5 Design Bases and Design Criteria
  - 1.2.5.5.6 Design Methodologies
  - 1.2.5.5.7 Consistency of Materials with Design Methodologies
  - 1.2.5.5.8 Design Codes and Standards
  - 1.2.5.5.9 Design Load Combinations
- 1.2.5.6 General References
- 1.2.6 Receipt Facility
  - 1.2.6.1 Receipt Facility Description
    - 1.2.6.1.1 Facility Description
      - 1.2.6.1.1.1 Cask Receipt Area
        - 1.2.6.1.1.1.1 Transportation Cask Vestibules and Annex (Rooms 1021 and 1021A)
        - 1.2.6.1.1.1.2 Site Transporter Vestibule (Room 1001)

**CONTENTS (Continued)**

- 1.2.6.1.1.2 Cask Preparation Room (Room 1017) and Annex (Room 1017A)
- 1.2.6.1.1.3 Cask Unloading Room (Room 1015) and Loading Room (Room 1013)
- 1.2.6.1.1.4 Canister Transfer Room (Room 2007)
- 1.2.6.1.1.5 Lid Bolting Room (Room 1002)
- 1.2.6.1.2 Operational Processes
  - 1.2.6.1.2.1 Cask Handling
  - 1.2.6.1.2.2 Canister Transfer
- 1.2.6.1.3 Safety Category Classification
- 1.2.6.1.4 Procedural Safety Controls to Prevent Event Sequences or Mitigate Their Effects
- 1.2.6.1.5 Design Bases and Design Criteria
- 1.2.6.1.6 Design Methodologies
- 1.2.6.1.7 Consistency of Materials with Design Methodologies
- 1.2.6.1.8 Design Codes and Standards
- 1.2.6.1.9 Design Load Combinations
- 1.2.6.2 Mechanical Handling System
  - 1.2.6.2.1 Cask Handling Subsystem
    - 1.2.6.2.1.1 Subsystem Description
      - 1.2.6.2.1.1.1 Subsystem Functions
      - 1.2.6.2.1.1.2 Subsystem Location and Functional Arrangement
      - 1.2.6.2.1.1.3 Subsystem and Components
    - 1.2.6.2.1.2 Operational Processes
    - 1.2.6.2.1.3 Safety Category Classification
    - 1.2.6.2.1.4 Procedural Safety Controls to Prevent Event Sequences or Mitigate Their Effects
    - 1.2.6.2.1.5 Design Bases and Design Criteria
    - 1.2.6.2.1.6 Design Methodologies
    - 1.2.6.2.1.7 Consistency of Materials with Design Methodologies
    - 1.2.6.2.1.8 Design Codes and Standards
    - 1.2.6.2.1.9 Design Load Combinations
  - 1.2.6.2.2 Canister Transfer Subsystem
    - 1.2.6.2.2.1 Subsystem Description
      - 1.2.6.2.2.1.1 Subsystem Functions
      - 1.2.6.2.2.1.2 Subsystem Location and Functional Arrangement
      - 1.2.6.2.2.1.3 Subsystem and Components
    - 1.2.6.2.2.2 Operational Processes



**CONTENTS (Continued)**

- 1.2.6.2.2.3 Safety Category Classification
- 1.2.6.2.2.4 Procedural Safety Controls to Prevent Event Sequences or Mitigate Their Effects
- 1.2.6.2.2.5 Design Bases and Design Criteria
- 1.2.6.2.2.6 Design Methodologies
- 1.2.6.2.2.7 Consistency of Materials with Design Methodologies
- 1.2.6.2.2.8 Design Codes and Standards
- 1.2.6.2.2.9 Design Load Combinations
- 1.2.6.3 Process Systems
  - 1.2.6.3.1 Cask Cavity Gas Sampling Subsystem
  - 1.2.6.3.2 Water Collection Subsystem
- 1.2.6.4 Receipt Facility HVAC System
  - 1.2.6.4.1 System Description
    - 1.2.6.4.1.1 System Functions
    - 1.2.6.4.1.2 System Location and Functional Arrangement
    - 1.2.6.4.1.3 Systems and Components
  - 1.2.6.4.2 Operational Processes
  - 1.2.6.4.3 Design Codes and Standards
- 1.2.6.5 General References
- 1.2.7 Aging Facility
  - 1.2.7.1 Aging Facility Description
    - 1.2.7.1.1 Functions
    - 1.2.7.1.2 Location and Functional Arrangement
    - 1.2.7.1.3 Major Components
      - 1.2.7.1.3.1 Aging Pad
      - 1.2.7.1.3.2 Aging Overpack
        - 1.2.7.1.3.2.1 Vertical Aging Overpacks for DPCs and TAD Canisters
        - 1.2.7.1.3.2.2 Horizontal Aging Modules for Dual-Purpose Canisters
      - 1.2.7.1.3.3 Overpack Transfer
  - 1.2.7.2 Operational Processes
    - 1.2.7.2.1 Aging and Staging in Vertical Orientation
    - 1.2.7.2.2 Aging in Horizontal Orientation
  - 1.2.7.3 Safety Category Classification
  - 1.2.7.4 Procedural Safety Controls to Prevent Event Sequences or Mitigate Their Effects
  - 1.2.7.5 Design Bases and Design Criteria
  - 1.2.7.6 Design Methodologies

**CONTENTS (Continued)**

- 1.2.7.6.1 Seismic Design
- 1.2.7.6.2 Structural Design
- 1.2.7.6.3 Shielding Design
- 1.2.7.6.4 Criticality Design
- 1.2.7.6.5 As Low as is Reasonably Achievable Design
- 1.2.7.6.6 Thermal Design
- 1.2.7.7 Consistency of Materials with Design Methodologies
- 1.2.7.8 Design Codes and Standards
- 1.2.7.9 Design Load Combinations
- 1.2.7.10 General References
- 1.2.8 Balance of Plant Facilities
  - 1.2.8.1 Balance of Plant Facility Descriptions
    - 1.2.8.1.1 Facility Descriptions
      - 1.2.8.1.1.1 Emergency Diesel Generator Facility
      - 1.2.8.1.1.2 Administration Facility (Area 620)
      - 1.2.8.1.1.3 Security Facilities (Areas 30A, 30B, 30C, 65A, and 65B)
      - 1.2.8.1.1.4 Central Control Center Facility (Area 240)
      - 1.2.8.1.1.5 Low-Level Waste Facility (Area 160)
      - 1.2.8.1.1.6 Warehouse and Non-Nuclear Receipt Facility (Area 230)
      - 1.2.8.1.1.7 Facilities for Utilities (Areas 25A, 25B, 25C, 26B, 27A, 27B, 28A, 28B, 28E, and 90A)
      - 1.2.8.1.1.8 Fire, Rescue, and Medical Facility (Area 63A)
      - 1.2.8.1.1.9 Materials and Consumables Facilities (Areas 68A, 68B, and 71B)
      - 1.2.8.1.1.10 Maintenance and Repair Facilities (Areas 71A and 220)
      - 1.2.8.1.1.11 Aging Overpack Staging Facility (Area 290)
      - 1.2.8.1.1.12 Other Facilities and Areas
    - 1.2.8.1.2 Facilities Operations
    - 1.2.8.1.3 Design Codes and Standards
  - 1.2.8.2 ITS Diesel Generator Mechanical Support Systems
    - 1.2.8.2.1 ITS Diesel Generator Fuel Oil System
      - 1.2.8.2.1.1 System Description
      - 1.2.8.2.1.2 Operational Processes
      - 1.2.8.2.1.3 Safety Category Classification
      - 1.2.8.2.1.4 Procedural Safety Controls to Prevent Event Sequences or Mitigate Their Effects
      - 1.2.8.2.1.5 Design Bases and Design Criteria
      - 1.2.8.2.1.6 Design Methodologies

**CONTENTS (Continued)**

- 1.2.8.2.1.7 Consistency of Materials with Design Methodologies
- 1.2.8.2.1.8 Design Codes and Standards
- 1.2.8.2.1.9 Design Load Combinations
- 1.2.8.2.2 ITS Diesel Generator Air Start System
  - 1.2.8.2.2.1 System Description
  - 1.2.8.2.2.2 Operational Processes
  - 1.2.8.2.2.3 Safety Category Classification
  - 1.2.8.2.2.4 Procedural Safety Controls to Prevent Event Sequences or Mitigate Their Effects
  - 1.2.8.2.2.5 Design Bases and Design Criteria
  - 1.2.8.2.2.6 Design Methodologies
  - 1.2.8.2.2.7 Consistency of Materials with Design Methodologies
  - 1.2.8.2.2.8 Design Codes and Standards
  - 1.2.8.2.2.9 Design Load Combinations
- 1.2.8.2.3 ITS Diesel Generator Jacket Water Cooling System
  - 1.2.8.2.3.1 System Description
  - 1.2.8.2.3.2 Operational Processes
  - 1.2.8.2.3.3 Safety Category Classification
  - 1.2.8.2.3.4 Procedural Safety Controls to Prevent Event Sequences or Mitigate Their Effects
  - 1.2.8.2.3.5 Design Bases and Design Criteria
  - 1.2.8.2.3.6 Design Methodologies
  - 1.2.8.2.3.7 Consistency of Materials with Design Methodologies
  - 1.2.8.2.3.8 Design Codes and Standards
  - 1.2.8.2.3.9 Design Load Combinations
- 1.2.8.2.4 ITS Diesel Generator Lubricating Oil System
  - 1.2.8.2.4.1 System Description
  - 1.2.8.2.4.2 Operational Processes
  - 1.2.8.2.4.3 Safety Category Classification
  - 1.2.8.2.4.4 Procedural Safety Controls to Prevent Event Sequences or Mitigate Their Effects
  - 1.2.8.2.4.5 Design Bases and Design Criteria
  - 1.2.8.2.4.6 Design Methodologies
  - 1.2.8.2.4.7 Consistency of Materials with Design Methodologies
  - 1.2.8.2.4.8 Design Codes and Standards
  - 1.2.8.2.4.9 Design Load Combinations
- 1.2.8.2.5 ITS Diesel Generator Air Intake and Exhaust System
  - 1.2.8.2.5.1 System Description
  - 1.2.8.2.5.2 Operational Processes

**CONTENTS (Continued)**

- 1.2.8.2.5.3 Safety Category Classification
- 1.2.8.2.5.4 Procedural Safety Controls to Prevent Event Sequences or Mitigate Their Effects
- 1.2.8.2.5.5 Design Bases and Design Criteria
- 1.2.8.2.5.6 Design Methodologies
- 1.2.8.2.5.7 Consistency of Materials with Design Methodologies
- 1.2.8.2.5.8 Design Codes and Standards
- 1.2.8.2.5.9 Design Load Combinations
- 1.2.8.3 Balance of Plant Facilities Heating, Ventilation, and Air-Conditioning
  - 1.2.8.3.1 Emergency Diesel Generator Facility Heating, Ventilation, and Air-Conditioning Systems
    - 1.2.8.3.1.1 System Description
      - 1.2.8.3.1.1.1 System Functions
      - 1.2.8.3.1.1.2 System Location and Functional Arrangement
      - 1.2.8.3.1.1.3 Systems and Components
    - 1.2.8.3.1.2 Operational Processes
    - 1.2.8.3.1.3 Safety Classification
    - 1.2.8.3.1.4 Procedural Safety Controls to Prevent Event Sequences or Mitigate Their Effects
    - 1.2.8.3.1.5 Design Bases and Design Criteria
    - 1.2.8.3.1.6 Design Methodologies
    - 1.2.8.3.1.7 Consistency of Materials with Design Methodologies
    - 1.2.8.3.1.8 Design Codes and Standards
    - 1.2.8.3.1.9 Design Load Combinations
  - 1.2.8.3.2 Facilities HVAC
    - 1.2.8.3.2.1 System Description
      - 1.2.8.3.2.1.1 System Functions
      - 1.2.8.3.2.1.2 System Location and Functional Arrangement
      - 1.2.8.3.2.1.3 Systems and Components
        - 1.2.8.3.2.1.3.1 Low-Level Waste Facility and Central Control Center Facility HVAC Systems
        - 1.2.8.3.2.1.3.2 Low-Level Waste Facility HVAC System
        - 1.2.8.3.2.1.3.3 Central Control Center Facility HVAC System
    - 1.2.8.3.2.2 Operational Processes
      - 1.2.8.3.2.2.1 Facilities HVAC Systems
      - 1.2.8.3.2.2.2 Central Control Center Facility HVAC System
      - 1.2.8.3.2.2.3 Low-Level Waste Facility HVAC System
    - 1.2.8.3.2.3 Design Codes and Standards
- 1.2.8.4 Surface Transportation

**CONTENTS (Continued)**

- 1.2.8.4.1 Site Transporter
  - 1.2.8.4.1.1 Description
  - 1.2.8.4.1.2 Operational Processes
  - 1.2.8.4.1.3 Safety Category Classification
  - 1.2.8.4.1.4 Procedural Safety Controls to Prevent Event Sequences or Mitigate Their Effects
  - 1.2.8.4.1.5 Design Bases and Design Criteria
  - 1.2.8.4.1.6 Design Methodologies
  - 1.2.8.4.1.7 Consistency of Materials with Design Methodologies
  - 1.2.8.4.1.8 Design Codes and Standards
  - 1.2.8.4.1.9 Design Load Combinations
- 1.2.8.4.2 Cask Tractor and Cask Transfer Trailers
  - 1.2.8.4.2.1 Description
  - 1.2.8.4.2.2 Operational Processes
  - 1.2.8.4.2.3 Safety Category Classification
  - 1.2.8.4.2.4 Procedural Safety Controls to Prevent Event Sequences or Mitigate Their Effects
  - 1.2.8.4.2.5 Design Bases and Design Criteria
  - 1.2.8.4.2.6 Design Methodologies
  - 1.2.8.4.2.7 Consistency of Material with Design Methodologies
  - 1.2.8.4.2.8 Design Codes and Standards
  - 1.2.8.4.2.9 Design Load Combinations
- 1.2.8.4.3 Site Prime Movers
  - 1.2.8.4.3.1 Description
  - 1.2.8.4.3.2 Operational Processes
  - 1.2.8.4.3.3 Safety Category Classification
  - 1.2.8.4.3.4 Procedural Safety Controls to Prevent Event Sequences or Mitigate Their Effects
  - 1.2.8.4.3.5 Design Bases and Design Criteria
  - 1.2.8.4.3.6 Design Methodologies
  - 1.2.8.4.3.7 Consistency of Material with Design Methodologies
  - 1.2.8.4.3.8 Design Codes and Standards
  - 1.2.8.4.3.9 Design Load Combinations
- 1.2.8.4.4 Roads and Rails
  - 1.2.8.4.4.1 Surface Roads
    - 1.2.8.4.4.1.1 System Description
    - 1.2.8.4.4.1.2 Operational Processes
    - 1.2.8.4.4.1.3 Design Codes and Standards
  - 1.2.8.4.4.2 Surface Rails

**CONTENTS (Continued)**

- 1.2.8.4.4.2.1 System Description
- 1.2.8.4.4.2.2 Operational Processes
- 1.2.8.4.4.2.3 Design Codes and Standards
- 1.2.8.4.5 Transportation Casks
  - 1.2.8.4.5.1 System Description
  - 1.2.8.4.5.2 Operational Processes
  - 1.2.8.4.5.3 Safety Category Classification
  - 1.2.8.4.5.4 Procedural Safety Controls to Prevent Event Sequences or Mitigate Their Effects
  - 1.2.8.4.5.5 Design Bases and Design Criteria
  - 1.2.8.4.5.6 Design Methodologies
  - 1.2.8.4.5.7 Consistency of Material with Design Methodologies
  - 1.2.8.4.5.8 Design Codes and Standards
  - 1.2.8.4.5.9 Design Load Combinations
- 1.2.8.5 General References
- 1.3 SUBSURFACE STRUCTURES, SYSTEMS, AND COMPONENTS AND OPERATIONAL PROCESS ACTIVITIES
  - 1.3.1 Subsurface Operations Overview
    - 1.3.1.1 Major Subsurface Facility Structures and Equipment
    - 1.3.1.2 Subsurface Facility Operations
      - 1.3.1.2.1 Support Operations in the Subsurface Facility
        - 1.3.1.2.1.1 Access Control Operations
        - 1.3.1.2.1.2 Personnel
        - 1.3.1.2.1.3 Task-Specific Activities
        - 1.3.1.2.1.4 Personnel Transportation
        - 1.3.1.2.1.5 Maintenance Activities
        - 1.3.1.2.1.6 Monitoring Activities
        - 1.3.1.2.1.7 Off-Normal Response Activities
      - 1.3.1.2.2 Waste Package Transportation
      - 1.3.1.2.3 Waste Package Emplacement
      - 1.3.1.2.4 Subsurface Facility Ventilation Operations
      - 1.3.1.2.5 Thermal Management
      - 1.3.1.2.6 Repository Performance Monitoring
      - 1.3.1.2.7 Concurrent Development and Emplacement Operations
        - 1.3.1.2.7.1 Sequence of Development and Operations
        - 1.3.1.2.7.2 Separation of Development from Operations
        - 1.3.1.2.7.3 Development of the Initial Operating Capability
        - 1.3.1.2.7.4 Concurrent Development Hazards
      - 1.3.1.2.8 Waste Retrieval Operations

**CONTENTS (Continued)**

- 1.3.1.2.9 Repository Closure Operations
- 1.3.1.3 Subsurface Facility Interfaces with Facilities and Systems
  - 1.3.1.3.1 Facilities
  - 1.3.1.3.2 Major Systems
  - 1.3.1.3.3 Infrastructure Systems
  - 1.3.1.3.4 Interfaces During Repository Development
- 1.3.1.4 Conformance of Design to Criteria and Bases
- 1.3.1.5 General References
- 1.3.2 General Subsurface Design Considerations
  - 1.3.2.1 General Design Approach
  - 1.3.2.2 Design Considerations
    - 1.3.2.2.1 General Layout of the Subsurface Facility
    - 1.3.2.2.2 Thermal Design Considerations
    - 1.3.2.2.3 Equipment Qualification
  - 1.3.2.3 Design of Subsurface Mechanical Handling Equipment
    - 1.3.2.3.1 Nuclear Safety Design Basis Requirements
    - 1.3.2.3.2 Design, Operational and Environmental Requirements
  - 1.3.2.4 Design of Subsurface Facility Structures, Systems, and Components
    - 1.3.2.4.1 Subsurface Electrical Distribution Criteria and Design Considerations
    - 1.3.2.4.2 Subsurface Facility Communications Criteria and Design Considerations
    - 1.3.2.4.3 Mining
      - 1.3.2.4.3.1 Criteria and Design Considerations for Sizing of Emplacement Areas
      - 1.3.2.4.3.2 Faulting
      - 1.3.2.4.3.3 Standoffs
      - 1.3.2.4.3.4 Excavation Stability
      - 1.3.2.4.3.5 Emplacement Drift Configuration
      - 1.3.2.4.3.6 Portal Flood Protection
    - 1.3.2.4.4 Design of Geotechnical Structures, Systems, and Components
      - 1.3.2.4.4.1 Ground Support
      - 1.3.2.4.4.2 Ground Support Design Methods
      - 1.3.2.4.4.3 Ground Support General Requirements
    - 1.3.2.4.5 Ventilation
      - 1.3.2.4.5.1 Ventilation Pressures
      - 1.3.2.4.5.2 Thermal
    - 1.3.2.4.6 Design of Civil and Structural Structures, Systems, and Components

**CONTENTS (Continued)**

- 1.3.2.4.6.1 Groundwater
- 1.3.2.4.6.2 Frost Line
- 1.3.2.4.6.3 Seismic Design Bases
- 1.3.2.4.6.4 Materials
- 1.3.2.4.6.5 Corrosion Effects
- 1.3.2.4.6.6 Reinforced Concrete Structures
- 1.3.2.4.6.7 Steel Structures
- 1.3.2.4.6.8 Permanent Subsurface Railway Design
- 1.3.2.4.6.9 Surface Structures That Are Part of Subsurface Facility
- 1.3.2.4.7 Design of Fire Protection Systems, Structures, and Components
- 1.3.2.4.8 Design for Waste Retrieval
- 1.3.2.4.9 Construction in Phases: Panel Sequencing
- 1.3.2.4.10 Design for Repository Closure
- 1.3.2.5 Design Methodologies for Subsurface Structures, Systems, and Components
  - 1.3.2.5.1 Seismic Design
  - 1.3.2.5.2 Criticality Design
  - 1.3.2.5.3 Shielding Design
  - 1.3.2.5.4 As Low as is Reasonably Achievable Design Methodology
  - 1.3.2.5.5 Consistency of Materials with Design Methodologies
- 1.3.2.6 Performance and Documentation of Design Analyses
- 1.3.2.7 Design Codes and Standards
- 1.3.2.8 Design Loads and Load Combinations
  - 1.3.2.8.1 Dead Loads
  - 1.3.2.8.2 Live Loads
  - 1.3.2.8.3 Seismic Loads
  - 1.3.2.8.4 Transport and Emplacement Vehicle Loads
  - 1.3.2.8.5 Waste Package Loads
  - 1.3.2.8.6 Drip Shield Loads
  - 1.3.2.8.7 Ventilation Pressure Loads
  - 1.3.2.8.8 Temperature Loads
  - 1.3.2.8.9 Load Combinations
    - 1.3.2.8.9.1 Structural Steel Structures
    - 1.3.2.8.9.2 Reinforced Concrete Structures
    - 1.3.2.8.9.3 Equipment
- 1.3.2.9 Conformance of Design to Criteria and Bases
- 1.3.2.10 General References
- 1.3.3 Nonemplacement Areas of the Subsurface Facility
  - 1.3.3.1 Nonemplacement Areas Design Description



**CONTENTS (Continued)**

- 1.3.3.1.1 Portals and Ramps
- 1.3.3.1.2 Access Mains
- 1.3.3.1.3 Exhaust Mains
- 1.3.3.1.4 Turnouts
- 1.3.3.1.5 Shafts
- 1.3.3.1.6 Performance Confirmation Openings
- 1.3.3.1.7 Alcoves and Niches
- 1.3.3.1.8 Electrical Service Distribution
- 1.3.3.1.9 Subsurface Equipment Communications and Controls
- 1.3.3.2 Excavation
- 1.3.3.3 Ground Support System
  - 1.3.3.3.1 System Description
    - 1.3.3.3.1.1 Ground Support for Portals
    - 1.3.3.3.1.2 Ground Support for Ramps
    - 1.3.3.3.1.3 Ground Support at Drift Intersections
    - 1.3.3.3.1.4 Ground Support for Access Mains, Exhaust Mains, and Turnouts
    - 1.3.3.3.1.5 Ground Support for Shafts
    - 1.3.3.3.1.6 Ground Support for Miscellaneous Openings
  - 1.3.3.3.2 Operational Processes
  - 1.3.3.3.3 Design Codes and Standards
- 1.3.3.4 Invert System
  - 1.3.3.4.1 System Description
  - 1.3.3.4.2 Operational Processes
  - 1.3.3.4.3 Design Codes and Standards
- 1.3.3.5 Waste Package Transportation System
  - 1.3.3.5.1 System Description
    - 1.3.3.5.1.1 Transport and Emplacement Vehicle Description
    - 1.3.3.5.1.2 Subsurface Rail and Invert System
    - 1.3.3.5.1.3 Mechanical Handling Sequences and Operations
    - 1.3.3.5.1.4 Fire Protection
    - 1.3.3.5.1.5 Radiation Shielding
  - 1.3.3.5.2 Operational Processes
    - 1.3.3.5.2.1 Operational Overview
    - 1.3.3.5.2.2 Operating Condition Monitoring
    - 1.3.3.5.2.3 Operational Control
    - 1.3.3.5.2.4 Transportation Routes and Operational Interfaces
  - 1.3.3.5.3 Safety Category Classification

**CONTENTS (Continued)**

- 1.3.3.5.4 Administrative or Procedural Safety Controls to Prevent Event Sequences or Mitigate Their Effects
- 1.3.3.5.5 Design Criteria and Design Bases
- 1.3.3.5.6 Design Methodologies
- 1.3.3.5.7 Consistency of Materials with Design Methodologies
- 1.3.3.5.8 Design Codes and Standards
- 1.3.3.5.9 Design Load Combinations
- 1.3.3.6 Conformance of Design to Criteria and Bases
- 1.3.3.7 General References
- 1.3.4 Emplacement Areas of the Subsurface Facility
  - 1.3.4.1 Description of Subsurface Facility Emplacement Areas
  - 1.3.4.2 Emplacement Areas Design Description
    - 1.3.4.2.1 Design Considerations for Location of the Emplacement Areas
    - 1.3.4.2.2 Design Considerations on Faulting
    - 1.3.4.2.3 Summary of Emplacement Area Design Features
  - 1.3.4.3 Excavation
  - 1.3.4.4 Ground Support System
    - 1.3.4.4.1 System Description
      - 1.3.4.4.1.1 Design Criteria
      - 1.3.4.4.1.2 Model Selection for Ground Support Analysis
      - 1.3.4.4.1.3 Summary of Ground Support Analyses
    - 1.3.4.4.2 Operational Processes
    - 1.3.4.4.3 Design Codes and Standards
  - 1.3.4.5 Invert System
    - 1.3.4.5.1 System Description
    - 1.3.4.5.2 Operational Processes
    - 1.3.4.5.3 Safety Category Classification
    - 1.3.4.5.4 Administrative or Procedural Safety Controls to Prevent Event Sequences or Mitigate Their Effects
    - 1.3.4.5.5 Design Criteria and Design Bases
    - 1.3.4.5.6 Design Methodologies
    - 1.3.4.5.7 Consistency of Materials with Design Methodologies
    - 1.3.4.5.8 Design Codes and Standards
    - 1.3.4.5.9 Design Load Combinations
      - 1.3.4.5.9.1 Loads
      - 1.3.4.5.9.2 Load Combinations
  - 1.3.4.6 Waste Package Emplacement Pallet System
    - 1.3.4.6.1 System Description
    - 1.3.4.6.2 Operational Processes

**CONTENTS (Continued)**

- 1.3.4.6.3 Safety Category Classification
- 1.3.4.6.4 Administrative or Procedural Safety Controls to Prevent Event Sequences or Mitigate Their Effects
- 1.3.4.6.5 Design Criteria and Design Bases
  - 1.3.4.6.5.1 Preclosure Requirements for the Waste Package Emplacement Pallet
  - 1.3.4.6.5.2 Postclosure Requirements for the Waste Package Emplacement Pallet
- 1.3.4.6.6 Design Methodologies
- 1.3.4.6.7 Consistency of Materials with Design Methodologies
- 1.3.4.6.8 Design Codes and Standards
- 1.3.4.6.9 Design Load Combinations
- 1.3.4.7 Drip Shield System
  - 1.3.4.7.1 System Description
  - 1.3.4.7.2 Operational Processes
  - 1.3.4.7.3 Safety Category Classification
  - 1.3.4.7.4 Administrative or Procedural Safety Controls to Prevent Event Sequences or Mitigate Their Effects
  - 1.3.4.7.5 Design Criteria and Design Bases
  - 1.3.4.7.6 Design Methodologies
  - 1.3.4.7.7 Consistency of Materials with Design Methodologies
  - 1.3.4.7.8 Design Codes and Standards
  - 1.3.4.7.9 Design Load Combinations
- 1.3.4.8 Waste Package Emplacement System
  - 1.3.4.8.1 System Description
    - 1.3.4.8.1.1 Transport and Emplacement Vehicle Design Description
    - 1.3.4.8.1.2 Fire Protection
  - 1.3.4.8.2 Operational Processes
    - 1.3.4.8.2.1 Operational Overview
    - 1.3.4.8.2.2 Operational Sequence
    - 1.3.4.8.2.3 Transport and Emplacement Vehicle Operational Controls
    - 1.3.4.8.2.4 Monitoring Processes
    - 1.3.4.8.2.5 In-Drift Positioning of Waste Packages
  - 1.3.4.8.3 Safety Category Classification
  - 1.3.4.8.4 Administrative or Procedural Safety Controls to Prevent Event Sequences or Mitigate Their Effects
  - 1.3.4.8.5 Design Criteria and Design Bases
  - 1.3.4.8.6 Design Methodologies
  - 1.3.4.8.7 Consistency of Materials with Design Methodologies

---

**CONTENTS (Continued)**

- 1.3.4.8.8 Design Codes and Standards
- 1.3.4.8.9 Design Load Combinations
- 1.3.4.9 Conformance of Design to Criteria and Bases
- 1.3.4.10 General References
- 1.3.5 Subsurface Facility Ventilation
  - 1.3.5.1 System Description
    - 1.3.5.1.1 System Function
    - 1.3.5.1.2 System Location and Functional Arrangement
    - 1.3.5.1.3 Subsystems and Major Components
      - 1.3.5.1.3.1 Fan Installations
      - 1.3.5.1.3.2 Isolation Barriers
      - 1.3.5.1.3.3 Turnout Bulkheads, Emplacement Access Doors, and Airflow Regulators
    - 1.3.5.1.4 System Interfaces
    - 1.3.5.1.5 System Maintenance Considerations
  - 1.3.5.2 Operational Processes and Procedures
    - 1.3.5.2.1 Emplacement Access Door Operation
    - 1.3.5.2.2 Airflow Regulator Operation
  - 1.3.5.3 Safety Category Classification
    - 1.3.5.3.1 Events Leading to Ventilation Shutdown
    - 1.3.5.3.2 Analysis of Thermal Effects from a Ventilation Shutdown
      - 1.3.5.3.2.1 Complete Ventilation System Shutdown without Natural Convection Cooling
      - 1.3.5.3.2.2 Complete Ventilation System Shutdown with Natural Convection Cooling
      - 1.3.5.3.2.3 Ventilating Partially Obstructed Emplacement Drifts
    - 1.3.5.3.3 Summary of Ventilation Loss Analyses Results
    - 1.3.5.3.4 Considerations for Potential Radioactive Releases from the Subsurface Facility
  - 1.3.5.4 Design Codes and Standards
  - 1.3.5.5 Conformance of Design to Criteria and Bases
  - 1.3.5.6 General References
- 1.3.6 Subsurface Facility Closure
  - 1.3.6.1 Closure Processes
    - 1.3.6.1.1 Final Inspection of Waste Packages
    - 1.3.6.1.2 Installation of Drip Shields
    - 1.3.6.1.3 Removal of Noncommitted Materials from the Subsurface
    - 1.3.6.1.4 Placement of Backfill
      - 1.3.6.1.4.1 Placement of Backfill in Ramps

**CONTENTS (Continued)**

- 1.3.6.1.4.2 Placement of Backfill in Shafts
- 1.3.6.1.5 Regrading and Site Restoration
- 1.3.6.2 Operational Processes
- 1.3.6.3 Safety Category Classification
- 1.3.6.4 Procedural Safety Controls to Prevent Event Sequences or Mitigate Their Effects
- 1.3.6.5 Design Criteria and Design Bases
- 1.3.6.6 Design Methodologies
- 1.3.6.7 Consistency of Materials with Design Methodologies
- 1.3.6.8 Design Codes and Standards
- 1.3.6.9 Design Load Combinations
- 1.3.6.10 Conformance of Design to Criteria and Bases
- 1.3.6.11 General References
- 1.4 INFRASTRUCTURE STRUCTURES, SYSTEMS, COMPONENTS, EQUIPMENT, AND OPERATIONAL PROCESS ACTIVITIES
  - 1.4.1 Electric Power
    - 1.4.1.1 Normal Electrical Power
      - 1.4.1.1.1 System Description
        - 1.4.1.1.1.1 Switchyard
        - 1.4.1.1.1.2 Normal Power
        - 1.4.1.1.1.3 Standby Diesel Generators
        - 1.4.1.1.1.4 Normal DC Electrical Power
        - 1.4.1.1.1.5 Normal Uninterruptible Power Supply Power Subsystem
      - 1.4.1.1.2 Normal Electrical Power Operational Processes
      - 1.4.1.1.3 Normal Electrical Power Codes and Standards
    - 1.4.1.2 ITS Power
      - 1.4.1.2.1 System Description
      - 1.4.1.2.2 Operational Processes
      - 1.4.1.2.3 Safety Category Classification
      - 1.4.1.2.4 Procedural Safety Controls to Prevent Event Sequences or Mitigate Their Effects
      - 1.4.1.2.5 Design Bases and Design Criteria
      - 1.4.1.2.6 Design Methodologies
      - 1.4.1.2.7 Consistency of Materials with Design Methodologies
      - 1.4.1.2.8 Design Codes and Standards for AC and DC ITS Electrical Power
      - 1.4.1.2.9 Load Combinations Used for Normal and Category 1 and Category 2 Event Sequence Conditions
    - 1.4.1.3 ITS DC Electrical Power and Uninterruptible Power Supply

---

**CONTENTS (Continued)**

- 1.4.1.3.1 System Description
- 1.4.1.3.2 Operational Processes
- 1.4.1.3.3 Safety Category Classification
- 1.4.1.3.4 Procedural Safety Controls to Prevent Event Sequences or Mitigate Their Effects
- 1.4.1.3.5 Design Bases and Design Criteria
- 1.4.1.3.6 Design Methodologies
- 1.4.1.3.7 Consistency of Materials with Design Methodologies
- 1.4.1.3.8 Design Codes and Standards
- 1.4.1.3.9 Load Combinations Used for Normal and Category 1 and Category 2 Event Sequence Conditions
- 1.4.1.4 Electrical Support Subsystems
  - 1.4.1.4.1 Lighting
    - 1.4.1.4.1.1 Normal Lighting Subsystem
    - 1.4.1.4.1.2 Essential Lighting Subsystem
    - 1.4.1.4.1.3 Emergency Lighting Subsystem
  - 1.4.1.4.2 Grounding
  - 1.4.1.4.3 Lightning Protection
  - 1.4.1.4.4 Cathodic Protection
  - 1.4.1.4.5 Heat Tracing
  - 1.4.1.4.6 Cable Raceway
  - 1.4.1.4.7 Design Codes and Standards
- 1.4.1.5 General References
- 1.4.2 Controls and Monitoring
  - 1.4.2.1 Digital Control and Management Information
    - 1.4.2.1.1 System Description
    - 1.4.2.1.2 Operational Processes
    - 1.4.2.1.3 Design Codes and Standards
  - 1.4.2.2 Radiation/Radiological Monitoring
    - 1.4.2.2.1 System Description
    - 1.4.2.2.2 Design Codes and Standards
  - 1.4.2.3 Environmental/Meteorological Monitoring System
    - 1.4.2.3.1 System Description
    - 1.4.2.3.2 Operational Processes
    - 1.4.2.3.3 Design Codes and Standards
  - 1.4.2.4 Communications
    - 1.4.2.4.1 System Description
      - 1.4.2.4.1.1 Data Subsystem
      - 1.4.2.4.1.2 Video Subsystem

**CONTENTS (Continued)**

- 1.4.2.4.1.3 Voice Subsystem
- 1.4.2.4.1.4 Network Subsystem
- 1.4.2.4.1.5 Transport Subsystem
- 1.4.2.4.1.6 Security
- 1.4.2.4.1.7 Facilities
- 1.4.2.4.1.8 System Interfaces
- 1.4.2.4.2 Communications Processes
  - 1.4.2.4.2.1 Communications with Transport and Emplacement Vehicle
  - 1.4.2.4.2.2 Emergency Communications
- 1.4.2.4.3 Design Codes and Standards
- 1.4.2.5 Postevent Monitoring
  - 1.4.2.5.1 Description
  - 1.4.2.5.2 Operational Processes
  - 1.4.2.5.3 Design Codes and Standards
- 1.4.2.6 General References
- 1.4.3 Fire Protection
  - 1.4.3.1 Fire Hazard Analyses
    - 1.4.3.1.1 Scope
    - 1.4.3.1.2 Analysis Methodology
  - 1.4.3.2 Fire Protection System Description
    - 1.4.3.2.1 Fire Protection System for Surface Facilities
      - 1.4.3.2.1.1 Fire Water Subsystem for Surface Facilities
      - 1.4.3.2.1.2 Fire Suppression Subsystem for Surface Facilities
      - 1.4.3.2.1.3 Fire Detection and Alarm Subsystems for Surface Facilities
      - 1.4.3.2.1.4 Fire Barrier Subsystem in Surface Facilities
    - 1.4.3.2.2 Fire Protection System for the Subsurface Emplacement Area
      - 1.4.3.2.2.1 Fire Suppression Subsystem for Subsurface Emplacement Areas
      - 1.4.3.2.2.2 Fire Detection and Alarm Subsystems for Subsurface Emplacement Area
      - 1.4.3.2.2.3 Fire Barrier Subsystem in the Subsurface
      - 1.4.3.2.2.4 Subsurface Layout Description
      - 1.4.3.2.2.5 Subsurface Life Safety Considerations
  - 1.4.3.3 Operational Processes
    - 1.4.3.3.1 Surface Fire Protection
    - 1.4.3.3.2 Subsurface Fire Protection
  - 1.4.3.4 Design Codes and Standards

---

**CONTENTS (Continued)**

- 1.4.3.5 Fire Protection Program
  - 1.4.3.5.1 Purpose
  - 1.4.3.5.2 Organization
  - 1.4.3.5.3 Qualifications for Fire Protection during Operations
  - 1.4.3.5.4 System Design
  - 1.4.3.5.5 Inspection, Testing, and Maintenance
  - 1.4.3.5.6 Operability Requirements, Impairments, and Compensatory Measures
  - 1.4.3.5.7 Fire Prevention
  - 1.4.3.5.8 Emergency Response
- 1.4.3.6 General References
- 1.4.4 Plant Services
  - 1.4.4.1 General Purpose and Instrument Air Subsystems
    - 1.4.4.1.1 System Description
    - 1.4.4.1.2 Operational Processes
    - 1.4.4.1.3 Design Codes and Standards
  - 1.4.4.2 Service Gases Subsystems
    - 1.4.4.2.1 System Description
    - 1.4.4.2.2 Operational Processes
    - 1.4.4.2.3 Design Codes and Standards
  - 1.4.4.3 Fuel Oil Subsystem
    - 1.4.4.3.1 System Description
    - 1.4.4.3.2 Operational Processes
    - 1.4.4.3.3 Design Codes and Standards
  - 1.4.4.4 Raw, Potable, and Deionized Water Subsystems
    - 1.4.4.4.1 System Description
    - 1.4.4.4.2 Operational Processes
    - 1.4.4.4.3 Design Codes and Standards
  - 1.4.4.5 Hot Water Heating and Chilled Water Cooling Subsystems
    - 1.4.4.5.1 System Description
    - 1.4.4.5.2 Operational Processes
    - 1.4.4.5.3 Design Codes and Standards
  - 1.4.4.6 General References
- 1.4.5 Waste Management
  - 1.4.5.1 Low-Level Radioactive Waste Management
    - 1.4.5.1.1 Description
      - 1.4.5.1.1.1 Solid Low-Level Radioactive Waste Management
      - 1.4.5.1.1.2 Liquid Low-Level Radioactive Waste Management
      - 1.4.5.1.1.3 Gaseous Low-Level Radioactive Waste Management



**CONTENTS (Continued)**

- 1.4.5.1.1.4 Mixed Waste Management
- 1.4.5.1.2 Operational Processes
- 1.4.5.1.3 Design Codes and Standards
- 1.4.5.2 Nonradiological Waste Management
  - 1.4.5.2.1 Description
  - 1.4.5.2.2 Operational Processes
  - 1.4.5.2.3 Design Codes and Standards
- 1.4.5.3 General References
- 1.5 WASTE FORM AND WASTE PACKAGE
  - 1.5.1 Characteristics of Spent Nuclear Fuel and High-Level Radioactive Waste
    - 1.5.1.1 Commercial SNF
      - 1.5.1.1.1 Physical Characteristics of Commercial SNF and Canisters
        - 1.5.1.1.1.1 Physical Characteristics of Commercial SNF
        - 1.5.1.1.1.2 Physical Characteristics of Commercial SNF Canisters
          - 1.5.1.1.1.2.1 Commercial SNF Canister Description
            - 1.5.1.1.1.2.1.1 Damaged-Fuel Cans
            - 1.5.1.1.1.2.1.2 Dual-Purpose Canisters
            - 1.5.1.1.1.2.1.3 Transportation, Aging, and Disposal Canisters
            - 1.5.1.1.1.2.1.4 TAD Canister General Characteristics
          - 1.5.1.1.1.2.2 TAD Canister Operational Processes
            - 1.5.1.1.1.2.2.1 TAD Canister Thermal Controls
            - 1.5.1.1.1.2.2.2 TAD Canister Criticality Controls
          - 1.5.1.1.1.2.3 Structures, Systems, and Components Important to Safety and Important to Waste Isolation
          - 1.5.1.1.1.2.4 Procedural Safety Controls to Prevent Event Sequences and Mitigate Their Effects
          - 1.5.1.1.1.2.5 Design Criteria and Design Bases
            - 1.5.1.1.1.2.5.1 Structural Design Criteria and Design Basis
            - 1.5.1.1.1.2.5.2 Criticality Safety Design Criteria and Design Basis
            - 1.5.1.1.1.2.5.3 Thermal Design Criteria and Design Basis
        - 1.5.1.1.1.2.6 Design Methodologies
          - 1.5.1.1.1.2.6.1 Structural Design
            - 1.5.1.1.1.2.6.1.1 TAD Canister Structural Characteristics
            - 1.5.1.1.1.2.6.1.2 TAD Canister Containment Characteristics
            - 1.5.1.1.1.2.6.1.3 TAD Canister Characteristics as Developed in the SAR or at Vendor
          - 1.5.1.1.1.2.6.2 Thermal Design
          - 1.5.1.1.1.2.6.3 Nuclear Criticality Safety of Commercial

**CONTENTS (Continued)**

- SNF
  - 1.5.1.1.1.2.6.4 TAD Canister Dose and Shielding Characteristics
  - 1.5.1.1.1.2.7 Consistency of Materials with Design Basis
  - 1.5.1.1.1.2.8 Design Codes and Standards
- 1.5.1.1.2 Thermal Characteristics of Commercial SNF
- 1.5.1.1.3 Nuclear Characteristics of Commercial SNF
- 1.5.1.1.4 Source-Term Characteristics of Commercial SNF
- 1.5.1.1.5 TAD Canister and DPC Conformance of Design to Criteria and Bases
- 1.5.1.2 High-Level Radioactive Waste
  - 1.5.1.2.1 Physical Characteristics of HLW and HLW Canisters
    - 1.5.1.2.1.1 Physical Characteristics of HLW
    - 1.5.1.2.1.2 Physical Characteristics of HLW Canister
      - 1.5.1.2.1.2.1 HLW Canister Description
      - 1.5.1.2.1.2.2 HLW Canister Operational Processes
      - 1.5.1.2.1.2.3 Canister Thermal Controls
      - 1.5.1.2.1.2.4 Canister Criticality Controls
    - 1.5.1.2.1.3 Structures, Systems, and Components Important to Safety and Important to Waste Isolation
    - 1.5.1.2.1.4 Procedural Safety Controls to Prevent Event Sequences or Mitigate Their Effect
    - 1.5.1.2.1.5 Design Criteria and Design Bases
    - 1.5.1.2.1.6 Consistency of Materials with Design Methodologies
    - 1.5.1.2.1.7 Design Codes and Standards
  - 1.5.1.2.2 Thermal Characteristics of HLW
  - 1.5.1.2.3 Nuclear Characteristics of HLW
  - 1.5.1.2.4 Source-Term Characteristics of HLW
  - 1.5.1.2.5 Conformance of Design to Criteria and Bases
- 1.5.1.3 DOE SNF
  - 1.5.1.3.1 Physical Characteristics of DOE SNF and Disposal Canisters
    - 1.5.1.3.1.1 Physical Characteristics of DOE SNF
      - 1.5.1.3.1.1.1 First Tier Grouping of DOE SNF
      - 1.5.1.3.1.1.2 Preclosure Releases Grouping of DOE SNF
      - 1.5.1.3.1.1.3 Criticality Evaluation Grouping of DOE SNF
      - 1.5.1.3.1.1.4 TSPA Grouping of DOE SNF
    - 1.5.1.3.1.2 Physical Characteristics of DOE SNF Canisters
      - 1.5.1.3.1.2.1 Canister Description
        - 1.5.1.3.1.2.1.1 Standardized Canister Shell
        - 1.5.1.3.1.2.1.2 Standardized Canister Internals

**CONTENTS (Continued)**

- 1.5.1.3.1.2.1.3 Multicanister Overpack Shell
- 1.5.1.3.1.2.1.4 Multicanister Overpack Internals
- 1.5.1.3.1.2.2 Operational Processes
  - 1.5.1.3.1.2.2.1 Standardized Canisters
  - 1.5.1.3.1.2.2.2 Multicanister Overpack
- 1.5.1.3.1.2.3 SSCs Important to Safety and Important to Waste Isolation
- 1.5.1.3.1.2.4 Procedural Safety Controls to Prevent Event Sequences or Mitigate Their Effects
- 1.5.1.3.1.2.5 Design Criteria and Design Bases
  - 1.5.1.3.1.2.5.1 Structural Design Criteria
  - 1.5.1.3.1.2.5.2 Criticality Control Design Criteria
- 1.5.1.3.1.2.6 Design Methodologies
  - 1.5.1.3.1.2.6.1 Structural Design
  - 1.5.1.3.1.2.6.2 Criticality Design
- 1.5.1.3.1.2.7 Consistency of Materials with Design Methodologies
- 1.5.1.3.1.2.8 Design Codes and Standards
  - 1.5.1.3.1.2.8.1 Standardized Canisters
  - 1.5.1.3.1.2.8.2 Multicanister Overpacks
- 1.5.1.3.1.2.9 Design Load Combinations
- 1.5.1.3.1.2.10 Weld and Material Flaws and Degraded Canisters
- 1.5.1.3.2 Thermal Characteristics of DOE SNF
- 1.5.1.3.3 Nuclear Characteristics of DOE SNF
- 1.5.1.3.4 Source-Term Characteristics of DOE SNF
- 1.5.1.3.5 Conformance of Design to Criteria and Bases
- 1.5.1.4 Naval SNF
  - 1.5.1.4.1 Physical Characteristics of Naval SNF and Canisters
    - 1.5.1.4.1.1 Physical Characteristics of Naval SNF
    - 1.5.1.4.1.2 Physical Characteristics of Naval SNF Canisters
      - 1.5.1.4.1.2.1 Naval SNF Canister Description
      - 1.5.1.4.1.2.2 Operational Processes for Naval SNF Canisters
        - 1.5.1.4.1.2.2.1 Naval SNF Canister Thermal Controls
        - 1.5.1.4.1.2.2.2 Naval SNF Canister Criticality Controls
      - 1.5.1.4.1.2.3 Structures, Systems, and Components Important to Safety and Important to Waste Isolation
      - 1.5.1.4.1.2.4 Procedural Safety Controls to Prevent Event Sequences or Mitigate Their Effects
      - 1.5.1.4.1.2.5 Design Criteria and Design Bases
        - 1.5.1.4.1.2.5.1 Structural Design Criteria and Design Bases

**CONTENTS (Continued)**

- 1.5.1.4.1.2.5.2 Criticality Safety Design Criteria and Design Bases
- 1.5.1.4.1.2.5.3 Thermal Design Criteria and Design Bases
- 1.5.1.4.1.2.6 Design Methodologies
  - 1.5.1.4.1.2.6.1 Structural Design
  - 1.5.1.4.1.2.6.2 Thermal Design
  - 1.5.1.4.1.2.6.3 Criticality Safety Design
  - 1.5.1.4.1.2.6.4 Radiation Sources
  - 1.5.1.4.1.2.7 Consistency of Materials with Design Methodologies
  - 1.5.1.4.1.2.8 Design Codes and Standards
- 1.5.1.4.2 Thermal Characteristics of Naval SNF
- 1.5.1.4.3 Nuclear Characteristics of Naval SNF
- 1.5.1.4.4 Source Term Characteristics of Naval SNF
- 1.5.1.4.5 Naval SNF Canister Conformance of Design to Criteria and Bases
- 1.5.1.5 General References
- 1.5.2 Waste Packages and Their Components
  - 1.5.2.1 Waste Package Description
    - 1.5.2.1.1 Waste Package Configurations
    - 1.5.2.1.2 Waste Package Configurations for Commercial SNF
      - 1.5.2.1.2.1 Internal Design
      - 1.5.2.1.2.2 Transportation, Aging, and Disposal Waste Package Specifications
    - 1.5.2.1.3 Waste Package Configurations for HLW and DOE SNF
      - 1.5.2.1.3.1 Internal Design
      - 1.5.2.1.3.2 HLW and DOE SNF Waste Package Specifications
    - 1.5.2.1.4 Waste Package Configurations for Naval SNF
      - 1.5.2.1.4.1 Internal Design
      - 1.5.2.1.4.2 Naval SNF Waste Package Specifications
  - 1.5.2.2 Operational Processes and Procedures
    - 1.5.2.2.1 Waste Package Loading to Satisfy Thermal Requirements
    - 1.5.2.2.2 Waste Package Loading to Satisfy Criticality Requirements
    - 1.5.2.2.3 Inerting
  - 1.5.2.3 Considerations Important to Safety and Important to Waste Isolation
    - 1.5.2.3.1 Structures, Systems, and Components Important to Safety
    - 1.5.2.3.2 Structures, Systems, and Components Important to Waste Isolation
  - 1.5.2.4 Design Bases and Design Criteria

**CONTENTS (Continued)**

- 1.5.2.5 Procedural Safety Controls to Prevent Event Sequences or Mitigate Their Effects
  - 1.5.2.6 Design Methodologies
    - 1.5.2.6.1 Structural Design
      - 1.5.2.6.1.1 Structural Design Methodology
      - 1.5.2.6.1.2 Structural Analysis Software
      - 1.5.2.6.1.3 Finite-Element Mesh Discretization
      - 1.5.2.6.1.4 Load Combinations
      - 1.5.2.6.1.5 Basis for Acceptance Criteria
      - 1.5.2.6.1.6 Acceptance Criteria
      - 1.5.2.6.1.7 Cases
      - 1.5.2.6.1.8 Structural Analysis Results for Normal Loads
      - 1.5.2.6.1.9 Structural Analysis Results for Event Sequences
    - 1.5.2.6.2 Radiation Shielding Methodology
    - 1.5.2.6.3 Waste Package Prototype Program
  - 1.5.2.7 Consistency of Materials with Design Methodologies
    - 1.5.2.7.1 Fabrication Materials and Process
    - 1.5.2.7.2 Lid Closure Processes
      - 1.5.2.7.2.1 Welding Requirements
      - 1.5.2.7.2.2 Stress Mitigation of Closure Welds
    - 1.5.2.7.3 Nondestructive Examination
      - 1.5.2.7.3.1 Fabrication Nondestructive Examination
      - 1.5.2.7.3.2 Closure Weld Nondestructive Examination
    - 1.5.2.7.4 Fabrication Pressure Testing
    - 1.5.2.7.5 Fabrication Helium Leakage Test for Inner Vessel
  - 1.5.2.8 Design Codes and Standards
  - 1.5.2.9 General References
- 1.6 IDENTIFICATION OF HAZARDS AND INITIATING EVENTS
- 1.6.1 Overview of Preclosure Safety Analysis
    - 1.6.1.1 Internal and External Event Identification
    - 1.6.1.2 Internal and External Initiating Event Screening
    - 1.6.1.3 Event Sequence Development
    - 1.6.1.4 Event Sequence Quantification and Categorization
    - 1.6.1.5 Dose Consequence Analysis
    - 1.6.1.6 Criticality Safety Analysis
    - 1.6.1.7 Identification of Structures, Systems, and Components Important to Safety and Waste Isolation and Nuclear Safety Design Bases
  - 1.6.2 Applications of Preclosure Safety Analyses
  - 1.6.3 Identification and Screening of Initiating Events
-

---

**CONTENTS (Continued)**

- 1.6.3.1 Identification of Internal Initiating Events
  - 1.6.3.1.1 Master Logic Diagrams
  - 1.6.3.1.2 Process Flow Diagrams
  - 1.6.3.1.3 Hazard and Operability Evaluation
  - 1.6.3.1.4 Interrelationship between Hazard and Operability Evaluation and Master Logic Diagram
- 1.6.3.2 Identification of External Initiating Events
- 1.6.3.3 Results of Internal and External Initiating Event Identification
- 1.6.3.4 Methodology and Results of External Initiating Event Screening
  - 1.6.3.4.1 Aircraft Impact
  - 1.6.3.4.2 Nonseismic Geologic Activity
  - 1.6.3.4.3 Volcanic Activity
  - 1.6.3.4.4 High Winds and Tornadoes
  - 1.6.3.4.5 External Floods
  - 1.6.3.4.6 Lightning
  - 1.6.3.4.7 Loss of Cooling Capability
  - 1.6.3.4.8 Nearby Industrial or Military Facility Accidents
  - 1.6.3.4.9 Onsite Hazardous Material Release
  - 1.6.3.4.10 External Fires
  - 1.6.3.4.11 Extraterrestrial Activity
- 1.6.3.5 Construction Hazard Event Screening
- 1.6.4 Summary of Initiating Events Included in Event Sequence Analysis
- 1.6.5 General References
- 1.7 EVENT SEQUENCE ANALYSIS
  - 1.7.1 Event Sequence Development and Categorization Methodology
    - 1.7.1.1 Event Sequence Diagrams and Event Trees
    - 1.7.1.2 Internal Events
      - 1.7.1.2.1 Event Sequences Initiated by Internal Random Initiating Events
      - 1.7.1.2.2 Event Sequences Initiated by Fire Events
      - 1.7.1.2.3 Event Sequences Initiated by Flooding Events
    - 1.7.1.3 External Events
    - 1.7.1.4 Seismic Events
  - 1.7.2 Reliability Methods
    - 1.7.2.1 Fault Tree Analysis
    - 1.7.2.2 Active System or Component Reliability
    - 1.7.2.3 Passive Structure, System, or Component Reliability
      - 1.7.2.3.1 Loss of Containment of Waste Form Container by Structural Challenge

**CONTENTS (Continued)**

- 1.7.2.3.2 Degradation or Loss of Shielding of Structure, System or Component by Structural Challenge
- 1.7.2.3.3 Loss of Containment of Waste Form Container by Thermal Challenge
  - 1.7.2.3.3.1 Loss of Containment by Fire
  - 1.7.2.3.3.2 Loss of Containment by Other Thermal Events
- 1.7.2.3.4 Degradation or Loss of Shielding of Structure, System or Component by Thermal Challenge
- 1.7.2.4 Seismic Fragilities
- 1.7.2.5 Human Reliability Analysis
- 1.7.3 Event Sequence Quantification
- 1.7.4 Event Sequence Grouping
- 1.7.5 Event Sequence Categorization
  - 1.7.5.1 Initial Handling Facility
  - 1.7.5.2 Receipt Facility
  - 1.7.5.3 Canister Receipt and Closure Facility
  - 1.7.5.4 Wet Handling Facility
  - 1.7.5.5 Intrasite Operations and Balance of Plant
  - 1.7.5.6 Subsurface
- 1.7.6 General References
- 1.8 CONSEQUENCE ANALYSIS
  - 1.8.1 Methodology for Dose Estimates
    - 1.8.1.1 Dose Estimate Methodology
    - 1.8.1.2 Dose Aggregation
    - 1.8.1.3 Source-Term Released Inputs
      - 1.8.1.3.1 Material at Risk
      - 1.8.1.3.2 Damage Ratio
      - 1.8.1.3.3 Release and Respirable Fractions
      - 1.8.1.3.4 Release Fractions for a Seismic Event
      - 1.8.1.3.5 Release Fractions for a Fire Event
      - 1.8.1.3.6 Leak Path Factors
    - 1.8.1.4 Other Dose Estimate Inputs
      - 1.8.1.4.1 Dose Coefficients
      - 1.8.1.4.2 Atmospheric Dispersion Factors
      - 1.8.1.4.3 Location of Maximum Offsite and Onsite Dose Receptors
      - 1.8.1.4.4 Site-Specific Input Parameters
  - 1.8.2 Potential Releases and Direct Radiation from Normal Operations and Category 1 and Category 2 Event Sequences
    - 1.8.2.1 Repository Operations

---

**CONTENTS (Continued)**

- 1.8.2.2 Normal Operations
  - 1.8.2.2.1 Potential Releases from Normal Surface Operations
  - 1.8.2.2.2 Potential Releases from Normal Subsurface Operations
  - 1.8.2.2.3 Potential Direct Radiation from Normal Operations
- 1.8.2.3 Description of Category 1 Event Sequences
- 1.8.2.4 Description of Category 2 Event Sequences
- 1.8.3 Potential Dose to Members of the Public from Normal Operations and Category 1 and Category 2 Event Sequences
  - 1.8.3.1 Public Dose Methodology
    - 1.8.3.1.1 Computer Code Used in Public Dose Calculations for Airborne Releases
    - 1.8.3.1.2 Public Airborne Release Dose Methodology
    - 1.8.3.1.3 Public Direct Radiation Methodology
  - 1.8.3.2 Potential Public Dose Results
    - 1.8.3.2.1 Potential Doses to Members of the Public from Normal Operations and Category 1 Event Sequences
    - 1.8.3.2.2 Potential Doses to Members of the Public from Category 2 Event Sequences
    - 1.8.3.2.3 Potential Doses to Members of the Public Being As Low As Is Reasonably Achievable
- 1.8.4 Potential Doses to Radiation Workers from Normal Operations and Category 1 Event Sequences
  - 1.8.4.1 Radiation Worker Dose Methodology
    - 1.8.4.1.1 Potential Radiation Worker Dose from Airborne Releases
    - 1.8.4.1.2 Potential Radiation Worker Dose from Resuspension of Surface Contamination
    - 1.8.4.1.3 Potential Radiation Worker Dose from Direct Radiation
  - 1.8.4.2 Potential Worker Dose Results
    - 1.8.4.2.1 Normal Operations
      - 1.8.4.2.1.1 Potential Radiation Worker Doses outside Facilities in the GROA
      - 1.8.4.2.1.2 Potential Radiation Worker Dose from Direct Radiation
    - 1.8.4.2.2 Category 1 Event Sequences
      - 1.8.4.2.2.1 Potential Surface Facility Radiation Worker Dose
      - 1.8.4.2.2.2 Potential Subsurface Facility Radiation Worker Dose
    - 1.8.4.2.3 Sum of Potential Radiation Worker Doses from Normal Operations and Category 1 Event Sequences
- 1.8.5 Uncertainty Analysis
  - 1.8.5.1 Use of Conservative or Bounding Input Parameters
    - 1.8.5.1.1 Normal Operations



**CONTENTS (Continued)**

- 1.8.5.1.2 Category 1 and Category 2 Event Sequences
- 1.8.5.1.3 Common Conservatism or Bounding Inputs
- 1.8.5.2 Uncertainty Analysis with GENII
- 1.8.5.3 Radionuclide and Input Parameter Screening
  - 1.8.5.3.1 Radionuclide Screening
  - 1.8.5.3.2 Input Parameter Screening
    - 1.8.5.3.2.1 Pathway Analysis for Input Parameter Screening
    - 1.8.5.3.2.2 Input Parameters Selected for Uncertainty Analysis
- 1.8.5.4 Uncertainty Analysis for a Chronic Release
  - 1.8.5.4.1 Radionuclide Dose Uncertainty for Chronic Release
  - 1.8.5.4.2 Input Parameter Rank Correlation Coefficients for Chronic Release
  - 1.8.5.4.3 Uncertainty Analysis for Chronic Release
- 1.8.5.5 Uncertainty Analysis for an Acute Release
  - 1.8.5.5.1 Radionuclide Dose Uncertainty for Acute Release
  - 1.8.5.5.2 Input Parameter Rank Correlation Coefficients for Acute Release
  - 1.8.5.5.3 Uncertainty Analysis for Acute Releases
- 1.8.5.6 Conclusions
- 1.8.6 Summary of Potential Public and Worker Dose Consequences and Compliance Confirmation
- 1.8.7 General References
- 1.9 STRUCTURES, SYSTEMS, AND COMPONENTS IMPORTANT TO SAFETY; NATURAL AND ENGINEERED BARRIERS IMPORTANT TO WASTE ISOLATION; SAFETY CONTROLS; AND MEASURES TO ENSURE AVAILABILITY OF THE SAFETY SYSTEMS
  - 1.9.1 Structures, Systems, and Components Classified as Important to Safety
    - 1.9.1.1 Means to Limit Concentration of Radioactive Material in Air
    - 1.9.1.2 Means to Limit Time Required to Perform Work in Radiological Areas
    - 1.9.1.3 Suitable Shielding
    - 1.9.1.4 Means to Monitor and Control Dispersal of Radioactive Contamination
    - 1.9.1.5 Means to Control Access to High Radiation Areas or Airborne Radioactivity Areas
    - 1.9.1.6 Means to Prevent and Control Criticality
    - 1.9.1.7 Radiation Alarm System
    - 1.9.1.8 Ability of Structures, Systems, and Components to Perform Their Intended Safety Functions
    - 1.9.1.9 Explosion and Fire Detection and Suppression Systems

---

**CONTENTS (Continued)**

- 1.9.1.10 Means to Control Radioactive Waste and Effluents and to Permit Prompt Termination of Operations and Evacuation of Personnel during an Emergency
- 1.9.1.11 Electrical Power
- 1.9.1.12 Redundant Systems and Inherent Reliability
- 1.9.1.13 Inspection, Test, and Maintenance Programs
- 1.9.1.14 ITS Structure, System, or Component/Non-ITS Structure, System, or Component Interactions
- 1.9.2 Identifying Postclosure Performance Assessment Design Control Parameters and Classifying ITWI Structures, Systems, and Components
- 1.9.3 Procedural Safety Controls
- 1.9.4 Risk Significance Categorization
- 1.9.5 General References
- 1.10 MEETING THE AS LOW AS IS REASONABLY ACHIEVABLE REQUIREMENTS FOR NORMAL OPERATIONS AND CATEGORY 1 EVENT SEQUENCES
  - 1.10.1 Management Commitment to Maintain Doses As Low As Is Reasonably Achievable
    - 1.10.1.1 Design and Construction
    - 1.10.1.2 Operation
    - 1.10.1.3 Decommissioning
  - 1.10.2 As Low As Is Reasonably Achievable Principles in Design
    - 1.10.2.1 General Considerations
      - 1.10.2.1.1 Design Objectives
      - 1.10.2.1.2 Design Considerations
      - 1.10.2.1.3 Implementation
        - 1.10.2.1.3.1 Policy and Procedures
        - 1.10.2.1.3.2 Training
        - 1.10.2.1.3.3 Design Reviews
        - 1.10.2.1.3.4 Cost–Benefit Analysis
        - 1.10.2.1.3.5 Self-Assessments
    - 1.10.2.2 Facility Layout Considerations
      - 1.10.2.2.1 Design Objectives
      - 1.10.2.2.2 Design Considerations
      - 1.10.2.2.3 Facility ALARA Features
    - 1.10.2.3 Equipment Design Considerations
      - 1.10.2.3.1 Design Objectives
      - 1.10.2.3.2 Design Considerations
      - 1.10.2.3.3 Features for Maintenance and Inspection
      - 1.10.2.3.4 Features of Shield Doors, Slide Gates, and Viewing Windows
    - 1.10.2.4 Access Control Considerations

**CONTENTS (Continued)**

- 1.10.2.5 Radiation Zones
- 1.10.2.6 Contamination Control
- 1.10.2.7 Ventilation Considerations
  - 1.10.2.7.1 Design Objectives
  - 1.10.2.7.2 Design Considerations
  - 1.10.2.7.3 HVAC Equipment
- 1.10.2.8 Radiation and Airborne Radioactivity Monitoring Instrumentation
  - 1.10.2.8.1 Design Objectives
- 1.10.2.9 Event Sequence Considerations
- 1.10.2.10 Decommissioning
- 1.10.2.11 Dose Assessment Considerations
  - 1.10.2.11.1 Radiation Workers
  - 1.10.2.11.2 Construction Workers
  - 1.10.2.11.3 Public
- 1.10.3 Surface and Subsurface Shielding Design
  - 1.10.3.1 Shielding Design Objectives
    - 1.10.3.1.1 Shielding Design Considerations
  - 1.10.3.2 Calculation Methodology and Computer Codes
  - 1.10.3.3 Radiation Sources
    - 1.10.3.3.1 Spent Nuclear Fuel and High-Level Radioactive Waste Containers
      - 1.10.3.3.1.1 Transportation Casks
        - 1.10.3.3.1.1.1 Rail
        - 1.10.3.3.1.1.2 Truck
      - 1.10.3.3.1.2 Transportation, Aging, and Disposal Canister
      - 1.10.3.3.1.3 Dual-Purpose Canister
      - 1.10.3.3.1.4 Naval SNF Canister
      - 1.10.3.3.1.5 DOE Spent Nuclear Fuel Canister
      - 1.10.3.3.1.6 High-Level Radioactive Waste Canister
      - 1.10.3.3.1.7 Aging Overpack and Shielded Transfer Cask
      - 1.10.3.3.1.8 HLW and SNF Waste Packages
      - 1.10.3.3.1.9 TAD Waste Packages
      - 1.10.3.3.1.10 Naval Waste Packages
    - 1.10.3.3.2 Waste Forms Received for Disposal
      - 1.10.3.3.2.1 Commercial Spent Nuclear Fuel
      - 1.10.3.3.2.2 Naval Spent Nuclear Fuel
      - 1.10.3.3.2.3 DOE Spent Nuclear Fuel
      - 1.10.3.3.2.4 DOE High-Level Radioactive Waste
    - 1.10.3.3.3 Low-Level Radioactive Waste

**CONTENTS (Continued)**

- 1.10.3.3.3.1 Pool Water Treatment System Filter Cartridges
- 1.10.3.3.3.2 Pool Water Treatment System Spent Resins
- 1.10.3.3.3.3 Liquid Low-Level Radioactive Waste
- 1.10.3.3.3.4 Dry Active Wastes
- 1.10.3.3.3.5 Empty DPCs and Miscellaneous Items
- 1.10.3.4 Source Terms
  - 1.10.3.4.1 Commercial SNF
  - 1.10.3.4.2 Naval Spent Nuclear Fuel
  - 1.10.3.4.3 DOE Spent Nuclear Fuel
  - 1.10.3.4.4 DOE High-Level Radioactive Waste
  - 1.10.3.4.5 Low-Level Radioactive Waste
- 1.10.3.5 Shielding Evaluation of Surface Repository Areas
  - 1.10.3.5.1 Open Areas
    - 1.10.3.5.1.1 Cask Receipt Security Station
    - 1.10.3.5.1.2 Aging Facility
    - 1.10.3.5.1.3 Buffer Areas
    - 1.10.3.5.1.4 Movement Corridors
  - 1.10.3.5.2 Initial Handling Facility
  - 1.10.3.5.3 Canister Receipt and Closure Facility
  - 1.10.3.5.4 Receipt Facility
  - 1.10.3.5.5 Wet Handling Facility
  - 1.10.3.5.6 Low-Level Waste Facility
  - 1.10.3.5.7 Common Shielding Features
    - 1.10.3.5.7.1 Shield Doors
    - 1.10.3.5.7.2 Shielded Viewing Windows
    - 1.10.3.5.7.3 Slide Gates
    - 1.10.3.5.7.4 Canister Transfer Machine
    - 1.10.3.5.7.5 Transfer Trolley
- 1.10.3.6 Shielding Evaluation of Subsurface Repository Areas
  - 1.10.3.6.1 Transport and Emplacement Vehicle
- 1.10.3.7 Event Sequence Considerations
- 1.10.4 As Low As Is Reasonably Achievable Principles in Operations
  - 1.10.4.1 Operational ALARA Considerations
    - 1.10.4.1.1 ALARA Program Administration
    - 1.10.4.1.2 Design Change Review
    - 1.10.4.1.3 ALARA Training
    - 1.10.4.1.4 General ALARA Guidelines
    - 1.10.4.1.5 Administrative Controls to Maintain Doses ALARA
    - 1.10.4.1.6 Task Planning and Preparation

**CONTENTS (Continued)**

- 1.10.4.1.7 Radiation Surveys
- 1.10.4.1.8 Housekeeping
- 1.10.4.2 Operational Radiation Protection Program
- 1.10.4.3 Recovery from Event Sequences
- 1.10.4.4 Decommissioning
- 1.10.5 General References
- 1.11 PLANS FOR RETRIEVAL AND ALTERNATE STORAGE OF RADIOACTIVE WASTES
  - 1.11.1 Retrieval Plans
    - 1.11.1.1 Operational Equipment and Processes
      - 1.11.1.1.1 Retrieval Equipment
        - 1.11.1.1.1.1 Mobile Equipment
        - 1.11.1.1.1.2 Surface Facilities
      - 1.11.1.1.2 Retrieval Operations Overview
    - 1.11.1.2 Identification of Design and Operational Conditions for Retrieval
      - 1.11.1.2.1 Considerations of Conditions Beyond the Licensing Bases
      - 1.11.1.2.2 Potential Retrieval Interference
      - 1.11.1.2.3 Methodologies for Identifying and Analyzing Potential Retrieval Problems
      - 1.11.1.2.4 Repository Conditions
        - 1.11.1.2.4.1 Subsurface Facility
        - 1.11.1.2.4.2 Mobile Equipment
        - 1.11.1.2.4.3 Surface Facilities
      - 1.11.1.2.5 Maintenance Plans
        - 1.11.1.2.5.1 Ground Support Maintenance
        - 1.11.1.2.5.2 Equipment Maintenance
      - 1.11.1.2.6 Backfill Option
      - 1.11.1.2.7 Performance Confirmation Program Effects
    - 1.11.1.3 Compliance with Preclosure Performance Objectives
      - 1.11.1.3.1 Preclosure Performance
      - 1.11.1.3.2 Implementation of As Low As Is Reasonably Achievable Concepts
  - 1.11.2 Alternate Storage Plans
    - 1.11.2.1 Alternate Storage Facility Location
    - 1.11.2.2 Alternate Storage Facility Size and Operations
      - 1.11.2.2.1 Alternate Storage Facility Size
      - 1.11.2.2.2 Alternate Storage Facility Operations
    - 1.11.2.3 Public and Repository Worker Safety
  - 1.11.3 Retrieval Operations Schedule

---

**CONTENTS (Continued)**

- 1.11.4 General References
- 1.12 PLANS FOR PERMANENT CLOSURE, DECONTAMINATION, AND DISMANTLEMENT OF SURFACE FACILITIES
  - 1.12.1 Design Considerations to Facilitate Permanent Closure and Dismantlement
  - 1.12.2 Plans for Permanent Closure
  - 1.12.3 Plans for Decontamination and Dismantlement of Surface Facilities
    - 1.12.3.1 Facility Operating History
    - 1.12.3.2 Facility Description
    - 1.12.3.3 Radiological Status of the Facility
      - 1.12.3.3.1 Structures and Buildings
      - 1.12.3.3.2 Systems and Components
      - 1.12.3.3.3 Soil Contamination
      - 1.12.3.3.4 Potential Water Contamination from Process Operations
    - 1.12.3.4 Dose Modeling Evaluations
    - 1.12.3.5 Alternatives for Decontamination and Dismantlement
    - 1.12.3.6 As Low As Is Reasonably Achievable Analyses
    - 1.12.3.7 Planned Decontamination and Dismantlement Activities
      - 1.12.3.7.1 Contaminated Structures
      - 1.12.3.7.2 Contaminated Systems and Components
      - 1.12.3.7.3 Contaminated Soil
      - 1.12.3.7.4 Surface Water
      - 1.12.3.7.5 Schedules
    - 1.12.3.8 Project Management and Organization
      - 1.12.3.8.1 Management Organization
      - 1.12.3.8.2 Decontamination and Dismantlement Task Management
      - 1.12.3.8.3 Decontamination and Dismantlement Management Positions and Qualifications
      - 1.12.3.8.4 Training
    - 1.12.3.9 Radiological Health and Safety Program during Decontamination and Dismantlement
    - 1.12.3.10 Environmental Monitoring and Control Program
    - 1.12.3.11 Low-Level Radioactive Waste Management Program
      - 1.12.3.11.1 Preliminary Estimates of the Types and Quantities of Low-Level Radioactive Waste
      - 1.12.3.11.2 Preliminary Plans for Minimizing and Disposing of the Quantities of Low-Level Radioactive Waste
    - 1.12.3.12 Quality Assurance Program
    - 1.12.3.13 Facility Radiation Surveys
    - 1.12.3.14 Development of a Decontamination and Dismantlement Plan
  - 1.12.4 General References

## CONTENTS (Continued)

### 1.13 EQUIPMENT QUALIFICATION PROGRAM

#### 1.13.1 Functions of the Equipment Qualification Program

#### 1.13.2 Equipment Qualification Program Requirements

##### 1.13.2.1 Harsh and Mild Environments

##### 1.13.2.2 Equipment Qualification Records

##### 1.13.2.3 Environmental Qualification Lists

##### 1.13.2.4 Testing and Analyses

##### 1.13.2.5 Procurement, Installation, Maintenance, Surveillance, and Monitoring

##### 1.13.2.6 Corrective Action Program Evaluation

##### 1.13.2.7 Equipment Qualification Margin

#### 1.13.3 Environmental Qualification Process

##### 1.13.3.1 Harsh Environment Qualification

##### 1.13.3.2 Qualification Methods

###### 1.13.3.2.1 Analysis

###### 1.13.3.2.2 Type Testing

###### 1.13.3.2.3 Operating Experience

###### 1.13.3.2.4 Combined Methods

##### 1.13.3.3 Qualified Life

##### 1.13.3.4 Environmental Qualification Documentation

#### 1.13.4 Seismic Qualification Process

##### 1.13.4.1 Methods

##### 1.13.4.2 Acceptance Criteria

##### 1.13.4.3 Process

##### 1.13.4.4 Qualification Methods

##### 1.13.4.5 Qualified Life

##### 1.13.4.6 Seismic Qualification Documentation

#### 1.13.5 General References

### 1.14 NUCLEAR CRITICALITY SAFETY

#### 1.14.1 Nuclear Criticality Safety Organization and Administration

#### 1.14.2 Nuclear Criticality Safety Technical Program

##### 1.14.2.1 Nuclear Criticality Safety Requirements

##### 1.14.2.2 Nuclear Criticality Analysis Process

##### 1.14.2.3 Nuclear Criticality Safety Evaluation

###### 1.14.2.3.1 Transportation Casks, Canisters, and Waste Packages

###### 1.14.2.3.1.1 Transportation Casks

###### 1.14.2.3.1.2 Dual-Purpose Canisters

###### 1.14.2.3.1.3 Transportation, Aging, and Disposal Canisters

###### 1.14.2.3.1.4 DOE High-Level Radioactive Waste Canisters

###### 1.14.2.3.1.5 DOE Standardized Spent Nuclear Fuel Canisters

**CONTENTS (Continued)**

- 1.14.2.3.1.6 DOE Multicanister Overpacks
- 1.14.2.3.1.7 Naval SNF Canisters
- 1.14.2.3.1.8 Waste Package Configurations
- 1.14.2.3.2 Criticality Control Parameters
  - 1.14.2.3.2.1 Criticality Control Parameters for Commercial SNF Dry Operations
    - 1.14.2.3.2.1.1 Waste Form Characteristics for Commercial SNF Dry Operations
    - 1.14.2.3.2.1.2 Moderation for Commercial SNF Dry Operations
    - 1.14.2.3.2.1.3 Fixed Neutron Absorber and Geometry for Commercial SNF Dry Operations
    - 1.14.2.3.2.1.4 Interaction for Commercial SNF Dry Operations
    - 1.14.2.3.2.1.5 Reflection for Commercial SNF Dry Operations
  - 1.14.2.3.2.2 Criticality Control Parameters for Commercial SNF Wet Operations
    - 1.14.2.3.2.2.1 Waste Form Characteristics for Commercial SNF Wet Operations
    - 1.14.2.3.2.2.2 Moderation for Commercial SNF Wet Operations
    - 1.14.2.3.2.2.3 Soluble Neutron Absorber for Commercial SNF Wet Operations
    - 1.14.2.3.2.2.4 Fixed Neutron Absorber, Geometry, and Interaction for Commercial SNF Wet Operations
    - 1.14.2.3.2.2.5 Reflection for Commercial SNF Wet Operations
  - 1.14.2.3.2.3 Criticality Control Parameters for DOE SNF
    - 1.14.2.3.2.3.1 Waste Form Characteristics for DOE SNF
    - 1.14.2.3.2.3.2 Moderation for DOE SNF
    - 1.14.2.3.2.3.3 Fixed Neutron Absorber and Geometry for DOE SNF
    - 1.14.2.3.2.3.4 Interaction for DOE SNF
    - 1.14.2.3.2.3.5 Reflection for DOE SNF
  - 1.14.2.3.2.4 Criticality Control Parameters for DOE HLW
  - 1.14.2.3.2.5 Summary of Criticality Control Parameters
- 1.14.2.3.3 Facility Criticality Safety Evaluations
  - 1.14.2.3.3.1 Initial Handling Facility Evaluation
  - 1.14.2.3.3.2 Receipt Facility Evaluation
  - 1.14.2.3.3.3 Canister Receipt and Closure Facility Evaluation
  - 1.14.2.3.3.4 Wet Handling Facility Evaluation
  - 1.14.2.3.3.5 Intrasite Operations and Aging Facility Evaluation



**CONTENTS (Continued)**

- 1.14.2.3.3.6 Subsurface Facility Evaluation
- 1.14.2.3.4 Criteria to Establish Subcriticality
  - 1.14.2.3.4.1 Administrative Margin and Justification
- 1.14.2.3.5 Criticality Alarm Systems
- 1.14.2.3.6 Offsite Operations
  - 1.14.2.3.6.1 Waste Form Characteristics
    - 1.14.2.3.6.1.1 Waste Form Characteristics for Commercial SNF
    - 1.14.2.3.6.1.2 Waste Form Characteristics for DOE SNF
  - 1.14.2.3.6.2 Moderation
    - 1.14.2.3.6.2.1 Moderation and Commercial SNF
    - 1.14.2.3.6.2.2 Moderation and DOE SNF
  - 1.14.2.3.6.3 Neutron Absorber
  - 1.14.2.3.6.4 Geometry
  - 1.14.2.3.6.5 Interaction
  - 1.14.2.3.6.6 Reflection
- 1.14.2.4 Example of the Criticality Safety Analysis
  - 1.14.2.4.1 Sensitivity Study
    - 1.14.2.4.1.1 Waste Form Characteristics
    - 1.14.2.4.1.2 Moderation
    - 1.14.2.4.1.3 Neutron Absorber
    - 1.14.2.4.1.4 Geometry
    - 1.14.2.4.1.5 Interaction (Neutronic Coupling)
    - 1.14.2.4.1.6 Reflection
    - 1.14.2.4.1.7 Summary of Sensitivity Study of Criticality Parameters
  - 1.14.2.4.2 Event Sequence Analysis
- 1.14.3 Nuclear Criticality Safety Regulations, Codes, and Standards
  - 1.14.3.1 Applicable Standards Documents
- 1.14.4 General References
- 2. REPOSITORY SAFETY AFTER PERMANENT CLOSURE
  - 2.1 System Description and Demonstration of Multiple Barriers
    - 2.1.1 Identification of Barriers
      - 2.1.1.1 Upper Natural Barrier
      - 2.1.1.2 Engineered Barrier System
      - 2.1.1.3 Lower Natural Barrier
    - 2.1.2 Barrier Capability Description
      - 2.1.2.1 Upper Natural Barrier
        - 2.1.2.1.1 Capability of the Topography and Surficial Soils to Prevent or Substantially Reduce Infiltration

**CONTENTS (Continued)**

- 2.1.2.1.2 Capability of the Unsaturated Zone above the Repository to Prevent or Substantially Reduce Seepage
- 2.1.2.1.3 Time Period over Which the Upper Natural Barrier Functions
- 2.1.2.1.4 Uncertainties Associated with Upper Natural Barrier Capability
- 2.1.2.1.5 Impact of Disruptive Events on the Upper Natural Barrier
- 2.1.2.1.6 Quantification of the Upper Natural Barrier Capability
  - 2.1.2.1.6.1 Topography and Surficial Soils
  - 2.1.2.1.6.2 Unsaturated Tuff Units and Repository Horizon
- 2.1.2.2 Engineered Barrier System
  - 2.1.2.2.1 Capability of the Engineered Barrier System to Prevent or Substantially Reduce the Contact of Seepage with the Waste Form
  - 2.1.2.2.2 Capability of the Engineered Barrier System to Prevent the Release or Substantially Reduce the Release Rate of Radionuclides from the Waste and Transport to the Lower Natural Barrier
  - 2.1.2.2.3 Time Period over Which the Engineered Barrier System Functions
  - 2.1.2.2.4 Uncertainties Associated with Engineered Barrier System Capability
  - 2.1.2.2.5 Impact of Disruptive Events on the Engineered Barrier System
  - 2.1.2.2.6 Quantification of the Engineered Barrier System Capability
- 2.1.2.3 Lower Natural Barrier
  - 2.1.2.3.1 Capability of the Unsaturated Zone below the Repository to Prevent or Substantially Reduce the Rate of Movement of Radionuclides to the Water Table
  - 2.1.2.3.2 Capability of the Saturated Zone to Prevent or Substantially Reduce the Rate of Movement of Radionuclides to the Accessible Environment
  - 2.1.2.3.3 Time Period over Which the Lower Natural Barrier Functions
  - 2.1.2.3.4 Uncertainties Associated with Lower Natural Barrier Capability
  - 2.1.2.3.5 Impact of Disruptive Events on the Lower Natural Barrier
  - 2.1.2.3.6 Overall Capability of the Lower Natural Barrier
- 2.1.3 Technical Bases for Barrier Capability
  - 2.1.3.1 Upper Natural Barrier
  - 2.1.3.2 Engineered Barrier System
  - 2.1.3.3 Lower Natural Barrier
  - 2.1.3.4 Technical Basis for Unlikely Events Potentially Affecting Barrier Capability
  - 2.1.3.5 Summary of Technical Bases for Barrier Capability
- 2.1.4 Summary

**CONTENTS (Continued)**

- 2.1.5 General References
- 2.2 SCENARIO ANALYSIS AND EVENT PROBABILITY
  - 2.2.1 Analysis of FEPs and Scenario Classes
    - 2.2.1.1 Identification and Classification of FEPs
      - 2.2.1.1.1 FEP Identification
      - 2.2.1.1.2 FEP Classification
    - 2.2.1.2 Screening of FEPs
    - 2.2.1.3 Event Class and Scenario Class Formation
      - 2.2.1.3.1 Scenario Class Formation Considering Individual Protection and Groundwater Protection Standards
      - 2.2.1.3.2 Scenario Class Formation For the Human Intrusion Standard
    - 2.2.1.4 Screening of Scenario Classes and Event Classes
      - 2.2.1.4.1 Screened-Out Event Class-Criticality
        - 2.2.1.4.1.1 Criticality Analysis Methodology
          - 2.2.1.4.1.1.1 Process
          - 2.2.1.4.1.1.2 Calculations
            - 2.2.1.4.1.1.2.1 Design Basis Configurations
            - 2.2.1.4.1.1.2.2 Analysis Considerations
            - 2.2.1.4.1.1.2.3 Analysis Software
              - 2.2.1.4.1.1.2.3.1 MCNP Version 4B2LV
              - 2.2.1.4.1.1.2.3.2 MCNP5 Version 1.40
              - 2.2.1.4.1.1.2.3.3 SCALE Version 4.4A
              - 2.2.1.4.1.1.2.3.4 SCALE Version 5.1
              - 2.2.1.4.1.1.2.3.5 EQ3/6
              - 2.2.1.4.1.1.2.3.6 PHREEQC
            - 2.2.1.4.1.1.2.4 Isotopic and Criticality Validation Methodology
              - 2.2.1.4.1.1.2.4.1 Isotopic Model Validation
              - 2.2.1.4.1.1.2.4.2 Criticality Model Validation
            - 2.2.1.4.1.1.2.5 Criticality Loading Curves
              - 2.2.1.4.1.1.3 Use of Criticality Loading Curves for Transportation, Aging, and Disposal Canisters
              - 2.2.1.4.1.1.4 Development of Criticality Loading Curves
                - 2.2.1.4.1.1.4.1 Source of Commercial SNF Burnup Values
          - 2.2.1.4.1.2 Processes Affecting Probability of Criticality
          - 2.2.1.4.1.3 Screening Evaluations
            - 2.2.1.4.1.3.1 Potential In-Package Intact Configurations
            - 2.2.1.4.1.3.2 Potential In-Package Degraded Configurations
              - 2.2.1.4.1.3.2.1 Nominal Scenario In-Package Degraded Configuration
              - 2.2.1.4.1.3.2.2 Seismic Scenario for In-package Degraded

**CONTENTS (Continued)**

- 2.2.1.4.1.3.2.3 Configuration
- 2.2.1.4.1.3.2.3 Rockfall Scenario for In-Package Degraded Configuration
- 2.2.1.4.1.3.2.4 Igneous Scenario for In-Package Degraded Configuration
- 2.2.1.4.1.3.3 Potential Near-Field Configurations
- 2.2.1.4.1.3.4 Potential Far-Field Configurations
- 2.2.1.4.1.4 Summary of Criticality Event Class Screening
- 2.2.2 Identification of Events with Probabilities Greater Than 1 Chance in 10,000 of Occurring over 10,000 Years
  - 2.2.2.1 Seismic Activity
    - 2.2.2.1.1 Probability of a Seismic Event
      - 2.2.2.1.1.1 Process Used for the PSHA
      - 2.2.2.1.1.2 Results from the PSHA
    - 2.2.2.1.2 Technical Bases of Probability Estimates
      - 2.2.2.1.2.1 Geologic Setting
      - 2.2.2.1.2.2 Seismicity of the Yucca Mountain Region
      - 2.2.2.1.2.3 Vibratory Ground Motion Information
      - 2.2.2.1.2.4 Fault Displacement
    - 2.2.2.1.3 Adequacy of Probability Model Support
      - 2.2.2.1.3.1 Seismic Source Characterization
      - 2.2.2.1.3.2 Ground Motion Characterization
      - 2.2.2.1.3.3 Fault Displacement Characterization
    - 2.2.2.1.4 Probability Model Parameters
    - 2.2.2.1.5 Uncertainty in Event Probability
  - 2.2.2.2 Igneous Activity
    - 2.2.2.2.1 Probability of an Igneous Event Intersecting the Repository
      - 2.2.2.2.1.1 Definition of Event
      - 2.2.2.2.1.2 Probability of Intrusion
      - 2.2.2.2.1.3 Probability of Eruption
      - 2.2.2.2.1.4 Process Used for Probabilistic Volcanic Hazard Analysis
    - 2.2.2.2.2 Technical Bases of Probability Estimates
      - 2.2.2.2.2.1 Geologic Setting
      - 2.2.2.2.2.2 Temporal and Spatial Models Used in Probabilistic Volcanic Hazard Analysis
    - 2.2.2.2.3 Probability Model Support
      - 2.2.2.2.3.1 Geologic Basis for the Probabilistic Volcanic Hazard Analysis
      - 2.2.2.2.3.2 Alternative Estimates of the Intersection Probability

**CONTENTS (Continued)**

- 2.2.2.2.4 Probability Model Parameters
- 2.2.2.2.5 Uncertainty in Event Probability
- 2.2.2.3 Early Waste Package and Drip Shield Failures
  - 2.2.2.3.1 Definition of the Event
  - 2.2.2.3.2 Early Waste Package Failure Probability
  - 2.2.2.3.3 Early Drip Shield Failure Probability
- 2.2.2.4 Human Intrusion
  - 2.2.2.4.1 Definition of Human Intrusion Event
  - 2.2.2.4.2 Probability of Human Intrusion Event
- 2.2.3 General References
- 2.3 MODEL ABSTRACTION
  - 2.3.1 Climate and Infiltration
    - 2.3.1.1 Summary and Overview
    - 2.3.1.2 Climate
      - 2.3.1.2.1 Conceptual Description of Climate
        - 2.3.1.2.1.1 Regional Climatic Characteristics
        - 2.3.1.2.1.2 Climate and Climate Change
          - 2.3.1.2.1.2.1 Relations between Present and Past Climate
          - 2.3.1.2.1.2.2 The Devils Hole Oxygen Isotope Record as Evidence of Cyclical Climate Change
          - 2.3.1.2.1.2.3 Earth-Orbital Parameters and the Timing of Past and Future Climate Change
          - 2.3.1.2.1.2.4 Reconstruction of Past Climate Details Using Data about Fossil Ostracodes in Owens Lake and Sizes of Prehistoric Lakes in the Great Basin
      - 2.3.1.2.2 Paleoclimatological Data and Data Uncertainty
        - 2.3.1.2.2.1 Paleoclimatological Data
          - 2.3.1.2.2.1.1 Devils Hole Oxygen Isotope Record
          - 2.3.1.2.2.1.2 Owens Lake Ostracode and Diatom Record
          - 2.3.1.2.2.1.3 Correlation of Owens Lake Paleolimnology and Devils Hole Oxygen Isotope Records
          - 2.3.1.2.2.1.4 Uncertainty in Paleoclimate Data
      - 2.3.1.2.3 Climate Analysis and Uncertainty
        - 2.3.1.2.3.1 Climate Analysis
          - 2.3.1.2.3.1.1 Nature and Sequence of Past and Future Climates
          - 2.3.1.2.3.1.2 Selection of Analogue Meteorological Stations
        - 2.3.1.2.3.2 Consideration of Uncertainty in the Climate Analysis
          - 2.3.1.2.3.2.1 Uncertainty in Paleoclimate Interpretations

---

**CONTENTS (Continued)**

- 2.3.1.2.3.2.2 Uncertainty in the Climate Forecasting Approach
- 2.3.1.3 Infiltration
  - 2.3.1.3.1 Conceptual Description of Infiltration Processes
    - 2.3.1.3.1.1 Precipitation, Runoff, and Infiltration
    - 2.3.1.3.1.2 Evapotranspiration
    - 2.3.1.3.1.3 Geomorphology and Surficial Features
    - 2.3.1.3.1.4 Factors Controlling Net Infiltration
  - 2.3.1.3.2 Infiltration Data and Data Uncertainty
    - 2.3.1.3.2.1 Infiltration Model Input Data
      - 2.3.1.3.2.1.1 Weather Data
      - 2.3.1.3.2.1.2 Geologic and Geographic Inputs
      - 2.3.1.3.2.1.3 Soil Properties
      - 2.3.1.3.2.1.4 Bedrock Properties
      - 2.3.1.3.2.1.5 Vegetation Parameters
    - 2.3.1.3.3 Infiltration Modeling and Uncertainty
      - 2.3.1.3.3.1 MASSIF Model
        - 2.3.1.3.3.1.1 Development of MASSIF Infiltration Model
        - 2.3.1.3.3.1.2 Results of Net Infiltration for Present-Day and Forecast Future Climates
      - 2.3.1.3.3.2 Consideration of Uncertainty in the Infiltration Model
        - 2.3.1.3.3.2.1 Infiltration Uncertainty Analysis Methodology
        - 2.3.1.3.3.2.2 Uncertainty in Infiltration Data and Parameters and Sensitivity of the Model Output to These Data and Parameters
    - 2.3.1.3.4 Confidence Building and Abstraction of the Infiltration Model
      - 2.3.1.3.4.1 Confidence Building During Model Development
      - 2.3.1.3.4.2 Post-Model Development Validation
        - 2.3.1.3.4.2.1 Corroboration of Model Results with Data
        - 2.3.1.3.4.2.2 Comparison of Model Results with Other Models and Data from Comparable Environments
        - 2.3.1.3.4.2.3 Corroboration of MASSIF Model Results with Other Alternative Mathematical Model Results
      - 2.3.1.3.4.3 Model Abstraction
  - 2.3.1.4 Conclusions
  - 2.3.1.5 General References
  - 2.3.2 Unsaturated Zone Flow
    - 2.3.2.1 Summary and Overview
    - 2.3.2.2 Conceptual Description of Unsaturated Zone Flow System

**CONTENTS (Continued)**

- 2.3.2.2.1 Overall Flow Patterns Within the Unsaturated Zone
  - 2.3.2.2.1.1 Flow Through the TCw Unit
  - 2.3.2.2.1.2 Flow Through the PTn Unit
  - 2.3.2.2.1.3 Flow Through the TSw Unit
  - 2.3.2.2.1.4 Flow Below the Repository
- 2.3.2.2.2 Specific Aspects of Unsaturated Zone Flow
  - 2.3.2.2.2.1 Fracture–Matrix Interaction
  - 2.3.2.2.2.2 Effect of Major Faults
  - 2.3.2.2.2.3 Flow Focusing and Fast Flow Paths
  - 2.3.2.2.2.4 Perched Water
  - 2.3.2.2.2.5 Transient Flow
  - 2.3.2.2.2.6 Thermal Processes
- 2.3.2.3 Data and Data Uncertainty
  - 2.3.2.3.1 Geologic Setting and Hydrologic Units
  - 2.3.2.3.2 Laboratory and In Situ Field Testing and Measurements
    - 2.3.2.3.2.1 Measurement of Matrix Properties
    - 2.3.2.3.2.2 In Situ Borehole Testing
    - 2.3.2.3.2.3 Borehole Temperature Logging
    - 2.3.2.3.2.4 Busted Butte Tests
    - 2.3.2.3.2.5 Drift Scale Test
    - 2.3.2.3.2.6 Alcove 1 Tests and Alcove 8–Niche 3 Crossover Tests
    - 2.3.2.3.2.7 Air Permeability Testing, Pneumatic Testing, and Fracture Geometry Data
  - 2.3.2.3.3 Hydrogeologic and Thermal Data
    - 2.3.2.3.3.1 Hydrogeologic Data for the Rock Matrix
    - 2.3.2.3.3.2 Hydrogeologic Data for Fractures
    - 2.3.2.3.3.3 Hydrologic Data for Faults
    - 2.3.2.3.3.4 Rock Thermal Properties
  - 2.3.2.3.4 Geochemical Data
    - 2.3.2.3.4.1 Geochemical Composition of Pore Water
    - 2.3.2.3.4.2 Ages of Pore Water and Gas Samples
    - 2.3.2.3.4.3 Isotopic Data
    - 2.3.2.3.4.4 Fracture-Coating Minerals
  - 2.3.2.3.5 Data Uncertainty
    - 2.3.2.3.5.1 Uncertainties Associated with Climate
    - 2.3.2.3.5.2 Uncertainties Associated with Geologic Data
    - 2.3.2.3.5.3 Uncertainties Associated with Hydrologic Data
    - 2.3.2.3.5.4 Uncertainties Associated with Major Faults
    - 2.3.2.3.5.5 Uncertainties Associated with Geochemical Data

**CONTENTS (Continued)**

- 2.3.2.3.5.6 Uncertainties Associated with Lithophysal Cavities
- 2.3.2.4 Model and Model Uncertainty
  - 2.3.2.4.1 Development of the Site-Scale Unsaturated Zone Flow Model
    - 2.3.2.4.1.1 Conceptual Models and Numerical Approaches
      - 2.3.2.4.1.1.1 Conceptual Model of Unsaturated Zone Flow
      - 2.3.2.4.1.1.2 Modeling Approaches to Flow in the Unsaturated Zone
      - 2.3.2.4.1.1.3 Active Fracture Model for Fracture–Matrix Interaction
      - 2.3.2.4.1.1.4 Treatment of Heterogeneity
    - 2.3.2.4.1.2 Numerical Models of Unsaturated Zone Flow
      - 2.3.2.4.1.2.1 Introduction
      - 2.3.2.4.1.2.2 Numerical Model Grids and Boundary Conditions
      - 2.3.2.4.1.2.3 Calibration of Model Properties
        - 2.3.2.4.1.2.3.1 Calibration Method
        - 2.3.2.4.1.2.3.2 Calibration of Drift-Scale Parameters
        - 2.3.2.4.1.2.3.3 Calibration of Site-Scale Parameters
        - 2.3.2.4.1.2.3.4 Calibration of Fault Parameters
      - 2.3.2.4.1.2.4 Ambient Flow Model
        - 2.3.2.4.1.2.4.1 Model Boundary Conditions
        - 2.3.2.4.1.2.4.2 Infiltration Scenarios
        - 2.3.2.4.1.2.4.3 Model Parameters and Rock Properties
        - 2.3.2.4.1.2.4.4 Three-Dimensional Calibration
        - 2.3.2.4.1.2.4.5 Calibration of Water Flux Uncertainty at the Upper Boundary of the Unsaturated Zone Flow Model for Present-Day, Monsoon, and Glacial-Transition Climates
          - 2.3.2.4.1.2.4.5.1 Prior Probabilities
          - 2.3.2.4.1.2.4.5.2 Temperature and Chloride Observations and Conceptual Models
          - 2.3.2.4.1.2.4.5.3 Temperature and Chloride Predictions
          - 2.3.2.4.1.2.4.5.4 Likelihood Functions and Calculation of Weights
          - 2.3.2.4.1.2.4.5.5 Results
          - 2.3.2.4.1.2.4.5.6 Results Using Temperature or Chloride Data Sets Independently
          - 2.3.2.4.1.2.4.5.7 Unsaturated Zone Expert Elicitation Findings
          - 2.3.2.4.1.2.4.5.8 Weighting Factors for Future Climates
        - 2.3.2.4.1.2.4.6 Model Simulation Results
      - 2.3.2.4.1.2.5 Site-Scale Coupled Process Models



**CONTENTS (Continued)**

- 2.3.2.4.1.2.5.1 Site-Scale Thermal-Hydrologic Model
- 2.3.2.4.1.2.5.2 Site-Scale Thermal-Hydrologic-Chemical Model
- 2.3.2.4.1.2.5.3 Site-Scale Thermal-Hydrologic-Mechanical Model
- 2.3.2.4.2 Model Uncertainty
  - 2.3.2.4.2.1 Alternative Conceptual Models
    - 2.3.2.4.2.1.1 Flow through the PTn Unit
    - 2.3.2.4.2.1.2 Episodic Flow
    - 2.3.2.4.2.1.3 Perched Water and Flow in the CHn Unit
    - 2.3.2.4.2.1.4 Flow through Faults
    - 2.3.2.4.2.1.5 Discrete-Fracture Network Model
    - 2.3.2.4.2.1.6 Film Flow
  - 2.3.2.4.2.2 Data and Parameter Uncertainty
- 2.3.2.5 Confidence Building and Model Abstraction
  - 2.3.2.5.1 Confidence Building
    - 2.3.2.5.1.1 Consistency with Hydrologic and Temperature Data
    - 2.3.2.5.1.2 Consistency with Geochemical Data
    - 2.3.2.5.1.3 Consistency with In Situ Test Results
    - 2.3.2.5.1.4 Consistency with Alternative Methods for Estimating Percolation Flux
    - 2.3.2.5.1.5 Consistency with Thermal-Hydrologic Data
    - 2.3.2.5.1.6 Consistency with Natural Analogues
      - 2.3.2.5.1.6.1 Analogues for Ambient Flow
      - 2.3.2.5.1.6.2 Analogues for Coupled Processes
  - 2.3.2.5.2 Abstraction of Site-Scale Unsaturated Zone Flow for Present-Day and Future Climate States
- 2.3.2.6 Conclusions
- 2.3.2.7 General References
- 2.3.3 Water Seeping into Drifts
  - 2.3.3.1 Summary and Overview
  - 2.3.3.2 Ambient Seepage
    - 2.3.3.2.1 Conceptual Description of Ambient Seepage Processes
      - 2.3.3.2.1.1 Significance of Seepage for Repository Performance
      - 2.3.3.2.1.2 Description of Ambient Seepage Process
      - 2.3.3.2.1.3 Factors and Properties Affecting Ambient Seepage
      - 2.3.3.2.1.4 Drift Degradation Effects
      - 2.3.3.2.1.5 Modeling Approach
    - 2.3.3.2.2 Data and Data Uncertainty
      - 2.3.3.2.2.1 Seepage Testing

**CONTENTS (Continued)**

- 2.3.3.2.2.1.1 Liquid-Release Tests
- 2.3.3.2.2.1.2 Air Injection Tests
- 2.3.3.2.2.1.3 Relative Humidity Monitoring
- 2.3.3.2.2.1.4 Mass Balance in Niche 5
- 2.3.3.2.2.1.5 Alcove 8–Niche 3 Testing
- 2.3.3.2.2.1.6 Summary of Active Seepage Testing
- 2.3.3.2.2.2 Moisture Monitoring in the ECRB Cross-Drift and Alcove 7
  - 2.3.3.2.2.2.1 Passive Hydrologic Tests
  - 2.3.3.2.2.2.2 Evidence of Ventilation Effects
  - 2.3.3.2.2.2.3 Observations Related to Wet Zones
  - 2.3.3.2.2.2.4 Chemical and Isotopic Water Analyses
  - 2.3.3.2.2.2.5 Summary of Moisture Monitoring in Drifts
- 2.3.3.2.2.3 Observation of Seepage Under Natural Conditions
  - 2.3.3.2.2.3.1 Impact of Forced Ventilation on Seepage
  - 2.3.3.2.2.3.2 Direct Observation of Seepage into the ESF South Ramp
- 2.3.3.2.2.4 Summary of Data and Data Uncertainty
- 2.3.3.2.3 Model and Model Uncertainty
  - 2.3.3.2.3.1 General Approach for Ambient Seepage Modeling
  - 2.3.3.2.3.2 Conceptual and Numerical Models of Seepage
  - 2.3.3.2.3.3 Model Calibration and Validation
  - 2.3.3.2.3.4 Prediction of Ambient Seepage
    - 2.3.3.2.3.4.1 Seepage into Intact Emplacement Drifts
    - 2.3.3.2.3.4.2 Seepage into Degraded Emplacement Drifts
    - 2.3.3.2.3.4.3 Seepage Predictions for Alcove 8–Niche 3 Tests
  - 2.3.3.2.3.5 Percolation Flux and Flow Focusing
  - 2.3.3.2.3.6 Parameter and Model Uncertainty
    - 2.3.3.2.3.6.1 Variability and Uncertainty of Capillary Strength
    - 2.3.3.2.3.6.2 Variability and Uncertainty of Fracture Permeability
    - 2.3.3.2.3.6.3 Variability and Uncertainty of Local Percolation Flux
    - 2.3.3.2.3.6.4 Model Uncertainty
  - 2.3.3.2.3.7 Alternative Conceptual Models of Ambient Seepage
    - 2.3.3.2.3.7.1 Discrete-Fracture Network Model
    - 2.3.3.2.3.7.2 Homogeneous Porous Medium Model
    - 2.3.3.2.3.7.3 Seepage Governed by Ponding Probability
    - 2.3.3.2.3.7.4 Inferring Seepage from Precipitates in Lithophysal Cavities

**CONTENTS (Continued)**

- 2.3.3.2.3.7.5 Inferring Seepage Threshold Directly from Liquid-Release Tests
- 2.3.3.2.3.7.6 Alternative Flow Focusing Model
- 2.3.3.2.3.8 Summary of Ambient Seepage Modeling
- 2.3.3.2.4 Ambient Component of Drift Seepage Abstraction
  - 2.3.3.2.4.1 Probability Distributions for Seepage-Relevant Parameters
  - 2.3.3.2.4.2 Ambient Seepage for Different Scenario Classes
    - 2.3.3.2.4.2.1 Ambient Seepage for the Nominal Scenario
    - 2.3.3.2.4.2.2 Ambient Seepage for Seismic Scenarios
    - 2.3.3.2.4.2.3 Seepage for an Intruded Drift (Igneous Scenario)
    - 2.3.3.2.4.2.4 Seepage During Preclosure Period
  - 2.3.3.2.4.3 Ambient Seepage Lookup Tables
- 2.3.3.3 Thermal Seepage
  - 2.3.3.3.1 Conceptual Description of Thermal-Hydrologic Processes
  - 2.3.3.3.2 Data and Data Uncertainty
  - 2.3.3.3.3 Model and Model Uncertainty
    - 2.3.3.3.3.1 Thermal-Hydrologic Seepage Model
    - 2.3.3.3.3.2 Thermal-Hydrologic Seepage Model Support
    - 2.3.3.3.3.3 Model Uncertainty
    - 2.3.3.3.3.4 Coupled Mechanical and Chemical Processes and Impact on Seepage
  - 2.3.3.3.4 Thermal Component of Drift Seepage Abstraction
- 2.3.3.4 Total System Performance Assessment Implementation of Drift Seepage
  - 2.3.3.4.1 General Approach
    - 2.3.3.4.1.1 Nominal and Seismic Scenarios
    - 2.3.3.4.1.2 Igneous Scenario
    - 2.3.3.4.1.3 Early Failure Scenario
  - 2.3.3.4.2 Example Calculation for Nominal and Seismic Scenarios
  - 2.3.3.4.3 Seepage Calculations for ESF South Ramp Seepage Event
- 2.3.3.5 Analogue Observations
- 2.3.3.6 Conclusions
- 2.3.3.7 General References
- 2.3.4 Mechanical Degradation of the Engineered Barrier System
  - 2.3.4.1 Summary and Overview
  - 2.3.4.2 System Description and Model Integration
    - 2.3.4.2.1 Summary Description of the Model

**CONTENTS (Continued)**

- 2.3.4.2.1.1 Summary Description of Seismic Scenario Class and Integration into the Total System Performance Assessment
- 2.3.4.3 Ground Motion and Fault Displacement Analyses
  - 2.3.4.3.1 Probabilistic Seismic Hazard Analysis
  - 2.3.4.3.2 Ground Motion Site-Response Analysis and Development of Time Histories
    - 2.3.4.3.2.1 Conceptual Approach
    - 2.3.4.3.2.2 Ground Motion Data and Data Uncertainty
    - 2.3.4.3.2.3 Ground Motion Site-Response Model and Model Uncertainty
    - 2.3.4.3.2.4 Abstraction
  - 2.3.4.3.3 Characterization of Low-Probability Peak Horizontal Ground Velocity
    - 2.3.4.3.3.1 Conceptual Approach
    - 2.3.4.3.3.2 Data and Data Uncertainty
    - 2.3.4.3.3.3 Model and Model Uncertainty
    - 2.3.4.3.3.4 Abstraction for TSPA
    - 2.3.4.3.3.5 Comparison to Supplemental Ground Motion Inputs for Preclosure Analyses
      - 2.3.4.3.3.5.1 Comparison of Acceleration Response Spectra
      - 2.3.4.3.3.5.2 Comparison of Horizontal PGV Hazard
- 2.3.4.4 Rockfall Analysis
  - 2.3.4.4.1 Conceptual Description of Rockfall Analysis
  - 2.3.4.4.2 Data and Data Uncertainty for Rockfall Analysis
    - 2.3.4.4.2.1 Geology of Repository Host Horizon
    - 2.3.4.4.2.2 In Situ Stress State
    - 2.3.4.4.2.3 Geotechnical Data
      - 2.3.4.4.2.3.1 Characterization of Fractures
      - 2.3.4.4.2.3.2 Characteristics of Lithophysae
      - 2.3.4.4.2.3.3 Mechanical Intact Rock Properties of Nonlithophysal and Lithophysal Rocks
        - 2.3.4.4.2.3.3.1 Time and Rate Dependence of Intact Rock Strength
        - 2.3.4.4.2.3.3.2 Effect of Sample Size and Anisotropy
        - 2.3.4.4.2.3.3.3 Effect of Sample Saturation
        - 2.3.4.4.2.3.3.4 Large-Core Laboratory Testing of Lithophysal Rocks
        - 2.3.4.4.2.3.3.5 Summary of Mechanical Properties Laboratory Testing

**CONTENTS (Continued)**

- 2.3.4.4.2.3.4 In Situ Mechanical Testing of Nonlithophysal and Lithophysal Rock Mass Properties
- 2.3.4.4.2.3.5 Mechanical Properties of Fractures
- 2.3.4.4.2.3.6 Thermal Properties
  - 2.3.4.4.2.3.6.1 Thermal Conductivity
  - 2.3.4.4.2.3.6.2 Heat Capacity
  - 2.3.4.4.2.3.6.3 Coefficient of Thermal Expansion
- 2.3.4.4.2.3.7 Base-Case Mechanical Property Sets for Rockfall Analysis
- 2.3.4.4.2.4 Data Uncertainty
- 2.3.4.4.3 Rockfall Analysis for In Situ and Thermal Stress Effects on Nonlithophysal and Lithophysal Units
  - 2.3.4.4.3.1 Conceptual Approach for Analysis of In Situ and Thermal Stress
  - 2.3.4.4.3.2 Results and Uncertainty Analysis for In Situ and Thermal Analysis
- 2.3.4.4.4 Rockfall Analysis for Seismic Effects on Nonlithophysal Units
  - 2.3.4.4.4.1 Conceptual Approach
  - 2.3.4.4.4.2 Development of the 3DEC Rockfall Analysis Model for Nonlithophysal Rock
  - 2.3.4.4.4.3 Vibratory Ground Motion
  - 2.3.4.4.4.4 Validation of the 3DEC Nonlithophysal Rockfall Model
  - 2.3.4.4.4.5 Results and Sensitivity Studies
    - 2.3.4.4.4.5.1 Results of Rockfall from Vibratory Ground Motion at Ambient Temperature
    - 2.3.4.4.4.5.2 Sensitivity Study of the Input Parameters and Model Conditions
  - 2.3.4.4.4.6 Consideration of Alternative Conceptual Models
- 2.3.4.4.5 Rockfall Analysis for Seismic Effects on Lithophysal Units
  - 2.3.4.4.5.1 Conceptual Description for Modeling Lithophysal Units
  - 2.3.4.4.5.2 Vibratory Ground Motion
  - 2.3.4.4.5.3 Model Description and Model Uncertainty
    - 2.3.4.4.5.3.1 Calibration of UDEC Discrete Element Model
    - 2.3.4.4.5.3.2 Validation of UDEC Lithophysal Rockfall Model
  - 2.3.4.4.5.4 Results for Vibratory Motion Analysis in Lithophysal Units
  - 2.3.4.4.5.5 Evaluation of Alternative Models
- 2.3.4.4.6 Time-Dependent Degradation of Rock Mass Strength in Lithophysal Units
  - 2.3.4.4.6.1 Conceptual Description of Analysis

**CONTENTS (Continued)**

- 2.3.4.4.6.2 Results of Time-Dependent Drift Degradation Analysis
- 2.3.4.4.6.3 Drip Shield Loading from Time-Dependent Drift Collapse Over Very Long Time Periods
  - 2.3.4.4.6.3.1 Model Description and Evaluation of Alternative Methods
  - 2.3.4.4.6.3.2 Static Loading to the Drip Shield from Caved Rock
- 2.3.4.4.7 Assumptions Used in Rockfall Models
- 2.3.4.4.8 Rockfall and Rubble Accumulation in the Emplacement Drifts
  - 2.3.4.4.8.1 Conceptual Description of Rockfall and Rubble Accumulation in the Emplacement Drifts
  - 2.3.4.4.8.2 Data and Data Uncertainty for Rockfall and Rubble Accumulation in the Emplacement Drifts
    - 2.3.4.4.8.2.1 Lithophysal Rock Strength and Modulus
    - 2.3.4.4.8.2.2 Rock Particle Size in the Lithophysal Rock
    - 2.3.4.4.8.2.3 Fracture Patterns in the Nonlithophysal Rock
    - 2.3.4.4.8.2.4 Ground Motions
    - 2.3.4.4.8.2.5 Bulking Factor of the Rubble
  - 2.3.4.4.8.3 Model and Model Uncertainty for Rockfall and Rubble Accumulation in the Emplacement Drifts
    - 2.3.4.4.8.3.1 Rubble Accumulation in Lithophysal Zones
    - 2.3.4.4.8.3.2 Rubble Accumulation in Nonlithophysal Zones
  - 2.3.4.4.8.4 Abstraction of Rubble Volumes in Lithophysal Rock Units
  - 2.3.4.4.8.5 Abstraction of Rubble Volumes in Nonlithophysal Rock Units
- 2.3.4.5 Structural Response of EBS Features to Mechanical Degradation
  - 2.3.4.5.1 Failure Criteria Used in the Seismic Scenario Class
    - 2.3.4.5.1.1 Engineered Barrier System Feature Description
    - 2.3.4.5.1.2 Conceptual Description of Failure Mechanisms and Failure Criteria for EBS Components
      - 2.3.4.5.1.2.1 Conceptual Description of Failure Through Formation of Stress Corrosion Cracks
      - 2.3.4.5.1.2.2 Conceptual Description of Failure Through Tensile Rupture
      - 2.3.4.5.1.2.3 Conceptual Description of Failure Through Buckling or Excessive Deformation of the Drip Shield Framework
    - 2.3.4.5.1.3 Data and Data Uncertainty for Failure Criteria of the EBS Components

**CONTENTS (Continued)**

- 2.3.4.5.1.3.1 Mechanical Properties of Waste Package and Drip Shield Materials
- 2.3.4.5.1.3.2 Residual Stress Threshold Criteria
- 2.3.4.5.1.3.3 Tensile Rupture Criteria
- 2.3.4.5.1.3.4 Buckling and Large Plastic Deformations of the Drip Shield Framework
- 2.3.4.5.1.3.5 Breach Due to Fault Displacement
- 2.3.4.5.1.3.6 Thinning of the EBS Components Due to General Corrosion
- 2.3.4.5.1.4 Model and Model Uncertainty
  - 2.3.4.5.1.4.1 Stress Corrosion Crack Networks
  - 2.3.4.5.1.4.2 Tensile Rupture
- 2.3.4.5.1.5 Abstraction of Residual Stress Threshold and Crack Network Transport Area
- 2.3.4.5.1.6 Abstraction of Rupture Probability
- 2.3.4.5.2 Structural Response of the Waste Package and Drip Shield to Vibratory Ground Motion During Time Frame of Structurally-Intact Drip Shields
  - 2.3.4.5.2.1 Waste Package Response to Vibratory Ground Motion for Intact Drip Shields
    - 2.3.4.5.2.1.1 Conceptual Description of Analysis of Waste Package Response to Vibratory Ground Motion for Intact Drip Shields
    - 2.3.4.5.2.1.2 Data and Data Uncertainty of Waste Package Response to Vibratory Ground Motion for Intact Drip Shields
      - 2.3.4.5.2.1.2.1 Ground Motions and Friction Coefficients
      - 2.3.4.5.2.1.2.2 Energy Dissipation on Impact
      - 2.3.4.5.2.1.2.3 Physical Characteristics, Material Properties, and Failure Criteria for Waste Package
      - 2.3.4.5.2.1.2.4 Dimensions and Masses of the Waste Package
      - 2.3.4.5.2.1.2.5 Degradation of Waste Package Internals
      - 2.3.4.5.2.1.2.6 General Corrosion Thinning of the Alloy 22 Outer Corrosion Barrier
    - 2.3.4.5.2.1.3 Model and Model Uncertainty of Waste Package Response to Vibratory Ground Motion for Intact Drip Shields
      - 2.3.4.5.2.1.3.1 Kinematic Analyses
      - 2.3.4.5.2.1.3.2 Detailed Structural Analysis and Development of Damage Lookup Tables
      - 2.3.4.5.2.1.3.3 Confidence-Building in the Kinematic Model

**CONTENTS (Continued)**

- 2.3.4.5.2.1.4 Damage and Rupture Abstractions for the TAD-Bearing and Codisposal Waste Packages
  - 2.3.4.5.2.1.4.1 Damage and Rupture Abstractions for the TAD-Bearing Waste Package with Intact Internals and 23-mm-thick Outer Corrosion Barrier
  - 2.3.4.5.2.1.4.2 Damage and Rupture Abstractions for the Codisposal Waste Package with Intact Internals and 23-mm-thick Outer Corrosion Barrier
  - 2.3.4.5.2.1.4.3 Damage and Rupture Abstractions for the Codisposal Waste Package with Degraded Internals and 17-mm-thick Outer Corrosion Barrier
- 2.3.4.5.2.2 Drip Shield Damage in Response to Vibratory Ground Motion
  - 2.3.4.5.2.2.1 Conceptual Description of Analysis for Damage to Drip Shield from Vibratory Ground Motion
  - 2.3.4.5.2.2.2 Data and Data Uncertainty for Analysis of Damage to Drip Shield from Vibratory Ground Motion
    - 2.3.4.5.2.2.2.1 Material Properties and Failure Criteria for Titanium Grade 7 and Grade 29
    - 2.3.4.5.2.2.2.2 Corrosion Thinning of Drip Shield Plates and Framework
    - 2.3.4.5.2.2.2.3 Rock Rubble Load
    - 2.3.4.5.2.2.2.4 Rock Block Size in Nonlithophysal Zone
  - 2.3.4.5.2.2.3 Model and Model Uncertainty for Analysis of Damage to Drip Shield from Vibratory Ground Motion
    - 2.3.4.5.2.2.3.1 Damaged Area Results for the Lithophysal Zone
    - 2.3.4.5.2.2.3.2 Static Rockfall Loads in the Lithophysal Zone
    - 2.3.4.5.2.2.3.3 Damaged Area Results for the Nonlithophysal Zone
  - 2.3.4.5.2.2.4 Models for Damage to Drip Shield from Vibratory Ground Motion
    - 2.3.4.5.2.2.4.1 Damaged Area Model for the Lithophysal Zone
    - 2.3.4.5.2.2.4.2 Damaged Area Model for the Nonlithophysal Zone
- 2.3.4.5.3 Drip Shield Fragility
  - 2.3.4.5.3.1 Conceptual Description of Drip Shield Fragility



**CONTENTS (Continued)**

- 2.3.4.5.3.2 Data and Data Uncertainty for Drip Shield Fragility
  - 2.3.4.5.3.2.1 Static Rockfall Rubble Load
  - 2.3.4.5.3.2.2 Peak Ground Acceleration
  - 2.3.4.5.3.2.3 Plastic Load Capacity of the Drip Shield Plates and Framework
- 2.3.4.5.3.3 Model and Model Uncertainty for Drip Shield Fragility
  - 2.3.4.5.3.3.1 Ultimate Plastic Load Capacity of the Drip Shield Plates
  - 2.3.4.5.3.3.2 Ultimate Plastic Load Capacity of the Drip Shield Framework
  - 2.3.4.5.3.3.3 Alternative Modeling Approach—Dynamic Analysis of the Drip Shield and Rubble Under Vibratory Ground Motion
- 2.3.4.5.3.4 Abstraction for Probability of Drip Shield Plate and Framework Failure
- 2.3.4.5.4 Structural Analysis of the Waste Package After Drip Shield Failure
  - 2.3.4.5.4.1 Conceptual Description of Analysis of Structural Analysis of the Waste Package After Drip Shield Failure
  - 2.3.4.5.4.2 Data and Data Uncertainty of Structural Analysis of the Waste Package After Drip Shield Failure
    - 2.3.4.5.4.2.1 Rock Rubble Load on Waste Package and Ground Motion Application
    - 2.3.4.5.4.2.2 Alloy 22 Outer Corrosion Barrier Material Properties and Damage Criteria
    - 2.3.4.5.4.2.3 Waste Package Outer Corrosion Barrier Thinning Due to General Corrosion
  - 2.3.4.5.4.3 Model and Model Uncertainty of Structural Analysis of the Waste Package After Drip Shield Failure
    - 2.3.4.5.4.3.1 Waste Package Surrounded by Rubble
      - 2.3.4.5.4.3.1.1 Model
      - 2.3.4.5.4.3.1.2 Results – Outer Corrosion Barrier Damage
    - 2.3.4.5.4.3.2 Waste Package Loaded by a Collapsed Drip Shield
      - 2.3.4.5.4.3.2.1 Results – Outer Corrosion Barrier Damage
  - 2.3.4.5.4.4 Abstraction of Waste Package Damage and Rupture Potential After Drip Shield Failure
    - 2.3.4.5.4.4.1 Abstraction of Waste Package Response After Drip Shield Buckling But Before Plate Rupture
    - 2.3.4.5.4.4.2 Abstraction of Waste Package Response After Plate Rupture
- 2.3.4.5.5 Structural Response to Fault Displacement

**CONTENTS (Continued)**

- 2.3.4.5.5.1 Conceptual Description of Analysis
- 2.3.4.5.5.2 Data and Data Uncertainty
  - 2.3.4.5.5.2.1 Clearances for EBS Components
    - 2.3.4.5.5.2.1.1 Clearances with an Intact Drip Shield
    - 2.3.4.5.5.2.1.2 Clearances with a Failed Drip Shield
  - 2.3.4.5.5.2.2 Failure Criteria for EBS Components in Response to Fault Displacement
  - 2.3.4.5.5.2.3 Faults Intersecting Emplacement Drifts
    - 2.3.4.5.5.2.3.1 Location of Known Faults
    - 2.3.4.5.5.2.3.2 Faulting at Generic Locations
    - 2.3.4.5.5.2.4 Fault Displacement Hazards
- 2.3.4.5.5.3 Model and Model Uncertainty
- 2.3.4.5.5.4 Abstraction for Fault Damage
- 2.3.4.5.6 Postseismic Changes for the In-Drift Environment
  - 2.3.4.5.6.1 Change in Seepage Flux into the Drift
  - 2.3.4.5.6.2 Changes for a Collapsed Drift
- 2.3.4.6 Computational Algorithm for Seismic Scenario Class
  - 2.3.4.6.1 Computational Approach
  - 2.3.4.6.2 Validation of Seismic Damage Abstractions
- 2.3.4.7 Evaluation of Material Supporting Mechanical Disruption of the EBS
- 2.3.4.8 Conclusions
  - 2.3.4.8.1 Summary of Significant Processes for Mechanical Degradation of the EBS
  - 2.3.4.8.2 Summary of Key Uncertainties Associated with Mechanical Degradation of the EBS
  - 2.3.4.8.3 Summary of Key Limitations/Conservatisms in Models Used to Assess Mechanical Degradation of the EBS.
  - 2.3.4.8.4 Summary of Consistency Between TSPA Model Abstractions and Process Models
  - 2.3.4.8.5 Summary of Key Output Parameters Provided to TSPA
- 2.3.4.9 General References
- 2.3.5 In-Drift Physical and Chemical Environment
  - 2.3.5.1 Summary and Overview
  - 2.3.5.2 Approach to Coupled Processes
    - 2.3.5.2.1 Coupled Processes
    - 2.3.5.2.2 Thermal-Hydrologic-Mechanical Coupled Processes
    - 2.3.5.2.3 Thermal-Hydrologic-Chemical Coupled Processes
  - 2.3.5.3 Near-Field Chemistry Model
    - 2.3.5.3.1 Conceptual Description
      - 2.3.5.3.1.1 Matrix Pore-Water Composition

**CONTENTS (Continued)**

- 2.3.5.3.1.2 Thermal-Hydrologic-Chemical Processes
- 2.3.5.3.2 Data and Data Uncertainty
  - 2.3.5.3.2.1 Data Sources
  - 2.3.5.3.2.2 Input Parameter Development
    - 2.3.5.3.2.2.1 Input Parameter Descriptions
    - 2.3.5.3.2.2.2 Input Parameter Uncertainty
- 2.3.5.3.3 Model and Model Uncertainty
  - 2.3.5.3.3.1 Model Development and Alternative Conceptualizations
  - 2.3.5.3.3.2 Model Description
    - 2.3.5.3.3.2.1 Assumptions, Model Domain, and Boundary Conditions
    - 2.3.5.3.3.2.2 Starting Pore-Water Compositions
    - 2.3.5.3.3.2.3 Water–Rock Interactions
    - 2.3.5.3.3.2.4 Treatment of Calcite and Silica Polymorphs
    - 2.3.5.3.3.2.5 Treatment of Alkali Feldspar
    - 2.3.5.3.3.2.6 Modeling the Evolution of the Thermal Field
    - 2.3.5.3.3.2.7 Modeling Flow Through the TSw
    - 2.3.5.3.3.2.8 Calculating the Amount of Feldspar Dissolved as Water Percolates through the Thermal Field
    - 2.3.5.3.3.2.9 Liquid-Gas Exchange along the Flow Path
    - 2.3.5.3.3.2.10 Predicting the Composition of Potential Seepage Waters
    - 2.3.5.3.3.2.11 The In-Drift Gas Composition
  - 2.3.5.3.3.3 Model Results
  - 2.3.5.3.3.4 Model Limitations, Approximations, and Uncertainty
  - 2.3.5.3.3.5 Model Support
    - 2.3.5.3.3.5.1 Strontium Isotopic Data
    - 2.3.5.3.3.5.2 Prediction of Ambient Pore-Water Compositional Trends and Alteration Mineral Assemblages
    - 2.3.5.3.3.5.3 Comparisons to the Thermal-Hydrologic-Chemical Seepage Model
    - 2.3.5.3.3.5.4 Comparison to Drift Scale Test Gas Phase Data
    - 2.3.5.3.3.5.5 Summary of Near-Field Chemistry Model Confidence Building Activities
- 2.3.5.3.4 TSPA Implementation of the Near-Field Chemistry Model
- 2.3.5.4 In-Drift Thermal-Hydrologic Environment
  - 2.3.5.4.1 Multiscale Thermal-Hydrologic Model
    - 2.3.5.4.1.1 Conceptual Description
      - 2.3.5.4.1.1.1 Thermal Hydrology in Repository Host Rock

**CONTENTS (Continued)**

- 2.3.5.4.1.1.2 Thermal Hydrology in Drifts
- 2.3.5.4.1.1.3 Time-Based Summary of Postclosure Thermal Regimes
- 2.3.5.4.1.2 Data and Data Uncertainty
  - 2.3.5.4.1.2.1 Data Sources
  - 2.3.5.4.1.2.2 Input Parameter Development
- 2.3.5.4.1.3 Model and Model Uncertainty
  - 2.3.5.4.1.3.1 Model Description
  - 2.3.5.4.1.3.2 Model Results
  - 2.3.5.4.1.3.3 Model Support and Uncertainty
- 2.3.5.4.1.4 Model Abstraction
  - 2.3.5.4.1.4.1 Abstraction Methodology
  - 2.3.5.4.1.4.2 Abstraction Implementation in TSPA
- 2.3.5.4.2 In-Drift Condensation Model
  - 2.3.5.4.2.1 Conceptual Description
  - 2.3.5.4.2.2 Data and Data Uncertainty
  - 2.3.5.4.2.3 Model and Model Uncertainty
    - 2.3.5.4.2.3.1 Model Description and Limitations
    - 2.3.5.4.2.3.2 Model Results
    - 2.3.5.4.2.3.3 Model Uncertainty
    - 2.3.5.4.2.3.4 Model Support
  - 2.3.5.4.2.4 Model Abstraction and Implementation in the TSPA
- 2.3.5.4.3 Near-Field Response to the Range of Design Thermal Loadings
- 2.3.5.5 In-Drift Chemical Environment Models
  - 2.3.5.5.1 Conceptual Description
  - 2.3.5.5.2 Data and Data Uncertainty
  - 2.3.5.5.3 Model and Model Uncertainty
    - 2.3.5.5.3.1 Model Description
    - 2.3.5.5.3.2 Seepage Evaporation Analyses and Results
    - 2.3.5.5.3.3 Model Support and Uncertainty
      - 2.3.5.5.3.3.1 Model Support
      - 2.3.5.5.3.3.2 Model Uncertainty
  - 2.3.5.5.4 Abstraction and TSPA Implementation
    - 2.3.5.5.4.1 Gas Phase Composition
      - 2.3.5.5.4.1.1 Oxygen Concentrations
      - 2.3.5.5.4.1.2 Carbon Dioxide Concentrations
    - 2.3.5.5.4.2 Seepage Evaporation Abstraction
      - 2.3.5.5.4.2.1 Seepage Evaporation Abstraction Description

**CONTENTS (Continued)**

- 2.3.5.5.4.2.2 Seepage Evaporation Abstraction Support and Uncertainty
- 2.3.5.5.4.3 TSPA Implementation of the Seepage Evaporation Abstraction
- 2.3.5.6 Conclusions
- 2.3.5.7 General References
- 2.3.6 Waste Package and Drip Shield Corrosion
  - 2.3.6.1 Summary and Overview
    - 2.3.6.1.1 Processes Contributing to EBS Barrier Capability
    - 2.3.6.1.2 Corrosion Test Environments and Relationship to In-Drift Chemical Environment
  - 2.3.6.2 Implementation of the Waste Package and Drip Shield Corrosion Models in Total System Performance Assessment
    - 2.3.6.2.1 Summary of Features, Events, and Processes Included in Waste Package and Drip Shield Corrosion Models
    - 2.3.6.2.2 Waste Package Degradation Processes
    - 2.3.6.2.3 Drip Shield Degradation Processes
    - 2.3.6.2.4 Total System Performance Assessment Treatment of Corrosion Uncertainty
  - 2.3.6.3 General Corrosion of the Waste Package Outer Barrier
    - 2.3.6.3.1 Conceptual Description
    - 2.3.6.3.2 Data and Data Uncertainty
      - 2.3.6.3.2.1 Long-Term Weight-Loss Measurements
      - 2.3.6.3.2.2 Temperature Dependence
      - 2.3.6.3.2.3 Effect of Microbial Activity
    - 2.3.6.3.3 Model and Model Uncertainty
      - 2.3.6.3.3.1 General Corrosion Model
      - 2.3.6.3.3.2 Microbially Influenced Corrosion
    - 2.3.6.3.4 Abstraction and Adequacy
      - 2.3.6.3.4.1 Abstraction for General Corrosion
      - 2.3.6.3.4.2 Model Adequacy
  - 2.3.6.4 Localized Corrosion of Waste Package
    - 2.3.6.4.1 Conceptual Description
    - 2.3.6.4.2 Data and Data Uncertainty
      - 2.3.6.4.2.1 Open-Circuit Corrosion Potential Data
      - 2.3.6.4.2.2 Cyclic Polarization Data
      - 2.3.6.4.2.3 Localized Corrosion Propagation Rate Data
    - 2.3.6.4.3 Model and Model Uncertainty
      - 2.3.6.4.3.1 Localized Corrosion Initiation Model

**CONTENTS (Continued)**

- 2.3.6.4.3.1.1 Localized Corrosion Initiation Model Development
- 2.3.6.4.3.1.2 Localized Corrosion Initiation Model Results
- 2.3.6.4.3.1.3 Conservatism for Localized Corrosion Initiation Model
- 2.3.6.4.3.2 Localized Corrosion Propagation Model
  - 2.3.6.4.3.2.1 Localized Corrosion Constant Propagation Model
  - 2.3.6.4.3.2.2 Alternative Conceptual Model for Time-Dependent Propagation Rate
- 2.3.6.4.4 Abstraction and Adequacy
  - 2.3.6.4.4.1 Abstracted Model for Localized Corrosion
  - 2.3.6.4.4.2 Localized Corrosion Model Adequacy
    - 2.3.6.4.4.2.1 Localized Corrosion Initiation Model Adequacy
    - 2.3.6.4.4.2.2 Localized Corrosion Propagation Model Adequacy
- 2.3.6.5 Stress Corrosion Cracking of the Waste Package Outer Barrier
  - 2.3.6.5.1 Conceptual Description
  - 2.3.6.5.2 Data and Data Uncertainty
    - 2.3.6.5.2.1 Threshold Stress Criterion for Initiation of Stress Corrosion Cracking
      - 2.3.6.5.2.1.1 Constant-Load Crack-Initiation Tests
      - 2.3.6.5.2.1.2 Slow Strain Rate Testing in Concentrated Brines
      - 2.3.6.5.2.1.3 U-Bend SCC Initiation Tests
    - 2.3.6.5.2.2 Weld Flaws and Incipient Cracks
    - 2.3.6.5.2.3 Stress and Stress Intensity Factor Profiles
    - 2.3.6.5.2.4 Stress Corrosion Crack Growth Rates for Alloy 22
  - 2.3.6.5.3 Model and Model Uncertainty
    - 2.3.6.5.3.1 Weld Flaw Analysis
    - 2.3.6.5.3.2 Stress Corrosion Cracking Model
    - 2.3.6.5.3.3 Alternative Conceptual Model
  - 2.3.6.5.4 Abstraction and Adequacy
    - 2.3.6.5.4.1 Waste Package Stress Corrosion Cracking Abstraction and Uncertainty
    - 2.3.6.5.4.2 Model Adequacy
- 2.3.6.6 Early Failure of Waste Packages
  - 2.3.6.6.1 Conceptual Description
  - 2.3.6.6.2 Data and Data Uncertainty
    - 2.3.6.6.2.1 Possible Defects Identified from Literature
    - 2.3.6.6.2.2 Human Error Probability Data

**CONTENTS (Continued)**

- 2.3.6.6.3 Analysis and Uncertainty
  - 2.3.6.6.3.1 Evaluation of Defect Types
  - 2.3.6.6.3.2 Determination of Early Failure Probability
    - 2.3.6.6.3.2.1 Improper Base Metal Selection
    - 2.3.6.6.3.2.2 Improper Weld Filler Material Selection
    - 2.3.6.6.3.2.3 Improper Heat Treatment of Outer Corrosion Barrier
    - 2.3.6.6.3.2.4 Improper Heat Treatment of Outer Lid
    - 2.3.6.6.3.2.5 Improper Low-Plasticity Burnishing
    - 2.3.6.6.3.2.6 Improper Handling
    - 2.3.6.6.3.2.7 Early Waste Package Failure Probability
  - 2.3.6.6.4 Abstraction and Adequacy
    - 2.3.6.6.4.1 Abstraction
    - 2.3.6.6.4.2 Abstraction Adequacy
- 2.3.6.7 Effects of Long-Term Thermal Aging and Phase Stability of Alloy 22
  - 2.3.6.7.1 Conceptual Description
  - 2.3.6.7.2 Data and Data Uncertainty
    - 2.3.6.7.2.1 Experimental Results
    - 2.3.6.7.2.2 Data Uncertainty
  - 2.3.6.7.3 Model and Model Uncertainty
    - 2.3.6.7.3.1 Thermal Aging Model
    - 2.3.6.7.3.2 Alternative Conceptual Model
    - 2.3.6.7.3.3 Natural Analogues
  - 2.3.6.7.4 Summary
  - 2.3.6.7.5 Effect of Aging and Phase Stability on Corrosion Behavior
- 2.3.6.8 Drip Shield Degradation
  - 2.3.6.8.1 General Corrosion
    - 2.3.6.8.1.1 Conceptual Description
    - 2.3.6.8.1.2 Data and Data Uncertainty
      - 2.3.6.8.1.2.1 Weight-Loss Data
      - 2.3.6.8.1.2.2 Microbially Influenced Corrosion Data
    - 2.3.6.8.1.3 Model and Model Uncertainty
    - 2.3.6.8.1.4 Drip Shield General Corrosion Model Abstraction
    - 2.3.6.8.1.5 General Corrosion Model Adequacy
  - 2.3.6.8.2 Localized Corrosion
    - 2.3.6.8.2.1 Conceptual Description
    - 2.3.6.8.2.2 Data
    - 2.3.6.8.2.3 Localized Corrosion Model
    - 2.3.6.8.2.4 Localized Corrosion Model Adequacy

**CONTENTS (Continued)**

- 2.3.6.8.3 Stress Corrosion Cracking of Drip Shield
- 2.3.6.8.4 Drip Shield Early Failure
  - 2.3.6.8.4.1 Conceptual Description
  - 2.3.6.8.4.2 Data and Data Uncertainty
  - 2.3.6.8.4.3 Analysis and Uncertainty
    - 2.3.6.8.4.3.1 Evaluation of Defect Types
    - 2.3.6.8.4.3.2 Determination of Early Failure Probability
      - 2.3.6.8.4.3.2.1 Base Metal Flaws
      - 2.3.6.8.4.3.2.2 Improper Weld Filler Material
      - 2.3.6.8.4.3.2.3 Improper Heat Treatment
      - 2.3.6.8.4.3.2.4 Improper Drip Shield Installation
      - 2.3.6.8.4.3.2.5 Early Drip Shield Failure Probability
  - 2.3.6.8.4.4 Abstraction and Adequacy
    - 2.3.6.8.4.4.1 Abstraction
    - 2.3.6.8.4.4.2 Abstraction Adequacy
- 2.3.6.8.5 Creep Deformation
- 2.3.6.8.6 Aging and Phase Stability
- 2.3.6.9 Conclusions
  - 2.3.6.9.1 Summary of Significant Processes for EBS Barrier Capability
  - 2.3.6.9.2 Key Uncertainties Associated with Barrier Capability
  - 2.3.6.9.3 Key Conservatism in Models Used to Assess Barrier Capability
  - 2.3.6.9.4 Summary of Key Abstraction Parameters Provided to TSPA and Consistency with Process Models
- 2.3.6.10 General References
- 2.3.7 Waste Form Degradation and Mobilization and Engineered Barrier System Flow and Transport
  - 2.3.7.1 Summary and Overview
  - 2.3.7.2 Summary of FEPs Evaluated in Waste Form Degradation and In-Drift Radionuclide Transport Models
  - 2.3.7.3 Implementation of Conceptual Models
    - 2.3.7.3.1 Nominal and Early Failure Scenario Classes
    - 2.3.7.3.2 Waste Form Degradation and Radionuclide Transport in the Seismic Scenario Class
    - 2.3.7.3.3 Waste Form Degradation and Radionuclide Transport in the Igneous Scenario
  - 2.3.7.4 Radionuclide Inventory
    - 2.3.7.4.1 Conceptual Description
      - 2.3.7.4.1.1 Waste Packaging and Waste Types to Be Disposed
      - 2.3.7.4.1.2 Radionuclide Screening and Radionuclide Inventory



**CONTENTS (Continued)**

- 2.3.7.4.2 Data and Data Uncertainty
  - 2.3.7.4.2.1 Commercial SNF Inventory Data and Data Uncertainty
  - 2.3.7.4.2.2 U.S. Department of Energy SNF Inventory Data and Data Uncertainty
  - 2.3.7.4.2.3 HLW Inventory Data and Data Uncertainty
- 2.3.7.4.3 Abstraction and Results
- 2.3.7.5 In-Package Water Chemistry
  - 2.3.7.5.1 Conceptual Description of the In-Package Water Chemistry
  - 2.3.7.5.2 Data and Data Uncertainty of the In-Package Water Chemistry
  - 2.3.7.5.3 Model and Model Uncertainty
    - 2.3.7.5.3.1 Results and Abstraction
    - 2.3.7.5.3.2 Validation
- 2.3.7.6 Commercial Spent Nuclear Fuel Cladding Degradation
- 2.3.7.7 Commercial Spent Nuclear Fuel Degradation
  - 2.3.7.7.1 Conceptual Description of Commercial Spent Nuclear Fuel Degradation
  - 2.3.7.7.2 Data and Data Uncertainty
  - 2.3.7.7.3 Model, Model Uncertainty, Abstraction, and Results
    - 2.3.7.7.3.1 Model for Release of Gap and Grain Boundary Inventory
    - 2.3.7.7.3.2 Model of Radionuclide Release from Matrix
- 2.3.7.8 U. S. Department of Energy Spent Nuclear Fuel Degradation
  - 2.3.7.8.1 Conceptual Description
  - 2.3.7.8.2 Data and Data Uncertainty
  - 2.3.7.8.3 Model, Model Uncertainty, Abstraction, and Results
- 2.3.7.9 High-Level Radioactive Waste Glass Dissolution
  - 2.3.7.9.1 Conceptual Description
  - 2.3.7.9.2 Data and Data Uncertainty
  - 2.3.7.9.3 Model, Model Uncertainty, Abstraction and Results
    - 2.3.7.9.3.1 Uncertainty in the HLW Glass Dissolution Model
    - 2.3.7.9.3.2 Model Validation
- 2.3.7.10 Dissolved Radionuclide Concentration Limits
  - 2.3.7.10.1 Conceptual Description
  - 2.3.7.10.2 Data and Data Uncertainty
  - 2.3.7.10.3 Model, Model Uncertainty, Abstraction and Results
    - 2.3.7.10.3.1 Plutonium
    - 2.3.7.10.3.2 Neptunium
    - 2.3.7.10.3.3 Uranium
    - 2.3.7.10.3.4 Thorium

**CONTENTS (Continued)**

- 2.3.7.10.3.5 Americium
- 2.3.7.10.3.6 Protactinium
- 2.3.7.10.3.7 Radium
- 2.3.7.10.3.8 Technetium, Carbon, Iodine, Cesium, Strontium, Selenium, and Chlorine
- 2.3.7.11 Colloidal Radionuclide Availability
  - 2.3.7.11.1 Conceptual Description
  - 2.3.7.11.2 Data and Data Uncertainty
    - 2.3.7.11.2.1 Tests on Commercial Spent Nuclear Fuel, U. S. Department of Energy Spent Nuclear Fuel, and High-Level Radioactive Waste Glass
    - 2.3.7.11.2.2 Tests to Examine Colloid Generation from Steel Corrosion
    - 2.3.7.11.2.3 Tests to Characterize Seepage Water Colloids
    - 2.3.7.11.2.4 Radionuclide Sorption Data
  - 2.3.7.11.3 Model and Model Uncertainty
    - 2.3.7.11.3.1 Validation
    - 2.3.7.11.3.2 Alternative Conceptual Models
- 2.3.7.12 Engineered Barrier System Flow and Transport Model
  - 2.3.7.12.1 Conceptual Description
  - 2.3.7.12.2 Data and Data Uncertainty
  - 2.3.7.12.3 Model and Model Uncertainty
    - 2.3.7.12.3.1 EBS Flow
    - 2.3.7.12.3.2 EBS Transport
    - 2.3.7.12.3.3 Model Uncertainties
    - 2.3.7.12.3.4 Model Validation
    - 2.3.7.12.3.5 Alternative Conceptual Models
- 2.3.7.13 Conclusions
  - 2.3.7.13.1 Summary of Significant Processes for EBS Capability
  - 2.3.7.13.2 Summary of Key Uncertainties Associated with EBS Capability
  - 2.3.7.13.3 Summary of Key Conservatisms in Models Used to Assess EBS Capability
  - 2.3.7.13.4 Summary of Consistency Between TSPA Model Abstractions and Process Models
  - 2.3.7.13.5 Summary of Key Outputs Provided to the TSPA
- 2.3.7.14 General References
- 2.3.8 Radionuclide Transport in Unsaturated Zone
  - 2.3.8.1 Summary and Overview
  - 2.3.8.2 Conceptual Description of Unsaturated Zone Transport Processes

**CONTENTS (Continued)**

- 2.3.8.2.1 Relationship of Radionuclide Transport to Other Components of the Repository System
- 2.3.8.2.2 Conceptual Description of Unsaturated Zone Radionuclide Transport Processes
  - 2.3.8.2.2.1 Advection, Matrix Diffusion, and Dispersion
  - 2.3.8.2.2.2 Sorption
  - 2.3.8.2.2.3 Colloid Transport
- 2.3.8.2.3 Temperature Effects on Transport Properties
- 2.3.8.3 Data and Data Uncertainty
  - 2.3.8.3.1 Laboratory Sorption Measurements
  - 2.3.8.3.2 Laboratory Matrix Diffusion Measurements
  - 2.3.8.3.3 Field Test Observations
    - 2.3.8.3.3.1 Busted Butte Test Series
      - 2.3.8.3.3.1.1 Phase 1A Test
      - 2.3.8.3.3.1.2 Phase 1B Tests
      - 2.3.8.3.3.1.3 Phase 2 Tests
      - 2.3.8.3.3.1.4 Results of Busted Butte Test Series
      - 2.3.8.3.3.1.5 Radionuclide Migration Experiments Using Tuff Samples from Busted Butte
    - 2.3.8.3.3.2 Alcove 8–Niche 3 Test
      - 2.3.8.3.3.2.1 Alcove 8–Niche 3 Fault Test
      - 2.3.8.3.3.2.2 Alcove 8–Niche 3 Large Plot Test
    - 2.3.8.3.3.3 Alcove 1 Tests
  - 2.3.8.3.4 Colloid Data Sources and Testing
  - 2.3.8.3.5 Chlorine-36
- 2.3.8.4 Model Development
  - 2.3.8.4.1 Framework for Unsaturated Zone Transport
  - 2.3.8.4.2 Alternative Conceptual and Numerical Models of Unsaturated Zone Radionuclide Transport
  - 2.3.8.4.3 Description of the Unsaturated Zone Radionuclide Transport Process Model
  - 2.3.8.4.4 Building Confidence in the Unsaturated Zone Radionuclide Transport Process Model
    - 2.3.8.4.4.1 Busted Butte Phase 1A Test
    - 2.3.8.4.4.2 Busted Butte Phase 1B Test
    - 2.3.8.4.4.3 Busted Butte Phase 2C Test
    - 2.3.8.4.4.4 Alcove 8–Niche 3 Test
      - 2.3.8.4.4.4.1 Alcove 8–Niche 3 Fault Test
      - 2.3.8.4.4.4.2 Alcove 8–Niche 3 Large Plot Test
      - 2.3.8.4.4.4.3 Implications of Alcove 8–Niche 3 Tests

**CONTENTS (Continued)**

- 2.3.8.4.4.5 Modeling of the Alcove 1 Test Results
- 2.3.8.4.4.6 Other Data and Natural Analogues Used for Model Confidence
- 2.3.8.4.5 Impacts of Uncertainties and Variabilities
  - 2.3.8.4.5.1 Variability in Flow Paths and Transport Times
  - 2.3.8.4.5.2 Uncertainties in Matrix Diffusion and Fracture–Matrix Interaction
  - 2.3.8.4.5.3 Uncertainties in Sorption
  - 2.3.8.4.5.4 Uncertainties in Colloid Filtration
  - 2.3.8.4.5.5 Impacts of Climate Variabilities and Uncertainties
- 2.3.8.5 Model Abstraction
  - 2.3.8.5.1 Particle-Tracking Methodology
  - 2.3.8.5.2 Transport Mechanisms and Associated Inputs Required for Model Abstraction
    - 2.3.8.5.2.1 Advection
    - 2.3.8.5.2.2 Dispersion
    - 2.3.8.5.2.3 Sorption
    - 2.3.8.5.2.4 Matrix Diffusion
    - 2.3.8.5.2.5 Colloid-Facilitated Transport
    - 2.3.8.5.2.6 Radioactive Decay
  - 2.3.8.5.3 Radionuclide Transport under Future Climatic Conditions
  - 2.3.8.5.4 Comparison of Transport of Radionuclide Species
  - 2.3.8.5.5 Sensitivity Analyses of the Unsaturated Zone Radionuclide Transport Abstraction Model
    - 2.3.8.5.5.1 Uncertainty in Transport Parameters and Models
    - 2.3.8.5.5.2 Sensitivity to Hydrologic Properties
    - 2.3.8.5.5.3 Sensitivity to Fracture–Matrix Interaction Parameters
  - 2.3.8.5.6 Building Confidence in the Unsaturated Zone Radionuclide Transport Abstraction Model
    - 2.3.8.5.6.1 Sensitivity to Numerical Approach for Treating Fracture–Matrix Interaction
    - 2.3.8.5.6.2 Comparison with the Unsaturated Zone Radionuclide Transport Process Model
- 2.3.8.6 Conclusions
- 2.3.8.7 General References
- 2.3.9 Saturated Zone Flow and Transport
  - 2.3.9.1 Summary and Overview
  - 2.3.9.2 Saturated Zone Flow System
    - 2.3.9.2.1 Conceptual Description
    - 2.3.9.2.2 Data and Data Uncertainty

**CONTENTS (Continued)**

- 2.3.9.2.2.1 Hydrogeologic Properties
- 2.3.9.2.2.2 Hydrogeologic Framework
- 2.3.9.2.2.3 Groundwater Recharge, Discharge, and Volumetric Flow Rates at the Boundaries of the Site-Scale Saturated Zone Flow Model
- 2.3.9.2.2.4 Water Level Data and Potentiometric Surface
- 2.3.9.2.2.5 Geochemistry
- 2.3.9.2.2.6 Expert Elicitation
- 2.3.9.2.3 Site-Scale Saturated Zone Flow Model and Model Uncertainty
  - 2.3.9.2.3.1 Site-Scale Saturated Zone Flow Model Development
  - 2.3.9.2.3.2 Site-Scale Saturated Zone Flow Model Calibration
  - 2.3.9.2.3.3 Calibration Results
  - 2.3.9.2.3.4 Site-Scale Saturated Zone Model Uncertainty and Sensitivity Analyses
  - 2.3.9.2.3.5 Uncertainty in Specific Discharge
  - 2.3.9.2.3.6 Parameter Uncertainty
- 2.3.9.2.4 Model Abstraction and Confidence Building
  - 2.3.9.2.4.1 Model Abstraction
  - 2.3.9.2.4.2 Confidence Building
- 2.3.9.3 Saturated Zone Radionuclide Transport
  - 2.3.9.3.1 Conceptual Description
  - 2.3.9.3.2 Data and Data Uncertainty
    - 2.3.9.3.2.1 Advection, Matrix Diffusion, and Dispersion Processes and Parameters
    - 2.3.9.3.2.2 Radionuclide Sorption Parameters and Mineral Precipitation Effects
    - 2.3.9.3.2.3 Colloid-Facilitated Transport
      - 2.3.9.3.2.3.1 Test Results for Radionuclide Sorption onto Colloids
      - 2.3.9.3.2.3.2 Test Results for Colloid Concentration in Groundwater
      - 2.3.9.3.2.3.3 Test Results for Colloid Transport in Fractured Volcanic Rock
      - 2.3.9.3.2.3.4 Test Results for Colloid Transport in Alluvial Material
      - 2.3.9.3.2.3.5 Estimates of Fractions of Colloids Transporting with No Retardation
  - 2.3.9.3.3 Site-Scale Saturated Zone Transport Model and Model Uncertainty
    - 2.3.9.3.3.1 Site-Scale Saturated Zone Transport Model Development

**CONTENTS (Continued)**

- 2.3.9.3.3.2 Description of the Uncertainty Incorporated into the Model
- 2.3.9.3.3.3 Consideration of Alternative Conceptual Models
  - 2.3.9.3.3.3.1 Fluid Flow in Matrix Blocks
  - 2.3.9.3.3.3.2 Irreversible Sorption onto Volcanic Rocks and Alluvium
  - 2.3.9.3.3.3.3 Sorption Reactions that are not Instantaneous
  - 2.3.9.3.3.3.4 Water Table Rise
  - 2.3.9.3.3.3.5 Locally Varying Sorption Parameters
  - 2.3.9.3.3.3.6 Channeling in Alluvium
  - 2.3.9.3.3.3.7 Diffusion into Low-Permeability Zones in the Alluvium
  - 2.3.9.3.3.3.8 Alternative Site-Scale Saturated Zone Flow Model
  - 2.3.9.3.3.3.9 Minimal Matrix Diffusion
- 2.3.9.3.3.4 Data/Parameter Uncertainty
- 2.3.9.3.4 Model Abstraction and Confidence Building
  - 2.3.9.3.4.1 The Saturated Zone Transport Abstraction Model
    - 2.3.9.3.4.1.1 Methods and Results
    - 2.3.9.3.4.1.2 Abstraction Model and Process Model Comparison
    - 2.3.9.3.4.1.3 Comparison of Site-Scale Saturated Zone Transport Model Results to Empirical Observation
    - 2.3.9.3.4.1.4 Analogues to Saturated Zone Radionuclide Transport
      - 2.3.9.3.4.1.4.1 Colloidal Transport in the Saturated Zone
      - 2.3.9.3.4.1.4.2 Uranium Studies
  - 2.3.9.3.4.2 Saturated Zone One-Dimensional Transport Model
    - 2.3.9.3.4.2.1 Saturated Zone One-Dimensional Transport Model Abstraction
    - 2.3.9.3.4.2.2 Saturated Zone One-Dimensional Abstraction Model and Process Model Comparison
- 2.3.9.4 Conclusions
- 2.3.9.5 General References
- 2.3.10 Biosphere Transport and Exposure
  - 2.3.10.1 Summary and Overview
  - 2.3.10.2 Conceptual Model of Biosphere Transport, Receptor, and Receptor Exposure
    - 2.3.10.2.1 Information Used to Characterize the Reference Biosphere

**CONTENTS (Continued)**

- 2.3.10.2.2 Information Used to Characterize the Reasonably Maximally Exposed Individual
- 2.3.10.2.3 Radionuclide Transport and Exposure Pathways
- 2.3.10.2.4 Radioactive Decay and Ingrowth in the Biosphere
- 2.3.10.2.5 Conceptual Model for the Groundwater Exposure Scenario
- 2.3.10.2.6 Conceptual Model for the Volcanic Ash Exposure Scenario
- 2.3.10.3 Data and Data Uncertainty
  - 2.3.10.3.1 Groundwater Exposure Scenario
    - 2.3.10.3.1.1 Surface Soil Submodel
    - 2.3.10.3.1.2 Air Submodel
    - 2.3.10.3.1.3 Plant Uptake Submodel
    - 2.3.10.3.1.4 Animal Uptake Submodel
    - 2.3.10.3.1.5 Fish Uptake Submodel
    - 2.3.10.3.1.6 <sup>14</sup>C Submodel
    - 2.3.10.3.1.7 External Exposure Submodel
    - 2.3.10.3.1.8 Inhalation Submodel
    - 2.3.10.3.1.9 Ingestion Submodel
  - 2.3.10.3.2 Volcanic Ash Exposure Scenario
    - 2.3.10.3.2.1 Surface Soil Submodel
    - 2.3.10.3.2.2 Air Submodel
    - 2.3.10.3.2.3 Plant Uptake Submodel
    - 2.3.10.3.2.4 Animal Uptake Submodel
    - 2.3.10.3.2.5 External Exposure Submodel
    - 2.3.10.3.2.6 Inhalation Submodel
    - 2.3.10.3.2.7 Ingestion Submodel
- 2.3.10.4 Model Uncertainty
  - 2.3.10.4.1 Conceptual Model Uncertainty
  - 2.3.10.4.2 Mathematical Model Uncertainty
- 2.3.10.5 Abstraction
  - 2.3.10.5.1 Groundwater Exposure Scenario
    - 2.3.10.5.1.1 Biosphere Dose Conversion Factors
    - 2.3.10.5.1.2 Individual Protection Standards Dose Calculations—  
Groundwater Exposure Scenario
  - 2.3.10.5.2 Volcanic Ash Exposure Scenario
    - 2.3.10.5.2.1 Biosphere Dose Conversion Factors
    - 2.3.10.5.2.2 Individual Protection Standard Dose Calculations—  
Volcanic Ash Exposure Scenario
- 2.3.10.6 Conclusions
- 2.3.10.7 General References

---

**CONTENTS (Continued)**

- 2.3.11 Igneous Activity
  - 2.3.11.1 Summary and Overview
  - 2.3.11.2 System Description and Integration
    - 2.3.11.2.1 Conceptual Model of Igneous Activity
      - 2.3.11.2.1.1 Igneous Framework
      - 2.3.11.2.1.2 Igneous Processes
      - 2.3.11.2.1.3 Postigneous Processes
    - 2.3.11.2.2 Probability of an Igneous Event Intersecting the Repository Footprint
      - 2.3.11.2.2.1 Definition of Event
      - 2.3.11.2.2.2 Process Used for Probabilistic Volcanic Hazard Analysis
      - 2.3.11.2.2.3 Probability of Future Igneous Intersection of the Repository
      - 2.3.11.2.2.4 Probability Model Support
      - 2.3.11.2.2.5 Geologic Basis for the Probabilistic Volcanic Hazard Analysis
      - 2.3.11.2.2.6 Alternative Estimates of the Intersection Probability
    - 2.3.11.2.3 Model Integration
  - 2.3.11.3 Igneous Intrusion Modeling Case
    - 2.3.11.3.1 Conceptual Model
    - 2.3.11.3.2 Model and Analysis Descriptions
      - 2.3.11.3.2.1 Natural and Induced Stresses at the Repository
      - 2.3.11.3.2.2 Dike Propagation from Depth
      - 2.3.11.3.2.3 Magma Flow in Drifts
      - 2.3.11.3.2.4 Effects on Waste Packages and Waste Forms
      - 2.3.11.3.2.5 Secondary Dike Propagation
      - 2.3.11.3.2.6 Magma Flow between Drifts
      - 2.3.11.3.2.7 Waste Packages Compromised During Igneous Intrusion
      - 2.3.11.3.2.8 Heat Flow and Magma Cooling
      - 2.3.11.3.2.9 Percolation Flux Through Cooled Basalt
    - 2.3.11.3.3 Data Uncertainty
      - 2.3.11.3.3.1 Natural and Induced Stresses at the Repository
      - 2.3.11.3.3.2 Dike Propagation from Depth
      - 2.3.11.3.3.3 Magma Flow in Drifts
      - 2.3.11.3.3.4 Effects on Waste Packages and Waste Forms
      - 2.3.11.3.3.5 Secondary Dike Propagation
      - 2.3.11.3.3.6 Magma flow Between Drifts



**CONTENTS (Continued)**

- 2.3.11.3.3.7 Waste Packages Compromised During an Igneous Intrusion
- 2.3.11.3.3.8 Heat Flow and Magma Cooling
- 2.3.11.3.3.9 Percolation Flux through Cooled Basalt
- 2.3.11.3.4 Model and Analysis Uncertainty and Alternative Models
  - 2.3.11.3.4.1 Natural and Induced Stresses at the Repository
  - 2.3.11.3.4.2 Dike Propagation from Depth
  - 2.3.11.3.4.3 Magma Flow in Drifts
  - 2.3.11.3.4.4 Secondary Dike Propagation
  - 2.3.11.3.4.5 Magma Flow Between Drifts
  - 2.3.11.3.4.6 Effects on Waste Packages and Waste Forms
  - 2.3.11.3.4.7 Waste Packages Compromised During an Igneous Intrusion
  - 2.3.11.3.4.8 Heat Flow and Magma Cooling
  - 2.3.11.3.4.9 Percolation Flux Through Cooled Basalt
- 2.3.11.3.5 Igneous Intrusion Model Abstraction
- 2.3.11.4 Volcanic Eruption Modeling Case
  - 2.3.11.4.1 Conceptual Model
    - 2.3.11.4.1.1 Eruption Model
      - 2.3.11.4.1.1.1 Number of Waste Packages Intersected by Eruptive Conduits
      - 2.3.11.4.1.1.2 Atmospheric Dispersal and Deposition of Tephra
      - 2.3.11.4.1.1.3 Tephra Redistribution
  - 2.3.11.4.2 Model/Analysis Description
    - 2.3.11.4.2.1 Number of Waste Packages Intersected by Conduits During an Eruption
      - 2.3.11.4.2.1.1 Formulation
      - 2.3.11.4.2.1.2 Analysis Parameters
      - 2.3.11.4.2.1.3 Results
    - 2.3.11.4.2.2 Atmospheric Dispersal and Deposition of Tephra
      - 2.3.11.4.2.2.1 Formulation
      - 2.3.11.4.2.2.2 Model Parameters
      - 2.3.11.4.2.2.3 Results
    - 2.3.11.4.2.3 Tephra Redistribution
      - 2.3.11.4.2.3.1 Formulation
      - 2.3.11.4.2.3.2 Model Parameters
      - 2.3.11.4.2.3.3 Model Results
  - 2.3.11.4.3 Data Uncertainty
    - 2.3.11.4.3.1 Number of Waste Packages Intersected by Eruptive Conduits

---

**CONTENTS (Continued)**

- 2.3.11.4.3.2 Atmospheric Dispersal and Deposition of Tephra
- 2.3.11.4.4 Model and Analysis Uncertainty and Alternative Models
  - 2.3.11.4.4.1 Number of Waste Packages Intersected by Eruptive Conduits
  - 2.3.11.4.4.2 Atmospheric Dispersal and Deposition of Tephra
  - 2.3.11.4.4.3 Tephra Redistribution
- 2.3.11.4.5 Volcanic Eruption Model Abstraction
  - 2.3.11.4.5.1 Number of Waste Packages Intersected by Eruptive Conduits
  - 2.3.11.4.5.2 Atmospheric Dispersal and Deposition of Tephra
  - 2.3.11.4.5.3 Tephra Redistribution
- 2.3.11.5 Summary of Igneous Scenario Class Model Abstraction
- 2.3.11.6 Conclusions
  - 2.3.11.6.1 Igneous Features, Events, and Processes
  - 2.3.11.6.2 Probability of Future Intersection and Consequences
  - 2.3.11.6.3 Uncertainties Associated with Igneous Activity
  - 2.3.11.6.4 Assumptions in Models Used to Assess Igneous Activity
  - 2.3.11.6.5 Conservatism in Models Used to Assess Igneous Activity
  - 2.3.11.6.6 Summary of Consistency Between TSPA Model Abstractions and Process Models
  - 2.3.11.6.7 Summary of Key Output Parameters Provided to TSPA
- 2.3.11.7 General References
- 2.4 DEMONSTRATION OF COMPLIANCE WITH THE POSTCLOSURE PUBLIC HEALTH AND ENVIRONMENTAL STANDARDS
  - 2.4.1 Total System Performance Assessment Model
    - 2.4.1.1 TSPA Method and Approach
    - 2.4.1.2 Scenario Classes and Modeling Cases
      - 2.4.1.2.1 Nominal Scenario Class
      - 2.4.1.2.2 Early Failure Scenario Class
      - 2.4.1.2.3 Igneous Scenario Class
      - 2.4.1.2.4 Seismic Scenario Class
    - 2.4.1.3 TSPA Computational Structure
    - 2.4.1.4 Summary of TSPA Model
    - 2.4.1.5 Summary of TSPA Model Results
  - 2.4.2 Demonstration of Compliance with the Postclosure Individual Protection Standard
    - 2.4.2.1 Scenario Classes and Modeling Cases Used in the Calculation of Annual Dose
      - 2.4.2.1.1 Treatment of Aleatory and Epistemic Uncertainty
      - 2.4.2.1.2 Calculation of Total Mean and Median Annual Dose

**CONTENTS (Continued)**

- 2.4.2.1.3 Event and Scenario Classes
- 2.4.2.1.4 Total Expected Annual Dose Approximations
- 2.4.2.1.5 Modeling Cases
  - 2.4.2.1.5.1 Nominal Scenario Class
  - 2.4.2.1.5.2 Early Failure Scenario Class
  - 2.4.2.1.5.3 Igneous Scenario Class
  - 2.4.2.1.5.4 Seismic Scenario Class
- 2.4.2.1.6 Scenario Class Probabilities
- 2.4.2.1.7 Overestimation in Annual Dose Arising from the Linearity Assumption
  - 2.4.2.1.7.1 Intersection of Nominal Scenario Class with Other Scenario Classes
  - 2.4.2.1.7.2 Intersection of Early-Failure Scenario Class with Other Scenario Classes
  - 2.4.2.1.7.3 Intersection of Igneous Scenario Class with Other Scenario Classes
  - 2.4.2.1.7.4 Intersection of Seismic Scenario Class with Other Scenario Classes
- 2.4.2.1.8 Conclusion
- 2.4.2.2 Evaluation of Annual Dose to the RMEI with Respect to the Postclosure Individual Protection Standard
  - 2.4.2.2.1 Annual Dose to the Reasonably Maximally Exposed Individual
    - 2.4.2.2.1.1 Quantitative Results for Total Mean or Median Annual Dose
      - 2.4.2.2.1.1.1 Total Annual Dose, with Associated Uncertainty
      - 2.4.2.2.1.1.2 Contribution of Modeling Cases to Total Mean Annual Dose
      - 2.4.2.2.1.1.3 Radionuclides Important to Postclosure Performance
    - 2.4.2.2.1.2 Expected Annual Doses for the Individual Modeling Cases
      - 2.4.2.2.1.2.1 Nominal Modeling Case
      - 2.4.2.2.1.2.2 Seismic Scenario Class Modeling Cases
        - 2.4.2.2.1.2.2.1 Seismic Ground Motion Modeling Case
        - 2.4.2.2.1.2.2.2 Seismic Fault Displacement Modeling Case
      - 2.4.2.2.1.2.3 Igneous Scenario Class Modeling Cases
        - 2.4.2.2.1.2.3.1 Igneous Intrusion Modeling Case
        - 2.4.2.2.1.2.3.2 Volcanic Eruption Modeling Case
      - 2.4.2.2.1.2.4 Early Failure Scenario Class Modeling Cases
        - 2.4.2.2.1.2.4.1 Drip Shield Early Failure Modeling Case
        - 2.4.2.2.1.2.4.2 Waste Package Early Failure Modeling Case

**CONTENTS (Continued)**

- 2.4.2.2.2 Statistical Stability
  - 2.4.2.2.2.1 Statistical Stability Methodology
  - 2.4.2.2.2.2 Statistical Stability for the Epistemic Uncertainty
  - 2.4.2.2.2.3 Statistical Stability for the Aleatory Uncertainty and Numerical Accuracy of the Expected Dose Integration
- 2.4.2.2.3 Consistency and Reasonableness of Repository Performance and the Performance of Individual Components or Subsystems
  - 2.4.2.2.3.1 Single-Realization Deterministic Analysis for the Nominal Modeling Case
  - 2.4.2.2.3.2 Single-Realization Deterministic Analyses for the Seismic Ground Motion Modeling Case
    - 2.4.2.2.3.2.1 Seismic Ground Motion Modeling Case for 10,000-Year Period
    - 2.4.2.2.3.2.2 Seismic Ground Motion Modeling Case for 1,000,000-Year Period
- 2.4.2.3 Credibility of the TSPA Results
  - 2.4.2.3.1 Consistency of Assumptions and Parameter Values within the Total System Performance Assessment Code
    - 2.4.2.3.1.1 Submodel Differences Related to EBS Thermal-Hydrologic Environment
    - 2.4.2.3.1.2 Submodel Differences Related to Drift-Scale Seepage and In-Drift Condensation
    - 2.4.2.3.1.3 Submodel Differences Related to EBS Chemical Environment
    - 2.4.2.3.1.4 Submodel Differences Related to Waste Package and Drip Shield Degradation
    - 2.4.2.3.1.5 Submodel Differences Related to Waste Form Degradation and Mobilization
    - 2.4.2.3.1.6 Submodel Differences Related to EBS Transport
    - 2.4.2.3.1.7 Submodel Differences Related to Unsaturated Zone Transport
    - 2.4.2.3.1.8 Submodel Differences Related to Saturated Zone Flow and Transport
    - 2.4.2.3.1.9 Submodel Differences Related to Biosphere Transport and Exposure
    - 2.4.2.3.1.10 Submodel Differences Related to Early Waste Package and Drip Shield Failures
    - 2.4.2.3.1.11 Submodel Differences Related to Igneous Processes
    - 2.4.2.3.1.12 Submodel Differences Related to Seismic Processes
    - 2.4.2.3.1.13 Summary
  - 2.4.2.3.2 TSPA Model and Code Verification, Validation, and Confidence-Building

**CONTENTS (Continued)**

- 2.4.2.3.2.1 TSPA Model Integration and Transfer of Data Between Modules of the TSPA Code
  - 2.4.2.3.2.1.1 Unsaturated Zone Flow
  - 2.4.2.3.2.1.2 Engineered Barrier System Thermal-Hydrologic Environment
  - 2.4.2.3.2.1.3 Drift Seepage and Drift-Wall Condensation
  - 2.4.2.3.2.1.4 Engineered Barrier System Chemical Environment
  - 2.4.2.3.2.1.5 Waste Package and Drip Shield Degradation
  - 2.4.2.3.2.1.6 Engineered Barrier System Flow
  - 2.4.2.3.2.1.7 Waste Form Degradation and Mobilization
  - 2.4.2.3.2.1.8 Engineered Barrier System Transport
  - 2.4.2.3.2.1.9 Unsaturated Zone Transport
  - 2.4.2.3.2.1.10 Saturated Zone Flow and Transport
  - 2.4.2.3.2.1.11 Biosphere
  - 2.4.2.3.2.1.12 Events
    - 2.4.2.3.2.1.12.1 Early Failure Scenario Class
    - 2.4.2.3.2.1.12.2 Igneous Scenario Class
    - 2.4.2.3.2.1.12.3 Seismic Scenario Class
- 2.4.2.3.2.2 During-Development Model Validation Activities for the TSPA Code
  - 2.4.2.3.2.2.1 Computer Code and Input Verification
  - 2.4.2.3.2.2.2 Model Stability Testing
  - 2.4.2.3.2.2.3 Uncertainty Characterization Reviews
  - 2.4.2.3.2.2.4 Surrogate Waste-Form Analyses
- 2.4.2.3.2.3 Post-Development Model Validation Activities for the TSPA Code
  - 2.4.2.3.2.3.1 Corroboration of Abstraction Results with the Underlying Validated Process Models
  - 2.4.2.3.2.3.2 Auxiliary Analyses
    - 2.4.2.3.2.3.2.1 Single-Realization Deterministic Analyses
    - 2.4.2.3.2.3.2.2 Comparison with the Simplified TSPA Analysis
    - 2.4.2.3.2.3.2.3 Comparison with EPRI Model
    - 2.4.2.3.2.3.2.4 Performance Margin Analysis and the Evaluation of Conservatism
  - 2.4.2.3.2.3.3 Natural Analogues
    - 2.4.2.3.2.3.3.1 Process Model Analogues
    - 2.4.2.3.2.3.3.2 Investigations Providing Corroborative Evidence
  - 2.4.2.3.2.3.4 Iteration and Independent Technical Review

**CONTENTS (Continued)**

- 2.4.2.3.3 Consistency of Uncertainty in the Performance Assessment Results with Model and Parameter Uncertainty
  - 2.4.2.3.3.1 Treatment of Parameter and Model Uncertainty in the TSPA Model
  - 2.4.2.3.3.2 Limitations and Applicability of Uncertainty and Sensitivity Analyses
  - 2.4.2.3.3.3 Uncertainty and Sensitivity Analysis Procedures
  - 2.4.2.3.3.4 Uncertainty and Sensitivity Analyses for the Nominal Scenario Class
  - 2.4.2.3.3.5 Uncertainty and Sensitivity Analyses for the Early Failure Scenario Class
    - 2.4.2.3.3.5.1 Uncertainty and Sensitivity Analyses for the Drip Shield Early Failure Modeling Case
    - 2.4.2.3.3.5.2 Uncertainty and Sensitivity Analyses for the Waste Package Early Failure Modeling Case
  - 2.4.2.3.3.6 Uncertainty and Sensitivity Analyses for the Seismic Scenario Class
  - 2.4.2.3.3.7 Uncertainty and Sensitivity Analyses for the Total Dose from All Scenario Classes
- 2.4.2.3.4 Parameters Sampled across Their Ranges of Uncertainty in TSPA
- 2.4.3 Demonstration of Compliance with the Individual Protection Standard for Human Intrusion
  - 2.4.3.1 TSPA Representation of the Human Intrusion Event
    - 2.4.3.1.1 EBS Flow and Transport for Human Intrusion
    - 2.4.3.1.2 Unsaturated Zone Transport for Human Intrusion
    - 2.4.3.1.3 Saturated Zone Transport for Human Intrusion
    - 2.4.3.1.4 Calculation of Annual Dose for the Human Intrusion Scenario
  - 2.4.3.2 Evaluation of the Earliest Occurrence Time of a Human Intrusion Event
    - 2.4.3.2.1 General Corrosion of the Waste Package and Drip Shield
    - 2.4.3.2.2 Occurrence of Unlikely Events
    - 2.4.3.2.3 Potential for Waste Package Penetration by Drilling
      - 2.4.3.2.3.1 Initial Bit Selection and Drilling Principles
      - 2.4.3.2.3.2 Bit Operating Conditions and Change in Conditions
      - 2.4.3.2.3.3 Penetration of the Drip Shield and Waste Package
      - 2.4.3.2.3.4 Comparative Material Strength
      - 2.4.3.2.3.5 Summary of Waste Package Penetration by Drilling
    - 2.4.3.2.4 Earliest Time of Waste Package Penetration by Human Intrusion—Analysis Summary and Findings
  - 2.4.3.3 Evaluation of Human Intrusion Dose to RMEI

**CONTENTS (Continued)**

- 2.4.3.3.1 Annual Dose to the RMEI for the Human Intrusion Standard
- 2.4.3.3.2 Treatment of Likely Waste Package Degradation Processes
- 2.4.3.3.3 Statistical Stability of the Mean Annual Dose
- 2.4.3.3.4 Statistical Stability of the Expected Annual Dose
- 2.4.3.3.5 Reasonableness and Consistency of Human Intrusion Repository Performance
  - 2.4.3.3.5.1 Single-Realization Deterministic Analysis for the Human Intrusion Modeling Case
  - 2.4.3.3.5.2 Comparison of the Human Intrusion Modeling Case with the Waste Package Early Failure Modeling Case
- 2.4.3.4 Credibility of the Human Intrusion Results
  - 2.4.3.4.1 Consistency of Assumptions and Parameter Values for the Human Intrusion
  - 2.4.3.4.2 TSPA Code Verification, Validation, and Confidence-Building for the Human Intrusion
  - 2.4.3.4.3 Propagation and Consistency of Uncertainty in the Human Intrusion TSPA
  - 2.4.3.4.4 Parameters Sampled across Their Ranges of Uncertainty in the Human Intrusion TSPA
- 2.4.4 Analysis of Repository Performance that Demonstrates Compliance with the Separate Standards for the Protection of Groundwater
  - 2.4.4.1 Demonstration that the Groundwater Radioactivity and Doses at Any Year During the Compliance Period Do Not Exceed the Limits in the Groundwater Protection Standards
    - 2.4.4.1.1 Methods Used to Estimate the Level of Radioactivity in the Groundwater
      - 2.4.4.1.1.1 Performance Assessment
      - 2.4.4.1.1.2 Quantities Calculated for Evaluating Compliance with the Groundwater Protection Standards
      - 2.4.4.1.1.3 Natural Background Levels of Gross Alpha-Emitting Radionuclides and  $^{226}\text{Ra}$  and  $^{228}\text{Ra}$
      - 2.4.4.1.1.4 Results
    - 2.4.4.2 Evaluation of Total Dissolved Solids in the Aquifer
    - 2.4.4.3 Physical Dimensions of the Representative Volume of Groundwater
      - 2.4.4.3.1 Methods and Assumptions Used to Determine the Physical Dimensions of the Representative Volume of Groundwater
      - 2.4.4.3.2 Determination of Physical Dimensions of the Representative Volume
  - 2.4.5 General References
- 3. RESEARCH AND DEVELOPMENT PROGRAM TO RESOLVE SAFETY QUESTIONS
  - 3.1 Identification of Safety Questions

---

**CONTENTS (Continued)**

- 3.2 Requirements for Identified Research and Development Programs
- 4. PERFORMANCE CONFIRMATION PROGRAM
  - 4.1 Program Objectives and Overview
    - 4.1.1 Program Implementation
    - 4.1.2 Program Documentation
    - 4.1.3 Evaluation of Results and Reporting
  - 4.2 Performance Confirmation Program Activity Descriptions
    - 4.2.1 General Requirements
      - 4.2.1.1 Precipitation Monitoring
      - 4.2.1.2 Seepage Monitoring
      - 4.2.1.3 Subsurface Water and Rock Testing
      - 4.2.1.4 Unsaturated Zone Testing
      - 4.2.1.5 Saturated Zone Monitoring
      - 4.2.1.6 Saturated Zone Fault Hydrology Testing
      - 4.2.1.7 Saturated Zone Alluvium Testing
      - 4.2.1.8 Drift Inspection
      - 4.2.1.9 Thermally Accelerated Drift Near-Field Monitoring
      - 4.2.1.10 Dust Buildup Monitoring
      - 4.2.1.11 Thermally Accelerated Drift In-Drift Environment Monitoring
    - 4.2.2 Geotechnical and Design Monitoring and Testing
      - 4.2.2.1 Subsurface Mapping
      - 4.2.2.2 Seismicity Monitoring
      - 4.2.2.3 Construction Effects Monitoring
      - 4.2.2.4 Thermally Accelerated Drift Thermal-Mechanical Monitoring
    - 4.2.3 Design Testing Other than Waste Packages
      - 4.2.3.1 Seal and Backfill Testing
    - 4.2.4 Monitoring and Testing of Waste Packages
      - 4.2.4.1 Waste Package Monitoring
      - 4.2.4.2 Corrosion Testing
      - 4.2.4.3 Corrosion Testing of Thermally Accelerated Drift Samples
      - 4.2.4.4 Waste Form Testing
- 4.3 GENERAL REFERENCES
- 5. MANAGEMENT SYSTEMS
  - 5.1 Quality Assurance
    - 5.1.1 Organization
    - 5.1.2 Quality Assurance Program
  - 5.2 RECORDS, REPORTS, TESTS, AND INSPECTIONS
    - 5.2.1 Records
      - 5.2.1.1 Program Objectives



**CONTENTS (Continued)**

- 5.2.1.2 Record Creation
- 5.2.1.3 Record Maintenance and Use
- 5.2.1.4 Records Storage
- 5.2.1.5 Disposition of Records
- 5.2.2 Reports
- 5.2.3 Tests
- 5.2.4 U.S. Nuclear Regulatory Commission Inspections
- 5.2.5 General References
- 5.3 TRAINING AND CERTIFICATION OF PERSONNEL
  - 5.3.1 Organizational Structure of the Office of Civilian Radioactive Waste Management within the DOE
    - 5.3.1.1 Organizational Structure of the Office of Civilian Radioactive Waste Management within the DOE during Construction and Operations
    - 5.3.1.2 Management Functions and Responsibilities of the Office of Civilian Radioactive Waste Management within the DOE during Construction and Operations
      - 5.3.1.2.1 Director of the Office of Civilian Radioactive Waste Management
      - 5.3.1.2.2 Site Operations Manager
      - 5.3.1.2.3 Quality Assurance Manager
      - 5.3.1.2.4 Engineering and Construction Manager
      - 5.3.1.2.5 Licensing Manager
      - 5.3.1.2.6 Postclosure Performance and Confirmation Manager
      - 5.3.1.2.7 Site Protection Manager
      - 5.3.1.2.8 Radiation Protection Manager
      - 5.3.1.2.9 Operations Manager
    - 5.3.1.3 DOE Points of Contact
    - 5.3.1.4 Procedure for Delegation of Authority
    - 5.3.1.5 Responsibilities of the Onsite Safety Committee
  - 5.3.2 Key Positions Assigned Responsibility for Safety and Operations at the Site
    - 5.3.2.1 General Functional Titles and Required Qualifications for Key Positions
      - 5.3.2.1.1 Site Operations Manager
      - 5.3.2.1.2 Quality Assurance Manager
      - 5.3.2.1.3 Engineering and Construction Manager
      - 5.3.2.1.4 Licensing Manager
      - 5.3.2.1.5 Postclosure Performance and Confirmation Manager
      - 5.3.2.1.6 Site Protection Manager
      - 5.3.2.1.7 Radiation Protection Manager
      - 5.3.2.1.8 Operations Manager

---

**CONTENTS (Continued)**

- 5.3.3 Personnel Qualification and Training Requirements
    - 5.3.3.1 Organization and Management of the Training Function
    - 5.3.3.2 Analysis and Identification of Functional Areas Requiring Training
      - 5.3.3.2.1 General Employee Training
      - 5.3.3.2.2 Radiation and Criticality Training
      - 5.3.3.2.3 Technical Training
        - 5.3.3.2.3.1 Fundamentals Training
        - 5.3.3.2.3.2 Worker Classification-Specific Training
        - 5.3.3.2.3.3 On-the-Job Training and Qualifications
        - 5.3.3.2.3.4 Continuing Training
        - 5.3.3.2.3.5 Special Training
  - 5.3.4 Basis and Objectives for Training
  - 5.3.5 Organization of Instruction Using Lesson Plans and Other Training Guides
  - 5.3.6 Evaluation of Trainee Learning
  - 5.3.7 Conduct of On-the-Job Training
  - 5.3.8 Evaluation of Training Effectiveness
  - 5.3.9 Personnel Qualification and Certification
  - 5.3.10 Periodic Work Performance Evaluations
  - 5.3.11 Physical Condition and General Health of Operations Personnel
  - 5.3.12 Methods for Selecting, Training, and Qualifying Security Guards
  - 5.3.13 General References
- 5.4 EXPERT ELICITATION
- 5.4.1 Probabilistic Volcanic Hazard Analysis
  - 5.4.2 Probabilistic Seismic Hazard Analysis
  - 5.4.3 Saturated Zone Flow and Transport
  - 5.4.4 General References
- 5.5 PLANS FOR INITIAL STARTUP ACTIVITIES AND TESTING
- 5.5.1 Compatibility of Testing Programs with Applicable Regulatory Guidance
  - 5.5.2 Use of Experience from Similar Facilities
  - 5.5.3 Methods Used to Develop, Review, and Approve Test Procedures and Methods to Evaluate Results
  - 5.5.4 Format and Content of Test Procedures
  - 5.5.5 Component Testing
  - 5.5.6 Systems Functional Testing
  - 5.5.7 Cold Integrated Systems Testing
  - 5.5.8 Operational Readiness Review
  - 5.5.9 Protection of Workers and the Public
  - 5.5.10 Hot Testing (Initial Startup Operations)
  - 5.5.11 Schedules

**CONTENTS (Continued)**

- 5.5.12 Testing and Evaluating Functional Adequacy of New or Untested Systems, Structures, and Components
- 5.5.13 General References
- 5.6 PLANS AND PROCEDURES FOR CONDUCT OF NORMAL ACTIVITIES, INCLUDING OPERATIONS, MAINTENANCE, SURVEILLANCE, AND PERIODIC TESTING
  - 5.6.1 Plans and Procedure Development
  - 5.6.2 Use of Experience from Other Facilities
  - 5.6.3 Plans and Procedures for Normal Operations
  - 5.6.4 Plans and Procedures for Maintenance
    - 5.6.4.1 Physical Plant Maintenance Philosophy and Strategy
    - 5.6.4.2 Maintenance Program Implementation
      - 5.6.4.2.1 Maintenance Activities
      - 5.6.4.2.2 Maintenance Facilities, Tools, and Equipment
    - 5.6.4.3 Equipment Controls
      - 5.6.4.3.1 Equipment Tagging and Isolation
      - 5.6.4.3.2 Housekeeping and Material Condition
      - 5.6.4.3.3 Foreign Material Exclusion
      - 5.6.4.3.4 Postmaintenance Testing
    - 5.6.4.4 Configuration Management
    - 5.6.4.5 Equipment Performance Monitoring
    - 5.6.4.6 Maintenance Personnel Knowledge, Skills, and Training
      - 5.6.4.6.1 Training
      - 5.6.4.6.2 Job Assignments
    - 5.6.4.7 Work Management Process
    - 5.6.4.8 Maintenance Procedures
      - 5.6.4.8.1 Compliance with Written Instructions
      - 5.6.4.8.2 Use, Development, and Approval
      - 5.6.4.8.3 Selective Use of Content
    - 5.6.4.9 Calibration and Testing
    - 5.6.4.10 Special Process Controls
  - 5.6.5 Plans and Procedures for Periodic Surveillance Testing
  - 5.6.6 General References
- 5.7 EMERGENCY PLANNING
  - 5.7.1 Responsibilities for Developing, Maintaining, and Updating the Emergency Plan
    - 5.7.1.1 Planning Goals
    - 5.7.1.2 Available Information Related to Responsibilities for Developing, Maintaining, and Updating the Emergency Plan
  - 5.7.2 Repository Description

---

**CONTENTS (Continued)**

- 5.7.2.1 Planning Goals
- 5.7.2.2 Available Information Related to Repository Description
  - 5.7.2.2.1 Description of Facility and Site
  - 5.7.2.2.2 Site Location and Geography
  - 5.7.2.2.3 Description of Site Features Affecting Emergency Response
  - 5.7.2.2.4 Description of Area Near Site
  - 5.7.2.2.5 Geologic Repository Operations Area Activities
    - 5.7.2.2.5.1 Surface and Subsurface Facilities
- 5.7.3 Types and Classification of Potential Accidents
  - 5.7.3.1 Planning Goals
  - 5.7.3.2 Available Information Related to Types and Classification of Potential Accidents
    - 5.7.3.2.1 Emergency Action Levels
    - 5.7.3.2.2 Alert
    - 5.7.3.2.3 Site Area Emergency
- 5.7.4 Detection of Accidents
  - 5.7.4.1 Planning Goals
  - 5.7.4.2 Available Information Related to Detection of Accidents
- 5.7.5 Mitigation of Consequences
  - 5.7.5.1 Planning Goals
  - 5.7.5.2 Available Information Related to Mitigation of Consequences
    - 5.7.5.2.1 Early Phase
    - 5.7.5.2.2 Intermediate Phase
    - 5.7.5.2.3 Late Phase
    - 5.7.5.2.4 Emergency Response Facilities
      - 5.7.5.2.4.1 Technical Support Center
      - 5.7.5.2.4.2 Operational Support Center
      - 5.7.5.2.4.3 Emergency Operations Facility
      - 5.7.5.2.4.4 Joint Information Center
      - 5.7.5.2.4.5 Communications
      - 5.7.5.2.4.6 Emergency Communications
- 5.7.6 Assessment of Releases
  - 5.7.6.1 Planning Goals
  - 5.7.6.2 Available Information Related to Assessment of Releases
- 5.7.7 Roles and Responsibilities for Repository Personnel during an Emergency
  - 5.7.7.1 Planning Goals
  - 5.7.7.2 Available Information Related to Roles and Responsibilities for Repository Personnel during an Emergency
    - 5.7.7.2.1 Normal Organization

**CONTENTS (Continued)**

- 5.7.7.2.1.1 Director of the Office of Civilian Radioactive Waste Management
- 5.7.7.2.1.2 Site Operations Manager
- 5.7.7.2.1.3 Delegation of Authority
- 5.7.7.2.2 Emergency Response Concept of Operations
  - 5.7.7.2.2.1 Direction and Coordination
  - 5.7.7.2.2.2 Facility Operating Area(s)
    - 5.7.7.2.2.3 Technical Support Center
      - 5.7.7.2.2.3.1 Technical Support Center Director
      - 5.7.7.2.2.3.2 Operations Manager
      - 5.7.7.2.2.3.3 Radiological Response Manager
      - 5.7.7.2.2.3.4 Engineering Manager
      - 5.7.7.2.2.3.5 Technical Support Center Manager
      - 5.7.7.2.2.3.6 Security Manager
    - 5.7.7.2.2.4 Operational Support Center
    - 5.7.7.2.2.5 Emergency Operations Facility
      - 5.7.7.2.2.5.1 OCRWM Emergency Director
      - 5.7.7.2.2.5.2 Emergency Operations Facility Coordinator
      - 5.7.7.2.2.5.3 Technical Support Manager
      - 5.7.7.2.2.5.4 Administrative Support Manager
      - 5.7.7.2.2.5.5 Public Information Manager
    - 5.7.7.2.2.6 Joint Information Center
      - 5.7.7.2.2.6.1 Joint Information Center Supervisor
      - 5.7.7.2.2.6.2 DOE Spokesperson
      - 5.7.7.2.2.6.3 Joint Information Center Coordinator
      - 5.7.7.2.2.6.4 Administrative Support Specialist
      - 5.7.7.2.2.6.5 Public Information Coordinator
    - 5.7.7.2.2.7 Emergency Response Records
- 5.7.8 Notification and Coordination of Offsite Groups
  - 5.7.8.1 Planning Goals
  - 5.7.8.2 Available Information Related to Notification and Coordination of Offsite Groups
- 5.7.9 Information to be Communicated
  - 5.7.9.1 Planning Goals
  - 5.7.9.2 Available Information Related to Information to be Communicated
- 5.7.10 Training
  - 5.7.10.1 Planning Goals
  - 5.7.10.2 Available Information Related to Training
    - 5.7.10.2.1 Emergency Preparedness Training Program

---

**CONTENTS (Continued)**

- 5.7.10.2.1.1 Emergency Preparedness Manager
- 5.7.10.2.1.2 Schedule
- 5.7.10.2.1.3 Delivery
- 5.7.10.2.1.4 Initial Training Requirements
- 5.7.10.2.1.5 Exams
- 5.7.10.2.1.6 Emergency Response Organization Position Qualification
- 5.7.10.2.1.7 Exceptions from Training/Credit for Previous Experience
- 5.7.10.2.1.8 Requalification Requirements
- 5.7.10.2.2 Training Records
- 5.7.11 Restoration of Repository Operations to a Safe Condition
  - 5.7.11.1 Planning Goals
  - 5.7.11.2 Available Information Related to Restoration of Repository Operations to a Safe Condition
    - 5.7.11.2.1 Reentry
      - 5.7.11.2.1.1 Reentry Planning
      - 5.7.11.2.1.2 Reentry for “Rescue and Recovery”
    - 5.7.11.2.2 Termination of an Emergency
    - 5.7.11.2.3 Recovery
      - 5.7.11.2.3.1 Recovery Organization
      - 5.7.11.2.3.2 Recovery Operations
        - 5.7.11.2.3.2.1 Accident Assessment and Investigation
        - 5.7.11.2.3.2.2 Planning and Scheduling
        - 5.7.11.2.3.2.3 Repair and Restoration
      - 5.7.11.2.3.3 Recovery Procedures
      - 5.7.11.2.3.4 Normal Operations
- 5.7.12 Exercises, Communication Checks, and Drills
  - 5.7.12.1 Planning Goals
  - 5.7.12.2 Available Information Related to Exercises, Communication Checks, and Drills
    - 5.7.12.2.1 Drill and Exercise Program
    - 5.7.12.2.2 Drills
    - 5.7.12.2.3 Tabletop Drills
    - 5.7.12.2.4 Walk-Through Drills
    - 5.7.12.2.5 Communications Drills
    - 5.7.12.2.6 Exercises
    - 5.7.12.2.7 Exercise Conduct
    - 5.7.12.2.8 Communications

**CONTENTS (Continued)**

- 5.7.12.2.9 Exercise Termination
- 5.7.12.2.10 Evaluation and Corrective Action
  - 5.7.12.2.10.1 Evaluations
  - 5.7.12.2.10.2 Exercise Critiques
  - 5.7.12.2.10.3 Exercise Report
  - 5.7.12.2.10.4 Corrective Actions
- 5.7.13 Hazardous Materials
  - 5.7.13.1 Planning Goals
  - 5.7.13.2 Available Information Related to Hazardous Materials
- 5.7.14 Comments on the Emergency Plan
  - 5.7.14.1 Planning Goals
  - 5.7.14.2 Available Information Related to Comments on the Emergency Plan
- 5.7.15 Offsite Assistance
  - 5.7.15.1 Planning Goals
  - 5.7.15.2 Available Information Related to Offsite Assistance
- 5.7.16 Public Information
  - 5.7.16.1 Planning Goals
  - 5.7.16.2 Available Information Related to Public Information
    - 5.7.16.2.1 Repository Emergency Public Information Program
    - 5.7.16.2.2 Joint Information Center
    - 5.7.16.2.3 Public Education
      - 5.7.16.2.3.1 News Media
- 5.7.17 General References
- 5.8 CONTROLS TO RESTRICT ACCESS AND REGULATE LAND USES
  - 5.8.1 Ownership of Land
    - 5.8.1.1 Current U.S. Department of Energy Land-Use Interests
    - 5.8.1.2 Legal Documentation of Ownership and Control
  - 5.8.2 Controls for Permanent Closure
    - 5.8.2.1 Legal Interests and Documentation
    - 5.8.2.2 Encumbrances on Land Surrounding Yucca Mountain
      - 5.8.2.2.1 Patented Mining Claim
      - 5.8.2.2.2 Unpatented Mining Claims
      - 5.8.2.2.3 Other Encumbrances
    - 5.8.2.3 Administering and Controlling Ownership Rights
  - 5.8.3 Additional Controls through Permanent Closure
    - 5.8.3.1 10 CFR 63.111(a) and (b) Requirements
    - 5.8.3.2 Legal Documentation
  - 5.8.4 Water Rights
  - 5.8.5 Conceptual Design of Monuments and Markers

---

**CONTENTS (Continued)**

- 5.8.5.1 Design Considerations
- 5.8.5.2 Monuments and Markers
- 5.8.6 Records Storage
- 5.8.7 General References
- 5.9 USES OF THE GEOLOGIC REPOSITORY OPERATIONS AREA FOR PURPOSES OTHER THAN DISPOSAL OF RADIOACTIVE WASTES
  - 5.9.1 Potential Activities Other Than Disposal
    - 5.9.1.1 Native American Cultural Activities
    - 5.9.1.2 Independent Performance Monitoring
    - 5.9.1.3 Protection of Flora and Fauna
    - 5.9.1.4 Activities in the Proximity of the Geologic Repository Operations Area
    - 5.9.1.5 Resource Exploitation
  - 5.9.2 Procedures for Potential Activities that Potentially Affect Structures, Systems, and Components
  - 5.9.3 General References
- 5.10 LICENSE SPECIFICATIONS
  - 5.10.1 Structure of Proposed License Specifications
  - 5.10.2 Probable Subjects of License Specifications
    - 5.10.2.1 Criteria for Selection of Probable Subjects
    - 5.10.2.2 Limiting Conditions for Operation
    - 5.10.2.3 Design Features
    - 5.10.2.4 Administrative Controls
      - 5.10.2.4.1 License Specification Bases
      - 5.10.2.4.2 Technical Requirements Manual
  - 5.10.3 Plans for Implementing License Specifications
    - 5.10.3.1 Procedures
    - 5.10.3.2 Testing
    - 5.10.3.3 Configuration Management System
  - 5.10.4 Draft License Specification Development
  - 5.10.5 General References
- 5.11 Operational Radiation Protection Program
  - 5.11.1 Organization
  - 5.11.2 Equipment, Instrumentation, and Facilities
    - 5.11.2.1 Radiation Protection Equipment
    - 5.11.2.2 Radiation Protection Instrumentation
    - 5.11.2.3 Radiation Protection Facilities
  - 5.11.3 Policies and Procedures
    - 5.11.3.1 Radiation Surveys



**CONTENTS (Continued)**

- 5.11.3.1.1 Radioactive Material Shipment Surveys
- 5.11.3.1.2 Radiological Postings
- 5.11.3.2 Access and Dose Control
  - 5.11.3.2.1 Radiological Access Control
  - 5.11.3.2.2 Onsite Dose Control
  - 5.11.3.2.3 Radioactive Material and Contamination Control
  - 5.11.3.2.4 Low-Level Radioactive Waste Management
- 5.11.3.3 External Dose Monitoring
- 5.11.3.4 Internal Dose Monitoring
- 5.11.3.5 Air Sampling and Analysis
- 5.11.3.6 Respiratory Protection
- 5.11.3.7 Radiation Protection Training
- 5.11.3.8 Notices to Workers
- 5.11.3.9 Pregnant Worker, Embryo, and Fetus Protection
- 5.11.3.10 Radiation Protection Records and Reports
  - 5.11.3.10.1 Records
  - 5.11.3.10.2 Reports
- 5.11.3.11 Environmental Radiological Monitoring
  - 5.11.3.11.1 Environmental Radiological Monitoring Program
  - 5.11.3.11.2 Effluent Monitoring
  - 5.11.3.11.3 Offsite Dose Calculation
  - 5.11.3.11.4 Meteorological Monitoring
- 5.11.4 General References

## **CONTENTS (Continued)**