



EPRI

ELECTRIC POWER
RESEARCH INSTITUTE

Inspection & Mitigation of Alloy 82/182 butt welds with Overlays

Industry Briefing to NRC on PWSCC Mitigation Research-Rockville

July 16, 2008

Jack Spanner
Program Manager

EPRI Nuclear Sector

Inspection & Mitigation of Alloy 82/182 butt welds

Project Description

- **Fabricate samples to support the following tasks:**
 - Obtain mitigation data to support the application of OWOL (Optimized design) on large diameter components
 - Develop procedures and techniques to examine cast SS base material under weld overlays
 - Develop procedures and techniques to examine beyond the outer 25% of the original base material in order to reduce the size of the overlay for large diameter thick components
 - Develop code criteria in order to qualify the techniques developed
 - Expand currently qualified procedure thickness ranges

Inspection & Mitigation of Alloy 82/182 butt welds

Tasks & Deliverables

– MRP Funded Portion

- Smaller Diameter Configurations
 - All have cast safe-ends
 - Surge Line Mock-ups have flaws at 50% and 75% of the original weld and base material thickness
 - Flaws located in cast base material and in weld
 - Delivered in January of 07
 - Samples being scanned by vendor
 - Results under review



Inspection & Mitigation of Alloy 82/182 butt welds

• Tasks & Deliverables

- MEOG/NDEC/MRP Projects
- Design and fabricate large diameter thick test samples (RCS)
 - *February 2008 (Complete)*
 - *Document Mitigation Design Data 2008*
- Characterize samples and evaluate techniques
 - *December 2008 (Data Collection Complete and Analysis Underway on Expedited Schedule to support Pilot Plant)*
- *If above task is successful, qualify techniques*
 - *December 2008*
(First Application for Preemptive Overlay Targeted for September 08, if techniques are successful 3 months early)
- *Complete Relief Request Template*
 - *November 2008 (Working with Pilot Plant on Expedited Schedule)*

Summary of Overlay UT Results

Thin Non-Cast

Detect Circ & Ax

Beyond Outer 25%

Refining sizing techniques

Heavy Non-Cast

Detect & Size Circ & Ax in outer 25%

Detect Circs beyond outer 25%

Thin Cast

Limited Detection of Circ & Ax flaws (Some flaws missed)

No sizing

Heavy Cast

No detections

No sizing

Inspection & Mitigation of Alloy 82/182 butt welds

- Inlays and Onlays

- Coordinated with PWROG to show that current PDI qualified techniques are effective for ISI of butt welds after application of Inlay
 - Fabricated Large Main Loop Inlay mock-up
 - Demonstrated equivalency of currently qualified inside surface procedures
 - Documented results
- Working with utility on the application of onlay mock-ups for Core Flood nozzle configurations