

Safety and Relief Valves Test
Preoperational Test Witnessing
Procedure No.: 70435B
Issue Date: 1/1/79

SECTION I
INSPECTION OBJECTIVES

1. Verify that the testing is conducted in accordance with approved procedures,
2. Independently verify the acceptability of test results, and
3. Evaluate the performance of licensee personnel conducting the test.

SECTION II
INSPECTION REQUIREMENTS

The inspector shall:

1. Schedule an inspection to coincide with this testing.
2. Obtain and review the Safety and Relief Valve Test Procedure prior to witnessing the test.
3. Review Regulatory Guide 1.68 and applicable portions of the FSAR, SER, Technical Specifications, and docket correspondence. Verify that Safety and Relief Valves are adequately tested to ensure that NRC requirements and licensee commitments are satisfied.
4. Observe licensee personnel conducting the test. Verify that:
 - a. tests are conducted in accordance with approved procedures,
 - b. approved test procedures are available to personnel conducting the test,
 - c. test equipment is properly installed,
 - d. test data is collected and recorded in the approved manner, and
 - e. evaluate the licensee personnel's ability to conduct the test.

SECTION III
INSPECTION GUIDANCE

1. By witnessing this test, the inspector should ensure that important system performance functions are adequately tested. Areas which should be witnessed include (but are not limited to):
 - a. proper actuation and operation of power operated relief valves,
 - b. measurement of lifting pressure required for steam safety valves,
 - c. proper operation of vacuum breaker valves,
 - d. proper operation and calibration of leak detection temperature sensors, and
 - e. demonstrated redundancy and electrical independence.

NOTE: Items may be part of other systems tests.