

**FINAL DATA REPORT Rev. 2
GEOTECHNICAL EXPLORATION AND TESTING**

**TURKEY POINT COL PROJECT
FLORIDA CITY, FLORIDA**

October 6, 2008

VOLUME 4

Prepared By:

**MACTEC Engineering and Consulting, Inc.
Raleigh, North Carolina**

MACTEC Project No. 6468-07-1950

Prepared For:

**Bechtel Power Corporation
Subcontract No. 25409-102-HC4-CY00-00001**

Contents

**Appendix F – RCTS Data Reports
Appendix G – Groundwater**

**FINAL DATA REPORT Rev. 2
GEOTECHNICAL EXPLORATION AND TESTING**

**TURKEY POINT COL PROJECT
FLORIDA CITY, FLORIDA**

October 6, 2008

**VOLUME 4
Appendix F – RCTS Data Reports**

Prepared By:

**MACTEC Engineering and Consulting, Inc.
Raleigh, North Carolina**

MACTEC Project No. 6468-07-1950

Prepared For:

**Bechtel Power Corporation
Subcontract No. 25352-102-HC4-CY00-00001**

APPENDIX F CONTENTS

Fugro Appendix A – B630-UD8
Fugro Appendix B – B630-UD2
Fugro Appendix C – B630-UD13
Fugro Appendix D – B630-UD16
Fugro Appendix E – B630-UD19
Fugro Appendix F – B630-UD23
Fugro Appendix G – B630-UD27



6100 Hillcroft (77081)
P.O. Box 740010
Houston, Texas 77274
Tel: 713-369-5400
Fax: 713-369-5518

June 24, 2008

Ms. Siesta Williams
MACTEC
3301 Atlantic Avenue
Raleigh, NC 27604

RE: Two (2) Reports For The Turkey Point Project

Dear Ms. Williams:

Fugro has completed two (2) RCTS tests, which are B630-UD8 and B630-UD2 for the Turkey Point project. Fugro has incorporated, as needed, Dr. Kenneth Stokoe's comments into the final reports. The final reports and the associated RCTS Test Approvals by Dr. Kenneth Stokoe have been attached.

Please let us know if you have questions. Thanks.

Very truly yours,

Fugro Consultants, Inc.

A handwritten signature in black ink, appearing to read "Jiewu Meng".

Jiewu Meng, PhD, P.E.
Project Engineer

A handwritten signature in black ink, appearing to read "Bill DeGroff".

Bill DeGroff, P.E.
Laboratory Department Manager

Enclosures



RCTS TEST APPROVAL

PROJECT SITE/NAME	Turkey Point
--------------------------	--------------

Test ID	Sample ID	Depth B.S. (Ft)	Approved By (Initials)	Date
RCTS#A	B630-UD8	163.1	KHS ⊕	18 June '08
RCTS#B	B630-UD2	131.9	KHS ⊕	18 June '08

Two RCTS tests for the site referenced above were tested, and two reports were prepared, by Fugro Consultants, Inc.

I have reviewed the data and associated results listed above and found them to be reasonable.

Approved By:



Dr. Kenneth Stokoe

⊕ Consider minor comments on a few figures.

APPENDIX A

Specimen B630-UD8

Borehole B630

Sample UD8

Depth = 163.1 ft (49.7 m)

Total Unit Weight = 118.7 lb/ft³

Water Content = 33.0 %

Estimated In-Situ K_o = 0.5

Estimated In-Situ Mean Effective

Stress = 47 psi

FUGRO JOB #: 0401-1701
Testing Station: RC9






Figure A.1 Variation in Low-Amplitude Shear Modulus with Magnitude and Duration of Isotropic Confining Pressure from Resonant Column Tests




Figure A.2 Variation in Low-Amplitude Material Damping Ratio with Magnitude and Duration of Isotropic Confining Pressure from Resonant Column Tests




Figure A.3 Variation in Estimated Void Ratio with Magnitude and Duration of Isotropic Confining Pressure from Resonant Column Tests




Figure A.4 Variation in Low-Amplitude Shear Wave Velocity with Isotropic Confining Pressure from Resonant Column Tests




Figure A.5 Variation in Low-Amplitude Shear Modulus with Isotropic Confining Pressure from Resonant Column Tests




Figure A.6 Variation in Low-Amplitude Material Damping Ratio with Isotropic Confining Pressure from Resonant Column Tests




Figure A.7 Variation in Estimated Void Ratio with Isotropic Confining Pressure from Resonant Column Tests




Figure A.8 Comparison of the Variation in Shear Modulus with Shearing Strain and Isotropic Confining Pressure from the Resonant Column Tests




Figure A.9 Comparison of the Variation in Normalized Shear Modulus with Shearing Strain and Isotropic Confining Pressure from the Resonant Column Tests




Figure A.10 Comparison of the Variation in Material Damping Ratio with Shearing Strain and Isotropic Confining Pressure from the Resonant Column Tests




Figure A.11 Comparison of the Variation in Shear Modulus with Shearing Strain at an Isotropic Confining Pressure of 47 psi from the Combined RCTS Tests




Figure A.12 Comparison of the Variation in Normalized Shear Modulus with Shearing Strain at an Isotropic Confining Pressure of 47 psi from the Combined RCTS Tests




Figure A.13 Comparison of the Variation in Material Damping Ratio with Shearing Strain at an Isotropic Confining Pressure of 47 psi from the Combined RCTS Tests




Figure A.14 Comparison of the Variation in Shear Modulus with Loading Frequency at an Isotropic Confining Pressure of 47 psi from the Combined RCTS Tests




Figure A.15 Comparison of the Variation in Material Damping Ratio with Loading Frequency at an Isotropic Confining Pressure of 47 psi from the Combined RCTS Tests




Figure A.16 Comparison of the Variation in Shear Modulus with Shearing Strain at an Isotropic Confining Pressure of 187 psi from the Combined RCTS Tests




Figure A.17 Comparison of the Variation in Normalized Shear Modulus with Shearing Strain at an Isotropic Confining Pressure of 187 psi from the Combined RCTS Tests




Figure A.18 Comparison of the Variation in Material Damping Ratio with Shearing Strain at an Isotropic Confining Pressure of 187 psi from the Combined RCTS Tests




Figure A.19 Comparison of the Variation in Shear Modulus with Loading Frequency at an Isotropic Confining Pressure of 187 psi from the Combined RCTS Tests




Figure A.20 Comparison of the Variation in Material Damping Ratio with Loading Frequency at an Isotropic Confining Pressure of 187 psi from the Combined RCTS Tests

Table A.1 Variation in Low-Amplitude Shear Wave Velocity, Low-Amplitude Shear Modulus, Low-Amplitude Material Damping Ratio and Estimated Void Ratio with Isotropic Confining Pressure from RC Tests of Specimen B630-UD8

Isotropic Confining Pressure, σ_o			Low-Amplitude Shear Modulus, G_{max}		Low-Amplitude Shear Wave Velocity, V_s	Low-Amplitude Material Damping Ratio, D_{min}	Estimated Void Ratio, e
(psi)	(psf)	(kPa)	(ksf)	(MPa)	(fps)	(%)	
12	1728	83	1609	77	659	0.76	0.85
23	3312	158	2230	107	775	0.70	0.84
47	6768	324	3183	153	924	0.42	0.83
97	13968	668	4530	217	1097	0.40	0.81
187	26928	1288	5967	286	1249	0.39	0.79

Table A.2 Variation in Shear Modulus and Material Damping Ratio with Shearing Strain from RC Tests of Specimen B630-UD8; Isotropic Confining Pressure, $\sigma_o=47$ psi (6.8 ksf = 324 kPa)

Peak Shearing Strain, %	Shear Modulus, G, ksf	Normalized Shear Modulus, G/G_{max}	Average ⁺ Shearing Strain, %	Material Damping Ratio [*] , D, %
4.04E-04	3196	1.00	4.04E-04	0.41
8.14E-04	3196	1.00	8.14E-04	0.41
1.55E-03	3196	1.00	1.46E-03	0.45
2.71E-03	3170	0.99	2.55E-03	0.55
4.86E-03	3090	0.97	4.52E-03	0.68
8.70E-03	3011	0.94	7.91E-03	0.95
1.51E-02	2903	0.91	1.36E-02	1.26
2.53E-02	2762	0.86	2.18E-02	1.75
4.22E-02	2556	0.80	3.50E-02	2.65
7.15E-02	2254	0.71	5.58E-02	3.96
1.31E-01	1886	0.59	9.54E-02	5.48

⁺ Average Shearing Strain from the First Three Cycles of the Free Vibration Decay Curve

^{*} Average Damping Ratio from the First Three Cycles of the Free Vibration Decay Curve

Table A.3 Variation in Shear Modulus, Normalized Shear Modulus and Material Damping Ratio with Shearing Strain from TS Tests of Specimen B630-UD8; Isotropic Confining Pressure, $\sigma_o = 47$ psi (6.8 ksf = 324 kPa)

First Cycle				Tenth Cycle			
Peak Shearing Strain, %	Shear Modulus, G, ksf	Normalized Shear Modulus, G/G_{max}	Material Damping Ratio, D, %	Peak Shearing Strain, %	Shear Modulus, G, ksf	Normalized Shear Modulus, G/G_{max}	Material Damping Ratio, D, %
1.03E-03	3020	1.00	0.68	1.04E-03	3016	1.00	0.70
2.09E-03	3005	0.99	0.61	2.09E-03	3010	1.00	0.63
4.25E-03	2956	0.98	1.00	4.25E-03	2954	0.98	0.86
8.86E-03	2834	0.94	1.60	8.87E-03	2832	0.94	1.49

Table A.4 Variation in Shear Modulus and Material Damping Ratio with Shearing Strain from RC Tests of Specimen B630-UD8; Isotropic Confining Pressure, $\sigma_3 = 187$ psi (26.9 ksf = 1288 kPa)

Peak Shearing Strain, %	Shear Modulus, G, ksf	Normalized Shear Modulus, G/G_{max}	Average ⁺ Shearing Strain, %	Material Damping Ratio [*] , D, %
3.09E-04	6071	1.00	3.09E-04	0.38
6.26E-04	6071	1.00	6.26E-04	0.41
1.21E-03	6071	1.00	1.14E-03	0.43
2.28E-03	6009	0.99	2.19E-03	0.46
4.16E-03	5935	0.98	3.95E-03	0.54
7.40E-03	5825	0.96	6.88E-03	0.73
1.28E-02	5666	0.93	1.19E-02	0.99
2.17E-02	5453	0.90	1.97E-02	1.30
3.69E-02	5120	0.84	3.25E-02	1.76
6.19E-02	4703	0.77	5.14E-02	2.68
1.03E-01	4115	0.68	8.04E-02	3.92
1.86E-01	3365	0.55	1.34E-01	5.34
2.64E-01	3175	0.52	1.80E-01	6.37

⁺ Average Shearing Strain from the First Three Cycles of the Free Vibration Decay Curve

^{*} Average Damping Ratio from the First Three Cycles of the Free Vibration Decay Curve

Table A.5 Variation in Shear Modulus, Normalized Shear Modulus and Material Damping Ratio with Shearing Strain from TS Tests of Specimen B630-UD8; Isotropic Confining Pressure, $\sigma_o=187$ psi (26.9 ksf = 1288 kPa)

First Cycle				Tenth Cycle			
Peak Shearing Strain, %	Shear Modulus, G, ksf	Normalized Shear Modulus, G/G_{max}	Material Damping Ratio, D, %	Peak Shearing Strain, %	Shear Modulus, G, ksf	Normalized Shear Modulus, G/G_{max}	Material Damping Ratio, D, %
1.03E-03	5671	0.98	0.60	1.01E-03	5744	1.00	0.69
2.02E-03	5768	1.00	0.97	2.05E-03	5698	0.99	0.78
4.13E-03	5650	0.98	1.06	4.10E-03	5684	0.99	0.89
8.40E-03	5551	0.96	1.14	8.38E-03	5565	0.97	0.97

APPENDIX B

Specimen B630-UD2

Borehole B630

Sample UD2

Depth = 131.9 ft (40.2 m)

Total Unit Weight = 120.1 lb/ft³

Water Content = 33.8 %

Estimated In-Situ K_o = 0.5

Estimated In-Situ Mean Effective

Stress = 38 psi

FUGRO JOB #: 0411-08-1701

Testing Station: RC5






Figure B.1 Variation in Low-Amplitude Shear Modulus with Magnitude and Duration of Isotropic Confining Pressure from Resonant Column Tests




Figure B.2 Variation in Low-Amplitude Material Damping Ratio with Magnitude and Duration of Isotropic Confining Pressure from Resonant Column Tests




Figure B.3 Variation in Estimated Void Ratio with Magnitude and Duration of Isotropic Confining Pressure from Resonant Column Tests




Figure B.4 Variation in Low-Amplitude Shear Wave Velocity with Isotropic Confining Pressure from Resonant Column Tests




Figure B.5 Variation in Low-Amplitude Shear Modulus with Isotropic Confining Pressure from Resonant Column Tests




Figure B.6 Variation in Low-Amplitude Material Damping Ratio with Isotropic Confining Pressure from Resonant Column Tests




Figure B.7 Variation in Estimated Void Ratio with Isotropic Confining Pressure from Resonant Column Tests




Figure B.8 Comparison of the Variation in Shear Modulus with Shearing Strain and Isotropic Confining Pressure from the Resonant Column Tests




Figure B.9 Comparison of the Variation in Normalized Shear Modulus with Shearing Strain and Isotropic Confining Pressure from the Resonant Column Tests




Figure B.10 Comparison of the Variation in Material Damping Ratio with Shearing Strain and Isotropic Confining Pressure from the Resonant Column Tests




Figure B.11 Comparison of the Variation in Shear Modulus with Shearing Strain at an Isotropic Confining Pressure of 38 psi from the Combined RCTS Tests




Figure B.12 Comparison of the Variation in Normalized Shear Modulus with Shearing Strain at an Isotropic Confining Pressure of 38 psi from the Combined RCTS Tests




Figure B.13 Comparison of the Variation in Material Damping Ratio with Shearing Strain at an Isotropic Confining Pressure of 38 psi from the Combined RCTS Tests




Figure B.14 Comparison of the Variation in Shear Modulus with Loading Frequency at an Isotropic Confining Pressure of 38 psi from the Combined RCTS Tests




Figure B.15 Comparison of the Variation in Material Damping Ratio with Loading Frequency at an Isotropic Confining Pressure of 38 psi from the Combined RCTS Tests

Table B.1 Variation in Low-Amplitude Shear Wave Velocity, Low-Amplitude Shear Modulus, Low-Amplitude Material Damping Ratio and Estimated Void Ratio with Isotropic Confining Pressure from RC Tests of Specimen B630-UD2

Isotropic Confining Pressure, σ_o			Low-Amplitude Shear Modulus, G_{max}		Low-Amplitude Shear Wave Velocity, V_s	Low-Amplitude Material Damping Ratio, D_{min}	Estimated Void Ratio, e
(psi)	(psf)	(kPa)	(ksf)	(MPa)	(fps)	(%)	
9	1296	62	1354	65	605	0.68	0.86
19	2736	131	1918	92	719	0.44	0.86
38	5472	262	2688	129	850	0.28	0.85

Table B.2 Variation in Shear Modulus and Material Damping Ratio with Shearing Strain from RC Tests of Specimen B630-UD2; Isotropic Confining Pressure, $\sigma_o = 38$ psi (5.5 ksf = 262 kPa)

Peak Shearing Strain, %	Shear Modulus, G, ksf	Normalized Shear Modulus, G/G_{max}	Average ⁺ Shearing Strain, %	Material Damping Ratio ^x , D, %
2.01E-04	2719	1.00	2.01E-04	0.27
4.01E-04	2719	1.00	4.01E-04	0.27
8.20E-04	2704	0.99	7.87E-04	0.32
1.55E-03	2689	0.99	1.47E-03	0.34
2.82E-03	2659	0.98	2.65E-03	0.40
5.00E-03	2600	0.96	4.55E-03	0.54
8.52E-03	2538	0.93	7.67E-03	0.74
1.41E-02	2445	0.90	1.21E-02	1.13
2.32E-02	2283	0.84	1.93E-02	1.70
3.74E-02	2099	0.77	2.92E-02	2.53
6.20E-02	1853	0.68	4.53E-02	4.04

⁺ Average Shearing Strain from the First Three Cycles of the Free Vibration Decay Curve

^x Average Damping Ratio from the First Three Cycles of the Free Vibration Decay Curve

Table B.3 Variation in Shear Modulus, Normalized Shear Modulus and Material Damping Ratio with Shearing Strain from TS Tests of Specimen B630-UD2; Isotropic Confining Pressure, $\sigma_o = 38$ psi (5.5 ksf = 262 kPa)

First Cycle				Tenth Cycle			
Peak Shearing Strain, %	Shear Modulus, G, ksf	Normalized Shear Modulus, G/G_{max}	Material Damping Ratio, D, %	Peak Shearing Strain, %	Shear Modulus, G, ksf	Normalized Shear Modulus, G/G_{max}	Material Damping Ratio, D, %
1.02E-03	2638	1.00	0.14	1.02E-03	2640	1.00	0.37
2.04E-03	2635	1.00	0.38	2.03E-03	2648	1.00	0.44
4.15E-03	2584	0.98	0.78	4.17E-03	2576	0.97	0.53
1.01E-02	2482	0.94	1.04	1.01E-02	2484	0.94	1.15



6100 Hillcroft (77081)
P.O. Box 740010
Houston, Texas 77274
Tel: 713-369-5400
Fax: 713-369-5518

July 10, 2008

Ms. Siesta Williams
MACTEC
3301 Atlantic Avenue
Raleigh, NC 27604

RE: Two (2) Reports For The Turkey Point Project

Dear Ms. Williams:

Fugro has completed two (2) RCTS tests, which are B630-UD13 and B630-UD16 for the Turkey Point project. Fugro has incorporated, as needed, Dr. Kenneth Stokoe's comments into the final reports. The final reports and the associated RCTS Test Approvals by Dr. Kenneth Stokoe have been attached.

Please let us know if you have questions. Thanks.

Very truly yours,

Fugro Consultants, Inc.

A handwritten signature in black ink, appearing to read "Meng".

Jiewu Meng, PhD, P.E.
Project Engineer

A handwritten signature in black ink, appearing to read "Bill DeGroff".

Bill DeGroff, P.E.
Laboratory Department Manager

Enclosures



RCTS TEST APPROVAL

PROJECT SITE/NAME	Turkey Point
--------------------------	--------------

Test ID	Sample ID	Depth B.S. (Ft)	Approved By (Initials)	Date
RCTS#C	B630-UD13	190	KHS ⊕	3 July 08
RCTS#D	B630-UD16	211	KHS ⊕	3 July 08

Two RCTS tests for the site referenced above were tested, and two reports were prepared, by Fugro Consultants, Inc.

I have reviewed the data and associated results listed above and found them to be reasonable.

Approved By:

K. H. Stokoe

Dr. Kenneth Stokoe

⊕ Carefully consider some of the suggested changes and/or deletions and some comments that could be added to a few figures.

⊖ See minor comments on a few figures

APPENDIX C

Specimen B630-UD13

Borehole 630

Sample UD13

Depth = 189.7 ft (57.8 m)

Total Unit Weight = 117.1 lb/ft³

Water Content = 32.5 %

Estimated In-Situ K_o = 0.5

Estimated In-Situ Mean Effective
Stress = 55 psi

FUGRO JOB #: 0411-08-1701
Testing Station: RC5






Figure C.1 Variation in Low-Amplitude Shear Modulus with Magnitude and Duration of Isotropic Confining Pressure from Resonant Column Tests




Figure C.2 Variation in Low-Amplitude Material Damping Ratio with Magnitude and Duration of Isotropic Confining Pressure from Resonant Column Tests




Figure C.3 Variation in Estimated Void Ratio with Magnitude and Duration of Isotropic Confining Pressure from Resonant Column Tests




Figure C.4 Variation in Low-Amplitude Shear Wave Velocity with Isotropic Confining Pressure from Resonant Column Tests




Figure C.5 Variation in Low-Amplitude Shear Modulus with Isotropic Confining Pressure from Resonant Column Tests




Figure C.6 Variation in Low-Amplitude Material Damping Ratio with Isotropic Confining Pressure from Resonant Column Tests




Figure C.7 Variation in Estimated Void Ratio with Isotropic Confining Pressure from Resonant Column Tests




Figure C.8 Comparison of the Variation in Shear Modulus with Shearing Strain and Isotropic Confining Pressure from the Resonant Column Tests




Figure C.9 Comparison of the Variation in Normalized Shear Modulus with Shearing Strain and Isotropic Confining Pressure from the Resonant Column Tests




Figure C.10 Comparison of the Variation in Material Damping Ratio with Shearing Strain and Isotropic Confining Pressure from the Resonant Column Tests




Figure C.11 Comparison of the Variation in Shear Modulus with Shearing Strain at an Isotropic Confining Pressure of 55 psi from the Combined RCTS Tests




Figure C.12 Comparison of the Variation in Normalized Shear Modulus with Shearing Strain at an Isotropic Confining Pressure of 55 psi from the Combined RCTS Tests




Figure C.13 Comparison of the Variation in Material Damping Ratio with Shearing Strain at an Isotropic Confining Pressure of 55 psi from the Combined RCTS Tests




Figure C.14 Comparison of the Variation in Shear Modulus with Loading Frequency at an Isotropic Confining Pressure of 55 psi from the Combined RCTS Tests




Figure C.15 Comparison of the Variation in Material Damping Ratio with Loading Frequency at an Isotropic Confining Pressure of 55 psi from the Combined RCTS Tests




Figure C.16 Comparison of the Variation in Shear Modulus with Shearing Strain at an Isotropic Confining Pressure of 219 psi from the Combined RCTS Tests




Figure C.17 Comparison of the Variation in Normalized Shear Modulus with Shearing Strain at an Isotropic Confining Pressure of 219 psi from the Combined RCTS Tests




Figure C.18 Comparison of the Variation in Material Damping Ratio with Shearing Strain at an Isotropic Confining Pressure of 219 psi from the Combined RCTS Tests




Figure C.19 Comparison of the Variation in Shear Modulus with Loading Frequency at an Isotropic Confining Pressure of 219 psi from the Combined RCTS Tests




Figure C.20 Comparison of the Variation in Material Damping Ratio with Loading Frequency at an Isotropic Confining Pressure of 219 psi from the Combined RCTS Tests

Table C.1 · Variation in Low-Amplitude Shear Wave Velocity, Low-Amplitude Shear Modulus, Low-Amplitude Material Damping Ratio and Estimated Void Ratio with Isotropic Confining Pressure from RC Tests of Specimen B630-UD13

Isotropic Confining Pressure, σ_o			Low-Amplitude Shear Modulus, G_{max}		Low-Amplitude Shear Wave Velocity, V_s	Low-Amplitude Material Damping Ratio, D_{min}	Estimated Void Ratio, e
(psi)	(psf)	(kPa)	(ksf)	(MPa)	(fps)	(%)	
14	2016	96	1794	86	701	0.81	0.87
27	3888	186	2417	116	814	0.71	0.87
55	7920	379	3381	162	961	0.63	0.86
109	15696	751	4596	221	1118	0.54	0.85
219	31536	1509	5732	275	1243	0.46	0.84

Table C.2 Variation in Shear Modulus and Material Damping Ratio with Shearing Strain from RC Tests of Specimen B630-UD13; Isotropic Confining Pressure, $\sigma_o = 55$ psi (7.9 ksf = 379 kPa)

Peak Shearing Strain, %	Shear Modulus, G, ksf	Normalized Shear Modulus, G/G_{max}	Average ⁺ Shearing Strain, %	Material Damping Ratio ^x , D, %
3.88E-04	3381	1.00	3.88E-04	0.63
8.14E-04	3381	1.00	8.14E-04	0.63
1.58E-03	3381	1.00	1.47E-03	0.62
3.06E-03	3326	0.98	2.79E-03	0.70
5.66E-03	3272	0.97	5.09E-03	0.85
1.03E-02	3164	0.94	9.17E-03	1.17
1.81E-02	3033	0.90	1.57E-02	1.54
2.98E-02	2908	0.86	2.50E-02	2.01
5.17E-02	2629	0.78	4.19E-02	2.79
8.86E-02	2362	0.70	6.65E-02	4.11
1.65E-01	2002	0.59	1.14E-01	5.69

⁺ Average Shearing Strain from the First Three Cycles of the Free Vibration Decay Curve

^x Average Damping Ratio from the First Three Cycles of the Free Vibration Decay Curve

Table C.3 Variation in Shear Modulus, Normalized Shear Modulus and Material Damping Ratio with Shearing Strain from TS Tests of Specimen B630-UD13; Isotropic Confining Pressure, $\sigma_0 = 55$ psi (7.9 ksf = 379 kPa)

First Cycle				Tenth Cycle			
Peak Shearing Strain, %	Shear Modulus, G, ksf	Normalized Shear Modulus, G/G_{max}	Material Damping Ratio, D, %	Peak Shearing Strain, %	Shear Modulus, G, ksf	Normalized Shear Modulus, G/G_{max}	Material Damping Ratio, D, %
1.02E-03	3420	1.00	---	1.04E-03	3407	1.00	---
2.07E-03	3390	0.99	0.83	2.05E-03	3407	1.00	0.58
4.33E-03	3239	0.95	0.98	4.22E-03	3325	0.98	0.56
1.04E-02	3097	0.91	1.38	1.04E-02	3108	0.91	1.54

Table C.4 Variation in Shear Modulus and Material Damping Ratio with Shearing Strain from RC Tests of Specimen B630-UD13; Isotropic Confining Pressure, $\sigma_o = 219$ psi (31.5 ksf = 1509 kPa)

Peak Shearing Strain, %	Shear Modulus, G, ksf	Normalized Shear Modulus, G/G_{max}	Average ⁺ Shearing Strain, %	Material Damping Ratio ^x , D, %
3.55E-04	5727	1.00	3.55E-04	0.46
7.29E-04	5727	1.00	7.29E-04	0.46
1.41E-03	5727	1.00	1.32E-03	0.46
2.69E-03	5691	0.99	2.50E-03	0.51
5.02E-03	5619	0.98	4.67E-03	0.61
9.09E-03	5513	0.96	8.45E-03	0.70
1.63E-02	5325	0.93	1.49E-02	0.92
2.77E-02	5141	0.90	2.47E-02	1.22
4.79E-02	4782	0.83	4.12E-02	1.80
8.05E-02	4398	0.77	6.60E-02	2.62
1.33E-01	3910	0.68	1.03E-01	3.68
2.49E-01	3283	0.57	1.76E-01	5.10

⁺ Average Shearing Strain from the First Three Cycles of the Free Vibration Decay Curve

^x Average Damping Ratio from the First Three Cycles of the Free Vibration Decay Curve

Table C.5 Variation in Shear Modulus, Normalized Shear Modulus and Material Damping Ratio with Shearing Strain from TS Tests of Specimen B630-UD13; Isotropic Confining Pressure, $\sigma_o = 219$ psi (31.5 ksf = 1509 kPa)

First Cycle				Tenth Cycle			
Peak Shearing Strain, %	Shear Modulus, G, ksf	Normalized Shear Modulus, G/G_{max}	Material Damping Ratio, D, %	Peak Shearing Strain, %	Shear Modulus, G, ksf	Normalized Shear Modulus, G/G_{max}	Material Damping Ratio, D, %
8.84E-04	5560	1.00	---	9.05E-04	5528	1.00	0.59
2.02E-03	5560	1.00	0.52	2.01E-03	5528	1.00	0.53
4.01E-03	5550	1.00	0.69	4.00E-03	5528	1.00	0.71
1.01E-02	5218	0.94	1.05	9.93E-03	5293	0.96	1.10

APPENDIX D

Specimen B630-UD16

Borehole 630

Sample UD16

Depth = 211.0 ft (64.3 m)

Total Unit Weight = 116.3 lb/ft³

Water Content = 31.1 %

Estimated In-Situ K_o = 0.5

Estimated In-Situ Mean Effective
Stress = 60 psi

FUGRO JOB #: 0411-08-1701
Testing Station: RC9






Figure D.1 Variation in Low-Amplitude Shear Modulus with Magnitude and Duration of Isotropic Confining Pressure from Resonant Column Tests




Figure D.2 Variation in Low-Amplitude Material Damping Ratio with Magnitude and Duration of Isotropic Confining Pressure from Resonant Column Tests




Figure D.3 Variation in Estimated Void Ratio with Magnitude and Duration of Isotropic Confining Pressure from Resonant Column Tests




Figure D.4 Variation in Low-Amplitude Shear Wave Velocity with Isotropic Confining Pressure from Resonant Column Tests




Figure D.5 Variation in Low-Amplitude Shear Modulus with Isotropic Confining Pressure from Resonant Column Tests




Figure D.6 Variation in Low-Amplitude Material Damping Ratio with Isotropic Confining Pressure from Resonant Column Tests




Figure D.7 Variation in Estimated Void Ratio with Isotropic Confining Pressure from Resonant Column Tests




Figure D.8 Comparison of the Variation in Shear Modulus with Shearing Strain and Isotropic Confining Pressure from the Resonant Column Tests




Figure D.9 Comparison of the Variation in Normalized Shear Modulus with Shearing Strain and Isotropic Confining Pressure from the Resonant Column Tests




Figure D.10 Comparison of the Variation in Material Damping Ratio with Shearing Strain and Isotropic Confining Pressure from the Resonant Column Tests




Figure D.11 Comparison of the Variation in Shear Modulus with Shearing Strain at an Isotropic Confining Pressure of 60 psi from the Combined RCTS Tests




Figure D.12 Comparison of the Variation in Normalized Shear Modulus with Shearing Strain at an Isotropic Confining Pressure of 60 psi from the Combined RCTS Tests




Figure D.13 Comparison of the Variation in Material Damping Ratio with Shearing Strain at an Isotropic Confining Pressure of 60 psi from the Combined RCTS Tests




Figure D.14 Comparison of the Variation in Shear Modulus with Loading Frequency at an Isotropic Confining Pressure of 60 psi from the Combined RCTS Tests




Figure D.15 Comparison of the Variation in Material Damping Ratio with Loading Frequency at an Isotropic Confining Pressure of 60 psi from the Combined RCTS Tests




Figure D.16 Comparison of the Variation in Shear Modulus with Shearing Strain at an Isotropic Confining Pressure of 242 psi from the Combined RCTS Tests




Figure D.17 Comparison of the Variation in Normalized Shear Modulus with Shearing Strain at an Isotropic Confining Pressure of 242 psi from the Combined RCTS Tests




Figure D.18 Comparison of the Variation in Material Damping Ratio with Shearing Strain at an Isotropic Confining Pressure of 242 psi from the Combined RCTS Tests




Figure D.19 Comparison of the Variation in Shear Modulus with Loading Frequency at an Isotropic Confining Pressure of 242 psi from the Combined RCTS Tests




Figure D.20 Comparison of the Variation in Material Damping Ratio with Loading Frequency at an Isotropic Confining Pressure of 242 psi from the Combined RCTS Tests

Table D.1 Variation in Low-Amplitude Shear Wave Velocity, Low-Amplitude Shear Modulus, Low-Amplitude Material Damping Ratio and Estimated Void Ratio with Isotropic Confining Pressure from RC Tests of Specimen B630-UD16

Isotropic Confining Pressure, σ_o			Low-Amplitude Shear Modulus, G_{max}		Low-Amplitude Shear Wave Velocity, V_s	Low-Amplitude Material Damping Ratio, D_{min}	Estimated Void Ratio, e
(psi)	(psf)	(kPa)	(ksf)	(MPa)	(fps)	(%)	
15	2160	103	2127	102	765	1.21	0.85
30	4320	207	3042	146	913	1.09	0.85
60	8640	413	4303	207	1083	1.00	0.84
121	17424	834	6033	290	1277	0.85	0.82
242	34848	1667	8347	401	1488	0.69	0.79

Table D.2 Variation in Shear Modulus and Material Damping Ratio with Shearing Strain from RC Tests of Specimen B630-UD16; Isotropic Confining Pressure, $\sigma_c = 60$ psi (8.6 ksf = 413 kPa)

Peak Shearing Strain, %	Shear Modulus, G, ksf	Normalized Shear Modulus, G/G_{max}	Average ⁺ Shearing Strain, %	Material Damping Ratio ^x , D, %
3.41E-04	4335	1.00	3.41E-04	0.99
6.93E-04	4335	1.00	6.93E-04	0.99
1.36E-03	4304	0.99	1.25E-03	1.01
2.60E-03	4273	0.99	2.39E-03	1.04
4.78E-03	4212	0.97	4.35E-03	1.10
8.53E-03	4091	0.94	7.68E-03	1.31
1.47E-02	3912	0.90	1.28E-02	1.80
2.48E-02	3652	0.84	2.08E-02	2.58
4.23E-02	3347	0.77	3.34E-02	3.58
7.52E-02	2929	0.68	5.42E-02	5.29
1.06E-01	2662	0.61	7.23E-02	6.47

⁺ Average Shearing Strain from the First Three Cycles of the Free Vibration Decay Curve

^x Average Damping Ratio from the First Three Cycles of the Free Vibration Decay Curve

Table D.3 Variation in Shear Modulus, Normalized Shear Modulus and Material Damping Ratio with Shearing Strain from TS Tests of Specimen B630-UD16; Isotropic Confining Pressure, $\sigma_o = 60$ psi (8.6 ksf = 413 kPa)

First Cycle				Tenth Cycle			
Peak Shearing Strain, %	Shear Modulus, G, ksf	Normalized Shear Modulus, G/G_{max}	Material Damping Ratio, D, %	Peak Shearing Strain, %	Shear Modulus, G, ksf	Normalized Shear Modulus, G/G_{max}	Material Damping Ratio, D, %
1.01E-03	3981	1.00	0.77	1.01E-03	3988	1.00	1.05
2.04E-03	3972	1.00	0.96	2.07E-03	3910	0.98	0.73
4.17E-03	3885	0.98	1.21	4.19E-03	3868	0.97	1.14
8.72E-03	3713	0.93	1.86	8.75E-03	3701	0.93	1.81

Table D.4 Variation in Shear Modulus and Material Damping Ratio with Shearing Strain from RC Tests of Specimen B630-UD16; Isotropic Confining Pressure, $\sigma_0 = 242$ psi (34.8 ksf = 1667 kPa)

Peak Shearing Strain, %	Shear Modulus, G, ksf	Normalized Shear Modulus, G/G_{max}	Average ⁺ Shearing Strain, %	Material Damping Ratio [*] , D, %
2.21E-04	8430	1.00	2.21E-04	0.69
4.43E-04	8430	1.00	4.43E-04	0.69
9.09E-04	8430	1.00	8.54E-04	0.69
1.79E-03	8390	1.00	1.68E-03	0.70
3.42E-03	8312	0.99	3.21E-03	0.73
6.28E-03	8195	0.97	5.90E-03	0.77
1.11E-02	7993	0.95	1.03E-02	0.94
1.88E-02	7689	0.91	1.69E-02	1.33
3.12E-02	7279	0.86	2.72E-02	1.94
5.17E-02	6777	0.80	4.29E-02	2.81
9.00E-02	5945	0.71	7.02E-02	4.07
1.65E-01	4867	0.58	1.16E-01	5.91

⁺ Average Shearing Strain from the First Three Cycles of the Free Vibration Decay Curve

^{*} Average Damping Ratio from the First Three Cycles of the Free Vibration Decay Curve

Table D.5 Variation in Shear Modulus, Normalized Shear Modulus and Material Damping Ratio with Shearing Strain from TS Tests of Specimen B630-UD16; Isotropic Confining Pressure, $\sigma_o = 242$ psi (34.8 ksf = 1667 kPa)

First Cycle				Tenth Cycle			
Peak Shearing Strain, %	Shear Modulus, G, ksf	Normalized Shear Modulus, G/G_{max}	Material Damping Ratio, D, %	Peak Shearing Strain, %	Shear Modulus, G, ksf	Normalized Shear Modulus, G/G_{max}	Material Damping Ratio, D, %
9.81E-04	7797	1.00	0.64	9.85E-04	7764	0.99	0.60
1.98E-03	7713	0.99	0.46	1.94E-03	7872	1.00	0.58
3.96E-03	7720	0.99	0.54	3.94E-03	7779	0.99	0.83
8.03E-03	7625	0.98	1.09	8.02E-03	7638	0.97	1.09



6100 Hillcroft (77081)
P.O. Box 740010
Houston, Texas 77274
Tel: 713-369-5400
Fax: 713-369-5518

July 12, 2008

Ms. Siesta Williams
MACTEC
3301 Atlantic Avenue
Raleigh, NC 27604

RE: Three (3) Reports For The Turkey Point Project

Dear Ms. Williams:

Fugro has completed three (3) RCTS tests, which are B630-UD19, B630-UD23, and B630-UD27 for the Turkey Point project. Fugro has incorporated, as needed, Dr. Kenneth Stokoe's comments into the final reports. The final reports and the associated RCTS Test Approvals by Dr. Kenneth Stokoe have been attached.

Please let us know if you have questions. Thanks.

Very truly yours,

Fugro Consultants, Inc.

A handwritten signature in black ink, appearing to read "Jiewu Meng".

Jiewu Meng, PhD, P.E.
Project Engineer

A handwritten signature in black ink, appearing to read "Bill DeGroff".

Bill DeGroff, P.E.
Laboratory Department Manager

Enclosures



RCTS TEST APPROVAL


PROJECT SITE/NAME	Turkey Point
-------------------	--------------

Test ID	Sample ID	Depth B.S. (Ft)	Approved By (Initials)	Date
RCTS#E	B630-UD19	231.0	K/S (⊕)	5 July '08
RCTS#F	B630-UD23	260.5	K/S (⊕) (A)	5 July '08
RCTS#G	B630-UD27	294.0	K/S (⊕)	5 July '08

Three RCTS tests for the site referenced above were tested, and three reports were prepared, by Fugro Consultants, Inc.

I have reviewed the data and associated results listed above and found them to be reasonable.

Approved By:



Dr. Kenneth Stokoe

- ⊕ See minor comments and suggestions on a few figures
- Ⓐ In Appendix F, the reported γ of 150.1 lb/ft^3 on the cover page can not be correct. Please correct to $\sim 121 \text{ lb/ft}^3$.

APPENDIX E

Specimen B630-UD19

Borehole 630

Sample UD19

Depth = 231.0 ft (70.6 m)

Total Unit Weight = 121.9 lb/ft³

Water Content = 26.6 %

Estimated In-Situ K_o = 0.5

Estimated In-Situ Mean Effective
Stress = 66 psi

FUGRO JOB #: 0411-08-1701
Testing Station: RC9






Figure E.1 Variation in Low-Amplitude Shear Modulus with Magnitude and Duration of Isotropic Confining Pressure from Resonant Column Tests




Figure E.2 Variation in Low-Amplitude Material Damping Ratio with Magnitude and Duration of Isotropic Confining Pressure from Resonant Column Tests




Figure E.3 Variation in Estimated Void Ratio with Magnitude and Duration of Isotropic Confining Pressure from Resonant Column Tests




Figure E.4 Variation in Low-Amplitude Shear Wave Velocity with Isotropic Confining Pressure from Resonant Column Tests




Figure E.5 Variation in Low-Amplitude Shear Modulus with Isotropic Confining Pressure from Resonant Column Tests




Figure E.6 Variation in Low-Amplitude Material Damping Ratio with Isotropic Confining Pressure from Resonant Column Tests




Figure E.7 Variation in Estimated Void Ratio with Isotropic Confining Pressure from Resonant Column Tests




Figure E.8 Comparison of the Variation in Shear Modulus with Shearing Strain and Isotropic Confining Pressure from the Resonant Column Tests




Figure E.9 Comparison of the Variation in Normalized Shear Modulus with Shearing Strain and Isotropic Confining Pressure from the Resonant Column Tests




Figure E.10 Comparison of the Variation in Material Damping Ratio with Shearing Strain and Isotropic Confining Pressure from the Resonant Column Tests




Figure E.11 Comparison of the Variation in Shear Modulus with Shearing Strain at an Isotropic Confining Pressure of 66 psi from the Combined RCTS Tests




Figure E.12 Comparison of the Variation in Normalized Shear Modulus with Shearing Strain at an Isotropic Confining Pressure of 66 psi from the Combined RCTS Tests




Figure E.13 Comparison of the Variation in Material Damping Ratio with Shearing Strain at an Isotropic Confining Pressure of 66 psi from the Combined RCTS Tests




Figure E.14 Comparison of the Variation in Shear Modulus with Loading Frequency at an Isotropic Confining Pressure of 66 psi from the Combined RCTS Tests




Figure E.15 Comparison of the Variation in Material Damping Ratio with Loading Frequency at an Isotropic Confining Pressure of 66 psi from the Combined RCTS Tests




Figure E.16 Comparison of the Variation in Shear Modulus with Shearing Strain at an Isotropic Confining Pressure of 265 psi from the Combined RCTS Tests




Figure E.17 Comparison of the Variation in Normalized Shear Modulus with Shearing Strain at an Isotropic Confining Pressure of 265 psi from the Combined RCTS Tests




Figure E.18 Comparison of the Variation in Material Damping Ratio with Shearing Strain at an Isotropic Confining Pressure of 265 psi from the Combined RCTS Tests




Figure E.19 Comparison of the Variation in Shear Modulus with Loading Frequency at an Isotropic Confining Pressure of 242 psi from the Combined RCTS Tests




Figure E.20 Comparison of the Variation in Material Damping Ratio with Loading Frequency at an Isotropic Confining Pressure of 242 psi from the Combined RCTS Tests

Table E.1 Variation in Low-Amplitude Shear Wave Velocity, Low-Amplitude Shear Modulus, Low-Amplitude Material Damping Ratio and Estimated Void Ratio with Isotropic Confining Pressure from RC Tests of Specimen B630-UD19

Isotropic Confining Pressure, σ_o			Low-Amplitude Shear Modulus, G_{max}		Low-Amplitude Shear Wave Velocity, V_s	Low-Amplitude Material Damping Ratio, D_{min}	Estimated Void Ratio, e
(psi)	(psf)	(kPa)	(ksf)	(MPa)	(fps)	(%)	
17	2448	117	1854	89	699	0.64	0.72
33	4752	227	2617	126	830	0.50	0.71
66	9504	455	3705	178	987	0.41	0.71
132	19008	909	5579	268	1209	0.36	0.71
265	38160	1826	7729	371	1420	0.34	0.70

Table E.2 Variation in Shear Modulus and Material Damping Ratio with Shearing Strain from RC Tests of Specimen B630-UD19; Isotropic Confining Pressure, $\sigma_0 = 66$ psi (9.5ksf = 455 kPa)

Peak Shearing Strain, %	Shear Modulus, G, ksf	Normalized Shear Modulus, G/G_{max}	Average ⁺ Shearing Strain, %	Material Damping Ratio [*] , D, %
3.29E-04	3762	1.00	3.29E-04	0.41
7.01E-04	3762	1.00	7.01E-04	0.41
1.33E-03	3728	0.99	1.27E-03	0.46
2.47E-03	3705	0.98	2.32E-03	0.49
4.45E-03	3637	0.97	4.18E-03	0.55
7.81E-03	3570	0.95	7.27E-03	0.65
1.33E-02	3452	0.92	1.22E-02	0.85
2.18E-02	3312	0.88	1.96E-02	1.29
3.54E-02	3107	0.83	3.04E-02	1.99
5.82E-02	2831	0.75	4.71E-02	2.94
9.82E-02	2473	0.66	7.46E-02	4.24
1.66E-01	2172	0.58	1.16E-01	5.77

⁺ Average Shearing Strain from the First Three Cycles of the Free Vibration Decay Curve

^{*} Average Damping Ratio from the First Three Cycles of the Free Vibration Decay Curve

Table E.3 Variation in Shear Modulus, Normalized Shear Modulus and Material Damping Ratio with Shearing Strain from TS Tests of Specimen B630-UD19; Isotropic Confining Pressure, $\sigma_o = 66$ psi (9.5 ksf = 455 kPa)

First Cycle				Tenth Cycle			
Peak Shearing Strain, %	Shear Modulus, G, ksf	Normalized Shear Modulus, G/G_{max}	Material Damping Ratio, D, %	Peak Shearing Strain, %	Shear Modulus, G, ksf	Normalized Shear Modulus, G/G_{max}	Material Damping Ratio, D, %
1.05E-03	3628	1.00	0.24	1.04E-03	3679	1.00	0.47
2.12E-03	3615	1.00	0.52	2.13E-03	3597	0.98	0.42
4.31E-03	3554	0.98	0.84	4.31E-03	3555	0.97	0.74
8.93E-03	3431	0.95	1.09	8.96E-03	3420	0.93	1.08

Table E.4 Variation in Shear Modulus and Material Damping Ratio with Shearing Strain from RC Tests of Specimen B630-UD19; Isotropic Confining Pressure, $\sigma_o = 265$ psi (38.2 ksf = 1826 kPa)

Peak Shearing Strain, %	Shear Modulus, G, ksf	Normalized Shear Modulus, G/G_{max}	Average ⁺ Shearing Strain, %	Material Damping Ratio ^x , D, %
2.99E-04	7729	1.00	2.99E-04	0.34
6.09E-04	7729	1.00	6.09E-04	0.34
1.16E-03	7729	1.00	1.12E-03	0.36
2.20E-03	7652	0.99	2.11E-03	0.37
4.02E-03	7614	0.99	3.86E-03	0.39
7.23E-03	7500	0.97	6.87E-03	0.44
1.22E-02	7354	0.95	1.16E-02	0.57
1.99E-02	7163	0.93	1.88E-02	0.74
3.26E-02	6834	0.88	2.96E-02	1.06
5.19E-02	6412	0.83	4.67E-02	1.78
8.07E-02	5896	0.76	6.70E-02	2.88
1.28E-01	5301	0.69	9.85E-02	4.19
1.57E-01	5057	0.65	1.14E-01	5.05

⁺ Average Shearing Strain from the First Three Cycles of the Free Vibration Decay Curve

^x Average Damping Ratio from the First Three Cycles of the Free Vibration Decay Curve

Table E.5 Variation in Shear Modulus, Normalized Shear Modulus and Material Damping Ratio with Shearing Strain from TS Tests of Specimen B630-UD19; Isotropic Confining Pressure, $\sigma_o = 265$ psi (38.2 ksf = 1826 kPa)

First Cycle				Tenth Cycle			
Peak Shearing Strain, %	Shear Modulus, G, ksf	Normalized Shear Modulus, G/G_{max}	Material Damping Ratio, D, %	Peak Shearing Strain, %	Shear Modulus, G, ksf	Normalized Shear Modulus, G/G_{max}	Material Damping Ratio, D, %
2.00E-03	7251	1.00	0.12	1.99E-03	7279	1.00	0.32
4.03E-03	7186	0.99	0.35	4.03E-03	7192	0.99	0.40
8.17E-03	7091	0.98	0.60	8.16E-03	7103	0.98	0.58

APPENDIX F

Specimen B630-UD23

Borehole 630

Sample UD23

Depth = 260.5 ft (79.4 m)

Total Unit Weight = 121.3 lb/ft³

Water Content = 27.1 %

Estimated In-Situ K_o = 0.5

Estimated In-Situ Mean Effective
Stress = 75 psi

FUGRO JOB #: 0411-08-1701
Testing Station: RC8






Figure F.1 Variation in Low-Amplitude Shear Modulus with Magnitude and Duration of Isotropic Confining Pressure from Resonant Column Tests




Figure F.2 Variation in Low-Amplitude Material Damping Ratio with Magnitude and Duration of Isotropic Confining Pressure from Resonant Column Tests




Figure F.3 Variation in Estimated Void Ratio with Magnitude and Duration of Isotropic Confining Pressure from Resonant Column Tests




Figure F.4 Variation in Low-Amplitude Shear Wave Velocity with Isotropic Confining Pressure from Resonant Column Tests




Figure F.5 Variation in Low-Amplitude Shear Modulus with Isotropic Confining Pressure from Resonant Column Tests




Figure F.6 Variation in Low-Amplitude Material Damping Ratio with Isotropic Confining Pressure from Resonant Column Tests




Figure F.7 Variation in Estimated Void Ratio with Isotropic Confining Pressure from Resonant Column Tests




Figure F.8 Comparison of the Variation in Shear Modulus with Shearing Strain and Isotropic Confining Pressure from the Resonant Column Tests




Figure F.9 Comparison of the Variation in Normalized Shear Modulus with Shearing Strain and Isotropic Confining Pressure from the Resonant Column Tests




Figure F.10 Comparison of the Variation in Material Damping Ratio with Shearing Strain and Isotropic Confining Pressure from the Resonant Column Tests




Figure F.11 Comparison of the Variation in Shear Modulus with Shearing Strain at an Isotropic Confining Pressure of 75 psi from the Combined RCTS Tests




Figure F.12 Comparison of the Variation in Normalized Shear Modulus with Shearing Strain at an Isotropic Confining Pressure of 75 psi from the Combined RCTS Tests




Figure F.13 Comparison of the Variation in Material Damping Ratio with Shearing Strain at an Isotropic Confining Pressure of 75 psi from the Combined RCTS Tests




Figure F.14 Comparison of the Variation in Shear Modulus with Loading Frequency at an Isotropic Confining Pressure of 75 psi from the Combined RCTS Tests




Figure F.15 Comparison of the Variation in Material Damping Ratio with Loading Frequency at an Isotropic Confining Pressure of 75 psi from the Combined RCTS Tests




Figure F.16 Comparison of the Variation in Shear Modulus with Shearing Strain at an Isotropic Confining Pressure of 300 psi from the Combined RCTS Tests




Figure F.17 Comparison of the Variation in Normalized Shear Modulus with Shearing Strain at an Isotropic Confining Pressure of 300 psi from the Combined RCTS Tests




Figure F.18 Comparison of the Variation in Material Damping Ratio with Shearing Strain at an Isotropic Confining Pressure of 300 psi from the Combined RCTS Tests




Figure F.19 Comparison of the Variation in Shear Modulus with Loading Frequency at an Isotropic Confining Pressure of 300 psi from the Combined RCTS Tests




Figure F.20 Comparison of the Variation in Material Damping Ratio with Loading Frequency at an Isotropic Confining Pressure of 300 psi from the Combined RCTS Tests

Table F.1 Variation in Low-Amplitude Shear Wave Velocity, Low-Amplitude Shear Modulus, Low-Amplitude Material Damping Ratio and Estimated Void Ratio with Isotropic Confining Pressure from RC Tests of Specimen B630-UD23

Isotropic Confining Pressure, σ_o			Low-Amplitude Shear Modulus, G_{max}		Low-Amplitude Shear Wave Velocity, V_s	Low-Amplitude Material Damping Ratio, D_{min}	Estimated Void Ratio, e
(psi)	(psf)	(kPa)	(ksf)	(MPa)	(fps)	(%)	
19	2736	131	1908	92	711	0.92	0.73
37	5328	255	2612	125	831	0.79	0.73
75	10800	517	3742	180	993	0.66	0.72
150	21600	1034	5405	259	1191	0.57	0.71
300	43200	2067	7663	368	1409	0.49	0.69

Table F.2 Variation in Shear Modulus and Material Damping Ratio with Shearing Strain from RC Tests of Specimen B630-UD23; Isotropic Confining Pressure, $\sigma_o = 75$ psi (10.8 ksf = 517 kPa)

Peak Shearing Strain, %	Shear Modulus, G, ksf	Normalized Shear Modulus, G/G_{max}	Average ⁺ Shearing Strain, %	Material Damping Ratio ^x , D, %
3.24E-04	3713	1.00	3.24E-04	0.66
6.60E-04	3713	1.00	6.60E-04	0.66
1.30E-03	3679	0.99	1.21E-03	0.74
2.43E-03	3656	0.98	2.26E-03	0.88
4.62E-03	3589	0.97	4.21E-03	1.08
8.71E-03	3523	0.95	7.83E-03	1.31
1.52E-02	3417	0.92	1.37E-02	1.58
2.50E-02	3302	0.89	2.20E-02	1.94
4.17E-02	3043	0.82	3.50E-02	2.49
6.85E-02	2760	0.74	5.48E-02	3.33
1.14E-01	2451	0.66	8.59E-02	4.39

⁺ Average Shearing Strain from the First Three Cycles of the Free Vibration Decay Curve

^x Average Damping Ratio from the First Three Cycles of the Free Vibration Decay Curve

Table F.3 Variation in Shear Modulus, Normalized Shear Modulus and Material Damping Ratio with Shearing Strain from TS Tests of Specimen B630-UD23; Isotropic Confining Pressure, $\sigma_o = 75$ psi (10.8 ksf = 517 kPa)

First Cycle				Tenth Cycle			
Peak Shearing Strain, %	Shear Modulus, G, ksf	Normalized Shear Modulus, G/G_{max}	Material Damping Ratio, D, %	Peak Shearing Strain, %	Shear Modulus, G, ksf	Normalized Shear Modulus, G/G_{max}	Material Damping Ratio, D, %
1.00E-03	3694	1.00	0.45	1.01E-03	3677	0.99	0.28
2.00E-03	3700	1.00	0.51	2.00E-03	3715	1.00	0.55
4.09E-03	3616	0.98	0.68	4.10E-03	3617	0.97	0.67
8.43E-03	3515	0.95	1.07	8.47E-03	3500	0.94	1.00

Table F.4 Variation in Shear Modulus and Material Damping Ratio with Shearing Strain from RC Tests of Specimen B630-UD23; Isotropic Confining Pressure, $\sigma_3 = 300$ psi (43.2 ksf = 2067 kPa)

Peak Shearing Strain, %	Shear Modulus, G, ksf	Normalized Shear Modulus, G/G_{max}	Average ⁺ Shearing Strain, %	Material Damping Ratio ^x , D, %
2.58E-04	7696	1.00	2.58E-04	0.49
5.02E-04	7696	1.00	5.02E-04	0.49
1.01E-03	7696	1.00	9.61E-04	0.57
1.92E-03	7635	0.99	1.82E-03	0.61
3.55E-03	7562	0.98	3.34E-03	0.68
6.32E-03	7489	0.97	5.94E-03	0.78
1.09E-02	7365	0.96	1.01E-02	0.91
1.82E-02	7146	0.93	1.66E-02	1.13
3.04E-02	6822	0.89	2.73E-02	1.43
4.81E-02	6430	0.84	4.19E-02	1.88
7.89E-02	5847	0.76	6.63E-02	2.67
1.24E-01	5386	0.70	9.81E-02	3.75
1.54E-01	5138	0.67	1.38E-01	4.68

⁺ Average Shearing Strain from the First Three Cycles of the Free Vibration Decay Curve

^x Average Damping Ratio from the First Three Cycles of the Free Vibration Decay Curve

Table F.5 Variation in Shear Modulus, Normalized Shear Modulus and Material Damping Ratio with Shearing Strain from TS Tests of Specimen B630-UD23; Isotropic Confining Pressure, $\sigma_o = 168$ psi (43.2 ksf = 2067 kPa)

First Cycle				Tenth Cycle			
Peak Shearing Strain, %	Shear Modulus, G, ksf	Normalized Shear Modulus, G/G_{max}	Material Damping Ratio, D, %	Peak Shearing Strain, %	Shear Modulus, G, ksf	Normalized Shear Modulus, G/G_{max}	Material Damping Ratio, D, %
9.87E-04	6865	1.00	0.54	9.81E-04	6898	1.00	0.44
2.02E-03	6865	1.00	0.54	2.01E-03	6898	1.00	0.49
4.05E-03	6865	1.00	0.47	4.04E-03	6893	1.00	0.42
8.17E-03	6817	0.99	0.55	8.17E-03	6820	0.99	0.68

APPENDIX G

Specimen B630-UD27

Borehole 630

Sample UD27

Depth = 294.0 ft (89.6m)

Total Unit Weight = 121.3 lb/ft³

Water Content = 25.5 %

Estimated In-Situ K_o = 0.5

Estimated In-Situ Mean Effective
Stress = 84 psi

FUGRO JOB #: 0411-08-1701
Testing Station: RC8






Figure G.1 Variation in Low-Amplitude Shear Modulus with Magnitude and Duration of Isotropic Confining Pressure from Resonant Column Tests




Figure G.2 Variation in Low-Amplitude Material Damping Ratio with Magnitude and Duration of Isotropic Confining Pressure from Resonant Column Tests




Figure G.3 Variation in Estimated Void Ratio with Magnitude and Duration of Isotropic Confining Pressure from Resonant Column Tests




Figure G.4 Variation in Low-Amplitude Shear Wave Velocity with Isotropic Confining Pressure from Resonant Column Tests




Figure G.5 Variation in Low-Amplitude Shear Modulus with Isotropic Confining Pressure from Resonant Column Tests




Figure G.6 Variation in Low-Amplitude Material Damping Ratio with Isotropic Confining Pressure from Resonant Column Tests




Figure G.7 Variation in Estimated Void Ratio with Isotropic Confining Pressure from Resonant Column Tests




Figure G.8 Comparison of the Variation in Shear Modulus with Shearing Strain and Isotropic Confining Pressure from the Resonant Column Tests




Figure G.9 Comparison of the Variation in Normalized Shear Modulus with Shearing Strain and Isotropic Confining Pressure from the Resonant Column Tests




Figure G.10 Comparison of the Variation in Material Damping Ratio with Shearing Strain and Isotropic Confining Pressure from the Resonant Column Tests




Figure G.11 Comparison of the Variation in Shear Modulus with Shearing Strain at an Isotropic Confining Pressure of 84 psi from the Combined RCTS Tests




Figure G.12 Comparison of the Variation in Normalized Shear Modulus with Shearing Strain at an Isotropic Confining Pressure of 84 psi from the Combined RCTS Tests




Figure G.13 Comparison of the Variation in Material Damping Ratio with Shearing Strain at an Isotropic Confining Pressure of 84 psi from the Combined RCTS Tests




Figure G.14 Comparison of the Variation in Shear Modulus with Loading Frequency at an Isotropic Confining Pressure of 84 psi from the Combined RCTS Tests




Figure G.15 Comparison of the Variation in Material Damping Ratio with Loading Frequency at an Isotropic Confining Pressure of 84 psi from the Combined RCTS Tests




Figure G.16 Comparison of the Variation in Shear Modulus with Shearing Strain at an Isotropic Confining Pressure of 338 psi from the Combined RCTS Tests




Figure G.17 Comparison of the Variation in Normalized Shear Modulus with Shearing Strain at an Isotropic Confining Pressure of 338 psi from the Combined RCTS Tests




Figure G.18 Comparison of the Variation in Material Damping Ratio with Shearing Strain at an Isotropic Confining Pressure of 338 psi from the Combined RCTS Tests




Figure G.19 Comparison of the Variation in Shear Modulus with Loading Frequency at an Isotropic Confining Pressure of 338 psi from the Combined RCTS Tests




Figure G.20 Comparison of the Variation in Material Damping Ratio with Loading Frequency at an Isotropic Confining Pressure of 338 psi from the Combined RCTS Tests

Table G.1 Variation in Low-Amplitude Shear Wave Velocity, Low-Amplitude Shear Modulus, Low-Amplitude Material Damping Ratio and Estimated Void Ratio with Isotropic Confining Pressure from RC Tests of Specimen B630-UD27

Isotropic Confining Pressure, σ_o			Low-Amplitude Shear Modulus, G_{max}		Low-Amplitude Shear Wave Velocity, V_s	Low-Amplitude Material Damping Ratio, D_{min}	Estimated Void Ratio, e
(psi)	(psf)	(kPa)	(ksf)	(MPa)	(fps)	(%)	
21	3024	145	2246	108	771	0.87	0.71
42	6048	289	3108	149	905	0.86	0.70
84	12096	579	4401	211	1075	0.52	0.69
169	24336	1164	6283	302	1279	0.50	0.68
338	48672	2329	8549	410	1485	0.47	0.67

Table G.2 Variation in Shear Modulus and Material Damping Ratio with Shearing Strain from RC Tests of Specimen B630-UD27; Isotropic Confining Pressure, $\sigma_3 = 84$ psi (12.1 ksf = 579 kPa)

Peak Shearing Strain, %	Shear Modulus, G, ksf	Normalized Shear Modulus, G/G_{max}	Average ⁺ Shearing Strain, %	Material Damping Ratio ^x , D, %
4.10E-04	4404	1.00	4.10E-04	0.52
8.37E-04	4404	1.00	8.37E-04	0.54
1.58E-03	4367	0.99	1.50E-03	0.55
2.94E-03	4318	0.98	2.77E-03	0.66
5.34E-03	4244	0.96	4.96E-03	0.81
9.49E-03	4147	0.94	8.73E-03	1.01
1.61E-02	4026	0.91	1.45E-02	1.36
2.71E-02	3780	0.86	2.35E-02	1.89
4.50E-02	3508	0.80	3.78E-02	2.62
7.47E-02	3183	0.72	5.90E-02	3.62
1.27E-01	2797	0.63	9.28E-02	5.11

⁺ Average Shearing Strain from the First Three Cycles of the Free Vibration Decay Curve

^x Average Damping Ratio from the First Three Cycles of the Free Vibration Decay Curve

Table G.3 Variation in Shear Modulus, Normalized Shear Modulus and Material Damping Ratio with Shearing Strain from TS Tests of Specimen B630-UD27; Isotropic Confining Pressure, $\sigma_o = 84$ psi (12.1 ksf = 579 kPa)

First Cycle				Tenth Cycle			
Peak Shearing Strain, %	Shear Modulus, G, ksf	Normalized Shear Modulus, G/G_{max}	Material Damping Ratio, D, %	Peak Shearing Strain, %	Shear Modulus, G, ksf	Normalized Shear Modulus, G/G_{max}	Material Damping Ratio, D, %
1.00E-03	4074	0.98	0.53	1.00E-03	4061	0.98	0.39
1.98E-03	4074	0.98	0.42	1.99E-03	4061	0.98	0.42
3.99E-03	4068	0.98	0.66	4.03E-03	4027	0.97	0.63
8.23E-03	3942	0.95	1.09	8.25E-03	3933	0.95	1.13

Table G.4 Variation in Shear Modulus and Material Damping Ratio with Shearing Strain from RC Tests of Specimen B630-UD27; Isotropic Confining Pressure, $\sigma_0 = 338$ psi (48.7 ksf = 2329 kPa)

Peak Shearing Strain, %	Shear Modulus, G, ksf	Normalized Shear Modulus, G/G_{max}	Average ⁺ Shearing Strain, %	Material Damping Ratio ^x , D, %
2.41E-04	8564	1.00	2.41E-04	0.47
4.81E-04	8564	1.00	4.81E-04	0.47
9.67E-04	8564	1.00	9.28E-04	0.48
1.83E-03	8495	0.99	1.75E-03	0.53
3.39E-03	8413	0.98	3.22E-03	0.56
6.12E-03	8291	0.97	5.82E-03	0.60
1.06E-02	8180	0.96	9.92E-03	0.74
1.76E-02	7925	0.93	1.62E-02	1.04
2.88E-02	7566	0.88	2.59E-02	1.49
4.30E-02	7151	0.84	3.83E-02	1.90
6.79E-02	6562	0.77	5.77E-02	2.69

⁺ Average Shearing Strain from the First Three Cycles of the Free Vibration Decay Curve

^x Average Damping Ratio from the First Three Cycles of the Free Vibration Decay Curve

Table G.5 Variation in Shear Modulus, Normalized Shear Modulus and Material Damping Ratio with Shearing Strain from TS Tests of Specimen B630-UD27; Isotropic Confining Pressure, $\sigma_o = 338$ psi (48.7 ksf = 2329 kPa)

First Cycle				Tenth Cycle			
Peak Shearing Strain, %	Shear Modulus, G, ksf	Normalized Shear Modulus, G/G_{max}	Material Damping Ratio, D, %	Peak Shearing Strain, %	Shear Modulus, G, ksf	Normalized Shear Modulus, G/G_{max}	Material Damping Ratio, D, %
1.01E-03	8551	1.00	0.45	1.02E-03	8486	1.00	0.47
2.03E-03	8551	1.00	0.47	2.05E-03	8486	1.00	0.35
4.10E-03	8551	1.00	0.53	4.07E-03	8523	1.00	0.63
8.31E-03	8362	0.98	0.77	8.32E-03	8352	0.98	0.75

**FINAL DATA REPORT Rev. 2
GEOTECHNICAL EXPLORATION AND TESTING**

**TURKEY POINT COL PROJECT
FLORIDA CITY, FLORIDA**

October 6, 2008

**VOLUME 4
Appendix G – Groundwater Data**

Prepared By:

**MACTEC Engineering and Consulting, Inc.
Raleigh, North Carolina**

MACTEC Project No. 6468-07-1950

Prepared For:

**Bechtel Power Corporation
Subcontract No. 25409-102-HC4-CY00-00001**

Contents

**Well Construction Permits
Observation Well Records
Well Development Records
Well Sampling Records
Laboratory Test Reports
Slug Test Data Forms**

Well Construction Permits

To: Tom Mc-Daniel

Folio #: 30-7034000-0010



STATE OF FLORIDA PERMIT APPLICATION TO CONSTRUCT, REPAIR, MODIFY, OR ABANDON A WELL

- Southwest
Northwest
St. Johns River
South Florida
Suwannee River

THIS FORM MUST BE FILLED OUT COMPLETELY. The water well contractor is responsible for completing this form and forwarding the permit to the appropriate delegated county where applicable.

CHECK BOX FOR APPROPRIATE DISTRICT. ADDRESS ON BACK OF PERMIT FORM.


Permit No. 13-99-2631
Florida Unique I.D.
Permit Editions Required (See attached)
62-324 Well
CUP Application No.

1. Florida Power & Light Co 9700 SW 344th Street Florida City 33034 3052466400
2. Turkey Point Nuclear Generating Station 9760 SW 344th Street Florida City FL 33035
3. MACTEC Engineering & Consulting Inc - Philip Pitts FL # 11035 404 873 4761
396 Plaster Ave
Atlanta GA 30324
Miami Dade N/A N/A N/A N/A

Print in this area in order that spaces be available for stamping.

7. Number of proposed wells 1 Check the use of well: Domestic Monitor (type) Observation Well
8. Application for: X New Construction
9. Estimated Well Depth 130' +/- Casing Depth 120'
10. If applicable: Proposed From 120 to 131 Seal Material 1/20 Silica Sand
11. Telescope Casing or Liner X (check one) Diameter 2" slurry
12. Method of Construction: X Rotary
13. Indicate total No. of wells on site 20. List number of unused wells on site 0
14. Is this well or any other well or water withdrawal on the owner's contiguous property covered under a Consumptive Water Use Permit (CUP/WUP) or CUP/WUP Application? X No

APPROVED
MAMI-DADE COUNTY HEALTH DEPARTMENT
5/23/08



15. I hereby certify that I will comply with the applicable rules of Title 40, Florida Administrative Code. I certify that I am the owner of the property, that the information provided is accurate, and that I am aware of my responsibilities under Chapter 373, Florida Statutes, to maintain or properly abandon the well or, I certify that I am the agent for the owner, that the information provided is accurate, and that I have informed the owner of his responsibilities as stated above. Other persons to be notified of the WUP or a representative access to the well site.
11035
Date 5/20/08

Approval Granted By: EDWARD EDWARDS Issue Date: 5/23/08 Hydrologist Approval:
Owner Number: Fee Received: \$ 50 Receipt No.: I080520430
THIS PERMIT NOT VALID UNTIL PROPERLY SIGNED BY AN AUTHORIZED OFFICER OR REPRESENTATIVE OF THE WMD. IT SHALL BE AVAILABLE AT THE WELL SITE DURING ALL DRILLING OPERATIONS. This permit is valid for 90 days from date of issue.

Form 0129 Rev. 4/95

13-WD-34019

I080520430



STATE OF FLORIDA PERMIT APPLICATION TO CONSTRUCT, REPAIR, MODIFY, OR ABANDON A WELL

- Southwest
Northwest
St. Johns River
South Florida
Suwannee River

THIS FORM MUST BE FILLED OUT COMPLETELY. The water well contractor is responsible for completing this form and forwarding the permit to the appropriate delegated county where applicable.

CHECK BOX FOR APPROPRIATE DISTRICT. ADDRESS ON BACK OF PERMIT FORM.

Permit No. 259-7743
Florida Unique I.D.
Permit stipulations Required (See attached)
62-524 well
CUP Application No.

Field as the line in order that address is visible through envelope window

1. Florida Power and Light Company, Attn: Mr. Ed Paula 9700 SW 344 Street Florida City 33034 305-246-6407
Owner, Legal Name of Entity if Corporation Address City Zip Telephone Number

2. Turkey Point Nuclear Generating Station - coordinates of proposed wells attached

Well Location - Address, Road Name or Number, City

3. MACTEC Engineering and Consulting, Inc. - Phillip K. Pitts FL # 11035 404-873-4761
Well Drilling Contractor License No. Telephone No.

396 Plasters Avenue Address City State Zip Atlanta Georgia 30324
4. SW 1/4 of NW 1/4 of Section 34 (Indicate Well on Chart) X

5. Township 57S Range 40E

6. Miami-Dade N/A N/A N/A N/A
County Subdivision Name Lot Block Unit SW SE

7. Number of proposed wells 1 Check the use of well: (See back of permit for additional choices) Domestic Monitor (type) Observation well
Irrigation (type) Public Water Supply (type) List Other

Distance from septic system N/A ft. Description of facility Estimated start of construction date 2/19/08

8. Application for: X New Construction Repair/Modify Abandonment

9. Estimated: Well Depth 101* ft Casing Depth 90 ft
Casing Material: Blk-Steel / Gal / PVC rvc Casing Diameter 2"

10. If applicable: Proposed From 88 to 100 Seal Material 10/20 silica sand
Grouting Interval From 85 to 85 Seal Material Bentonite

11. Telescope Casing or Liner X (check one) Diameter 2"
Blk-Steel / Galvanized / PVC/PVC Other (specify):

12. Method of Construction: X Rotary Cable Tool Combination
X Auger Other (specify):

13. Indicate total No. of wells on site 0 List number of unused wells on site 0

14. In this well or any other well or water withdrawal on the owner's contiguous property covered under a Consumptive Water Use Permit (CUP/WUP) or CUP/WUP Application? X No Yes

(If yes, complete the following) CUP/WUP No. N/A

District well I.D. No. N/A

Latitude N/A Longitude N/A

Data obtained from GPS or map or survey (map datum NAD 83 NAD 68)

15. I hereby certify that I will comply with applicable rules of Title 40, Florida Administrative Code... I certify that I am the owner of the property, that the information provided is accurate, and that I am aware of my responsibilities under Chapter 62, Florida Statutes...

Approval Granted By: ASTER EDWARDS Issue Date: 2-19-08 Hydrologist Approval

Owner Number: Fee Received: \$ 50 Receipt No. 1080215406 Check No. 524534

THIS PERMIT NOT VALID UNTIL PROPERLY SIGNED BY AN AUTHORIZED OFFICER OR REPRESENTATIVE OF THE WMD. IT SHALL BE AVAILABLE AT THE WELL SITE DURING ALL DRILLING OPERATIONS. This permit is valid for 90 days from date of issue.

Form 0123 Rev. 4/95

DCN# TUR060

Fax #: 919-831-8136



STATE OF FLORIDA PERMIT APPLICATION TO CONSTRUCT, REPAIR, MODIFY, OR ABANDON A WELL

- Southwest
Northwest
St. Johns River
South Florida
Suwannee River

THIS FORM MUST BE FILLED OUT COMPLETELY.

The water well contractor is responsible for completing this form and forwarding the permit to the appropriate delegated county where applicable.

CHECK BOX FOR APPROPRIATE DISTRICT. ADDRESS ON BACK OF PERMIT FORM.

Permit No. 13-69-2241
Florida Unique I.D. 30-7024-01-0010
Permit Stipulations Required (See attached)
62-624 well
CUP/WUP Application No.

1. Florida Power and Light Company, Attn: Mr. Ed Paula 9700 SW 344 Street Florida City 33034 305-246-6407

Owner, Legal Name of Entity & Corporation Address City Zip Telephone Number

2. Turkey Point Nuclear Generating Station - coordinates of proposed wells attached 8760 SW 344 St Homestead FL 33035

Well Location - Address, Road Name or Number, City

3. MACTEC Engineering and Consulting, Inc. - Phillip K. Pitts FL # 11035 404-873-4761

Well Drilling Contractor License No. Telephone No.

396 Plasters Avenue Address

Atlanta Georgia 30324 City State Zip

4. SW 1/4 of NW 1/4 of Section 34 (Indicate Well on Chart)

5. Township 57S Range 40E

6. Miami-Dade N/A N/A N/A N/A County Subdivision Name Lot Block Unit SW SE

7. Number of proposed wells 1 Check the use of well: Domestic Monitor (type) Observation well

8. Application for: X New Construction Repair/Modify Abandonment

Estimated: Well Depth 26 ft Casing Depth 15 ft Screen Interval from 15 to 25

10. If applicable: Proposed From 13 to 25 Seal Material 10/20 silica sand

11. Telescope Casing or Liner X (check one) Diameter 2"

12. Method of Construction: X Rotary Cable Tool Combination

13. Indicate total No. of wells on site 0 List number of unused wells on site 0

14. Is this well or any other well or water withdrawal on the owner's contiguous property covered under a Consumptive Water Use Permit (CUP/WUP) or CUP/WUP Application? X No Yes

15. I hereby certify that I will comply with the applicable rules of Title 40, Florida Administrative Code, and that a water use permit or artificial recharge permit, if needed, has been or will be obtained prior to commencement of well construction.

I certify that I am the owner of the property, that the information provided is accurate, and that I am aware of my responsibilities under Chapter 379, Florida Statutes, to maintain or properly abandon this well, or, I certify that I am the agent for the owner, and the information provided is accurate, and that I have informed the owner of his responsibilities as stated above.

Signature of Contractor License No. 11035 Owner's or Agent's Signature Date 2/19/08

Approval Granted By: ASTRID EDWARDS Issue Date: 2-19-08 Hydrologist Approval

Owner Number: Fee Received: \$ 50 Receipt No: I080215406 Check No.: 524534

THIS PERMIT NOT VALID UNTIL PROPERLY SIGNED BY AN AUTHORIZED OFFICER OR REPRESENTATIVE OF THE WMD. IT SHALL BE AVAILABLE AT THE WELL SITE DURING ALL DRILLING OPERATIONS. This permit is valid for 90 days from date of issue.

Form 0128 Rev. 4/95

13-WD-33815 I080215406

DCN# TUR060

Volume 4, Rev 2 - 10/6/2008 Page 189 of 537 DCN# TUR512



STATE OF FLORIDA PERMIT APPLICATION TO CONSTRUCT, REPAIR, MODIFY, OR ABANDON A WELL

- Southwest
Northwest
St. Johns River
South Florida
Suwannee River

THIS FORM MUST BE FILLED OUT COMPLETELY. The water well contractor is responsible for completing this form and forwarding the permit to the appropriate delegated county where applicable.

CHECK BOX FOR APPROPRIATE DISTRICT. ADDRESS ON BACK OF PERMIT FORM.

Permit No. 13-69-2742
Florida Unique I.D.
Permit Stipulations Required (See attached)
62-624 well
CUP/WUP Application No.

Print all data three times in order that address is visible through envelope window

1. Florida Power and Light Company, Attn: Mr. Ed Paula 9700 SW 344 Street Florida City 33034 305-246-6407
Owner, Legal Name of Entity if Corporation Address City Zip Telephone Number

2. Turkey Point Nuclear Generating Station - coordinates of proposed wells attached
Well Location - Address, Road Name or Number, City

3. MACTEC Engineering and Consulting, Inc. - Phillip K. Pitts P.E. # 11035 404-873-4761
Well Drilling Contractor License No. Telephone No.

396 Plasters Avenue Address
Atlanta Georgia 30324 City State Zip
4. NW 1/4 of NW 1/4 of Section 34
5. Township 57S Range 40E

6. Miami-Dade N/A N/A N/A N/A
County Subdivision Name Lot Block Unit SW SE

7. Number of proposed wells 1 Check the use of well: (See back of permit for additional choices) Domestic Monitor (type) Observation well
Irrigation (type) Public Water Supply (type) List Other

8. Application for: X New Construction Repair/Modify Abandonment
Estimated: Wall Depth 101 ft Casing Depth 90 ft
Casing Material: Blk-Steel / Gal / PVC Casing Diameter 2"

9. Estimated: Wall Depth 101 ft Casing Depth 90 ft
Casing Material: Blk-Steel / Gal / PVC Casing Diameter 2"

10. If applicable: Proposed From 88 to 100 Seal Material 10/20 silica sand
Grouting Interval From 85 to 85 Seal Material Bentonite
From 0 to 83 Seal Material Portland/bentonite slurry


11. Telescope Casing or Liner X (check one) Diameter 2"
Blk-Steel / Galvanized / PVC PVC Other (specify):

12. Method of Construction: X Rotary Cable Tool Combination
X Auger Other (specify):

13. Indicate total No. of wells on site 0 List number of unused wells on site 0

14. Is this well or any other well or water withdrawal on the owner's contiguous property covered under a Consumptive Water Use Permit (CUP/WUP) or CUP/WUP Application? X No Yes
District well I.D. No. N/A
Latitude N/A Longitude N/A
Data obtained from GPS or map or survey (map datum NAD 27 NAD 83)

15. I hereby certify that I will comply with the applicable rules of Title 60, Florida Administrative Code... I certify that I am the owner of the property... Signature of Contractor License No. 1035 Signature of Wells Signatory Date 2/19/08



APPROVED
Permit No. 13-69-2742
Miami-Dade County Health Department

Approval Granted By: ASTRID BOWARDS Issue Date: 2-19-08 Hydrologist Approval:
Owner Number: Fee Received: \$ 50 Receipt No.: T020215446 Check No.: 524534

THIS PERMIT NOT VALID UNTIL PROPERLY SIGNED BY AN AUTHORIZED OFFICER OR REPRESENTATIVE OF THE WMD. IT SHALL BE AVAILABLE AT THE WELL SITE DURING ALL DRILLING OPERATIONS. This permit is valid for 90 days from date of issue.



STATE OF FLORIDA PERMIT APPLICATION TO CONSTRUCT, REPAIR, MODIFY, OR ABANDON A WELL

- Southwest
- Northwest
- St. Johns River
- South Florida
- Suwannee River

THIS FORM MUST BE FILLED OUT COMPLETELY.
 The water well contractor is responsible for completing this form and forwarding the permit to the appropriate delegated county where applicable.

CHECK BOX FOR APPROPRIATE DISTRICT. ADDRESS ON BACK OF PERMIT FORM.

Permit No. 1269-2744
 Florida Unique ID. _____
 Permit Stipulations Required (See attached)
 02-524 well
 CUP/WUP Application No. _____

Fold at this line to enter that address in visible through envelope window

1. **Florida Power and Light Company, Attn: Mr. Ed Paula** 9700 SW 344 Street Florida City 33034 305-246-6407
 Owner, Legal Name of Entity if Corporation Address City Zip Telephone Number

2. **Turkey Point Nuclear Generating Station - coordinates of proposed wells attached**
 Well Location - Address, Road Name or Number, City

3. **MACTEC Engineering and Consulting, Inc. - Phillip K. Pitts FL # 11035** 404-873-4761
 Well Drilling Contractor License No. Telephone No.

396 Plasters Avenue
 Address

4. NW 1/4 of NW 1/4 of Section 34
 (smaller) (larger) (indicate Well on Chart)

Atlanta Georgia 30324
 City State Zip

5. Township 57S Range 40E

6. Miami-Dade N/A N/A N/A N/A
 County Subdivision Name Lot Block Unit

NW	NE
X	
SW	SE

7. Number of proposed wells 1 Check the use of well: (See back of permit for additional choices) Domestic Monitor (type) Observation well
 Irrigation (type) Public Water Supply (type) List Other: _____
 (See Back) (See Back)

Distance from septic system N/A ft. Description of facility Ind. wastewater discharge area Estimated start of construction date 2/19/08


8. Application for: New Construction Repair/Modify Abandonment
 (Reason for Abandonment)

9. Estimated: Well Depth 26* ft Casing Depth 15 ft Screen Interval from 15 to 25
 Casing Material: Blk-Steel / Gal / PVC rvc Casing Diameter 2" Seal Material see below

10. If applicable: Proposed From 13 to 25 Seal Material 10/20 silica sand
 Grouting Interval From 10 to 13 Seal Material Bentonite
 From 0 to 10 Seal Material Portland/tematic slurry

11. Telescope Casing _____ or Liner (check one) Diameter 2"
 Blk-Steel / Galvanized / PVC/PVC Other (specify): _____

APPROVED
 Permit no. 1269-2744
 Date 2-19-08
 Miami-Dade County
 Health Department



12. Method of Construction: Rotary Cable Tool Combination
 Auger Other (specify): _____

13. Indicate total No. of wells on site 0 List number of unused wells on site 0

14. Is this well or any other well or water withdrawal on the owner's contiguous property covered under a Consumptive Water Use Permit (CUP/WUP) or CUP/WUP Application? No Yes
 (If yes, complete the following) CUP/WUP No. N/A
 District well I.D. No. N/A
 Latitude N/A Longitude N/A
 Data obtained from GPS _____ or map _____ or survey _____ (map datum NAD 83 NAD 83)

15. I hereby certify that I will comply with the applicable rules of Title 40, Florida Administrative Code, and that a water use permit or discharge permit, if needed, has been or will be obtained prior to commencement of well construction. I further certify that all information provided on this application is accurate and that I will obtain necessary approvals from other federal, state, or local governments. I agree to provide a well completion report to the District within 30 days after drilling operations are completed.

I certify that I am the owner of the property, that the information provided is accurate, and that I am aware of my responsibilities under Chapter 62A, Florida Statutes, to maintain or properly abandon this well; or, I certify that I am the agent for the owner, that the information provided is accurate, and that I have informed the owner of his or her responsibilities as stated above. I am authorized to describe to the WMD or a representative access to the well site.

Signature of Contractor [Signature] License No. 11035 Owner's or Agent's Signature [Signature] Date 2/19/08

DO NOT WRITE BELOW THIS LINE - FOR OFFICIAL USE ONLY

Approval Granted By: STEP EDWARDS Issue Date: 2-19-08 Hydrologist Approval _____
 Owner Number: _____ Fee Received: \$ 50 Receipt No. T620215406 Check No.: 524534

THIS PERMIT NOT VALID UNTIL PROPERLY SIGNED BY AN AUTHORIZED OFFICER OR REPRESENTATIVE OF THE WMD. IT SHALL BE AVAILABLE AT THE WELL SITE DURING ALL DRILLING OPERATIONS. *This permit is valid for 90 days from date of issue.*

Form 0123 Rev. 4/85



STATE OF FLORIDA PERMIT APPLICATION TO CONSTRUCT, REPAIR, MODIFY, OR ABANDON A WELL

- Southwest
Northwest
St. Johns River
South Florida
Suwannee River

THIS FORM MUST BE FILLED OUT COMPLETELY. The water well contractor is responsible for completing this form and forwarding the permit to the appropriate delegated county where applicable.

CHECK BOX FOR APPROPRIATE DISTRICT. ADDRESS ON BACK OF PERMIT FORM.

Permit No. 1259-2046
Florida Unique I.D.
Permit Stipulations Required (See attached)
62-624 well
CUP/WUP Application No.

1. Florida Power and Light Company, Attn: Mr. Ed Paula 9700 SW 344 Street Florida City 33034 305-246-6407
Owner, Legal Name of Entity if Corporation Address City Zip Telephone Number

2. Turkey Point Nuclear Generating Station - coordinates of proposed wells attached
Well Location - Address, Road Name or Number, City

3. MACTEC Engineering and Consulting, Inc. - Phillip K. Pitts FL # 11035 404-873-4761
Well Drilling Contractor License No. Telephone No.

396 Plasters Avenue Address
Atlanta Georgia 30324 City State Zip
4. SE 1/4 of SE 1/4 of Section 34 (Indicate Well on Chart)
5. Township 57S Range 40E

6. Miami-Dade N/A N/A N/A N/A
County Subdivision Name Lot Block Unit

7. Number of proposed wells 1 Check the use of well: (See back of permit for additional choices) Domestic Monitor (type) Observation well
Irrigation (type) Public Water Supply (type) List Other
Distance from septic system N/A ft. Description of facility Estimated start of construction date 2/19/08

8. Application for: X New Construction Repair/Modify Abandonment
(Reason for Abandonment)

8. Estimated: Well Depth 101* ft Casing Depth 90 ft
Casing Material: Blk-Steel / Gal / PVC PVC Casing Diameter 2"
Screen Interval from 90 to 100
Seal Material see below


10. If applicable: Proposed From 88 to 100 Seal Material 10/20 silica sand
Grouting Interval From 85 to 85 Seal Material Bentonite
From 0 to 83 Seal Material Portland/bentonite slurry
*Well will be installed with a one-foot screen

11. Telescope Casing or Liner X (check one) Diameter 2"
Blk-Steel / Galvanized / PVC/PVC Other (specify):

12. Method of Construction: X Rotary Cable Tool Combination
X Auger Other (specify):

13. Indicate total No. of wells on site 0 List number of unused wells on site 0

14. Is this well or any other well or water withdrawal on the owner's contiguous property covered under a Consumptive Water Use Permit (CUP/WUP) or CUP/WUP Application? X No Yes
(If yes, complete the following) CUP/WUP No. N/A
District well I.D. No. N/A
Latitude N/A Longitude N/A
Data obtained from GPS or map or survey (map datum NAD 87 NAD 83)



15. I hereby certify that I will comply with the applicable rules of Title 40, Florida Administrative Code, and that a water use permit or artificial recharge permit, if needed, has been or will be obtained prior to commencement of well construction. I further certify that all information provided on this application is accurate and that I will obtain necessary approval from other federal, state, or local governments, if applicable, to provide a well completion report to the District within 30 days after drilling or test completion, whichever occurs first.
Signature of Contractor License No. 11035
I certify that I am the owner of the property, that the information provided is accurate, and that I am aware of my responsibilities under Chapter 672, Florida Statutes, to maintain or properly abandon this well; or, I certify that I am the agent for the owner, that the information provided is accurate, and that I have informed the owner of his responsibilities as stated above. Owner (or agent) Signature Date 2/19/08

DO NOT WRITE BELOW THIS LINE - FOR OFFICIAL USE ONLY

Approval Granted By: APTED EDWARDS Issue Date: 2-19-08 Hydrologist Approval
Owner Number: Fee Received: \$ 96 Receipt No.: TD2021546 Check No.: 524534

THIS PERMIT NOT VALID UNTIL PROPERLY SIGNED BY AN AUTHORIZED OFFICER OR REPRESENTATIVE OF THE WMD. IT SHALL BE AVAILABLE AT THE WELL SITE DURING ALL DRILLING OPERATIONS. This permit is valid for 90 days from date of issue.



STATE OF FLORIDA PERMIT APPLICATION TO CONSTRUCT, REPAIR, MODIFY, OR ABANDON A WELL

- Southwest
Northwest
St. Johns River
South Florida
Suwannee River

THIS FORM MUST BE FILLED OUT COMPLETELY. The water well contractor is responsible for completing this form and forwarding the permit to the appropriate delegated county where applicable.

CHECK BOX FOR APPROPRIATE DISTRICT. ADDRESS ON BACK OF PERMIT FORM.

Permit No. 1459-2245
Florida Unique I.D.
Permit Stipulations Required (See attached)
82-524 well
CUP/WUP Application No.

1. Florida Power and Light Company, Attn: Mr. Ed Paula 9700 SW 344 Street Florida City 33034 305-246-6407
2. Turkey Point Nuclear Generating Station - coordinates of proposed wells attached
3. MACTEC Engineering and Consulting, Inc. - Phillip K. Pitts FL # 11035 404-873-4761

Field of this form is under that address is visible through average vehicle

7. Number of proposed wells 1 Check the use of well: (See back of permit for additional choices) Domestic Monitor (type) Observation well
Irrigation (type) Public Water Supply (type) List Other
Distance from septic system N/A Description of facility Estimated start of construction date 2/19/08

8. Application for: X New Construction Repair/Modify Abandonment
9. Estimated: Well Depth 26 ft Casing Depth 15 ft
Casing Material: Blk-Steel / Gal / PVC rvc Casing Diameter 2"

10. If applicable: Proposed From 13' to 25' Seal Material 10/20 silica sand
Grouting Interval From 2" to 13' Seal Material Bentonite
From 0' to 10' Seal Material Portland/bentonite slurry

11. Telescope Casing or Liner (check one) Diameter 2"
Blk-Steel / Galvanized / PVGPVC Other (specify):


12. Method of Construction: X Rotary Cable Tool Combination
X Auger Other (specify):

13. Indicate total No. of wells on site 0 List number of unused wells on site 0

14. Is this well or any other well or water withdrawal on the owner's contiguous property covered under a Consumptive Water Use Permit (CUP/WUP) or CUP/WUP Application? X No Yes
District well I.D. No. N/A
Latitude N/A Longitude N/A
Data obtained from GPS or map or survey (map datum NAD 27 NAD 83)

15. I hereby certify that I will comply with the applicable rules of Title 40, Florida Administrative Code, and that a water use permit or approval to discharge... I certify that I am the owner of the property, that the information provided is accurate, and that I am aware of my responsibilities under Chapter 373, Florida Statutes...

APPROVED
Permit No. 1459-2245
Date: 2-19-08
Depts: Miami-Dade County Health Department



Approval Granted By: ASTRO EDWARDS Issue Date: 2-19-08 Hydrologist Approval
Owner Number: Fee Received: \$50 Receipt No. 168021546 Check No.: 524534

THIS PERMIT NOT VALID UNTIL PROPERLY SIGNED BY AN AUTHORIZED OFFICER OR REPRESENTATIVE OF THE WMD. IT SHALL BE AVAILABLE AT THE WELL SITE DURING ALL DRILLING OPERATIONS. This permit is valid for 90 days from date of issue.

To: TOM MU DANIEL

FAX: 305-826-1799

Folio #: 30-7034004-0010



STATE OF FLORIDA PERMIT APPLICATION TO CONSTRUCT, REPAIR, MODIFY, OR ABANDON A WELL

- Southwest
- Northwest
- St. Johns River
- South Florida
- Suwannee River

THIS FORM MUST BE FILLED OUT COMPLETELY.

The well contractor is responsible for completing this form and forwarding the permit to the appropriate delegated county where applicable.

CHECK BOX FOR APPROPRIATE DISTRICT. ADDRESS ON BACK OF PERMIT FORM.

Permit No. 10-59-2692
 Florida Unique I.D. _____
 Permit Stipulations Required (See attached) _____
 B2-524 well
 SWP Application No. _____
 APPROVED FOR CONSTRUCTION BY WMD

Read all rules in order that address to be visible through envelope window.

1. Florida Power & Light Co. 9700 SW 34th St Florida City 33034 305 246 6467
 Owner, Legal Name of Entity & Corporation Address City Zip Telephone Number

2. Turkey Point Nuclear Generating Station 9760 SW 34th Street Florida City FL 33035
 Well Location - Address, Road Name or Number, City

3. MACTEC Engineering & Consulting Inc- Philo PHS FL # 11035 404 673 4761
 Well Drilling Contractor License No. Telephone No.

396 Pleasant Ave NE 1/4 of SE 1/4 of Section 33
 Address (Indicate Well on Chart)

Atlanta GA 30324 7 S 40 E
 City State Zip Township Range

6. Miami Dade N/A N/A N/A N/A
 County Subdivision Name Lot Block Unit

7. Number of proposed wells 1 Check the use of well: (See back of permit for additional choices) Domestic Monitor (type) Observation Well
 Irrigation (type) Public Water Supply (type) List Other _____
 (See Back) (See Back)

Distance from septic system N/A ft. Description of facility _____ Estimated start of construction date _____

8. Application for: New Construction Repair/Modify Abandonment (Reason for Abandonment) _____ Date _____

9. Estimated: Well Depth 130' + 1' Sump Casing Depth 120' Screen Interval from _____
 Casing Material: Blk-Steel / Gal / PVC Casing Diameter 2" Steel Material _____

10. If applicable: Proposed From 120 to 131 Seal Material 10/20 Silica Sand
 Grouting Interval From 117 to 120 Seal Material Bentonite
 From 0 to 117 Seal Material Portland/Bentonite Slurry

11. Telescope Casing _____ or Liner _____ (check one) Diameter _____
 Blk-Steel / Galvanized PVC Other (specify): _____

12. Method of Construction: Rotary Cable Tool Combination
 Auger Other (specify): _____


13. Indicate total No. of wells on site 20. List number of unused wells on site 0

14. Is this well or any other well or water withdrawal on the owner's contiguous property covered under a Consumptive Water Use Permit (CUP/WUP) or CUP/WUP Application? No Yes
 (If yes, complete the following) CUP/WUP No. N/A
 District well I.D. No. N/A
 Latitude N/A Longitude N/A
 Data obtained from GPS _____ or map _____ or survey _____ (map datum NAD 27 _____ NAD 83 _____)

15. I hereby certify that I will comply with the applicable rules of Title 61, Florida Administrative Code, and that a water use permit or artificial recharge permit, if needed, has been or will be obtained prior to commencement of well construction. I hereby certify that all information provided on this application is true and that I am doing necessary approval from other federal, state, or local government. If a permit is required to construct a well, I agree to provide a well completion report to the District within 30 days after drilling or the permit expiration, whichever is later.

I certify that I am the owner of the property, that the information provided is accurate, and that I am aware of my responsibilities under Chapter 370, Florida Statutes, to maintain or properly abandon this well, or, I certify that I am the agent for the owner; that the information provided is accurate, and that I have informed the owner of the responsibilities as stated above. Owner or agent for the owner of the WMD or a representative access to the well site.

[Signature] 11035 [Signature] 5/20/08
 Signature of Contractor License No. Owner's Signature Date



Approval Granted By: RYAN DOWDAYS (Issue Date: 5-20-08) Hydrologist Approval: _____
 Owner Number: _____ Fee Received: \$ 60 Receipt No.: 1680520430 Check No.: _____

THIS PERMIT NOT VALID UNTIL PROPERLY SIGNED BY AN AUTHORIZED OFFICER OR REPRESENTATIVE OF THE WMD. IT SHALL BE AVAILABLE AT THE WELL SITE DURING ALL DRILLING OPERATIONS. This permit is valid for 90 days from date of issue.

Form 0123 Rev. 4/95
13-WA-34019 I080520430



STATE OF FLORIDA PERMIT APPLICATION TO CONSTRUCT, REPAIR, MODIFY, OR ABANDON A WELL

- Southwest
Northwest
St. Johns River
South Florida
Suwannee River

THIS FORM MUST BE FILLED OUT COMPLETELY. The water well contractor is responsible for completing this form and forwarding the permit to the appropriate delegated county where applicable.


CHECK BOX FOR APPROPRIATE DISTRICT. ADDRESS ON BACK OF PERMIT FORM.

Permit No. 13-59-2248
Florida Unique I.D.
Permit Stipulations Required (See attached)
62-824 well
CUPWUP Application No.

Find all state forms in order that address this website through envelope window

Main permit application form with sections 1-15, including owner information, well location, contractor details, and technical specifications.

APPROVED stamp with date 2-19-08 and signature of Miami-Dade County Health Department.



Approval Granted By: AGUED EDWARDS, Issue Date: 2/19/08, Hydrologist Approval, Owner Number, Fee Received: \$50, Receipt No., Check No.: 524534

THIS PERMIT NOT VALID UNTIL PROPERLY SIGNED BY AN AUTHORIZED OFFICER OR REPRESENTATIVE OF THE WMD. IT SHALL BE AVAILABLE AT THE WELL SITE DURING ALL DRILLING OPERATIONS. This permit is valid for 90 days from date of issue.



STATE OF FLORIDA PERMIT APPLICATION TO CONSTRUCT, REPAIR, MODIFY, OR ABANDON A WELL

- Southwest
Northwest
St. Johns River
South Florida
Suwannee River

THIS FORM MUST BE FILLED OUT COMPLETELY.

The water well contractor is responsible for completing this form and forwarding the permit to the appropriate delegated county where applicable.

CHECK BOX FOR APPROPRIATE DISTRICT. ADDRESS ON BACK OF PERMIT FORM.

Permit No. 1259-2247
Florida Unique I.D.
Permit Stipulations Required (See attached)
62-524 well
CUP/WUP Application No.

1. Florida Power and Light Company, Attn: Mr. Ed Paula 9700 SW 344 Street Florida City 33034 305-246-6407
Owner, Legal Name of Entity if Corporation Address City Zip Telephone Number

2. Turkey Point Nuclear Generating Station - coordinates of proposed wells attached
Well Location - Address, Road Name or Number, City

3. MACTEC Engineering and Consulting, Inc. - Phillip K. Pitts FL # 11035 404-873-4761
Well Drilling Contractor License No. Telephone No.

396 Plasters Avenue Address
Atlanta Georgia 30324 City State Zip
4. NE 1/4 of SE 1/4 of Section 33
5. Township 57S Range 40E

6. Miami-Dade N/A N/A N/A N/A
County Subdivision Name Lot Block Unit SW SE

7. Number of proposed wells 1 Chuck the use of well: Domestic Monitor (type) Observation well
Irrigation (type) Public Water Supply (type) List Other
Distance from septic system N/A ft. Description of facility Estimated start of construction date 2/19/08

8. Application for: X New Construction Repair/Modify Abandonment
Estimated: Well Depth 26* ft Casing Depth 15 ft Screen interval from 15 to 25
Casing Material: Blk-Steel / Gal / PVC rvc Casing Diameter 2"

10. If applicable: Proposed From 13 to 26 Seal Material 10/20 silica sand
Grouting Interval From 10 to 13 Seal Material Bentonite
From 8 to 10 Seal Material Portland/bentonite slurry

11. Telescope Casing or Liner X (check one) Diameter 2"
Blk-Steel / Galvanized / PVC/PVC Other (specify):


12. Method of Construction: X Rotary Cable Tool Combination
X Auger Other (specify):

13. Indicate total No. of wells on site 0 List number of unused wells on site 0

14. Is this well or any other well or water with drawal on the owner's contiguous property covered under a Consumptive Water Use Permit (CUP/WUP) or CUP/WUP Application? X No Yes
District well I.D. No. N/A
Latitude N/A Longitude N/A
Data obtained from GPS or map or survey (map datum NAD 87 NAD 83)

15. I hereby certify that I will comply with the applicable rules of Title 40, Florida Administrative Code... I certify that I am the owner of the property, that the information provided is accurate, and that I am aware of my responsibilities under Chapter 373, Florida Statutes...

APPROVED
Permit no. 1259-2247
Date: 2-19-08
Miami-Dade County Health Department



GENERAL NOTE: DO NOT WRITE BELOW THIS LINE - FOR OFFICIAL USE ONLY

Approval Granted By: ASTRID EDWARDS Issue Date: 2-19-08 Hydrologist Approval
Owner Number: Fee Received: \$ 50 Receipt No.: 108021506 Check No.: 528534

THIS PERMIT NOT VALID UNTIL PROPERLY SIGNED BY AN AUTHORIZED OFFICER OR REPRESENTATIVE OF THE WMD. IT SHALL BE AVAILABLE AT THE WELL SITE DURING ALL DRILLING OPERATIONS. This permit is valid for 90 days from date of issue.



STATE OF FLORIDA PERMIT APPLICATION TO CONSTRUCT, REPAIR, MODIFY, OR ABANDON A WELL

- Southwest
Northwest
St. Johns River
South Florida
Suwannee River

THIS FORM MUST BE FILLED OUT COMPLETELY.


The water well contractor is responsible for completing the form and forwarding the permit to the appropriate delegated county where applicable.

CHECK BOX FOR A PROPRATE DISTRICT, ADDRESS ON BACK OF PERMIT FORM.

Permit No. 1059-2260
Florida Unique I.D.
Permit Stipulations Required (See attached)
62-524 well
CUP/WUP Application No.

Main permit application form with sections 1-15, including owner information, well location, contractor details, and technical specifications.

APPROVED
Permit no. 1059-2260
Date: 2-19-08
Miami-Dade County Health Department



Approval section with signatures of contractor and owner, and hydrologist approval.

THIS PERMIT NOT VALID UNTIL PROPERLY SIGNED BY AN AUTHORIZED OFFICER OR REPRESENTATIVE OF THE WMD. IT SHALL BE AVAILABLE AT THE WELL SITE DURING ALL DRILLING OPERATIONS. Form 0123 Rev. 4/95



STATE OF FLORIDA PERMIT APPLICATION TO CONSTRUCT, REPAIR, MODIFY, OR ABANDON A WELL

- Southwest
- Northwest
- St. Johns River
- South Florida
- Suwannee River

THIS FORM MUST BE FILLED OUT COMPLETELY.
 The well well contractor is responsible for completing this form and forwarding the permit to the appropriate delegated county where applicable.

CHECK BOX FOR APPROPRIATE DISTRICT. ADDRESS ON BACK OF PERMIT FORM.

Permit No. 13-59-2249
 Florida Unique I.D. _____
 Permit Stipulations Required (See attached)
 02-524 well
 CUPW Application No. _____

Fold at this line in order that address is visible through envelope window

1. Florida Power and Light Company, Attn: Mr. Ed Paula 9700 SW 344 Street Florida City 33034 305-246-6407
 Owner, Legal Name of Entity if Corporation Address City Zip Telephone Number

2. Turkey Point Nuclear Generating Station - coordinates of proposed wells attached
 Well Location - Address, Road Name or Number, City

3. MACTEC Engineering and Consulting, Inc. - Phillip K. Pitts FL # 11035 404-873-4761
 Well Drilling Contractor License No. Telephone No.

396 Plasters Avenue
 Address
 Atlanta Georgia 30324
 City State Zip

4. SE 1/4 of NE 1/4 of Section 33
(smallest) (largest)
 (Indicate Well on Chart)

5. Township 57S Range 40E

NW	NE
	X
SW	SE

6. Miami-Dade N/A N/A N/A N/A
 County Subdivision Name Lot Block Unit SW SE

7. Number of proposed wells 1 Check the use of well: (See back of permit for additional choices) Domestic Monitor (type) Observation well
 Irrigation (type) Public Water Supply (type) List Other _____
(See Back) (See Back)
 Distance from septic system N/A ft. Description of facility Ind. wastewater discharge area Estimated start of construction date 2/19/08

8. Application for: New Construction Repair/Modify Abandonment
(Reason for Abandonment)

9. Estimated: Well Depth 26± ft Casing Depth 15 ft Screen Interval from 15 to 25
 Casing Material: Blk-Steel / Gal / PVC rvc Casing Diameter 2" Seal Material see below
*Well will be installed with a one-foot slump

10. If applicable: Proposed From 13 to 25 Seal Material 10/20 silica sand
 Grouting Interval From 10 to 13 Seal Material Bentonite
 From 0 to 10 Seal Material Portland/bentonite slurry

11. Telescope Casing _____ or L liner (check one) Diameter 2"
 Blk-Steel / Galvanized / PVC PVC Other (specify): _____

12. Method of Construction: Rotary Cable Tool Combination
 Auger Other (specify): _____

12. Indicate total No. of wells on site 0 List number of unused wells on site 0

14. Is this well or any other well or water withdrawal on the owner's contiguous property covered under a Consumptive Water Use Permit (CJW/WUP) or CUP/WUP Application? No Yes
(If yes, complete the following) CUP/WUP No. N/A
 District well I.D. No. N/A
 Latitude N/A Longitude N/A
 Data obtained from GPS _____ or map _____ or survey _____ (map datum NAD 27 NAD 83)

North

OW-72IU

↑

see attached drawings for proposed well locations

South

15. I hereby certify that I will comply with the applicable rules of Title 60, Florida Administrative Code, and that a water use permit or additional required permit, if no deed, has been or will be obtained prior to commencement of well construction. I further certify that all information provided on this application is accurate and that I will obtain necessary approval from other federal, state, or local governmental agencies. I agree to provide a well completion report to the District within 30 days after drilling of the well is complete, whichever occurs first.

I certify that I am the owner of the property, that the information provided is accurate, and that I am aware of my responsibilities under Chapter 373, Florida Statutes, to maintain or properly abandon this well, or, I certify that I am the agent for the owner, that the information provided is accurate, and that I have informed the owner of his responsibilities as stated above. Owner consents to personnel of the WMD or a representative access to the well site.

Signature of Contractor [Signature] License No. 11035 Owner's or Agent's Signature [Signature] Date 2/19/08

APPROVED
 Permit no. 13-59-2249
 Date: 2-19-08
 Miami-Dade County Health Department

Approval Granted By: ASTRID EDWARDS Issue Date: 2-19-08 Hydrologist Approval _____
 Owner Number: _____ Fee Received: \$ 50 Receipt No.: T08025406 Check No.: 524534
Enter numerical month, day and full, four-digit year.

THIS PERMIT NOT VALID UNTIL PROPERLY SIGNED BY AN AUTHORIZED OFFICER OR REPRESENTATIVE OF THE WMD. IT SHALL BE AVAILABLE AT THE WELL SITE DURING ALL DRILLING OPERATIONS. This permit is valid for 90 days from date of issue.



STATE OF FLORIDA PERMIT APPLICATION TO CONSTRUCT, REPAIR, MODIFY, OR ABANDON A WELL

- Southwest
Northwest
St. Johns River
South Florida
Suwannee River

THIS FORM MUST BE FILLED OUT COMPLETELY. The water well contractor is responsible for completing this form and forwarding the permit to the appropriate delegated county where applicable.

CHECK BOX FOR APPROPRIATE DISTRICT. ADDRESS ON BACK OF PERMIT FORM.

Permit No. 13-59-2252
Florida Unique I.D.
Permit Stipulations Required (See attached)
62-524 well
GUP Application No.

1. Florida Power and Light Company, Attn: Mr. Ed Paula 9700 SW 344 Street Florida City 33034 305-246-6407
Owner, Legal Name of Entity if Corporation Address City Zip Telephone Number

2. Turkey Point Nuclear Generating Station - coordinates of proposed wells attached
Well Location - Address, Road Name or Number, City

3. MACTEC Engineering and Consulting, Inc. - Phillip K. Pitts FL # 11035 404-873-4761
Well Drilling Contractor License No. Telephone No.

396 Plasters Avenue Address 4. SW 1/4 of SE 1/4 of Section 33 (Indicate Well on Chart)

Atlanta Georgia 30324 City State Zip 5. Township 57S Range 40E

6. Miami-Dade N/A N/A N/A N/A
County Subdivision Name Lot Block Unit SW SE

7. Number of proposed wells: 1 Check the use of well: (See back of permit for additional choices) Domestic Monitor (type) Observation well

Distance from septic system: N/A ft. Description of facility: Estimated start of construction date: 2/19/08

8. Application for: X New Construction Repair/Modify Abandonment

9. Estimated: Well Depth 101 ft Casing Depth 90 ft
Casing Material: Blk-Steel / Gal / PVC PVC Casing Diameter 2"

10. If applicable: Proposed From 38 to 100 Seal Material 10/20 silica sand
Grouting Interval From 23 to 85 Seal Material Bentonite

11. Telescope Casing or Liner X (check one) Diameter 2"
Blk-Steel / Galvanized / PVC PVC Other (specify):

12. Method of Construction: X Rotary Cable Tool Combination
X Auger Other (specify):

13. Indicate total No. of wells on site 0 List number of unused wells on site 0

14. Is this well or any other well or water withdrawal on the owner's contiguous property covered under a Consumptive Water Use Permit (CUP/WUP) or CUP/WUP Application? X No Yes

District well I.D. No. N/A

Latitude N/A Longitude N/A

Data obtained from GPS or map or survey (map datum NAD 27 NAD 83)

15. I hereby certify that I will comply with the applicable rules of Title 40, Florida Administrative Code, and that a water use permit or a flow exchange permit, if needed, has been or will be obtained prior to commencement of well construction. I further certify that all information provided on this application is accurate and true and that I will obtain necessary approval from other federal, state, or local governmental agencies, if applicable, to provide a well completion report to the District within 30 days after drilling the well to final completion, whichever occurs first.

I certify that I am the Owner of the property; that the information provided is accurate, and that I am aware of my responsibilities under Chapter 379, Florida Statutes, to maintain or properly abandon the well; or, I certify that I am the agent for the owner, that the information provided is accurate, and that I have informed the owner of his responsibilities as stated above. Owner consents to the removal of the permit or a representative society to the well site.

Signatures of Contractor License No. 11035 Owners or Agent's Signature Date 2/15/08

APPROVED stamp with date 2-19-08 and signature. Includes a well location diagram with 'OW-735L' label and a north arrow. Text: 'Draw a map of well location and indicate well site with... Identify known roads and landmarks; provide distances between... and landmarks.'

Approval Granted By: AGUED EDWARDS Issue Date: 2/19/08 Hydrologist Approval

Owner Number: Fee Received: \$ 60 Receipt No. 103022546 Check No. 524534

THIS PERMIT NOT VALID UNTIL PROPERLY SIGNED BY AN AUTHORIZED OFFICER OR REPRESENTATIVE OF THE WMD. IT SHALL BE AVAILABLE AT THE WELL SITE DURING ALL DRILLING OPERATIONS. This permit is valid for 90 days from date of issue.



STATE OF FLORIDA PERMIT APPLICATION TO CONSTRUCT, REPAIR, MODIFY, OR ABANDON A WELL

- Southwest
Northwest
St. Johns River
South Florida
Suwannee River

THIS FORM MUST BE FILLED OUT COMPLETELY. The water well contractor is responsible for completing this form and forwarding the permit to the appropriate delegated county where applicable.

CHECK BOX FOR APPROPRIATE DISTRICT. ADDRESS ON BACK OF PERMIT FORM.

Permit No. 13-59-7251
Florida Unique I.D.
Permit Stipulations Required (See attached)
02-624 well
CUP Application No.

Fill in this area in order that address is visible through envelope window

1. Florida Power and Light Company, Attn: Mr. Ed Paula 9700 SW 344 Street Florida City 33034 305-246-6407
2. Turkey Point Nuclear Generating Station - coordinates of proposed wells attached
3. MACTEC Engineering and Consulting, Inc. - Phillip K. Pitts FL # 11035 404-873-4761
4. SW 1/4 of SE 1/4 of Section 33
5. Township 57S Range 40E

7. Number of proposed wells 1 Check the use of well: Domestic Monitor (type) Observation well
8. Application for: X New Construction Repair/Modify Abandonment
9. Estimated: Well Depth 26* ft Casing Depth 15 ft Screen Interval from 15 to 25
10. If applicable: Proposed From 13 to 25 Seal Material 10/20 silica sand
11. Telescope Casing or Liner X (check one) Diameter 2"

12. Method of Construction: X Rotary Cable Tool Combination
13. Indicate total No. of wells on site 0 List number of unused wells on site 0
14. Is this well or any other well or water withdrawal on the owner's contiguous property covered under a Consumptive Water Use Permit (CUP/WUP) or CUP/WUP Application? X No Yes
15. I hereby certify that I will comply with the applicable rules of Title 40, Florida Administrative Code...

APPROVED
Permit no. 13-59-7251
Date 2-19-08
Miami-Dade County
Date Stamp
Draw a map of well location and indicate well site location in vicinity known roads and landmarks; provide distances between well and landmarks.

15. I hereby certify that I will comply with the applicable rules of Title 40, Florida Administrative Code...
Signature of Contractor 11035
Signature of Applicant

Approval Granted By: ASTRID FERRAZOS Issue Date: 2-19-08 Hydrologist Approval
Owner Number: Fee Received: \$ 50 Receipt No.: 1090215406 Check No.: 524534

THIS PERMIT NOT VALID UNTIL PROPERLY SIGNED BY AN AUTHORIZED OFFICER OR REPRESENTATIVE OF THE WMD. IT SHALL BE AVAILABLE AT THE WELL SITE DURING ALL DRILLING OPERATIONS. This permit is valid for 90 days from date of issue.



STATE OF FLORIDA PERMIT APPLICATION TO CONSTRUCT, REPAIR, MODIFY, OR ABANDON A WELL

- Southwest
Northwest
St. Johns River
South Florida
Suwannee River

THIS FORM MUST BE FILLED OUT COMPLETELY.

The water well contractor is responsible for completing this form and forwarding the permit to the appropriate delegated county where applicable.


CHECK BOX FOR APPROPRIATE DISTRICT. ADDRESS ON BACK OF PERMIT FORM.

Permit No. 19-59-2254
Florida Unique I.D.
Permit Situations Required (See attached)
62-624 well
CUP Application No.

Read all this fine in order that address is visible through embossed window

Main application form with sections 1-15. Includes owner information (Florida Power and Light Company), well location (Turkey Point Nuclear Generating Station), contractor (MACTEC Engineering), well depth (101 ft), and various technical specifications.

APPROVED
Date: 2-19-08
Permit no. 19-59-2254
Miami-Dade County
Health Department



Signature of Contractor: [Signature] License No. 11035

Signature of Owner: [Signature] Date: 2/19/08

Approval Granted By: ASTRID EDWARDS Issue Date: 2/19/08 Hydrologist Approval
Owner Number: Fee Received: \$ 90 Receipt No. 108021406 Check No. 524534

THIS PERMIT NOT VALID UNTIL PROPERLY SIGNED BY AN AUTHORIZED OFFICER OR REPRESENTATIVE OF THE WMD. IT SHALL BE AVAILABLE AT THE WELL SITE DURING ALL DRILLING OPERATIONS. This permit is valid for 90 days from date of issue.



STATE OF FLORIDA PERMIT APPLICATION TO CONSTRUCT, REPAIR, MODIFY, OR ABANDON A WELL

- Southwest
Northwest
St. Johns River
South Florida
Suwannee River

THIS FORM MUST BE FILLED OUT COMPLETELY.

The water well contractor is responsible for completing this form and forwarding the permit to the appropriate designated county where applicable.

CHECK BOX FOR APPROPRIATE DISTRICT. ADDRESS ON BACK OF PERMIT FORM.

Permit No. 19-09-7743
Florida Unique ID.
Permit Stipulations Required (See attached)
62-524 well cup/wup Application No.

1. Florida Power and Light Company, Attn: Mr. Ed Paula 9700 SW 344 Street Florida City 33034 305-246-6407
Owner, Legal Name of Entity if Corporation Address City Zip Telephone Number

2. Turkey Point Nuclear Generating Station - coordinates of proposed wells attached
Well Location - Address, Road Name or Number, City

3. MACTEC Engineering and Consulting, Inc. - Phillip K. Pitts FL # 11035 404-873-4761
Well Drilling Contractor License No. Telephone No.

396 Plasters Avenue Address
Atlanta Georgia 30324 City State Zip
4. NE 1/4 of NE 1/4 of Section 34 (smaller) (bigger) (indicate Well on Chart)
5. Township 57S Range 40E

6. Miami-Dade N/A N/A N/A N/A
County Subdivision Name Lot Block Unit SW SE

7. Number of proposed wells 1 Check the use of well: (See back of permit for additional choices) Domestic Monitor (type) Observation well
Irrigation (type) Public Water Supply (type) List Other
Distance from septic system N/A ft. Description of facility Est. start of construction date 2/19/08

8. Application for: X New Construction Repair/Modify Abandonment
(Reason for Abandonment)

9. Estimated: Well Depth 26 ft Casing Depth 15 ft Screen (interval from 15 to 25)
Casing Material: Blk-Steel / Gal / PVC pvc Casing Diameter 2" Seal Material see below

10. If applicable: Proposed Grouting Interval From 13 to 25 Seal Material 10/20 silica sand
From 10 to 13 Seal Material Bentonite
From 0 to 10 Seal Material Portland/bentonite slurry

11. Telescope Casing or Liner X (check one) Diameter 2"
Blk-Steel / Galvanized / PVC/PVC Other (specify):


12. Method of Construction: X Rotary Cable Tool Combination
X Auger Other (specify):

13. Indicate total No. of wells on site 0 List number of unused wells on site 0

14. Is this well or any other well for water withdrawal on the owner's contiguous property covered under a Consumptive Water Use Permit (CUP/WUP) or CUP/WUP Application? X No Yes
District well I.D. No. N/A
Latitude N/A Longitude N/A
Date obtained from GPS or map or survey (map datum NAD 27 NAD 83)

15. I hereby certify that I will comply with the applicable rules of the 4th Florida Administrative Code, and that a water use permit or artificial recharge permit, if needed, has been or will be obtained prior to commencement of well construction. I further certify that all information provided on this application is accurate and that I will obtain necessary approval from other federal, state, or local governments. I agree to provide a well completion report to the District within 30 days after drilling or any other completion, whichever occurs first.
I certify that I am the owner of the property, that the information provided is accurate, and that I am aware of my responsibilities under Chapter 372, Florida Statutes, to maintain or properly abandon this well or, I certify that I am the agent for the owner, that the information provided is accurate, and that I have informed the owner of his responsibilities as stated above. Owner's signature to personnel of the WMO or a representative access to the well site.

APPROVED
Date Stamp: 2-19-08
Permit No. 19-09-7743
Date: 2-19-08
Miami-Dade County Health Department



DO NOT WRITE BELOW THIS LINE FOR OFFICIAL USE ONLY

Approval Granted By: ARTHUR EDWARDS Issue Date: 2-19-08 Hydrologist Approval

Owner Number: Fee Received: \$ 50 Receipt No. 108021546 Check No.: 524534

THIS PERMIT NOT VALID UNTIL PROPERLY SIGNED BY AN AUTHORIZED OFFICER OR REPRESENTATIVE OF THE WMO. IT SHALL BE AVAILABLE AT THE WELL SITE DURING ALL DRILLING OPERATIONS. This permit is valid for 90 days from date of issue.

Form 0123 Rev. 4/95

Volume 4, Rev 2 - 10/6/2008 Page 202 of 537 DCN# TUR060 DCN# TUR512



STATE OF FLORIDA PERMIT APPLICATION TO CONSTRUCT, REPAIR, MODIFY, OR ABANDON A WELL

- Southwest
Northwest
St. Johns River
South Florida
Suwannee River

THIS FORM MUST BE FILLED OUT COMPLETELY. The water well contractor is responsible for completing this form and forwarding the permit to the appropriate delegated county where applicable.

CHECK BOX FOR APPROPRIATE DISTRICT. ADDRESS ON BACK OF PERMIT FORM.

Permit No. 1369-2256
Florida Unique I.D.
Permit Stipulations Required (See attached)
62-524 well
CUP/ WUP Application No.


Print as this box in circle that address is visible through computer screen

1. Florida Power and Light Company, Attn: Mr. Ed Paula 9700 SW 344 Street Florida City 33034 305-246-6407
Owner, Legal Name of Entity if Corporation Address City Zip Telephone Number

2. Turkey Point Nuclear Generating Station - coordinates of proposed wells attached
Well Location - Address, Road Name or Number, City

3. MACTEC Engineering and Consulting, Inc. - Phillip K. Pitts FL # 11035 404-873-4761
Well Drilling Contractor License No. Telephone No.
396 Plasters Avenue
Address City State Zip
Atlanta Georgia 30324
City State Zip

4. NE 1/4 of SE 1/4 of Section 34
5. Township 57S Range 40E
6. Miami-Dade N/A N/A N/A N/A
County Subdivision Name Lot Block Unit



7. Number of proposed wells 1 Check the use of well: (See back of permit for additional choices) Domestic Monitor (type) Observation well
Irrigation (type) Public Water Supply (type) List Other

Distance from septic system N/A ft. Description of facility Est. start of construction date 2/19/08

8. Application for: X New Construction Repair/Modify Abandonment
Estimated: Well Depth 101* ft Casing Depth 90 ft
Casing Material: Blk-Steel / Gal / PVC PVC Casing Diameter 2"

9. If applicable: Proposed Grouting Interval From 88 to 100 Seal Material 10/20 silica sand
From 85 to 85 Seal Material Bentonite
From 0 to 83 Seal Material Portland/bentonite slurry

10. Telescopes Casing or Liner (check one) Diameter 2"
Blk-Steel / Galvanized / PVC/PVC Other (specify):


11. Method of Construction: X Rotary Cable Tool Combination
X Auger Other (specify):

12. Indicate total No. of wells on site 0 List number of unused wells on site 0

13. Is this well or any other well or water well drawal on the owner's contiguous property covered under a Consumptive Water Use Permit (CUP/WUP) or CUP/WUP Application? X No Yes

14. District well I.D. No. N/A
Latitude N/A Longitude N/A
Data obtained from GPS or map or survey (map datum NAD 87 NAD 83)

15. I hereby certify that I will comply with the applicable rules of Title 40, Florida Administrative Code, and that a water use permit or artificial recharge permit, if needed, has been or will be obtained prior to commencement of well construction. I further certify that all information provided on this application is accurate and that I will obtain necessary approval from other federal, state, or local governmental agencies, if applicable, to provide a well completion report to the District within 30 days after drilling or other completion, whichever occurs first.



APPROVED
Permit No. 1369-2256
Date: 2-19-08
Miami-Dade County Health Department

15. I hereby certify that I am the owner of the property, that the information provided is accurate, and that I am aware of my responsibilities under Chapter 375, Florida Statutes, to maintain or properly abandon this well or, I certify that I am the agent for the owner, that the information provided is accurate, and that I have informed the owner of his responsibilities as stated above. Owner consents to personnel of the WMD or a representative access to the well site.
Signature of Contractor License No. 11035
Director of Agency Signature Date 2/19/08

Approval Granted By: ASTRID EDWARDS Issue Date: 2/19/08 Hydrologist Approval

Owner Number: Fee Received: \$ 50 Receipt No.: T080215406 Check No.: 524534
Enter numerical month, day and full, four-digit year.

THIS PERMIT NOT VALID UNTIL PROPERLY SIGNED BY AN AUTHORIZED OFFICER OR REPRESENTATIVE OF THE WMD. IT SHALL BE AVAILABLE AT THE WELL SITE DURING ALL DRILLING OPERATIONS. This permit is valid for 90 days from date of issue.



STATE OF FLORIDA PERMIT APPLICATION TO CONSTRUCT, REPAIR, MODIFY, OR ABANDON A WELL

- Southwest
Northwest
St. Johns River
South Florida
Suwannee River

THIS FORM MUST BE FILLED OUT COMPLETELY.

The water well contractor is responsible for completing this form and forwarding the permit to the appropriate delegated county where applicable.

CHECK BOX FOR APPROPRIATE DISTRICT. ADDRESS ON BACK OF PERMIT FORM

Permit No. W-69-2756
Florida Unique ID.
Permit Stipulations Required (See attached)
62-524 well
Application No.

1. Florida Power and Light Company, Attn: Mr. Ed Paula 9700 SW 344 Street Florida City 33034 305-246-6407
Owner, Legal Name of Entity if Corporation Address City Zip Telephone Number

2. Turkey Point Nuclear Generating Station - coordinates of proposed wells attached
Well Location - Address, Road Name or Number, City

3. MACTEC Engineering and Consulting, Inc. - Phillip K. Pitts FL # 11035 404-873-4761
Well Drilling Contractor License No. Telephone No.

396 Plasters Avenue Address
Atlanta Georgia 30324 City State Zip
4. NE 1/4 of SE 1/4 of Section 34 (smaller) (larger) (Indicate Well on Chart)
5. Township 57S Range 40E

6. Miami-Dade N/A N/A N/A N/A
County Subdivision Name Lot Block Unit SW SE

7. Number of proposed wells 1 Check the use of well: (See back of permit for additional choices) Domestic Monitor (type) Observation well
Irrigation (type) Public Water Supply (type) List Other
Distance from septic system N/A ft. Description of facility In a wastewater discharge area Estimated start of construction date 2/19/08

8. Application for: X New Construction Repair/Modify Abandonment
(Reason for Abandonment)

9. Estimated: Well Depth 26* ft Casing Depth 15 ft Screen Interval from 15 to 25
Casing Material: Blk-Steel / Gal / PVC PVC Casing Diameter 2" Seal Material see below

10. If applicable: Proposed From 13 to 25 Seal Material 10/20 silica sand
Grouting Interval From 10 to 13 Seal Material Bentonite
From 0 to 10 Seal Material Portland/Bentonite slurry


11. Telescope Casing or Liner X (check one) Diameter 2"
Blk-Steel / Galvanized / PVC/PVC Other (specify):

12. Method of Construction: X Rotary Cable Tool Combination
X Auger Other (specify):

13. Indicate total No. of wells on site 0 List number of unused wells on site 0

14. Is this well or any other well or water withdrawal on the owner's contiguous property covered under a Consumptive Water Use Permit (CUP/WUP) or CUP/WUP Application? X No Yes
District well I.D. No. N/A
Latitude N/A Longitude N/A
Data obtained from GPS or map (X survey (map datum NAD 83 NAD 83))

15. I hereby certify that I will comply with the applicable rules of Title 40, Florida Administrative Code, and that a water use permit or annual recharge permit, if needed, has been or will be obtained prior to commencement of well construction. I further certify that all information provided on this application is accurate and that I will obtain necessary approval from other federal, state, or local governments, if applicable, to complete a well construction report to the District within 30 days after drilling of the well is completed, with two copies first.
Signature of Contractor License No. 11035 Date 2/15/08



APPROVED
Permit No. W-69-2756
Date 2-19-08
Miami-Dade County Health Department

DO NOT WRITE BELOW THIS LINE FOR OFFICIAL USE ONLY

Approval Granted By: Arturo Edwards Issue Date: 2/19/08 Hydrologist Approval
Owner Number: Fee Received: \$ 50 Receipt No.: 108215406 Check No.: 524534

THIS PERMIT NOT VALID UNTIL PROPERLY SIGNED BY AN AUTHORIZED OFFICER OR REPRESENTATIVE OF THE WMD. IT SHALL BE AVAILABLE AT THE WELL SITE DURING ALL DRILLING OPERATIONS. This permit is valid for 90 days from date of issue.



STATE OF FLORIDA PERMIT APPLICATION TO CONSTRUCT, REPAIR, MODIFY, OR ABANDON A WELL

- Southwest
Northwest
St. Johns River
South Florida
Suwannee River

THIS FORM MUST BE FILLED OUT COMPLETELY. The well contractor is responsible for completing this form and forwarding the permit to the appropriate delegated county where applicable.

CHECK BOX FOR APPROPRIATE DISTRICT. ADDRESS ON BACK OF PERMIT FORM.

Permit No. 17169-2258
Florida Unique I.D.
Permit Stipulations Required (See attached)
B2-524 well
CUP/WUP Application No.


Fill out this line in order that address is visible through envelope window

1. Florida Power and Light Company, Attn: Mr. Ed Paula 9700 SW 344 Street Florida City 33034 305-246-6407
Owner, Legal Name of Entity if Corporation Address City Zip Telephone Number

2. Turkey Point Nuclear Generating Station - coordinates of proposed wells attached
Well Location - Address, Road Name or Number, City

3. MACTEC Engineering and Consulting, Inc. - Phillip K. Pitts FL # 11035 404-873-4761
Well Drilling Contractor License No. Telephone No.

396 Plasters Avenue Address
Atlanta Georgia 30324 City State Zip
4. NW 1/4 of SE 1/4 of Section 33 (Indicate Well on Chart)
5. Township 57S Range 40E



6. Miami-Dade N/A N/A N/A N/A
County Subdivision Name Lot Block Unit

7. Number of proposed wells: 1 Check the use of well: Domestic Monitor (type) Observation well
Irrigation (type) Public Water Supply (type) List Other

Distance from septic system: N/A Description of facility: Estimated start of construction date: 2/19/08

8. Application for: X New Construction Repair/Modify Abandonment

9. Estimated: Well Depth: 101* ft Casing Depth: 90 ft
Casing Material: Blk-Steel / Gal / PVC PVC Casing Diameter: 2"


10. If applicable: Proposed From 88 to 100 Seal Material: 10/20 silica sand
Grouting Interval From 83 to 85 Seal Material: Bentonite
From 0 to 83 Seal Material: Portland/bentonite slurry

11. Telescope Casing or Liner (check one) Diameter 2"
Blk-Steel / Galvanized / PVC PVC Other (specify):

12. Method of Construction: X Rotary Cable Tool Combination
X Auger Other (specify):

13. Indicate total No. of wells on site: 0 List number of unused wells on site: 0

14. Is this well or any other well or water withdrawal on the owner's contiguous property covered under a Consumptive Water Use Permit (CUP/WUP) or CUP/WUP Application? X No Yes
District well I.D. No. N/A
Latitude N/A Longitude N/A
Data obtained from GPS or map or survey (map datum NAD 27 NAD 83)



15. I hereby certify that I will comply with the applicable rules of Title 40, Florida Administrative Code, and that a water use permit or artificial recharge permit, if needed, has been or will be obtained prior to commencement of well construction. I further certify that all information provided on this application is accurate and that I will obtain necessary approval from other federal, state, or local government agencies and I agree to provide a well completion report to the District within 30 days after drilling and/or pump installation, if so required.
Signature of Contractor License No. 11035 Date 2/15/08

Approval Granted By: ASTRID EDWARDS Issue Date: 2-19-08 Hydrologist Approval

Owner Number: Fee Received: \$ 50 Receipt No.: 108021544 Check No.: 524534

THIS PERMIT NOT VALID UNTIL PROPERLY SIGNED BY AN AUTHORIZED OFFICER OR REPRESENTATIVE OF THE WMD. IT SHALL BE AVAILABLE AT THE WELL SITE DURING ALL DRILLING OPERATIONS. This permit is valid for 90 days from date of issue.



STATE OF FLORIDA PERMIT APPLICATION TO CONSTRUCT, REPAIR, MODIFY, OR ABANDON A WELL

- Southwest
Northwest
St. Johns River
South Florida
Suwannee River

THIS FORM MUST BE FILLED OUT COMPLETELY. The well contractor is responsible for completing this form and forwarding the permit to the appropriate delegated county where applicable.

CHECK BOX FOR APPROPRIATE DISTRICT. ADDRESS ON BACK OF PERMIT FORM.

Permit No. 12-69-2257
Florida Unique I.D.
Permit Stipulations Required (See attached)
62-524 well
CUPW Application No.

1. Florida Power and Light Company, Attn: Mr. Ed Paula 9700 SW 344 Street Florida City 33034 305-246-6407
Owner, Legal Name of Entity if Corporation Address City Zip Telephone Number

2. Turkey Point Nuclear Generating Station - coordinates of proposed wells attached
Well Location - Address, Road Name or Number, City

3. MACTEC Engineering and Consulting, Inc. - Phillip K. Pitts FL # 11035 404-873-4761
Well Drilling Contractor License No. Telephone No.

Address 396 Plasters Avenue
City Atlanta State Georgia Zip 30324
4. NW 1/4 of SE 1/4 of Section 33
5. Township 57S Range 40E

6. Miami-Dade N/A N/A N/A N/A
County Subdivision Name Lot Block Unit

7. Number of proposed wells: 1 Check the use of well: Domestic Monitor (type) Observation well
Irrigation (type) Public Water Supply (type) List Other

Distance from septic system N/A ft. Description of facility Ind. water use discharge area Estimated start of construction date 2/19/08

8. Application for: X New Construction Repair/Modify Abandonment

9. Estimated: Well Depth 26* ft Casing Depth 15 ft
Casing Material: Blk-Steel / Gal / PVC rvc Casing Diameter 2"

10. If applicable: Proposed From 13 to 25 Seal Material 10/20 silica sand
Grouting Interval From 10 to 13 Seal Material Bentonite
From 0 to 10 Seal Material Portland/bentonite slurry


11. Telescope Casing or Liner X (check one) Diameter 2"
Blk-Steel / Galvanized / PVC/PVC Other (specify):

12. Method of Construction: X Rotary Cable Tool Combination
X Auger Other (specify):

13. Indicate total No. of wells on site 0 List number of unused wells on site 0

14. Is this well or any other well or water withdrawal on the owner's contiguous property covered under a Consumptive Water Use Permit (CUP/WUP) or CUP/WUP Application? X No Yes
District well I.D. No. N/A
Latitude N/A Longitude N/A
Data obtained from GPS or map or survey (map datum NAD 27 NAD 83)

15. I hereby certify that I will comply with the applicable rules of Title 40, Florida Administrative Code and that a water use permit or sufficient discharge permit, if needed, has been or will be obtained prior to commencement of well construction. I further certify that all information provided on this application is accurate and that I will obtain necessary approval from other federal, state, or local governments, if applicable, to provide a well completion report to the District within 30 days after completion of the permit operation, if a change occurs to it.
I certify that I am the owner of the property; that the information provided is accurate, and that I am aware of my responsibilities under Chapter 373, Florida Statutes, to maintain or properly abandon this well; or, to notify me (or the agent) for the owner that the information provided is accurate, and that I have informed the owner of his responsibilities as stated above. Other consents, purchases of the Well, or a representative access to the well site.



APPROVED
Permit No. 12-69-2257
Date 2-19-08
Miami-Dade County
Public Works Department

Approval Granted By: AGUSTO EDWARDS Issue Date: 2-19-08 Hydrologist Approval

Owner Number: Fee Received: \$ 50 Receipt No. T080215406 Check No.: 52 4534

THIS PERMIT NOT VALID UNTIL PROPERLY SIGNED BY AN AUTHORIZED OFFICER OR REPRESENTATIVE OF THE WMD. IT SHALL BE AVAILABLE AT THE WELL SITE DURING ALL DRILLING OPERATIONS. This permit is valid for 90 days from date of issue.

Fax #: 919-831-8106



STATE OF FLORIDA PERMIT APPLICATION TO CONSTRUCT, REPAIR, MODIFY, OR ABANDON A WELL

- Southwest
Northwest
St. Johns River
South Florida
Suwannee River

THIS FORM MUST BE FILLED OUT COMPLETELY. The water well contractor is responsible for completing this form and forwarding the permit to the appropriate delegated county where applicable.

CHECK BOX FOR APPROPRIATE DISTRICT, ADDRESS ON BACK OF PERMIT FORM

Permit No. 13-59-2260
Florida Unique I.D.
Permit Stipulations Required (See attached)
G2-524 well
CUP/WUP Application No.

1. Florida Power and Light Company, Attn: Mr. Ed Pauln 9700 SW 344 Street Florida City 33034 305-246-6407
2. Turkey Point Nuclear Generating Station - coordinates of proposed wells attached
3. MACTEC Engineering and Consulting, Inc. - Phillip K. Pitts FL # 11035 404-873-4761

7. Number of proposed wells 1 Check the use of well: (See back of permit for additional choices) Domestic Monitor (type) Observation well
Irrigation (type) Public Water Supply (type) List Other
Distance from septic system N/A ft. Description of facility Int. wastewater discharge area Estimated start of construction date 2/19/08

8. Application for: X New Construction Repair/Modify Abandonment
9. Estimated: Well Depth 101 ft Casing Depth 90 ft
Casing Material: Blk-Steel / Gal / PVC PVC Casing Diameter 2"
Screen Interval from 90 to 100
Seal Material sec below

10. If applicable: Proposed From 55 to 100 Seal Material 10/20 silica sand
Grouting Interval From 85 to 85 Seal Material Bentonite
From 0 to 83 Seal Material Portland/mononite slurry

11. Telescope Casing or Liner X (tick one) Diameter 2"
Blk-Steel / Galvanized / PVC/PVC Other (specify):


12. Method of Construction: X Rotary Cable Tool Combination
X Auger Other (specify):

13. Indicate total No. of wells on site 0 List number of unused wells on site 0

14. Is this well or any other well or water withdrawal on the owner's contiguous property covered under a Consumptive Water Use Permit (CUP/WUP) or CUP/WUP Application? X No Yes
District well I.D. No. N/A
Latitude N/A Longitude N/A
Data obtained from GPS or map X survey (map datum NAD 27 NAD 83)

15. I hereby certify that I will comply with the applicable rules of Title 40, Florida Administrative Code... I certify that I am the owner of the property, that the information provided is accurate, and that I am aware of my responsibilities under Chapter 373, Florida Statutes...

APPROVED
Permit no. 13-59-2260
Date: 2-19-08
Miami-Dade County
Health Department



Approval Granted By: ASTRAD EDW ABRS Issue Date: 2-19-08 Hydrologist Approval

Owner Number: Fee Received: \$ 50 Receipt No. 1080215406 Check No.: 524534

THIS PERMIT NOT VALID UNTIL PROPERLY SIGNED BY AN AUTHORIZED OFFICER OR REPRESENTATIVE OF THE WMD. IT SHALL BE AVAILABLE AT THE WELL SITE DURING ALL DRILLING OPERATIONS. This permit is valid for 90 days from date of issue.



STATE OF FLORIDA PERMIT APPLICATION TO CONSTRUCT, REPAIR, MODIFY, OR ABANDON A WELL.

- Southwest
Northwest
St. Johns River
South Florida
Suwannee River

THIS FORM MUST BE FILLED OUT COMPLETELY.

The water well contractor is responsible for completing this form and forwarding the permit to the appropriate delegated county where applicable.

CHECK BOX FOR APPROPRIATE DISTRICT. ADDRESS ON BACK OF PERMIT FORM.


Permit No. 13-59-2259
Florida Unique ID.
Permit Situations Required (See attached)
62-524 well
CWP Application No.

1. Florida Power and Light Company, Attn: Mr. Ed Paula 9700 SW 344 Street Florida City 33034 305-246-6407
Owner, Legal Name of Entity if Corporation Address City Zip Telephone Number

2. Turkey Point Nuclear Generating Station - coordinates of proposed wells attached
Well Location - Address, Road Name or Number, City

3. MACTEC Engineering and Consulting, Inc. - Phillip K. Pitts FL # 11035 404-873-4761
Well Drilling Contractor License No. Telephone No.

396 Plasters Avenue Address
Atlanta Georgia 30324 City State Zip
4. NW 1/4 of NE 1/4 of Section 33 (Indicate Well on Chart)
5. Township 57S Range 40E



8. Miami-Dade N/A N/A N/A N/A
County Subdivision Name Lot Block Unit

7. Number of proposed wells 1 Check the use of well: Domestic Monitor (type) Observation well
Irrigation (type) Public Water Supply (type) List Other

Distance from septic system N/A ft. Description of facility Est. wastewater discharge area Estimated start of construction date 2/19/08

8. Application for: X New Construction Repair/Modify Abandonment
(Reason for Abandonment)

9. Estimated: Well Depth 26* ft Casing Depth 15 ft
Casing Material: Blk-Steel / Gal / PVC rvc Casing Diameter 2"
Screen interval from 15 to 25
Seal Material see below


10. If applicable: Proposed From 13 to 25 Seal Material 10/20 silica sand
Grouting Interval From 10 to 13 Seal Material Bentonite
From 0 to 10 Seal Material Portland/bentonite slurry

11. Telescope Casing or Liner X (check one) Diameter 2"
Blk-Steel / Galvanized / PVC/PVC Other (specify):

12. Method of Construction: X Rotary Cable Tool Combination
X Auger Other (specify):

13. Indicate total No. of wells on site 0 List number of unused wells on site 0

14. Is this well or any other well or water withdrawal on the owner's contiguous property covered under a Consumptive Water Use Permit (CUP/WUP) or CUP/WUP Application? X No Yes
District well I.D. No. N/A
Latitude N/A Longitude N/A
Data obtained from GPS or map or survey (map datum NAD 27 NAD 83)



APPROVED
Date of Permit 2/19/08
Permit No. 13-59-2259
Date 2/19/08
Miami-Dade County
Florida Department of Natural Resources

15. I hereby certify that I will comply with the applicable rules of Title 40, Florida Administrative Code, and that a water use permit or artificial recharge permit, if needed, has been or will be obtained prior to commencement of well construction. I further certify that all information provided on this application is accurate and that I will obtain necessary approval from other federal, state, or local governments, if applicable. I agree to provide a well completion report to the District within 30 days after drilling of this permit expiration, whichever occurs first.
I certify that I am the owner of the property, that the information provided is accurate, and that I am aware of my responsibilities under Chapter 373, Florida Statutes, to maintain or properly abandon this well; or, I certify that I am the agent for the owner, that the information provided is accurate, and that I have informed the owner of his or her responsibilities as stated above. Owner consents to personnel of the WMD of a representative access to the well site.

Approval Granted By: AARLE EDWARDS Issue Date: 2-19-08 Hydrologist Approval
Owner Number: Fee Received: \$ 50 Receipt No.: 1080215406 Check No.: 524534

THIS PERMIT NOT VALID UNTIL PROPERLY SIGNED BY AN AUTHORIZED OFFICER OR REPRESENTATIVE OF THE WMD. IT SHALL BE AVAILABLE AT THE WELL SITE DURING ALL DRILLING OPERATIONS. This permit is valid for 90 days from date of issue.

Observation Well Records

Observation Well Data Sheet

Prepared by: WSP Date: 7-10-08
 Checked by: CBS Date: 7/10/08

Project Name / No. : Turkey Point Power Station / 6468-07-1950 Observation Well Permit No.: 13-59-2671
 County: Miami-Dade County, Florida Observation Well I.D.: OW-606D
 Date of Observation Well Installation: 5/28/08 Date of Well Development: 6/4/08
 Observation Well Northing: 396962.8 US ft Easting: 876712.9 US ft
 Observation Well Location: Main Island Observation Well Driller


Name: MACTEC
 License No.: 11035

NOTES:

- Centralizer installation depths not recorded
- PVC well screen machine-slotted by the manufacturer.
- Observation well developed using a submersible pump.
- Static water measurement collected 6/4/08.
- Upon completion of well installation, MACTEC installed two seep holes in the protective steel cover.

Geologist, Hydrologist, or Engineer Supervising Well Installation: Harry Lyatuu
 Static Water Level Elevation (with respect to NAVD88) after Well Development: 1.3
 Name of Geologic Formation(s) in which Well is completed: See boring log B-606

Type of Locking Device: Masterlock - 0536 Type of Casing Protection: Steel
 Concrete Surface Pad (with steel reinforcement) Dimensions: 2'x2'x0.5'



Observation Well Data Sheet

Prepared by: WJG Date: 7-10-08
 Checked by: CBS Date: 7/10/08

Project Name / No. : Turkey Point Power Station / 6468-07-1950 Observation Well Permit No.: 13-59-2243
 County: Miami-Dade County, Florida Observation Well I.D.: OW-6061
 Date of Observation Well Installation: 5/14/08 Date of Well Development: 5/17/08
 Observation Well Northing: 396979.9 US ft Easting: 876732.6 US ft
 Observation Well Location: Main Island Observation Well Driller


Name: Miller Drilling/MACTEC
 License No.: 11035

NOTES:

Two, stainless-steel centralizers installed at approximately 47 ft. and 96 ft.
 PVC well screen machine-slotted by the manufacturer.
 Observation well developed using a submersible pump.
 Static water measurement collected 5/18/08.
 Upon completion of well installation, MACTEC installed two seep holes in the protective steel cover.
 Drill bit lost in hole at 110.0 ft. Bentonite seal installed from 109.0-110.0', with approval of Bechtel.

Geologist, Hydrologist, or Engineer Supervising Well Installation: Kim Charles-Smith
 Static Water Level Elevation (with respect to NAVD88) after Well Development: -1.9
 Name of Geologic Formation(s) in which Well is completed: See boring log B-606

Type of Locking Device: Masterlock - 0536 Type of Casing Protection: Steel
 Concrete Surface Pad (with steel reinforcement) Dimensions: 2'x2'x0.5'



Observation Well Data Sheet

Prepared by: WSE Date: 7-10-08
 Checked by: CBS Date: 7/10/08


Project Name / No. : Turkey Point Power Station / 6468-07-1950 Observation Well Permit No.: 13-59-2241
 County: Miami-Dade County, Florida Observation Well I.D.: OW-606U
 Date of Observation Well Installation: 4/22/08 Date of Well Development: 5/1/08
 Observation Well Northing: 396938.0 US ft Easting: 876734.8 US ft
 Observation Well Location: Main Island Observation Well Driller
 Name: Miller Drilling/MACTEC
 License No.: 11035

NOTES:

One stainless-steel centralizer installed at approximately 11.5 ft.
 PVC well screen machine-slotted by the manufacturer.
 Observation well developed using a submersible pump.
 Static water measurement collected 5/20/08.
 Upon completion of well installation, MACTEC installed two seep holes in the protective steel cover.

Geologist, Hydrologist, or Engineer Supervising Well Installation: Kim Charles-Smith
 Static Water Level Elevation (with respect to NAVD88) after Well Development: -2.1
 Name of Geologic Formation(s) in which Well is completed: See boring log B-606

Type of Locking Device: Masterlock - 0536 Type of Casing Protection: Steel
 Concrete Surface Pad (with steel reinforcement) Dimensions: 2'x2'x0.5'



Observation Well Data Sheet

Prepared by: WJ Date: 7-008
 Checked by: CBS Date: 7/10/08

Project Name / No. : Turkey Point Power Station / 6468-07-1950 Observation Well Permit No.: 13-59-2242
 County: Miami-Dade County, Florida Observation Well I.D.: OW-621L
 Date of Observation Well Installation: 4/18/08 Date of Well Development: 5/3/08
 Observation Well Northing: 397364.5 US ft Easting: 876970.0 US ft
 Observation Well Location: Main Island Observation Well Driller


Name: Miller Drilling/MACTEC
 License No.: 11035

NOTES:

Two, stainless-steel centralizers installed at approximately 48 ft. and 98 ft.
 PVC well screen machine-slotted by the manufacturer.
 Observation well developed using a submersible pump.
 Static water measurement collected 5/17/08.
 Upon completion of well installation, MACTEC installed two seep holes in the protective steel cover.

Geologist, Hydrologist, or Engineer Supervising Well Installation: Chris Burroughs
 Static Water Level Elevation (with respect to NAVD88) after Well Development: -1.0
 Name of Geologic Formation(s) in which Well is completed: See boring log B-621

Type of Locking Device: Masterlock - 0536 Type of Casing Protection: Steel
 Concrete Surface Pad (with steel reinforcement) Dimensions: 2'x2'x0.5'



Observation Well Data Sheet

Prepared by: usb Date: 7-10-08
 Checked by: CBS Date: 7/10/08


Project Name / No. : Turkey Point Power Station / 6468-07-1950 Observation Well Permit No.: 13-59-2244
 County: Miami-Dade County, Florida Observation Well I.D.: OW-621U
 Date of Observation Well Installation: 4/19/08 Date of Well Development: 5/3/08
 Observation Well Northing: 397375.8 US ft Easting: 876930.0 US ft
 Observation Well Location: Main Island Observation Well Driller
 Name: Miller Drilling/MACTEC
 License No.: 11035

NOTES:

One stainless-steel centralizer installed at approximately 11 ft.
 PVC well screen machine-slotted by the manufacturer.
 Observation well developed using a submersible pump.
 Static water measurement collected 5/20/08.
 Upon completion of well installation, MACTEC installed two seep holes in the protective steel cover.

Geologist, Hydrologist, or Engineer Supervising Well Installation: Chris Burroughs
 Static Water Level Elevation (with respect to NAVD88) after Well Development: -1.8
 Name of Geologic Formation(s) in which Well is completed: See boring log B-621

Type of Locking Device: Masterlock - 0536 Type of Casing Protection: Steel
 Concrete Surface Pad (with steel reinforcement) Dimensions: 2'x2'x0.5'



Observation Well Data Sheet

Prepared by: WJ Date: 7-10-08
 Checked by: CBS Date: 7/10/08

Project Name / No. : Turkey Point Power Station / 6468-07-1950 Observation Well Permit No.: 13-59-2246
 County: Miami-Dade County, Florida Observation Well I.D.: OW-636L
 Date of Observation Well Installation: 4/8/08 Date of Well Development: 5/5/08
 Observation Well Northing: 395290.8 US ft Easting: 877257.2 US ft
 Observation Well Location: South Island Observation Well Driller


Name: MACTEC
 License No.: 11035

NOTES:

Two, stainless-steel centralizers installed at approximately 49.5 ft. and 96.6 ft.
 PVC well screen machine-slotted by the manufacturer.
 Observation well developed using a submersible pump.
 Static water measurement collected 5/21/08.
 Upon completion of well installation, MACTEC installed two seep holes in the protective steel cover.
 Encountered an apparent obstruction at 69.3 ft.

Geologist, Hydrologist, or Engineer Supervising Well Installation: Chris Burroughs
 Static Water Level Elevation (with respect to NAVD88) after Well Development: 0.3
 Name of Geologic Formation(s) in which Well is completed: See boring log B-806

Type of Locking Device: Masterlock - 0536 Type of Casing Protection: Steel
 Concrete Surface Pad (with steel reinforcement) Dimensions: 2'x2'x0.5'



Observation Well Data Sheet

Prepared by: WS Date: 7-10-08
 Checked by: CBS Date: 7/10/08

Project Name / No. : Turkey Point Power Station / 6468-07-1950 Observation Well Permit No.: 13-59-2245
 County: Miami-Dade County, Florida Observation Well I.D.: OW-636U
 Date of Observation Well Installation: 4/3/08 Date of Well Development: 5/5/08
 Observation Well Northing: 395285.8 US ft Easting: 877215.7 US ft
 Observation Well Location: South Island Observation Well Driller


Name: MACTEC
 License No.: 11035

NOTES:

One stainless-steel centralizer installed at approximately 16.5 ft.
 PVC well screen machine-slotted by the manufacturer.
 Observation well developed using a submersible pump.
 Static water measurement collected 5/21/08.
 Upon completion of well installation, MACTEC installed two seep holes in the protective steel cover.

Geologist, Hydrologist, or Engineer Supervising Well Installation: Chris Burroughs
 Static Water Level Elevation (with respect to NAVD88) after Well Development: -1.6
 Name of Geologic Formation(s) in which Well is completed: See boring log B-806

Type of Locking Device: Masterlock - 0536 Type of Casing Protection: Steel
 Concrete Surface Pad (with steel reinforcement) Dimensions: 2'x2'x0.5'



Observation Well Data Sheet

Prepared by: WSR Date: 7-10-08
 Checked by: CBS Date: 7/10/08

Project Name / No. : Turkey Point Power Station / 6468-07-1950 Observation Well Permit No.: 13-59-2672
 County: Miami-Dade County, Florida Observation Well I.D.: OW-706D
 Date of Observation Well Installation: 5/29/08 Date of Well Development: 6/4/08
 Observation Well Northing: 396960.1 US ft Easting: 875864.4 US ft
 Observation Well Location: Main Island Observation Well Driller


Name: MACTEC
 License No.: 11035

NOTES:

- Centralizer installation depths not recorded
- PVC well screen machine-slotted by the manufacturer.
- Observation well developed using a submersible pump.
- Static water measurement collected 6/4/08.
- Upon completion of well installation, MACTEC installed two seep holes in the protective steel cover.

Geologist, Hydrologist, or Engineer Supervising Well Installation: Chris Burroughs
 Static Water Level Elevation (with respect to NAVD88) after Well Development: 1.4
 Name of Geologic Formation(s) in which Well is completed: See boring log B-706

Type of Locking Device: Masterlock - 0536 Type of Casing Protection: Steel
 Concrete Surface Pad (with steel reinforcement) Dimensions: 2'x2'x0.5'



Observation Well Data Sheet

Prepared by: WSB Date: 7-10-08
 Checked by: CBS Date: 7/10/08

Project Name / No. : Turkey Point Power Station / 6468-07-1950 Observation Well Permit No.: 13-59-2248
 County: Miami-Dade County, Florida Observation Well I.D.: OW-706L
 Date of Observation Well Installation: 3/25/08 Date of Well Development: 4/30/08
 Observation Well Northing: 396978.2 US ft Easting: 875904.6 US ft
 Observation Well Location: Main Island Observation Well Driller


Name: MACTEC
 License No.: 11035

NOTES:

- Centralizer installation depths not recorded
- PVC well screen machine-slotted by the manufacturer.
- Observation well developed using a submersible pump.
- Static water measurement collected 5/16/08.
- Upon completion of well installation, MACTEC installed two seep holes in the protective steel cover.

Geologist, Hydrologist, or Engineer Supervising Well Installation: Chris Burroughs
 Static Water Level Elevation (with respect to NAVD88) after Well Development: 0.7
 Name of Geologic Formation(s) in which Well is completed: See boring log B-706

Type of Locking Device: Masterlock - 0536 Type of Casing Protection: Steel
 Concrete Surface Pad (with steel reinforcement) Dimensions: 2'x2'x0.5'



Observation Well Data Sheet

Prepared by: WSU Date: 7-10-08
 Checked by: CBS Date: 7/10/08

Project Name / No. : Turkey Point Power Station / 6468-07-1950 Observation Well Permit No.: 13-59-2247
 County: Miami-Dade County, Florida Observation Well I.D.: OW-706U
 Date of Observation Well Installation: 3/27/08 Date of Well Development: 4/30/08
 Observation Well Northing: 396940.1 US ft Easting: 875895.7 US ft
 Observation Well Location: Main Island Observation Well Driller


Name: MACTEC
 License No.: 11035

NOTES:

One stainless-steel centralizer installed at approximately 16.28 ft.
 PVC well screen machine-slotted by the manufacturer.
 Observation well developed using a submersible pump.
 Static water measurement collected 5/16/08.
 Upon completion of well installation, MACTEC installed two seep holes in the protective steel cover.

Geologist, Hydrologist, or Engineer Supervising Well Installation: Chris Burroughs
 Static Water Level Elevation (with respect to NAVD88) after Well Development: -2.0
 Name of Geologic Formation(s) in which Well is completed: See boring log B-706

Type of Locking Device: Masterlock - 0536 Type of Casing Protection: Steel
 Concrete Surface Pad (with steel reinforcement) Dimensions: 2'x2'x0.5'



Observation Well Data Sheet

Prepared by: LSB Date: 7-10-08
 Checked by: CBS Date: 7/10/08

Project Name / No. : Turkey Point Power Station / 6468-07-1950 Observation Well Permit No.: 13-59-2250
 County: Miami-Dade County, Florida Observation Well I.D.: OW-7211
 Date of Observation Well Installation: 5/3/08 Date of Well Development: 5/4/08
 Observation Well Northing: 397321.5 US ft Easting: 876120.3 US ft
 Observation Well Location: Main Island Observation Well Driller


Name: MACTEC
 License No.: 11035

NOTES:

Two, stainless-steel centralizers installed at approximately 45 ft. and 95 ft.
 PVC well screen machine-slotted by the manufacturer.
 Observation well developed using a submersible pump.
 Static water measurement collected 5/20/08.
 Upon completion of well installation, MACTEC installed two seep holes in the protective steel cover.

Geologist, Hydrologist, or Engineer Supervising Well Installation: Kim Charles-Smith
 Static Water Level Elevation (with respect to NAVD88) after Well Development: 0.0
 Name of Geologic Formation(s) in which Well is completed: See boring log B-721

Type of Locking Device: Masterlock - 0536 Type of Casing Protection: Steel
 Concrete Surface Pad (with steel reinforcement) Dimensions: 2'x2'x0.5'



Observation Well Data Sheet

Prepared by: WSB Date: 7-0-08
 Checked by: CBS Date: 7/10/08

Project Name / No. : Turkey Point Power Station / 6468-07-1950 Observation Well Permit No.: 13-59-2249
 County: Miami-Dade County, Florida Observation Well I.D.: OW-721U
 Date of Observation Well Installation: 5/1/08 Date of Well Development: 5/4/08
 Observation Well Northing: 397361.2 US ft Easting: 876121.4 US ft
 Observation Well Location: Main Island Observation Well Driller


Name: MACTEC
 License No.: 11035

NOTES:

- One stainless-steel centralizer installed at approximately 13.5 ft.
- PVC well screen machine-slotted by the manufacturer.
- Observation well developed using a submersible pump.
- Static water measurement collected 5/15/08.
- Upon completion of well installation, MACTEC installed two seep holes in the protective steel cover.

Geologist, Hydrologist, or Engineer Supervising Well Installation: Kim Charles-Smith
 Static Water Level Elevation (with respect to NAVD88) after Well Development: -2.4
 Name of Geologic Formation(s) in which Well is completed: See boring log B-721

Type of Locking Device: Masterlock - 0536 Type of Casing Protection: Steel
 Concrete Surface Pad (with steel reinforcement) Dimensions: 2'x2'x0.5'



Observation Well Data Sheet

Prepared by: WSL Date: 7-10-08
 Checked by: CBS Date: 7/10/08

Project Name / No. : Turkey Point Power Station / 6468-07-1950 Observation Well Permit No.: 13-59-2252
 County: Miami-Dade County, Florida Observation Well I.D.: OW-735L
 Date of Observation Well Installation: 4/19/08 Date of Well Development: 4/30/08
 Observation Well Northing: 395824.3 US ft Easting: 875669.6 US ft
 Observation Well Location: South Island Observation Well Driller


Name: MACTEC
 License No.: 11035

NOTES:

Two, stainless-steel centralizers installed at approximately 45 ft. and 96 ft.
 PVC well screen machine-slotted by the manufacturer.
 Observation well developed using a submersible pump.
 Static water measurement collected 5/13/08.
 Upon completion of well installation, MACTEC installed two seep holes in the protective steel cover.

Geologist, Hydrologist, or Engineer Supervising Well Installation: Kim Charles-Smith
 Static Water Level Elevation (with respect to NAVD88) after Well Development: -0.3
 Name of Geologic Formation(s) in which Well is completed: See boring log B-735

Type of Locking Device: Masterlock - 0536 Type of Casing Protection: Steel
 Concrete Surface Pad (with steel reinforcement) Dimensions: 2'x2'x0.5'



Observation Well Data Sheet

Prepared by: WSR Date: 7-10-08
 Checked by: CBS Date: 7/10/08

Project Name / No. : Turkey Point Power Station / 6468-07-1950 Observation Well Permit No.: 13-59-2251
 County: Miami-Dade County, Florida Observation Well I.D.: OW-735U
 Date of Observation Well Installation: 4/20/08 Date of Well Development: 4/29/08
 Observation Well Northing: 395823.3 US ft Easting: 875709.2 US ft
 Observation Well Location: South Island Observation Well Driller


Name: MACTEC
 License No.: 11035

NOTES:

One stainless-steel centralizer installed at approximately 15.5 ft.
 PVC well screen machine-slotted by the manufacturer.
 Observation well developed using a submersible pump.
 Static water measurement collected 5/16/08.
 Upon completion of well installation, MACTEC installed two seep holes in the protective steel cover.

Geologist, Hydrologist, or Engineer Supervising Well Installation: Kim Charles-Smith
 Static Water Level Elevation (with respect to NAVD88) after Well Development: -1.9
 Name of Geologic Formation(s) in which Well is completed: See boring log B-735

Type of Locking Device: Masterlock - 0536 Type of Casing Protection: Steel
 Concrete Surface Pad (with steel reinforcement) Dimensions: 2'x2'x0.5'



Observation Well Data Sheet

Prepared by: W4 Date: 7-10-08
 Checked by: CBS Date: 7/10/08

Project Name / No. : Turkey Point Power Station / 6468-07-1950 Observation Well Permit No.: 13-59-2254
 County: Miami-Dade County, Florida Observation Well I.D.: OW-802L
 Date of Observation Well Installation: 5/3/08 Date of Well Development: 5/5/08
 Observation Well Northing: 398817.1 US ft Easting: 876265.7 US ft
 Observation Well Location: North Island Observation Well Driller


Name: MACTEC
 License No.: 11035

NOTES:

- Centralizer installation depths not recorded
- PVC well screen machine-slotted by the manufacturer.
- Observation well developed using a submersible pump.
- Static water measurement collected 5/20/08.
- Upon completion of well installation, MACTEC installed two seep holes in the protective steel cover.

Geologist, Hydrologist, or Engineer Supervising Well Installation: Harry Lyatuu
 Static Water Level Elevation (with respect to NAVD88) after Well Development: -1.0
 Name of Geologic Formation(s) in which Well is completed: See boring log B-802

Type of Locking Device: Masterlock - 0536 Type of Casing Protection: Steel
 Concrete Surface Pad (with steel reinforcement) Dimensions: 2'x2'x0.5'



Observation Well Data Sheet

Prepared by: WSU Date: 7-10-08
 Checked by: CBS Date: 7/10/08

Project Name / No. : Turkey Point Power Station / 6468-07-1950 Observation Well Permit No.: 13-59-2253
 County: Miami-Dade County, Florida Observation Well I.D.: OW-802U
 Date of Observation Well Installation: 5/4/08 Date of Well Development: 5/7/08
 Observation Well Northing: 398820.2 US ft Easting: 876243.7 US ft
 Observation Well Location: North Island Observation Well Driller


Name: MACTEC
 License No.: 11035

NOTES:

Centralizer installation depths not recorded
 PVC well screen machine-slotted by the manufacturer.
 Observation well developed using a submersible pump.
 Static water measurement collected 5/20/08.
 Upon completion of well installation, MACTEC installed two seep holes in the protective steel cover.
 Depth to bottom of concrete seal not recorded (NR) and elevation not determined (ND).

Geologist, Hydrologist, or Engineer Supervising Well Installation: Harry Lyatuu
 Static Water Level Elevation (with respect to NAVD88) after Well Development: -2.4
 Name of Geologic Formation(s) in which Well is completed: See boring log B-802

Type of Locking Device: Masterlock - 0536 Type of Casing Protection: Steel
 Concrete Surface Pad (with steel reinforcement) Dimensions: 2'x2'x0.5'



Observation Well Data Sheet

Prepared by: W36 Date: 7-10-08
 Checked by: CBS Date: 7/10/08

Project Name / No. : Turkey Point Power Station / 6468-07-1950 Observation Well Permit No.: 13-59-2256
 County: Miami-Dade County, Florida Observation Well I.D.: OW-805I
 Date of Observation Well Installation: 5/22/08 Date of Well Development: 6/5/08
 Observation Well Northing: 396883.0 US ft Easting: 877239.5 US ft
 Observation Well Location: Main Island Observation Well Driller


Name: MACTEC
 License No.: 11035

NOTES:

Centralizer installation depths not recorded
 PVC well screen machine-slotted by the manufacturer.
 Observation well developed using a submersible pump.
 Static water measurement collected 6/6/08.
 Upon completion of well installation, MACTEC installed two seep holes in the protective steel cover.

Geologist, Hydrologist, or Engineer Supervising Well Installation: Harry Lyatuu
 Static Water Level Elevation (with respect to NAVD88) after Well Development: -1.0
 Name of Geologic Formation(s) in which Well is completed: See boring log B-805

Type of Locking Device: Masterlock - 0536 Type of Casing Protection: Steel
 Concrete Surface Pad (with steel reinforcement) Dimensions: 2'x2'x0.5'



Observation Well Data Sheet

Prepared by: WSL Date: 7-6-08
 Checked by: CRS Date: 7/10/08

Project Name / No. : Turkey Point Power Station / 6468-07-1950 Observation Well Permit No.: 13-59-2255
 County: Miami-Dade County, Florida Observation Well I.D.: OW-805U
 Date of Observation Well Installation: 5/27/08 Date of Well Development: 6/5/08
 Observation Well Northing: 396842.8 US ft Easting: 877240.9 US ft
 Observation Well Location: Main Island Observation Well Driller


Name: MACTEC
 License No.: 11035

NOTES:

Centralizer installation depths not recorded
 PVC well screen machine-slotted by the manufacturer.
 Observation well developed using a submersible pump.
 Static water measurement collected 6/6/08.
 Upon completion of well installation, MACTEC installed two seep holes in the protective steel cover.

Geologist, Hydrologist, or Engineer Supervising Well Installation: Harry Lyatuu
 Static Water Level Elevation (with respect to NAVD88) after Well Development: -1.8
 Name of Geologic Formation(s) in which Well is completed: See boring log B-805

Type of Locking Device: Masterlock - 0536 Type of Casing Protection: Steel
 Concrete Surface Pad (with steel reinforcement) Dimensions: 2'x2'x0.5'



Observation Well Data Sheet

Prepared by: WSB Date: 7-10-08
 Checked by: CBS Date: 7/10/08

Project Name / No. : Turkey Point Power Station / 6468-07-1950 Observation Well Permit No.: 13-59-2258
 County: Miami-Dade County, Florida Observation Well I.D.: OW-809I
 Date of Observation Well Installation: 5/7/08 Date of Well Development: 5/13/08
 Observation Well Northing: 397007.9 US ft Easting: 875152.3 US ft
 Observation Well Location: Main Island Observation Well Driller


Name: MACTEC
 License No.: 11035

NOTES:

Two, stainless-steel centralizers installed at approximately 45.5 ft. and 95 ft.
 PVC well screen machine-slotted by the manufacturer.
 Observation well developed using a submersible pump.
 Static water measurement collected 5/15/08.
 Upon completion of well installation, MACTEC installed two seep holes in the protective steel cover.

Geologist, Hydrologist, or Engineer Supervising Well Installation: Gautham Pillappa/Kim Charles-Smith
 Static Water Level Elevation (with respect to NAVD88) after Well Development: -0.9
 Name of Geologic Formation(s) in which Well is completed: See boring log B-809

Type of Locking Device: Masterlock - 0536 Type of Casing Protection: Steel
 Concrete Surface Pad (with steel reinforcement) Dimensions: 2'x2'x0.5'



Observation Well Data Sheet

Prepared by: WB Date: 7-10-08
 Checked by: CBS Date: 7/10/08

Project Name / No. : Turkey Point Power Station / 6468-07-1950 Observation Well Permit No.: 13-59-2257
 County: Miami-Dade County, Florida Observation Well I.D.: OW-809U
 Date of Observation Well Installation: 4/1/08 Date of Well Development: 5/1/08
 Observation Well Northing: 397045.8 US ft Easting: 875152.4 US ft
 Observation Well Location: Main Island Observation Well Driller


Name: MACTEC
 License No.: 11035

NOTES:

One stainless-steel centralizer installed at approximately 14.8 ft.
 PVC well screen machine-slotted by the manufacturer.
 Observation well developed using a submersible pump.
 Static water measurement collected 5/15/08.
 Upon completion of well installation, MACTEC installed two seep holes in the protective steel cover.

Geologist, Hydrologist, or Engineer Supervising Well Installation: Chris Burroughs
 Static Water Level Elevation (with respect to NAVD88) after Well Development: -2.2
 Name of Geologic Formation(s) in which Well is completed: See boring log B-809

Type of Locking Device: Masterlock - 0536 Type of Casing Protection: Steel
 Concrete Surface Pad (with steel reinforcement) Dimensions: 2'x2'x0.5'



Observation Well Data Sheet

Prepared by: WS Date: 7-10-08
 Checked by: CBS Date: 7/10/08

Project Name / No. : Turkey Point Power Station / 6468-07-1950 Observation Well Permit No.: 13-59-2260
 County: Miami-Dade County, Florida Observation Well I.D.: OW-812L
 Date of Observation Well Installation: 5/7/08 Date of Well Development: 5/13/08
 Observation Well Northing: 398892.8 US ft Easting: 875045.5 US ft
 Observation Well Location: North Island Observation Well Driller


Name: MACTEC
 License No.: 11035

NOTES:

- Centralizer installation depths not recorded
- PVC well screen machine-slotted by the manufacturer.
- Observation well developed using a submersible pump.
- Static water measurement collected 5/20/08.
- Upon completion of well installation, MACTEC installed two seep holes in the protective steel cover.

Geologist, Hydrologist, or Engineer Supervising Well Installation: Harry Lyatuu
 Static Water Level Elevation (with respect to NAVD88) after Well Development: -0.9
 Name of Geologic Formation(s) in which Well is completed: See boring log B-812

Type of Locking Device: Masterlock - 0536 Type of Casing Protection: Steel
 Concrete Surface Pad (with steel reinforcement) Dimensions: 2'x2'x0.5'



Observation Well Data Sheet

Prepared by: WSB Date: 7-10-08
 Checked by: CBS Date: 7/10/08

Project Name / No. : Turkey Point Power Station / 6468-07-1950 Observation Well Permit No.: 13-59-2259
 County: Miami-Dade County, Florida Observation Well I.D.: OW-812U
 Date of Observation Well Installation: 5/6/08 Date of Well Development: 5/7/08
 Observation Well Northing: 398933.9 US ft Easting: 875043.5 US ft
 Observation Well Location: North Island Observation Well Driller


Name: MACTEC
 License No.: 11035

NOTES:

Centralizer installation depths not recorded
 PVC well screen machine-slotted by the manufacturer.
 Observation well developed using a submersible pump.
 Static water measurement collected 5/20/08.
 Upon completion of well installation, MACTEC installed two seep holes in the protective steel cover.
 Depth to bottom of concrete seal not recorded (NR) and elevation not determined (ND).

Geologist, Hydrologist, or Engineer Supervising Well Installation: Harry Lyatuu
 Static Water Level Elevation (with respect to NAVD88) after Well Development: -2.4
 Name of Geologic Formation(s) in which Well is completed: See boring log B-812

Type of Locking Device: Masterlock - 0536 Type of Casing Protection: Steel
 Concrete Surface Pad (with steel reinforcement) Dimensions: 2'x2'x0.5'



Well Development Records

Well Development Record

Well No.:

OW-606L

Project No. 6068-07-1950 Logged By: Kim Chels-Smith

Client Name: Bechtel Project Name: TP COL Checked By:

Well Installation Date: 5-14-08 Start Date: 4-23-08 Finish Date: 5-14-08

Well Development Date: 5-17-08 Start Time: 1002 Finish Time: 1132

Initial Water Level (ft.): 0.48' From TOC

Water Level during Initial Pumping/Purging (ft.): 0.88' From TOC

Water Level at Termination of Pumping/Purging (ft.): 0.68' From TOC

Weather: Sunny ~ 80°F

Height of Water Column: _____ (ft.) x _____ gal./ft. (2 in.) = _____ gal./ft. (4 in.)

_____ gal./ft. (6 in.) = _____ gal./ft. (_____ in.) = _____ Well Volume (gal./ft.)

Handwritten: Hy 5-17-08
see notes

0.88'
0.89'
0.88'
0.88'

Number of Well Volumes:	Time:	Temperature: °C	pH: su	Conductivity: mS/cm	Approximate Pumping Rate (gal./min.):	Turbidity (NTU's):
1) 26 gal.	1011	27.95	6.43	9.29	3.1 gpm	197
2) 52 gal.	1020	29.03	7.01	9.04	↓	153
3) 78 gal.	1029	31.00	7.02	8.64	↓	107
4) 104 gal.	1038	31.55	7.08	8.96	3.1 gpm	104
5) 130 gal.	1047	28.59	7.09	9.04	↓	101
6) 156 gal.	1056	28.82	7.08	8.98	↓	20
7) 182 gal.	1105	28.60	7.07	9.03	3.1 gpm	8
8) 208 gal.	1114	28.61	7.08	9.03	↓	7 <i>Hy 5-17-08</i>
9) 234 gal.	1123	28.65	7.07	9.01	↓	55
10) 260 gal.	1132	28.59	7.09	9.03	↓	3

Notes: Surged well pump + screen for entire 1st well volume at which pumping. Water is gray w/very Fine Sand. Set pump in middle of screen. - see well volume calculation spreadsheet for volume calcs.

Well Developers Signature: Kim Chels-Smith

FIGURE 9

Well Development Record

Well No.: **OW-606U**

Project No. **6468-07** Logged By: **Kim**
 Client Name: **Bechtel** Project Name: **TPCOL** Checked By:
 Well Installation Date: **4-22-08** Start Date: **4-22-08** Finish Date: **4-22-08**
 Well Development Date: **5-1-08** Start Time: **1107** Finish Time: **1137**
 Initial Water Level (ft.): **Artesia Flawing**
 Water Level during Initial Pumping/Purging (ft.): **0.24' From TOC**
 Water Level at Termination of Pumping/Purging (ft.): **0.35' From TOC**
 Weather: **Sunny ~ 75°F**

Height of Water Column: _____ (ft.)
 _____ gal./ft. (2 in.)
 x _____ gal./ft. (4 in.)
 _____ gal./ft. (8 in.)
 _____ gal./ft. (_____ in.) = _____ Well Volume (gal./ft.)

See notes
KJ 5-1-08

Water level below toe

	Number of Well Volumes:	Time:	Temperature:	pH:	Conductivity:	Approximate Pumping Rate (gal./min.):	Turbidity (NTU's):
0.24'	(1) 13 gal.	1110	27.74	7.14	62.8	5 gpm	6.93
	(2) 26 gal.	1113	27.83	7.13	62.9	5 gpm	2.69
	(3) 39 gal.	1116	27.84	7.13	63.0	5 gpm	1.67
0.24'	(4) 52 gal.	1119	27.83	7.12	63.3	5 gpm	1.43
	(5) 65 gal.	1122	27.85	7.14	63.4	5 gpm	1.24
	(6) 78 gal.	1125	27.38	7.15	63.7	5 gpm	1.01
0.20'	(7) 91 gal.	1128	27.41	7.13	63.4	5 gpm	0.96
	(8) 104 gal.	1131	28.01	7.14	63.1	5 gpm	0.80
	(9) 117 gal.	1134	28.03	7.14	63.4	5 gpm	0.75
0.20'	(10) 130 gal.	1137	28.03	7.16	63.2	5 gpm	0.53

Notes: — Surged well with Grindfos to remove sediment from bottom of well.
 — See well volume calculation sheet for volume calcs.

Well Developers Signature: *Kim [Signature]*

FIGURE 9

Well Development Record

Well No.:

OW-621L

Project No. 6468-07-1950

Logged By: Kim Chalo-Smith

Client Name: Bedford

Project Name: TPCOL

Checked By:

Well Installation Date: 4-18-08

Start Date: 4-17-08

Finish Date: 4-18-08

Well Development Date: 5-3-08

Start Time: 1335

Finish Time: 1505

Initial Water Level (ft.): 0' Artesian Flowing 4/5-3-08 4/5-3-08

Water Level during Initial Pumping/Purging (ft.): 0' Artesian Flowing 0.80'

Water Level at Termination of Pumping/Purging (ft.): 0.80' 5-3-08

Weather: Sunny ~ 80°F

Height of Water Column: _____ ft. x _____ gal./ft. (2 in.)
 _____ gal./ft. (4 in.)
 _____ gal./ft. (6 in.)
 _____ gal./ft. (_____ in.) = _____ Well Volume (gal./ft.)

5-3-08 KJ see notes

Water level below T&C

Number of Well Volumes:	Time:	Temperature: °C	pH: Su	Conductivity: mS/cm	Approximate Pumping Rate (gal./min.):	Turbidity (NTU's):
0.80' (1) 26 gal.	1344	28.62	6.98	55.3	3.0 gpm	56.9
(2) 52 gal.	1353	28.27	7.00	56.3	3.0 gpm	17.6
0.80' (3) 78 gal.	1402	28.21	7.07	57.0	3.0 gpm	11.8
(4) 104 gal.	1411	28.46	7.11	57.4	3.0 gpm	6.08
0.80' (5) 130 gal.	1420	28.20	7.12	57.6	3.0 gpm	5.23
(6) 156 gal.	1429	28.43	7.12	57.8	3.0 gpm	3.97
(7) 182 gal.	1438	28.33	7.13	57.9	3.0 gpm	3.90
0.81' (8) 208 gal.	1447	28.36	7.13	58.0	3.0 gpm	3.52
(9) 234 gal.	1456	28.27	7.12	58.1	3.0 gpm	3.54
0.80' (10) 260 gal.	1505	28.17	7.13	58.1	3.0 gpm	3.04
_____	_____	_____	_____	_____	_____	_____
_____	_____	_____	_____	_____	_____	_____
_____	_____	_____	_____	_____	_____	_____
_____	_____	_____	_____	_____	_____	_____
_____	_____	_____	_____	_____	_____	_____

Notes: Set Grundfos approx. 2' above screen and surged well w/pump to clean out sump. cannot pump.
 - see well volume calculation spreadsheet for volume calcs.

Well Developers Signature: Kim Chalo-Smith

FIGURE 9

Well Development Record

Well No.: **OW-6214**

Project No. **6468-07-1950** Logged By: **Kim Chab-Smith**

Client Name: **Bechtel** Project Name: **TPCOL 4-18-08** Checked By:

Well Installation Date: **4-19-08** Start Date: **5-3-08** Finish Date: **4-19-08**

Well Development Date: **5-3-08** Start Time: **1554 hrs** Finish Time: **1624**

Initial Water Level (ft.): **1.166'** **5308**

Water Level during Initial Pumping/Purging (ft.): **1.86'**

Water Level at Termination of Pumping/Purging (ft.): **1.88'**

Weather: **Sunny ~ 80°F**

Height of Water Column: _____ 0.16 gal./ft. (2 in.)
 _____ (ft.) x _____ 0.65 gal./ft. (4 in.)
 _____ 1.5 gal./ft. (6 in.)
 _____ gal./ft. (_____ in.) = _____ Well Volume (gal./ft.)

Handwritten: **5-3-08 See notes**

Number of Well Volumes:	Time:	Temperature: °C	pH:	Conductivity: µS/cm	Approximate Pumping Rate (gal./min.):	Turbidity (NTU's):
1.86' (1) 13 gal.	1557	29.07	7.17	54.9	5 gpm	24.5
(2) 26 gal.	1600	28.67	7.17	55.0	5 gpm	12.5
1.86' (3) 39 gal.	1603	28.54	7.17	54.8	5 gpm	8.12
(4) 52 gal.	1606	28.44	7.16	54.9	5 gpm	6.67
1.88' (5) 65 gal.	1609	28.40	7.16	55.0	5 gpm	5.58
(6) 78 gal.	1612	28.64	7.16	55.0	5 gpm	3.97
1.88' (7) 91 gal.	1615	28.55	7.16	55.1	5 gpm	3.59
(8) 104 gal.	1618	28.46	7.15	55.1	5 gpm	3.46
(9) 117 gal.	1621	28.48	7.15	55.2	5 gpm	2.07
1.88' (10) 130 gal.	1624	28.65	7.15	55.2	5 gpm	2.19
	5-3-08					

Notes: **Set Grundfos Approx. 2' Above bottom of well surged well while pumping.**
- See well volume calculation sheet for volume calcs.

Well Developers Signature: *Kim Chab-Smith*

FIGURE 9

Well Development Record Well No.: 0W-636L

Project No. 6468-07-1950 Logged By: Kim Charles - Smith
 Client Name: Bechtel KY Project Name: TPCOL # 5508 Checked By:
 Well Installation Date: 4-4-08 ⁵⁻⁵⁻⁰⁸ 4-6-08 Start Date: 4-6-08 Finish Date: 4-6-08
 Well Development Date: 5-5-08 Start Time: 0958 Finish Time: 1138

Initial Water Level (ft.): 2.16'
 Water Level during Initial Pumping/Purging (ft.): 3.92'
 Water Level at Termination of Pumping/Purging (ft.): 2.07'
 Weather: Sunny ~ 84°F

Height of Water Column: _____ (ft.) x _____ gal./ft. (____ in.) = _____ Well Volume (gal./ft.)
~~0.16 gal./ft. (2 in.)~~
~~0.65 gal./ft. (4 in.)~~
~~1.5 gal./ft. (6 in.)~~
 KJ 5-5-08 See notes

Water level from TAC
 # 5-5-08
3.92
4.12'
4.10'
4.09'
4.07'
4.06'

Number of Well Volumes:	Time:	Temperature: °C	pH: SU	Conductivity: mS/cm	Approximate Pumping Rate (gal./min.):	Turbidity (NTU's):
(1) 24 gal.	1008	29.46	7.05	36.4	2.5 gpm	2.73
(2) 48 gal.	1018	29.28	7.01	36.2	2.5 gpm	1.23
(3) 72 gal.	1028	29.34	7.05	36.4	3.0 gpm	1.13
(4) 96 gal.	1038	29.40	7.01	36.7	3.0 gpm	1.31
(5) 120 gal.	1048	29.43	7.02	37.1	3.0 gpm	1.34
(6) 144 gal.	1058	29.49	7.02	37.1	3.0 gpm	1.32
(7) 168 gal.	1108	29.56	7.02	37.4	3.0 gpm	1.21
(8) 192 gal.	1118	29.64	7.03	37.4	3.0 gpm	1.15
(9) 216 gal.	1128	29.96	7.03	37.5	3.0 gpm	0.88
(10) 240 gal.	1138	29.62	7.04	37.7	3.0 gpm	0.84

Notes: Set Grundfos pump approx 2' above sump and surge well with pump running for first volume.
 - See well volume calculation spreadsheet for volume calcs.

Well Developers Signature: Kim Charles - Smith

FIGURE 9

Well Development Record

Well No.:

OW-636U

Project No. CA68-07-1950

Logged By: Kim Charles Smith

Client Name: Bechtel

Project Name: TPCOL

Checked By:

Well Installation Date: 4-3-08

Start Date: 4-3-08

Finish Date: 4-3-08

Well Development Date: 5-5-08

Start Time: 0906

Finish Time: 0924

Initial Water Level (ft.): 3.90'

Water Level during Initial Pumping/Purging (ft.): 3.90'

Water Level at Termination of Pumping/Purging (ft.): 2.95'

Weather: Sunny ~ 84°F

Height of Water Column: _____
 _____ (ft.)
 _____ 0.16 gal./ft. (2 in.)
 _____ 0.65 gal./ft. (4 in.)
 _____ 1.5 gal./ft. (6 in.)
 _____ gal./ft. (_____ in.)

KJ 5-5-08
See notes

Well Volume (gal./ft.)

Water level below TOC

3.90'

3.90'

3.08'

3.08'

Number of Well Volumes:	Time:	Temperature: °C	pH:	Conductivity: µS/cm	Approximate Pumping Rate (gal./min.):	Turbidity (NTU's):
(1) 10 gal.	0906	26.70	7.03	46.9	5 gpm	3.13
(2) 20 gal.	0908	27.04	6.91	41.3	↓	1.51
(3) 30 gal.	0910	27.15	6.95	42.2	↓	0.85
(4) 40 gal.	0912	27.22	6.99	42.6	↓	1.50
(5) 50 gal.	0914	27.27	7.01	42.8	5 gpm	0.72
(6) 60 gal.	0916	27.31	7.00	42.8	↓	0.40
(7) 70 gal.	0918	27.24	7.01	42.8	↓	0.67
(8) 80 gal.	0920	27.31	7.00	43.1	↓	0.61
(9) 90 gal.	0922	27.33	7.02	43.1	↓	0.70
(10) 100 gal.	0924	27.31	7.02	43.2	5 gpm	0.83
_____	_____	_____	_____	_____	_____	_____
_____	_____	_____	_____	_____	_____	_____
_____	_____	_____	_____	_____	_____	_____
_____	_____	_____	_____	_____	_____	_____
_____	_____	_____	_____	_____	_____	_____

Notes:

KJ 5-5-08
 Set Granafos 2' above surge and surged well with pump running for first volume - see well volume calculator spreadsheet for volume calcs.


Well Developers Signature: Kim Charles Smith

FIGURE 9

Well Development Record

Well No.:

Project No: ALB-07-1950 Logged By: Kim Chris Smith AW-706L
 Client Name: Bechtel Project Name: TR COL Checked By:
 Well Installation Date: 3-22-08 to 3-25-08 Start Date: 3-22-08 Finish Date: 3-25-08
 Well Development Date: 4-30-08 Start Time: 1230 Finish Time: 1420
 Initial Water Level (ft.): 0.21' from TOC (Artesian)
 Water Level during Initial Pumping/Purging (ft.): 1.07' H₂O 4-30-08
 Water Level at Termination of Pumping/Purging (ft.): 0.30' below TOC
 Weather: Sunny ~ 75°F 0.52'



TOC
water level

1.07'
1.19'
1.19'
1.21'

Number of Well Volumes:	Time:	Temperature: °C	pH:	Conductivity: MFCM	Approximate Pumping Rate (gal./min.):	Turbidity (NTU's):
(1) 25 gal.	1245	29.84	7.06	49.0	2.5 gpm	2.19
(2) 50 gal.	1255	27.67	7.00	49.3	2.5 gpm	0.75
(3) 75 gal.	1310	27.50	7.06	50.9	2.5 gpm	0.58
(4) 100 gal.	1320	27.62	7.99	52.1	2.5 gpm	0.68
(5) 125 gal.	1330	27.66	7.00	52.4	2.5 gpm	0.80
(6) 150 gal.	1340	27.63	7.00	53.1	2.5 gpm	0.56
(7) 175 gal.	1350	27.64	7.01	53.5	2.5 gpm	0.73
(8) 200 gal.	1400	27.81	7.00	53.4	2.5 gpm	0.44
(9) 225 gal.	1410	27.71	6.99	54.4	2.5 gpm	0.38
(10) 250 gal.	1420	27.78	7.00	54.5	2.5 gpm	0.40
_____	_____	_____	_____	_____	_____	_____
_____	_____	_____	_____	_____	_____	_____
_____	_____	_____	_____	_____	_____	_____
_____	_____	_____	_____	_____	_____	_____

Notes: Set Granafos ~ 2' above bottom of well surged well while running pump until water ran clear, Approx. 5-10 gallons.

Well Developers Signature: Kim Chris Smith

FIGURE 9

See well volume calculation spread sheet for volume calcs.

Well Development Record

Well No.:

00-7060

Project No. 6468-07-1950 Logged By: Kim Charles Smith

Client Name: Bechtel Project Name: TPCOL Checked By:

Well Installation Date: 3-26-08 to 3-27-08 Start Date: 3-26-08 Finish Date: 3-27-08


Well Development Date: 4-30-08 Start Time: 1509 Finish Time: 1539

Initial Water Level (ft.): 1.60' from TOC

Water Level during Initial Pumping/Purging (ft.): 1.68' below toe

Water Level at Termination of Pumping/Purging (ft.): 1.62' below toe

Weather: Sunny ~ 75°F



Water level from TOC

	Number of Well Volumes:	Time:	Temperature: °C	pH: Su	Conductivity: µS/cm	Approximate Pumping Rate (gal./min.):	Turbidity (NTU's):
<u>1.68'</u>	<u>(1) 11 gal.</u>	<u>1512</u>	<u>28.83</u>	<u>6.86</u>	<u>82.5</u>	<u>4.0 gpm</u>	<u>5.99</u>
<u>1.72'</u>	<u>(2) 22 gal.</u>	<u>1515</u>	<u>28.51</u>	<u>6.85</u>	<u>83.1</u>	<u>5.0 gpm</u>	<u>5.99</u>
	<u>(3) 33 gal.</u>	<u>1518</u>	<u>27.66</u>	<u>6.89</u>	<u>83.1</u>	<u>5.0 gpm</u>	<u>7.33</u>
	<u>(4) 44 gal.</u>	<u>1521</u>	<u>28.50</u>	<u>6.86</u>	<u>82.4</u>	<u>5.0 gpm</u>	<u>4.20</u>
<u>1.76'</u>	<u>(5) 55 gal.</u>	<u>1524</u>	<u>28.25</u>	<u>6.84</u>	<u>82.7</u>	<u>5.0 gpm</u>	<u>3.38</u>
	<u>(6) 66 gal.</u>	<u>1527</u>	<u>28.26</u>	<u>6.86</u>	<u>82.6</u>	<u>5.0 gpm</u>	<u>3.50</u>
<u>1.76'</u>	<u>(7) 77 gal.</u>	<u>1530</u>	<u>28.20</u>	<u>6.86</u>	<u>82.3</u>	<u>5.0 gpm</u>	<u>2.18</u>
	<u>(8) 88 gal.</u>	<u>1533</u>	<u>27.85</u>	<u>6.84</u>	<u>82.7</u>	<u>5.0 gpm</u>	<u>2.77</u>
<u>1.76'</u>	<u>(9) 99 gal.</u>	<u>1536</u>	<u>27.64</u>	<u>6.86</u>	<u>82.6</u>	<u>5.0 gpm</u>	<u>1.80</u>
<u>1.76'</u>	<u>(10) 110 gal.</u>	<u>1539</u>	<u>27.66</u>	<u>6.86</u>	<u>82.8</u>	<u>5.0 gpm</u>	<u>1.82</u>

Notes: Set Grundfos pump ~ 2' from bottom of well. Surged well w/pump until water ran clear approx. 5 gallons. *Ref 4-30-08*

See well volume calculation spreadsheet for volume calcs.

Well Developers Signature: Kim Charles Smith

FIGURE 9

Well Development Record

Well No.:

OW-721L

Project No. 6468-07-1950

Logged By: Kim Chels Smith

Client Name: Bechtel

Project Name: TPCOL

Checked By:

Well Installation Date: 5-3-08

Start Date: 5-2-08

Finish Date: 5-3-08

Well Development Date: 5-4-08

Start Time: 1101

Finish Time: 1337

Initial Water Level (ft.): 1.93'

Water Level during Initial Pumping/Purging (ft.): 4.40'

Water Level at Termination of Pumping/Purging (ft.): 2.56'

Weather: Sunny ~ 80°F

Height of Water Column: _____ (ft.)

0.16 gal./ft. (2 in.)

0.65 gal./ft. (4 in.)

1.5 gal./ft. (6 in.)

gal./ft. (in) = _____

Well Volume (gal./ft.)

~~See notes~~
5-4-08

water level from TOC

4.40'
193 feet
5-4-08
3.59'
3.95'
3.87'
3.87'

Number of Well Volumes:	Time:	Temperature: °C	pH:	Conductivity: mS/cm	Approximate Pumping Rate (gal./min.):	Turbidity (NTU's):
1) 23 gal.	1127	29.38	7.12	51.1	2.25 gpm	71000
2) 46 gal.	1137	29.32	7.07	42.8	2.25 gpm	146
3) 69 gal.	1147	29.30	7.06	42.0	2.25 gpm	106
4) 92 gal.	1157	29.38	7.07	42.0	2.25 gpm	86.8
5) 115 gal.	1207	29.45	7.06	42.1	2.25 gpm	78.8
6) 138 gal.	1217	29.35	7.06	41.2	2.25 gpm	72.4
7) 161 gal.	1227	29.56	7.07	42.3	2.25 gpm	72.6
8) 184 gal.	1237	29.33	7.05	42.9	2.25 gpm	21.8
9) 207 gal.	1247	29.30	7.05	42.8	2.25 gpm	16.5
10) 230 gal.	1257	29.31	7.06	42.5	2.25 gpm	28.9
11) 253 gal.	1317	29.69	7.05	42.5	2.25 gpm	16.2
12) 276 gal.	1337	29.44	7.05	42.5	2.25 gpm	8.41
_____	_____	_____	_____	_____	_____	_____
_____	_____	_____	_____	_____	_____	_____
_____	_____	_____	_____	_____	_____	_____

Notes: Set Grandfos approx 2' above suspended stage well with pump.
- see well volume calculator sheet for volume calcs.

Well Developers Signature: Kim Chels Smith

FIGURE 9

Well Development Record

Well No.:

OW-7214

Project No. 668-07-1950

Logged By: Kim Chab-Smith

Client Name: Bechtel

Project Name: TPCOL

Checked By:

Well Installation Date: 5-2-08

Start Date: 5-2-08

Finish Date: 5-2-08

Well Development Date: 5-4-08

Start Time: 0948

Finish Time: 1008

Initial Water Level (ft.): 0.84'

Water Level during Initial Pumping/Purging (ft.): 1.86'

Water Level at Termination of Pumping/Purging (ft.): 0.97'

Weather: Sunny ~ 80°F

Height of Water Column (ft.)

0.16 gal./ft. (2 in.)

x 5-4-08

0.65 gal./ft. (4 in.)

1.5 gal./ft. (6 in.)

gal./ft. (in.)

See notes

Well Volume (gal./ft.)

water level
From TOC

1.86'

1.73'

1.50'

1.49'

Number of Well Volumes:	5-4-08 Time:	Temperature: °C	pH:	Conductivity: $\mu\text{S}/\text{cm}$	Approximate Pumping Rate (gal./min.):	Turbidity (NTU's):
(1) 10 gal.	0950	27.76	6.69	41.0	5 gpm	54.8
(2) 20 gal.	0952	28.07	7.00	42.4	↓	25.4
(3) 30 gal.	0954	28.64	7.03	42.3	↓	14.2
(4) 40 gal.	0956	28.77	7.06	43.0	5 gpm	14.6
(5) 50 gal.	0958	28.79	7.05	43.1	↓	16.9
(6) 60 gal.	1000	28.74	7.08	43.5	5 gpm	9.73
(7) 70 gal.	1002	28.84	7.07	43.3	↓	7.92
(8) 80 gal.	1004	28.93	7.08	43.2	↓	7.14
(9) 90 gal.	1006	28.95	7.07	43.0	5 gpm	6.31
(10) 100 gal.	1008	28.96	7.07	43.1	5 gpm	5.03

Notes: Set Grundfos Approx 2' above bottom of well + Surged to clean out sump.
- See well volume calculation spreadsheet for volume calcs.

Well Developers Signature: Kim Chab-Smith

FIGURE 9

Well Development Record

Well No.:

OW-735L

Project No. 6468-07-1950 Logged By: Kim Chris Smith

Client Name: Bechtel Project Name: TPCOL Checked By:

Well Installation Date: 4-15-08 to 4-19-08 Start Date: 4-15-08 Finish Date: 4-19-08

Well Development Date: 4-29-08/4-30-08 Start Time: 1440 Finish Time: 0932

Initial Water Level (ft.): 0.34' from TOC 4-29-08 4-30-08

Water Level during Initial Pumping/Purging (ft.): 0.49'

Water Level at Termination of Pumping/Purging (ft.): TOC (Artesian)

Weather: Sunny / partly cloudy 72°F

4-30-08 See notes

Height of Water Column: _____ (ft.) x _____ 0.16 gal./ft. (2 in.)
 _____ x _____ 0.65 gal./ft. (4 in.)
 _____ x _____ 1.5 gal./ft. (6 in.)
 _____ gal./ft. (_____ in.) = _____ Well Volume (gal./ft.)

water level from TOC

Number of Well Volumes:	Time:	Temperature: °C	pH:	Conductivity: mS/cm	Approximate Pumping Rate (gal./min.):	Turbidity (NTU's):
0.83' { 1) 25 gal.	1430	29.51	6.63	62.8	2.5 gpm	25.3
{ 2) 50 gal.	1440	29.44	6.64	62.5	2.5 gpm	14.4
{ 3) 75 gal.	1450	29.31	6.65	62.6	2.5 gpm	9.95
{ 4) 100 gal.	1500	29.19	6.65	62.5	2.5 gpm	9.59
0.84' { 5) 125 gal.	1510	28.93	6.66	62.3	2.5 gpm	7.94
{ 6) 150 gal.	1520	28.71	6.66	62.1	2.5 gpm	7.26
{ 7) 175 gal.	1530	28.72	6.65	62.2	2.5 gpm	7.45
{ 8) 200 gal.	1540	28.71	6.66	62.5	2.5 gpm	6.24
0.65' { 9) 225 gal.	0922	27.38	6.65	79.0	2.5 gpm	8.21
{ 10) 250 gal.	0932	28.41	6.67	82.9	2.5 gpm	4.42
_____	_____	_____	_____	_____	_____	_____
_____	_____	_____	_____	_____	_____	_____
_____	_____	_____	_____	_____	_____	_____
_____	_____	_____	_____	_____	_____	_____
_____	_____	_____	_____	_____	_____	_____

Notes:
 Set Grundfos pump ~ 2' from bottom of well tagged T.D. Surged well w/pump and lowered pump to clean out Sediment.
 Completed well Development volumes 9 + 10 on 4-30-08 due to Thunder rain on 4-29-08.

Well Developers Signature: Kim Chris Smith

FIGURE 9

See well volume calculation sheet for volume calcs.

Well Development Record

Well No.:

OW-7354

Project No. CA68-07-1950 Logged By: Kim Cholo-Smith

Client Name: Bechtel Project Name: TP COL Checked By:

Well Installation Date: 4-20-08 Start Date: 4-20-08 Finish Date: 4-20-08


Well Development Date: 4-29-08 Start Time: 1130 Finish Time: 1353

Initial Water Level (ft.): 2.0' from TOC

Water Level during Initial Pumping/Purging (ft.): Unchanged - 2.04'

Water Level at Termination of Pumping/Purging (ft.): 2.03'

Weather: SUNNY ~ 75°F



Water level

2.03'
2.04'
2.02'
2.03'

Number of Well Volumes:	Time:	Temperature:	pH:	See note Conductivity: ms/cm	Approximate Pumping Rate (gal./min.):	Turbidity (NTU's):
1 (10 gal.)	1130	28.12	6.77	60.5	2.0 gpm	17.7
2 (20 gal.)	1141	29.83	6.89	60.4	2.0 gpm	12.0
3 (30 gal.)	1156	30.31	6.88	60.5	2.5 gpm	7.96
4 (40 gal.)	1200	29.25	6.48	60.4	2.5 gpm	5.82
5 (50 gal.)	1335	29.70	6.73	61.7	2.5 gpm	2.71
6 (60 gal.)	1339	29.95	6.77	62.0	3.0 gpm	4.34
7 (70 gal.)	1344	29.77	6.78	62.5	4.0 gpm	7.65
8 (80 gal.)	1347	29.72	6.79	62.2	4.0 gpm	8.80
9 (90 gal.)	1350	29.81	6.80	62.1	4.5 gpm	8.41
10 (100 gal.)	1353	29.93	6.81	62.5	4.5 gpm	8.20

Notes:

- Grundfos pump set approximately 2.0' off bottom of tagged T.D
- Surged well for first 3 vol. by turning off pump and allowing well to settle then turning pump again.
- Lowered pump to bottom of well @ approximately 50 gal.

Well Developers Signature: Kim Cholo-Smith

FIGURE 9

note: had a problem with conductivity, had to clean probes. First two conductivity readings not valid.

Well Development Record

Well No.:

OW-802L

Project No. 4468-07-1950

Logged By: Kim Chads Smith

Client Name: Bechtel

Project Name: TPCD

Checked By:

Well Installation Date: 5-4-08

Start Date: 5-3-08

Finish Date: 5-4-08

Well Development Date: 5-5-08

Start Time: 1451


Finish Time: 1631

Initial Water Level (ft.): Artesian Flowing

Water Level during Initial Pumping/Purging (ft.): 0.77'

Water Level at Termination of Pumping/Purging (ft.): 0.28'

Weather: Sunny ~ 84°F



water level from TOC

0.77'
0.81'
0.86'
0.87'
0.89'

Number of Well Volumes:	Time:	Temperature: °C	pH:	Conductivity: mS/cm	Approximate Pumping Rate (gal./min.):	Turbidity (NTU's):
1) 24 gal.	1501	29.39	6.86	49.9	3.0 gpm	0.49
2) 48 gal.	1509	29.40	6.88	50.5		0.42
3) 72 gal.	1517	28.95	6.92	50.7		0.35
4) 96 gal.	1525	29.12	6.93	51.0		0.32
5) 120 gal.	1533	29.22	6.96	51.7	↓	0.44
6) 144 gal.	1541	28.97	6.95	51.8	3.0 gpm	0.29
7) 168 gal.	1549	28.76	6.95	52.4		0.77
8) 192 gal.	1557	28.65	6.95	52.6		0.59
9) 216 gal.	1605	28.59	6.94	52.9	↓	0.65
10) 240 gal.	1613	28.61	6.94	52.8	3.0 gpm	0.36
	1621					
	Key 5-5-08					

Notes: Surged Samp w/ gradients while pumping, for first well volumes removed.
 - See well volume calculation spreadsheet for volume calcd.

Well Developers Signature: Kim Chads Smith

FIGURE 9

Well Development Record

Well No.: 00-8024

Project No. 6468-07-1950 Logged By: Kim Charles Smith
 Client Name: Bechtel Project Name: TPCOL Checked By: _____
 Well Installation Date: 5-4-08 Start Date: 5-4-08 Finish Date: 5-4-08
 Well Development Date: 5-7-08 Start Time: 5:30 AM Finish Time: 1:13 PM
 Initial Water Level (ft.): 2.10' K 5-7-08 15135-08
 Water Level during Initial Pumping/Purging (ft.): 2.10' 2.64' 155 AM 5-7-08
 Water Level at Termination of Pumping/Purging (ft.): 2.99'

Weather: Sunny ~ 85°F

Height of Water Column: _____ (ft.) x _____ gal./ft. (2 in.) see notes
 _____ gal./ft. (4 in.) K 5-7-08
 _____ gal./ft. (6 in.)
 _____ gal./ft. (_____ in.) = _____ Well Volume (gal./ft.)

Water level from TAC

2.64'
2.65'
2.67'
2.68'
2.68'

Number of Well Volumes:	Time:	Temperature: °C	pH: SU	Conductivity: mS/cm	Approximate Pumping Rate (gal./min.):	Turbidity (NTU's):
1) 10 gal.	<u>151355</u>	<u>28.97</u>	<u>6.36</u>	<u>66.5</u>	<u>5 gpm</u>	<u>4.92</u>
2) 20 gal.	<u>151357</u>	<u>28.68</u>	<u>6.70</u>	<u>68.6</u>	<u>↓</u>	<u>2.49</u>
3) 30 gal.	<u>151359</u>	<u>28.66</u>	<u>6.75</u>	<u>69.8</u>	<u>5 gpm</u>	<u>1.87</u>
4) 40 gal.	<u>151401</u>	<u>28.64</u>	<u>6.76</u>	<u>70.4</u>	<u>↓</u>	<u>1.84</u>
5) 50 gal.	<u>151403</u>	<u>28.58</u>	<u>6.77</u>	<u>70.2</u>	<u>↓</u>	<u>1.76</u>
6) 60 gal.	<u>151405</u>	<u>28.70</u>	<u>6.75</u>	<u>70.6</u>	<u>5 gpm</u>	<u>1.25</u>
7) 70 gal.	<u>151407</u>	<u>28.68</u>	<u>6.81</u>	<u>70.7</u>	<u>↓</u>	<u>1.19</u>
8) 80 gal.	<u>151409</u>	<u>28.70</u>	<u>6.82</u>	<u>71.1</u>	<u>↓</u>	<u>1.16</u>
9) 90 gal.	<u>151411</u>	<u>28.69</u>	<u>6.82</u>	<u>71.1</u>	<u>5 gpm</u>	<u>1.06</u>
10) 100 gal.	<u>151413</u>	<u>28.71</u>	<u>6.82</u>	<u>71.3</u>	<u>5 gpm</u>	<u>0.82</u>
	<u>K 5-7-08</u>					

Notes: Surged sump with Grundfos for 1st volume until water ran clear.
 - See well volume calculation spreadsheet for volume calcs.

Well Developers Signature: Kim Charles Smith

FIGURE 9

Well Development Record

Well No.:

aw-809L

Project No. LA68-07-1950 Logged By: Kim Chels-Smith

Client Name: Dechdel Project Name: TRCOL Checked By:

Well Installation Date: 5-07-08 Start Date: 5-5-08 Finish Date: 5-7-08

Well Development Date: 5-13-08 Start Time: 1337 Finish Time: 1507

Initial Water Level (ft.): 3.36'

Water Level during Initial Pumping/Purging (ft.): 3.92'

Water Level at Termination of Pumping/Purging (ft.): 3.44'

Weather: Sunny ~ 85°F

Height of Water Column: _____ 0.16 gal./ft. (2 in.)
 _____ (ft.) x _____ 0.65 gal./ft. (4 in.)
 _____ 1.5 gal./ft. (6 in.)
 _____ gal./ft. (in.) = _____ Well Volume (gal./ft.)

KCS 5-13-08 See notes

3.92'
KCS 5-13-08
 3.94'
KCS 5-13-08
 3.95'
 3.92'

Number of Well Volumes:	Time:	Temperature: °C	pH: su	Conductivity: µS/cm	Approximate Pumping Rate (gal./min.):	Turbidity (NTU's):
1) 23 gal.	1346	31.38	6.71	40.5	2.8 gpm	13.3
2) 46 gal.	1355	29.76	6.66	40.8	↓	7.47
3) 69 gal.	1404	29.78	6.67	41.1	↓	5.31
4) 92 gal.	1413	29.60	6.68	41.5	2.8 gpm	3.83
5) 115 gal.	1422	29.75	6.70	41.8	↓	2.96
6) 138 gal.	1431	29.76	6.71	42.1	↓	2.45
7) 161 gal.	1440	29.72	6.70	42.7	↓	2.43
8) 184 gal.	1449	29.74	6.72	43.0	↓	2.49
9) 207 gal.	1458	29.81	6.73	43.3	2.8 gpm	2.06
10) 230 gal.	1507	29.77	6.72	43.3		2.05

Notes: *KCS 5-13-08 KCS 5-13-08*
 Surged sand pump sump w/Grundfos to remove sediment. Set pump in middle of screen and removed 10 well volumes.
 - See well volume calculator spreadsheet for volume calcs.

Well Developers Signature: Kim Chels-Smith

FIGURE 9

Well Development Record

Well No.:

0W-809U

Project No. 6468-07-1950

Logged By: *Kim Clark-Smith*

Client Name: *Bechtel*

Project Name: *TPOA*

Checked By:

Well Installation Date: *4-1-08*

Start Date: *4-1-08*

Finish Date: *4-1-08*

Well Development Date: *5-1-08*

Start Time: *0844*

Finish Time: *0910*

Initial Water Level (ft.): *2.79'*

Water Level during Initial Pumping/Purging (ft.): *3.92'*

Water Level at Termination of Pumping/Purging (ft.): *2.82'*

Weather: *Sunny ~ 73°F*

Height of Water Column: _____
 (ft.) x _____
 _____ gal./ft. (2 in.)
 _____ gal./ft. (4 in.)
 _____ gal./ft. (6 in.)
 _____ gal./ft. (_____ in.) =

See notes

Fig 5-1-08

Well Volume (gal./ft.)

*water level
from TOC*

3.92'
2.99'
2.98'
2.98'
2.98'

Number of Well Volumes:	Time:	Temperature: °C	pH: SU	Conductivity: ms/cm	Approximate Pumping Rate (gal./min.):	Turbidity (NTU's):
<i>(1) 10 gal.</i>	<i>0847</i>	<i>26.80</i>	<i>6.38</i>	<i>65.8</i>	<i>4.0 spm</i>	<i>2.37</i>
<i>(2) 20 gal.</i>	<i>0850</i>	<i>27.97</i>	<i>6.91</i>	<i>69.1</i>	<i>4.0 spm</i>	<i>1.86</i>
<i>(3) 30 gal.</i>	<i>0853</i>	<i>29.29</i>	<i>6.96</i>	<i>69.3</i>	<i>4.0 spm</i>	<i>1.53</i>
<i>(4) 40 gal.</i>	<i>0856</i>	<i>29.34</i>	<i>6.99</i>	<i>68.9</i>	<i>4.0 spm</i>	<i>1.46</i>
<i>(5) 50 gal.</i>	<i>0859</i>	<i>29.32</i>	<i>6.97</i>	<i>68.8</i>	<i>4.0 spm</i>	<i>1.48</i>
<i>(6) 60 gal.</i>	<i>0902</i>	<i>29.53</i>	<i>6.99</i>	<i>68.9</i>	<i>5.0 spm</i>	<i>1.23</i>
<i>(7) 70 gal.</i>	<i>0904</i>	<i>29.43</i>	<i>7.00</i>	<i>68.9</i>	<i>5.0 spm</i>	<i>0.63</i>
<i>(8) 80 gal.</i>	<i>0906</i>	<i>29.04</i>	<i>7.02</i>	<i>68.8</i>	<i>5.0 spm</i>	<i>0.92</i>
<i>(9) 90 gal.</i>	<i>0908</i>	<i>29.15</i>	<i>7.01</i>	<i>68.7</i>	<i>5.0 spm</i>	<i>1.29</i>
<i>(10) 100 gal.</i>	<i>0910</i>	<i>29.18</i>	<i>7.00</i>	<i>68.6</i>	<i>5.0 spm</i>	<i>1.58</i>
_____	_____	_____	_____	_____	_____	_____
_____	_____	_____	_____	_____	_____	_____
_____	_____	_____	_____	_____	_____	_____
_____	_____	_____	_____	_____	_____	_____
_____	_____	_____	_____	_____	_____	_____

Notes: - Surged well with Grindfos to remove sediment from bottom of well.
 - See well volume calculation sheet for volume calcs.

Well Developers Signature: *Kim Clark-Smith*

FIGURE 9

Well Development Record

Well No.:

OW - 812L

Project No. <u>6468-07-150</u>	Logged By: <u>Kim Charles Smith</u>	Checked By:	
Client Name: <u>Buchtel</u>	Project Name: <u>TPCOL</u>	Well Installation Date: <u>5-6-08</u> ^{KCS} <u>5-13-08</u>	Start Date: <u>5-6-08</u> Finish Date: <u>5-7-08</u>
Well Development Date: <u>5-13-08</u>	Start Time: <u>1010</u>	Finish Time: <u>1136</u>	
Initial Water Level (ft.): <u>1.46'</u>			
Water Level during Initial Pumping/Purging (ft.): <u>1.90'</u>			
Water Level at Termination of Pumping/Purging (ft.): <u>1.55'</u>			
Weather: <u>Sunny ~ 80°F</u>			

Height of Water Column: _____ (ft.) x _____ gal./ft. (_____ in.) = _____ Well Volume (gal./ft.)

_____ 0.16 gal./ft. (2 in.) ^{Key see notes}
 _____ 0.65 gal./ft. (4 in.) 5-13-08
 _____ 1.5 gal./ft. (6 in.)

1.90'
1.85'
1.85'
1.86'
1.85'

Number of Well Volumes:	Time:	Temperature: °C	pH:	Conductivity: ^{at 5-13-08} 500 <u>ms/cm</u>	Approximate Pumping Rate (gal./min.):	Turbidity (NTU's):
1) 23 gal.	1024	31.74	6.57	<u>43.6</u>	<u>3.0 gpm</u>	0.75
2) 46 gal.	1032	31.23	6.84	42.0	↓	1.23
3) 69 gal.	1040	31.01	6.84	42.5	↓	0.80
4) 92 gal.	1048	30.78	6.84	42.2	↓	0.58
5) 115 gal.	1056	30.93	6.85	42.2	3.0 gpm	0.42
6) 138 gal.	1104	30.83	6.86	42.6	↓	0.63
7) 161 gal.	1112	30.91	6.86	42.6	↓	0.58
8) 184 gal.	1120	30.83	6.86	42.7	↓	0.64
9) 207 gal.	1128	30.77	6.86	42.8	3.0 gpm	0.66
10) 230 gal.	1136	30.80	6.85	42.7	↓	0.51

Notes: Surged well sump with Grundfos to remove sediment set 8 Grundfos pump in screen and removed 10 well volumes.
 - see well volume calculation spreadsheet for volume calcs.

Well Developers Signature: Kim Charles Smith

FIGURE 9

Well Development Record

Well No.:

0W-812U

Project No. 6468-07-1950 Logged By: Kim Chels-Smith

Client Name: Bechtel Project Name: TPCOL Checked By:

Well Installation Date: 5-7-08 Start Date: 5-7-08 Finish Date: 5-7-08

Well Development Date: 5-7-08 Start Time: 1333 Finish Time: 1453

Initial Water Level (ft.): 2.31' 13:45
5-7-08

Water Level during Initial Pumping/Purging (ft.): 2.68'

Water Level at Termination of Pumping/Purging (ft.): 2.45'

Weather: Sunny ~ 85°F

Height of Water Column: _____ 0.16 gal./ft. (2 in.)
 _____ (ft.) * 0.65 gal./ft. (4 in.)
 _____ 1.5 gal./ft. (6 in.)
 _____ gal./ft. (_____ in.)

Well Volume (gal./ft.)

see notes
KJ 5-7-08

Water level from TOC

	Number of Well Volumes:	Time:	Temperature: °C	pH:	Conductivity: mS/cm	Approximate Pumping Rate (gal./min.):	Turbidity (NTU's):
<u>2.68'</u>	<u>1) 10 gal.</u>	<u>1335</u>	<u>32.77</u>	<u>6.80</u>	<u>76.3</u>	<u>5 gpm</u>	<u>5.08</u>
	<u>2) 20 gal.</u>	<u>1337</u>	<u>32.44</u>	<u>6.79</u>	<u>76.7</u>		<u>3.30</u>
	<u>3) 30 gal.</u>	<u>1339</u>	<u>32.90</u>	<u>6.80</u>	<u>79.6</u>		<u>1.89</u>
<u>2.76'</u>	<u>4) 40 gal.</u>	<u>1341</u>	<u>33.05</u>	<u>6.80</u>	<u>77.7</u>	<u>5 gpm</u>	<u>1.26</u>
	<u>5) 50 gal.</u>	<u>1343</u>	<u>33.28</u>	<u>6.81</u>	<u>77.6</u>		<u>0.80</u>
<u>2.78'</u>	<u>6) 60 gal.</u>	<u>1345</u>	<u>33.20</u>	<u>6.81</u>	<u>77.5</u>		<u>0.83</u>
	<u>7) 70 gal.</u>	<u>1347</u>	<u>33.01</u>	<u>6.82</u>	<u>77.8</u>		<u>0.78</u>
<u>2.79'</u>	<u>8) 80 gal.</u>	<u>1349</u>	<u>33.17</u>	<u>6.81</u>	<u>77.7</u>		<u>0.88</u>
	<u>9) 90 gal.</u>	<u>13451</u>	<u>33.16</u>	<u>6.81</u>	<u>77.7</u>	<u>5 gpm</u>	<u>0.67</u>
<u>2.80'</u>	<u>10) 100 gal.</u>	<u>13453</u>	<u>33.10</u>	<u>6.81</u>	<u>77.4</u>	<u>5 gpm</u>	<u>0.51</u>

Notes:
 until Surged Song with grandfos for 1st volume unclear water ran clear.
 KJ 5-7-08
 - See well volume calculator spreadsheet for volume calcs.
 KJ 5-7-08

Well Developers Signature: Kim Chels-Smith

FIGURE 9

Well Sampling Records



MACTEC Engineering and Consulting, Inc.
3301 Atlantic Avenue
Raleigh, North Carolina 27604

OBSERVATION WELL SAMPLING WORKSHEET

OBSERVATION WELL ID: OW-606U		MACTEC JOB NUMBER: 6468-07-1950	
PROJECT: Turkey Point COL Project	SITE: Florida City, Florida	DATE: 5/28/2008	
MEASURED WELL DEPTH: 31.91 FT.	SCREENED INTERVAL: 18-28 FT.	WELL DIAMETER: 2 IN.	
HEIGHT OF MEASURING POINT ABOVE LAND SURFACE: 3.0		CASING MATERIAL: PVC	
SAMPLING DEVICE: See below	TUBING TYPE: Dedicated, Disposable Tubing		
MEASURING POINT: Top of Casing	DEPTH TO GROUNDWATER: 2.71		
SAMPLING PERSONNEL: L. Bisson	WATER-COLUMN HEIGHT: 29.20		
STEEL GUARD PIPE AROUND CASING:	<input checked="" type="checkbox"/> YES	<input type="checkbox"/> NO	
LOCKING CAP:	<input checked="" type="checkbox"/> YES	<input type="checkbox"/> NO	
PROTECTIVE POST/ABUTMENT:	<input type="checkbox"/> YES	<input checked="" type="checkbox"/> NO	
NONPOTABLE LABEL:	<input checked="" type="checkbox"/> YES	<input type="checkbox"/> NO	
ID PLATE:	<input checked="" type="checkbox"/> YES	<input type="checkbox"/> NO	
WELL INTEGRITY SATISFACTORY:	<input checked="" type="checkbox"/> YES	<input type="checkbox"/> NO	
WELL YIELD:	<input checked="" type="checkbox"/> HIGH	<input type="checkbox"/> MODERATE	<input type="checkbox"/> LOW
COMMENTS: Monsoon submersible pump, Horiba U-22 S/N MO15-09.			
Purge volume determined by multiplying water-column height by 0.16 gal/ft for a 2-inch well			

PURGE VOLUME (gallons)	PURGE RATE (gpm)	TEMP (°C)	PH (S.U.)	D.O. (mg/L)	SP. COND. (mS/cm)	TURBIDITY (NTU)	O.R.P. (± mV)	NOTES
12.2	0.4	28.66	6.86	1.65	66.7	2.00	-355	
26.2	0.4	28.70	6.88	1.55	66.9	0.39	-368	
32.6	0.4	28.70	6.84	1.61	66.8	0.46	-339	
39.0	0.4	28.71	6.84	1.66	66.9	0.30	-342	
45.4	0.4	28.71	6.84	1.64	66.9	0.34	-347	
Sample	0.3	28.71	6.84	1.66	66.9	0.34	-344	
Sample collected at 16:10 for the following tests								
TDS - Method 160.1 / Alkalinity - Method 310.1								
Anions and Nitrate/Nitrite - Method 300.0								
Cations - Method 6020								
Ammonia - Method 350.1								
Kd - distribution coefficient								

Observation wells purged in accordance with ASTM D-6452-99

Prepared by: WLB Date: 7-7-08
Checked by: CBS Date: 7/7/08



MACTEC Engineering and Consulting, Inc.
3301 Atlantic Avenue
Raleigh, North Carolina 27604

OBSERVATION WELL SAMPLING WORKSHEET

OBSERVATION WELL ID:	OW-606L		MACTEC JOB NUMBER:	6468-07-1950	
PROJECT:	Turkey Point COL Project	SITE:	Florida Cirty, Florida	DATE:	5/28/2008
MEASURED WELL DEPTH:	111.31 FT.	SCREENED INTERVAL:	97-107 FT.	WELL DIAMETER:	2 IN.
HEIGHT OF MEASURING POINT ABOVE LAND SURFACE:			2.8	CASING MATERIAL: PVC	
SAMPLING DEVICE:	See below	TUBING TYPE:		Dedicated, Disposable Tubing	
MEASURING POINT:	Top of Casing	DEPTH TO GROUNDWATER:		2.30	
SAMPLING PERSONNEL:	K. Charles-Smith	WATER-COLUMN HEIGHT:		109.01	
STEEL GUARD PIPE AROUND CASING:	<input checked="" type="checkbox"/>	YES	<input type="checkbox"/>	NO	
LOCKING CAP:	<input checked="" type="checkbox"/>	YES	<input type="checkbox"/>	NO	
PROTECTIVE POST/ABUTMENT:	<input type="checkbox"/>	YES	<input checked="" type="checkbox"/>	NO	
NONPOTABLE LABEL:	<input checked="" type="checkbox"/>	YES	<input type="checkbox"/>	NO	
ID PLATE:	<input checked="" type="checkbox"/>	YES	<input type="checkbox"/>	NO	
WELL INTEGRITY SATISFACTORY:	<input checked="" type="checkbox"/>	YES	<input type="checkbox"/>	NO	
WELL YIELD:	<input checked="" type="checkbox"/>	HIGH	<input type="checkbox"/>	MODERATE	<input type="checkbox"/> LOW
COMMENTS	Monsoon submersible pump, Horiba U-22 S/N MO15-09.				
	Purge volume determined by multiplying water-column height by 0.16 gal/ft for a 2-inch well				

PURGE VOLUME (gallons)	PURGE RATE (gpm)	TEMP (°C)	PH (S.U.)	D.O. (mg/L)	SP. COND. (mS/cm)	TURBIDITY (NTU)	O.R.P. (± mV)	NOTES
26	0.4	28.78	7.41	10.02	52.6	1.22	-306	
52	0.4	28.32	7.09	9.57	52.8	0.61	-365	
65	0.4	28.38	7.08	9.89	52.9	0.91	-367	
78	0.4	28.14	7.09	9.98	52.7	0.74	-370	
91	0.4	28.09	7.08	9.84	52.7	0.83	-370	
Sample	0.3	28.29	7.08	9.92	52.8	0.77	-370	
Sample collected at 15:40 for the following tests								
Analytical Method								
TDS - Method 160.1 / Alkalinity - Method 310.1								
Anions and Nitrate/Nitrite - Method 300.0								
Cations - Method 6020								
Ammonia - Method 350.1								
Kd - distribution coefficient								

Observation wells purged in accordance with ASTM D-6452-99

Prepared by: WLU Date: 7-7-08
Checked by: CBS Date: 7/7/08



MACTEC Engineering and Consulting, Inc.
3301 Atlantic Avenue
Raleigh, North Carolina 27604

OBSERVATION WELL SAMPLING WORKSHEET

OBSERVATION WELL ID: OW-621U		MACTEC JOB NUMBER: 6468-07-1950						
PROJECT: Turkey Point COL Project	SITE: Florida City, Florida	DATE: 5/29/2008						
MEASURED WELL DEPTH: 32.36 FT.	SCREENED INTERVAL: 17.4-27.4 FT.	WELL DIAMETER: 2 IN.						
HEIGHT OF MEASURING POINT ABOVE LAND SURFACE: 3.30		CASING MATERIAL: PVC						
SAMPLING DEVICE: See below	TUBING TYPE: Dedicated, Disposable Tubing							
MEASURING POINT: Top of Casing	DEPTH TO GROUNDWATER: 5.23							
SAMPLING PERSONNEL: K. Charles-Smith	WATER-COLUMN HEIGHT: 27.13							
STEEL GUARD PIPE AROUND CASING:	<input checked="" type="checkbox"/>	YES	<input type="checkbox"/> NO					
LOCKING CAP:	<input checked="" type="checkbox"/>	YES	<input type="checkbox"/> NO					
PROTECTIVE POST/ABUTMENT:	<input type="checkbox"/>	YES	<input checked="" type="checkbox"/> NO					
NONPOTABLE LABEL:	<input checked="" type="checkbox"/>	YES	<input type="checkbox"/> NO					
ID PLATE:	<input checked="" type="checkbox"/>	YES	<input type="checkbox"/> NO					
WELL INTEGRITY SATISFACTORY:	<input checked="" type="checkbox"/>	YES	<input type="checkbox"/> NO					
WELL YIELD:	<input checked="" type="checkbox"/>	HIGH	<input type="checkbox"/> MODERATE <input type="checkbox"/> LOW					
COMMENTS Monsoon submersible pump, Horiba U-22 S/N MO15-09.								
Purge volume determined by multiplying water-column height by 0.16 gal/ft for a 2-inch well								
PURGE VOLUME (gallons)	PURGE RATE (gpm)	TEMP (°C)	PH (S.U.)	D.O. (mg/L)	SP. COND. (mS/cm)	TURBIDITY (NTU)	O.R.P. (± mV)	NOTES
12	0.4	27.81	7.16	0.07	92.6	21.8	-306	
24	0.4	27.82	7.10	0.05	90.6	3.72	-342	
30	0.4	27.81	7.08	0.05	90.9	2.93	-349	
36	0.4	27.81	7.08	0.05	91.0	2.89	-351	
42	0.4	27.83	7.07	0.05	91.1	2.90	-350	
Sample	0.3	27.82	7.08	0.05	91.0	2.91	-351	
Sample collected at 16:10 for the following tests								
Analytical Method								
TDS - Method 160.1 / Alkalinity - Method 310.1								
Anions and Nitrate/Nitrite - Method 300.0								
Cations - Method 6020								
Ammonia - Method 350.1								
Kd - distribution coefficient								

Observation wells purged in accordance with ASTM D-6452-99

Prepared by: CWSL Date: 7-7-08
Checked by: CBS Date: 7/7/08



MACTEC Engineering and Consulting, Inc.
3301 Atlantic Avenue
Raleigh, North Carolina 27604

OBSERVATION WELL SAMPLING WORKSHEET

OBSERVATION WELL ID:	OW-621L	MACTEC JOB NUMBER:	6468-07-1950
PROJECT:	Turkey Point COL Project	SITE:	Florida City, Florida
MEASURED WELL DEPTH:	111.55 FT.	SCREENED INTERVAL:	98.6-108.6 FT.
HEIGHT OF MEASURING POINT ABOVE LAND SURFACE:	3.0	WELL DIAMETER:	2 IN.
SAMPLING DEVICE:	See below	CASING MATERIAL:	PVC
MEASURING POINT:	Top of Casing	TUBING TYPE:	Dedicated, Disposable Tubing
SAMPLING PERSONNEL:	K. Charles-Smith	DEPTH TO GROUNDWATER:	3.50
STEEL GUARD PIPE AROUND CASING:	<input checked="" type="checkbox"/>	WATER-COLUMN HEIGHT:	108.05
LOCKING CAP:	<input checked="" type="checkbox"/>	YES	<input type="checkbox"/> NO
PROTECTIVE POST/ABUTMENT:	<input type="checkbox"/>	YES	<input checked="" type="checkbox"/> NO
NONPOTABLE LABEL:	<input checked="" type="checkbox"/>	YES	<input type="checkbox"/> NO
ID PLATE:	<input checked="" type="checkbox"/>	YES	<input type="checkbox"/> NO
WELL INTEGRITY SATISFACTORY:	<input checked="" type="checkbox"/>	YES	<input type="checkbox"/> NO
WELL YIELD:	<input checked="" type="checkbox"/>	HIGH	<input type="checkbox"/> MODERATE <input type="checkbox"/> LOW
COMMENTS	Monsoon submersible pump, Horiba U-22 S/N MO15-09.		
	Purge volume determined by multiplying water-column height by 0.16 gal/ft for a 2-inch well		

PURGE VOLUME (gallons)	PURGE RATE (gpm)	TEMP (°C)	PH (S.U.)	D.O. (mg/L)	SP. COND. (mS/cm)	TURBIDITY (NTU)	O.R.P. (± mV)	NOTES
26	0.4	27.74	7.07	1.68	>99.9	0.31	-353	
52	0.4	27.72	7.06	1.67	>99.9	0.34	-352	
65	0.4	27.81	7.05	1.66	>99.9	0.20	-347	
78	0.4	27.81	7.06	1.66	>99.9	0.21	-347	
91	0.4	27.81	7.06	1.66	>99.9	0.21	-349	
Sample	0.3	27.80	7.06	1.66	>99.9	0.21	-349	
Sample collected at 14:20 for the following tests								
Analytical Method								
TDS - Method 160.1 / Alkalinity - Method 310.1								
Anions and Nitrate/Nitrite - Method 300.0								
Cations - Method 6020								
Ammonia - Method 350.1								
Kd - distribution coefficient								

Observation wells purged in accordance with ASTM D-6452-99

Prepared by: WSE Date: 7-7-08
Checked by: CBS Date: 7/7/08



MACTEC Engineering and Consulting, Inc.
3301 Atlantic Avenue
Raleigh, North Carolina 27604

OBSERVATION WELL SAMPLING WORKSHEET

OBSERVATION WELL ID:	OW-706U		MACTEC JOB NUMBER:	6468-07-1950	
PROJECT:	Turkey Point COL Project	SITE:	Florida City, Florida	DATE:	5/29/2008
MEASURED WELL DEPTH:	31.72 FT.	SCREENED INTERVAL:	17-27 FT.	WELL DIAMETER:	2 IN.
HEIGHT OF MEASURING POINT ABOVE LAND SURFACE:		3.2	CASING MATERIAL:		PVC
SAMPLING DEVICE:	See below		TUBING TYPE:	Dedicated, Disposable Tubing	
MEASURING POINT:	Top of Casing		DEPTH TO GROUNDWATER:	3.02	
SAMPLING PERSONNEL:	L. Bisson and K. Charles-Smith		WATER-COLUMN HEIGHT:	28.70	
STEEL GUARD PIPE AROUND CASING:	<input checked="" type="checkbox"/>	YES	<input type="checkbox"/>	NO	
LOCKING CAP:	<input checked="" type="checkbox"/>	YES	<input type="checkbox"/>	NO	
PROTECTIVE POST/ABUTMENT:	<input type="checkbox"/>	YES	<input checked="" type="checkbox"/>	NO	
NONPOTABLE LABEL:	<input checked="" type="checkbox"/>	YES	<input type="checkbox"/>	NO	
ID PLATE:	<input checked="" type="checkbox"/>	YES	<input type="checkbox"/>	NO	
WELL INTEGRITY SATISFACTORY:	<input checked="" type="checkbox"/>	YES	<input type="checkbox"/>	NO	
WELL YIELD:	<input checked="" type="checkbox"/>	HIGH	<input type="checkbox"/>	MODERATE	<input type="checkbox"/> LOW
COMMENTS	Monsoon submersible pump, Horiba U-22 S/N MO15-09.				
	Purge volume determined by multiplying water-column height by 0.16 gal/ft for a 2-inch well				

PURGE VOLUME (gallons)	PURGE RATE (gpm)	TEMP (°C)	PH (S.U.)	D.O. (mg/L)	SP. COND. (mS/cm)	TURBIDITY (NTU)	O.R.P. (± mV)	NOTES
10	0.4	29.16	6.67	1.17	74.9	18.1	-373	
20	0.4	29.55	6.62	1.34	76.5	1.84	-378	
26	0.4	29.95	6.66	1.20	76.7	1.25	-385	
32	0.4	30.19	6.67	1.10	76.7	1.09	-388	
38	0.4	30.70	6.66	1.15	76.7	1.08	-391	
Sample	0.3	30.85	6.65	1.13	76.6	0.83	-392	
Sample collected at 11:00 for the following tests								
Analytical Method								
TDS - Method 160.1 / Alkalinity - Method 310.1								
Anions and Nitrate/Nitrite - Method 300.0								
Cations - Method 6020								
Ammonia - Method 350.1								
Kd - distribution coefficient								

Observation wells purged in accordance with ASTM D-6452-99

Prepared by: LS Date: 7-7-08
Checked by: CBS Date: 7/7/08



MACTEC Engineering and Consulting, Inc.
 3301 Atlantic Avenue
 Raleigh, North Carolina 27604

OBSERVATION WELL SAMPLING WORKSHEET

OBSERVATION WELL ID: OW-706L		MACTEC JOB NUMBER: 6468-07-1950	
PROJECT: Turkey Point COL Project	SITE: Florida City, Florida	DATE: 5/29/2008	
MEASURED WELL DEPTH: 114.56 FT.	SCREENED INTERVAL: 17-27 FT.	WELL DIAMETER: 2 IN.	
HEIGHT OF MEASURING POINT ABOVE LAND SURFACE: 3.2		CASING MATERIAL: PVC	
SAMPLING DEVICE: See below	TUBING TYPE: Dedicated, Disposable Tubing		
MEASURING POINT: Top of Casing	DEPTH TO GROUNDWATER: 0.62		
SAMPLING PERSONNEL: K. Charles-Smith	WATER-COLUMN HEIGHT: 113.94		
STEEL GUARD PIPE AROUND CASING:	<input checked="" type="checkbox"/> YES	<input type="checkbox"/> NO	
LOCKING CAP:	<input checked="" type="checkbox"/> YES	<input type="checkbox"/> NO	
PROTECTIVE POST/ABUTMENT:	<input type="checkbox"/> YES	<input checked="" type="checkbox"/> NO	
NONPOTABLE LABEL:	<input checked="" type="checkbox"/> YES	<input type="checkbox"/> NO	
ID PLATE:	<input checked="" type="checkbox"/> YES	<input type="checkbox"/> NO	
WELL INTEGRITY SATISFACTORY:	<input checked="" type="checkbox"/> YES	<input type="checkbox"/> NO	
WELL YIELD:	<input checked="" type="checkbox"/> HIGH	<input type="checkbox"/> MODERATE	<input type="checkbox"/> LOW
COMMENTS: Monsoon submersible pump, Horiba U-22 S/N MO15-09.			
Purge volume determined by multiplying water-column height by 0.16 gal/ft for a 2-inch well			

PURGE VOLUME (gallons)	PURGE RATE (gpm)	TEMP (°C)	PH (S.U.)	D.O. (mg/L)	SP. COND. (mS/cm)	TURBIDITY (NTU)	O.R.P. (± mV)	NOTES
24	0.4	29.50	6.87	1.92	44.4	9.05	-287	
48	0.4	29.42	6.85	1.79	46.7	0.86	-334	
60	0.4	29.54	6.88	1.61	45.7	0.57	-343	
72	0.4	29.57	6.85	1.57	46.2	0.35	-346	
84	0.4	29.60	6.86	1.51	46.2	0.24	-351	
Sample	0.3	29.61	6.83	1.49	46.4	0.20	-351	
Sample collected at 12:35 for the following tests								
Analytical Method								
TDS - Method 160.1 / Alkalinity - Method 310.1								
Anions and Nitrate/Nitrite - Method 300.0								
Cations - Method 6020								
Ammonia - Method 350.1								
Kd - distribution coefficient								

Observation wells purged in accordance with ASTM D-6452-99

Prepared by: lwb Date: 7-7-08
 Checked by: CBS Date: 7/7/08



MACTEC Engineering and Consulting, Inc.
3301 Atlantic Avenue
Raleigh, North Carolina 27604

OBSERVATION WELL SAMPLING WORKSHEET

OBSERVATION WELL ID:	OW-721U	MACTEC JOB NUMBER:	6468-07-1950
PROJECT:	Turkey Point COL Project	SITE:	Florida City, Florida
MEASURED WELL DEPTH:	28.00 FT.	SCREENED INTERVAL:	14-24 FT.
HEIGHT OF MEASURING POINT ABOVE LAND SURFACE:	3.1	CASING MATERIAL:	PVC
SAMPLING DEVICE:	See below	TUBING TYPE:	Dedicated, Disposable Tubing
MEASURING POINT:	Top of Casing	DEPTH TO GROUNDWATER:	3.23
SAMPLING PERSONNEL:	K. Charles-Smith	WATER-COLUMN HEIGHT:	24.77
STEEL GUARD PIPE AROUND CASING:	<input checked="" type="checkbox"/>	YES	<input type="checkbox"/> NO
LOCKING CAP:	<input checked="" type="checkbox"/>	YES	<input type="checkbox"/> NO
PROTECTIVE POST/ABUTMENT:	<input type="checkbox"/>	YES	<input checked="" type="checkbox"/> NO
NONPOTABLE LABEL:	<input checked="" type="checkbox"/>	YES	<input type="checkbox"/> NO
ID PLATE:	<input checked="" type="checkbox"/>	YES	<input type="checkbox"/> NO
WELL INTEGRITY SATISFACTORY:	<input checked="" type="checkbox"/>	YES	<input type="checkbox"/> NO
WELL YIELD:	<input checked="" type="checkbox"/>	HIGH	<input type="checkbox"/> MODERATE <input type="checkbox"/> LOW
COMMENTS	Monsoon submersible pump, Horiba U-22 S/N MO15-09.		
	Purge volume determined by multiplying water-column height by 0.16 gal/ft for a 2-inch well		

PURGE VOLUME (gallons)	PURGE RATE (gpm)	TEMP (°C)	PH (S.U.)	D.O. (mg/L)	SP. COND. (mS/cm)	TURBIDITY (NTU)	O.R.P. (± mV)	NOTES
9	0.4	28.91	7.12	10.8	54.8	0.28	-361	
18	0.4	29.22	7.11	10.6	55.5	0.48	-364	
22.5	0.4	29.26	7.08	10.6	52.7	0.37	-364	
27	0.4	29.27	7.08	10.6	53.0	0.46	-362	
31.5	0.4	29.30	7.07	10.8	52.8	0.30	-362	
Sample	0.3	28.92	7.10	10.6	53.1	0.36	-364	
Sample collected at 11:00 for the following tests								
Analytical Method								
TDS - Method 160.1 / Alkalinity - Method 310.1								
Anions and Nitrate/Nitrite - Method 300.0								
Cations - Method 6020								
Ammonia - Method 350.1								
Kd - distribution coefficient								

Observation wells purged in accordance with ASTM D-6452-99

Prepared by: WJS Date: 7-7-08
Checked by: CBS Date: 7/7/08



MACTEC Engineering and Consulting, Inc.
3301 Atlantic Avenue
Raleigh, North Carolina 27604

OBSERVATION WELL SAMPLING WORKSHEET

OBSERVATION WELL ID: OW-721L		MACTEC JOB NUMBER: 6468-07-1950	
PROJECT: Turkey Point COL Project	SITE: Florida City, Florida	DATE: 5/28/2008	
MEASURED WELL DEPTH: 107.62 FT.	SCREENED INTERVAL: 96-106 FT.	WELL DIAMETER: 2 IN.	
HEIGHT OF MEASURING POINT ABOVE LAND SURFACE: 3.2		CASING MATERIAL: PVC	
SAMPLING DEVICE: See below	TUBING TYPE: Dedicated, Disposable Tubing		
MEASURING POINT: Top of Casing	DEPTH TO GROUNDWATER: 1.07		
SAMPLING PERSONNEL: L. Bisson	WATER-COLUMN HEIGHT: 106.55		
STEEL GUARD PIPE AROUND CASING:	<input checked="" type="checkbox"/> YES	<input type="checkbox"/> NO	
LOCKING CAP:	<input checked="" type="checkbox"/> YES	<input type="checkbox"/> NO	
PROTECTIVE POST/ABUTMENT:	<input type="checkbox"/> YES	<input checked="" type="checkbox"/> NO	
NONPOTABLE LABEL:	<input checked="" type="checkbox"/> YES	<input type="checkbox"/> NO	
ID PLATE:	<input checked="" type="checkbox"/> YES	<input type="checkbox"/> NO	
WELL INTEGRITY SATISFACTORY:	<input checked="" type="checkbox"/> YES	<input type="checkbox"/> NO	
WELL YIELD:	<input checked="" type="checkbox"/> HIGH	<input type="checkbox"/> MODERATE	<input type="checkbox"/> LOW
COMMENTS: Monsoon submersible pump, Horiba U-22 S/N MO15-09.			
Purge volume determined by multiplying water-column height by 0.16 gal/ft for a 2-inch well			

PURGE VOLUME (gallons)	PURGE RATE (gpm)	TEMP (°C)	PH (S.U.)	D.O. (mg/L)	SP. COND. (mS/cm)	TURBIDITY (NTU)	O.R.P. (± mV)	NOTES
25.2	0.4	28.86	6.80	1.71	73.6	175	-337	
48.0	0.4	28.68	6.78	1.18	74.3	5.41	-358	
60.0	0.4	28.62	6.75	1.24	74.4	7.20	-361	
72.0	0.4	28.64	6.75	1.08	74.4	7.60	-364	
84.0	0.4	28.60	6.77	1.17	74.3	7.55	-369	
Sample	0.3	28.56	6.76	1.18	74.3	7.55	-370	
Sample collected at 13:25 for the following tests								
Analytical Method								
TDS - Method 160.1 / Alkalinity - Method 310.1								
Anions and Nitrate/Nitrite - Method 300.0								
Cations - Method 6020								
Ammonia - Method 350.1								
Kd - distribution coefficient								

Observation wells purged in accordance with ASTM D-6452-99

Prepared by: WSB Date: 7-7-08
Checked by: CBS Date: 7/7/08



MACTEC Engineering and Consulting, Inc.
3301 Atlantic Avenue
Raleigh, North Carolina 27604

OBSERVATION WELL SAMPLING WORKSHEET

OBSERVATION WELL ID: OW-735U		MACTEC JOB NUMBER: 6468-07-1950	
PROJECT: Turkey Point COL Project	SITE: Florida City, Florida	DATE: 5/27/2008	
MEASURED WELL DEPTH: 30.19 FT.	SCREENED INTERVAL: 16-26 FT.	WELL DIAMETER: 2 IN.	
HEIGHT OF MEASURING POINT ABOVE LAND SURFACE: 3.3		CASING MATERIAL: PVC	
SAMPLING DEVICE: See below	TUBING TYPE: Dedicated, Disposable Tubing		
MEASURING POINT: Top of Casing	DEPTH TO GROUNDWATER: 4.40		
SAMPLING PERSONNEL: K. Charles-Smith	WATER-COLUMN HEIGHT: 25.79		
STEEL GUARD PIPE AROUND CASING:	<input checked="" type="checkbox"/> YES	<input type="checkbox"/> NO	
LOCKING CAP:	<input checked="" type="checkbox"/> YES	<input type="checkbox"/> NO	
PROTECTIVE POST/ABUTMENT:	<input type="checkbox"/> YES	<input checked="" type="checkbox"/> NO	
NONPOTABLE LABEL:	<input checked="" type="checkbox"/> YES	<input type="checkbox"/> NO	
ID PLATE:	<input checked="" type="checkbox"/> YES	<input type="checkbox"/> NO	
WELL INTEGRITY SATISFACTORY:	<input checked="" type="checkbox"/> YES	<input type="checkbox"/> NO	
WELL YIELD:	<input checked="" type="checkbox"/> HIGH	<input type="checkbox"/> MODERATE	<input type="checkbox"/> LOW
COMMENTS: Monsoon submersible pump, Horiba U-22 S/N MO15-09.			
Purge volume determined by multiplying water-column height by 0.16 gal/ft for a 2-inch well			

PURGE VOLUME (gallons)	PURGE RATE (gpm)	TEMP (°C)	PH (S.U.)	D.O. (mg/L)	SP. COND. (mS/cm)	TURBIDITY (NTU)	O.R.P. (± mV)	NOTES
9.5	0.4	29.42	7.02	0.04	84.6	0.99	-334	
19	0.4	29.46	7.01	0.02	84.7	0.99	-351	
23.75	0.4	29.46	7.00	0.01	84.8	0.92	-357	
28.5	0.4	29.45	6.99	0.02	84.8	0.86	-357	
33.25	0.4	29.48	6.99	0.02	84.8	0.90	-357	
Sample	0.3	29.47	7.00	0.02	86.6	0.92	-360	
Sample collected at 11:35 for the following tests								
Analytical Method								
TDS - Method 160.1 / Alkalinity - Method 310.1								
Anions and Nitrate/Nitrite - Method 300.0								
Cations - Method 6020								
Ammonia - Method 350.1								
Kd - distribution coefficient								

Observation wells purged in accordance with ASTM D-6452-99

Prepared by: WJG Date: 7-7-08
Checked by: CBS Date: 7/7/08



MACTEC Engineering and Consulting, Inc.
3301 Atlantic Avenue
Raleigh, North Carolina 27604

OBSERVATION WELL SAMPLING WORKSHEET

OBSERVATION WELL ID:	OW-802U	MACTEC JOB NUMBER:	6468-07-1950
PROJECT:	Turkey Point COL Project	SITE:	Florida City, Florida
MEASURED WELL DEPTH:	29.11 FT.	SCREENED INTERVAL:	15-25 FT.
HEIGHT OF MEASURING POINT ABOVE LAND SURFACE:	3.4	CASING MATERIAL:	PVC
SAMPLING DEVICE:	See below	TUBING TYPE:	Dedicated, Disposable Tubing
MEASURING POINT:	Top of Casing	DEPTH TO GROUNDWATER:	4.05
SAMPLING PERSONNEL:	K. Charles-Smith	WATER-COLUMN HEIGHT:	25.06
STEEL GUARD PIPE AROUND CASING:	<input checked="" type="checkbox"/>	YES	<input type="checkbox"/> NO
LOCKING CAP:	<input checked="" type="checkbox"/>	YES	<input type="checkbox"/> NO
PROTECTIVE POST/ABUTMENT:	<input type="checkbox"/>	YES	<input checked="" type="checkbox"/> NO
NONPOTABLE LABEL:	<input checked="" type="checkbox"/>	YES	<input type="checkbox"/> NO
ID PLATE:	<input checked="" type="checkbox"/>	YES	<input type="checkbox"/> NO
WELL INTEGRITY SATISFACTORY:	<input checked="" type="checkbox"/>	YES	<input type="checkbox"/> NO
WELL YIELD:	<input checked="" type="checkbox"/>	HIGH	<input type="checkbox"/> MODERATE <input type="checkbox"/> LOW
COMMENTS	Monsoon submersible pump, Horiba U-22 S/N MO15-09.		
	Purge volume determined by multiplying water-column height by 0.16 gal/ft for a 2-inch well		

PURGE VOLUME (gallons)	PURGE RATE (gpm)	TEMP (°C)	PH (S.U.)	D.O. (mg/L)	SP. COND. (mS/cm)	TURBIDITY (NTU)	O.R.P. (± mV)	NOTES
10	0.4	28.23	6.86	2.05	82.7	0.91	-352	
20	0.4	28.20	6.86	1.76	82.7	0.50	-355	
25	0.4	28.22	6.89	1.90	82.7	0.57	-360	
30	0.4	28.50	6.88	1.91	82.6	0.52	-363	
35	0.4	28.36	6.84	1.90	82.6	0.48	-361	
Sample	0.3	28.27	6.80	1.90	82.8	0.48	-322	
Sample collected at 12:35 for the following tests								
Analytical Method								
TDS - Method 160.1 / Alkalinity - Method 310.1								
Anions and Nitrate/Nitrite - Method 300.0								
Cations - Method 6020								
Ammonia - Method 350.1								
Kd - distribution coefficient								

Observation wells purged in accordance with ASTM D-6452-99

Prepared by: LSL Date: 7-7-08
Checked by: CBS Date: 7/7/08



MACTEC Engineering and Consulting, Inc.
3301 Atlantic Avenue
Raleigh, North Carolina 27604

OBSERVATION WELL SAMPLING WORKSHEET

OBSERVATION WELL ID:	OW-805U		MACTEC JOB NUMBER:	6468-07-1950	
PROJECT:	Turkey Point COL Project	SITE:	Florida City, Florida	DATE:	6/5/2008
MEASURED WELL DEPTH:	33.85 FT.	SCREENED INTERVAL:	18-28 FT.	WELL DIAMETER:	2 IN.
HEIGHT OF MEASURING POINT ABOVE LAND SURFACE:		2.8	CASING MATERIAL:		PVC
SAMPLING DEVICE:	See below		TUBING TYPE:	Dedicated, Disposable Tubing	
MEASURING POINT:	Top of Casing		DEPTH TO GROUNDWATER:	3.05	
SAMPLING PERSONNEL:	K. Charles-Smith		WATER-COLUMN HEIGHT:	30.80	

STEEL GUARD PIPE AROUND CASING:	<input checked="" type="checkbox"/>	YES	<input type="checkbox"/>	NO		
LOCKING CAP:	<input checked="" type="checkbox"/>	YES	<input type="checkbox"/>	NO		
PROTECTIVE POST/ABUTMENT:	<input type="checkbox"/>	YES	<input checked="" type="checkbox"/>	NO		
NONPOTABLE LABEL:	<input checked="" type="checkbox"/>	YES	<input type="checkbox"/>	NO		
ID PLATE:	<input checked="" type="checkbox"/>	YES	<input type="checkbox"/>	NO		
WELL INTEGRITY SATISFACTORY:	<input checked="" type="checkbox"/>	YES	<input type="checkbox"/>	NO		
WELL YIELD:	<input checked="" type="checkbox"/>	HIGH	<input type="checkbox"/>	MODERATE	<input type="checkbox"/>	LOW

COMMENTS **Monsoon submersible pump, Horiba U-22 S/N MO15-09.**
Purge volume determined by multiplying water-column height by 0.16 gal/ft for a 2-inch well

PURGE VOLUME (gallons)	PURGE RATE (gpm)	TEMP (°C)	PH (S.U.)	D.O. (mg/L)	SP. COND. (mS/cm)	TURBIDITY (NTU)	O.R.P. (± mV)	NOTES
10.5	0.4	28.04	7.29	1.19	64.0	0.86	-296	
21.0	0.4	28.31	7.14	1.18	61.1	0.43	-342	
26.5	0.4	28.19	7.13	1.18	61.0	0.36	-345	
32.0	0.4	28.31	7.10	1.19	60.8	0.32	-345	
37.5	0.4	28.35	7.11	1.19	61.1	0.33	-344	
Sample	0.3	28.26	7.10	1.19	60.9	0.32	-346	
Sample collected at 15:00 for the following tests								
Analytical Method								
TDS - Method 160.1 / Alkalinity - Method 310.1								
Anions and Nitrate/Nitrite - Method 300.0								
Cations - Method 6020								
Ammonia - Method 350.1								
Kd - distribution coefficient								

Observation wells purged in accordance with ASTM D-6452-99

Prepared by: WJ Date: 7-7-08
Checked by: CBS Date: 7/7/08



MACTEC Engineering and Consulting, Inc.
 3301 Atlantic Avenue
 Raleigh, North Carolina 27604

OBSERVATION WELL SAMPLING WORKSHEET

OBSERVATION WELL ID: OW-809U		MACTEC JOB NUMBER: 6468-07-1950	
PROJECT: Turkey Point COL Project	SITE: Florida City, Florida	DATE: 5/27/2008	
MEASURED WELL DEPTH: 29.71 FT.	SCREENED INTERVAL: 15-25 FT.	WELL DIAMETER: 2 IN.	
HEIGHT OF MEASURING POINT ABOVE LAND SURFACE: 3.2		CASING MATERIAL: PVC	
SAMPLING DEVICE: See below	TUBING TYPE: Dedicated, Disposable Tubing		
MEASURING POINT: Top of Casing	DEPTH TO GROUNDWATER: 3.38		
SAMPLING PERSONNEL: K. Charles-Smith	WATER-COLUMN HEIGHT: 26.33		
STEEL GUARD PIPE AROUND CASING:	<input checked="" type="checkbox"/>	YES	<input type="checkbox"/> NO
LOCKING CAP:	<input checked="" type="checkbox"/>	YES	<input type="checkbox"/> NO
PROTECTIVE POST/ABUTMENT:	<input type="checkbox"/>	YES	<input checked="" type="checkbox"/> NO
NONPOTABLE LABEL:	<input checked="" type="checkbox"/>	YES	<input type="checkbox"/> NO
ID PLATE:	<input checked="" type="checkbox"/>	YES	<input type="checkbox"/> NO
WELL INTEGRITY SATISFACTORY:	<input checked="" type="checkbox"/>	YES	<input type="checkbox"/> NO
WELL YIELD:	<input checked="" type="checkbox"/>	HIGH	<input type="checkbox"/> MODERATE <input type="checkbox"/> LOW
COMMENTS: Monsoon submersible pump, Horiba U-22 S/N MO15-09.			
Purge volume determined by multiplying water-column height by 0.16 gal/ft for a 2-inch well			

PURGE VOLUME (gallons)	PURGE RATE (gpm)	TEMP (°C)	PH (S.U.)	D.O. (mg/L)	SP. COND. (mS/cm)	TURBIDITY (NTU)	O.R.P. (± mV)	NOTES
9	0.4	31.02	6.99	0.01	85.1	4.39	-368	
18	0.4	30.83	6.98	0.02	84.0	1.09	-370	
22.5	0.4	30.99	6.98	0.02	84.1	0.97	-371	
27	0.4	30.81	6.98	0.01	84.0	0.99	-370	
31.5	0.4	30.81	6.98	0.01	83.9	0.99	-371	
Sample	0.3	30.82	6.98	0.01	83.9	0.97	-371	
Sample collected at 14:55 for the following tests								
Analytical Method								
TDS - Method 160.1 / Alkalinity - Method 310.1								
Anions and Nitrate/Nitrite - Method 300.0								
Cations - Method 6020								
Ammonia - Method 350.1								
Kd - distribution coefficient								

Observation wells purged in accordance with ASTM D-6452-99

Prepared by: WJL Date: 7-7-08
 Checked by: CBS Date: 7/7/08

Laboratory Test Reports



Supplier Deviation Disposition Request

Notes

1. COMPLETE INSTRUCTIONS ON BACK OF THIS SHEET
2. Items 1-18 below to be completed by supplier
3. *Items, Bechtel entries only
4. Nonapplicable items to be marked "N/A"
5. Attach additional information whenever necessary
6. Bechtel must be notified within 5 days after detection of deviation
7. A copy of the completed SDDR form shall be included by the supplier in the quality verification data package for each item to which this SDDR applies.

For Supplier Use				For Bechtel Use			
Supplier SDDR No.		Date Submitted		Project		Bechtel SDDR No.	
76		5/18/09		FPL Turkey Point COL		see above	
		Job No.				Date Received	
		25409				4/19/09	
1. Supplier Name			Address		City & State		Zip Code
MACTEC Engineering and Consulting, Inc			3301 Atlantic Avenue		Raleigh, NC		27604
2. Supplier's Order No.		3. Supplier's Part No.	4. Supplier's Part Name		5. Deviation Detected		6. All Previous SDDRs (Numbers and Dates)
NA		NA	NA		Date Method		
				9/22/2008 NCR			
7. Bechtel PO & Rev. No.		8. Bechtel Part No.		9. Bechtel Part Name		10. Bechtel SQR Notified	11. Bechtel Eng. Notified
Subcontract No. 25409-102-3PS-CT20-00001 rev 001		NA		NA		Date Method	Date Method
						5/18/2009 SDDR	5/18/2009 SDDR
12. Deviation Description (Attach extra sheets, photographs, sketches, etc., as necessary and identify quantity and serial numbers as applicable)							
Please see attached NCR TP 40 (attachment 3 pgs).							
13. Supplier's Proposed Disposition							
<input type="checkbox"/> Use-As-Is		<input type="checkbox"/> Repair		<input checked="" type="checkbox"/> Modify Bechtel Requirement			
<i>DATA REJECTED AS INDICATED BY ATTACHED NCR TP 40.</i>							
14. Cost Impact				15. Schedule Impact			
None				None			
16. Proposed Disposition and Technical (plus Cost/Schedule if applicable) Justification: Attach extra sheets, sketches, etc., as necessary							
Please see attached document with information (attachment 3 pgs).							
17. Associated Supplier Document Change(s) none							
18. Supplier's Authorized Representative							
Name		Signature		Title		Date	
RICHARD S. AULLEN		<i>[Signature]</i>		PROJECT MANAGER		5-18-09	
*19. Bechtel Engineering Action							
<input type="checkbox"/> Accepted		Engineering		<input type="checkbox"/> Drawing Change		<input type="checkbox"/> Bechtel	
<input checked="" type="checkbox"/> Rejected		Follow-up		<input type="checkbox"/> Spec/Req. Change		<input type="checkbox"/> Bechtel	
				<input type="checkbox"/> Other Suppliers Affected		<input type="checkbox"/> Other	
*20. Bechtel Disposition Statement Including Justification (Attach extra sheets, sketches, etc., as necessary).							
<i>SEE PAGE 5 FOR DISPOSITION</i>							
						Construction Action Required <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No	
*21. Bechtel Disposition Approval/Signature				Date		22. Supplier	
RE <i>[Signature]</i>				6/17/09		N/A	
Checker <i>[Signature]</i>				6/17/09			
EGS <i>[Signature]</i>				6/17/09		*23. Bechtel Supplier Quality Representative	
PE <i>[Signature]</i>				6-17-09		N/A	
						Date	

5-19-09

6-15-09

SDDR Document – attachment 3 Pages

DCN# TUR765

PAGE 1 of 5

FPL COL PROJECT - Turkey Point

MACTEC Project No. 6468-07-1950

NCR TP 40		Nonconformance and Corrective Action Report	
Organization: MACTEC Engineering and Consulting		Location: Raleigh	
Reported By: William S. Grimes		Date: 9/22/08	
Nonconformance			
Description of Nonconformance:			
Description of Nonconformance: Based on review of the laboratory test reports, it appears that the total dissolved solids (TDS) results are erroneous. The measured TDS results are typically less than the sum of the individual analytes. TDS values should be as large or larger than the sum of the available analytes.			
Representative Notified: Al Tice			
Date Notified: 9/22/2008		Date Corrective Action Plan Due: 10/10/2008	
Corrective Action Plan			
Description of Evaluation to Determine Root Cause: MACTEC Senior Scientists reviewed the laboratory test reports and concluded that the TDS results did not appear accurate. Additionally, MACTEC QA personnel interviewed TestAmerica to review their testing procedures to determine if errors were made during the testing.			
Assignable Cause: Due to the high concentrations of analytes in the samples, a diluted aliquot was necessary to meet the final method requirements of not exceeding 200 milligrams of residue for the TDS tests. TestAmerica reported in their investigation that any suspended particulates may have affected pipette volume accuracy. Therefore, the TDS values could differ from the sum of available analytes based on an insufficient sample volume.			
Potential Harm: Based on discussions with the Bechtel, we understand that the primary objective for the groundwater sampling and testing assignment was to support review of specific conductivity data. Therefore, we believe the potentially erroneous TDS test results will not compromise Bechtel's objective for the assignment. This will be confirmed with formal submittal of an SDDR to cover this NCR.			
Description of Corrective Actions (current and to prevent recurrence): A MACTEC Senior Chemist reviewed the laboratory test reports to identify issues and disposition the data. Additionally, MACTEC QA coordinated with TestAmerica to identify steps /procedures to make sure this issue is not repeated in future analyses.			
Estimated Completion Date: 10/15/08			
Recommended disposition of nonconforming items (i.e. reject/dispose, repair, rework, use-as-is) Include technical justification: MACTEC rejects the TDS results, please see attached disposition statement.			
10 CFR 21 Notification Required: YES NO			
Signature of Preparer: William S. Grimes <i>William S. Grimes</i>		Date: 5-14-09	
Corrective Action Approval Signature: (Principal or Chief Engineer) <i>[Signature]</i>		Date: 5-14-09	
Corrective Action Closure			
Comments:			
Approved/Actual Disposition of Nonconforming Items:			
BECHTEL Approval Signature: To be confirmed with SDDR		Date:	
MACTEC QAR Approval Signature: <i>[Signature]</i>		Date: 5/14/09	
MACTEC Chief Engineer Signature: <i>[Signature]</i>		Date: 5/13/09 ^{SJC} 5/14/09	

DCN: TUR

SDDR PAGE 2 of 5

NCR TP 40 Disposition Statement

Laboratory reported TDS values should be at least equal to, if not greater than the summation of the individual cations and anions that comprise TDS. During our review of the TDS data, MACTEC identified that the reported TDS values for eight of the twelve groundwater samples tested were less than the summation of the individual analytes. MACTEC identified that the charge balances were all below 10% error which suggests good analytical accuracy for the cation and anion results thus supporting the use of the summed totals for comparison with reported TDS values. Based on these comparisons, the TDS values reported by TestAmerica were deemed suspect.

MACTEC QA personnel interviewed TestAmerica to determine if there were operational or procedural issues that affected the test results. TestAmerica identified that to meet the method requirement for final residue weight, they had to dilute the sample and use a smaller than normal sample aliquot. TestAmerica used a narrow tipped pipette and determined that any suspended particles could have affected pipette volume accuracy, which would have produced lower TDS results (see attached report). To eliminate this potential source of error, TestAmerica ordered custom-made, wide mouth pipettes for drawing small volume aliquots. Additionally, TestAmerica implemented a policy to check to TDS/chloride ratio for samples to determine if the test needs to be rerun within the hold times.

No definite cause for this error could be determined through our investigation. However, MACTEC suspects that inaccurate sample volume is the source for the lower than expected TDS results. Therefore, MACTEC **rejects** all TDS results reported by TestAmerica.

TestAmerica

THE LEADER IN ENVIRONMENTAL TESTING

10-10-08

Turkey Point Data

After re-reviewing the data for the TDS and Chlorides, no definitive answer for the higher Chloride result could be determined. The data for the samples, balances, pipettes and internal QC were re-reviewed and no definitive cause for the low bias to the TDS could be determined. The laboratory conducted an ion mass balance evaluation for the samples, which showed that the charge balance differences were all below 10%, indicating good analytical accuracy for the cations and anions, including chloride. Data was also reviewed by a corporate technical director. The samples were run, for all parameters, at a high dilution due to the high levels of the requested analytes present in the samples. Initially it was suspected that the high levels of the salts may have been a contributing factor. After reviewing technical documents it was decided that the high salt levels in the samples, while making the analysis difficult due to the dilutions we had to apply, really would not explain the lower TDS numbers. The original sample containers were pulled and there were no visible solids found in the sample remaining in the containers.

The Method blanks and LCS samples run with each set of data met all criteria. The balances and pipettes used for the analyses were calibrated the day of use and fell within acceptance criteria. The laboratory has passed the last several sets of PT samples for TDS.

One possible reason for the low TDS result in these samples is the small amount of material used to perform the TDS analysis. The method requires that the final weight of the residue not exceed 200 mg. In order to meet this, the lab used 1 ml of sample, due to the high levels of TDS present. The one ml aliquot is drawn up using a narrow tipped pipette. Any suspended particulates in the sample could interfere with the pipette volume accuracy. The lab has ordered a custom made Class A wide mouth pipette to eliminate this potential source of error.

Another corrective action we will implement is an immediate check of the TDS/Chloride ratio for samples, so that if it fails we can re-run within hold time.

We continue to monitor and evaluate the TDS analysis.



Marti Ward
Quality Assurance Manager

TestAmerica
THE LEADER IN ENVIRONMENTAL TESTING

13715 Rider Trail North
Earth City, MO 63045
314-298-8566
www.testamericainc.com

Supplier Deviation Disposition Request (Continuation Sheet)**Bechtel SDDR No. 25409-102-YD4-CY00-00076****20. Bechtel Disposition Statement**

This SDDR addresses MACTEC NCR TP 40 regarding the laboratory test results for water sample TDS values. The test results have been rejected by MACTEC as the total TDS values for eight of the twelve groundwater samples tested were less than the summation of the individual analytes. TDS totals should be as large as or larger than the sum of the analytes.

Bechtel concurs with rejecting the data and requests that groundwater samples be retested. The October 10, 2008 letter from TestAmerica indicates there are changes that could be made to improve the test procedure and the TDS results while staying within the 200 mg residue limit. Bechtel requests that the TestAmerica test procedure be reviewed and accepted prior to running any further tests as the extremely high salinity values in the groundwater must be accounted for.

Bechtel does not concur with the proposed disposition of **MODIFY BECHTEL REQUIREMENT** as the data has been rejected.



Supplier Deviation Disposition Request

Notes

1. COMPLETE INSTRUCTIONS ON BACK OF THIS SHEET
2. Items 1-18 below to be completed by supplier
3. *Items, Bechtel entries only
4. Nonapplicable items to be marked "N/A"
5. Attach additional information whenever necessary
6. Bechtel must be notified within 5 days after detection of deviation
7. A copy of the completed SDDR form shall be included by the supplier in the quality verification data package for each item to which this SDDR applies.

For Supplier Use				For Bechtel Use			
Supplier SDDR No. 77		Date Submitted 6/5/09		Project FPL Turkey Point COL		Bechtel SDDR No. SEE ABOVE	
		Job No. 25409				Date Received 6/9/09	
1. Supplier Name MACTEC Engineering and Consulting, Inc			Address 3301 Atlantic Avenue		City & State Raleigh, NC		Zip Code 27604
2. Supplier's Order No. NA		3. Supplier's Part No. NA	4. Supplier's Part Name NA		5. Deviation Detected Date: 5/20/2009 Method: NCR		6. All Previous SDDRs (Numbers and Dates)
7. Bechtel PO & Rev. No. Subcontract No. 25409-102-3PS-CT20-00001 rev 001		8. Bechtel Part No. NA	9. Bechtel Part Name NA		10. Bechtel SQR Notified Date: 6/5/2009 Method: SDDR		11. Bechtel Eng. Notified Date: 6/5/2009 Method: SDDR
12. Deviation Description (Attach extra sheets, photographs, sketches, etc., as necessary and identify quantity and serial numbers as applicable) Please see attached NCR TP 41 (attachment 6 pgs).							
13. Supplier's Proposed Disposition <input type="checkbox"/> Use-As-Is <input checked="" type="checkbox"/> Repair <input type="checkbox"/> Modify Bechtel Requirement							
14. Cost Impact None				15. Schedule Impact None			
16. Proposed Disposition and Technical (plus Cost/Schedule if applicable) Justification: Attach extra sheets, sketches, etc., as necessary Please see attached document with information (attachment 6 pgs).							
17. Associated Supplier Document Change(s) none							
18. Supplier's Authorized Representative							
Name RICHARD S. AUGER		Signature 			Title PROJECT MANAGER		Date 6/5/09
*19. Bechtel Engineering Action							
<input checked="" type="checkbox"/> Accepted		Engineering	<input type="checkbox"/> Drawing Change	Bechtel	<input type="checkbox"/> Supplier	<input type="checkbox"/> Licensing Doc. Changes	
<input type="checkbox"/> Rejected		Follow-up	<input type="checkbox"/> Spec/Req. Change	Bechtel	<input type="checkbox"/> Supplier	<input type="checkbox"/> Price Adjustment	
			<input type="checkbox"/> Other Suppliers Affected		<input type="checkbox"/> Other		
*20. Bechtel Disposition Statement Including Justification (Attach extra sheets, sketches, etc., as necessary). SEE PAGE 8 FOR DISPOSITION Construction Action Required <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No							
*21. Bechtel Disposition Approval/Signature		Date		22. Supplier		Date	
RE Thomas Bleda		6/17/09		S CRISCENZO		6-3-09	
Checker		6/17/09		(SEE NCARTP 41)			
EGS for JLM		6/17/09		*23. Bechtel Supplier Quality Representative		Date	
PE WDEES		6-17-09		N/A			

SDDR Document - attachment 6 Pages

DCN# TUR781

Handwritten: 6-16-09

FPL COL PROJECT - Turkey Point

MACTEC Project No. 6468-07-1950

NCR TP 41		Nonconformance and Corrective Action Report	
Organization: MACTEC Engineering and Consulting		Location: Raleigh	
Reported By: William S. Grimes		Date: 5/20/2009	
Nonconformance			
Description of Nonconformance: During review of the bicarbonate and carbonate alkalinity results (Method 310.1) and total alkalinity results (SM18 2320 B), it was noted that the summation of the bicarbonate and carbonate values were significantly lower than the reported total alkalinity results for seven of the twelve samples. TestAmerica informed MACTEC that bicarbonate values reported for these samples were not valid.			
Representative Notified: Al Tice			
Date Notified: 5/20/2009		Date Corrective Action Plan Due: 5/20/2009	
Corrective Action Plan			
Description of Evaluation to Determine Root Cause: MACTEC Senior Scientists reviewed the laboratory test reports and concluded that seven of the Total Alkalinity results did not agree with the summation of the bicarbonate and carbonate results. Upon receiving information from TestAmerica that the bicarbonate results were erroneous, MACTEC requested that TestAmerica evaluate this condition. TestAmerica reported that the test results manually entered into the report generation software were inadvertently copied from the pH 4.5 column of the bench sheet as opposed to the bicarbonate result column.			
Assignable Cause: The assignable cause is a data entry error. Additionally, a second level review of the data was not thoroughly conducted.			
Potential Harm: Based on discussions with the Bechtel, we understand that the primary objective for the groundwater sampling and testing assignment was to support review of specific conductivity data. Therefore, we believe this deviation will not compromise Bechtel's objective for the assignment. This will be confirmed with formal submittal of an SDDR to cover this NCR.			
Description of Corrective Actions (current and to prevent recurrence): MACTEC requested that TestAmerica investigate this error and prepare a report that describes their investigation, corrective action, and steps to prevent recurrence. No MACTEC corrective action is required. TestAmerica reported that the analyst and second level reviewer were both alerted to the error and re-trained on the critical aspects of TestAmerica's QA policies. To prevent recurrence, TestAmerica has modified their spreadsheet such that the columns to be entered into the laboratory LIMS system are highlighted to serve as a reminder as to what data should be reported.			
Estimated Completion Date: 5/28/2009			
Recommended disposition of nonconforming items (i.e. reject/dispose, repair, rework, use-as-is) include technical justification: Repair - see attached disposition			
10 CFR 21 Notification Required: YES NO			
Signature of Preparer: William S. Grimes <i>William S. Grimes</i>		Date: 5-28-09	
Corrective Action Approval Signature: <i>[Signature]</i> (Principal or Chief Engineer)		Date: 6-2-09	
Corrective Action Closure			
Comments:			
Approved/Actual Disposition of Nonconforming Items: REPAIR <i>REWORK</i> <i>JOM 6/4/09</i>			
BECHTEL Approval Signature: To be confirmed with SDDR		Date:	
MACTEC QAR Approval Signature: <i>[Signature]</i>		Date: 6/4/09	
MACTEC Chief Engineer Signature: <i>[Signature]</i>		Date: 6/3/09	
DCN: TUR			

JOM 6/4/09

SDDR PAGE 2 of 8

NCR TP 41 Disposition Statement

Review of the laboratory test data collected from the selected observation wells indicated that the total alkalinity results were significantly greater than the summation of the bicarbonate and carbonate alkalinity results for the groundwater samples collected from observation wells OW-606L, OW-606U, OW-621U, OW-706L, OW-706U, OW-721L, and OW-721U. After being informed of this condition, TestAmerica reported that the bicarbonate alkalinity results were in error and conducted an investigation.

Through their investigation, TestAmerica identified that a data entry error had occurred during the transfer of the data from the laboratory bench sheets to the LIMS system used for data report preparation. The analyst had apparently transferred the results from the pH 4.5 column into the reporting software as opposed to transferring to bicarbonate results. Additionally, TestAmerica identified that the second level data review was not thoroughly conducted for the two sample lots affected. TestAmerica reported that the analyst and second-level reviewer were alerted to this error, and were re-trained in the critical aspects of TestAmerica's Quality Assurance policies. To prevent recurrence, TestAmerica reported that they have modified the bench sheets such that the columns of data that are transferred to the LIMS system are highlighted to remind analysts to import the correct data. A copy of TestAmerica's Non-Conformance Report is attached.

Based on these findings, TestAmerica issued revised laboratory test reports for those two sample lots. MACTEC has reviewed these reports and accepted the revised bicarbonate alkalinity results. MACTEC has revised Table 5.3 "Summary of Groundwater Test Results" that was included in the Final Data Report Revision 2 10-6-2008. A copy of this table is attached.

MACTEC's recommended disposition of the bicarbonate alkalinity data is to repair the data to include the revisions made by TestAmerica. The revised data, as shown on the attached table, is released as project data.

DCN# TUR781

SDIR PAGE 3 of 8

2/6

TestAmerica

THE LEADER IN ENVIRONMENTAL TESTING

TestAmerica Laboratories, Inc.

Non-Conformance Report: Alkalinity (Lot F8E300223, F8E290268)

The alkalinity data was incorrectly reported for Lots F8E290268 and F8E300223. The client notified the lab that in both reports, the total alkalinity results were much higher than the summation of Alkalinity-bicarbonate and Alkalinity-carbonate results. The sample duplicate results were outside (high) of the QC limits for total alkalinity. All other method QC samples were within acceptance criteria.


Review of the data shows an error in transcribing the results from the bench sheet to the laboratory's LIM system. The results manually entered into the report generation software were inadvertently taken from the pH 4.5 column on the spreadsheet, instead of from the bicarbonate results column. (See attached bench sheet) No calculation errors were found, and no changes to the raw data are required.

A second, or peer, review of the data is a requirement of the TestAmerica St. Louis QA program. This review includes a comparison of the data on the spreadsheet to the data entered into the LIMs system. In this instance, the second level review was not thoroughly conducted. We recognize the importance of providing accurate results, the analyst and the second level reviewer have been made aware of the issue and re-trained on the key aspects of our process. QA will monitor the process to ensure compliance.

To determine the extent of the error and to determine if it is systematic, QA reviewed sets of alkalinity data before and after this occurrence. No other instances were identified, indicating that the error is isolated and not indicative of the process. No systematic deficiencies were noted. To prevent further occurrences, the spreadsheet is being updated to highlight the columns that are to be used to enter data into the LIMs system. This will act as a reminder as to which data is to be reported.

TestAmerica St. Louis apologizes for any inconvenience caused by this error. If you have any questions, or require additional information, please contact me at (314) 298-8566 or marti.ward@testamericainc.com.

Regards,



Marti Ward
Quality Assurance Manager
TestAmerica St. Louis

SDDR PAGE 4 of 8

3/6

Test Area: Water Laboratory
 Alkalinity Method 318.1
 (Waters)

Analyst: zsb

Batch: 815406 815406 815406

Titrant Normality (N) 0.0200

Analysis Date: 6/2/2008

Laboratory ID	Standard Conc. mg/L	Sample Volume mL (Nom. 50ml)	Lecithate Volume DI water (Nom. 100ml)	Titrated Volume mL (Nom. 90ml)	Sample					Alkalinity, Total mg/L			Alkalinity as CaCO ₃ mg/L			Recovery %	RPD %
					pH	pH 4.5	pH 4.2	pH 8.3	Total pH 4.5	Low pH 4.5	Phenyl pH 8.3	Carbonate	Bicarbonate	Hydroxide			
R000AK		50		80	6.88	8.85			177.00		0.00	0.00	177.00				
R001HJ		50		80	7.05	8.2			164.00		0.00	0.00	164.00				
R001LD		50		80	7.12	9			160.00		0.00	0.00	160.00				
R001LR		50		80	7.22	7.78			168.00		0.00	0.00	168.00				
R001LT		50		80	7.31	8.25			165.00		0.00	0.00	165.00				
R001LV		50		80	7.07	10.2			204.00		0.00	0.00	204.00				
R001V1		50		80	7.34	8.58			191.00		0.00	0.00	191.00				
R001Z		50		80	7.55	8.48			188.00		0.00	0.00	188.00				
R001ZB		50		80	8.42	12.58			279.00		0.00	0.00	279.00				
R001ZX		50		80	7.31	8.3			168.00		0.00	0.00	168.00				12.0%
									\$VALUE		\$VALUE	\$VALUE	\$VALUE	\$VALUE			
									\$VALUE		\$VALUE	\$VALUE	\$VALUE	\$VALUE			
									\$VALUE		\$VALUE	\$VALUE	\$VALUE	\$VALUE			
									\$VALUE		\$VALUE	\$VALUE	\$VALUE	\$VALUE			
									\$VALUE		\$VALUE	\$VALUE	\$VALUE	\$VALUE			
									\$VALUE		\$VALUE	\$VALUE	\$VALUE	\$VALUE			
									\$VALUE		\$VALUE	\$VALUE	\$VALUE	\$VALUE			
									\$VALUE		\$VALUE	\$VALUE	\$VALUE	\$VALUE			
									\$VALUE		\$VALUE	\$VALUE	\$VALUE	\$VALUE			
									\$VALUE		\$VALUE	\$VALUE	\$VALUE	\$VALUE			
									\$VALUE		\$VALUE	\$VALUE	\$VALUE	\$VALUE			
									\$VALUE		\$VALUE	\$VALUE	\$VALUE	\$VALUE			
									\$VALUE		\$VALUE	\$VALUE	\$VALUE	\$VALUE			
									\$VALUE		\$VALUE	\$VALUE	\$VALUE	\$VALUE			
									\$VALUE		\$VALUE	\$VALUE	\$VALUE	\$VALUE			
									\$VALUE		\$VALUE	\$VALUE	\$VALUE	\$VALUE			

Control Limits (Water): LCS = 90 - 110 RPD 20%
 Control Limits (Water): MS = 50 - 121 RPD 20%

SOP Rev Date
 STL-WC-0018 7 10/22/2007

Total Alkalinity as CaCO₃ = $\frac{\text{Total Volume (pH 4.5)} - \text{ml Diphenylamine} \times \text{N} \times 50000}{\text{Titrated Vol., ml}}$

Total Alkalinity, Low as CaCO₃ = $\frac{2 \times \text{Total Volume (pH 4.5)} - \text{ml Diphenylamine} \times \text{N} \times 50000}{\text{Titrated Vol., ml}}$

* Results are raw calculation and do not reflect rounding, requested significant figures, or client reporting limits.
 * Results on spreadsheet are "wet weight".

slav01\VolChem\Results\Alkalinity.xls, modified 11/18/06

DCN# TUR781

4/6

STDR PAGE 5 of 8

Lims Data Entry Print Out

WDE115

TestAmerica Laboratories, Inc.
Inorganics Batch Review
QC Batch 8154062

Date 6/02/2008
Time 12:53:33

Method Code:UK Alkalinity, Bicarbonate (310.1)
Analyst:Steve Brantz

Work Order	Result	Units	LDL/Dil	Prep. - Anal.	Total Solids	ESRL Flag	R/R	Revised Result	Output LDL	Dil
KN210-1-AJ	175	mg/L	5	06/02/08	.00	N		175	5.0	1.00
KN216-1-AJ	177	mg/L	5	06/02/08	.00	N		177	5.0	1.00
KN218-1-AJ	91	mg/L	5	06/02/08	.00	N		91.0	5.0	1.00
KN21J-1-AE	71	mg/L	5	06/02/08	.00	N		71.0	5.0	1.00
KN21J-1-BK	73	mg/L	5	06/02/08	.00	N		73.0	5.0	1.00
KN21W-1-AE	55	mg/L	5	06/02/08	.00	N		55.0	5.0	1.00
KN21W-1-BK	52	mg/L	5	06/02/08	.00	N		52.0	5.0	1.00
KN21J-1-AJ	51	mg/L	5	06/02/08	.00	N		51.0	5.0	1.00
KN21J-1-G7	50	mg/L	5	06/02/08	.00	N		50.0	5.0	1.00
KN21K-1-AE	56	mg/L	5	06/02/08	.00	N		56.0	5.0	1.00
KN21K-1-AE	55	mg/L	5	06/02/08	.00	N		55.0	5.0	1.00
KN31J-1-AJ	8.2	mg/L	5	06/02/08	.00	N		8.2	5.0	1.00
KN31D-1-AJ	9	mg/L	5	06/02/08	.00	N		9.0	5.0	1.00
KN31R-1-AJ	7.75	mg/L	5	06/02/08	.00	N		7.8	5.0	1.00
KN31T-1-AJ	8.25	mg/L	5	06/02/08	.00	N		8.2	5.0	1.00
KN41M-1-A2	76	mg/L	5	06/02/08	.00	N		76.0	5.0	1.00
KN41M-1-DM	78	mg/L	5	06/02/08	.00	N		78.0	5.0	1.00
KN41P-1-AD	55	mg/L	5	06/02/08	.00	N		55.0	5.0	1.00
KN51V-1-AE	10.2	mg/L	5	06/02/08	.00	N		10.2	5.0	1.00
KN51L-1-AM	9.55	mg/L	5	06/02/08	.00	N		9.6	5.0	1.00
KN51J-1-AM	9.45	mg/L	5	06/02/08	.00	N		9.4	5.0	1.00
KN51J-1-A5	9.3	mg/L	5	06/02/08	.00	N		9.3	5.0	1.00
KN61W-1-A3	52	mg/L	5	06/02/08	.00	N		52.0	5.0	1.00
KN61A-1-AE	79	mg/L	5	06/02/08	.00	N		79.0	5.0	1.00
KN61H-1-AE	121	mg/L	5	06/02/08	.00	N		121	5.0	1.00

5/11
6-1-8

DCN# TUR781

5/6

STDR PAGE 6 of 8

TABLE 5.3
SUMMARY OF GROUNDWATER TEST RESULTS
TURKEY POINT COL PROJECT
MACTEC PROJECT NO. 6468-07-1950

Analytical Method →		168.1	6820C								306.0						310.1 - Alkalinity		SM 15 2320B	390.1	SM 15 1030F & API
Constituent →		TDS	Calcium	Iron	Magnesium	Manganese	Potassium	Silica	Silicon	Sodium	Bromide	Chloride	Fluoride	Sulfate	Nitrate	Nitrite	Bicarbonate / Carbonate	Total Alkalinity	Ammonia*	Ion Balance Difference	
Well ID	Date Collected	mg/L	µg/L								mg/L						mg/L	mg/L	%		
OW-606L	5/28/2008	49100 [#]	632,000 N	<50U	1,880,000 N	39.1	549,000 N	2,690 [#]	<250,000 N	15,100,000 N	62.5	29,600	<20.0	3,860	<0.20	<200	165	<5.0	165	1,580	3.2
OW-606U	5/28/2008	43100 [#]	535,000 N	318 NB	1,730,000 N	35.4	525,000 N	729	<250,000 N	14,400,000 N	56.6	27,900	<20.0	3,470	<0.20	<200	155	<5.0	155	844	2.7
OW-621L	6/4/2008	52800 [#]	574,000 N	<50,000 N	1,960,000 N	<2,000 N	586,000 N	133,000 JB	62,100 JB	16,300,000 N	65.9	31,300 B	<20.0	3,610	<0.20	<200	181	<5.0	181	1,300	2.8
OW-621U	5/29/2008	19400 [#]	492,000 N	453 NB	1,600,000 N	36.8	476,000 N	637	<250,000 N	13,100,000 N	50.6	25,500	<1.0	3,210	<4.0	<200	189	<5.0	189	588	2.7
OW-706L	5/29/2008	17400 [#]	413,000 N	531 NB	1,170,000 N	8.3	327,000 N	7,560	<250,000 N	9,440,000 N	37.7 J	19,100	<1.0	2,280	<4.0	<200	191	<5.0	191	611	4.0
OW-706U	5/29/2008	40500 [#]	725,000 N	178 NB	2,150,000 N	43.5	658,000 N	1,840	<250,000 N	17,500,000 N	70.5	33,300	<1.0	3,850	<4.0	<200	204	<5.0	204	2,090	1.1
OW-721L	5/28/2008	54600 [#]	667,000 N	362 NB	2,020,000 N	46.2	587,000 N	3,170	<250,000 N	16,300,000 N	64.9	31,100	<20.0	3,990	<0.20	<200	180	<5.0	180	1,820	1.7
OW-721U	5/28/2008	45400 [#]	603,000 N	329 NB	1,890,000 N	58.1	569,000 N	848	<250,000 N	15,400,000 N	60.1	29,900	<20.0	3,860	<0.20	<200	164	<5.0	164	1,680	2.8
OW-735U	5/27/2008	40,200 [#]	749,000 N	133 NB	2,140,000 N	32.7	655,000 N	<250	<250,000 N	17,700,000 N	262	37,500	<20.0	4,090	<4.0	<200	179	<5.0	179	2,150	6.7
OW-802U	6/5/2008	53900 [#]	579,000 N	<50,000 N	1,980,000 N	<2,000 N	586,000 N	143,000 J	66,700 JB	16,490,000 N	65.1	31,600 B	<20.0	3,720	<0.20	<200	178	<5.0	178	1,400	3.0
OW-805U	6/5/2008	45700 [#]	447,000 N	<50,000 N	1,570,000 N	<2,000 N	493,000 N	107,000 J	49,900 JB	13,200,000 N	53.6	27,600 B	<20.0	3,070	<0.20	<200	177	<5.0	177	548	6.9
OW-809U	5/27/2008	34,800 [#]	704,000 N	158 NB	2,040,000 N	28.1	607,000 N	<250	<250,000 N	16,700,000 N	241 J	35,900	<1.0	4,050	<4.0	<200	177	<5.0	177	2,210	7.4

* = Test conducted on Nitrogen, as Ammonia.
 <# = Indicates analyte not detected at or above the method detection limit.
 <50U = Indicates analyte detected in the associated method blank at a concentration between the method detection limit and quantitation limit. Based on EPA 540-R-04-004, this result has been flagged as "non-detect" at the quantitation limit.
 N = Spiked analyte recovery is outside stated control limits. Method performance confirmed using Laboratory Control Spike sample results.
 J = Estimated result. Result is less than the reporting limit.
 B = Method blank concentration. The associated method blank contains the target analyte at a reportable level. These data should be used with caution.
 † = Because the initial results exceeded the SOP limits for this test, the samples were diluted and re-analyzed. Re-analysis was conducted out of hold time.
 # = Indicates result has been rejected during data review process (see Section 5.5 for discussion). These results are not considered valid and should not be used.

Prepared by: lwb
 Checked by: CBS

Date: 5-22-09
 Date: 5/22/09

SIDE PAGE 7 of 8

6/6 JENH
 TUR781


Supplier Deviation Disposition Request (Continuation Sheet)**Bechtel SDDR No. 25409-102-YD4-CY00-00077****20. Bechtel Disposition Statement**


This SDDR addresses MACTEC NCR TP 41 regarding the bicarbonate alkalinity laboratory test results for groundwater sample from observation wells OW-606L, OW-606U, OW-621U, OW-706L, OW-706U, OW-721L, and OW-721U. The reported total alkalinity results were much higher than the summation of alkalinity-bicarbonate and alkalinity-carbonate results.

Bechtel concurs with the corrective actions taken:

- MACTEC notified the analytical laboratory (TestAmerica), which after review of the data identified that a data entry error had occurred during transfer of the data from the laboratory bench sheets to the LIMs system used for report preparation. No calculation errors were found, and no changes in the raw data were required.
- TestAmerica, in order to prevent a recurrence of this problem, retrained their analysts in the critical aspects of TestAmerica's Quality Assurance policies and modified data sheets to highlight columns of data that are transferred to the LIMs system as a reminder to the analysts to import the correct data.
- TestAmerica issued revised laboratory test reports to MACTEC.
- MACTEC QA reviewed these reports and accepted the revised bicarbonate alkalinity results and revised Table 5.3 "Summary of Groundwater Test Results" included in the Final Data Report Revision 2 10-6-2008.

Bechtel concurs with the proposed disposition of **REPAIR** the data to include the revisions made by TestAmerica.


6-16-09


~~Sheet 7 of 7~~



**DOCUMENTATION OF TECHNICAL REVIEW
SUBCONTRACTOR WORK PRODUCT**

Project Name: Turkey Point COL Project

Project Number: 6468-07-1950

Project Manager: Scott Auger

Project Principal: Tom McDaniel

The report described below has been prepared by the named subcontractor retained in accordance with the MACTEC QAPD. The work and report have been reviewed by a MACTEC technically qualified person. Comments on the work or report, if any, have been satisfactorily addressed by the subcontractor. The attached report is approved in accordance with section QS-7 of MACTEC's QAPD.

The information and data contained in the attached report are hereby released by MACTEC for project use.

REPORT : Analytical Report Lot #: F8F050344 rev1

SUBCONTRACTOR: TestAmerica, Earth City, MO

DATE OF ACCEPTANCE : 7/23/2008

TECHNICAL REVIEWER: William S. Grimes

William S. Grimes
W S Grimes

PROJECT PRINCIPAL: Tom McDaniel



3301 Atlantic Avenue, Raleigh, NC 27604



LABORATORY DATA REVIEW CHECKLIST

	<u>YES</u>	<u>NO</u>	<u>NOT APPLICABLE</u>
1. Laboratory analytical data report appears complete (all data results present for all samples submitted for analysis) and there are no apparent transcription errors:	✓	___	___
2. Samples analyzed within applicable holding times (based on date of sample collection):*	✓	___	___
3. Trip blanks, field blanks or laboratory method blanks are free of blank contamination:	___	✓ ¹	___
4. If field duplicate samples collected, calculated results meet Relative Percent Difference guidelines: **	___	___	✓
5. Surrogate recoveries (organic analyses only) within laboratory reported recovery acceptance ranges:	___	___	✓
6. If Matrix Spike/Matrix Spike Duplicate (MS/MSD) samples required to meet project objectives, Percent Recoveries (%R) and Relative Percent Difference (RPD) within laboratory reported acceptance ranges:	___	✓ ²	___
7. Reported detection limits meet project objectives (e.g., are capable of achieving applicable site standards):	✓	___	___
8. Completed Chain-Of-Custody received noting sample/custody seal condition (with airbill, if appropriate):	✓	___	___
9. Analytical costs within authorized budget for these services:	___	___	✓

COMMENTS: ¹ Estimated concentrations of silica, silicon, and chloride were detected in the method blank, at concentrations between the PQL and MDL. Concentrations of these analytes in site samples were considerably higher, and likely reflect ambient aquifer conditions. ² MS/MSD recoveries were outside QC limits for several analytes possibly due to matrix interference. QC established based on acceptable LCS recoveries and results for analytes with acceptable recoveries.

Notes: 1. This checklist is intended for use with the laboratory reporting formats typical of most projects. If "no" is answered to one or more of the above checklist questions 1 through 7, a more detailed Data Validation may be required, and a person knowledgeable in Data Validation protocols should be consulted. This checklist should not be used if the project scope requires Data Validation from the onset.

2. * = Based upon EPA Guidance and the applicable analytical method references. See reverse side of checklist for details.

3. ** = Based upon EPA Guidance. Use these criteria on duplicate and sample results which exceed five times the reported detection limit. See reverse side of checklist for details.

Checked by: Walter A. Kim Date: 7-14-08



ANALYTICAL REPORT

REVISED

PROJECT NO. 6468071950

FPL Turkey Point COL

Lot #: F8F050344

Al Tice

MACTEC Engineering and Cons.
3301 Atlantic Ave.
Raleigh, NC 27604

TESTAMERICA LABORATORIES, INC.

A handwritten signature in black ink, appearing to read "Ivan Vania", is written over a light gray background.

Ivan Vania
Project Manager

July 9, 2008

Case Narrative

LOT NUMBER: F8F050344 – Revision 1

This report contains the analytical results for the sample received under chain of custody by TestAmerica St. Louis on June 5, 2008. This sample is associated with your FPL Turkey Point COL project.

The analytical results included in this report meet all applicable quality control procedure requirements except as noted on the following page.

The test results in this report meet all NELAP requirements for parameters in which accreditations are held by TestAmerica St. Louis. Any exceptions to NELAP requirements are noted in the case narrative. The case narrative is an integral part of this report.

All chemical analysis results are based upon sample as received, wet weight, unless noted otherwise. All radiochemistry results are based upon sample as dried and ground with the exception of tritium, unless requested wet weight by the client.

This revision contains results for TDS analysis and corrections to flags for ion balance.

Observations/Nonconformances

Reference the chain of custody and condition upon receipt report for any variations on receipt conditions and temperature of samples on receipt.

ICP-MS (SW846-6020)

The MS (MSD) recoveries for batch 8168278 - calcium, potassium, magnesium, sodium, silicon are outside the established QC limits. The analyte concentrations in the original sample are greater than four times the amount spiked, making percent recovery information ineffective. Method performance is demonstrated by acceptable LCS recovery.

Affected Samples:

F8F050344 (1): OW-6211

The MS (MSD) recoveries for batch 8168278 – iron are outside the established QC limits. The RPD is within method acceptance criteria indicating possible matrix interference. Method performance is demonstrated by acceptable LCS recovery.

Affected Samples:

F8F050344 (1): OW-6211

The MS (MSD) recoveries for batch 8164260 - manganese are outside the established QC limits due to matrix interference. Method performance is demonstrated by acceptable LCS recovery.

Affected Samples:

F8F050344 (1): OW-6211

Batch 8168278:

The samples were analyzed at a dilution due to high concentrations of target analytes. The reporting limits were adjusted for the dilution since no analysis at a lesser dilution was performed.

Affected Samples:

F8F050344 (1): OW-6211

Batch 8168278:

The serial dilution for calcium is outside of method acceptance criteria indicating a potential matrix interference. All associated samples are flagged accordingly.

Affected Samples:

F8F050344 (1): OW-6211

There were no other nonconformances or observations noted with any analysis on this lot.

METHODS SUMMARY

F8F050344

<u>PARAMETER</u>	<u>ANALYTICAL METHOD</u>	<u>PREPARATION METHOD</u>
pH Aqueous	SW846 9040	SW846 9040
Alkalinity, Total	SM18 2320 B	SM18 2320 B
Bicarbonate Alkalinity	MCAWW 310.1	MCAWW 310.1
Bromide	MCAWW 300.0A	MCAWW 300.0A
Carbonate Alkalinity	MCAWW 310.1	MCAWW 310.1
Chloride	MCAWW 300.0A	MCAWW 300.0A
Filterable Residue (TDS)	MCAWW 160.1	MCAWW 160.1
Fluoride	MCAWW 300.0A	MCAWW 300.0A
Ion Balance (%Difference)	SM18 1030F & AP	SM18 1030F & AP
ICP-MS (6020)	SW846 6020	
Nitrate as N	MCAWW 300.0A	MCAWW 300.0A
Nitrite as N	MCAWW 300.0A	MCAWW 300.0A
Nitrogen, Ammonia	MCAWW 350.1	MCAWW 350.1
Sulfate	MCAWW 300.0A	MCAWW 300.0A

References:

- MCAWW "Methods for Chemical Analysis of Water and Wastes", EPA-600/4-79-020, March 1983 and subsequent revisions.
- SM18 "Standard Methods for the Examination of Water and Wastewater", 18th Edition, 1992.
- SW846 "Test Methods for Evaluating Solid Waste, Physical/Chemical Methods", Third Edition, November 1986 and its updates.

SAMPLE SUMMARY

F8F050344

<u>WO #</u>	<u>SAMPLE#</u>	<u>CLIENT SAMPLE ID</u>	<u>SAMPLED DATE</u>	<u>SAMP TIME</u>
KPF63	001	OW-6211	06/04/08	14:20

NOTE (S) :

- The analytical results of the samples listed above are presented on the following pages.
- All calculations are performed before rounding to avoid round-off errors in calculated results.
- Results noted as "ND" were not detected at or above the stated limit.
- This report must not be reproduced, except in full, without the written approval of the laboratory.
- Results for the following parameters are never reported on a dry weight basis: color, corrosivity, density, flashpoint, ignitability, layers, odor, paint filter test, pH, porosity pressure, reactivity, redox potential, specific gravity, spot tests, solids, solubility, temperature, viscosity, and weight.

MACTEC Engineering & Consulting Inc

Client Sample ID: OW-6211

TOTAL Metals

Lot-Sample #...: F8F050344-001
 Date Sampled...: 06/04/08 14:20 Date Received...: 06/05/08

Matrix.....: WATER

PARAMETER	RESULT	REPORTING LIMIT	UNITS	METHOD	PREPARATION- ANALYSIS DATE	WORK ORDER #
Prep Batch #...	8168278					
Calcium	574000 N	100000	ug/L	SW846 6020	06/16-06/25/08	KPF631AD
		Dilution Factor: 1000		Analysis Time...: 17:38		
Iron	ND N	50000	ug/L	SW846 6020	06/16-06/25/08	KPF631AE
		Dilution Factor: 1000		Analysis Time...: 17:38		
Potassium	586000 N	100000	ug/L	SW846 6020	06/16-06/25/08	KPF631AF
		Dilution Factor: 1000		Analysis Time...: 17:38		
Magnesium	1960000 N	50000	ug/L	SW846 6020	06/16-06/25/08	KPF631AG
		Dilution Factor: 1000		Analysis Time...: 17:38		
Manganese	ND N	2000	ug/L	SW846 6020	06/16-06/25/08	KPF631AH
		Dilution Factor: 1000		Analysis Time...: 17:38		
Sodium	16300000 N	50000	ug/L	SW846 6020	06/16-06/25/08	KPF631AJ
		Dilution Factor: 1000		Analysis Time...: 17:38		
Silicon	62100 BN	250000	ug/L	SW846 6020	06/16-06/25/08	KPF631AK
		Dilution Factor: 1000		Analysis Time...: 17:38		
Prep Batch #...	8175115					
Silica	133000 J,B	250000	ug/L	SW846 6020	06/16-06/25/08	KPF631AL
		Dilution Factor: 1000		Analysis Time...: 17:38		

NOTE(S):

- N Spiked analyte recovery is outside stated control limits.
- J Estimated result. Result is less than RL.
- B The associated method blank contains the target analyte at a reportable level.

MACTEC Engineering & Consulting Inc

Client Sample ID: OW-6211

General Chemistry

Lot-Sample #....: F8F050344-001 Work Order #....: KPF63
 Date Sampled...: 06/04/08 14:20 Date Received...: 06/05/08

Matrix.....: WATER

PARAMETER	RESULT	RL	UNITS	METHOD	PREPARATION- ANALYSIS DATE	PREP BATCH #
pH (liquid)	7.2	0.10	No Units	SW846 9040	06/05/08	8158106
				Dilution Factor: 1	Analysis Time...: 00:00	
Bicarbonate Alkalinity	181	5.0	mg/L	MCAWW 310.1	06/10/08	8161269
				Dilution Factor: 1	Analysis Time...: 00:00	
Bromide	65.9	50.0	mg/L	MCAWW 300.0A	06/05/08	8175487
				Dilution Factor: 200	Analysis Time...: 08:25	
Carbonate Alkalinity	ND	5.0	mg/L	MCAWW 310.1	06/10/08	8161267
				Dilution Factor: 1	Analysis Time...: 00:00	
Chloride	31300 J	2000	mg/L	MCAWW 300.0A	06/05/08	8175488
				Dilution Factor: 10000	Analysis Time...: 08:49	
Fluoride	ND	20.0	mg/L	MCAWW 300.0A	06/05/08	8175489
				Dilution Factor: 200	Analysis Time...: 08:25	
Ion Balance Difference	2.8	0.10	%	SML8 1030F & API	07/01/08	8183319
				Dilution Factor: 1	Analysis Time...: 00:00	
Nitrate	ND	0.20	mg/L	MCAWW 300.0A	06/05/08	8158391
				Dilution Factor: 10	Analysis Time...: 08:13	
Nitrite	ND	200	mg/L	MCAWW 300.0A	06/05/08	8158392
				Dilution Factor: 10000	Analysis Time...: 08:49	
Nitrogen, as Ammonia	1300	100	ug/L	MCAWW 350.1	06/06/08	8156506
				Dilution Factor: 2	Analysis Time...: 00:00	
Sulfate	3610	500	mg/L	MCAWW 300.0A	06/05/08	8175490
				Dilution Factor: 1000	Analysis Time...: 08:37	
Total Alkalinity	181	5.0	mg/L	SML8 2320 B	06/10/08	8161265
				Dilution Factor: 1	Analysis Time...: 00:00	
Total Dissolved Solids	52800	500	mg/L	MCAWW 160.1	06/11-06/12/08	8163486
				Dilution Factor: 100	Analysis Time...: 00:00	

NOTE(S):

RL Reporting Limit

J Method blank contamination. The associated method blank contains the target analyte at a reportable level.

METHOD BLANK REPORT

TOTAL Metals

Client Lot #...: F8F050344

Matrix.....: WATER

PARAMETER	RESULT	REPORTING LIMIT	UNITS	METHOD	PREPARATION- ANALYSIS DATE	WORK ORDER #
MB Lot-Sample #: F8F160000-278 Prep Batch #...: 8168278						
Calcium	ND B	100	ug/L	SW846 6020	06/16-06/25/08	KP13D1AA
		Dilution Factor: 1				
		Analysis Time...: 17:30				
Iron	ND	50	ug/L	SW846 6020	06/16-06/25/08	KP13D1AC
		Dilution Factor: 1				
		Analysis Time...: 17:30				
Magnesium	ND	50	ug/L	SW846 6020	06/16-06/25/08	KP13D1AE
		Dilution Factor: 1				
		Analysis Time...: 17:30				
Manganese	ND	2	ug/L	SW846 6020	06/16-06/25/08	KP13D1AF
		Dilution Factor: 1				
		Analysis Time...: 17:30				
Potassium	ND	100	ug/L	SW846 6020	06/16-06/25/08	KP13D1AD
		Dilution Factor: 1				
		Analysis Time...: 17:30				
Silicon	67.1 B	250	ug/L	SW846 6020	06/16-06/25/08	KP13D1AH
		Dilution Factor: 1				
		Analysis Time...: 17:30				
Sodium	ND	50	ug/L	SW846 6020	06/16-06/25/08	KP13D1AG
		Dilution Factor: 1				
		Analysis Time...: 17:30				

MB Lot-Sample #: F8F230000-115 Prep Batch #...: 8175115						
Silica	144 J	250	ug/L	SW846 6020	06/16-06/25/08	KQL7H1AA
		Dilution Factor: 1				
		Analysis Time...: 17:38				

NOTE(S):

Calculations are performed before rounding to avoid round-off errors in calculated results.

B Estimated result. Result is less than RL.

METHOD BLANK REPORT

General Chemistry

Client Lot #....: F8F050344

Matrix.....: WATER

PARAMETER	RESULT	REPORTING LIMIT	UNITS	METHOD	PREPARATION- ANALYSIS DATE	PREP BATCH #
Bicarbonate Alkalinity	ND	Work Order #: KPLC11AA 5.0	mg/L	MB Lot-Sample #: MCAWW 310.1	F8F090000-269 06/10/08	8161269
		Dilution Factor: 1 Analysis Time...: 00:00				
Bromide	ND	Work Order #: KQG151AA 0.25	mg/L	MB Lot-Sample #: MCAWW 300.0A	F8F230000-487 06/05/08	8175487
		Dilution Factor: 1 Analysis Time...: 07:51				
Carbonate Alkalinity	ND	Work Order #: KPLCR1AA 5.0	mg/L	MB Lot-Sample #: MCAWW 310.1	F8F090000-267 06/10/08	8161267
		Dilution Factor: 1 Analysis Time...: 00:00				
Chloride	0.026 B	Work Order #: KQG161AA 0.20	mg/L	MB Lot-Sample #: MCAWW 300.0A	F8F230000-488 06/05/08	8175488
		Dilution Factor: 1 Analysis Time...: 07:51				
Fluoride	ND	Work Order #: KQG191AA 0.10	mg/L	MB Lot-Sample #: MCAWW 300.0A	F8F230000-489 06/05/08	8175489
		Dilution Factor: 1 Analysis Time...: 07:51				
Nitrate	ND	Work Order #: KPM9F1AA 0.020	mg/L	MB Lot-Sample #: MCAWW 300.0A	F8F060000-391 06/05/08	8158391
		Dilution Factor: 1 Analysis Time...: 07:51				
Nitrite	ND	Work Order #: KPM9K1AA 0.020	mg/L	MB Lot-Sample #: MCAWW 300.0A	F8F060000-392 06/05/08	8158392
		Dilution Factor: 1 Analysis Time...: 07:51				
Nitrogen, as Ammonia	ND	Work Order #: KPD7C1AA 50.0	ug/L	MB Lot-Sample #: MCAWW 350.1	F8F040000-506 06/06/08	8156506
		Dilution Factor: 1 Analysis Time...: 00:00				
Sulfate	ND	Work Order #: KQG2C1AA 0.50	mg/L	MB Lot-Sample #: MCAWW 300.0A	F8F230000-490 06/05/08	8175490
		Dilution Factor: 1 Analysis Time...: 07:51				

(Continued on next page)

METHOD BLANK REPORT

General Chemistry

Client Lot #...: F8F050344

Matrix.....: WATER

PARAMETER	RESULT	REPORTING LIMIT	UNITS	METHOD	PREPARATION- ANALYSIS DATE	PREP BATCH #
Total Alkalinity	ND	Work Order #: KPLCP1AA 5.0	mg/L	MB Lot-Sample #: SM18 2320 B	F8F090000-265 06/10/08	8161265
		Dilution Factor: 1 Analysis Time...: 00:00				
Total Dissolved Solids	ND	Work Order #: KPQXJ1AA 5.0	mg/L	MB Lot-Sample #: MCAWW 160.1	F8F110000-486 06/11-06/12/08	8163486
		Dilution Factor: 1 Analysis Time...: 00:00				

NOTE(S):

Calculations are performed before rounding to avoid round-off errors in calculated results.

B Estimated result. Result is less than RL.

LABORATORY CONTROL SAMPLE EVALUATION REPORT

TOTAL Metals

Client Lot #...: F8F050344

Matrix.....: WATER

<u>PARAMETER</u>	<u>PERCENT RECOVERY</u>	<u>RECOVERY LIMITS</u>	<u>METHOD</u>	<u>PREPARATION- ANALYSIS DATE</u>	<u>WORK ORDER #</u>
LCS Lot-Sample#: F8F160000-278 Prep Batch #...: 8168278					
Calcium	104	(85 - 115)	SW846 6020	06/16-06/25/08	KP13D1AJ
		Dilution Factor: 1		Analysis Time...: 17:34	
Iron	107	(85 - 115)	SW846 6020	06/16-06/25/08	KP13D1AK
		Dilution Factor: 1		Analysis Time...: 17:34	
Potassium	105	(85 - 115)	SW846 6020	06/16-06/25/08	KP13D1AL
		Dilution Factor: 1		Analysis Time...: 17:34	
Magnesium	102	(85 - 115)	SW846 6020	06/16-06/25/08	KP13D1AM
		Dilution Factor: 1		Analysis Time...: 17:34	
Manganese	112	(85 - 115)	SW846 6020	06/16-06/25/08	KP13D1AN
		Dilution Factor: 1		Analysis Time...: 17:34	
Sodium	102	(85 - 115)	SW846 6020	06/16-06/25/08	KP13D1AP
		Dilution Factor: 1		Analysis Time...: 17:34	
Silicon	113	(85 - 115)	SW846 6020	06/16-06/25/08	KP13D1AQ
		Dilution Factor: 1		Analysis Time...: 17:34	
LCS Lot-Sample#: F8F230000-115 Prep Batch #...: 8175115					
Silica	113 N	(0.0- 0.0)	SW846 6020	06/16-06/25/08	KQL7H1AC
		Dilution Factor: 1		Analysis Time...: 00:00	

NOTE(S) :

Calculations are performed before rounding to avoid round-off errors in calculated results.

N Spiked analyte recovery is outside stated control limits.

LABORATORY CONTROL SAMPLE EVALUATION REPORT

General Chemistry

Lot-Sample #....: F8F050344

Matrix.....: WATER

<u>PARAMETER</u>	<u>PERCENT RECOVERY</u>	<u>RECOVERY LIMITS</u>	<u>RPD</u>	<u>RPD LIMITS</u>	<u>METHOD</u>	<u>PREPARATION- ANALYSIS DATE</u>	<u>PREP BATCH #</u>
Nitrogen, as Ammonia		WO#:KPD7C1AC-LCS/KPD7C1AD-LCSD		LCS Lot-Sample#: F8F040000-506			
	103	(90 - 110)			MCAWW 350.1	06/06/08	8156506
	100	(90 - 110)	2.7	(0-20)	MCAWW 350.1	06/06/08	8156506
		Dilution Factor: 1		Analysis Time...: 00:00			

NOTE(S):

Calculations are performed before rounding to avoid round-off errors in calculated results.

LABORATORY CONTROL SAMPLE EVALUATION REPORT

General Chemistry

Client Lot #...: F8F050344

Matrix.....: WATER

<u>PARAMETER</u>	<u>PERCENT RECOVERY</u>	<u>RECOVERY LIMITS</u>	<u>METHOD</u>	<u>PREPARATION- ANALYSIS DATE</u>	<u>PREP BATCH #</u>
pH (liquid)	100	(99 - 101)	Work Order #: KPGWD1AA SW846 9040	LCS Lot-Sample#: F8F060000-106 06/05/08	8158106
			Dilution Factor: 1	Analysis Time...: 00:00	
Bicarbonate Alkalinity	101	(90 - 110)	Work Order #: KPLC11AC MCAWW 310.1	LCS Lot-Sample#: F8F090000-269 06/10/08	8161269
			Dilution Factor: 1	Analysis Time...: 00:00	
Bromide	101	(90 - 110)	Work Order #: KQG151AC MCAWW 300.0A	LCS Lot-Sample#: F8F230000-487 06/05/08	8175487
			Dilution Factor: 1	Analysis Time...: 07:41	
Carbonate Alkalinity	101	(90 - 110)	Work Order #: KPLCR1AC MCAWW 310.1	LCS Lot-Sample#: F8F090000-267 06/10/08	8161267
			Dilution Factor: 1	Analysis Time...: 00:00	
Chloride	98	(90 - 110)	Work Order #: KQG161AC MCAWW 300.0A	LCS Lot-Sample#: F8F230000-488 06/05/08	8175488
			Dilution Factor: 1	Analysis Time...: 07:41	
Fluoride	99	(90 - 110)	Work Order #: KQG191AC MCAWW 300.0A	LCS Lot-Sample#: F8F230000-489 06/05/08	8175489
			Dilution Factor: 1	Analysis Time...: 07:41	
Nitrate	101	(90 - 110)	Work Order #: KPM9F1AC MCAWW 300.0A	LCS Lot-Sample#: F8F060000-391 06/05/08	8158391
			Dilution Factor: 1	Analysis Time...: 07:41	
Nitrite	100	(90 - 110)	Work Order #: KPM9K1AC MCAWW 300.0A	LCS Lot-Sample#: F8F060000-392 06/05/08	8158392
			Dilution Factor: 1	Analysis Time...: 07:41	
Sulfate	95	(90 - 110)	Work Order #: KQG2C1AC MCAWW 300.0A	LCS Lot-Sample#: F8F230000-490 06/05/08	8175490
			Dilution Factor: 1	Analysis Time...: 07:41	
Total Alkalinity	101	(90 - 110)	Work Order #: KPLCP1AC SM18 2320 B	LCS Lot-Sample#: F8F090000-265 06/10/08	8161265
			Dilution Factor: 1	Analysis Time...: 00:00	

NOTE(S) :

Calculations are performed before rounding to avoid round-off errors in calculated results.

MATRIX SPIKE SAMPLE EVALUATION REPORT

TOTAL Metals

Client Lot #...: F8F050344
 Date Sampled...: 06/04/08 14:20 Date Received...: 06/05/08

Matrix.....: WATER

PARAMETER	PERCENT RECOVERY	RECOVERY LIMITS	RPD	RPD LIMITS	METHOD	PREPARATION- ANALYSIS DATE	WORK ORDER #
MS Lot-Sample #: F8F050344-001 Prep Batch #...: 8168278							
Calcium	0 N	(75 - 125)			SW846 6020	06/16-06/25/08	KPF631A8
	0 N	(75 - 125)	0.0	(0-20)	SW846 6020	06/16-06/25/08	KPF631A9
			Dilution Factor: 1000				
			Analysis Time...: 17:45				
Iron	0 N	(75 - 125)			SW846 6020	06/16-06/25/08	KPF631CA
	0 N	(75 - 125)	0.0	(0-20)	SW846 6020	06/16-06/25/08	KPF631CC
			Dilution Factor: 1000				
			Analysis Time...: 17:45				
Magnesium	0 N	(75 - 125)			SW846 6020	06/16-06/25/08	KPF631CF
	0 N	(75 - 125)	0.0	(0-20)	SW846 6020	06/16-06/25/08	KPF631CG
			Dilution Factor: 1000				
			Analysis Time...: 17:45				
Manganese	117	(75 - 125)			SW846 6020	06/16-06/25/08	KPF631CH
	130 N	(75 - 125)	11	(0-20)	SW846 6020	06/16-06/25/08	KPF631CJ
			Dilution Factor: 1000				
			Analysis Time...: 17:45				
Potassium	0 N	(75 - 125)			SW846 6020	06/16-06/25/08	KPF631CD
	17 N	(75 - 125)	0.0	(0-20)	SW846 6020	06/16-06/25/08	KPF631CE
			Dilution Factor: 1000				
			Analysis Time...: 17:45				
Silicon	85 B	(75 - 125)			SW846 6020	06/16-06/25/08	KPF631CM
	0 N	(75 - 125)	0.0	(0-20)	SW846 6020	06/16-06/25/08	KPF631CN
			Dilution Factor: 1000				
			Analysis Time...: 17:45				
Sodium	0 N	(75 - 125)			SW846 6020	06/16-06/25/08	KPF631CK
	0 N	(75 - 125)	0.0	(0-20)	SW846 6020	06/16-06/25/08	KPF631CL
			Dilution Factor: 1000				
			Analysis Time...: 17:45				

NOTE(S) :

Calculations are performed before rounding to avoid round-off errors in calculated results.

N Spiked analyte recovery is outside stated control limits.

B Estimated result. Result is less than RL.

MATRIX SPIKE SAMPLE EVALUATION REPORT

General Chemistry

Client Lot #...: F8F050344

Matrix.....: WATER

Date Sampled...: 06/04/08 14:20 Date Received...: 06/05/08

PARAMETER	PERCENT RECOVERY	RECOVERY LIMITS	METHOD	PREPARATION- ANALYSIS DATE	PREP BATCH #
Bromide	92	Work Order #...: KPF631CP (90 - 110)	MCAWW 300.0A	MS Lot-Sample #: F8F050344-001 06/05/08	8175487
		Dilution Factor: 200		Analysis Time...: 08:25	
Chloride	97	Work Order #...: KPF631CR (90 - 110)	MCAWW 300.0A	MS Lot-Sample #: F8F050344-001 06/05/08	8175488
		Dilution Factor: 10000		Analysis Time...: 08:49	
Fluoride	100	Work Order #...: KPF631CU (90 - 110)	MCAWW 300.0A	MS Lot-Sample #: F8F050344-001 06/05/08	8175489
		Dilution Factor: 200		Analysis Time...: 08:25	
Nitrate	93	Work Order #...: KPF631A2 (90 - 110)	MCAWW 300.0A	MS Lot-Sample #: F8F050344-001 06/05/08	8158391
		Dilution Factor: 10		Analysis Time...: 08:13	
Nitrite	102	Work Order #...: KPF631A4 (90 - 110)	MCAWW 300.0A	MS Lot-Sample #: F8F050344-001 06/05/08	8158392
		Dilution Factor: 10000		Analysis Time...: 08:49	
Nitrogen, as Ammonia	96	Work Order #...: KPC951C5 (90 - 110)	MCAWW 350.1	MS Lot-Sample #: F8F040293-001 06/06/08	8156506
		Dilution Factor: 1		Analysis Time...: 00:00	
Sulfate	100	Work Order #...: KPF631CW (90 - 110)	MCAWW 300.0A	MS Lot-Sample #: F8F050344-001 06/05/08	8175490
		Dilution Factor: 1000		Analysis Time...: 08:37	
Total Alkalinity	92	Work Order #...: KPF631A0 (80 - 120)	SM18 2320 B	MS Lot-Sample #: F8F050344-001 06/10/08	8161265
		Dilution Factor: 1		Analysis Time...: 00:00	

NOTE(S):

Calculations are performed before rounding to avoid round-off errors in calculated results.

SAMPLE DUPLICATE EVALUATION REPORT

General Chemistry

Client Lot #...: F8F050344 Work Order #...: KPF63-SMP Matrix.....: WATER
 KPF63-DUP
 Date Sampled...: 06/04/08 14:20 Date Received...: 06/05/08

<u>PARAM</u>	<u>RESULT</u>	<u>DUPLICATE</u>	<u>UNITS</u>	<u>RPD</u>	<u>RPD</u>	<u>METHOD</u>	<u>PREPARATION-</u>	<u>PREP</u>
		<u>RESULT</u>		<u>RPD</u>	<u>LIMIT</u>		<u>ANALYSIS DATE</u>	<u>BATCH #</u>
Bromide	65.9	65.0	mg/L	1.5	(0-20)	MCAWW 300.0A	06/05/08	8175487
						SD Lot-Sample #: F8F050344-001		
						Dilution Factor: 200		
						Analysis Time...: 08:25		
Chloride	31300 J	32900	mg/L	4.8	(0-20)	MCAWW 300.0A	06/05/08	8175488
						SD Lot-Sample #: F8F050344-001		
						Dilution Factor: 10000		
						Analysis Time...: 08:49		
Fluoride	ND	ND	mg/L	0	(0-20)	MCAWW 300.0A	06/05/08	8175489
						SD Lot-Sample #: F8F050344-001		
						Dilution Factor: 200		
						Analysis Time...: 08:25		
Sulfate	3610	3600	mg/L	0.34	(0-20)	MCAWW 300.0A	06/05/08	8175490
						SD Lot-Sample #: F8F050344-001		
						Dilution Factor: 1000		
						Analysis Time...: 08:37		
Nitrite	ND	ND	mg/L	0	(0-20)	MCAWW 300.0A	06/05/08	8158392
						SD Lot-Sample #: F8F050344-001		
						Dilution Factor: 10000		
						Analysis Time...: 08:49		
Nitrate	ND	ND	mg/L	0	(0-20)	MCAWW 300.0A	06/05/08	8158391
						SD Lot-Sample #: F8F050344-001		
						Dilution Factor: 10		
						Analysis Time...: 08:13		
Total Alkalinity	181	183	mg/L	1.1	(0-20)	SM18 2320 B	06/10/08	8161265
						SD Lot-Sample #: F8F050344-001		
						Dilution Factor: 1		
						Analysis Time...: 00:00		
pH (liquid)	7.2	7.2	No Units	0.0	(0-0.0)	SW846 9040	06/05/08	8158106
						SD Lot-Sample #: F8F050344-001		
						Dilution Factor: 1		
						Analysis Time...: 00:00		

NOTE(S):

Calculations are performed before rounding to avoid round-off errors in calculated results.
 J Method blank contamination. The associated method blank contains the target analyte at a reportable level.

F8F050344

CLIENT ANALYSIS SUMMARY

Storage Loc: 1-131-132,M
 Date Received: 2008-06-05
 Analytical Due Date: 2008-06-24
 Report Due Date: 2008-06-26
 Report Type: W
 EDD Code: 00

Project Manager: IV Quote #: 79192 SDG:
 Project: 6468071950 FPL Turkey Point COL
 PO#: 200807151 Report to: AI Tice
 Client: 63036 MACTEC Engineering & Consulting Inc

#SMPS In LOT: 1

Inform PM of any receiving issues.

SAMPLE #	CLIENT SAMPLE ID	Site ID	Client Matrix	DATE/TIME SAMPLED	WORKORDER	I
1	OW-6211			2008-06-04 / 1420	KPF63	WATER
SAMPLE COMMENTS:						
FE	MH SW846 6020		WATER, 6020, Metals	GJ	METALS, TOTAL - 2% HCL	01 STANDARD TEST SET PROT: A WRK LOC 06
KX	MH SW846 6020		WATER, 6020, Metals	GJ	METALS, TOTAL - 2% HCL	01 STANDARD TEST SET PROT: A WRK LOC 06
MG	MH SW846 6020		WATER, 6020, Metals	GJ	METALS, TOTAL - 2% HCL	01 STANDARD TEST SET PROT: A WRK LOC 06
MN	MH SW846 6020		WATER, 6020, Metals	GJ	METALS, TOTAL - 2% HCL	01 STANDARD TEST SET PROT: A WRK LOC 06
NA	MH SW846 6020		WATER, 6020, Metals	GJ	METALS, TOTAL - 2% HCL	01 STANDARD TEST SET PROT: A WRK LOC 06
SA	MH SW846 6020		WATER, Silica by calculation	0X	CALCULATION ONLY	9Q ORG FLAGS FOR INORG; STANDARD PROT: A WRK LOC 06
SI	MH SW846 6020		WATER, 6020, Metals	GJ	METALS, TOTAL - 2% HCL	01 STANDARD TEST SET PROT: A WRK LOC 06
CA	MH SW846 6020		WATER, 6020, Metals	GJ	METALS, TOTAL - 2% HCL	01 STANDARD TEST SET PROT: A WRK LOC 06
XX	AK MCAW 180.1 W		WATER, 180.1, Solids, Filterable "TDS"	88	NO SAMPLE PREPARATION PERFORMED / DIRECT	01 STANDARD TEST SET PROT: A WRK LOC 06
XX	C8 MCAW 300.0A W		WATER, 300.0A, Fluoride	88	NO SAMPLE PREPARATION PERFORMED / DIRECT	01 STANDARD TEST SET PROT: A WRK LOC 06
XX	C9 MCAW 300.0A W		WATER, 300.0A, Nitrate as N	88	NO SAMPLE PREPARATION PERFORMED / DIRECT	01 STANDARD TEST SET PROT: A WRK LOC 06
XX	CB MCAW 310.1 W		WATER, 310.1, Alkalinity, Carbonate	88	NO SAMPLE PREPARATION PERFORMED / DIRECT	01 STANDARD TEST SET PROT: A WRK LOC 06
XX	CX MCAW 300.0A W		WATER, 300.0A, Chloride	88	NO SAMPLE PREPARATION PERFORMED / DIRECT	01 STANDARD TEST SET PROT: A WRK LOC 06
XX	CY MCAW 300.0A W		WATER, 300.0A, Sulfate	88	NO SAMPLE PREPARATION PERFORMED / DIRECT	01 STANDARD TEST SET PROT: A WRK LOC 06
XX	FJ SW846 9040		WATER, 9040C, pH	88	NO SAMPLE PREPARATION PERFORMED / DIRECT	01 STANDARD TEST SET PROT: A WRK LOC 06
XX	GM MCAW 300.0A W		WATER, 300.0A, Bromide	88	NO SAMPLE PREPARATION PERFORMED / DIRECT	01 STANDARD TEST SET PROT: A WRK LOC 06
XX	GO MCAW 300.0A W		WATER, 300.0A, Nitrite as N	88	NO SAMPLE PREPARATION PERFORMED / DIRECT	01 STANDARD TEST SET PROT: A WRK LOC 06
XX	LV SM18 2320 B		WATER, 2320 B, Alkalinity, Total	88	NO SAMPLE PREPARATION PERFORMED / DIRECT	01 STANDARD TEST SET PROT: A WRK LOC 06
XX	SL SM18 1030F & API		WATER, 1030F & API, Ion Balance	0X	CALCULATION ONLY	01 STANDARD TEST SET PROT: A WRK LOC 06
XX	UX MCAW 310.1 W		WATER, 310.1, Alkalinity, Bicarbonate	88	NO SAMPLE PREPARATION PERFORMED / DIRECT	01 STANDARD TEST SET PROT: A WRK LOC 06
XX	VM MCAW 350.1 W		WATER, 350.1, Nitrogen, Ammonia	88	NO SAMPLE PREPARATION PERFORMED / DIRECT	01 STANDARD TEST SET PROT: A WRK LOC 06
S	XX C9 MCAW 300.0A W		WATER, 300.0A, Nitrate as N	88	NO SAMPLE PREPARATION PERFORMED / DIRECT	01 STANDARD TEST SET PROT: A WRK LOC 06
S	XX GO MCAW 300.0A W		WATER, 300.0A, Nitrite as N	88	NO SAMPLE PREPARATION PERFORMED / DIRECT	01 STANDARD TEST SET PROT: A WRK LOC 06
S	XX LV SM18 2320 B		WATER, 2320 B, Alkalinity, Total	88	NO SAMPLE PREPARATION PERFORMED / DIRECT	01 STANDARD TEST SET PROT: A WRK LOC 06
X	XX C9 MCAW 300.0A W		WATER, 300.0A, Nitrate as N	88	NO SAMPLE PREPARATION PERFORMED / DIRECT	01 STANDARD TEST SET PROT: A WRK LOC 06
X	XX FJ SW846 9040		WATER, 9040C, pH	88	NO SAMPLE PREPARATION PERFORMED / DIRECT	01 STANDARD TEST SET PROT: A WRK LOC 06
X	XX GO MCAW 300.0A W		WATER, 300.0A, Nitrite as N	88	NO SAMPLE PREPARATION PERFORMED / DIRECT	01 STANDARD TEST SET PROT: A WRK LOC 06
X	XX LV SM18 2320 B		WATER, 2320 B, Alkalinity, Total	88	NO SAMPLE PREPARATION PERFORMED / DIRECT	01 STANDARD TEST SET PROT: A WRK LOC 06

owl 3550

Chain of Custody Record

Temperature on Receipt _____

Drinking Water? Yes No

TestAmerica

THE LEADER IN ENVIRONMENTAL TESTING

TAL-4124 (1007)

Client MACTEC	Project Manager Scott Auger	Date 06-04-08	Chain of Custody Number 062466
Address 3301 Atlantic Avenue	Telephone Number (Area Code)/Fax Number 919-976-0416	Lab Number	Page 1 of 1

City Raleigh	State NC	Zip Code 27604	Site Contact Matt Coole	Lab Contact Ivan Vania	Analysis (Attach list if more space is needed)
Project Name and Location (State) Turkey Point Col			Carrier/Waybill Number FE 8656 2694 6664		

Contract/Purchase Order/Quote No. 6468-07-1950	Sample I.D. No. and Description (Containers for each sample may be combined on one line)	Date	Time	Matrix				Containers & Preservatives								Special Instructions/ Conditions of Receipt				
				Air	Aqueous	Sed.	Soil	Unpres.	H2SO4	HNO3	HCl	NaOH	ZnAc2	NaOH						
	OW-621L	06/04/08	1420		X				1	2	1								(250 ml)	Ca, Mg, Fe, Mn, Zn, Cu, Pb, Cd, Ni, Cr, As, Se, Hg, TSS, TDS, Chloride, Nitrate, Ammonia, Sulfate, Silica, Fluoride, Phosphate, Barium, Strontium, Potassium, Sodium, Cation, Anion
																				- pH-EPA SW846 9045(D)
																				TDS-EPA 160.1
																				- Cation-EPA 6020C
																				Inorganic Ions
																				MEAWW 300.0 A
																				- Alkalinity-EPA 310.1
																				- Ammonia-EPA-350.1
																				Nitrate
																				Nitrite-EPA 300.0

Possible Hazard Identification: Non-Hazard Flammable Skin Irritant Poison B Unknown

Sample Disposal: Return To Client Disposal By Lab Archive For _____ Months (A fee may be assessed if samples are retained longer than 1 month)

Turn Around Time Required: 24 Hours 48 Hours 7 Days 14 Days 21 Days Other **Standard**

QC Requirements (Specify)

1. Relinquished By Kristina Chup-Smit	Date 06/04/08	Time	1. Received By S. Vania	Date 6/5/08	Time 0915
2. Relinquished By	Date	Time	2. Received By	Date	Time
3. Relinquished By	Date	Time	3. Received By	Date	Time

Comments

DISTRIBUTION: WHITE - Returned to Client with Report; CANARY - Stays with the Sample; PINK - Field Copy



Lot #(s): F8F050334
- 3550 - 544

Client: Nature COC/RFA No: 062466 Date: 4/5/08
Quote No: 79192 Initiated By: bn Time: 09:5

Shipping Information

Shipper Name: FE Multiple Packages Y (N)
Shipping # (s)*: 8156 2694 6664 Sample Temperature (s)**: 7
1. _____ 6. _____
2. _____ 7. _____
3. _____ 8. _____
4. _____ 9. _____
5. _____ 10. _____

*Numbered shipping lines correspond to Numbered Sample Temp lines
**Sample must be received at 4°C ± 2°C- If not, note contents below. Temperature variance does NOT affect the following: Metals-Liquid or Rad tests- Liquid or Solids

Condition (Circle "Y" for yes, "N" for no and "N/A" for not applicable):

1. <u>(Y)</u> N	Are there custody seals present on the cooler?	8. Y <u>(N)</u>	Are there custody seals present on bottles?
2. Y <u>(N)</u> N/A	Do custody seals on cooler appear to be tampered with?	9. Y N <u>(N/A)</u>	Do custody seals on bottles appear to be tampered with?
3. <u>(Y)</u> N	Were contents of cooler frisked after opening, but before unpacking?	10. <u>(Y)</u> N N/A	Was sample received with proper pH? (If not, make note below)
4. <u>(Y)</u> N	Sample received with Chain of Custody?	11. Y N	If N/A- Was pH taken by original TestAmerica lab?
5. <u>(Y)</u> N N/A	Does the Chain of Custody match sample ID's on the container(s)?	12. <u>(Y)</u> N	Sample received in proper containers?
6. Y <u>(N)</u>	Was sample received broken?	13. Y N <u>(N/A)</u>	Headspace in VOA or TOX liquid samples? (If Yes, note sample ID's below)
7. <u>(Y)</u> N	Is sample volume sufficient for analysis?	14. Y N	Was Internal COC/Workshare received?

¹ For DOE-AL (Pantex, LANL, Sandia) sites, pH of ALL containers received must be verified, EXCEPT VOA, TOX and soils.

Notes:

Corrective Action:
 Client Contact Name: _____ Informed by: _____
 Sample(s) processed "as is"
 Sample(s) on hold until: _____ If released, notify: _____
Project Management Review: _____ Date: 6-6-8
THIS FORM MUST BE COMPLETED AT THE TIME THE ITEMS ARE BEING CHECKED IN. IF ANY ITEM IS COMPLETED BY SOMEONE OTHER THAN THE INITIATOR, THEN THAT PERSON IS REQUIRED TO APPLY THEIR INITIAL AND THE DATE NEXT TO THAT ITEM.
ADMIN-0004, REVISED 08/06/07\AS\svr01\QA\FORMS\ST-LOUIS\ADMIN\Aadmin004 rev11.doc