

10 CFR 50.75(f)(1)

RS-09-111

August 27, 2009

U.S. Nuclear Regulatory Commission
ATTN: Document Control Desk
Washington, DC 20555-0001Clinton Power Station
Facility Operating License No. NPF-62
NRC Docket No. 50-461**Subject:** Submittal of Clinton Power Station Site-Specific SAFSTOR
Decommissioning Cost Estimate**Reference:** Letter from Keith R. Jury (Exelon Generation Company) to U.S. NRC,
"Decommissioning Funding Assurance Plan," dated July 29, 2009

In the referenced letter, Exelon Generation Company, LLC (EGC) committed to provide a site-specific SAFSTOR Decommissioning Cost Estimate (DCE) for Clinton Power Station (CPS). The DCE is provided as Attachment 1, and, in accordance with 10 CFR 50.75(b)(1), is greater than the amount specified in 10 CFR 50.75(c). The DCE has been performed assuming that CPS is granted license extension, since it is intended to reflect the most likely decommissioning scenario for CPS. However, this determination of the minimum funding requirement does not credit the additional 20-year license renewal period.

Attachment 2 shows the radiological decommissioning (license termination) cash flow based on the DCE in Attachment 1, assuming the SAFSTOR scenario, and does not include the costs of dismantling non-radiological systems and structures or the cost of managing and storing spent fuel onsite. EGC has not made a final determination of the decommissioning approach for CPS. For the purpose of choosing a decommissioning option to demonstrate adequacy of funding to meet regulatory requirements, the SAFSTOR option has been selected. EGC may choose a different decommissioning option in the future, recognizing that the chosen option must meet NRC requirements for decommissioning funding.

The costs presented in Attachment 2 occur 20 years earlier than those in the Attachment 1 DCE to model the current license expiration date. No credit is taken for license renewal. The cash flow analysis assumes a 2% annual real rate of return on trust fund dollars until plant shutdown and on remaining trust fund dollars through the decommissioning period. The site-specific estimate is based on a period of safe storage specifically described in the Attachment 1 DCE. The Attachment 1 DCE presents the results in 2007 dollars. These results are converted into 2009 dollars by using the latest site-specific escalation factor, which is re-calculated on an annual basis.


For CPS, the decommissioning funding assurance is provided by the prepayment method, coupled with an external trust fund, in accordance with 10 CFR 50.75(e)(1)(i). There are no additional amounts to be collected from ratepayers for CPS, nor are there any contracts relied upon pursuant to 10 CFR 50.75(e)(1)(v).

Attachment 3 presents the calculation of radiological decommissioning funding assurance. The Table in Attachment 3 compares the funding assurance, calculated using the NRC generic formula, as recently published by the NRC, to the funding assurance calculated using the site-specific DCE methodology, as allowed by 10 CFR 50.75(e)(1)(i). Based on the site-specific methodology, and July 31, 2009 trust fund values, CPS meets all NRC radiological decommissioning funding assurance requirements.

There are no new regulatory commitments contained in this letter.

If you have any questions about this letter, please contact Patrick Simpson at (630) 657-2823.

Respectfully,



Patrick R. Simpson
Manager – Licensing
Exelon Generation Company, LLC

- Attachments:
1. Clinton Power Station Decommissioning Cost Estimate
 2. Clinton Power Station Radiological Decommissioning Projected SAFSTOR Cash Flow
 3. Clinton Power Station NRC Funding Assurance Calculations

ATTACHMENT 1

**Clinton Power Station
Decommissioning Cost Estimate**

DECOMMISSIONING COST ANALYSIS
for the
CLINTON POWER STATION



prepared for

AmerGen Energy, LLC

prepared by

TLG Services, Inc.
Bridgewater, Connecticut

October 2007

APPROVALS





| | | |
|---------------------------------------|---|---------------------------|
| Project Manager |  _____ William A. Cloutier, Jr. | <u>10/29/2007</u> Date |
| Project Engineer |  _____ Albert A. Koehl | <u>10/29/2007</u> Date |
| Technical Manager |  _____ Francis W. Seymore | <u>10/29/07</u> Date |
| Quality Assurance Manager (acting) |  _____ Joseph J. Adler | <u>10/29/07</u> Date |

TABLE OF CONTENTS

| <u>SECTION</u> | <u>PAGE</u> |
|--|--------------------|
| EXECUTIVE SUMMARY..... | vii-xvi |
| 1. INTRODUCTION | 1-1 |
| 1.1 Objectives of Study | 1-1 |
| 1.2 Site Description..... | 1-1 |
| 1.3 Regulatory Guidance | 1-2 |
| 1.3.1 Nuclear Waste Policy Act..... | 1-4 |
| 1.3.2 Low-Level Radioactive Waste Acts | 1-6 |
| 1.3.3 Radiological Criteria for License Termination..... | 1-7 |
| 2. DECOMMISSIONING ALTERNATIVES..... | 2-1 |
| 2.1 DECON..... | 2-2 |
| 2.1.1 Period 1 - Preparations | 2-2 |
| 2.1.2 Period 2 - Decommissioning Operations..... | 2-4 |
| 2.1.3 Period 3 - Site Restoration | 2-8 |
| 2.1.4 ISFSI Operations and Decommissioning | 2-9 |
| 2.2 SAFSTOR AND DELAYED DECOMMISSIONING..... | 2-10 |
| 2.2.1 Period 1 - Preparations | 2-10 |
| 2.2.2 Period 2 - Dormancy..... | 2-11 |
| 2.2.3 Periods 3 and 4 - Delayed Decommissioning..... | 2-12 |
| 2.2.4 Period 5 - Site Restoration | 2-14 |
| 3. COST ESTIMATE..... | 3-1 |
| 3.1 Basis of Estimate | 3-1 |
| 3.2 Methodology | 3-1 |
| 3.3 Financial Components of the Cost Model | 3-3 |
| 3.3.1 Contingency | 3-3 |
| 3.3.2 Financial Risk..... | 3-5 |
| 3.4 Site-Specific Considerations..... | 3-7 |
| 3.4.1 Spent Fuel Management..... | 3-7 |
| 3.4.2 Reactor Vessel and Internal Components | 3-10 |
| 3.4.3 Primary System Components..... | 3-11 |
| 3.4.4 Main Turbine and Condenser..... | 3-11 |
| 3.4.5 Transportation Methods | 3-12 |
| 3.4.6 Low-Level Radioactive Waste Disposal..... | 3-12 |
| 3.4.7 Site Conditions Following Decommissioning | 3-14 |

TABLE OF CONTENTS
(continued)

| <u>SECTION</u> | <u>PAGE</u> |
|---|--------------------|
| 3.5 Assumptions..... | 3-14 |
| 3.5.1 Estimating Basis | 3-14 |
| 3.5.2 Labor Costs | 3-15 |
| 3.5.3 Design Conditions..... | 3-15 |
| 3.5.4 General..... | 3-16 |
| 3.6 Cost Estimate Summary | 3-18 |
| 4. SCHEDULE ESTIMATE | 4-1 |
| 4.1 Schedule Estimate Assumptions | 4-1 |
| 4.2 Project Schedule..... | 4-2 |
| 5. RADIOACTIVE WASTES | 5-1 |
| 6. RESULTS | 6-1 |
| 7. REFERENCES | 7-1 |

TABLES

| | |
|--|------|
| Summary of Decommissioning Cost Elements, DECON | xv |
| Summary of Decommissioning Cost Elements, Delayed DECON | xvi |
| Summary of Decommissioning Cost Elements, SAFSTOR..... | xvii |
| 3.1 Schedule of Annual Expenditures, DECON | 3-19 |
| 3.2 Schedule of Annual Expenditures, Delayed DECON..... | 3-20 |
| 3.3 Schedule of Annual Expenditures, SAFSTOR..... | 3-21 |
| 5.1 Decommissioning Waste Summary, DECON | 5-3 |
| 5.2 Decommissioning Waste Summary, Delayed DECON..... | 5-4 |
| 5.3 Decommissioning Waste Summary, SAFSTOR..... | 5-5 |
| 6.1 Summary of Decommissioning Cost Elements, DECON | 6-4 |
| 6.2 Summary of Decommissioning Cost Elements, Delayed DECON..... | 6-5 |
| 6.3 Summary of Decommissioning Cost Elements, SAFSTOR..... | 6-6 |

**TABLE OF CONTENTS
(continued)**

SECTION PAGE

FIGURES

| | | |
|-----|--|-----|
| 4.1 | Activity Schedule | 4-3 |
| 4.2 | Decommissioning Timeline, DECON | 4-4 |
| 4.3 | Decommissioning Timeline, Delayed DECON..... | 4-5 |
| 4.4 | Decommissioning Timeline, SAFSTOR | 4-6 |

APPENDICES

| | | |
|----|---|-----|
| A. | Unit Cost Factor Development..... | A-1 |
| B. | Unit Cost Factor Listing | B-1 |
| C. | Detailed Cost Analysis, DECON | C-1 |
| D. | Detailed Cost Analysis, Delayed DECON | D-1 |
| E. | Detailed Cost Analysis, SAFSTOR | E-1 |

REVISION LOG

| No. | CRA No. | Date | Item Revised | Reason for Revision |
|------------|----------------|-------------|---------------------|----------------------------|
| 0 | | | 10-29-2007 | Original Issue |

EXECUTIVE SUMMARY

This report presents estimates of the cost to decommission the Clinton Power Station (Clinton) for the identified decommissioning scenarios following a scheduled cessation of plant operations. The analysis relies upon site-specific, technical information, developed in an evaluation in 2003-04 ^[1] for AmerGen Energy, LLC (AmerGen), a wholly owned subsidiary of Exelon Corporation, and updated to reflect current assumptions pertaining to the disposition of the nuclear unit and relevant industry experience in undertaking such projects. The updated estimates are designed to provide AmerGen with sufficient information to assess their financial obligations, as they pertain to the eventual decommissioning of the nuclear station.

The primary goal of the decommissioning is the removal and disposal of the contaminated systems and structures so that the plant's operating license can be terminated. The analysis recognizes that spent fuel will be stored at the site in the fuel building's storage pool and/or in an independent spent fuel storage installation (ISFSI) until such time that it can be transferred to a Department of Energy (DOE) facility. Consequently, the estimates also include those costs to manage and subsequently decommission these storage facilities.

The estimates are based on numerous fundamental assumptions, including regulatory requirements, project contingencies, low-level radioactive waste disposal practices, high-level radioactive waste management options, and site restoration requirements. The estimates incorporate a minimum cooling period of approximately five and one-half years for the spent fuel that resides in the fuel building's storage pool when operations cease. In the DECON and SAFSTOR scenarios, any residual fuel remaining in the pool after the cooling period is relocated to the ISFSI to await transfer to a DOE facility (the fuel is assumed to remain in the storage pool for the Delayed DECON scenario and transferred directly from the pool to an off-site DOE facility). The estimates also include the dismantling of non-essential structures and limited restoration of the site.

Alternatives and Regulations

The Nuclear Regulatory Commission (NRC or Commission) provided initial decommissioning requirements in its rule adopted on June 27, 1988.^[2] In this rule,

¹ "Decommissioning Cost Analysis for the Clinton Power Station," Document No. E16-1455-007, Rev. 0, TLG Services, Inc., May 2004

² U.S. Code of Federal Regulations, Title 10, Parts 30, 40, 50, 51, 70 and 72 "General Requirements for Decommissioning Nuclear Facilities," Nuclear Regulatory Commission, Federal Register Volume 53,

the NRC set forth financial criteria for decommissioning licensed nuclear power facilities. The regulations addressed planning needs, timing, funding methods, and environmental review requirements for decommissioning. The rule also defined three decommissioning alternatives as being acceptable to the NRC: DECON, SAFSTOR, and ENTOMB.

DECON is defined as "the alternative in which the equipment, structures, and portions of a facility and site containing radioactive contaminants are removed or decontaminated to a level that permits the property to be released for unrestricted use shortly after cessation of operations."^[3]

SAFSTOR is defined as "the alternative in which the nuclear facility is placed and maintained in a condition that allows the nuclear facility to be safely stored and subsequently decontaminated (deferred decontamination) to levels that permit release for unrestricted use."^[4] Decommissioning is to be completed within 60 years, although longer time periods will be considered when necessary to protect public health and safety.

ENTOMB is defined as "the alternative in which radioactive contaminants are encased in a structurally long-lived material, such as concrete; the entombed structure is appropriately maintained and continued surveillance is carried out until the radioactive material decays to a level permitting unrestricted release of the property."^[5] As with the SAFSTOR alternative, decommissioning is currently required to be completed within 60 years.

The 60-year restriction has limited the practicality for the ENTOMB alternative at commercial reactors that generate significant amounts of long-lived radioactive material. In 1997, the Commission directed its staff to re-evaluate this alternative and identify the technical requirements and regulatory actions that would be necessary for entombment to become a viable option. The resulting evaluation provided several recommendations, however, rulemaking has been deferred based upon several factors (e.g., no licensee has committed to pursuing the entombment option, the unresolved issues associated with the disposition of greater-than-Class C material (GTCC), and the NRC's current priorities) at least until after the additional research studies are complete. The Commission concurred with the staff's recommendation.

Number 123 (p 24018 et seq.), June 27, 1988

³ Ibid. Page FR24022, Column 3

⁴ Ibid.

⁵ Ibid. Page FR24023, Column 2

In 1996, the NRC amended its decommissioning regulations to clarify ambiguities and codify procedures and terminology as a means of enhancing efficiency and uniformity in the decommissioning process.^[6] The amendments allow for greater public participation and better define the transition process from operations to decommissioning. Regulatory Guide 1.184, issued in July 2000, further described the methods and procedures acceptable to the NRC staff for implementing the requirements of the 1996 amendments relating to the initial activities and major phases of the decommissioning process. The costs and schedules presented in this analysis follow the general guidance and processes described in these regulations.

Decommissioning Scenarios

The following scenarios were evaluated and are representative of the alternatives available to the owner:

1. **DECON:** The plant's operating license currently expires on September 29, 2026. However, for purposes of this study, the license is assumed to be renewed for an additional 20 years (until 2046). The first scenario assumes that an ISFSI is constructed to accommodate any residual spent fuel so as to facilitate decontamination and dismantling activities within the fuel building. Spent fuel storage operations continue at the site until the transfer of the fuel to the DOE is complete, assumed to be in the year 2058.
2. **Delayed DECON:** In the second scenario, the unit is prepared for an abbreviated period of storage. The spent fuel discharged to the storage pool once operations cease remains in the pool until it can be transferred to a DOE facility. Decommissioning is delayed until the transfer of the fuel to the DOE is complete (i.e., in the year 2058). The unit is then decommissioned.
3. **SAFSTOR:** The nuclear unit is placed into safe-storage in the third scenario. However, decommissioning is deferred beyond the fuel storage period to the maximum extent possible; termination of the license would conclude within the maximum required 60-year period. As in the DECON scenario, spent fuel is relocated to an ISFSI until it can be transferred to a DOE facility. Dormancy continues following the removal of spent fuel from the site, timed to allow final decommissioning and license termination to be completed within 60 years of final shutdown.

⁶ U.S. Code of Federal Regulations, Title 10, Parts 2, 50, and 51, "Decommissioning of Nuclear Power Reactors," NRC, Federal Register Volume 61, (p 39278 et seq.), July 29, 1996

Methodology

The methodology used to develop the estimates described within this document follows the basic approach originally presented in the cost estimating guidelines ^[7] developed by the Atomic Industrial Forum (now Nuclear Energy Institute). This reference describes a unit factor method for determining decommissioning activity costs. The unit factors used in this analysis incorporate site-specific costs and the latest available information on worker productivity in decommissioning.

An activity duration critical path is used to determine the total decommissioning program schedule. The schedule is relied upon in calculating the carrying costs, which include program management, administration, field engineering, equipment rental, and support services such as quality control and security. This systematic approach for assembling decommissioning estimates ensures a high degree of confidence in the reliability of the resulting cost estimate.

Contingency

Consistent with standard cost estimating practice, contingencies are applied to the decontamination and dismantling costs as "specific provision for unforeseeable elements of cost within the defined project scope, particularly important where previous experience relating estimates and actual costs has shown that unforeseeable events which will increase costs are likely to occur."^[8] The cost elements in the estimates are based on ideal conditions; therefore, the types of unforeseeable events that are almost certain to occur in decommissioning, based on industry experience, are addressed through a percentage contingency applied on a line-item basis. This contingency factor is a nearly universal element in all large-scale construction and demolition projects. It should be noted that contingency, as used in this analysis, does not account for price escalation and inflation in the cost of decommissioning over the remaining operating life of the station.

The use and role of contingency within decommissioning estimates is not a safety factor issue. Safety factors provide additional security and address situations that may never occur. Contingency funds, by contrast, are expected to be fully expended throughout the program. Inclusion of contingency is necessary to provide assurance that sufficient funding will be available to accomplish the intended tasks.

⁷ T.S. LaGuardia et al., "Guidelines for Producing Commercial Nuclear Power Plant Decommissioning Cost Estimates," AIF/NESP-036, May 1986

⁸ Project and Cost Engineers' Handbook, Second Edition, American Association of Cost Engineers, Marcel Dekker, Inc., New York, New York, p. 239

Low-Level Radioactive Waste Disposal

The contaminated and activated material generated in the decontamination and dismantling of a commercial nuclear reactor is classified as low-level (radioactive) waste, although not all of the material is suitable for “shallow-land” disposal. With the passage of the “Low-Level Radioactive Waste Policy Act” in 1980,^[9] and its Amendments of 1985,^[10] the states became ultimately responsible for the disposition of low-level radioactive waste generated within their own borders.

AmerGen is currently able to access the disposal facility in Barnwell, South Carolina. However, in June 2000, South Carolina formally joined with Connecticut and New Jersey to form the Atlantic Compact. The legislation allows South Carolina to gradually limit access to the Barnwell facility, with only Atlantic Compact members having access to the facility after mid-year 2008. At that time, EnergySolutions’ disposal facility in Clive, Utah may be the only alternative destination for a majority of the waste forms generated from decontamination and dismantling. As such, the costs reported for direct disposal (burial) are primarily based upon Exelon’s current pricing agreement with EnergySolutions.

EnergySolutions does not have a license to dispose of the more highly radioactive waste (Class B and C as defined by 10 CFR §61) generated in the decontamination and dismantling of the reactor vessel. In the interim (at least until new waste disposal options become available) and for purposes of this analysis, waste disposal costs for this material (generally less than 2% of the total waste volume) are based upon Exelon’s currently negotiated cost of disposal at the Barnwell site.

Material exceeding Class C limits (limited to material closest to the reactor core and comprising approximately 0.2% of the total waste volume) is generally not suitable for shallow-land disposal. This material is packaged in the same multipurpose canisters used for spent fuel storage/transport and designated for geologic disposal.

A significant portion of the metallic waste generated during decommissioning may only be potentially contaminated by radioactive materials. This waste can be surveyed on site or shipped off site to licensed facilities for further analysis, for processing and/or for conditioning/recovery. Reduction in the volume of low-level radioactive waste requiring disposal in a licensed low-level radioactive waste disposal facility can be accomplished through a variety of methods, including analyses and surveys or decontamination to eliminate the portion of waste that does

⁹ “Low-Level Radioactive Waste Policy Act of 1980,” Public Law 96-573, 1980

¹⁰ “Low-Level Radioactive Waste Policy Amendments Act of 1985,” Public Law 99-240, 1986

not require disposal as radioactive waste, compaction, incineration or metal melt. The estimates reflect the savings from waste recovery/volume reduction.

High-Level Radioactive Waste Management

Congress passed the “Nuclear Waste Policy Act”^[11] (NWPA) in 1982, assigning the responsibility for disposal of the spent nuclear fuel created by the commercial nuclear generating plants to the DOE. Two permanent disposal facilities were envisioned, as well as an interim storage facility. To recover the cost, the legislation created a Nuclear Waste Fund through which money is collected from the sale of electricity generated by the power plants. The NWPA, along with the individual disposal contracts with the utilities, specified that the DOE was to begin accepting spent fuel by January 31, 1998.

Since the original legislation, the DOE has announced several delays in the program schedule. By January 1998, the DOE had failed to initiate the disposal of spent nuclear fuel and high level waste, as required by the NWPA and the utility contracts. As a result, utilities initiated legal action against the DOE. While legal actions continue, the DOE has no plans to receive spent fuel prior to completing the construction of its geologic repository.

Operation of DOE’s yet-to-be constructed repository is contingent upon the review and approval of the facility’s license application by the NRC and the successful resolution of pending litigation. The latest timetable for submittal of the license application is mid-2008. Assuming a timely review, DOE expects that receipt of fuel could begin as early as 2017,^[12] although 2020 may be more likely according to the director of the DOE’s waste program.^[13]

Once the repository is operational, fuel acceptance will be prioritized and spent fuel assemblies will need to meet certain acceptance criteria, including heat output. These conditions require that the fuel discharged upon the cessation of operations be actively cooled and stored for a minimum period at the generating site prior to transfer (a minimum of five years as defined in 10CFR§961 for standard fuel). As such, the NRC requires that licensees establish a program to manage and provide funding for the management of all irradiated fuel at the reactor until title of the fuel is transferred to the Secretary of Energy, pursuant to 10CFR§50.54(bb).^[14] This

¹¹ “Nuclear Waste Policy Act of 1982 and Amendments,” U.S. Department of Energy’s Office of Civilian Radioactive Management, 1982

¹² “DOE Announces Yucca Mountain License Application Schedule”, U.S. Department of Energy’s Office of Public Affairs, Press Release July 19, 2006

¹³ Remarks of OCRWM Director Ward Sproat to the National Academy of Science, November 2006

¹⁴ U.S. Code of Federal Regulations, Title 10, Part 50, “Domestic Licensing of Production and Utilization Facilities,”

funding requirement is fulfilled through inclusion of certain cost elements in the decommissioning estimates, for example, associated with the isolation and continued operation of the spent fuel pool and/or ISFSI.

At shutdown, the spent fuel pool is expected to contain freshly discharged assemblies (from the most recent refueling cycles) as well as the final reactor core. In the DECON and SAFSTOR scenarios the assemblies are packaged into multipurpose canisters for transfer to a newly constructed ISFSI. A five and one-half year cooling period is provided for the final core to meet the conditions for dry storage.

Once the storage pool is emptied, the fuel building can be either decontaminated and dismantled or prepared for long-term storage. The ISFSI, which can be operated under the station's general license, will be designed to accommodate the dry storage casks needed to off-load the wet storage pool. In the Delayed DECON scenario, the storage pool remains operational and used for the interim storage of the fuel until the transfer to DOE can be completed (no ISFSI is required).

The DOE's generator allocation/receipt schedules are based upon the oldest fuel receiving the highest priority. For purposes of this analysis, acceptance of commercial spent fuel by the DOE is expected to begin in 2018. With a large fleet of reactors, Exelon is able to re-assign allocations between its units to minimize on-site storage costs. Assuming spent fuel from the older units is given priority and with a maximum rate of transfer of 3,000 metric tons of uranium (MTU)/year, the assemblies residing in the Clinton storage pool at the time of shutdown would be scheduled for pickup in the years 2056 through 2058 (assuming the cessation of plant operations in 2046). This equates to 64 multi-purpose canisters (at 68 assemblies per canister).

Exelon's strongly held position is that the DOE has a contractual obligation to accept Clinton's fuel in a timely manner and consistent with its contract commitments. No assumption made in this study should be interpreted to be inconsistent with this claim. However, at this time, including the cost of storing spent fuel in this study is the most reasonable approach because it insures the availability of sufficient decommissioning funds at the end of the station's life if, contrary to its contractual obligation, the DOE has not performed.

Site Restoration

The efficient removal of the contaminated materials at the site will result in damage to many of the site structures. Blasting, coring, drilling, and the other decontamination activities will substantially damage power block structures, potentially weakening the footings and structural supports. Prompt demolition once the license is terminated is clearly the most appropriate and cost-effective option. It is unreasonable to anticipate that these structures would be repaired and preserved after the radiological contamination is removed. The cost to dismantle site structures with a work force already mobilized is more efficient and less costly than if the process were deferred. Experience at shutdown generating stations has shown that plant facilities quickly degrade without maintenance, adding additional expense and creating potential hazards to the public and the demolition work force. Consequently, this analysis assumes that non-essential site structures within the restricted access area are removed to a nominal depth of three feet below the local grade level wherever possible. The site is then graded and stabilized.

Summary

The costs to decommission Clinton were evaluated for several decommissioning scenarios, incorporating the attributes of both the DECON and SAFSTOR decommissioning alternatives. Regardless of the timing of the decommissioning activities, the estimates assume the eventual removal of all the contaminated and activated plant components and structural materials, such that the facility operator may then have unrestricted use of the site with no further requirement for an operating license. Delayed decommissioning is initiated after the spent fuel has been removed from the site and is accomplished within the 60-year period required by current NRC regulations. In the interim, the spent fuel remains in storage at the site until such time that the transfer to a DOE facility can be completed. Once the transfer is complete, the storage facilities are also decommissioned.

The scenarios analyzed for the purpose of generating the estimates are described in Section 2. The assumptions are presented in Section 3, along with schedules of annual expenditures. The major cost contributors are identified in Section 6, with detailed activity costs, waste volumes, and associated manpower requirements delineated in Appendices C, D, and E. Cost summaries for the various scenarios are provided at the end of this section for the major cost components.

SUMMARY OF DECOMMISSIONING COST ELEMENTS

DECON

(thousands of 2007 dollars)

| Activity | Total |
|--|----------------|
| Decontamination | 20,716 |
| Removal | 158,458 |
| Packaging | 15,829 |
| Transportation | 10,548 |
| Waste Disposal | 55,662 |
| Off-site Waste Processing | 25,564 |
| Program Management ^[1] | 298,887 |
| Spent Fuel Pool Isolation | 10,503 |
| Spent Fuel Management | 124,876 |
| Insurance and Regulatory Fees | 10,669 |
| Energy | 6,731 |
| Characterization and Licensing Surveys | 15,676 |
| Property Taxes | 22,305 |
| Miscellaneous Equipment | 5,972 |
| Site O&M | 3,666 |
| Total ^[2] | 786,061 |
| | |
| NRC License Termination | 547,591 |
| Spent Fuel Management | 155,245 |
| Site Restoration | 83,225 |

^[1] Includes engineering and security

^[2] Columns may not add due to rounding

**SUMMARY OF DECOMMISSIONING COST ELEMENTS
DELAYED DECON**
(thousands of 2007 dollars)

| Activity | Total |
|--|----------------|
| Decontamination | 28,052 |
| Removal | 148,111 |
| Packaging | 12,819 |
| Transportation | 7,604 |
| Waste Disposal | 37,773 |
| Off-site Waste Processing | 25,564 |
| Program Management ^[1] | 353,365 |
| Spent Fuel Pool Isolation | 10,503 |
| Spent Fuel Management | 31,915 |
| Insurance and Regulatory Fees | 15,732 |
| Energy | 8,872 |
| Characterization and Licensing Surveys | 17,100 |
| Property Taxes | 29,948 |
| Miscellaneous Equipment | 9,630 |
| Site O&M | 5,663 |
| Total ^[2] | 742,651 |
| | |
| NRC License Termination | 476,232 |
| Spent Fuel Management | 181,048 |
| Site Restoration | 85,372 |

^[1] Includes engineering and security

^[2] Columns may not add due to rounding

**SUMMARY OF DECOMMISSIONING COST ELEMENTS
SAFSTOR**
(thousands of 2007 dollars)

| Activity | Total |
|--|------------------|
| Decontamination | 27,039 |
| Removal | 152,473 |
| Packaging | 12,025 |
| Transportation | 6,251 |
| Waste Disposal | 30,714 |
| Off-site Waste Processing | 30,148 |
| Program Management ^[1] | 424,198 |
| Spent Fuel Pool Isolation | 10,503 |
| Spent Fuel Management | 123,640 |
| Insurance and Regulatory Fees | 46,990 |
| Energy | 12,765 |
| Characterization and Licensing Surveys | 17,100 |
| Property Taxes | 76,770 |
| Miscellaneous Equipment | 22,433 |
| Site O&M | 17,901 |
| Total ^[2] | 1,010,952 |
| | |
| NRC License Termination | 691,981 |
| Spent Fuel Management | 233,606 |
| Site Restoration | 85,365 |

^[1] Includes engineering and security

^[2] Columns may not add due to rounding

1. INTRODUCTION

This report presents estimates of the cost to decommission the Clinton Power Station (Clinton), for the scenarios described in Section 2, following a scheduled cessation of plant operations. The analysis relies upon site-specific, technical information from an earlier evaluation prepared in 2003-04,^[1] updated to reflect current assumptions pertaining to the disposition of the nuclear units and relevant industry experience in undertaking such projects. The current estimate is designed to provide AmerGen Energy, LLC (AmerGen), a wholly owned subsidiary of Exelon Corporation (Exelon), with sufficient information to assess their financial obligations, as they pertain to the eventual decommissioning of the nuclear unit. It is not a detailed engineering document, but a financial analysis prepared in advance of the detailed engineering that will be required to carry out the decommissioning

1.1 OBJECTIVES OF STUDY

The objectives of this study are to prepare comprehensive estimates of the cost to decommission Clinton, to provide a sequence or schedule for the associated activities, and to develop waste stream projections from the decontamination and dismantling activities. The plant's operating license currently expires on September 29, 2026. However, for purposes of this study, the license is assumed to be renewed for an additional 20 years (until 2046).

1.2 SITE DESCRIPTION

Clinton is located in east central Illinois, approximately 60 miles northeast of Springfield. The station is comprised of a single boiling water reactor with supporting facilities.

The Nuclear Steam Supply System (NSSS) consists of a BWR/6 boiling water reactor system designed by General Electric. The reactor recirculation system is comprised of the reactor vessel and two recirculation pump loops external to the reactor vessel which provides the driving flow of water to the reactor vessel jet pumps. Each external loop contains one high-capacity, motor-driven recirculation pump and three motor-operated gate valves for pump maintenance. The recirculation loops are a part of the nuclear system process barrier and are located inside the containment structure. The design reactor thermal power level is 3473 Megawatts thermal (MWt). The corresponding net electrical output is approximately 1022 Megawatts electric (MWe).

The BWR-Mark III containment structure at Clinton consists of a lined, reinforced concrete cylinder with a hemispherical domed roof and a flat base slab. The drywell consists of a cylindrical reinforced concrete structure that surrounds the reactor vessel. The lower portion of the drywell is submerged in the suppression pool. The drywell and suppression pool are connected by three rows of circular vents which are located below the normal water level of the suppression pool.

Heat produced in the reactor is converted to electrical energy by the power conversion system. A turbine-generator system converts the thermal energy of the steam produced in the reactor into mechanical shaft power and then into electrical energy. The turbine consists of one high-pressure, double-flow turbine element, and two double-flow, low-pressure turbine elements all aligned in tandem. The generator is driven at 1800 rpm and rated at 1100 MVA. The exhaust steam from the turbine is condensed and deaerated in the main condenser. The heat rejected to the main condenser is removed by the circulating water system.

The circulating water system provides the heat sink required for removal of waste heat in the power plant's thermal cycle. The system has the principal function of removing heat by absorbing this energy in the main condenser. Water is withdrawn from Lake Clinton via the intake tunnels by the circulating water pumps. After passing through the plant condensers, the water is routed through the 3.4 mile long discharge flume back to the lake.

1.3 REGULATORY GUIDANCE

The Nuclear Regulatory Commission (NRC or Commission) provided initial decommissioning requirements in its rule "General Requirements for Decommissioning Nuclear Facilities," issued in June 1988.^{[2]*} This rule set forth financial criteria for decommissioning licensed nuclear power facilities. The regulation addressed decommissioning planning needs, timing, funding methods, and environmental review requirements. The intent of the rule was to ensure that decommissioning would be accomplished in a safe and timely manner and that adequate funds would be available for this purpose. Subsequent to the rule, the NRC issued Regulatory Guide 1.159, "Assuring the Availability of Funds for Decommissioning Nuclear Reactors,^[3]" which provided additional guidance to the licensees of nuclear facilities on the financial methods acceptable to the NRC staff for complying with the requirements of the rule. The regulatory guide addressed the funding

* Annotated references for citations in Sections 1-6 are provided in Section 7.

requirements and provided guidance on the content and form of the financial assurance mechanisms indicated in the rule.

The rule defined three decommissioning alternatives as being acceptable to the NRC: DECON, SAFSTOR, and ENTOMB. The DECON alternative assumes that any contaminated or activated portion of the plant's systems, structures, and facilities are removed or decontaminated to levels that permit the site to be released for unrestricted use shortly after the cessation of plant operations. The rule also placed limits on the time allowed to complete the decommissioning process. For SAFSTOR, the process is restricted in overall duration to 60 years, unless it can be shown that a longer duration is necessary to protect public health and safety. The guidelines for ENTOMB are similar, providing the NRC with both sufficient leverage and flexibility to ensure that these deferred options are only used in situations where it is reasonable and consistent with the definition of decommissioning. At the conclusion of a 60-year dormancy period (or longer for ENTOMB if the NRC approves such a case), the site would still require significant remediation to meet the unrestricted release limits for license termination.

The ENTOMB alternative has not been viewed as a viable option for power reactors due to the significant time required to isolate the long-lived radionuclides for decay to permissible levels. However, with recent rulemaking permitting the controlled release of a site, the NRC has re-evaluated this alternative.^[4] The resulting feasibility study, based upon an assessment by Pacific Northwest National Laboratory, concluded that the method did have conditional merit for some, if not most, reactors. However, the staff also found that additional rulemaking would be needed before this option could be treated as a generic alternative. The NRC had considered rulemaking to alter the 60-year time for completing decommissioning and to clarify the use of engineered barriers for reactor entombments.^[5] However, the NRC's staff has recommended that rulemaking be deferred, based upon several factors, e.g., no licensee has committed to pursuing the entombment option, the unresolved issues associated with the disposition of greater-than-Class C material (GTCC), and the NRC's current priorities, at least until after the additional research studies are complete. The Commission concurred with the staff's recommendation.

The NRC published amendments to its decommissioning regulations in 1996.^[6] When the regulations were originally adopted in 1988, it was assumed that the majority of licensees would decommission at the end of the facility's operating licensed life. Since that time, several licensees permanently and prematurely ceased operations. Exemptions from certain

operating requirements were required once the reactor was defueled to facilitate the decommissioning. Each case was handled individually, without clearly defined generic requirements. The NRC amended the decommissioning regulations in 1996 to clarify ambiguities and codify procedures and terminology as a means of enhancing efficiency and uniformity in the decommissioning process. The new amendments allow for greater public participation and better define the transition process from operations to decommissioning.

Under the revised regulations, licensees will submit written certification to the NRC within 30 days after the decision to cease operations. Certification will also be required once the fuel is permanently removed from the reactor vessel. Submittal of these notices will entitle the licensee to a fee reduction and eliminate the obligation to follow certain requirements needed only during operation of the reactor. Within two years of submitting notice of permanent cessation of operations, the licensee is required to submit a Post-Shutdown Decommissioning Activities Report (PSDAR) to the NRC. The PSDAR describes the planned decommissioning activities, the associated sequence and schedule, and an estimate of expected costs. Prior to completing decommissioning, the licensee is required to submit applications to the NRC to terminate the license, which will include a License Termination Plan (LTP).

1.3.1 Nuclear Waste Policy Act

Congress passed the “Nuclear Waste Policy Act”^[7] (NWPA) in 1982, assigning the responsibility for disposal of the spent nuclear fuel created by the commercial nuclear generating plants to the DOE. Two permanent disposal facilities were envisioned, as well as an interim storage facility. To recover the cost, the legislation created a Nuclear Waste Fund through which money is collected from the sale of electricity generated by the power plants. NWPA, along with the individual disposal contracts with the utilities, specified that the DOE was to begin accepting spent fuel by January 31, 1998.

Since the original legislation, the DOE has announced several delays in the program schedule. By January 1998, the DOE had failed to initiate the disposal of spent nuclear fuel and high level waste, as required by the NWPA and utility contracts. Delays continue and, as a result, generators have initiated legal action against the DOE in an attempt to resolve the impasse.^[8]

Operation of DOE's yet-to-be constructed repository is contingent upon the review and approval of the facility's license application by the NRC and the successful resolution of pending litigation. The latest timetable for submittal of the license application is mid-2008. Assuming a timely review, DOE expects that receipt of fuel could begin as early as 2017,^[9] although 2020 may be more likely according to the director of the DOE's waste program.^[10]

Once the repository is operational, fuel acceptance will be prioritized and spent fuel assemblies will need to meet certain acceptance criteria, including heat output. These conditions require that the fuel discharged upon the cessation of operations be actively cooled and stored for a minimum period at the generating site prior to transfer (five years as defined in 10CFR§961 for standard fuel). As such, the NRC requires that licensees establish a program to manage and provide funding for the management of all irradiated fuel at the reactor until title of the fuel is transferred to the Secretary of Energy, pursuant to 10CFR§50.54(bb).^[11] This funding requirement is fulfilled through inclusion of certain cost elements in the decommissioning estimate, for example, associated with the isolation and continued operation of the spent fuel pools and ISFSI.

At shutdown, the spent fuel pools are expected to contain freshly discharged assemblies (from the most recent refueling cycles) as well as the final reactor core. Over the next five and one-half years the assemblies are packaged into multipurpose canisters for transfer to the repository or to the ISFSI. It is assumed that this period provides the necessary cooling for the final core to meet DOE's transport system requirements for decay heat.

The DOE's generator allocation/receipt schedules are based upon the oldest fuel receiving the highest priority. For purposes of this analysis, the acceptance of commercial spent fuel by the DOE is expected to begin in 2018. Given this scenario and an anticipated rate of transfer, spent fuel is projected to remain at the Clinton site for approximately 12 years after the cessation of operations. Consequently, costs are included within the analysis for the continued operation of the storage pool and the construction of an ISFSI, as required, and for the long-term caretaking of the spent fuel at the site until the year 2058.

AmerGen will construct an independent spent fuel storage installation (ISFSI) to support decommissioning operations (DECON and

SAFSTOR scenarios). Once the storage pool is emptied, the fuel building is either decontaminated and dismantled or prepared for long-term storage. In the Delayed DECON scenario, the storage pool remains operational and is used for the interim storage of the fuel (i.e., no ISFSI is required).

Exelon's strongly held position is that the DOE has a contractual obligation to accept Clinton's fuel in a timely manner and consistent with its contract commitments. No assumption made in this study should be interpreted to be inconsistent with this claim. However, at this time, including the cost of storing spent fuel in this study is the most reasonable approach because it insures the availability of sufficient decommissioning funds at the end of the station's life if, contrary to its contractual obligation, the DOE has not performed.

1.3.2 Low-Level Radioactive Waste Acts

The contaminated and activated material generated in the decontamination and dismantling of a commercial nuclear reactor is classified as low-level (radioactive) waste, although not all of the material is suitable for "shallow-land" disposal. Congress passed the "Low-Level Radioactive Waste Policy Act" in 1980,^[12] declaring the states as being ultimately responsible for the disposition of low-level radioactive waste generated within their own borders. The federal law encouraged the formation of regional groups or compacts to implement this objective safely, efficiently, and economically, and set a target date of 1986 for implementation. After little progress, the "Low-Level Radioactive Waste Policy Amendments Act of 1985,"^[13] extended the implementation schedule, with specific milestones and stiff sanctions for non-compliance. However, to date, no new compact facilities have been successfully sited, licensed, and constructed.

AmerGen is currently able to access the disposal facility in Barnwell, South Carolina. However, in June 2000, South Carolina formally joined with Connecticut and New Jersey to form the Atlantic Compact. The legislation allows South Carolina to gradually limit access to the Barnwell facility, with only Atlantic Compact members having access to the facility after mid-year 2008. At that time, EnergySolutions' disposal facility in Clive, Utah may be the only alternative destination for a majority of the waste forms generated from decontamination and dismantling. As such, the costs reported for direct disposal (burial) are

primarily based upon Exelon's current pricing agreement with EnergySolutions.

EnergySolutions does not have a license to dispose of the more highly radioactive waste (Class B and C as defined by 10 CFR §61) generated in the dismantling of the reactor vessel. In the interim (at least until new waste disposal options become available) and for purposes of this analysis, waste disposal costs for this material (generally less than 2% of the total waste volume) are based upon Exelon's currently negotiated cost of disposal at the Barnwell site.

Material exceeding Class C limits (limited to material closest to the reactor core and comprising approximately 0.2% of the total waste volume) is generally not suitable for shallow-land disposal. This material is packaged in the same multipurpose canisters used for spent fuel storage/transport and designated for geologic disposal.

A significant portion of the metallic waste generated during decommissioning may only be potentially contaminated by radioactive materials. This waste can be surveyed on site or shipped off site to licensed facilities for further analysis, for processing and/or for conditioning/recovery. Reduction in the volume of low-level radioactive waste requiring disposal in a licensed low-level radioactive waste disposal facility can be accomplished through a variety of methods, including analyses and surveys or decontamination to eliminate the portion of waste that does not require disposal as radioactive waste, compaction, incineration or metal melt. The estimates reflect the savings from waste recovery/volume reduction.

1.3.3 Radiological Criteria for License Termination

In 1997, the NRC published Subpart E, "Radiological Criteria for License Termination,"^[14] amending 10 CFR §20. This subpart provides radiological criteria for releasing a facility for unrestricted use. The regulation states that the site can be released for unrestricted use if radioactivity levels are such that the average member of a critical group would not receive a Total Effective Dose Equivalent (TEDE) in excess of 25 millirem per year, and provided that residual radioactivity has been reduced to levels that are As Low As Reasonably Achievable (ALARA). The decommissioning estimates for Clinton assume that the site will be remediated to a residual level consistent with the NRC-prescribed level.

It should be noted that the NRC and the Environmental Protection Agency (EPA) differ on the amount of residual radioactivity considered acceptable in site remediation. The EPA has two limits that apply to radioactive materials. An EPA limit of 15 millirem per year is derived from criteria established by the Comprehensive Environmental Response, Compensation, and Liability Act (CERCLA or Superfund).^[15] An additional limit of 4 millirem per year, as defined in 40 CFR §141.16, is applied to drinking water.^[16]

On October 9, 2002, the NRC signed an agreement with the EPA on the radiological decommissioning and decontamination of NRC-licensed sites. The Memorandum of Understanding (MOU) ^[17] provides that EPA will defer exercise of authority under CERCLA for the majority of facilities decommissioned under NRC authority. The MOU also includes provisions for NRC and EPA consultation for certain sites when, at the time of license termination, (1) groundwater contamination exceeds EPA-permitted levels; (2) NRC contemplates restricted release of the site; and/or (3) residual radioactive soil concentrations exceed levels defined in the MOU.

The MOU does not impose any new requirements on NRC licensees and should reduce the involvement of the EPA with NRC licensees who are decommissioning. Most sites are expected to meet the NRC criteria for unrestricted use, and the NRC believes that only a few sites will have groundwater or soil contamination in excess of the levels specified in the MOU that trigger consultation with the EPA. However, if there are other hazardous materials on the site, the EPA may be involved in the cleanup. As such, the possibility of dual regulation remains for certain licensees. The present study does not include any costs for this occurrence.

2. DECOMMISSIONING ALTERNATIVES

Detailed cost estimates were developed to decommission the Clinton for three variations of the approved decommissioning alternatives: DECON and SAFSTOR. Although the scenarios differ with respect to technique, process, cost, and schedule, they attain the same result: the ultimate release of the site for unrestricted use.

Three decommissioning scenarios were evaluated for the nuclear unit. The scenarios selected are representative of alternatives available to the owner and are defined as follows:

1. **DECON:** The plant's operating license currently expires on September 29, 2026. However, for purposes of this study, the license is assumed to be renewed for an additional 20 years (until 2046). The first scenario assumes that an ISFSI is constructed to accommodate any residual spent fuel so as to facilitate decontamination and dismantling activities within the fuel building. Spent fuel storage operations continue at the site until the transfer of the fuel to the DOE is complete, assumed to be in the year 2058.
2. **Delayed DECON:** In the second scenario, the unit is prepared for an abbreviated period of storage. The spent fuel discharged to the storage pool once operations cease remains in the pool until it can be transferred to a DOE facility. Decommissioning is delayed until the transfer of the fuel to the DOE is complete (i.e., in the year 2058). The unit is then decommissioned.
3. **SAFSTOR:** The nuclear unit is placed into safe-storage in the third scenario. However, decommissioning is deferred beyond the fuel storage period to the maximum extent possible; termination of the license would conclude within the maximum required 60-year period. As in the DECON scenario, spent fuel is relocated to an ISFSI until it can be transferred to a DOE facility. Dormancy continues following the removal of spent fuel from the site, timed to allow final decommissioning and license termination to be completed within 60 years of final shutdown.

The following sections describe the basic activities associated with each alternative. Although detailed procedures for each activity identified are not provided, and the actual sequence of work may vary, the activity descriptions provide a basis not only for estimating but also for the expected scope of work (i.e., engineering and planning at the time of decommissioning).

The conceptual approach that the NRC has described in its regulations divides decommissioning into three phases. The initial phase commences with the effective date of permanent cessation of operations and involves the transition of both plant and licensee from reactor operations (i.e., power production) to facilitate deactivation and closure. During the first phase, notification is to be provided to the NRC certifying the permanent cessation of operations and the removal of fuel from the reactor vessel. The licensee would then be prohibited from reactor operation.

The second phase encompasses activities during the storage period or during major decommissioning activities, or a combination of the two. The third phase pertains to the activities involved in license termination. The decommissioning estimates developed for Clinton are also divided into phases or periods; however, demarcation of the phases is based upon major milestones within the project or significant changes in the projected expenditures.

2.1 DECON

The DECON alternative, as defined by the NRC, is "the alternative in which the equipment, structures, and portions of a facility and site containing radioactive contaminants are removed or decontaminated to a level that permits the property to be released for unrestricted use shortly after cessation of operations." This study does not address the cost to dispose of the spent fuel residing at the site; such costs are funded through a surcharge on electrical generation. However, the study does estimate the costs incurred with the interim on-site storage of the fuel pending shipment by the DOE to an off-site disposal facility.

2.1.1 Period 1 - Preparations

In anticipation of the cessation of plant operations, detailed preparations are undertaken to provide a smooth transition from plant operations to site decommissioning. Through implementation of a staffing transition plan, the organization required to manage the intended decommissioning activities is assembled from available plant staff and outside resources. Preparations include the planning for permanent defueling of the reactor, revision of technical specifications applicable to the operating conditions and requirements, a characterization of the facility and major components, and the development of the PSDAR.

Engineering and Planning

The PSDAR, required within two years of the notice to cease operations, provides a description of the licensee's planned decommissioning activities, a timetable, and the associated financial requirements of the intended decommissioning program. Upon receipt of the PSDAR, the NRC will make the document available to the public for comment in a local meeting to be held in the vicinity of the reactor site. Ninety days following submittal and NRC receipt of the PSDAR, the licensee may begin to perform major decommissioning activities under a modified 10 CFR §50.59 procedure, i.e., without specific NRC approval. Major activities are defined as any activity that results in permanent removal of major radioactive components, permanently modifies the structure of the containment, or results in dismantling components (for shipment) containing GTCC, as defined by 10 CFR §61. Major components are further defined as comprising the reactor vessel and internals, large bore reactor recirculation system piping, and other large components that are radioactive. The NRC includes the following additional criteria for use of the §50.59 process in decommissioning. The proposed activity must not:

- foreclose release of the site for possible unrestricted use,
- significantly increase decommissioning costs,
- cause any significant environmental impact, or
- violate the terms of the licensee's existing license.

Existing operational technical specifications are reviewed and modified to reflect plant conditions and the safety concerns associated with permanent cessation of operations. The environmental impact associated with the planned decommissioning activities is also considered. Typically, a licensee will not be allowed to proceed if the consequences of a particular decommissioning activity are greater than that bounded by previously evaluated environmental assessments or impact statements. In this instance, the licensee would have to submit a license amendment for the specific activity and update the environmental report.

The decommissioning program outlined in the PSDAR will be designed to accomplish the required tasks within the ALARA guidelines (as defined in 10 CFR §20) for protection of personnel from exposure to radiation hazards. It will also address the continued protection of the health and safety of the public and the environment during the

dismantling activity. Consequently, with the development of the PSDAR, activity specifications, cost-benefit and safety analyses, and work packages and procedures, would be assembled to support the proposed decontamination and dismantling activities.

Site Preparations

Following final plant shutdown, and in preparation for actual decommissioning activities, the following activities are initiated:

- Characterization of the site and surrounding environs. This includes radiation surveys of work areas, major components (including the reactor vessel and its internals), internal piping, and primary shield cores.
- An ISFSI is designed, licensed and constructed to support offloading the spent fuel pool in support of the decommissioning program.
- Isolation of the spent fuel storage pool and fuel handling systems, such that decommissioning operations can commence on the balance of the plant. Decommissioning operations are scheduled around the fuel handling areas to optimize the overall project schedule. The fuel is transferred to the ISFSI as it decays to the point that it meets the heat load criteria of the containers. Consequently, it is assumed that the fuel pool remain operational for approximately 5½ years following the cessation of plant operations.
- Specification of transport and disposal requirements for activated materials and/or hazardous materials, including shielding and waste stabilization.
- Development of procedures for occupational exposure control, control and release of liquid and gaseous effluent, processing of radwaste (including dry-active waste, resins, filter media, metallic and non-metallic components generated in decommissioning), site security and emergency programs, and industrial safety.

2.1.2 Period 2- Decommissioning Operations

This period includes the physical decommissioning activities associated with the removal and disposal of contaminated and activated components and structures, including the successful termination of the

10 CFR §50 operating license. Significant decommissioning activities in this phase include:

- Construction of temporary facilities and/or modification of existing facilities to support dismantling activities. This may include a centralized processing area to facilitate equipment removal and component preparations for off-site disposal.
- Reconfiguration and modification of site structures and facilities as needed to support decommissioning operations. This may include the upgrading of roads (on- and off-site) to facilitate hauling and transport. Modifications may be required to the containment structure to facilitate access of large/heavy equipment. Modifications may also be required to the refueling area of the reactor buildings to support the segmentation of the reactor vessel internals and component extraction.
- Design and fabrication of temporary and permanent shielding to support removal and transportation activities, construction of contamination control envelopes, and the procurement of specialty tooling.
- Procurement (lease or purchase) of shipping canisters, cask liners, and industrial packages.
- Decontamination of components and piping systems as required to control (minimize) worker exposure.
- Removal of piping and components no longer essential to support decommissioning operations.
- Transfer of the steam separator and dryer assemblies to the dryer-separator pool for segmentation. Segmentation by weight and activity maximizes the loading of the shielded transport casks. The operations are conducted under water using remotely operated tooling and contamination controls.
- Disconnection of the control blades from the drives on the vessel lower head. Blades are transferred to the spent fuel pool for packaging.
- Disassembly, segmentation, and packaging of the core shroud and in-core guide tubes. Some of the material is expected to exceed Class C disposal requirements. As such, those segments are packaged in a modified fuel storage canister for geologic disposal.

- Removal and segmentation of the remaining internals including the jet pump assemblies, fuel support castings, and core plate assembly.
- Draining and decontamination of the reactor well and the permanent sealing of the spent fuel transfer gate. Install a shielded platform for segmentation of the reactor vessel. Cutting operations are performed in air using remotely operated equipment within a contamination control envelope, with the water level maintained just below the cut to minimize the working area dose rates. Sections are transferred to the dryer-separator pool for packaging and interim storage.
- Disconnection of the control rod drives and instrumentation tubes from reactor vessel lower head. The lower reactor head and vessel supporting structure are then segmented.
- Removal of the reactor recirculation pumps. Exterior surfaces are decontaminated and openings covered. Components can serve as their own burial containers provided that all penetrations are properly sealed.
- Demolition of the sacrificial shield activated concrete by controlled demolition.
- Transfer of the spent fuel from the storage pool to the ISFSI pad for interim storage. Spent fuel storage operations continue throughout the active decommissioning period. Fuel transfer is expected to begin in 2056 and to be completed by the end of the year 2058.

At least two years prior to the anticipated date of license termination, an LTP is required. Submitted as a supplement to the Final Safety Analysis Report (FSAR) or its equivalent, the plan must include: a site characterization, description of the remaining dismantling activities, plans for site remediation, procedures for the final radiation survey, designation of the end use of the site, an updated cost estimate to complete the decommissioning, and any associated environmental concerns. The NRC will notice the receipt of the plan, make the plan available for public comment, and schedule a local meeting. LTP approval will be subject to any conditions and limitations as deemed appropriate by the Commission. The licensee may then commence with the final remediation of site facilities and services, including:

- Removal of remaining plant systems and associated components as they become nonessential to the decommissioning program or

worker health and safety (e.g., waste collection and treatment systems, electrical power and ventilation systems).

- Removal of the steel liners from the drywell, disposing of the activated and contaminated sections as radioactive waste. Removal of any activated/contaminated concrete.
- Removal of the steel liners from the steam separator and dryer pool, reactor well, and spent fuel storage pool.
- Surveys of the decontaminated areas of the containment structure.
- Removal of the contaminated equipment and material from the turbine and radwaste buildings, and any other contaminated facility. Use radiation and contamination control techniques until radiation surveys indicate that the structures can be released for unrestricted access and conventional demolition. This activity may necessitate the dismantling and disposition of most of the systems and components (both clean and contaminated) located within these buildings. This activity will facilitate surface decontamination and subsequent verification surveys required prior to obtaining release for demolition.
- Removal of the remaining components, equipment, and plant services in support of the area release survey(s).
- Routing of material removed in the decontamination and dismantling to a central processing area. Material certified to be free of contamination is released for unrestricted disposition, e.g., as scrap, recycle, or general disposal. Contaminated material is characterized and segregated for additional off-site processing (disassembly, chemical cleaning, volume reduction, and waste treatment), and/or packaged for controlled disposal at a low-level radioactive waste disposal facility.

Incorporated into the LTP is the Final Survey Plan. This plan identifies the radiological surveys to be performed once the decontamination activities are completed and is developed using the guidance provided in the “Multi-Agency Radiation Survey and Site Investigation Manual (MARSSIM).”^[18] This document incorporates the statistical approaches to survey design and data interpretation used by the EPA. It also identifies commercially available instrumentation and procedures for conducting radiological surveys. Use of this guidance ensures that the surveys are conducted in a manner that provides a high degree of confidence that applicable NRC criteria are satisfied.

Once the survey is complete, the results are provided to the NRC in a format that can be verified. The NRC then reviews and evaluates the information, performs an independent confirmation of radiological site conditions, and makes a determination on final termination of the license.

The NRC will terminate the operating license if it determines that site remediation has been performed in accordance with the LTP, and that the terminal radiation survey and associated documentation demonstrate that the facility is suitable for release.

2.1.3 Period 3 - Site Restoration

Following completion of decommissioning operations, site restoration activities will begin. Efficient removal of the contaminated materials and verification that residual radionuclide concentrations are below the NRC limits will result in substantial damage to many of the structures. Although performed in a controlled, safe manner, blasting, coring, drilling, scarification (surface removal), and the other decontamination activities will substantially degrade power block structures including the reactor, turbine and radwaste buildings. Under certain circumstances, verifying that subsurface radionuclide concentrations meet NRC site release requirements will require removal of grade slabs and lower floors, potentially weakening footings and structural supports. This removal activity will be necessary for those facilities and plant areas where historical records, when available, indicate the potential for radionuclides having been present in the soil, where system failures have been recorded, or where it is required to confirm that subsurface process and drain lines were not breached over the operating life of the station.

Prompt dismantling of site structures is clearly the most appropriate and cost-effective option. It is unreasonable to anticipate that these structures would be repaired and preserved after the radiological contamination is removed. The cost to dismantle site structures with a work force already mobilized on site is more efficient than if the process were deferred. Site facilities quickly degrade without maintenance, adding additional expense and creating potential hazards to the public as well as to future workers. Abandonment creates a breeding ground for vermin infestation as well as other biological hazards.

This cost study presumes that non-essential structures and site facilities are dismantled as a continuation of the decommissioning activity. Foundations and exterior walls are removed to a nominal depth of three feet below grade. The three-foot depth allows for the placement of gravel for drainage, as well as topsoil, so that vegetation can be established for erosion control. Site areas affected by the dismantling activities are restored and the plant area graded as required to prevent ponding and inhibit the refloating of subsurface materials.

Concrete rubble produced by demolition activities is processed to remove rebar and miscellaneous embedments. The processed material is then used on site to backfill voids. Excess materials are trucked to an off-site area for disposal as construction debris.

2.1.4 ISFSI Operations and Decommissioning

The ISFSI will continue to operate under a separate and independent license (10 CFR §72) following the termination of the §50 operating license. Assuming the DOE starts accepting fuel in 2018, transfer of spent fuel from Clinton is anticipated to begin in 2056 and continue through the year 2058.

At the conclusion of the spent fuel transfer process, the ISFSI will be decommissioned. The Commission will terminate the §72 license if it determines that the remediation of the ISFSI has been performed in accordance with an ISFSI license termination plan and that the final radiation survey and associated documentation demonstrate that the facility is suitable for release. Once the requirements are satisfied, the NRC can terminate the license for the ISFSI.

The assumed design for the ISFSI is based upon the use of a multi-purpose canister and a concrete overpack for pad storage. For purposes of this cost analysis, it is assumed that once the inner canisters containing the spent fuel assemblies have been removed, any required decontamination performed, and the license for the facility terminated, the modules can be dismantled using conventional techniques for the demolition of reinforced concrete. The concrete storage pad will then be removed, and the area graded and landscaped to conform to the surrounding environment.

2.2 SAFSTOR AND DELAYED DECOMMISSIONING

The NRC defines SAFSTOR as "the alternative in which the nuclear facility is placed and maintained in a condition that allows the nuclear facility to be safely stored and subsequently decontaminated (deferred decontamination) to levels that permit release for unrestricted use." The facility is left intact (during the dormancy period), with structures maintained in a sound condition. Systems not required to operate in support of the spent fuel pool or site surveillance and security are drained, de-energized, and secured. Minimal cleaning/removal of loose contamination and/or fixation and sealing of remaining contamination is performed. Access to contaminated areas is secured to provide controlled access for inspection and maintenance.

The engineering and planning requirements are similar to those for the DECON alternative, although a shorter time period is expected for these activities due to the more limited work scope. Site preparations are also similar to those for the DECON alternative. However, with the exception of the required radiation surveys and site characterizations, the mobilization and preparation of site facilities is less extensive.

The following discussion is appropriate for both the SAFSTOR and Delayed DECON scenarios, the primary differences being in the length of the dormancy period. In the Delayed DECON scenario, the fuel remains in the fuel building's storage pool until such time that the transfer to a DOE facility is complete. Decommissioning operations are assumed to begin once fuel is off site. By contrast, in the SAFSTOR scenario, the spent fuel is relocated to a newly constructed ISFSI. The plant remains in safe-storage after the fuel is removed from site. Decommissioning operations are initiated such that the license is terminated within the required 60-year time period.

2.2.1 Period 1 - Preparations

Preparations for long-term storage include the planning for permanent defueling of the reactors, revision of technical specifications appropriate to the operating conditions and requirements, a characterization of the facility and major components, and the development of the PSDAR.

The process of placing the plant in safe-storage includes, but is not limited to, the following activities:

- Isolation of the spent fuel storage services and fuel handling systems located in the fuel building so that safe-storage operations may commence on the balance of the plant. This activity may be carried out by plant personnel in accordance with existing operating technical specifications. Activities are scheduled around the fuel handling systems to the greatest extent possible.
- In the SAFSTOR scenario an ISFSI is designed, licensed and constructed to support offloading the spent fuel pool in support of the decommissioning program.
- Draining and de-energizing of the non-contaminated systems not required to support continued site operations or maintenance.
- Disposing of contaminated filter elements and resin beds not required for processing wastes from layup activities for future operations.
- Draining of the reactor vessel, with the internals left in place and the vessel head secured.
- Draining and de-energizing non-essential, contaminated systems with decontamination as required for future maintenance and inspection.
- Preparing lighting and alarm systems whose continued use is required; de-energizing portions of fire protection, electric power, and HVAC systems whose continued use is not required.
- Cleaning of the loose surface contamination from building access pathways.
- Performing an interim radiation survey of plant, posting warning signs where appropriate.
- Erecting physical barriers and/or securing all access to radioactive or contaminated areas, except as required for inspection and maintenance.
- Installing security and surveillance monitoring equipment and relocating security fence around secured structures, as required.

2.2.2 Period 2 - Dormancy

The second phase identified by the NRC in its rule addresses licensed activities during a storage period and is applicable to the dormancy phases of the deferred decommissioning alternatives. Dormancy activities include a 24-hour security force, preventive and corrective

maintenance on security systems, area lighting, general building maintenance, heating and ventilation of buildings, routine radiological inspections of contaminated structures, maintenance of structural integrity, and a site environmental and radiation monitoring program. Resident maintenance personnel perform equipment maintenance, inspection activities, routine services to maintain safe conditions, adequate lighting, heating, and ventilation, and periodic preventive maintenance on essential site services.

An environmental surveillance program is carried out during the dormancy period to ensure that releases of radioactive material to the environment are prevented and/or detected and controlled. Appropriate emergency procedures are established and initiated for potential releases that exceed prescribed limits. The environmental surveillance program constitutes an abbreviated version of the program in effect during normal plant operations.

Security during the dormancy period is conducted primarily to prevent unauthorized entry and to protect the public from the consequences of its own actions. The security fence, sensors, alarms, and other surveillance equipment provide security. Fire and radiation alarms are also monitored and maintained. While remote surveillance is an option, it does not offer the immediate response time of a physical presence.

The transfer of the spent fuel to a DOE facility continues during this period until complete. Fuel is shipped from the pool or the ISFSI (depending upon the scenario). After an optional period of storage (such that license terminations are accomplished within 60 years of final shutdown), it is required that the licensee submit applications to terminate the license, along with an LTP (described in Section 2.1.2), thereby initiating the third phase.

2.2.3 Periods 3 and 4 - Delayed Decommissioning

Prior to the commencement of decommissioning operations, preparations are undertaken to reactivate site services and prepare for decommissioning. Preparations include engineering and planning, a detailed site characterization, and the assembly of a decommissioning management organization. Final planning for activities and the writing of activity specifications and detailed procedures are also initiated at this time.

Much of the work in developing a termination plan is relevant to the development of the detailed engineering plans and procedures. The activities associated with this phase and the follow-on decontamination and dismantling processes are detailed in Sections 2.1.1 and 2.1.2. The primary difference between the sequences anticipated for the DECON and deferred scenarios is the absence, in the latter, of any constraint on the availability of the fuel storage facilities located within the reactor buildings for decommissioning.

Variations in the length of the dormancy period are expected to have little effect upon the quantities of radioactive wastes generated from system and structure removal operations. Given the levels of radioactivity and spectrum of radionuclides expected from fifty to sixty years of plant operation, no plant process system identified as being contaminated upon final shutdown will become releasable due to the decay period alone, i.e., there is no significant reduction in the waste generated from the decommissioning activities. However, due to the lower activity levels, a greater percentage of the waste volume can be designated for off-site processing and recovery.

The delay in decommissioning also yields lower working area radiation levels. As such, the estimates for the delayed scenarios incorporate reduced ALARA controls for the lower occupational exposure potential.

Although the initial radiation levels due to ^{60}Co will decrease during the dormancy period, the internal components of the reactor vessel will still exhibit sufficiently high radiation dose rates to require remote sectioning under water due to the presence of long-lived radionuclides such as ^{94}Nb , ^{59}Ni , and ^{63}Ni . Therefore, the dismantling procedures described for the DECON alternative would still be employed during deferred scenarios. Portions of the sacrificial shield will still be radioactive due to the presence of activated trace elements with long half-lives (^{152}Eu and ^{154}Eu). Decontamination will require controlled removal and disposal. It is assumed that radioactive corrosion products on inner surfaces of piping and components will not have decayed to levels that will permit unrestricted use or allow conventional removal. These systems and components will be surveyed as they are removed and disposed of in accordance with the existing radioactive release criteria.

2.2.4 Period 5 - Site Restoration

Following completion of decommissioning operations, site-restoration activities can begin. If the site structures are to be dismantled, dismantling as a continuation of the decommissioning process is clearly the most appropriate and cost-effective option, as described in Section 2.1.3. The basis for the dismantling cost in the deferred scenarios is consistent with that described for DECON, presuming the removal of structures and site facilities to a nominal depth of three feet below grade and the limited restoration of the site.

3. COST ESTIMATE

The cost estimates prepared for decommissioning Clinton consider the unique features of the site, including the NSSS, power generation systems, support services, site buildings, and ancillary facilities. The basis of the estimates, including the sources of information relied upon, the estimating methodology employed, site-specific considerations, and other pertinent assumptions, is described in this section.

3.1 BASIS OF ESTIMATE

The estimates were developed with site-specific, technical information developed in an evaluation prepared for AmerGen Energy in 2003-04. The information was reviewed for the current analysis and updated as deemed appropriate. The site-specific considerations and assumptions used in the previous evaluation were also revisited. Modifications were incorporated where new information was available or experience from ongoing decommissioning programs provided viable alternatives or improved processes.

3.2 METHODOLOGY

The methodology used to develop the estimates follows the basic approach originally presented in the AIF/NESP-036 study report, "Guidelines for Producing Commercial Nuclear Power Plant Decommissioning Cost Estimates,"^[19] and the DOE "Decommissioning Handbook."^[20] These documents present a unit factor method for estimating decommissioning activity costs, which simplifies the estimating calculations. Unit factors for concrete removal (\$/cubic yard), steel removal (\$/ton), and cutting costs (\$/inch) were developed using local labor rates. The activity-dependent costs were estimated with the item quantities (cubic yards and tons), developed from plant drawings and inventory documents. Removal rates and material costs for the conventional disposition of components and structures relied upon information available in the industry publication, "Building Construction Cost Data," published by R.S. Means.^[21]

This analysis reflects lessons learned from TLG's involvement in the Shippingport Station Decommissioning Project, completed in 1989, as well as the decommissioning of the Cintichem reactor, hot cells, and associated facilities, completed in 1997. In addition, the planning and engineering for the Pathfinder, Shoreham, Rancho Seco, Trojan, Yankee Rowe, Big Rock

Point, Maine Yankee, Humboldt Bay-3, Oyster Creek, Connecticut Yankee, and San Onofre-1 nuclear units have provided additional insight into the process, the regulatory aspects, and the technical challenges of decommissioning commercial nuclear units.

The unit factor method provides a demonstrable basis for establishing reliable cost estimates. The detail provided in the unit factors, including activity duration, labor costs (by craft), and equipment and consumable costs, ensures that essential elements have not been omitted. Appendix A presents the detailed development of a typical unit factor. Appendix B provides the values contained within one set of factors developed for this analysis.

Work Difficulty Factors

TLG has historically applied work difficulty adjustment factors (WDFs) to account for the inefficiencies in working in a power plant environment. WDFs were assigned to each unique set of unit factors, commensurate with the inefficiencies associated with working in confined, hazardous environments. The ranges used for the WDFs are as follows:

- | | |
|---------------------------------|------------|
| • Access Factor | 10% to 20% |
| • Respiratory Protection Factor | 10% to 50% |
| • Radiation/ALARA Factor | 10% to 40% |
| • Protective Clothing Factor | 10% to 30% |
| • Work Break Factor | 8.33% |

The factors and their associated range of values were developed in conjunction with the AIF/NESP-036 study. The application of the factors is discussed in more detail in that publication.

Scheduling Program Durations

The unit factors, adjusted by the WDFs as described above, are applied against the inventory of materials to be removed in the radiologically controlled areas. The resulting man-hours, or crew-hours, are used in the development of the decommissioning program schedule, using resource loading and event sequencing considerations. The scheduling of conventional removal and dismantling activities are based upon productivity information available from the "Building Construction Cost Data" publication.

An activity duration critical path is used to determine the total decommissioning program schedule. The schedule is relied upon in

calculating the carrying costs, which include program management, administration, field engineering, equipment rental, and support services such as quality control and security. This systematic approach for assembling decommissioning estimates ensures a high degree of confidence in the reliability of the resulting cost estimate.

3.3 FINANCIAL COMPONENTS OF THE COST MODEL

TLG's proprietary decommissioning cost model, DECCER, produces a number of distinct cost elements. These direct expenditures, however, do not comprise the total cost to accomplish the project goal, i.e., license termination and site restoration.

Inherent in any cost estimate that does not rely on historical data is the inability to specify the precise source of costs imposed by factors such as tool breakage, accidents, illnesses, weather delays, and labor stoppages. In the DECCER cost model, contingency fulfills this role. Contingency is added to each line item to account for costs that are difficult or impossible to develop analytically. Such costs are historically inevitable over the duration of a job of this magnitude; therefore, this cost analysis includes funds to cover these types of expenses.

3.3.1 Contingency

The activity- and period-dependent costs are combined to develop the total decommissioning cost. A contingency is then applied on a line-item basis, using one or more of the contingency types listed in the AIF/NESP-036 study. "Contingencies" are defined in the American Association of Cost Engineers "Project and Cost Engineers' Handbook^[22] as "specific provision for unforeseeable elements of cost within the defined project scope; particularly important where previous experience relating estimates and actual costs has shown that unforeseeable events which will increase costs are likely to occur." The cost elements in this analysis are based upon ideal conditions and maximum efficiency; therefore, consistent with industry practice, a contingency factor has been applied. In the AIF/NESP-036 study, the types of unforeseeable events that are likely to occur in decommissioning are discussed and guidelines are provided for percentage contingency in each category. It should be noted that contingency, as used in this analysis, does not account for price escalation and inflation in the cost of decommissioning over the remaining operating life of the station.

The use and role of contingency within decommissioning estimates is not a “safety factor issue.” Safety factors provide additional security and address situations that may never occur. Contingency funds are expected to be fully expended throughout the program. They also provide assurance that sufficient funding is available to accomplish the intended tasks. An estimate without contingency, or from which contingency has been removed, can disrupt the orderly progression of events and jeopardize a successful conclusion to the decommissioning process.

For example, the most technologically challenging task in decommissioning a commercial nuclear station is the disposition of the reactor vessel and internal components, now highly radioactive after a lifetime of exposure to core activity. The disposition of these components forms the basis of the critical path (schedule) for decommissioning operations. Cost and schedule are interdependent, and any deviation in schedule has a significant impact on cost for performing a specific activity.

Disposition of the reactor vessel internals involves the underwater cutting of complex components that are highly radioactive. Costs are based upon optimum segmentation, handling, and packaging scenarios. The schedule is primarily dependent upon the turnaround time for the heavily shielded shipping casks, including preparation, loading, and decontamination of the containers for transport. The number of casks required is a function of the pieces generated in the segmentation activity, a value calculated on optimum performance of the tooling employed in cutting the various subassemblies. The expected optimization, however, may not be achieved, resulting in delays and additional program costs. For this reason, contingency must be included to mitigate the consequences of the expected inefficiencies inherent in this complex activity, along with related concerns associated with the operation of highly specialized tooling, field conditions, and water clarity.

Contingency funds are an integral part of the total cost to complete the decommissioning process. Exclusion of this component puts at risk a successful completion of the intended tasks and, potentially, subsequent related activities. For this study, TLG examined the major activity-related problems (decontamination, segmentation, equipment handling, packaging, transport, and waste disposal) that necessitate a contingency. Individual activity contingencies ranged from 10% to 75%,

depending on the degree of difficulty judged to be appropriate from TLG's actual decommissioning experience. The contingency values used in this study are as follows:

| | |
|--|-----|
| Decontamination | 50% |
| Contaminated Component Removal | 25% |
| Contaminated Component Packaging | 10% |
| Contaminated Component Transport | 15% |
| Low-Level Radioactive Waste Disposal | 25% |
| Reactor Segmentation | 75% |
| NSSS Component Removal | 25% |
| Reactor Waste Packaging | 25% |
| Reactor Waste Transport | 25% |
| Reactor Vessel Component Disposal | 50% |
| GTCC Disposal | 15% |
| Non-Radioactive Component Removal | 15% |
| Heavy Equipment and Tooling | 15% |
| Supplies | 25% |
| Engineering | 15% |
| Energy | 15% |
| Characterization and Termination Surveys | 30% |
| Construction | 15% |
| Taxes and Fees | 10% |
| Insurance | 10% |
| Staffing | 15% |

The contingency values are applied to the appropriate components of the estimates on a line item basis. A composite value is then reported at the end of each estimate. For example, the composite contingency value reported for the DECON alternative is 18.6%. Values for the other alternatives are delineated within the detailed cost tables in Appendices D and E.

3.3.2 Financial Risk

In addition to the routine uncertainties addressed by contingency, another cost element that is sometimes necessary to consider when bounding decommissioning costs relates to uncertainty, or risk. Examples can include changes in work scope, pricing, job performance,

and other variations that could conceivably, but not necessarily, occur. Consideration is sometimes necessary to generate a level of confidence in the estimate, within a range of probabilities. TLG considers these types of costs under the broad term “financial risk.” Included within the category of financial risk are:

- Transition activities and costs: ancillary expenses associated with eliminating 50% to 80% of the site labor force shortly after the cessation of plant operations, added cost for worker separation packages throughout the decommissioning program, national or company-mandated retraining, and retention incentives for key personnel.
- Delays in approval of the decommissioning plan due to intervention, public participation in local community meetings, legal challenges, and national and local hearings.
- Changes in the project work scope from the baseline estimate, involving the discovery of unexpected levels of contaminants, contamination in places not previously expected, contaminated soil previously undiscovered (either radioactive or hazardous material contamination), variations in plant inventory or configuration not indicated by the as-built drawings.
- Regulatory changes (e.g., affecting worker health and safety, site release criteria, waste transportation, and disposal).
- Policy decisions altering national commitments (e.g., in the ability to accommodate certain waste forms for disposition or in the timetable for such, for example, in the start and rate of acceptance of spent fuel by the DOE).
- Pricing changes for basic inputs, such as labor, energy, materials, and burial.

It has been TLG’s experience that the results of a risk analysis, when compared with the base case estimate for decommissioning, indicate that the chances of the base decommissioning estimate’s being too high is a low probability, and the chances that the estimate is too low is a higher probability. This cost study, however, does not add any additional cost to the estimate for financial risk since there is insufficient historical data from which to project future liabilities. Consequently, the areas of uncertainty or risk are revisited periodically and addressed through repeated revisions or updates of the base estimate.

3.4 SITE-SPECIFIC CONSIDERATIONS

There are a number of site-specific considerations that affect the method for dismantling and removal of equipment from the site and the degree of restoration required. The cost impact of the considerations identified below is included in this cost study.

3.4.1 Spent Fuel Management

The cost to dispose of spent fuel generated from plant operations is not reflected within the estimates to decommission the Clinton site. Ultimate disposition of the spent fuel is within the province of the DOE's Waste Management System, as defined by the NWPA. As such, the disposal cost is financed by a 1 mill/kWhr surcharge paid into the DOE's waste fund during operations. However, the NRC requires licensees to establish a program to manage and provide funding for the management of all irradiated fuel at the reactors until title of the fuel is transferred to the Secretary of Energy. This funding requirement is fulfilled through inclusion of certain high-level waste cost elements within the estimate, as described below.

The total inventory of assemblies that will require handling during decommissioning is based upon several assumptions. The pickup of commercial fuel is assumed to begin in the year 2018. The maximum rate at which the fuel is removed from the commercial sites is based upon an annual capacity at the geologic repository of 3,000 metric tons of uranium (MTU). Any delay in the startup of the repository or decrease in the rate of acceptance will correspondingly prolong the transfer process and result in the fuel remaining at the site longer.

In the DECON and SAFSTOR scenarios, an ISFSI is constructed for the interim caretaking of the spent fuel until such time that the transfer of spent fuel to the DOE is complete. Assuming that the DOE commences repository operation in 2018, fuel is projected to be removed from the Clinton site by the year 2058. In the Delayed DECON scenario, the fuel remains in the storage pool.

Operation and maintenance costs for the storage facilities are included within the estimates and address the cost for staffing the facilities, as well as security, insurance, and licensing fees. The estimates include the costs to purchase (DECON and SAFSTOR scenarios), load, and

transfer the fuel storage canisters. Costs are also provided for the final disposition of the facilities once the transfer is complete.

Repository Startup

Operation of the DOE's yet-to-be constructed geologic repository is contingent upon the review and approval of the facility's license application by the NRC, the successful resolution of pending litigation, and the development of a national transportation system. By comparison, the NRC's review of the application for an interim storage facility submitted by the Private Fuel Storage consortium began in 1997. The Nuclear Regulatory Commission granted an operating license for the facility in September 2005, after eight years of review. With a more technically complex and politically sensitive application for permanent disposal, it is not unreasonable to expect that NRC approval to construct the repository at Yucca Mountain will require at least as long a review period. Therefore, the spent fuel management plan described in this section is predicated upon the DOE initiating the pickup of commercial fuel in the year 2018.

Spent Fuel Management Model

The Exelon nuclear fleet consists of 21 units at 11 sites in Illinois, Pennsylvania, and New Jersey, including the inactive units at Dresden, Peach Bottom, and Zion. The ability to complete the decommissioning of these units, particularly for the DECON and Delayed DECON alternatives, is highly dependent upon when the DOE is assumed to remove spent fuel from the sites.

The DOE's repository program assumes that spent fuel will be accepted for disposal from the nation's commercial nuclear plants in the order (the "queue") in which it was removed from service ("oldest fuel first").^[23] A computer model developed by Exelon Nuclear was used to determine when the DOE would provide allocations in the queue for removal of spent fuel from the individual sites. Repository operations were based upon annual industry-wide acceptance rates of 400 MTU/year for year 1, 600 MTU/year for year 2, 1200 MTU/year for year 3, 2000 MTU/year for year 4, and 3000 MTU/year for year 5 and beyond.^[24]

ISFSIs are constructed as necessary to maintain full-core discharge capability at the individual sites. Once the DOE begins repository

operations, queue allocations are used to ship spent fuel from Exelon's operating sites. Spent fuel shipments are then made from decommissioning sites in the order of retirement.

Canister Design

A multi-purpose storage canister (similar to the HOLTEC HI-STORM system), with a 68-fuel assemblies capacity, is assumed for future cask acquisitions. A unit cost of \$500,000 is used for pricing the internal multi-purpose canister (MPC), with an additional cost of \$250,000 for the concrete overpack. The DOE is assumed to provide the MPC for fuel transferred directly from the pool to the DOE at no cost to the owner.

Canister Loading and Transfer

An average cost of \$250,000 is used for the labor to load/transport the spent fuel from the pool to the ISFSI pad, based upon Exelon experience. For estimating purposes, 50% of this cost is used to estimate the cost to transfer the fuel from the ISFSI to the DOE.

Operations and Maintenance

Annual costs (excluding labor) of approximately \$738,410 and \$82,164 are used for operation and maintenance of the spent fuel pool and the ISFSI, respectively.

ISFSI Design Considerations

A multi-purpose (storage and transport) dry shielded storage canister with a vertical, reinforced concrete storage overpack is used as a basis for the cost analyses. Approximately 50% of the overpacks are assumed to have some level of neutron-induced activation as a result of the long-term storage of the fuel (i.e., to levels exceeding free-release limits). Approximately 10% of the concrete and steel is assumed to be removed from the overpacks for controlled disposal. The cost to dispose of this material, as well as the demolition of the ISFSI facility, is included in the estimates.

3.4.2 Reactor Vessel and Internal Components

The NSSS (reactor vessel and reactor recirculation system components) will be decontaminated using chemical agents prior to the start of cutting operations (for DECON alternative only). A decontamination factor (average reduction) of 10 is assumed for the process.

The reactor pressure vessel and internal components are segmented for disposal in shielded, reusable transportation casks. Segmentation is performed in the dryer-separator pool, where a turntable and remote cutter are installed. The vessel is segmented in place, using a mast-mounted cutter supported off the lower head and directed from a shielded work platform installed overhead in the reactor cavity. Transportation cask specifications and transportation regulations will dictate segmentation and packaging methodology.

The dismantling of the reactor internals will generate radioactive waste considered unsuitable for shallow land disposal (i.e., GTCC). Although the material is not classified as high-level waste, the DOE has indicated it will accept this waste for disposal at the future high-level waste repository.^[25] However, the DOE has not been forthcoming with an acceptance criteria or disposition schedule for this material, and numerous questions remain as to the ultimate disposal cost and waste form requirements. As such, for purposes of this study, the GTCC has been packaged and disposed of as high-level waste, at a cost equivalent to that envisioned for the spent fuel. It is not anticipated that the DOE would accept this waste prior to completing the transfer of spent fuel. Therefore, until such time the DOE is ready to accept GTCC waste, it is reasonable to assume that this material would remain in storage at the Clinton site.

Intact disposal of the reactor vessel and internal components can provide savings in cost and worker exposure by eliminating the complex segmentation requirements, isolation of the GTCC material, and transport/storage of the resulting waste packages. Portland General Electric (PGE) was able to dispose of the Trojan reactor as an intact package. However, its location on the Columbia River simplified the transportation analysis since:

- the reactor package could be secured to the transport vehicle for the entire journey, i.e., the package was not lifted during transport,
- there were no man-made or natural terrain features between the plant site and the disposal location that could produce a large drop, and
- transport speeds were very low, limited by the overland transport vehicle and the river barge.

As a member of the Northwest Compact, PGE had a site available for disposal of the package - the US Ecology facility in Washington State. The characteristics of this arid site proved favorable in demonstrating compliance with land disposal regulations.

It is not known whether this option will be available when Clinton ceases operation. Future viability of this option will depend upon the ultimate location of the disposal site, as well as the disposal site licensee's ability to accept highly radioactive packages and effectively isolate them from the environment. Additionally, with BWRs, the diameter of the reactor vessel may severely limit overland transport. Consequently, the study assumes the reactor vessel will require segmentation, as a bounding condition.

3.4.3 Primary System Components

Reactor recirculation piping is cut from the reactor vessel once the water level in the vessel (used for personnel shielding during dismantling and cutting operations in and around the vessel) is dropped below the nozzle zone. The piping is boxed and transported by shielded van. The reactor recirculation pumps and motors are lifted out intact, packaged, and transported for processing and/or disposal.

3.4.4 Main Turbine and Condenser

The main turbine will be dismantled using conventional maintenance procedures. The turbine rotors and shafts will be removed to a laydown area. The lower turbine casings will be removed from their anchors by controlled demolition. The main condensers will also be disassembled and moved to a laydown area. Material is then prepared for transportation to an off-site recycling facility where it will be surveyed and designated for either decontamination or volume reduction, conventional disposal, or controlled disposal. Components will be

packaged and readied for transport in accordance with the intended disposition.

3.4.5 Transportation Methods

Contaminated piping, components, and structural material other than the highly activated reactor vessel and internal components will qualify as LSA-I, II or III or Surface Contaminated Object, SCO-I or II, as described in Title 49.^[26] The contaminated material will be packaged in Industrial Packages (IP 1, IP-2, or IP-3, as defined in subpart 173.411) for transport unless demonstrated to qualify as their own shipping containers. The reactor vessel and internal components are expected to be transported in accordance with §71, as Type B. It is conceivable that the reactor, due to its limited specific activity, could qualify as LSA II or III. However, the high radiation levels on the outer surface would require that additional shielding be incorporated within the packaging so as to attenuate the dose to levels acceptable for transport.

Transport of the highly activated metal, produced in the segmentation of the reactor vessels and internal components, will be by shielded truck cask. Cask shipments may exceed 95,000 pounds, including vessel segment(s), supplementary shielding, cask tie-downs, and tractor-trailer. The maximum level of activity per shipment assumed permissible was based upon the license limits of the available shielded transport casks. The segmentation scheme for the vessel and internal segments is designed to meet these limits.

The transport of large intact components (e.g., large heat exchangers and other oversized components) will be by a combination of truck, rail, and/or multi-wheeled transporter. Truck transport costs were estimated using published tariffs from Tri-State Motor Transit.^[27]

3.4.6 Low-Level Radioactive Waste Disposal

To the greatest extent practical, metallic material generated in the decontamination and dismantling processes is treated to reduce the total volume requiring controlled disposal. The treated material, meeting the regulatory and/or site release criterion, is released as scrap, requiring no further cost consideration. Conditioning and recovery of the waste stream is performed off site at a licensed processing center.

The mass of radioactive waste generated during the various decommissioning activities is reported by line-item in Appendices C, D and E, and summarized in Section 5. The Section 5 waste summaries are consistent with 10 CFR §61 classifications. Commercially available steel containers are used for the disposal of piping, small components, and concrete. Larger components can serve as their own containers, with proper closure of all openings, access ways, and penetrations. The waste volumes are calculated on the exterior package dimensions for containerized material or a dimensional calculation for components serving as their own waste containers.

The more highly activated reactor components are transported in reusable, shielded truck casks with disposable liners. In calculating disposal costs, the burial fees are applied against the liner volume, with surcharges added for the special handling requirements and the radiological characteristics of the payload. Packaging efficiencies are lower for the highly activated materials (greater than Type A quantity waste), where high concentrations of gamma-emitting radionuclides limit the capacity of the shipping canisters.

Disposal fees are calculated using current disposal agreements, with surcharges added for the highly activated components, for example, generated in the segmentation of the reactor vessel. The cost to dispose of the majority of the material generated from the decontamination and dismantling activities (> 98%) is based upon Exelon's current disposal agreement with EnergySolutions for its facility in Clive, Utah.

Since the EnergySolutions facility is not able to accept the higher activity waste (Class B and C) generated in the decontamination of the reactor vessel and segmentation of the components closest to the core, the cost of disposal of this material (< 2% of the total volume) at a yet-to-be determined facility were based upon Exelon's rates for the Barnwell facility.

Material exceeding Class C limits (limited to material closest to the reactor core and comprising approximately 0.2% of the total waste volume) is generally not suitable for shallow-land disposal. This material is packaged in the same multipurpose canisters used for spent fuel storage/transport and designated for geologic disposal.

3.4.7 Site Conditions Following Decommissioning

The NRC will terminate (or amend) the site license if it determines that site remediation has been performed in accordance with the license termination plan, and that the terminal radiation survey and associated documentation demonstrate that the facility is suitable for release. The NRC's involvement in the decommissioning process will end at this point. Building codes and environmental regulations will dictate the next step in the decommissioning process, as well as the owner's own future plans for the site.

Non-essential structures or buildings severely damaged in decontamination process are removed to a nominal depth of three feet below grade. Concrete rubble generated from demolition activities is processed and made available as clean fill. The excavations will be regraded such that the power block area will have a final contour consistent with adjacent surroundings.

The estimates do not assume the remediation of any significant volume of contaminated soil. This assumption may be affected by continued plant operations and/or future regulatory actions, such as the development of site-specific release criteria.

3.5 ASSUMPTIONS

The following are the major assumptions made in the development of the estimates for decommissioning the site.

3.5.1 Estimating Basis

The study follows the principles of ALARA through the use of work duration adjustment factors. These factors address the impact of activities such as radiological protection instruction, mock-up training, and the use of respiratory protection and protective clothing. The factors lengthen a task's duration, increasing costs and lengthening the overall schedule. ALARA planning is considered in the costs for engineering and planning, and in the development of activity specifications and detailed procedures. Changes to worker exposure limits may impact the decommissioning cost and project schedule.

3.5.2 Labor Costs

The craft labor required to decontaminate and dismantle the nuclear units will be acquired through standard site contracting practices. The current cost of labor at the site is used as an estimating basis. Costs for site administration, operations, construction, and maintenance personnel are based upon average salary information provided by AmerGen or from comparable industry information.

AmerGen will hire a Decommissioning Operations Contractor (DOC) to manage the decommissioning. The owner will provide site security, radiological health and safety, quality assurance and overall site administration during the decommissioning and demolition phases. Contract personnel will provide engineering services (e.g., for preparing the activity specifications, work procedures, activation, and structural analyses) under the direction of AmerGen.

3.5.3 Design Conditions

Any fuel cladding failure that occurred during the lifetime of the plant is assumed to have released fission products at sufficiently low levels that the buildup of quantities of long-lived isotopes (e.g., ¹³⁷Cs, ⁹⁰Sr, or transuranics) has been prevented from reaching levels exceeding those that permit the major NSSS components to be shipped under current transportation regulations and disposal requirements.

The curie contents of the vessel and internals at final shutdown are derived from those listed in NUREG/CR-3474.^[28] Actual estimates are derived from the curie/gram values contained therein and adjusted for the different mass of the Clinton components, projected operating life, and different periods of decay. Additional short-lived isotopes were derived from CR-0130^[29] and CR-0672,^[30] and benchmarked to the long-lived values from CR-3474.

The disposal cost for the control blades removed from the vessel with the final core load is included within the estimates. Control blade residence time in the reactor is assumed to be controlled such that the blades do not become GTCC material. Disposition of any blades stored in the pool from operations is considered an operating expense and therefore not accounted for in the estimates.

Activation of the reactor building structures is confined to the sacrificial shield. More extensive activation (at very low levels) of the interior structures within containment has been detected at several reactors and their owners have elected to dispose of the affected material at a controlled facility rather than reuse the material as fill on site or send it to a landfill. The ultimate disposition of the material removed from the reactor buildings will depend upon the site release criteria selected, as well as the designated end use for the site.

3.5.4 General

Transition Activities

Existing warehouses will be cleared of non-essential material and remain for use by Exelon and its subcontractors. The plant's operating staff will perform the following activities at no additional cost or credit to the project during the transition period:

- Drain and collect fuel oils, lubricating oils, and transformer oils for recycle and/or sale.
- Drain and collect acids, caustics, and other chemical stores for recycle and/or sale.
- Processes operating waste inventories, i.e., the estimates do not address the disposition of any legacy wastes; the disposal of operating wastes during this initial period is not considered a decommissioning expense.

Scrap and Salvage

The existing plant equipment is considered obsolete and suitable for scrap as deadweight quantities only. Exelon will make economically reasonable efforts to salvage equipment following final plant shutdown. However, dismantling techniques assumed by TLG for equipment in this analysis are not consistent with removal techniques required for salvage (resale) of equipment. Experience has indicated that some buyers wanted equipment stripped down to very specific requirements before they would consider purchase. This required expensive rework after the equipment had been removed from its installed location. Since placing a salvage value on this machinery and equipment would be speculative, and the value would be small in comparison to the overall decommissioning expenses, this analysis

does not attempt to quantify the possible salvage value that an owner may realize based upon those efforts.

It is assumed, for purposes of this analysis, that any value received from the sale of scrap generated in the dismantling process would be more than offset by the on-site processing costs. The dismantling techniques assumed in the decommissioning estimates do not include the additional cost for size reduction and preparation to meet “furnace ready” conditions. For example, the recovery of copper from electrical cabling may require the removal and disposition of any contaminated insulation, an added expense. With a volatile market, the potential profit margin in scrap recovery is highly speculative, regardless of the ability to free release this material. This assumption is an implicit recognition of scrap value in the disposal of clean metallic waste at no additional cost to the project.

Furniture, tools, mobile equipment such as forklifts, trucks, bulldozers, and other property will be removed at no cost or credit to the decommissioning project. Disposition may include relocation to other facilities. Spare parts will also be made available for alternative use.

Energy

For estimating purposes, the plant is assumed to be de-energized, with the exception of those facilities associated with spent fuel storage. Replacement power costs are used for the cost of energy consumption during decommissioning for tooling, lighting, ventilation, and essential services.

Insurance

Costs for continuing coverage (nuclear liability and property insurance) following cessation of plant operations and during decommissioning are included and based upon current operating premiums. Reductions in premiums, throughout the decommissioning process, are based upon the guidance and the limits for coverage defined in the NRC’s proposed rulemaking “Financial Protection Requirements for Permanently Shutdown Nuclear Power Reactors.”^[31] NRC’s financial protection requirements are based on various reactor (and spent fuel) configurations.

Taxes

Property taxes are included for all decommissioning periods. Exelon provided a schedule of decreasing tax payments against the current tax assessment. These reductions continue until reaching a minimum property tax payment of \$1 million per year; this level is maintained for the balance of the decommissioning program.

Site Modifications

The perimeter fence and in-plant security barriers will be moved, as appropriate, to conform to the Site Security Plan in force during the various stages of the project.

3.6 COST ESTIMATE SUMMARY

A schedule of expenditures for each scenario is provided in Tables 3.1 through 3.3. Decommissioning costs are reported in the year of projected expenditure; however, the values are provided in thousands of 2007 dollars. Costs are not inflated, escalated, or discounted over the period of expenditure. The annual expenditures are based upon the detailed activity costs reported in Appendices C through E, along with the schedules discussed in Section 4.

**TABLE 3.1
SCHEDULE OF ANNUAL EXPENDITURES
DECON**
(thousands, 2007 dollars)

| Year | Labor | Equipment & Materials | Energy | Burial | Other | Total |
|------|---------|--------------------------|--------|--------|--------|---------|
| 2046 | 15,748 | 9,144 | 285 | 12 | 2,681 | 27,870 |
| 2047 | 58,639 | 31,625 | 1,394 | 1,782 | 15,380 | 108,820 |
| 2048 | 59,993 | 24,661 | 1,339 | 22,385 | 13,296 | 121,675 |
| 2049 | 62,537 | 25,927 | 1,053 | 27,317 | 7,977 | 124,811 |
| 2050 | 58,334 | 16,463 | 837 | 7,290 | 5,167 | 88,091 |
| 2051 | 58,215 | 16,196 | 831 | 6,726 | 5,088 | 87,056 |
| 2052 | 41,364 | 7,751 | 538 | 5,599 | 4,253 | 59,505 |
| 2053 | 34,407 | 5,315 | 222 | 471 | 2,693 | 43,107 |
| 2054 | 25,128 | 12,462 | 111 | 0 | 2,458 | 40,159 |
| 2055 | 25,128 | 12,462 | 111 | 0 | 2,458 | 40,159 |
| 2056 | 6,297 | 3,330 | 11 | 0 | 2,301 | 11,938 |
| 2057 | 4,286 | 2,355 | 0 | 0 | 2,277 | 8,918 |
| 2058 | 4,248 | 2,663 | 0 | 2 | 11,618 | 18,532 |
| 2059 | 1,387 | 1,957 | 0 | 265 | 1,810 | 5,420 |
| | 455,713 | 172,312 | 6,731 | 71,849 | 79,457 | 786,061 |

**TABLE 3.2
SCHEDULE OF ANNUAL EXPENDITURES
DELAYED DECON**
(thousands, 2007 dollars)

| Year | Labor | Equipment & Materials | Energy | Burial | Other | Total |
|------|---------|--------------------------|--------|--------|--------|---------|
| 2046 | 10,580 | 253 | 285 | 12 | 2,657 | 13,787 |
| 2047 | 49,525 | 5,943 | 1,108 | 285 | 20,648 | 77,509 |
| 2048 | 18,586 | 1,634 | 438 | 138 | 4,853 | 25,649 |
| 2049 | 11,144 | 947 | 222 | 32 | 3,437 | 15,781 |
| 2050 | 11,144 | 947 | 222 | 32 | 3,437 | 15,781 |
| 2051 | 11,144 | 947 | 222 | 32 | 3,437 | 15,781 |
| 2052 | 11,175 | 951 | 222 | 32 | 3,447 | 15,826 |
| 2053 | 11,144 | 947 | 222 | 32 | 3,437 | 15,781 |
| 2054 | 11,144 | 947 | 222 | 32 | 3,437 | 15,781 |
| 2055 | 11,144 | 947 | 222 | 32 | 3,437 | 15,781 |
| 2056 | 11,750 | 2,676 | 222 | 32 | 3,447 | 18,126 |
| 2057 | 12,006 | 3,534 | 222 | 32 | 3,437 | 19,231 |
| 2058 | 12,068 | 3,534 | 224 | 32 | 3,434 | 19,292 |
| 2059 | 34,131 | 1,352 | 1,108 | 43 | 2,180 | 38,814 |
| 2060 | 47,182 | 11,702 | 1,083 | 13,187 | 7,470 | 80,624 |
| 2061 | 54,705 | 16,222 | 1,021 | 23,181 | 11,423 | 106,552 |
| 2062 | 58,212 | 10,055 | 831 | 11,704 | 4,523 | 85,326 |
| 2063 | 44,405 | 6,459 | 485 | 5,087 | 3,024 | 59,460 |
| 2064 | 24,256 | 10,878 | 131 | 6 | 1,172 | 36,444 |
| 2065 | 22,101 | 12,390 | 111 | 0 | 1,015 | 35,616 |
| 2066 | 9,749 | 5,465 | 49 | 0 | 448 | 15,710 |
| | 487,291 | 98,728 | 8,871 | 53,960 | 93,799 | 742,651 |

**TABLE 3.3
SCHEDULE OF ANNUAL EXPENDITURES
SAFSTOR**
(thousands, 2007 dollars)

| Year | Labor | Equipment & Materials | Energy | Burial | Other | Total |
|------|--------|--------------------------|--------|--------|--------|---------|
| 2046 | 13,507 | 9,036 | 285 | 12 | 2,681 | 25,521 |
| 2047 | 58,847 | 33,644 | 1,108 | 285 | 20,742 | 114,626 |
| 2048 | 21,722 | 11,041 | 438 | 138 | 5,158 | 38,498 |
| 2049 | 14,164 | 10,009 | 222 | 32 | 3,809 | 28,236 |
| 2050 | 14,164 | 10,009 | 222 | 32 | 3,809 | 28,236 |
| 2051 | 14,164 | 10,009 | 222 | 32 | 3,809 | 28,236 |
| 2052 | 7,165 | 2,634 | 138 | 30 | 2,805 | 12,772 |
| 2053 | 4,923 | 289 | 111 | 30 | 2,477 | 7,830 |
| 2054 | 4,923 | 289 | 111 | 30 | 2,477 | 7,830 |
| 2055 | 4,923 | 289 | 111 | 30 | 2,477 | 7,830 |
| 2056 | 5,513 | 2,018 | 111 | 30 | 2,484 | 10,156 |
| 2057 | 5,786 | 2,877 | 111 | 30 | 2,477 | 11,280 |
| 2058 | 5,779 | 2,874 | 111 | 30 | 2,476 | 11,270 |
| 2059 | 2,769 | 284 | 111 | 29 | 2,150 | 5,343 |
| 2060 | 2,776 | 284 | 111 | 29 | 2,156 | 5,357 |
| 2061 | 2,769 | 284 | 111 | 29 | 2,150 | 5,343 |
| 2062 | 2,769 | 284 | 111 | 29 | 2,150 | 5,343 |
| 2063 | 2,769 | 284 | 111 | 29 | 2,150 | 5,343 |
| 2064 | 2,776 | 284 | 111 | 29 | 2,156 | 5,357 |
| 2065 | 2,769 | 284 | 111 | 29 | 2,150 | 5,343 |
| 2066 | 2,769 | 284 | 111 | 29 | 2,150 | 5,343 |
| 2067 | 2,769 | 284 | 111 | 29 | 2,150 | 5,343 |
| 2068 | 2,776 | 284 | 111 | 29 | 2,156 | 5,357 |
| 2069 | 2,769 | 284 | 111 | 29 | 2,150 | 5,343 |
| 2070 | 2,769 | 284 | 111 | 29 | 2,150 | 5,343 |
| 2071 | 2,769 | 284 | 111 | 29 | 2,150 | 5,343 |
| 2072 | 2,776 | 284 | 111 | 29 | 2,156 | 5,357 |
| 2073 | 2,769 | 284 | 111 | 29 | 2,150 | 5,343 |
| 2074 | 2,769 | 284 | 111 | 29 | 2,150 | 5,343 |
| 2075 | 2,769 | 284 | 111 | 29 | 2,150 | 5,343 |
| 2076 | 2,776 | 284 | 111 | 29 | 2,156 | 5,357 |
| 2077 | 2,769 | 284 | 111 | 29 | 2,150 | 5,343 |
| 2078 | 2,769 | 284 | 111 | 29 | 2,150 | 5,343 |
| 2079 | 2,769 | 284 | 111 | 29 | 2,150 | 5,343 |
| 2080 | 2,776 | 284 | 111 | 29 | 2,156 | 5,357 |
| 2081 | 2,769 | 284 | 111 | 29 | 2,150 | 5,343 |

**TABLE 3.3 (continued)
SCHEDULE OF ANNUAL EXPENDITURES
SAFSTOR**
(thousands, 2007 dollars)

| Year | Labor | Equipment & Materials | Energy | Burial | Other | Total |
|------|---------|--------------------------|--------|--------|---------|-----------|
| 2082 | 2,769 | 284 | 111 | 29 | 2,150 | 5,343 |
| 2083 | 2,769 | 284 | 111 | 29 | 2,150 | 5,343 |
| 2084 | 2,776 | 284 | 111 | 29 | 2,156 | 5,357 |
| 2085 | 2,769 | 284 | 111 | 29 | 2,150 | 5,343 |
| 2086 | 2,769 | 284 | 111 | 29 | 2,150 | 5,343 |
| 2087 | 2,769 | 284 | 111 | 29 | 2,150 | 5,343 |
| 2088 | 2,776 | 284 | 111 | 29 | 2,156 | 5,357 |
| 2089 | 2,769 | 284 | 111 | 29 | 2,150 | 5,343 |
| 2090 | 2,769 | 284 | 111 | 29 | 2,150 | 5,343 |
| 2091 | 2,769 | 284 | 111 | 29 | 2,150 | 5,343 |
| 2092 | 2,776 | 284 | 111 | 29 | 2,156 | 5,357 |
| 2093 | 2,769 | 284 | 111 | 29 | 2,150 | 5,343 |
| 2094 | 2,769 | 284 | 111 | 29 | 2,150 | 5,343 |
| 2095 | 2,769 | 284 | 111 | 29 | 2,150 | 5,343 |
| 2096 | 2,776 | 284 | 111 | 29 | 2,156 | 5,357 |
| 2097 | 2,769 | 284 | 111 | 29 | 2,150 | 5,343 |
| 2098 | 2,769 | 284 | 111 | 29 | 2,150 | 5,343 |
| 2099 | 2,769 | 284 | 111 | 29 | 2,150 | 5,343 |
| 2100 | 2,769 | 284 | 111 | 29 | 2,150 | 5,343 |
| 2101 | 13,847 | 657 | 463 | 33 | 2,161 | 17,161 |
| 2102 | 36,161 | 2,998 | 1,108 | 408 | 2,213 | 42,889 |
| 2103 | 52,705 | 16,052 | 1,061 | 20,938 | 10,972 | 101,728 |
| 2104 | 56,866 | 13,107 | 928 | 16,886 | 8,202 | 95,989 |
| 2105 | 58,036 | 9,564 | 831 | 11,235 | 4,983 | 84,649 |
| 2106 | 30,886 | 6,057 | 193 | 27 | 1,665 | 38,827 |
| 2107 | 22,170 | 12,909 | 111 | 0 | 1,036 | 36,226 |
| 2108 | 22,231 | 12,945 | 111 | 0 | 1,039 | 36,325 |
| 2109 | 182 | 106 | 1 | 0 | 9 | 298 |
| | 585,032 | 181,336 | 12,765 | 51,486 | 180,333 | 1,010,952 |

4. SCHEDULE ESTIMATE

The schedules for the decommissioning scenarios considered in this study follow the sequence presented in the AIF/NESP-036 study, with minor changes to reflect recent experience and site-specific constraints. In addition, the scheduling has been revised to reflect the spent fuel management plans described in Section 3.4.1.

A schedule or sequence of activities is presented in Figure 4.1 for the DECON decommissioning alternative. The schedule is also representative of the work activities identified in the delayed dismantling scenarios, absent any spent fuel constraints. The scheduling sequence assumes that fuel is removed from the spent fuel pool within the first 5½ years after operations cease. The key activities listed in the schedule do not reflect a one-to-one correspondence with those activities in the cost tables, but reflect dividing some activities for clarity and combining others for convenience. The schedule was prepared using the "Microsoft Project 2003" computer software.^[32]

4.1 SCHEDULE ESTIMATE ASSUMPTIONS

The schedule reflects the results of a precedence network developed for the site decommissioning activities, i.e., a PERT (Program Evaluation and Review Technique) Software Package. The work activity durations used in the precedence network reflect the actual man-hour estimates from the cost tables, adjusted by stretching certain activities over their slack range and shifting the start and end dates of others. The following assumptions were made in the development of the DECON decommissioning schedule:

- The fuel building is isolated until such time that all spent fuel has been discharged from the spent fuel pool to the DOE or to the ISFSI. Decontamination and dismantling of the storage pool are initiated once the transfer of spent fuel to the ISFSI is complete.
- All work (except vessel and internals removal) is performed during an 8-hour workday, 5 days per week, with no overtime. There are eleven paid holidays per year.
- Reactor and internals removal activities are performed by using separate crews for different activities working on different shifts, with a corresponding backshift charge for the second shift.
- Multiple crews work parallel activities to the maximum extent possible, consistent with optimum efficiency, adequate access for cutting, removal

and laydown space, and with the stringent safety measures necessary during demolition of heavy components and structures.


- For plant systems removal, the systems with the longest removal durations in areas on the critical path are considered to determine the duration of the activity.

4.2 PROJECT SCHEDULE

The period-dependent costs presented in the detailed cost tables are based upon the durations developed in the schedule for decommissioning Clinton. Durations are established between several milestones in each project period; these durations are used to establish a critical path for the entire project. In turn, the critical path duration for each period is used as the basis for determining the period-dependent costs. A second critical path is also shown for the spent fuel cooling period, which determines the release of the fuel building for final decontamination.


In Figure 4.1, the schedule is based upon years following the final shutdown date of September 29, 2046. Project timelines are provided in Figures 4.2 through 4.4; the milestone dates are based on this same shutdown date. The start of decommissioning activities in the Delayed Decommissioning scenario is concurrent with the end of the fuel transfer activity (i.e. to an off-site DOE facility).

**FIGURE 4.1
ACTIVITY SCHEDULE**




**FIGURE 4.2
DECOMMISSIONING TIMELINE
DECON
(not to scale)**

(Shutdown September 29, 2046)




**FIGURE 4.3
DECOMMISSIONING TIMELINE
DELAYED DECON
(not to scale)**

(Shutdown September 29, 2046)



**FIGURE 4.4
DECOMMISSIONING TIMELINE
SAFSTOR
(not to scale)**

(Shutdown September 29, 2046)



5. RADIOACTIVE WASTES

The objectives of the decommissioning process are the removal of all radioactive material from the site that would restrict its future use and the termination of the NRC license(s). This currently requires the remediation of all radioactive material at the site in excess of applicable legal limits. Under the Atomic Energy Act,^[33] the NRC is responsible for protecting the public from sources of ionizing radiation. Title 10 of the Code of Federal Regulations delineates the production, utilization, and disposal of radioactive materials and processes. In particular, §71 defines radioactive material as it pertains to packaging and transportation and §61 specifies its disposition.

Most of the materials being transported for controlled burial are categorized as Low Specific Activity (LSA) or Surface Contaminated Object (SCO) materials containing Type A quantities, as defined in 49 CFR §173-178. Shipping containers are required to be Industrial Packages (IP-1, IP-2 or IP-3, as defined in subpart 173.411). For this study, commercially available steel containers are presumed to be used for the disposal of piping, small components, and concrete. Larger components can serve as their own containers, with proper closure of all openings, access ways, and penetrations.

The volumes of radioactive waste generated during the various decommissioning activities at the site is shown on a line-item basis in Appendices C, D, and E and summarized in Tables 5.1 through 5.3. The quantified waste volume summaries shown in these tables are consistent with §61 classifications. The volumes are calculated based on the exterior dimensions for containerized material and on the displaced volume of components serving as their own waste containers.

The reactor vessel and internals are categorized as large quantity shipments and, accordingly, will be shipped in reusable, shielded truck casks with disposable liners. In calculating disposal costs, the burial fees are applied against the liner volume, as well as the special handling requirements of the payload. Packaging efficiencies are lower for the highly activated materials (greater than Type A quantity waste), where high concentrations of gamma-emitting radionuclides limit the capacity of the shipping canisters.

No process system containing/handling radioactive substances at shutdown is presumed to meet material release criteria by decay alone, i.e., systems radioactive at shutdown will still be radioactive over the time period during which the decommissioning is accomplished, due to the presence of long-lived radionuclides.

While the dose rates decrease with time, radionuclides such as ^{137}Cs will still control the disposition requirements.

The waste material generated in the decontamination and dismantling of Clinton is primarily generated during Period 2 of the DECON alternative and Period 4 of the deferred alternatives. Material that is considered potentially contaminated when removed from the radiologically controlled area is sent to processing facilities in Tennessee for conditioning and disposal. Heavily contaminated components and activated materials are routed for controlled disposal. The disposal volumes reported in the tables reflect the savings resulting from reprocessing and recycling.

Disposal fees are calculated using current disposal agreements, with surcharges added for the highly activated components, for example, generated in the segmentation of the reactor vessel. The cost to dispose of the majority of the material generated from the decontamination and dismantling activities (> 98%) is based upon Exelon's current disposal agreement with EnergySolutions for its facility in Clive, Utah.

Since the EnergySolutions facility is not able to accept the higher activity waste (Class B and C) generated in the decontamination of the reactor vessel and segmentation of the components closest to the core, the cost of disposal of this material (< 2% of the total volume) at a yet-to-be determined facility were based upon Exelon's rates for the Barnwell facility.

**TABLE 5.1
DECOMMISSIONING WASTE SUMMARY
DECON**

| | Waste Class ¹ | Volume (cubic feet) | Weight (pounds) |
|--|-----------------------------|------------------------|--------------------|
| Low-Level Radioactive Waste | | | |
| EnergySolutions (Clive, Utah) | | | |
| Containerized | A | 160,829 | 11,833,483 |
| Bulk | A | 33,347 | 3,363,716 |
| Future Disposal Facility ² | | | |
| | B | 2,156 | 246,431 |
| | C | 689 | 43,240 |
| Geologic Repository (Greater-than Class C) | | | |
| | >C | 482 | 86,500 |
| | | 197,503 | 15,573,370 |
| Total ³ | | | |
| Processed Waste (off-site) | | 505,717 | 21,170,880 |
| Scrap Metal | | | 150,712,000 |

¹ Waste is classified according to the requirements as delineated in Title 10 CFR, Part 61.55

² EnergySolutions is currently not able to receive Class B and C material

³ Columns may not add due to rounding.

**TABLE 5.2
DECOMMISSIONING WASTE SUMMARY
DELAYED DECON**

| | Waste Class ¹ | Volume (cubic feet) | Weight (pounds) |
|--|-----------------------------|------------------------|--------------------|
| Low-Level Radioactive Waste | | | |
| EnergySolutions (Clive, Utah) | | | |
| Containerized | A | 160,392 | 11,621,662 |
| Bulk | A | 29,242 | 2,856,638 |
| Future Disposal Facility ² | | | |
| | B | 1,502 | 157,200 |
| | C | 287 | 36,625 |
| Geologic Repository (Greater-than Class C) | | | |
| | >C | 482 | 86,500 |
| | | 191,906 | 14,758,625 |
| Total ³ | | 191,906 | 14,758,625 |
| Processed Waste (off-site) | | 505,717 | 21,170,880 |
| Scrap Metal | | | 150,712,000 |

¹ Waste is classified according to the requirements as delineated in Title 10 CFR, Part 61.55

² EnergySolutions is currently not able to receive Class B and C material

³ Columns may not add due to rounding.

**TABLE 5.3
DECOMMISSIONING WASTE SUMMARY
SAFSTOR**

| | Waste Class ¹ | Volume (cubic feet) | Weight (pounds) |
|--|-----------------------------|------------------------|--------------------|
| Low-Level Radioactive Waste | | | |
| EnergySolutions (Clive, Utah) | | | |
| Containerized | A | 128,355 | 7,665,828 |
| Bulk | A | 23,784 | 2,407,445 |
| Future Disposal Facility ² | | | |
| | B | 1,502 | 157,200 |
| | C | 287 | 36,625 |
| Geologic Repository (Greater-than Class C) | | | |
| | >C | 482 | 86,500 |
| | | 154,411 | 10,353,598 |
| Total ³ | | | |
| Processed Waste (off-site) | | 597,250 | 24,967,690 |
| Scrap Metal | | | 150,712,000 |

¹ Waste is classified according to the requirements as delineated in Title 10 CFR, Part 61.55

² EnergySolutions is currently not able to receive Class B and C material

³ Columns may not add due to rounding.

6. RESULTS

The analysis to estimate the costs to decommission Clinton relied upon the site-specific, technical information developed for a previous analysis prepared in 2003-04. While not an engineering study, the estimates provide AmerGen with sufficient information to assess their financial obligations, as they pertain to the eventual decommissioning of the nuclear station.

The estimates described in this report are based on numerous fundamental assumptions, including regulatory requirements, project contingencies, low-level radioactive waste disposal practices, high-level radioactive waste management options, and site restoration requirements. The decommissioning scenarios assume continued operation of the plant's spent fuel pool for a minimum of 5½ years following the cessation of operations for continued cooling of the assemblies. For the DECON and SAFSTOR scenarios, an ISFSI is constructed and used to safeguard the spent fuel, once sufficiently cooled, until such time that the DOE can complete the transfer of the assemblies to its repository. The spent fuel remains in the storage pool in the Delayed-DECON alternative.

The cost projected to promptly decommission (DECON) Clinton is estimated to be \$786.1 million. The majority of this cost (approximately 69.7%) is associated with the physical decontamination and dismantling of the nuclear unit so that the license can be terminated. Another 19.7% is associated with the management, interim storage, and eventual transfer of the spent fuel. The remaining 10.6% is for the demolition of the designated structures and limited restoration of the site.

The primary cost contributors, identified in Tables 6.1 through 6.3, are either labor-related or associated with the management and disposition of the radioactive waste. Program management is the largest single contributor to the overall cost. The magnitude of the expense is a function of both the size of the organization required to manage the decommissioning, as well as the duration of the program. It is assumed, for purposes of this analysis, that AmerGen will oversee the decommissioning program, using a DOC to manage the decommissioning labor force and the associated subcontractors. The size and composition of the management organization varies with the decommissioning phase and associated site activities. However, once the operating license is terminated, the staff is substantially reduced for the conventional demolition and restoration of the site, and the long-term care of the spent fuel (for the DECON alternative).

As described in this report, the spent fuel pool will remain operational for a minimum of 5½ years following the cessation of operations. The pool will be isolated

and an independent spent fuel island created. This will allow decommissioning operations to proceed in and around the pool areas. Over the 5½-year period, the spent fuel will be packaged into transportable steel canisters for loading into a DOE-provided transport cask (DECON and SAFSTOR alternatives). The canisters will be stored in concrete overpacks at the ISFSI until the DOE is able to receive them. Dry storage of the fuel under a separate license provides additional flexibility in the event the DOE is not able to meet the current timetable for completing the transfer of assemblies to an off-site facility and minimizes the associated caretaking expenses.

The cost for waste disposal includes only those costs associated with the controlled disposition of the low-level radioactive waste generated from decontamination and dismantling activities, including plant equipment and components, structural material, filters, resins and dry-active waste. As described in Section 5, disposal of the majority of the radioactive material is at EnergySolutions facility in Clive, Utah or some alternative facility. Highly activated components, requiring additional isolation from the environment, are packaged for geologic disposal. Disposal of these components is based upon a cost equivalent for spent fuel.

A significant portion of the metallic waste is designated for additional processing and treatment at an off-site facility. Processing reduces the volume of material requiring controlled disposal through such techniques and processes as survey and sorting, decontamination, and volume reduction. The material that cannot be unconditionally released is packaged for controlled disposal at one of the currently operating facilities. The cost identified in the summary table for processing is all-inclusive, incorporating the ultimate disposition of the material.

Removal costs reflect the labor-intensive nature of the decommissioning process, as well as the management controls required to ensure a safe and successful program. Decontamination and packaging costs also have a large labor component that is based upon prevailing union wages. Non-radiological demolition is a natural extension of the decommissioning process. The methods employed in decontamination and dismantling are generally destructive and indiscriminate in inflicting collateral damage. With a work force mobilized to support decommissioning operations, non-radiological demolition can be an integrated activity and a logical expansion of the work being performed in the process of terminating the operating license. Prompt demolition reduces future liabilities and can be more cost effective than deferral, due to the deterioration of the facilities (and therefore the working conditions) with time.

The reported cost for transport includes the tariffs and surcharges associated with moving large components and/or overweight shielded casks overland, as well as the

general expense, e.g., labor and fuel, of transporting material to the destinations identified in this report. For purposes of this analysis, material is primarily moved overland by truck.

Decontamination is used to reduce the plant's radiation fields and minimize worker exposure. Slightly contaminated material or material located within a contaminated area is sent to an off-site processing center, i.e., this analysis does not assume that contaminated plant components and equipment can be decontaminated for uncontrolled release in-situ. Centralized processing centers have proven to be a more economical means of handling the large volumes of material produced in the dismantling of a nuclear unit.

License termination survey costs are associated with the labor intensive and complex activity of verifying that contamination has been removed from the site to the levels specified by the regulating agency. This process involves a systematic survey of all remaining plant surface areas and surrounding environs, sampling, isotopic analysis, and documentation of the findings. The status of any plant components and materials not removed in the decommissioning process will also require confirmation and will add to the expense of surveying the facilities alone.

The remaining costs include allocations for heavy equipment and temporary services, as well as for other expenses such as regulatory fees and the premiums for nuclear insurance. While site operating costs are greatly reduced following the final cessation of plant operations, certain administrative functions do need to be maintained either at a basic functional or regulatory level.

**TABLE 6.1
SUMMARY OF DECOMMISSIONING COST ELEMENTS
DECON**
(thousands of 2007 dollars)

| Work Category | Cost | % |
|--|----------------|--------------|
| Decontamination | 20,716 | 2.6 |
| Removal | 158,458 | 20.2 |
| Packaging | 15,829 | 2.0 |
| Transportation | 10,548 | 1.3 |
| Waste Disposal | 55,662 | 7.1 |
| Off-site Waste Processing | 25,564 | 3.3 |
| Program Management ^[1] | 298,887 | 38.0 |
| Spent Fuel Pool Isolation | 10,503 | 1.3 |
| Spent Fuel Management | 124,876 | 15.9 |
| Insurance and Regulatory Fees | 10,669 | 1.4 |
| Energy | 6,731 | 0.9 |
| Characterization and Licensing Surveys | 15,676 | 2.0 |
| Property Taxes | 22,305 | 2.8 |
| Miscellaneous Equipment | 5,972 | 0.8 |
| Site O&M | 3,666 | 0.5 |
| Total ^[2] | 786,061 | 100.0 |
| | | |
| NRC License Termination | 547,591 | 69.7 |
| Spent Fuel Management | 155,245 | 19.7 |
| Site Restoration | 83,225 | 10.6 |

^[1] Includes engineering and security

^[2] Columns may not add due to rounding

TABLE 6.2
SUMMARY OF DECOMMISSIONING COST ELEMENTS
DELAYED DECON
(thousands of 2007 dollars)

| Work Category | Cost | % |
|--|----------------|--------------|
| Decontamination | 28,052 | 3.8 |
| Removal | 148,111 | 19.9 |
| Packaging | 12,819 | 1.7 |
| Transportation | 7,604 | 1.0 |
| Waste Disposal | 37,773 | 5.1 |
| Off-site Waste Processing | 25,564 | 3.4 |
| Program Management ^[1] | 353,365 | 47.6 |
| Spent Fuel Pool Isolation | 10,503 | 1.4 |
| Spent Fuel Management | 31,915 | 4.3 |
| Insurance and Regulatory Fees | 15,732 | 2.1 |
| Energy | 8,872 | 1.2 |
| Characterization and Licensing Surveys | 17,100 | 2.3 |
| Property Taxes | 29,948 | 4.0 |
| Miscellaneous Equipment | 9,630 | 1.3 |
| Site O&M | 5,663 | 0.8 |
| Total ^[2] | 742,651 | 100.0 |
| | | |
| NRC License Termination | 476,232 | 64.1 |
| Spent Fuel Management | 181,048 | 24.4 |
| Site Restoration | 85,372 | 11.5 |

^[1] Includes engineering and security

^[2] Columns may not add due to rounding

TABLE 6.3
SUMMARY OF DECOMMISSIONING COST ELEMENTS
SAFSTOR
(thousands of 2007 dollars)

| Work Category | Cost | % |
|--|------------------|--------------|
| Decontamination | 27,039 | 2.7 |
| Removal | 152,473 | 15.1 |
| Packaging | 12,025 | 1.2 |
| Transportation | 6,251 | 0.6 |
| Waste Disposal | 30,714 | 3.0 |
| Off-site Waste Processing | 30,148 | 3.0 |
| Program Management ^[1] | 424,198 | 42.0 |
| Spent Fuel Pool Isolation | 10,503 | 1.0 |
| Spent Fuel Management | 123,640 | 12.2 |
| Insurance and Regulatory Fees | 46,990 | 4.6 |
| Energy | 12,765 | 1.3 |
| Characterization and Licensing Surveys | 17,100 | 1.7 |
| Property Taxes | 76,770 | 7.6 |
| Miscellaneous Equipment | 22,433 | 2.2 |
| Site O&M | 17,901 | 1.8 |
| Total ^[2] | 1,010,952 | 100.0 |
| | | |
| NRC License Termination | 691,981 | 68.4 |
| Spent Fuel Management | 233,606 | 23.1 |
| Site Restoration | 85,365 | 8.4 |

^[1] Includes engineering and security

^[2] Columns may not add due to rounding

7. REFERENCES

1. "Decommissioning Cost Analysis for the Clinton Power Station," Document No. E16-1455-007, Rev. 0, TLG Services, Inc., May 2004
2. U.S. Code of Federal Regulations, Title 10, Parts 30, 40, 50, 51, 70 and 72, "General Requirements for Decommissioning Nuclear Facilities," Nuclear Regulatory Commission, Federal Register Volume 53, Number 123 (p 24018 et seq.), June 27, 1988
3. U.S. Nuclear Regulatory Commission, Regulatory Guide 1.159, "Assuring the Availability of Funds for Decommissioning Nuclear Reactors," October 2003
4. U.S. Code of Federal Regulations, Title 10, Part 20, Subpart E, "Radiological Criteria for License Termination"
5. U.S. Code of Federal Regulations, Title 10, Parts 20 and 50, "Entombment Options for Power Reactors," Advanced Notice of Proposed Rulemaking, Federal Register Volume 66, Number 200, October 16, 2001
6. U.S. Code of Federal Regulations, Title 10, Parts 2, 50 and 51, "Decommissioning of Nuclear Power Reactors," Nuclear Regulatory Commission, Federal Register Volume 61 (p 39278 et seq.), July 29, 1996
7. "Nuclear Waste Policy Act of 1982 and Amendments," U.S. Department of Energy's Office of Civilian Radioactive Management, 1982
8. U.S. Court of Federal Claims awarded Yankee Atomic, Connecticut Yankee and Maine Yankee damages over the federal government's failure to remove spent fuel from the sites in a September 2006 ruling
9. "DOE Announces Yucca Mountain License Application Schedule", U.S. Department of Energy's Office of Public Affairs, Press Release July 19, 2006
10. Remarks of OCRWM Director Ward Sproat to the National Academy of Science, November 2006
11. U.S. Code of Federal Regulations, Title 10, Part 50, "Domestic Licensing of Production and Utilization Facilities," Subpart 54 (bb), "Conditions of Licenses"

7. REFERENCES

(continued)

12. "Low-Level Radioactive Waste Policy," Public Law 96-573, 1980
13. "Low-Level Radioactive Waste Policy Amendments Act of 1985," Public Law 99-240, January 15, 1986
14. U.S. Code of Federal Regulations, Title 10, Part 20, Subpart E, "Radiological Criteria for License Termination," Federal Register, Volume 62, Number 139 (p 39058 et seq.), July 21, 1997
15. "Establishment of Cleanup Levels for CERCLA Sites with Radioactive Contamination," EPA Memorandum OSWER No. 9200.4-18, August 22, 1997
16. U.S. Code of Federal Regulations, Title 40, Part 141.16, "Maximum contaminant levels for beta particle and photon radioactivity from man-made radionuclides in community water systems"
17. "Memorandum of Understanding Between the Environmental Protection Agency and the Nuclear Regulatory Commission: Consultation and Finality on Decommissioning and Decontamination of Contaminated Sites," OSWER 9295.8-06a, October 9, 2002
18. "Multi-Agency Radiation Survey and Site Investigation Manual (MARSSIM)," NUREG/CR-1575, Rev. A, EPA 402-R-97-016, Rev. A, August 2000
19. T.S. LaGuardia et al., "Guidelines for Producing Commercial Nuclear Power Plant Decommissioning Cost Estimates," AIF/NESP-036, May 1986
20. W.J. Manion and T.S. LaGuardia, "Decommissioning Handbook," U.S. Department of Energy, DOE/EV/10128-1, November 1980
21. "Building Construction Cost Data 2007," Robert Snow Means Company, Inc., Kingston, Massachusetts
22. Project and Cost Engineers' Handbook, Second Edition, p. 239, American Association of Cost Engineers, Marcel Dekker, Inc., New York, New York, 1984

7. REFERENCES

(continued)

23. "Acceptance Priority Ranking & Annual Capacity Report," DOE/RW-0567, July 2004
24. "Civilian Radioactive Waste Management System Total System Description," Revision 02 (TDR-CRW-SE-000002), DOE/RW-0500, September 2001
25. "Strategy for Management and Disposal of Greater-Than-Class C Low-Level Radioactive Waste," Federal Register Volume 60, Number 48 (p 13424 et seq.), March 1995
26. U.S. Department of Transportation, Title 49 of the Code of Federal Regulations, "Transportation," Parts 173 through 178, 1996
27. Tri-State Motor Transit Company, published tariffs, Interstate Commerce Commission (ICC), Docket No. MC-427719 Rules Tariff, March 2004, Radioactive Materials Tariff, January 2004
28. J.C. Evans et al., "Long-Lived Activation Products in Reactor Materials" NUREG/CR-3474, Pacific Northwest Laboratory for the Nuclear Regulatory Commission. August 1984
29. R.I. Smith, G.J. Konzek, W.E. Kennedy, Jr., "Technology, Safety and Costs of Decommissioning a Reference Pressurized Water Reactor Power Station," NUREG/CR-0130 and addenda, Pacific Northwest Laboratory for the Nuclear Regulatory Commission. June 1978
30. H.D. Oak, et al., "Technology, Safety and Costs of Decommissioning a Reference Boiling Water Reactor Power Station," NUREG/CR-0672 and addenda, Pacific Northwest Laboratory for the Nuclear Regulatory Commission. June 1980
31. "Financial Protection Requirements for Permanently Shutdown Nuclear Power Reactors," 10 CFR Parts 50 and 140, Federal Register Notice, Vol. 62, No. 210, October 30, 1997
32. "Microsoft Project 2003," Microsoft Corporation, Redmond, WA, 2003
33. "Atomic Energy Act of 1954," (68 Stat. 919)

APPENDIX A
UNIT COST FACTOR DEVELOPMENT

**APPENDIX A
UNIT COST FACTOR DEVELOPMENT**

Example: Unit Factor for Removal of Contaminated Heat Exchanger < 3,000 lbs.

1. SCOPE

Heat exchangers weighing < 3,000 lbs. will be removed in one piece using a crane or small hoist. They will be disconnected from the inlet and outlet piping. The heat exchanger will be sent to the waste processing area.

2. CALCULATIONS

| Act ID | Activity Description | Activity Duration (minutes) | Critical Duration (minutes)* |
|--------|---|-----------------------------|------------------------------|
| a | Remove insulation | 60 | (b) |
| b | Mount pipe cutters | 60 | 60 |
| c | Install contamination controls | 20 | (b) |
| d | Disconnect inlet and outlet lines | 60 | 60 |
| e | Cap openings | 20 | (d) |
| f | Rig for removal | 30 | 30 |
| g | Unbolt from mounts | 30 | 30 |
| h | Remove contamination controls | 15 | 15 |
| i | Remove, wrap, send to waste processing area | <u>60</u> | <u>60</u> |
| | Totals (Activity/Critical) | 355 | 255 |

Duration adjustment(s):

+ Respiratory protection adjustment (50% of critical duration) 128

+ Radiation/ALARA adjustment (37.1% of critical duration) 95

Adjusted work duration 478

+ Protective clothing adjustment (30% of adjusted duration) 143

Productive work duration 621

+ Work break adjustment (8.33 % of productive duration) 52

Total work duration (minutes) 673

***** Total duration = 11.217 hr *****

* Alpha designators indicate activities that can be performed in parallel

**APPENDIX A
(Continued)**

3. LABOR REQUIRED

| Crew | Number | Duration (Hours) | Rate (\$/hr) | Cost |
|---------------------------|--------|---------------------|-----------------|-------------------|
| Laborers | 3.00 | 11.217 | 40.37 | 1358.49 |
| Craftsmen | 2.00 | 11.217 | 50.71 | 1137.63 |
| Foreman | 1.00 | 11.217 | 52.52 | 589.12 |
| General Foreman | 0.25 | 11.217 | 55.22 | 154.85 |
| Fire Watch | 0.05 | 11.217 | 40.37 | 22.64 |
| Health Physics Technician | 1.00 | 11.217 | 46.32 | 519.57 |
| Total labor cost | | | | <u>\$3,782.30</u> |

4. EQUIPMENT & CONSUMABLES COSTS

| | |
|---|--|
| Equipment Costs | none |
| Consumables/Materials Costs | |
| <ul style="list-style-type: none"> • Blotting paper 50 @ \$0.46/sq ft {1} • Plastic sheets/bags 50 @ \$0.14/sq ft {2} • Gas torch consumables 1 @ \$7.60 x 1 /hr {3} | <p>\$23.50</p> <p>\$7.00</p> <p>\$7.60</p> |
| Subtotal cost of equipment and materials | <u>\$37.60</u> |
| Overhead & profit on equipment and materials @ 16.25 % | <u>\$6.11</u> |
| Total costs, equipment & material | \$43.71 |

TOTAL COST:

| | |
|--|------------|
| Removal of contaminated heat exchanger <3000 pounds: | \$3,826.01 |
| Total labor cost: | \$3,782.30 |
| Total equipment/material costs: | \$43.71 |
| Total craft labor man-hours required per unit: | 81.88 |

5. NOTES AND REFERENCES

- Work difficulty factors were developed in conjunction with the Atomic Industrial Forum's (now NEI) program to standardize nuclear decommissioning cost estimates and are delineated in Volume 1, Chapter 5 of the "Guidelines for Producing Commercial Nuclear Power Plant Decommissioning Cost Estimates," AIF/NESP-036, May 1986.
- References for equipment & consumables costs:
 1. www.mcmaster.com online catalog - Spill Control (7193T88)
 2. R.S. Means (2007) 01 56 13.60-0200, page 20
 3. R.S. Means (2007) 01 54 33.40-6360, page 608
- Material and consumable costs were adjusted using the regional indices for Bloomington, Illinois.

APPENDIX B
UNIT COST FACTOR LISTING
(DECON: Power Block Structures Only)

APPENDIX B

**UNIT COST FACTOR LISTING
(Power Block Structures Only)**

| Unit Cost Factor | Cost/Unit |
|---|------------------|
| Removal of clean instrument and sampling tubing, \$/linear foot | 0.44 |
| Removal of clean pipe 0.25 to 2 inches diameter, \$/linear foot | 4.67 |
| Removal of clean pipe >2 to 4 inches diameter, \$/linear foot | 6.62 |
| Removal of clean pipe >4 to 8 inches diameter, \$/linear foot | 12.84 |
| Removal of clean pipe >8 to 14 inches diameter, \$/linear foot | 24.91 |
| Removal of clean pipe >14 to 20 inches diameter, \$/linear foot | 32.31 |
| Removal of clean pipe >20 to 36 inches diameter, \$/linear foot | 47.55 |
| Removal of clean pipe >36 inches diameter, \$/linear foot | 56.54 |
| Removal of clean valve >2 to 4 inches | 84.97 |
| Removal of clean valve >4 to 8 inches | 128.39 |
| Removal of clean valve >8 to 14 inches | 249.12 |
| Removal of clean valve >14 to 20 inches | 323.06 |
| Removal of clean valve >20 to 36 inches | 475.52 |
| Removal of clean valve >36 inches | 565.36 |
| Removal of clean pipe hanger for small bore piping | 27.74 |
| Removal of clean pipe hanger for large bore piping | 102.07 |
| Removal of clean pump, <300 pound | 214.82 |
| Removal of clean pump, 300-1000 pound | 596.40 |
| Removal of clean pump, 1000-10,000 pound | 2,370.45 |
| Removal of clean pump, >10,000 pound | 4,578.23 |
| Removal of clean pump motor, 300-1000 pound | 251.29 |
| Removal of clean pump motor, 1000-10,000 pound | 987.83 |
| Removal of clean pump motor, >10,000 pound | 2,222.62 |
| Removal of clean heat exchanger <3000 pound | 1,269.19 |
| Removal of clean heat exchanger >3000 pound | 3,186.37 |
| Removal of clean feedwater heater/deaerator | 9,008.39 |
| Removal of clean moisture separator/reheater | 18,554.33 |
| Removal of clean tank, <300 gallons | 276.53 |
| Removal of clean tank, 300-3000 gallon | 875.31 |
| Removal of clean tank, >3000 gallons, \$/square foot surface area | 7.29 |

APPENDIX B

**UNIT COST FACTOR LISTING
(Power Block Structures Only)**

| Unit Cost Factor | Cost/Unit |
|--|------------------|
| Removal of clean electrical equipment, <300 pound | 118.03 |
| Removal of clean electrical equipment, 300-1000 pound | 409.11 |
| Removal of clean electrical equipment, 1000-10,000 pound | 818.23 |
| Removal of clean electrical equipment, >10,000 pound | 1,938.19 |
| Removal of clean electrical transformer < 30 tons | 1,346.04 |
| Removal of clean electrical transformer > 30 tons | 3,876.36 |
| Removal of clean standby diesel generator, <100 kW | 1,374.86 |
| Removal of clean standby diesel generator, 100 kW to 1 MW | 3,068.79 |
| Removal of clean standby diesel generator, >1 MW | 6,353.02 |
| Removal of clean electrical cable tray, \$/linear foot | 10.98 |
| Removal of clean electrical conduit, \$/linear foot | 4.79 |
| Removal of clean mechanical equipment, <300 pound | 118.03 |
| Removal of clean mechanical equipment, 300-1000 pound | 409.11 |
| Removal of clean mechanical equipment, 1000-10,000 pound | 818.23 |
| Removal of clean mechanical equipment, >10,000 pound | 1,938.19 |
| Removal of clean HVAC equipment, <300 pound | 118.03 |
| Removal of clean HVAC equipment, 300-1000 pound | 409.11 |
| Removal of clean HVAC equipment, 1000-10,000 pound | 818.23 |
| Removal of clean HVAC equipment, >10,000 pound | 1,938.19 |
| Removal of clean HVAC ductwork, \$/pound | 0.46 |
| Removal of contaminated instrument and sampling tubing, \$/linear foot | 1.38 |
| Removal of contaminated pipe 0.25 to 2 inches diameter, \$/linear foot | 18.22 |
| Removal of contaminated pipe >2 to 4 inches diameter, \$/linear foot | 31.81 |
| Removal of contaminated pipe >4 to 8 inches diameter, \$/linear foot | 50.44 |
| Removal of contaminated pipe >8 to 14 inches diameter, \$/linear foot | 99.94 |
| Removal of contaminated pipe >14 to 20 inches diameter, \$/linear foot | 120.35 |
| Removal of contaminated pipe >20 to 36 inches diameter, \$/linear foot | 167.29 |
| Removal of contaminated pipe >36 inches diameter, \$/linear foot | 198.10 |
| Removal of contaminated valve >2 to 4 inches | 389.16 |
| Removal of contaminated valve >4 to 8 inches | 468.84 |

APPENDIX B

**UNIT COST FACTOR LISTING
(Power Block Structures Only)**

| Unit Cost Factor | Cost/Unit |
|---|------------------|
| Removal of contaminated valve >8 to 14 inches | 964.54 |
| Removal of contaminated valve >14 to 20 inches | 1,227.69 |
| Removal of contaminated valve >20 to 36 inches | 1,638.04 |
| Removal of contaminated valve >36 inches | 1,946.10 |
| Removal of contaminated pipe hanger for small bore piping | 95.16 |
| Removal of contaminated pipe hanger for large bore piping | 314.68 |
| Removal of contaminated pump, <300 pound | 833.51 |
| Removal of contaminated pump, 300-1000 pound | 1,925.74 |
| Removal of contaminated pump, 1000-10,000 pound | 6,317.24 |
| Removal of contaminated pump, >10,000 pound | 15,387.15 |
| Removal of contaminated pump motor, 300-1000 pound | 810.97 |
| Removal of contaminated pump motor, 1000-10,000 pound | 2,563.34 |
| Removal of contaminated pump motor, >10,000 pound | 5,754.95 |
| Removal of contaminated heat exchanger <3000 pound | 3,826.01 |
| Removal of contaminated heat exchanger >3000 pound | 11,057.37 |
| Removal of contaminated feedwater heater/deaerator | 27,067.28 |
| Removal of contaminated moisture separator/reheater | 59,257.58 |
| Removal of contaminated tank, <300 gallons | 1,383.82 |
| Removal of contaminated tank, >300 gallons, \$/square foot | 27.17 |
| Removal of contaminated electrical equipment, <300 pound | 651.00 |
| Removal of contaminated electrical equipment, 300-1000 pound | 1,568.59 |
| Removal of contaminated electrical equipment, 1000-10,000 pound | 3,019.73 |
| Removal of contaminated electrical equipment, >10,000 pound | 5,879.30 |
| Removal of contaminated electrical cable tray, \$/linear foot | 31.40 |
| Removal of contaminated electrical conduit, \$/linear foot | 14.37 |
| Removal of contaminated mechanical equipment, <300 pound | 724.84 |
| Removal of contaminated mechanical equipment, 300-1000 pound | 1,734.48 |
| Removal of contaminated mechanical equipment, 1000-10,000 pound | 3,333.70 |
| Removal of contaminated mechanical equipment, >10,000 pound | 5,879.30 |
| Removal of contaminated HVAC equipment, <300 pound | 724.84 |

APPENDIX B

**UNIT COST FACTOR LISTING
(Power Block Structures Only)**

| Unit Cost Factor | Cost/Unit |
|---|------------------|
| Removal of contaminated HVAC equipment, 300-1000 pound | 1,734.48 |
| Removal of contaminated HVAC equipment, 1000-10,000 pound | 3,333.70 |
| Removal of contaminated HVAC equipment, >10,000 pound | 5,879.30 |
| Removal of contaminated HVAC ductwork, \$/pound | 1.90 |
| Removal/plasma arc cut of contaminated thin metal components, \$/linear in. | 3.45 |
| Additional decontamination of surface by washing, \$/square foot | 7.11 |
| Additional decontamination of surfaces by hydrolasing, \$/square foot | 30.74 |
| Decontamination rig hook up and flush, \$/ 250 foot length | 6,155.66 |
| Chemical flush of components/systems, \$/gallon | 12.74 |
| Removal of clean standard reinforced concrete, \$/cubic yard | 115.91 |
| Removal of grade slab concrete, \$/cubic yard | 157.76 |
| Removal of clean concrete floors, \$/cubic yard | 308.75 |
| Removal of sections of clean concrete floors, \$/cubic yard | 914.22 |
| Removal of clean heavily rein concrete w/#9 rebar, \$/cubic yard | 206.24 |
| Removal of contaminated heavily rein concrete w/#9 rebar, \$/cubic yard | 1,835.23 |
| Removal of clean heavily rein concrete w/#18 rebar, \$/cubic yard | 260.73 |
| Removal of contaminated heavily rein concrete w/#18 rebar, \$/cubic yard | 2,429.54 |
| Removal heavily rein concrete w/#18 rebar & steel embedments, \$/cubic yard | 395.41 |
| Removal of below-grade suspended floors, \$/cubic yard | 308.75 |
| Removal of clean monolithic concrete structures, \$/cubic yard | 777.20 |
| Removal of contaminated monolithic concrete structures, \$/cubic yard | 1,834.53 |
| Removal of clean foundation concrete, \$/cubic yard | 609.46 |
| Removal of contaminated foundation concrete, \$/cubic yard | 1,708.95 |
| Explosive demolition of bulk concrete, \$/cubic yard | 26.33 |
| Removal of clean hollow masonry block wall, \$/cubic yard | 86.49 |
| Removal of contaminated hollow masonry block wall, \$/cubic yard | 291.29 |
| Removal of clean solid masonry block wall, \$/cubic yard | 86.49 |
| Removal of contaminated solid masonry block wall, \$/cubic yard | 291.29 |
| Backfill of below-grade voids, \$/cubic yard | 17.17 |
| Removal of subterranean tunnels/voids, \$/linear foot | 97.18 |

APPENDIX B

**UNIT COST FACTOR LISTING
(Power Block Structures Only)**

| Unit Cost Factor | Cost/Unit |
|---|------------------|
| Placement of concrete for below-grade voids, \$/cubic yard | 126.19 |
| Excavation of clean material, \$/cubic yard | 2.34 |
| Excavation of contaminated material, \$/cubic yard | 34.53 |
| Removal of clean concrete rubble (tipping fee included), \$/cubic yard | 176.67 |
| Removal of contaminated concrete rubble, \$/cubic yard | 22.28 |
| Removal of building by volume, \$/cubic foot | 0.26 |
| Removal of clean building metal siding, \$/square foot | 1.02 |
| Removal of contaminated building metal siding, \$/square foot | 3.62 |
| Removal of standard asphalt roofing, \$/square foot | 2.05 |
| Removal of transite panels, \$/square foot | 2.06 |
| Scarifying contaminated concrete surfaces (drill & spall), \$/square foot | 12.18 |
| Scabbling contaminated concrete floors, \$/square foot | 7.14 |
| Scabbling contaminated concrete walls, \$/square foot | 18.59 |
| Scabbling contaminated ceilings, \$/square foot | 63.56 |
| Scabbling structural steel, \$/square foot | 5.98 |
| Removal of clean overhead crane/monorail < 10 ton capacity | 568.59 |
| Removal of contaminated overhead crane/monorail < 10 ton capacity | 1,615.30 |
| Removal of clean overhead crane/monorail >10-50 ton capacity | 1,364.64 |
| Removal of contaminated overhead crane/monorail >10-50 ton capacity | 3,876.03 |
| Removal of polar crane > 50 ton capacity | 5,681.55 |
| Removal of gantry crane > 50 ton capacity | 24,227.29 |
| Removal of structural steel, \$/pound | 0.19 |
| Removal of clean steel floor grating, \$/square foot | 3.95 |
| Removal of contaminated steel floor grating, \$/square foot | 11.57 |
| Removal of clean free standing steel liner, \$/square foot | 10.93 |
| Removal of contaminated free standing steel liner, \$/square foot | 31.81 |
| Removal of clean concrete-anchored steel liner, \$/square foot | 5.47 |
| Removal of contaminated concrete-anchored steel liner, \$/square foot | 37.06 |
| Placement of scaffolding in clean areas, \$/square foot | 13.71 |
| Placement of scaffolding in contaminated areas, \$/square foot | 23.31 |

APPENDIX B

**UNIT COST FACTOR LISTING
(Power Block Structures Only)**

| Unit Cost Factor | Cost/Unit |
|--|------------------|
| Landscaping with topsoil, \$/acre | 17,857.85 |
| Cost of CPC B-88 LSA box & preparation for use | 1,576.14 |
| Cost of CPC B-25 LSA box & preparation for use | 1,412.58 |
| Cost of CPC B-12V 12 gauge LSA box & preparation for use | 1,208.16 |
| Cost of CPC B-144 LSA box & preparation for use | 6,188.48 |
| Cost of LSA drum & preparation for use | 131.05 |
| Cost of cask liner for CNSI 14 195 cask | 158.68 |
| Cost of cask liner for CNSI 8 120A cask (resins) | 6,290.96 |
| Cost of cask liner for CNSI 8 120A cask (filters) | 1,025.30 |
| Decontamination of surfaces with vacuuming, \$/square foot | 0.62 |

APPENDIX C
DETAILED COST ANALYSIS
DECON

Table C
Clinton Power Station
DECON Decommissioning Cost Estimate
(Thousands of 2007 Dollars)

| Activity Index | Activity Description | Decon Cost | Removal Cost | Packaging Costs | Transport Costs | Off-Site Processing Costs | LLRW Disposal Costs | Other Costs | Total Contingency | Total Costs | NRC Lic. Term. Costs | Spent Fuel Management Costs | Site Restoration Costs | Processed Volume | Burial Volumes | | | Burial/Processed Wt., Lbs. | Craft Manhours | Utility and Contractor Manhours |
|--|--|------------|--------------|-----------------|-----------------|---------------------------|---------------------|-------------|-------------------|-------------|----------------------|-----------------------------|------------------------|------------------|------------------|------------------|------------------|----------------------------|----------------|---------------------------------|
| | | | | | | | | | | | | | | | Class A Cu. Feet | Class B Cu. Feet | Class C Cu. Feet | | | |
| PERIOD Ia - Shutdown through Transition | | | | | | | | | | | | | | | | | | | | |
| Period Ia Direct Decommissioning Activities | | | | | | | | | | | | | | | | | | | | |
| Ia.1.1 | Prepare preliminary decommissioning cost | - | - | - | - | - | - | 118 | 18 | 136 | 136 | - | - | - | - | - | - | - | - | 1,300 |
| Ia.1.2 | Notification of Cessation of Operations | - | - | - | - | - | - | n/a | a | - | - | - | - | - | - | - | - | - | - | - |
| Ia.1.3 | Remove fuel & source material | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| Ia.1.4 | Notification of Permanent Defueling | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| Ia.1.5 | Deactivate plant systems & process waste | - | - | - | - | - | - | 181 | 27 | 209 | 209 | - | - | - | - | - | - | - | - | 2,000 |
| Ia.1.6 | Prepare and submit PSDAR | - | - | - | - | - | - | 417 | 63 | 480 | 480 | - | - | - | - | - | - | - | - | 4,600 |
| Ia.1.7 | Review plant dwgs & specs. | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| Ia.1.8 | Perform detailed rad survey | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| Ia.1.9 | Estimate by-product inventory | - | - | - | - | - | - | 91 | 14 | 104 | 104 | - | - | - | - | - | - | - | - | 1,000 |
| Ia.1.10 | End product description | - | - | - | - | - | - | 91 | 14 | 104 | 104 | - | - | - | - | - | - | - | - | 1,000 |
| Ia.1.11 | Detailed by-product inventory | - | - | - | - | - | - | 118 | 18 | 136 | 136 | - | - | - | - | - | - | - | - | 1,300 |
| Ia.1.12 | Define major work sequence | - | - | - | - | - | - | 680 | 102 | 782 | 782 | - | - | - | - | - | - | - | - | 7,500 |
| Ia.1.13 | Perform SER and EA | - | - | - | - | - | - | 281 | 42 | 323 | 323 | - | - | - | - | - | - | - | - | 3,100 |
| Ia.1.14 | Perform Site-Specific Cost Study | - | - | - | - | - | - | 454 | 68 | 522 | 522 | - | - | - | - | - | - | - | - | 5,000 |
| Ia.1.15 | Prepare/submit License Termination Plan | - | - | - | - | - | - | 372 | 56 | 427 | 427 | - | - | - | - | - | - | - | - | 4,086 |
| Ia.1.16 | Receive NRC approval of termination plan | - | - | - | - | - | - | - | a | - | - | - | - | - | - | - | - | - | - | - |
| Activity Specifications | | | | | | | | | | | | | | | | | | | | |
| Ia.1.17.1 | Plant & temporary facilities | - | - | - | - | - | - | 446 | 67 | 513 | 462 | - | 51 | - | - | - | - | - | - | 4,920 |
| Ia.1.17.2 | Plant systems | - | - | - | - | - | - | 378 | 57 | 435 | 391 | - | 43 | - | - | - | - | - | - | 4,167 |
| Ia.1.17.3 | NSSS Decontamination Flush | - | - | - | - | - | - | 45 | 7 | 52 | 52 | - | - | - | - | - | - | - | - | 500 |
| Ia.1.17.4 | Reactor internals | - | - | - | - | - | - | 644 | 97 | 741 | 741 | - | - | - | - | - | - | - | - | 7,100 |
| Ia.1.17.5 | Reactor vessel | - | - | - | - | - | - | 590 | 88 | 678 | 678 | - | - | - | - | - | - | - | - | 6,500 |
| Ia.1.17.6 | Sterilized shield | - | - | - | - | - | - | 45 | 7 | 52 | 52 | - | - | - | - | - | - | - | - | 500 |
| Ia.1.17.7 | Moisture separator/reheaters | - | - | - | - | - | - | 91 | 14 | 104 | 104 | - | - | - | - | - | - | - | - | 1,000 |
| Ia.1.17.8 | Reinforced concrete | - | - | - | - | - | - | 145 | 22 | 167 | 83 | - | 83 | - | - | - | - | - | - | 1,600 |
| Ia.1.17.9 | Main Turbine | - | - | - | - | - | - | 189 | 28 | 218 | 218 | - | - | - | - | - | - | - | - | 2,088 |
| Ia.1.17.10 | Main Condensers | - | - | - | - | - | - | 189 | 28 | 218 | 218 | - | - | - | - | - | - | - | - | 2,088 |
| Ia.1.17.11 | Pressure suppression structure | - | - | - | - | - | - | 181 | 27 | 209 | 209 | - | - | - | - | - | - | - | - | 2,000 |
| Ia.1.17.12 | Drywell | - | - | - | - | - | - | 145 | 22 | 167 | 167 | - | - | - | - | - | - | - | - | 1,600 |
| Ia.1.17.13 | Plant structures & buildings | - | - | - | - | - | - | 283 | 42 | 325 | 163 | - | 163 | - | - | - | - | - | - | 3,120 |
| Ia.1.17.14 | Waste management | - | - | - | - | - | - | 417 | 63 | 480 | 480 | - | - | - | - | - | - | - | - | 4,600 |
| Ia.1.17.15 | Facility & site closure | - | - | - | - | - | - | 82 | 12 | 94 | 47 | - | 47 | - | - | - | - | - | - | 900 |
| Ia.1.17 | Total | - | - | - | - | - | - | 3,871 | 551 | 4,422 | 4,064 | - | 388 | - | - | - | - | - | - | 42,663 |
| Planning & Site Preparations | | | | | | | | | | | | | | | | | | | | |
| Ia.1.18 | Prepare dismantling sequence | - | - | - | - | - | - | 218 | 33 | 250 | 250 | - | - | - | - | - | - | - | - | 2,400 |
| Ia.1.19 | Plant prep. & temp. specs | - | - | - | - | - | - | 2,419 | 363 | 2,782 | 2,782 | - | - | - | - | - | - | - | - | - |
| Ia.1.20 | Design water clean-up system | - | - | - | - | - | - | 127 | 19 | 146 | 146 | - | - | - | - | - | - | - | - | 1,400 |
| Ia.1.21 | Rigging/Cont. Chtrl Envirps/fooling/etc. | - | - | - | - | - | - | 2,048 | 307 | 2,355 | 2,355 | - | - | - | - | - | - | - | - | - |
| Ia.1.22 | Procure caskeyners & containers | - | - | - | - | - | - | 112 | 17 | 128 | 128 | - | - | - | - | - | - | - | - | 1,200 |
| Ia.1 | Subtotal Period Ia Activity Costs | - | - | - | - | - | - | 11,597 | 1,740 | 13,336 | 12,948 | - | 388 | - | - | - | - | - | - | 75,609 |
| Period Ia Collateral Costs | | | | | | | | | | | | | | | | | | | | |
| Ia.3.1 | Spent Fuel Capital and Transfer | - | - | - | - | - | - | 39,540 | 5,931 | 45,471 | - | 45,471 | - | - | - | - | - | - | - | - |
| Ia.3 | Subtotal Period Ia Collateral Costs | - | - | - | - | - | - | 39,540 | 5,931 | 45,471 | - | 45,471 | - | - | - | - | - | - | - | - |

Table C
Clinton Power Station
DECON Decommissioning Cost Estimate
(Thousands of 2007 Dollars)

| Activity Index | Activity Description | Decon Cost | Removal Cost | Packaging Costs | Transport Costs | Off-Site Processing Costs | LLRW Disposal Costs | Other Costs | Total Contingency | Total Costs | NRC Lic. Term. Costs | Spent Fuel Management Costs | Site Restoration Costs | Processed Volume | | Burial Volumes | | Burial/Processed Wt., Lbs. | Craft Manhours | Utility and Contractor Manhours |
|---|---|------------|--------------|-----------------|-----------------|---------------------------|---------------------|-------------|-------------------|-------------|----------------------|-----------------------------|------------------------|------------------|----------|------------------|------------------|----------------------------|----------------|---------------------------------|
| | | | | | | | | | | | | | | Cu. Feet | Cu. Feet | Class A Cu. Feet | Class B Cu. Feet | | | |
| Period 1a Period-Dependent Costs | | | | | | | | | | | | | | | | | | | | |
| 1a.4.1 | Insurance | - | - | - | - | - | - | 1,320 | 132 | 1,452 | 1,452 | - | - | - | - | - | - | - | - | - |
| 1a.4.2 | Property taxes | - | - | - | - | - | - | 6,312 | 631 | 6,943 | 6,943 | - | - | - | - | - | - | - | - | - |
| 1a.4.3 | Health physics supplies | 377 | - | - | - | - | - | - | 94 | 471 | 471 | - | - | - | - | - | - | - | - | - |
| 1a.4.4 | Heavy equipment rental | 549 | - | - | - | - | - | - | 52 | 401 | 401 | - | - | - | - | - | - | - | - | - |
| 1a.4.5 | Disposal of DAW generated | - | - | 14 | 6 | - | 38 | - | 12 | 70 | 70 | - | - | - | - | - | - | 13,531 | 21 | - |
| 1a.4.6 | Plant energy budget | - | - | - | - | - | - | 964 | 145 | 1,108 | 1,108 | - | - | - | - | - | - | - | - | - |
| 1a.4.7 | NRC Fees | - | - | - | - | - | - | 258 | 26 | 284 | 284 | - | - | - | - | - | - | - | - | - |
| 1a.4.8 | Emergency Planning Fees | - | - | - | - | - | - | 450 | 45 | 495 | 495 | - | - | - | - | - | - | - | - | - |
| 1a.4.9 | Site O&M Cost | - | - | - | - | - | - | 250 | 37 | 287 | 287 | - | - | - | - | - | - | - | - | - |
| 1a.4.10 | Spent Fuel Pool O&M | - | - | - | - | - | - | 738 | 111 | 849 | 849 | - | - | - | - | - | - | - | - | - |
| 1a.4.11 | ISFSI Operating Costs | - | - | - | - | - | - | 82 | 12 | 94 | 94 | - | - | - | - | - | - | - | - | - |
| 1a.4.12 | Security Staff Cost | - | - | - | - | - | - | 5,955 | 893 | 6,848 | 6,848 | - | - | - | - | - | - | - | - | - |
| 1a.4.13 | Utility Staff Cost | - | - | - | - | - | - | 26,183 | 3,927 | 30,110 | 30,110 | - | - | - | - | - | - | - | - | - |
| 1a.4 | Subtotal Period 1a Period-Dependent Costs | - | 726 | 14 | 6 | - | 38 | 42,511 | 6,118 | 49,413 | 47,975 | - | - | - | 675 | - | - | 13,531 | 21 | 580,871 |
| 1a.0 | TOTAL PERIOD 1a COST | - | 726 | 14 | 6 | - | 38 | 93,648 | 13,789 | 108,220 | 60,924 | - | 388 | - | 675 | - | - | 13,531 | 21 | 659,480 |
| PERIOD 1b - Decommissioning Preparations | | | | | | | | | | | | | | | | | | | | |
| Period 1b Direct Decommissioning Activities | | | | | | | | | | | | | | | | | | | | |
| Detailed Work Procedures | | | | | | | | | | | | | | | | | | | | |
| 1b.1.1.1 | Plant systems | - | - | - | - | - | - | 429 | 64 | 494 | 444 | - | - | - | - | - | - | - | - | - |
| 1b.1.1.2 | NSSS Decontamination Flush | - | - | - | - | - | - | 91 | 14 | 104 | 104 | - | - | - | - | - | - | - | - | - |
| 1b.1.1.3 | Reactor internals | - | - | - | - | - | - | 363 | 54 | 417 | 417 | - | - | - | - | - | - | - | - | - |
| 1b.1.1.4 | Remaining buildings | - | - | - | - | - | - | 122 | 18 | 141 | 35 | - | - | 106 | - | - | - | - | - | - |
| 1b.1.1.5 | CRD housings & NIs | - | - | - | - | - | - | 91 | 14 | 104 | 104 | - | - | - | - | - | - | - | - | - |
| 1b.1.1.6 | Incore instrumentation | - | - | - | - | - | - | 91 | 14 | 104 | 104 | - | - | - | - | - | - | - | - | - |
| 1b.1.1.7 | Removal primary containment | - | - | - | - | - | - | 181 | 27 | 209 | 209 | - | - | - | - | - | - | - | - | - |
| 1b.1.1.8 | Reactor vessel | - | - | - | - | - | - | 329 | 49 | 379 | 379 | - | - | - | - | - | - | - | - | - |
| 1b.1.1.9 | Facility closure | - | - | - | - | - | - | 109 | 16 | 125 | 63 | - | - | 63 | - | - | - | - | - | - |
| 1b.1.1.10 | Sterilized shield | - | - | - | - | - | - | 109 | 16 | 125 | 125 | - | - | - | - | - | - | - | - | - |
| 1b.1.1.11 | Reinforced concrete | - | - | - | - | - | - | 91 | 14 | 104 | 52 | - | - | 52 | - | - | - | - | - | - |
| 1b.1.1.12 | Main Turbine | - | - | - | - | - | - | 189 | 28 | 217 | 217 | - | - | - | - | - | - | - | - | - |
| 1b.1.1.13 | Main Condensers | - | - | - | - | - | - | 189 | 28 | 218 | 218 | - | - | - | - | - | - | - | - | - |
| 1b.1.1.14 | Moisture separators & reheaters | - | - | - | - | - | - | 181 | 27 | 209 | 209 | - | - | - | - | - | - | - | - | - |
| 1b.1.1.15 | Radiation building | - | - | - | - | - | - | 248 | 37 | 285 | 285 | - | - | - | - | - | - | - | - | - |
| 1b.1.1.16 | Reactor building | - | - | - | - | - | - | 248 | 37 | 285 | 285 | - | - | - | - | - | - | - | - | - |
| 1b.1.1 | Total | - | - | - | - | - | - | 3,060 | 499 | 3,519 | 3,193 | - | - | - | 327 | - | - | - | - | - |
| 1b.1.2 | Decon NSSS | 430 | - | - | - | - | - | - | 215 | 645 | 645 | - | - | - | - | - | - | - | - | 1,067 |
| 1b.1 | Subtotal Period 1b Activity Costs | 430 | - | - | - | - | - | 3,060 | 674 | 4,164 | 3,838 | - | 327 | - | - | - | - | - | - | 1,067 |
| Period 1b Additional Costs | | | | | | | | | | | | | | | | | | | | |
| 1b.2.1 | Spent Fuel Pool Isolation | - | - | - | - | - | - | 9,133 | 1,370 | 10,503 | 10,503 | - | - | - | - | - | - | - | - | - |
| 1b.2.2 | Site Characterization | - | - | - | - | - | - | 897 | 269 | 1,167 | 1,167 | - | - | - | - | - | - | - | - | - |
| 1b.2.3 | Hazardous liquid disposal | - | - | - | 7 | - | 411 | - | 104 | 925 | 925 | - | - | - | - | - | - | 89,546 | - | - |
| 1b.2.4 | Contaminated asbestos disposal | - | - | - | 8 | - | 5 | - | 2 | 15 | 15 | - | - | - | - | - | - | 1,800 | - | - |
| 1b.2.5 | Clean asbestos disposal | - | - | - | 0 | - | 2 | - | 0 | 2 | 2 | - | - | - | - | - | - | 1,800 | - | - |
| 1b.2 | Subtotal Period 1b Additional Costs | - | - | - | 15 | - | 416 | 10,033 | 1,746 | 12,210 | 12,210 | - | - | - | - | - | - | 1,631 | - | - |

Table C
Clinton Power Station
DECON Decommissioning Cost Estimate
(Thousands of 2007 Dollars)

| Activity Index | Activity Description | Decon Cost | Removal Cost | Packaging Costs | Transport Costs | Off-Site Processing Costs | LLRW Disposal Costs | Other Costs | Total Contingency | Total Costs | NRC Lic. Term. Costs | Spent Fuel Management Costs | Site Restoration Costs | Processed Volume | | Burial Volumes | | Burial/Processed Wt., Lbs. | Craft Manhours | Utility and Contractor Manhours |
|--|---|------------|--------------|-----------------|-----------------|---------------------------|---------------------|-------------|-------------------|-------------|----------------------|-----------------------------|------------------------|------------------|------------------|------------------|------------------|----------------------------|----------------|---------------------------------|
| | | | | | | | | | | | | | | Cu. Feet | Class A Cu. Feet | Class B Cu. Feet | Class C Cu. Feet | | | |
| Period 1b Collateral Costs | | | | | | | | | | | | | | | | | | | | |
| 1b.3.1 | Decon equipment | 726 | - | - | - | - | - | - | 109 | 834 | 834 | - | - | - | - | - | - | - | - | - |
| 1b.3.2 | DOC staff relocation expenses | - | - | - | - | - | - | 829 | - | 124 | 953 | - | - | - | - | - | - | - | - | - |
| 1b.3.3 | Process liquid waste | 28 | - | 47 | 270 | - | 2,284 | - | 630 | 3,260 | 3,260 | - | - | - | 183 | 721 | - | 90,984 | 176 | - |
| 1b.3.4 | Small tool allowance | - | 1 | - | - | - | - | - | 0 | 2 | 2 | - | - | - | - | - | - | - | - | - |
| 1b.3.5 | Pipe cutting equipment | - | 957 | - | - | - | - | - | 143 | 1,100 | 1,100 | - | - | - | - | - | - | - | - | - |
| 1b.3.6 | Decon rig | 1,243 | - | - | - | - | - | - | 186 | 1,430 | 1,430 | - | - | - | - | - | - | - | - | - |
| 1b.3.7 | Spent Fuel Capital and Transfer | - | - | - | - | - | - | 6,000 | 900 | 6,900 | 6,900 | - | - | - | - | - | - | - | - | - |
| 1b.3 | Subtotal Period 1b Collateral Costs | 1,997 | 958 | 47 | 270 | - | 2,284 | 6,829 | 2,094 | 14,479 | 7,579 | - | - | - | 183 | 721 | - | 90,984 | 176 | - |
| Period 1b Period-Dependent Costs | | | | | | | | | | | | | | | | | | | | |
| 1b.4.1 | Decon supplies | 22 | - | - | - | - | - | 662 | 6 | 28 | 28 | - | - | - | - | - | - | - | - | - |
| 1b.4.2 | Insurance | - | - | - | - | - | - | 2,110 | 211 | 2,321 | 2,321 | - | - | - | - | - | - | - | - | - |
| 1b.4.3 | Property taxes | - | 193 | - | - | - | - | - | 48 | 242 | 242 | - | - | - | - | - | - | - | - | - |
| 1b.4.4 | Health physics supplies | 175 | - | - | - | - | - | 26 | 201 | 201 | 201 | - | - | - | - | - | - | - | - | - |
| 1b.4.5 | Heavy equipment rental | - | - | - | - | - | - | - | 6 | 37 | 37 | - | - | - | - | - | - | 7,109 | 11 | - |
| 1b.4.6 | Disposal of DAW generated | - | - | 8 | 3 | - | 20 | - | 145 | 1,111 | 1,111 | - | - | - | - | - | - | - | - | - |
| 1b.4.7 | Plant energy budget | - | - | - | - | - | - | 966 | 130 | 1,143 | 1,143 | - | - | - | - | - | - | - | - | - |
| 1b.4.8 | NRC Fees | - | - | - | - | - | - | 130 | 13 | 143 | 143 | - | - | - | - | - | - | - | - | - |
| 1b.4.9 | Emergency Planning Fees | - | - | - | - | - | - | 225 | 23 | 248 | 248 | - | - | - | - | - | - | - | - | - |
| 1b.4.10 | Site O&M Cost | - | - | - | - | - | - | 125 | 19 | 144 | 144 | - | - | - | - | - | - | - | - | - |
| 1b.4.11 | Spent Fuel Pool O&M | - | - | - | - | - | - | 370 | 55 | 425 | 425 | - | - | - | - | - | - | - | - | - |
| 1b.4.12 | ISFSI Operating Costs | - | - | - | - | - | - | 41 | 6 | 47 | 47 | - | - | - | - | - | - | - | - | - |
| 1b.4.13 | Security Staff Cost | - | - | - | - | - | - | 2,986 | 448 | 3,434 | 3,434 | - | - | - | - | - | - | - | - | - |
| 1b.4.14 | DOC Staff Cost | - | - | - | - | - | - | 41,336 | 620 | 47,956 | 47,956 | - | - | - | - | - | - | - | - | - |
| 1b.4.15 | Utility Staff Cost | - | - | - | - | - | - | 9,311 | 1,397 | 10,708 | 10,708 | - | - | - | - | - | - | - | - | - |
| 1b.4 | Subtotal Period 1b Period-Dependent Costs | 22 | 368 | 8 | 3 | - | 20 | 21,062 | 3,089 | 24,572 | 23,851 | 721 | - | - | 355 | - | - | 71,099 | 11 | - |
| 1b.0 | TOTAL PERIOD 1b COST | 2,449 | 1,326 | 55 | 288 | - | 2,720 | 40,984 | 7,603 | 55,425 | 47,478 | 7,621 | 327 | - | 2,169 | 721 | - | 189,439 | 1,254 | 324,450 |
| PERIOD 1 TOTALS | | 2,449 | 2,052 | 69 | 294 | - | 2,758 | 134,632 | 21,391 | 163,646 | 108,401 | 54,530 | 715 | - | 2,844 | 721 | - | 202,970 | 1,274 | 983,990 |
| PERIOD 2a - Large Component Removal | | | | | | | | | | | | | | | | | | | | |
| Period 2a Direct Decommissioning Activities | | | | | | | | | | | | | | | | | | | | |
| Nuclear Steam Supply System Removal | | | | | | | | | | | | | | | | | | | | |
| 2a.1.1.1 | Recirculation System Piping & Valves | 49 | 45 | 8 | 12 | - | 69 | - | 63 | 277 | 277 | - | - | - | - | - | - | 64,091 | 1,943 | - |
| 2a.1.1.2 | Recirculation Pumps & Motors | 49 | 42 | 13 | 31 | 18 | 263 | - | 110 | 327 | 327 | - | - | 250 | 2,473 | - | - | 187,000 | 1,998 | - |
| 2a.1.1.3 | CRDMs & NIE Removal | 199 | 158 | 921 | 111 | - | 203 | - | 239 | 1,231 | 1,231 | - | - | - | 6,985 | - | - | 131,119 | 4,284 | - |
| 2a.1.1.4 | Reactor Vessel Internals | 166 | 2,726 | 5,033 | 2,034 | - | 15,013 | 280 | 11,443 | 36,695 | 36,695 | - | - | - | 1,753 | 1,485 | 689 | 337,865 | 39,200 | 1,700 |
| 2a.1.1.5 | Reactor Vessel | 81 | 5,751 | 1,904 | 890 | - | 2,046 | 280 | 6,107 | 17,019 | 17,019 | - | - | - | 12,291 | - | - | 1,319,980 | 39,200 | 1,700 |
| 2a.1.1 | Totals | 545 | 8,722 | 7,279 | 3,038 | 18 | 17,625 | 560 | 17,962 | 55,749 | 55,749 | - | - | 250 | 24,032 | 1,485 | 689 | 2,059,953 | 89,625 | 3,400 |
| Removal of Major Equipment | | | | | | | | | | | | | | | | | | | | |
| 2a.1.2 | Main Turbine/Generator | - | 348 | 885 | 180 | 2,586 | 132 | - | 628 | 4,780 | 4,780 | - | - | 54,728 | 1,613 | - | - | 2,607,544 | 7,309 | - |
| 2a.1.3 | Main Condensers | - | 1,174 | 952 | 194 | 2,781 | 163 | - | 876 | 6,139 | 6,139 | - | - | 95,848 | 1,735 | - | - | 2,803,515 | 24,651 | - |
| Caseworking Costs from Clean Building Demolition | | | | | | | | | | | | | | | | | | | | |
| 2a.1.4.1 | Reactor Building | - | 905 | - | - | - | - | - | 136 | 1,041 | 1,041 | - | - | - | - | - | - | - | 11,450 | - |
| 2a.1.4.2 | Auxiliary Building | - | 216 | - | - | - | - | - | 32 | 248 | 248 | - | - | - | - | - | - | - | 2,382 | - |
| 2a.1.4.3 | Radiation Building | - | 500 | - | - | - | - | - | 75 | 575 | 575 | - | - | - | - | - | - | - | 6,493 | - |
| 2a.1.4.4 | Turbine Building | - | 508 | - | - | - | - | - | 76 | 585 | 585 | - | - | - | - | - | - | - | 6,771 | - |

Table C
Clinton Power Station
DECON Decommissioning Cost Estimate
(Thousands of 2007 Dollars)

| Activity Index | Activity Description | Decon Cost | Removal Cost | Packaging Costs | Transport Costs | Off-Site Processing Costs | LLRW Disposal Costs | Other Costs | Total Contingency | Total Costs | NRC Lic. Term. Costs | Spent Fuel Management Costs | Site Restoration Costs | Processed Volume Cu. Feet | Burial Volumes | | | Burial/Processed Wt., Lbs. | Craft Manhours | Utility and Contractor Manhours | |
|--|---|------------|--------------|-----------------|-----------------|---------------------------|---------------------|-------------|-------------------|-------------|----------------------|-----------------------------|------------------------|---------------------------|------------------|------------------|------------------|----------------------------|----------------|---------------------------------|---|
| | | | | | | | | | | | | | | | Class A Cu. Feet | Class B Cu. Feet | Class C Cu. Feet | | | | |
| Cascading Costs from Clean Building Demolition (continued) | | | | | | | | | | | | | | | | | | | | | |
| 2a.1.4.5 | Fuel Building | - | 237 | - | - | - | - | - | 36 | 273 | 273 | - | - | - | - | - | - | - | - | 2,912 | - |
| 2a.1.4 | Totals | - | 2,367 | - | - | - | - | - | 355 | 2,722 | 2,722 | - | - | - | - | - | - | - | - | 30,209 | - |
| Disposal of Plant Systems | | | | | | | | | | | | | | | | | | | | | |
| 2a.1.5.1 | Acid Feed & Handling | - | 484 | 13 | 19 | 21 | 319 | - | 10 | 59 | 59 | - | - | 488 | - | - | - | - | 19,822 | 533 | - |
| 2a.1.5.2 | Auxiliary Steam | - | 36 | - | - | - | - | - | 5 | 42 | - | - | 42 | - | - | - | - | - | 304,278 | 9,740 | - |
| 2a.1.5.3 | Breathing Air | - | 16 | - | - | - | - | - | 2 | 18 | - | - | 18 | - | - | - | - | - | - | 820 | - |
| 2a.1.5.4 | CO2 & Generator Purge | - | 13 | - | - | - | - | - | 5 | 26 | 26 | - | - | 183 | - | - | - | - | 7,431 | 256 | - |
| 2a.1.5.5 | Cautic Handling | 395 | 391 | 39 | 36 | 84 | 168 | - | 361 | 1,484 | 1,484 | - | - | 2,211 | 2,121 | - | - | - | 249,802 | 14,872 | - |
| 2a.1.5.6 | Chem Raw/Waste Reprocessing & Disposal | - | 1,035 | 27 | 40 | 679 | - | - | 369 | 2,149 | 2,149 | - | - | 15,914 | - | - | - | - | 646,286 | 20,760 | - |
| 2a.1.5.7 | Chilled Water - RCA | - | 166 | - | - | - | - | - | 25 | 191 | - | - | 191 | - | - | - | - | - | 3,682 | - | - |
| 2a.1.5.8 | Chilled Water Non-RCA | - | 44 | - | - | - | - | - | 7 | 51 | - | - | 51 | - | - | - | - | - | - | 953 | - |
| 2a.1.5.9 | Chlorination | - | 161 | 16 | 24 | 400 | - | - | 105 | 706 | 706 | - | - | 9,379 | - | - | - | - | 380,377 | 3,419 | - |
| 2a.1.5.10 | Circulating Water - RCA | - | 51 | - | - | - | - | - | 8 | 58 | - | - | 58 | - | - | - | - | - | - | 1,090 | - |
| 2a.1.5.11 | Circulating Water Non-RCA | - | 90 | 5 | 5 | 8 | 24 | - | 31 | 162 | 162 | - | - | 187 | 253 | - | - | - | 30,046 | 1,844 | - |
| 2a.1.5.12 | Crnmtt Aux & Fuel Bldg Equip Drains | - | 156 | 8 | 8 | 34 | 32 | - | 54 | 292 | 292 | - | - | 792 | 367 | - | - | - | 62,536 | 3,212 | - |
| 2a.1.5.13 | Crnmtt Aux & Fuel Bldg Floor Drains | - | 119 | - | - | - | - | - | 18 | 137 | - | - | 137 | - | - | - | - | - | - | 2,622 | - |
| 2a.1.5.14 | Component Cooling Water Non-RCA | - | 904 | 159 | 174 | 584 | 772 | - | 549 | 3,142 | 3,142 | - | - | 13,689 | 8,197 | - | - | - | 1,281,159 | 19,496 | - |
| 2a.1.5.15 | Condensate | - | 855 | 161 | 178 | 543 | 806 | - | 539 | 3,082 | 3,082 | - | - | 12,724 | 8,568 | - | - | - | 1,284,382 | 18,468 | - |
| 2a.1.5.16 | Condensate Booster | 690 | 690 | 46 | 45 | 188 | 188 | - | 259 | 1,416 | 1,416 | - | - | 4,398 | 2,104 | - | - | - | 357,430 | 14,429 | - |
| 2a.1.5.17 | Condensate Polishing | - | 179 | 17 | 25 | 430 | - | - | 115 | 767 | 767 | - | - | 10,094 | - | - | - | - | 409,927 | 3,731 | - |
| 2a.1.5.18 | Containment Combustible Gas | - | 75 | 4 | 4 | 33 | 14 | - | 28 | 158 | 158 | - | - | 781 | 147 | - | - | - | 44,863 | 1,568 | - |
| 2a.1.5.19 | Containment Non-Combustible Gas | - | 617 | 41 | 40 | 181 | 163 | - | 232 | 1,275 | 1,275 | - | - | 4,242 | 1,929 | - | - | - | 327,937 | 12,878 | - |
| 2a.1.5.20 | Cyclot Cooling | - | 138 | 11 | 15 | 118 | 42 | - | 179 | 1,012 | 1,012 | - | - | 5,664 | 655 | - | - | - | 288,770 | 9,748 | - |
| 2a.1.5.21 | Drywell Purge | - | 72 | 2 | 4 | 51 | 3 | - | 27 | 139 | 139 | - | - | 2,764 | 451 | - | - | - | 152,087 | 2,951 | - |
| 2a.1.5.22 | ECCS Equipment Cooling | - | 473 | 54 | 63 | 236 | 271 | - | 296 | 1,333 | 1,333 | - | - | 1,190 | 32 | - | - | - | 51,154 | 1,484 | - |
| 2a.1.5.23 | Extraction Steam | - | 519 | 88 | 100 | 331 | 445 | - | 315 | 1,799 | 1,799 | - | - | 5,551 | 2,875 | - | - | - | 482,498 | 10,135 | - |
| 2a.1.5.24 | Feedwater | - | 1,238 | 112 | 126 | 507 | 527 | - | 548 | 3,058 | 3,058 | - | - | 7,772 | 4,722 | - | - | - | 739,273 | 11,221 | - |
| 2a.1.5.25 | Feedwater Heater Drains Turbine Cycle | - | 193 | 13 | 13 | 29 | 62 | - | 71 | 382 | 382 | - | - | 11,869 | 5,704 | - | - | - | 985,659 | 26,301 | - |
| 2a.1.5.26 | Feedwater Heater Misc. | - | 4 | - | - | - | - | - | 1 | 4 | - | - | 4 | - | - | - | - | - | 87,316 | 4,010 | - |
| 2a.1.5.27 | Filtered Water | - | 25 | 0 | 1 | 10 | - | - | 8 | 44 | 44 | - | - | 243 | - | - | - | - | 9,883 | 469 | - |
| 2a.1.5.28 | Generator Hydrogen Seal Oil | - | 16 | 0 | 1 | 9 | - | - | 6 | 32 | 32 | - | - | 207 | - | - | - | - | 8,423 | 339 | - |
| 2a.1.5.29 | Generator Stator Cooling | - | 251 | 36 | 39 | 131 | 170 | - | 134 | 761 | 761 | - | - | 3,077 | 1,807 | - | - | - | 287,030 | 5,388 | - |
| 2a.1.5.30 | High Pressure Core Spray | - | 22 | 0 | 0 | 7 | - | - | 7 | 36 | 36 | - | - | 168 | - | - | - | - | 6,515 | 403 | - |
| 2a.1.5.31 | Hydrogen | - | 209 | 14 | 14 | 90 | 49 | - | 82 | 469 | 469 | - | - | 2,116 | 646 | - | - | - | 132,517 | 4,389 | - |
| 2a.1.5.32 | Laundry Equip & Flr Drains RW Reprocess | - | 42 | 1 | 1 | 1 | 3 | - | 11 | 58 | 58 | - | - | 30 | 29 | - | - | - | 3,822 | 928 | - |
| 2a.1.5.33 | Leak Detection | - | 5 | - | - | - | - | - | 6 | 365 | 365 | - | - | 1,535 | 1,028 | - | - | - | 154,545 | 2,081 | - |
| 2a.1.5.34 | Local Instrument Panels | - | 97 | 21 | 21 | 65 | 97 | - | 64 | 365 | 365 | - | - | 2,665 | 71 | - | - | - | 114,605 | 4,249 | - |
| 2a.1.5.35 | Low Pressure Core Spray | - | 10 | 0 | 1 | 10 | - | - | 4 | 25 | 25 | - | - | 2,665 | 71 | - | - | - | 61,424 | 1,762 | - |
| 2a.1.5.36 | Machine Shop Equipment | - | 222 | 5 | 8 | 114 | 7 | - | 76 | 431 | 431 | - | - | 6,957 | 3,685 | - | - | - | 51,157 | 429 | - |
| 2a.1.5.37 | Machine Shop Ventilation | - | 833 | 74 | 80 | 298 | 347 | - | 359 | 1,891 | 1,891 | - | - | 23 | 47 | - | - | - | 98,255 | 3,395 | - |
| 2a.1.5.38 | Main Steam | - | 21 | 1 | 1 | 1 | - | - | 7 | 35 | 35 | - | - | 2,419 | - | - | - | - | 85,161 | 4,912 | - |
| 2a.1.5.39 | Main Steam Isolation Valve | - | 184 | 4 | 6 | 103 | - | - | 63 | 360 | 360 | - | - | 518 | 715 | - | - | - | 4,416 | 337 | - |
| 2a.1.5.40 | Main Steam Isolation Valve | - | 208 | - | - | - | - | - | 31 | 239 | 239 | - | - | 19 | - | - | - | - | - | 643 | - |
| 2a.1.5.41 | Make-up Demineralizer - RCA | - | 240 | 16 | 14 | 22 | 67 | - | 2 | 49 | 49 | - | - | 34 | - | - | - | - | - | 359 | - |
| 2a.1.5.42 | Make-up Demineralizer Non-RCA | - | 30 | - | - | - | - | - | 4 | 34 | 34 | - | - | 17 | - | - | - | - | - | 363 | - |
| 2a.1.5.43 | Makeup Condensate Storage | - | 90 | 4 | 6 | 104 | 3 | - | 39 | 243 | 243 | - | - | 2,429 | 1,796 | - | - | - | 98,602 | 1,894 | - |
| 2a.1.5.44 | Misc. Building Drains | - | 216 | 15 | 15 | 77 | 57 | - | 84 | 463 | 463 | - | - | 1,796 | 698 | - | - | - | 127,607 | 4,557 | - |
| 2a.1.5.45 | Misc. Building Ventilation | - | 0 | - | - | - | - | - | 5 | 27 | 27 | - | - | 17 | - | - | - | - | - | 363 | - |
| 2a.1.5.46 | Nuclear Boiler | - | 90 | 4 | 6 | 104 | 3 | - | 39 | 243 | 243 | - | - | 2,429 | 1,796 | - | - | - | 98,602 | 1,894 | - |
| 2a.1.5.47 | Oil Transfer | - | 216 | 15 | 15 | 77 | 57 | - | 84 | 463 | 463 | - | - | 1,796 | 698 | - | - | - | 127,607 | 4,557 | - |
| 2a.1.5.48 | Reactor Core Isolation Cooling | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - |

Table C
Clinton Power Station
DECON Decommissioning Cost Estimate
(Thousands of 2007 Dollars)

| Activity Index | Activity Description | Decom Cost | Removal Cost | Packaging Costs | Transport Costs | Off-Site Processing Costs | LLRW Disposal Costs | Other Costs | Total Contingency | Total Costs | NRC Lic. Term. Costs | Spent Fuel Management Costs | Site Restoration Costs | Processed Volume | | | Burial Volumes | | | Burial/Processed Wt., Lbs. | Craft Manhours | Utility and Contractor Manhours | |
|---------------------------------------|---|------------|--------------|-----------------|-----------------|---------------------------|---------------------|-------------|-------------------|-------------|----------------------|-----------------------------|------------------------|------------------|------------------|------------------|------------------|----------|------------------|----------------------------|----------------|---------------------------------|------------------|
| | | | | | | | | | | | | | | Cu. Feet | Class A Cu. Feet | Class B Cu. Feet | Class C Cu. Feet | Cu. Feet | Class A Cu. Feet | | | | Class B Cu. Feet |
| Disposal of Plant Systems (continued) | | | | | | | | | | | | | | | | | | | | | | | |
| 2a.1.5.49 | Refrigeration Piping | - | 17 | - | - | - | - | - | 3 | 20 | - | - | 20 | - | - | - | - | - | - | - | - | 388 | - |
| 2a.1.5.50 | Sanitary | - | 151 | - | - | - | - | - | 23 | 174 | - | - | 174 | - | - | - | - | - | - | - | - | 3,202 | - |
| 2a.1.5.51 | Screena House & MU Pump House Ventilation | - | 31 | - | - | - | - | - | 5 | 36 | - | - | 36 | - | - | - | - | - | - | - | - | 736 | - |
| 2a.1.5.52 | Standby Liquid Control | - | 26 | 1 | - | 18 | - | - | 9 | 55 | 55 | - | 36 | - | - | - | - | - | - | - | 16,763 | 529 | - |
| 2a.1.5.53 | Switchgear/Heat Removal | - | 16 | - | - | - | - | - | 2 | 19 | - | - | 19 | - | - | - | - | - | - | - | - | 356 | - |
| 2a.1.5.54 | Turbine Building Closed Cooling Water | - | 148 | 4 | 5 | 90 | - | - | 52 | 299 | 299 | - | - | - | - | - | - | - | - | - | 85,331 | 2,948 | - |
| 2a.1.5.55 | Turbine Electrohydraulic Control | - | 50 | 0 | 0 | 4 | 9 | - | 3 | 16 | 16 | - | - | - | - | - | - | - | - | - | 3,405 | 185 | - |
| 2a.1.5.56 | Turbine Gen Misc Drains & Vents | - | 335 | 40 | 50 | 453 | 130 | - | 196 | 1,205 | 1,205 | - | - | - | - | - | - | - | - | - | 14,138 | 1,013 | - |
| 2a.1.5.57 | Turbine Oil | - | 54 | 4 | 5 | 37 | 18 | - | 25 | 144 | 144 | - | - | - | - | - | - | - | - | - | 555,788 | 7,100 | - |
| 2a.1.5.58 | Turbine-Gen Aux & Misc Devices | - | 240 | 51 | 62 | 289 | 250 | - | 180 | 1,073 | 1,073 | - | - | - | - | - | - | - | - | - | 52,601 | 1,145 | - |
| 2a.1.5.59 | Turbine-Gen Aux & Misc Devices | - | 13,063 | 1,131 | 1,280 | 6,974 | 4,732 | - | 5,922 | 33,558 | 32,510 | - | 1,048 | - | - | - | - | - | - | - | 513,573 | 5,243 | - |
| 2a.1.5 | Totals | 396 | 13,063 | 1,131 | 1,280 | 6,974 | 4,732 | - | 5,922 | 33,558 | 32,510 | - | 1,048 | - | - | - | - | - | - | - | 11,205,730 | 280,825 | - |
| 2a.1.6 | Scaffolding in support of decommissioning | - | 3,063 | 50 | 11 | 140 | 17 | - | 798 | 4,080 | 4,080 | - | - | - | - | - | - | - | - | - | 150,174 | 70,739 | - |
| 2a.1 | Subtotal Period 2a Activity Costs | 941 | 28,737 | 10,296 | 4,704 | 12,489 | 22,750 | 580 | 26,540 | 107,027 | 105,979 | - | 1,048 | - | - | - | - | - | - | - | 18,827,220 | 506,388 | 3,400 |
| Period 2a Additional Costs | | | | | | | | | | | | | | | | | | | | | | | |
| 2a.2.1 | Disposal of stored turbine rotors | - | 17 | 100 | 40 | 743 | - | - | 130 | 1,030 | 1,030 | - | - | - | - | - | - | - | - | - | 707,558 | 352 | - |
| 2a.2 | Subtotal Period 2a Additional Costs | - | 17 | 100 | 40 | 743 | - | - | 130 | 1,030 | 1,030 | - | - | - | - | - | - | - | - | - | 707,558 | 352 | - |
| Period 2a Collateral Costs | | | | | | | | | | | | | | | | | | | | | | | |
| 2a.3.1 | Process liquid waste | 138 | - | 65 | 359 | - | 138 | - | 164 | 864 | 864 | - | - | - | - | - | - | - | - | - | - | 241 | - |
| 2a.3.2 | Small tool allowance | - | 375 | - | - | - | - | 23,000 | 96 | 431 | 388 | - | 43 | - | - | - | - | - | - | - | - | - | - |
| 2a.3.3 | Spent Fuel Capital and Transfer | - | - | - | - | - | - | - | 3,450 | 26,450 | - | - | - | - | - | - | - | - | - | - | - | - | - |
| 2a.3 | Subtotal Period 2a Collateral Costs | 138 | 375 | 65 | 359 | - | 138 | 23,000 | 3,670 | 27,745 | 1,252 | - | 43 | - | - | - | - | - | - | - | 89,037 | 241 | - |
| Period 2a Period-Dependent Costs | | | | | | | | | | | | | | | | | | | | | | | |
| 2a.4.1 | Decom supplies | 79 | - | - | - | - | - | - | 20 | 99 | 99 | - | - | - | - | - | - | - | - | - | - | - | - |
| 2a.4.2 | Insurance | - | - | - | - | - | - | 905 | 91 | 996 | 996 | - | - | - | - | - | - | - | - | - | - | - | - |
| 2a.4.3 | Property taxes | - | - | - | - | - | - | 3,380 | 339 | 3,729 | 3,356 | - | 373 | - | - | - | - | - | - | - | - | - | - |
| 2a.4.4 | Health physics supplies | - | 2,450 | - | - | - | - | - | 613 | 3,063 | 3,063 | - | - | - | - | - | - | - | - | - | - | - | - |
| 2a.4.5 | Heavy equipment rental | - | 3,043 | - | - | - | - | - | 496 | 3,500 | 3,500 | - | - | - | - | - | - | - | - | - | - | - | - |
| 2a.4.6 | Disposal of DAW generated | - | - | 212 | 87 | - | 556 | - | 173 | 1,028 | 1,028 | - | - | - | - | - | - | - | - | - | 199,586 | 304 | - |
| 2a.4.7 | Plant energy budget | - | - | - | - | - | - | 1,635 | 245 | 1,880 | 1,880 | - | - | - | - | - | - | - | - | - | - | - | - |
| 2a.4.8 | NRC Fees | - | - | - | - | - | - | 614 | 61 | 676 | 676 | - | - | - | - | - | - | - | - | - | - | - | - |
| 2a.4.9 | Emergency Planning Fees | - | - | - | - | - | - | 357 | 36 | 393 | 393 | - | - | - | - | - | - | - | - | - | - | - | - |
| 2a.4.10 | Site O&M Cost | - | - | - | - | - | - | 446 | 67 | 513 | 513 | - | - | - | - | - | - | - | - | - | - | - | - |
| 2a.4.11 | Spent Fuel Pool O&M | - | - | - | - | - | - | 1,318 | 198 | 1,516 | 1,516 | - | - | - | - | - | - | - | - | - | - | - | - |
| 2a.4.12 | SFSL Operating Costs | - | - | - | - | - | - | 147 | 22 | 169 | 169 | - | - | - | - | - | - | - | - | - | - | - | - |
| 2a.4.13 | Security Staff Cost | - | - | - | - | - | - | 8,912 | 1,357 | 10,269 | 10,248 | - | - | - | - | - | - | - | - | - | - | - | - |
| 2a.4.14 | DOC Staff Cost | - | - | - | - | - | - | 15,424 | 2,764 | 21,188 | 21,188 | - | - | - | - | - | - | - | - | - | - | - | - |
| 2a.4.15 | Utility Staff Cost | - | - | - | - | - | - | 33,174 | 4,976 | 38,150 | 38,150 | - | - | - | - | - | - | - | - | - | - | - | - |
| 2a.4 | Subtotal Period 2a Period-Dependent Costs | 79 | 5,493 | 212 | 87 | - | 556 | 69,323 | 11,397 | 87,148 | 84,697 | - | 373 | - | - | - | - | - | - | - | 199,586 | 304 | - |
| 2a.0 | TOTAL PERIOD 2a COST | 1,156 | 34,622 | 10,673 | 5,190 | 13,241 | 23,443 | 92,884 | 41,738 | 222,949 | 192,958 | - | 1,464 | - | - | - | - | - | - | - | 19,823,200 | 504,285 | 1,045,394 |

Table C
Clinton Power Station
DECON Decommissioning Cost Estimate
(Thousands of 2007 Dollars)

| Activity Index | Activity Description | Decom Cost | Removal Cost | Packaging Costs | Transport Costs | Off-Site Processing Costs | LLRW Disposal Costs | Other Costs | Total Contingency | Total Costs | NRC Lic. Term. Costs | Spent Fuel Management Costs | Site Restoration Costs | Processed Volume | | Burial Volumes | | Burial/Processed Wt., Lbs. | Craft Manhours | Utility and Contractor Manhours |
|---|---|------------|--------------|-----------------|-----------------|---------------------------|---------------------|-------------|-------------------|-------------|----------------------|-----------------------------|------------------------|------------------|----------|------------------|------------------|----------------------------|----------------|---------------------------------|
| | | | | | | | | | | | | | | Cu. Feet | Cu. Feet | Class A Cu. Feet | Class B Cu. Feet | | | |
| PERIOD 2b - Site Decontamination | | | | | | | | | | | | | | | | | | | | |
| Period 2b Direct Decommissioning Activities | | | | | | | | | | | | | | | | | | | | |
| Disposal of Plant Systems | | | | | | | | | | | | | | | | | | | | |
| 2b.1.1.1 | Component Cooling Water - RCA | - | 178 | 4 | 6 | 101 | 4 | - | 61 | 350 | 350 | - | - | 2,361 | - | - | - | 95,865 | 3,548 | - |
| 2b.1.1.2 | Containment Monitoring | - | 56 | 1 | 1 | 4 | 4 | - | 16 | 83 | 83 | - | - | 98 | - | - | - | 7,962 | 1,241 | - |
| 2b.1.1.3 | Control Rod Drive | - | 397 | 19 | 19 | 57 | 88 | - | 135 | 715 | 715 | - | - | 1,333 | - | - | - | 137,526 | 8,291 | - |
| 2b.1.1.4 | Diesel Fuel Oil | - | 59 | - | - | - | - | - | 9 | 68 | - | - | 68 | - | - | - | - | - | 1,256 | - |
| 2b.1.1.5 | Diesel General | - | 52 | - | - | - | - | - | 8 | 60 | - | - | 88 | - | - | - | - | - | 1,133 | - |
| 2b.1.1.6 | Diesel-Generator Room Ventilation | - | 77 | - | - | - | - | - | 12 | 88 | - | - | 88 | - | - | - | - | - | 1,817 | - |
| 2b.1.1.7 | Drains-Laudry to Radwaste | - | 17 | - | 1 | 1 | 4 | - | 232 | 1,777 | - | - | 1,777 | - | - | - | - | 4,837 | 340 | - |
| 2b.1.1.8 | Electrical - Clean RCA | - | 1,545 | 125 | 188 | 3,190 | - | - | 2,052 | 11,087 | 11,087 | - | - | 74,814 | - | - | - | 3,038,544 | 126,548 | - |
| 2b.1.1.9 | Equip Drain Radwaste Reprocessing | - | 6,131 | 69 | 67 | 307 | 271 | - | 414 | 2,261 | 2,261 | - | 177 | 7,207 | - | - | - | 511,230 | 23,620 | - |
| 2b.1.1.10 | Equip Drain Radwaste Reprocessing | - | 1,132 | 54 | 55 | 235 | 227 | - | 282 | 1,558 | 1,558 | - | - | 5,507 | - | - | - | 439,585 | 14,712 | - |
| 2b.1.1.11 | Fire Protection Non-RCA | - | 154 | - | - | - | - | - | 23 | 177 | - | - | - | 540 | - | - | - | 25,200 | 663 | - |
| 2b.1.1.12 | Floor Drain Radwaste Reprocessing | - | 31 | 1 | 2 | 23 | 3 | - | 12 | 73 | 73 | - | 279 | - | - | - | - | 5,686 | - | - |
| 2b.1.1.13 | HVAC - Auxiliary Building | - | 242 | - | - | - | - | - | 36 | 279 | - | - | - | 3,782 | - | - | - | 163,158 | 5,975 | - |
| 2b.1.1.14 | HVAC - Control Room | - | 313 | - | 11 | 161 | 10 | - | 107 | 611 | 611 | - | - | 6,035 | - | - | - | 261,272 | 9,695 | - |
| 2b.1.1.15 | HVAC - Fuel Building | - | 504 | 13 | 18 | 257 | 17 | - | 173 | 982 | 982 | - | - | 1,499 | - | - | - | 78,082 | 2,607 | - |
| 2b.1.1.16 | HVAC - Laboratory | - | 128 | 6 | 7 | 64 | 18 | - | 271 | 271 | - | - | - | 9,269 | - | - | - | 411,319 | 13,769 | - |
| 2b.1.1.17 | HVAC - Off Gas Building | - | 713 | 21 | 30 | 385 | 37 | - | 253 | 1,449 | 1,449 | - | 60 | - | - | - | - | 1,145 | - | - |
| 2b.1.1.18 | HVAC - Radwaste Building | - | 52 | - | - | - | - | - | 8 | 60 | - | - | - | 7,421 | - | - | - | 320,323 | 11,248 | - |
| 2b.1.1.19 | HVAC - Service Building | - | 589 | 15 | 22 | 316 | 20 | - | 204 | 1,167 | 1,167 | - | 7 | - | - | - | - | 109,971 | 7,089 | - |
| 2b.1.1.20 | HVAC - Turbine Building | - | 6 | - | - | - | - | - | 1 | 7 | - | - | - | 2,708 | - | - | - | 389 | - | - |
| 2b.1.1.21 | Hoist Cranes & Elevators | - | 374 | 5 | 7 | 115 | - | - | 112 | 613 | 613 | - | 20 | - | - | - | - | 91,689 | 3,537 | - |
| 2b.1.1.22 | Instrument Air - RCA | - | 17 | - | - | - | - | - | 3 | 20 | - | - | - | 3,043 | - | - | - | 123,583 | 3,532 | - |
| 2b.1.1.23 | Instrument Air - Non-RCA | - | 176 | 5 | 8 | 130 | 33 | - | 63 | 349 | 349 | - | - | 3,043 | - | - | - | 23,024 | 1,902 | - |
| 2b.1.1.24 | Off Gas | - | 156 | - | - | - | - | - | 23 | 180 | 180 | - | 180 | - | - | - | - | 25,067 | 1,390 | - |
| 2b.1.1.25 | Plant Service Water - RCA | - | 93 | 4 | 3 | 11 | 13 | - | 29 | 154 | 154 | - | - | 253 | - | - | - | 648,075 | 14,073 | - |
| 2b.1.1.26 | Plant Service Water - Non-RCA | - | 47 | - | 4 | 6 | 21 | - | 29 | 130 | 130 | - | - | 140 | - | - | - | 141,994 | 8,682 | - |
| 2b.1.1.27 | Process Radiation Monitoring | 20 | 286 | 20 | 21 | 48 | 101 | - | 224 | 931 | 931 | - | - | 6,526 | - | - | - | 14,073 | 132 | - |
| 2b.1.1.28 | Reactor Recirculation | 230 | 538 | 87 | 89 | 278 | 402 | - | 530 | 2,386 | 2,386 | - | 7 | - | - | - | - | 100,556 | 4,507 | - |
| 2b.1.1.29 | Reactor Water Clean-up | 462 | 6 | - | - | - | - | - | 1 | 7 | - | - | - | 2,476 | - | - | - | 60,155 | 1,829 | - |
| 2b.1.1.30 | Residual Heat Removal | - | 230 | 4 | 6 | 106 | - | - | 75 | 421 | 421 | - | 16 | - | - | - | - | 275,491 | 19,866 | - |
| 2b.1.1.31 | Screen Wash | - | 14 | - | - | - | - | - | 2 | 16 | - | - | - | 1,481 | - | - | - | 24,299 | 1,386 | - |
| 2b.1.1.32 | Service Air - RCA | - | 92 | 2 | 4 | 63 | - | - | 35 | 195 | 195 | - | 114 | - | - | - | - | 65,367 | 2,296 | - |
| 2b.1.1.33 | Service Air - Non-RCA | - | 99 | - | - | - | - | - | 15 | 114 | 114 | - | - | 3,684 | - | - | - | 64,491 | 1,065 | - |
| 2b.1.1.34 | Shutdown Service Water - RCA | - | 435 | 33 | 33 | 157 | 132 | - | 424 | 1,781 | 1,781 | - | - | 313 | - | - | - | 152,020 | 5,124 | - |
| 2b.1.1.35 | Shutdown Service Water - Non-RCA | - | 67 | 2 | 2 | 22 | 4 | - | 21 | 118 | 118 | - | - | 913 | - | - | - | 167,636 | 6,823 | - |
| 2b.1.1.36 | Solid Radwaste Reprocessing & Disposal | - | 108 | 9 | 8 | 36 | 46 | - | 28 | 238 | 238 | - | - | 615 | - | - | - | 51,758 | 1,735 | - |
| 2b.1.1.37 | Steady Gas Treatment | - | 49 | 7 | 8 | 32 | 36 | - | 38 | 160 | 160 | - | - | 742 | - | - | - | 12,124 | 412 | - |
| 2b.1.1.38 | Suppression Pool Cleanup & Transfer | - | 203 | 11 | 10 | 18 | 46 | - | 119 | 692 | 692 | - | - | 425 | - | - | - | 157,636 | 5,823 | - |
| 2b.1.1.39 | Suppression Pool Make-up | - | 229 | 20 | 19 | 91 | 75 | - | 6,000 | 32,355 | 30,104 | - | 2,850 | 147,259 | - | - | - | 358,965 | 11,248 | - |
| 2b.1.1.40 | Turb OG RW Chnl & DG Bldg Equip Drains | - | 1,146 | 16,704 | 558 | 662 | 1,605 | - | 997 | 5,100 | 5,100 | - | - | 3,711 | - | - | - | 187,718 | 88,424 | - |
| 2b.1.1.41 | Turb OG RW Chnl & DG Bldg Equip Drains | - | 3,829 | 62 | 14 | 175 | 22 | - | 2,891 | 12,236 | 12,236 | - | - | 7,794 | - | - | - | 2,570,182 | 127,462 | - |
| 2b.1.1.2 | Scuffolding in support of decommissioning | - | 2,786 | 412 | 464 | 330 | 1,843 | - | 248 | 968 | 968 | - | - | 1,171 | - | - | - | 217,579 | 10,157 | - |
| 2b.1.3.1 | Reactor Buildings | 324 | 192 | 29 | 38 | 50 | 87 | - | 248 | 968 | 968 | - | - | 1,171 | - | - | - | 217,579 | 10,157 | - |
| 2b.1.3.2 | Auxiliary Building | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - |

Table C
Clinton Power Station
DECON Decommissioning Cost Estimate
(Thousands of 2007 Dollars)

| Activity Index | Activity Description | Decom Cost | Removal Cost | Packaging Costs | Transport Costs | Off-Site Processing Costs | LLRW Disposal Costs | Other Costs | Total Contingency | Total Costs | NRC Lic. Term. Costs | Spent Fuel Management Costs | Site Restoration Costs | Processed Volume | | Burial Volumes | | Burial/Processed Wt., Lbs. | Craft Manhours | Utility and Contractor Manhours |
|--|---|------------|--------------|-----------------|-----------------|---------------------------|---------------------|-------------|-------------------|-------------|----------------------|-----------------------------|------------------------|------------------|------------------|------------------|------------------|----------------------------|----------------|---------------------------------|
| | | | | | | | | | | | | | | Cu. Feet | Class A Cu. Feet | Class B Cu. Feet | Class C Cu. Feet | | | |
| Decontamination of Site Buildings (continued) | | | | | | | | | | | | | | | | | | | | |
| 2b.1.3.3 | Control Building | 374 | 145 | 29 | 38 | 2 | 91 | - | 255 | 935 | 935 | - | - | 56 | - | - | - | 184,349 | 10,282 | - |
| 2b.1.3.4 | Diesel Generator Building | 108 | 38 | 8 | 10 | - | 25 | - | 72 | 263 | 263 | - | - | - | - | - | - | 49,962 | 2,911 | - |
| 2b.1.3.5 | Radiation Building | 1,269 | 575 | 105 | 140 | 45 | 330 | - | 899 | 3,364 | 3,364 | - | - | 1,067 | - | - | - | 701,151 | 36,363 | - |
| 2b.1.3.6 | Turbine Building | 1,135 | 605 | 97 | 129 | 117 | 298 | - | 840 | 3,221 | 3,221 | - | - | 2,735 | - | - | - | 699,469 | 34,324 | - |
| 2b.1.3 | Totals | 5,997 | 5,064 | 681 | 820 | 544 | 2,674 | - | 5,206 | 20,986 | 20,986 | - | - | 12,763 | - | - | - | 4,423,191 | 221,509 | - |
| 2b.1 | Subtotal Period 2b Activity Costs | 7,144 | 25,397 | 1,301 | 1,496 | 6,989 | 4,301 | - | 12,203 | 59,040 | 56,190 | - | 2,850 | 163,733 | - | - | - | 12,120,130 | 668,896 | - |
| Period 2b Collateral Costs | | | | | | | | | | | | | | | | | | | | |
| 2b.3.1 | Process liquid waste | 231 | - | 190 | 1,072 | - | 501 | - | 421 | 2,415 | 2,415 | - | - | - | - | - | - | 323,419 | 707 | - |
| 2b.3.2 | Small fuel allowance | - | 493 | - | - | - | - | 22,000 | 74 | 967 | 967 | - | - | - | - | - | - | - | - | - |
| 2b.3.3 | Spent Fuel Capital and Transfer | - | - | - | - | - | - | - | 3,300 | 25,300 | - | - | - | - | - | - | - | - | - | - |
| 2b.3 | Subtotal Period 2b Collateral Costs | 231 | 493 | 190 | 1,072 | - | 501 | 22,000 | 3,795 | 28,282 | 2,982 | - | - | - | - | - | - | 3,628 | - | 707 |
| Period 2b Period-Dependent Costs | | | | | | | | | | | | | | | | | | | | |
| 2b.4.1 | Decon supplies | 2,012 | - | - | - | - | - | - | 503 | 2,515 | 2,515 | - | - | - | - | - | - | - | - | - |
| 2b.4.2 | Insurance | - | - | - | - | - | - | 1,122 | 112 | 1,234 | 1,234 | - | - | - | - | - | - | - | - | - |
| 2b.4.3 | Property taxes | - | - | - | - | - | - | 2,212 | 221 | 2,433 | 2,433 | - | - | - | - | - | - | - | - | - |
| 2b.4.4 | Health physics supplies | - | 3,182 | - | - | - | - | - | 795 | 3,977 | 3,977 | - | - | - | - | - | - | - | - | - |
| 2b.4.5 | Heavy equipment rental | - | 3,742 | - | - | - | - | - | 561 | 4,304 | 4,304 | - | - | - | - | - | - | - | - | - |
| 2b.4.6 | Disposal of DAW generated | - | - | 255 | 105 | - | 670 | - | 209 | 1,240 | 1,240 | - | - | - | - | - | - | 12,008 | - | 366 |
| 2b.4.7 | Plant energy budget | - | - | - | - | - | - | 1,600 | 240 | 1,840 | 1,840 | - | - | - | - | - | - | - | - | - |
| 2b.4.8 | NRC Fees | - | - | - | - | - | - | 761 | 76 | 838 | 838 | - | - | - | - | - | - | - | - | - |
| 2b.4.9 | Emergency Planning Fees | - | - | - | - | - | - | 442 | 44 | 487 | 487 | - | - | - | - | - | - | - | - | - |
| 2b.4.10 | Site O&M Cost | - | - | - | - | - | - | 553 | 83 | 636 | 636 | - | - | - | - | - | - | - | - | - |
| 2b.4.11 | Spent Fuel Pool O&M | - | - | - | - | - | - | 1,634 | 245 | 1,879 | 1,879 | - | - | - | - | - | - | - | - | - |
| 2b.4.12 | Radwaste Processing Equipment/Services | - | - | - | - | - | - | 411 | 62 | 473 | 473 | - | - | - | - | - | - | - | - | - |
| 2b.4.13 | RSFSI Operating Costs | - | - | - | - | - | - | 182 | 27 | 209 | 209 | - | - | 209 | - | - | - | - | - | - |
| 2b.4.14 | Security Staff Cost | - | - | - | - | - | - | 11,044 | 1,657 | 12,701 | 12,701 | - | - | - | - | - | - | - | - | 292,094 |
| 2b.4.15 | DOC Staff Cost | - | - | - | - | - | - | 21,946 | 3,282 | 25,238 | 25,238 | - | - | - | - | - | - | - | - | 337,051 |
| 2b.4.16 | Utility Staff Cost | - | - | - | - | - | - | 39,471 | 5,921 | 45,391 | 45,391 | - | - | - | - | - | - | - | - | 625,623 |
| 2b.4 | Subtotal Period 2b Period-Dependent Costs | 2,012 | 6,924 | 255 | 105 | - | 670 | 81,379 | 14,049 | 105,394 | 102,820 | - | - | 2,574 | - | - | - | 240,639 | 366 | 1,254,709 |
| 2b.0 | TOTAL PERIOD 2b COST | 9,387 | 33,014 | 1,747 | 2,673 | 6,989 | 5,472 | 103,379 | 30,046 | 192,717 | 161,992 | - | 2,850 | 163,733 | - | - | - | 12,684,190 | 669,970 | 1,254,709 |
| PERIOD 2c - Decontamination Following Wet Fuel Storage | | | | | | | | | | | | | | | | | | | | |
| Period 2c Direct Decommissioning Activities | | | | | | | | | | | | | | | | | | | | |
| 2c.1.1 | Remove spent fuel racks | 500 | 45 | 92 | 104 | - | 572 | - | 429 | 1,740 | 1,740 | - | - | - | - | - | - | 544,292 | 1,017 | - |
| Disposal of Plant Systems | | | | | | | | | | | | | | | | | | | | |
| 2c.1.2.1 | Electrical - Contaminated | - | 1,014 | 16 | 23 | 385 | 20 | - | 314 | 1,722 | 1,722 | - | - | 7,867 | - | - | - | 338,266 | 21,336 | - |
| 2c.1.2.2 | Fire Protection - RCA | - | 616 | 15 | 2 | 385 | - | - | 217 | 1,255 | 1,255 | - | - | 9,018 | - | - | - | 306,214 | 12,406 | - |
| 2c.1.2.3 | Fuel Handling & Transfer | - | 24 | 2 | 2 | 7 | 9 | - | 10 | 55 | 55 | - | - | 173 | - | - | - | 15,919 | 321 | - |
| 2c.1.2.4 | Fuel Pool Cooling & Cleanup | - | 874 | 92 | 92 | 277 | 417 | - | 387 | 2,139 | 2,139 | - | - | 6,503 | - | - | - | 660,961 | 18,344 | - |
| 2c.1.2.5 | Fuel Support | - | 99 | 10 | 12 | 47 | 82 | - | 48 | 268 | 268 | - | - | 1,100 | - | - | - | 94,533 | 2,141 | - |
| 2c.1.2.6 | HVAC - Containment Building | - | 734 | 33 | 45 | 477 | 35 | - | 288 | 1,669 | 1,669 | - | - | 11,185 | - | - | - | 942,563 | 14,540 | - |
| 2c.1.2.7 | Portable Water | - | 111 | - | 14 | 32 | 68 | - | 141 | 733 | 733 | - | 12 | 758 | - | - | - | 95,460 | 9,361 | - |
| 2c.1.2.8 | Process Sampling | - | 489 | - | 19 | 14 | 659 | - | 1,406 | 7,842 | 7,842 | - | 12 | 36,603 | - | - | - | 2,113,916 | 78,881 | - |
| 2c.1.2 | Totals | - | 3,850 | 187 | 212 | 1,561 | 659 | - | 1,406 | 7,842 | 7,842 | - | 12 | 36,603 | - | - | - | 12,684,190 | 669,970 | 1,254,709 |

Table C
Clinton Power Station
DECON Decommissioning Cost Estimate
(Thousands of 2007 Dollars)

| Activity Index | Activity Description | Decon Cost | Removal Cost | Packaging Costs | Transport Costs | Off-Site Processing Costs | LLRW Disposal Costs | Other Costs | Total Contingency | Total Costs | NRC Lic. Term. Costs | Spent Fuel Management Costs | Site Restoration Costs | Processed Volume | | Burial Volumes | | Burial/Processed Wt., Lbs. | Craft Manhours | Utility and Contractor Manhours |
|--|--|------------|--------------|-----------------|-----------------|---------------------------|---------------------|-------------|-------------------|-------------|----------------------|-----------------------------|------------------------|------------------|------------------|------------------|------------------|----------------------------|----------------|---------------------------------|
| | | | | | | | | | | | | | | Cu. Feet | Class A Cu. Feet | Class B Cu. Feet | Class C Cu. Feet | | | |
| Decontamination of Site Buildings | | | | | | | | | | | | | | | | | | | | |
| 2c.1.3.1 | Fuel Building | 821 | 785 | 33 | 43 | 110 | 94 | - | 656 | 2,542 | 2,542 | - | - | 2,574 | 1,829 | - | - | 284,744 | 32,703 | - |
| 2c.1.3 | Totals | 821 | 785 | 33 | 43 | 110 | 94 | - | 656 | 2,542 | 2,542 | - | - | 2,574 | 1,829 | - | - | 284,744 | 32,703 | - |
| 2c.1.4 | Scaffolding in support of decommissioning | - | 766 | 12 | 3 | 35 | 4 | - | 199 | 1,020 | 1,020 | - | - | 742 | 46 | - | - | 37,544 | 17,685 | - |
| 2c.1 | Subtotal Period 2c: Activity Costs | 1,321 | 5,425 | 324 | 361 | 1,706 | 1,328 | - | 2,690 | 13,156 | 13,143 | - | 12 | 39,919 | 15,001 | - | - | 2,980,496 | 130,286 | - |
| Period 2c: Collateral Costs | | | | | | | | | | | | | | | | | | | | |
| 2c.3.1 | Process liquid waste | 121 | - | 44 | 240 | - | 77 | - | 120 | 603 | 603 | - | - | - | 833 | - | - | 49,965 | 162 | - |
| 2c.3.2 | Small tool allowance | - | 103 | - | - | - | - | - | 16 | 119 | 119 | - | - | - | - | - | - | - | - | - |
| 2c.3.3 | Decommissioning Equipment Disposition | - | - | 100 | 27 | 284 | 35 | - | 65 | 511 | 511 | - | - | 6,000 | 373 | - | - | 303,307 | 88 | - |
| 2c.3 | Subtotal Period 2c: Collateral Costs | 121 | 103 | 144 | 267 | 284 | 113 | - | 201 | 1,233 | 1,233 | - | - | 6,000 | 1,206 | - | - | 333,472 | 251 | - |
| Period 2c: Period-Dependent Costs | | | | | | | | | | | | | | | | | | | | |
| 2c.4.1 | Decon supplies | 223 | - | - | - | - | - | - | 56 | 278 | 278 | - | - | - | - | - | - | - | - | - |
| 2c.4.2 | Insurance | - | - | - | - | - | - | 429 | 43 | 472 | 472 | - | - | - | - | - | - | - | - | - |
| 2c.4.3 | Property taxes | - | - | - | - | - | - | 846 | 85 | 931 | 931 | - | - | - | - | - | - | - | - | - |
| 2c.4.4 | Health physics supplies | - | 747 | - | - | - | - | - | 187 | 934 | 934 | - | - | - | - | - | - | - | - | - |
| 2c.4.5 | Heavy equipment rental | - | 1,431 | - | - | - | - | - | 215 | 1,646 | 1,646 | - | - | - | - | - | - | - | - | - |
| 2c.4.6 | Disposal of DAW generated | - | - | 101 | 42 | - | 266 | - | 83 | 492 | 492 | - | - | 4,767 | - | - | 95,523 | 145 | - | - |
| 2c.4.7 | Plant energy budget | - | - | - | - | - | - | 326 | 49 | 375 | 375 | - | - | - | - | - | - | - | - | - |
| 2c.4.8 | NRC Fees | - | - | - | - | - | - | 291 | 29 | 320 | 320 | - | - | - | - | - | - | - | - | - |
| 2c.4.9 | Emergency Planning Fees | - | - | - | - | - | - | 169 | 17 | 186 | 186 | - | - | - | - | - | - | - | - | - |
| 2c.4.10 | Site O&M Cost | - | - | - | - | - | - | 211 | 32 | 243 | 243 | - | - | - | - | - | - | - | - | - |
| 2c.4.11 | Rawaste Processing Equipment/Services | - | - | - | - | - | - | 315 | 47 | 362 | 362 | - | - | - | - | - | - | - | - | - |
| 2c.4.12 | ISFSI Operating Costs | - | - | - | - | - | - | 70 | 10 | 80 | 80 | - | - | - | - | - | - | - | - | - |
| 2c.4.13 | Security Staff Cost | - | - | - | - | - | - | 2,220 | 333 | 2,553 | 2,553 | - | - | - | - | - | - | - | - | - |
| 2c.4.14 | DOC Staff Cost | - | - | - | - | - | - | 5,862 | 879 | 6,741 | 6,741 | - | - | - | - | - | - | - | - | - |
| 2c.4.15 | Utility Staff Cost | - | - | - | - | - | - | 11,138 | 1,671 | 12,809 | 12,809 | - | - | - | - | - | - | - | - | - |
| 2c.4 | Subtotal Period 2c: Period-Dependent Costs | 223 | 2,178 | 101 | 42 | - | 266 | 21,878 | 3,795 | 28,423 | 28,157 | - | - | 4,767 | - | - | 95,523 | 145 | - | - |
| 2c.0 | TOTAL PERIOD 2c: COST | 1,665 | 7,707 | 570 | 670 | 1,989 | 1,707 | 21,878 | 6,626 | 42,811 | 42,533 | - | 12 | 45,919 | 20,974 | - | 3,429,491 | 130,682 | 319,153 | - |
| PERIOD 2c - License Termination | | | | | | | | | | | | | | | | | | | | |
| Period 2c: Direct Decommissioning Activities | | | | | | | | | | | | | | | | | | | | |
| 2c.1.1 | ORISE confirmatory survey | - | - | - | - | - | - | 141 | 42 | 183 | 183 | - | - | - | - | - | - | - | - | - |
| 2c.1.2 | Terminate license | - | - | - | - | - | - | - | a | - | - | - | - | - | - | - | - | - | - | - |
| 2c.1 | Subtotal Period 2c: Activity Costs | - | - | - | - | - | - | 141 | 42 | 183 | 183 | - | - | - | - | - | - | - | - | - |
| Period 2c: Additional Costs | | | | | | | | | | | | | | | | | | | | |
| 2c.2.1 | Final Site Survey | - | - | - | - | - | - | 11,020 | 3,306 | 14,326 | 14,326 | - | - | - | - | - | - | - | - | - |
| 2c.2 | Subtotal Period 2c: Additional Costs | - | - | - | - | - | - | 11,020 | 3,306 | 14,326 | 14,326 | - | - | - | - | - | - | - | - | - |
| Period 2c: Collateral Costs | | | | | | | | | | | | | | | | | | | | |
| 2c.3.1 | DOC staff/retention expenses | - | - | - | - | - | - | 829 | 124 | 953 | 953 | - | - | - | - | - | - | - | - | - |
| 2c.3 | Subtotal Period 2c: Collateral Costs | - | - | - | - | - | - | 829 | 124 | 953 | 953 | - | - | - | - | - | - | - | - | - |
| Period 2c: Period-Dependent Costs | | | | | | | | | | | | | | | | | | | | |
| 2c.4.1 | Insurance | - | - | - | - | - | - | 350 | 35 | 385 | 385 | - | - | - | - | - | - | - | - | - |
| 2c.4.2 | Property taxes | - | - | - | - | - | - | 745 | 74 | 819 | 819 | - | - | - | - | - | - | - | - | - |
| 2c.4.3 | Health physics supplies | - | 1,034 | - | - | - | - | - | 298 | 1,292 | 1,292 | - | - | - | - | - | - | - | - | - |
| 2c.0 | TOTAL PERIOD 2c: COST | 1,665 | 7,707 | 570 | 670 | 1,989 | 1,707 | 21,878 | 6,626 | 42,811 | 42,533 | - | 12 | 45,919 | 20,974 | - | 3,429,491 | 130,682 | 319,153 | - |

Table C
Clinton Power Station
DECON Decommissioning Cost Estimate
(Thousands of 2007 Dollars)

| Activity Index | Activity Description | Decon Cost | Removal Cost | Packaging Costs | Transport Costs | Off-Site Processing Costs | LLRW Disposal Costs | Other Costs | Total Contingency | Total Costs | NRC Lic. Term. Costs | Spent Fuel Management Costs | Site Restoration Costs | Processed Volume Cu. Feet | Burial Volumes | | | Burial / Processed Wt., Lbs. | Craft Manhours | Utility and Contractor Manhours | |
|---|--|------------|--------------|-----------------|-----------------|---------------------------|---------------------|-------------|-------------------|-------------|----------------------|-----------------------------|------------------------|---------------------------|------------------|------------------|------------------|------------------------------|----------------|---------------------------------|-----------|
| | | | | | | | | | | | | | | | Class A Cu. Feet | Class B Cu. Feet | Class C Cu. Feet | | | | |
| Period 2a: Period-Dependent Costs (continued) | | | | | | | | | | | | | | | | | | | | | |
| 2c.4.4 | Disposal of DAW generated | - | - | 8 | 3 | - | 22 | - | 7 | 40 | 40 | - | - | - | - | - | - | - | - | - | - |
| 2c.4.5 | Plant energy budget | - | - | - | - | - | - | 144 | - | 165 | 165 | - | - | - | - | - | - | - | - | - | - |
| 2c.4.6 | NRC Fees | - | - | - | - | - | - | 256 | 26 | 282 | 282 | - | - | - | - | - | - | - | - | - | - |
| 2c.4.7 | Emergency Planning Fees | - | - | - | - | - | - | 149 | 15 | 164 | 164 | - | - | - | - | - | - | - | - | - | - |
| 2c.4.8 | Site O&M Cost | - | - | - | - | - | - | 186 | 28 | 214 | 214 | - | - | - | - | - | - | - | - | - | - |
| 2c.4.9 | ISFSI Operating Costs | - | - | - | - | - | - | 61 | 9 | 70 | 70 | - | - | - | - | - | - | - | - | - | - |
| 2c.4.10 | Security Staff Cost | - | - | - | - | - | - | 1,910 | 287 | 2,197 | 2,197 | - | - | - | - | - | - | - | - | - | - |
| 2c.4.11 | DOC Staff Cost | - | - | - | - | - | - | 3,905 | 586 | 4,490 | 4,490 | - | - | - | - | - | - | - | - | - | - |
| 2c.4.12 | Utility Staff Cost | - | - | - | - | - | - | 5,574 | 836 | 6,410 | 6,410 | - | - | - | - | - | - | - | - | - | - |
| 2c.4 | Subtotal Period 2a: Period-Dependent Costs | - | 1,034 | 8 | 3 | - | 22 | 13,280 | 2,182 | 16,294 | 16,294 | 234 | - | - | 389 | - | - | - | 7,792 | 12 | 187,291 |
| 2c.0 | TOTAL PERIOD 2a: COST | - | 1,034 | 8 | 3 | - | 22 | 25,269 | 5,635 | 31,891 | 31,756 | 234 | - | - | 389 | - | - | - | 7,792 | 230,152 | 187,291 |
| PERIOD 2 TOTALS | | 12,210 | 76,377 | 12,997 | 8,536 | 22,229 | 30,644 | 245,409 | 84,005 | 490,468 | 429,240 | 56,902 | 4,326 | 505,717 | 187,075 | 1,435 | 689 | - | 35,944,680 | 1,535,088 | 2,810,547 |
| PERIOD 3b - Site Restoration | | | | | | | | | | | | | | | | | | | | | |
| Period 3b: Direct Decommissioning Activities | | | | | | | | | | | | | | | | | | | | | |
| Demolition of Remaining Site Buildings | | | | | | | | | | | | | | | | | | | | | |
| 3b.1.1.1 | Reactor Building | - | 5,134 | - | - | - | - | - | 770 | 5,904 | - | - | 5,904 | - | - | - | - | - | - | - | 65,001 |
| 3b.1.1.2 | Auxiliary Building | - | 1,945 | - | - | - | - | - | 282 | 2,236 | - | - | 2,236 | - | - | - | - | - | - | - | 23,242 |
| 3b.1.1.3 | Circulating Water Screenhouse | - | 3,165 | - | - | - | - | - | 475 | 3,640 | - | - | 3,640 | - | - | - | - | - | - | - | 38,383 |
| 3b.1.1.4 | Control Building | - | 4,641 | - | - | - | - | - | 696 | 5,337 | - | - | 5,337 | - | - | - | - | - | - | - | 66,578 |
| 3b.1.1.5 | Diesel Generator Building | - | 1,618 | - | - | - | - | - | 243 | 1,860 | - | - | 1,860 | - | - | - | - | - | - | - | 20,234 |
| 3b.1.1.6 | Make-Up Water Pump House | - | 344 | - | - | - | - | - | 52 | 396 | - | - | 396 | - | - | - | - | - | - | - | 5,100 |
| 3b.1.1.7 | Miscellaneous Site Work | - | 1,504 | - | - | - | - | - | 226 | 1,729 | - | - | 1,729 | - | - | - | - | - | - | - | 21,227 |
| 3b.1.1.8 | Miscellaneous Structures | - | 2,442 | - | - | - | - | - | 396 | 2,808 | - | - | 2,808 | - | - | - | - | - | - | - | 44,561 |
| 3b.1.1.9 | Radiation Building | - | 4,302 | - | - | - | - | - | 675 | 5,177 | - | - | 5,177 | - | - | - | - | - | - | - | 58,440 |
| 3b.1.1.10 | Service Building | - | 353 | - | - | - | - | - | 53 | 406 | - | - | 406 | - | - | - | - | - | - | - | 5,585 |
| 3b.1.1.11 | Transformer and Tank Pads | - | 147 | - | - | - | - | - | 22 | 169 | - | - | 169 | - | - | - | - | - | - | - | 2,463 |
| 3b.1.1.12 | Turbine Building | - | 4,693 | - | - | - | - | - | 704 | 5,397 | - | - | 5,397 | - | - | - | - | - | - | - | 63,415 |
| 3b.1.1.13 | Turbine Pedestal | - | 1,080 | - | - | - | - | - | 162 | 1,243 | - | - | 1,243 | - | - | - | - | - | - | - | 12,474 |
| 3b.1.1.14 | Fuel Building | - | 2,139 | - | - | - | - | - | 324 | 2,463 | - | - | 2,463 | - | - | - | - | - | - | - | 26,720 |
| 3b.1.1 | Totals | - | 33,727 | - | - | - | - | - | 5,059 | 38,786 | - | - | 38,786 | - | - | - | - | - | - | - | 443,422 |
| Site Closeout Activities | | | | | | | | | | | | | | | | | | | | | |
| 3b.1.2 | Backfill Site | - | 57 | - | - | - | - | - | 9 | 66 | - | - | 66 | - | - | - | - | - | - | - | 201 |
| 3b.1.3 | Grate & landscape site | - | 1,408 | - | - | - | - | - | 211 | 1,619 | - | - | 1,619 | - | - | - | - | - | - | - | 4,449 |
| 3b.1.4 | Final report to NRC | - | - | - | - | - | - | 141 | 21 | 163 | 163 | - | - | - | - | - | - | - | - | - | 1,560 |
| 3b.1 | Subtotal Period 3b: Activity Costs | - | 35,192 | - | - | - | - | 141 | 5,300 | 40,634 | 163 | - | 40,471 | - | - | - | - | - | - | - | 448,071 |
| Period 3b: Additional Costs | | | | | | | | | | | | | | | | | | | | | |
| 3b.2.1 | Concrete Crushing | - | 1,281 | - | - | - | - | - | 193 | 1,482 | - | - | 1,482 | - | - | - | - | - | - | - | 7,355 |
| 3b.2.2 | Screenhouse Cofferdam | - | 934 | - | - | - | - | - | 140 | 1,074 | - | - | 1,074 | - | - | - | - | - | - | - | 10,159 |
| 3b.2.3 | Discharge Frame Backfill | - | 3,741 | - | - | - | - | - | 561 | 4,302 | - | - | 4,302 | - | - | - | - | - | - | - | 23,931 |
| 3b.2.4 | Unit 2 Excavation Backfill | - | 1,226 | - | - | - | - | - | 154 | 1,410 | - | - | 1,410 | - | - | - | - | - | - | - | 13,128 |
| 3b.2 | Subtotal Period 3b: Additional Costs | - | 7,183 | - | - | - | - | - | 1,079 | 8,269 | - | - | 8,269 | - | - | - | - | - | - | - | 94,573 |
| Period 3b: Collateral Costs | | | | | | | | | | | | | | | | | | | | | |
| 3b.3.1 | Small tool allowance | - | 386 | - | - | - | - | - | 58 | 444 | - | - | 444 | - | - | - | - | - | - | - | - |
| 3b.3.2 | Spent Fuel Capital and Transfer | - | - | - | - | - | - | 191 | 29 | 220 | - | 220 | - | - | - | - | - | - | - | - | - |

Table C
Clinton Power Station
DECON Decommissioning Cost Estimate
(Thousands of 2007 Dollars)

| Activity Index | Activity Description | Decon Cost | Removal Cost | Packaging Costs | Transport Costs | Off-Site Processing Costs | LLRW Disposal Costs | Other Costs | Total Contingency | Total Costs | NRC Lic. Term. Costs | Spent Fuel Management Costs | Site Restoration Costs | Processed Volume | | | Burial Volumes | | | Burial/Processed Wt., Lbs. | Craft Manhours | Utility and Contractor Manhours |
|---|---|------------|--------------|-----------------|-----------------|---------------------------|---------------------|-------------|-------------------|-------------|----------------------|-----------------------------|------------------------|------------------|----------|----------|------------------|------------------|------------------|----------------------------|----------------|---------------------------------|
| | | | | | | | | | | | | | | Cu. Feet | Cu. Feet | Cu. Feet | Class A Cu. Feet | Class B Cu. Feet | Class C Cu. Feet | | | |
| 3b.3 | Subtotal Period 3b Collateral Costs | - | 386 | - | - | - | - | 191 | 87 | 664 | - | 220 | 444 | - | - | - | - | - | - | - | - | - |
| Period 3b Period-Dependent Costs | | | | | | | | | | | | | | | | | | | | | | |
| 3b.4.1 | Insurance | - | - | - | - | - | - | 1,063 | 106 | 1,169 | - | 1,169 | - | - | - | - | - | - | - | - | - | - |
| 3b.4.2 | Property taxes | - | - | - | - | - | - | 2,264 | 226 | 2,491 | 0 | 2,092 | 398 | - | - | - | - | - | - | - | - | - |
| 3b.4.3 | Heavy equipment rental | - | 5,246 | - | - | - | - | - | 787 | 6,033 | - | - | 6,033 | - | - | - | - | - | - | - | - | - |
| 3b.4.4 | Plant energy budget | - | - | - | - | - | - | - | 33 | 251 | - | - | 251 | - | - | - | - | - | - | - | - | - |
| 3b.4.5 | NRC ISFSI Fees | - | - | - | - | - | - | 489 | 49 | 537 | - | 537 | - | - | - | - | - | - | - | - | - | - |
| 3b.4.6 | Emergency Planning Fees | - | - | - | - | - | - | 453 | 45 | 498 | - | 498 | - | - | - | - | - | - | - | - | - | - |
| 3b.4.7 | ISFSI Operating Costs | - | - | - | - | - | - | 186 | 28 | 214 | - | 214 | - | - | - | - | - | - | - | - | - | - |
| 3b.4.8 | Site O&M Cost | - | - | - | - | - | - | 566 | 85 | 651 | - | 651 | - | - | - | - | - | - | - | - | - | - |
| 3b.4.9 | Security Staff Cost | - | - | - | - | - | - | 5,808 | 871 | 6,679 | - | 5,544 | 1,136 | - | - | - | - | - | - | - | - | 153,586 |
| 3b.4.10 | DOC Staff Cost | - | - | - | - | - | - | 11,330 | 1,699 | 13,029 | - | - | 13,029 | - | - | - | - | - | - | - | - | 160,674 |
| 3b.4.11 | Utility Staff Cost | - | - | - | - | - | - | 5,584 | 1,288 | 9,872 | 0 | 2,369 | 7,503 | - | - | - | - | - | - | - | - | 128,776 |
| 3b.4 | Subtotal Period 3b Period-Dependent Costs | - | 5,246 | - | - | - | - | 30,961 | 5,218 | 41,425 | 0 | 12,424 | 29,001 | - | - | - | - | - | - | - | - | 443,006 |
| 3b.0 | TOTAL PERIOD 3b COST | - | 48,007 | - | - | - | - | 31,302 | 11,683 | 90,991 | 163 | 12,644 | 78,184 | - | - | - | - | - | - | - | - | 502,644 |
| PERIOD 3c - Fuel Storage Operations/Shipping | | | | | | | | | | | | | | | | | | | | | | |
| Period 3c Direct Decommissioning Activities | | | | | | | | | | | | | | | | | | | | | | |
| Period 3c Collateral Costs | | | | | | | | | | | | | | | | | | | | | | |
| 3c.3.1 | Spent Fuel Capital and Transfer | - | - | - | - | - | - | 7,809 | 1,171 | 8,980 | - | 8,980 | - | - | - | - | - | - | - | - | - | - |
| 3c.3 | Subtotal Period 3c Collateral Costs | - | - | - | - | - | - | 7,809 | 1,171 | 8,980 | - | 8,980 | - | - | - | - | - | - | - | - | - | - |
| Period 3c Period-Dependent Costs | | | | | | | | | | | | | | | | | | | | | | |
| 3c.4.1 | Insurance | - | - | - | - | - | - | 1,342 | 134 | 1,476 | - | 1,476 | - | - | - | - | - | - | - | - | - | - |
| 3c.4.2 | Property taxes | - | - | - | - | - | - | 2,398 | 240 | 2,637 | - | 2,637 | - | - | - | - | - | - | - | - | - | - |
| 3c.4.3 | Plant energy budget | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| 3c.4.4 | NRC ISFSI Fees | - | - | - | - | - | - | 617 | 62 | 679 | - | 679 | - | - | - | - | - | - | - | - | - | - |
| 3c.4.5 | Emergency Planning Fees | - | - | - | - | - | - | 572 | 57 | 629 | - | 629 | - | - | - | - | - | - | - | - | - | - |
| 3c.4.6 | Site O&M Cost | - | - | - | - | - | - | 715 | 107 | 822 | - | 822 | - | - | - | - | - | - | - | - | - | - |
| 3c.4.7 | ISFSI Operating Costs | - | - | - | - | - | - | 235 | 35 | 270 | - | 270 | - | - | - | - | - | - | - | - | - | - |
| 3c.4.8 | Security Staff Cost | - | - | - | - | - | - | 6,091 | 914 | 7,005 | - | 7,005 | - | - | - | - | - | - | - | - | - | 161,074 |
| 3c.4.9 | Utility Staff Cost | - | - | - | - | - | - | 2,617 | 393 | 3,010 | - | 3,010 | - | - | - | - | - | - | - | - | - | 40,269 |
| 3c.4 | Subtotal Period 3c Period-Dependent Costs | - | - | - | - | - | - | 14,586 | 1,942 | 16,328 | - | 16,328 | - | - | - | - | - | - | - | - | - | 201,343 |
| 3c.0 | TOTAL PERIOD 3c COST | - | - | - | - | - | - | 22,395 | 3,113 | 25,508 | - | 25,508 | - | - | - | - | - | - | - | - | - | 201,343 |
| PERIOD 3d - GTCC shipping | | | | | | | | | | | | | | | | | | | | | | |
| Period 3d Direct Decommissioning Activities | | | | | | | | | | | | | | | | | | | | | | |
| Nuclear Steam Supply System Removal | | | | | | | | | | | | | | | | | | | | | | |
| 3d.1.1.1 | Vessel & Internals GTCC Disposal | - | - | 375 | - | - | - | 8,132 | 1,260 | 9,787 | 9,787 | - | - | - | - | - | - | - | - | - | - | 86,500 |
| 3d.1.1 | Totals | - | - | 375 | - | - | - | 8,132 | 1,260 | 9,787 | 9,787 | - | - | - | - | - | - | - | - | - | - | 86,500 |
| 3d.1 | Subtotal Period 3d Activity Costs | - | - | 375 | - | - | - | 8,132 | 1,260 | 9,787 | 9,787 | - | - | - | - | - | - | - | - | - | - | 86,500 |
| Period 3d Period-Dependent Costs | | | | | | | | | | | | | | | | | | | | | | |
| 3d.4.1 | Insurance | - | - | - | - | - | - | 21 | 2 | 23 | - | 23 | - | - | - | - | - | - | - | - | - | - |
| 3d.4.2 | Property taxes | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| 3d.4.3 | Plant energy budget | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - |

Table C
Clinton Power Station
DECON Decommissioning Cost Estimate
(Thousands of 2007 Dollars)

| Activity Index | Activity Description | Decon Cost | Removal Cost | Packaging Costs | Transport Costs | Processing Costs | Off-Site Processing Costs | LLRW Disposal Costs | Other Costs | Total Contingency | Total Costs | NRC Lic. Term. Costs | Spent Fuel Management Costs | Site Restoration Costs | Processed Volume | | Burial Volumes | | Burial/Processed Wt., Lbs. | Craft Manhours | Utility and Contractor Manhours | |
|--|---|------------|--------------|-----------------|-----------------|------------------|---------------------------|---------------------|-------------|-------------------|-------------|----------------------|-----------------------------|------------------------|------------------|---------|----------------|---------|----------------------------|----------------|---------------------------------|----------|
| | | | | | | | | | | | | | | | Cu. Feet | Class C | Class A | Class B | | | | Cu. Feet |
| Period 3d Period-Dependent Costs (continued) | | | | | | | | | | | | | | | | | | | | | | |
| 3d4.4 | NRC ISFSI Fees | - | - | - | - | - | - | - | 9 | 1 | 10 | - | - | - | - | - | - | - | - | - | - | |
| 3d4.5 | Emergency Planning Fees | - | - | - | - | - | - | - | 9 | 1 | 10 | - | - | - | - | - | - | - | - | - | - | |
| 3d4.6 | Site O&M Cost | - | - | - | - | - | - | - | 11 | 2 | 13 | - | - | - | - | - | - | - | - | - | - | |
| 3d4.7 | ISFSI Operating Costs | - | - | - | - | - | - | - | 4 | 1 | 4 | - | - | - | - | - | - | - | - | - | - | |
| 3d4.8 | Security Staff Cost | - | - | - | - | - | - | - | 93 | 14 | 107 | - | - | - | - | - | - | - | - | - | 2,469 | |
| 3d4.9 | Utility Staff Cost | - | - | - | - | - | - | - | 40 | 6 | 46 | - | - | - | - | - | - | - | - | - | 617 | |
| 3d4 | Subtotal Period 3d Period-Dependent Costs | - | - | - | - | - | - | - | 187 | 26 | 213 | - | - | - | - | - | - | - | - | - | 3,086 | |
| 3d0 | TOTAL PERIOD 3d COST | - | - | 375 | - | - | - | 8,152 | 187 | 1,286 | 10,000 | 9,787 | - | 213 | - | - | - | - | 482 | 86,500 | - | 3,086 |
| PERIOD 3e - ISFSI Decontamination | | | | | | | | | | | | | | | | | | | | | | |
| Period 3e Direct Decommissioning Activities | | | | | | | | | | | | | | | | | | | | | | |
| Period 3e Additional Costs | | | | | | | | | | | | | | | | | | | | | | |
| 3e2.1 | ISFSI License Termination | 724 | - | 3 | 85 | - | - | - | 1,170 | 423 | 2,617 | - | 2,617 | - | - | - | - | - | - | 510,109 | 11,226 | 2,560 |
| 3e2 | Subtotal Period 3e Additional Costs | 724 | - | 3 | 85 | - | - | - | 1,170 | 423 | 2,617 | - | 2,617 | - | - | - | - | - | - | 510,109 | 11,226 | 2,560 |
| Period 3e Collateral Costs | | | | | | | | | | | | | | | | | | | | | | |
| 3e3.1 | Small tool allowance | 7 | - | - | - | - | - | - | - | 1 | 8 | - | 8 | - | - | - | - | - | - | - | - | - |
| 3e3 | Subtotal Period 3e Collateral Costs | 7 | - | - | - | - | - | - | - | 1 | 8 | - | 8 | - | - | - | - | - | - | - | - | - |
| Period 3e Period-Dependent Costs | | | | | | | | | | | | | | | | | | | | | | |
| 3e4.1 | Insurance | - | - | - | - | - | - | - | 158 | 16 | 174 | - | 174 | - | - | - | - | - | - | - | - | - |
| 3e4.2 | Property taxes | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| 3e4.3 | Heavy equipment rental | 225 | - | - | - | - | - | - | - | 34 | 259 | - | 259 | - | - | - | - | - | - | - | - | - |
| 3e4.4 | Plant energy budget | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| 3e4.5 | Site O&M Cost | - | - | - | - | - | - | - | 84 | 13 | 97 | - | 97 | - | - | - | - | - | - | - | - | - |
| 3e4.6 | Security Staff Cost | - | - | - | - | - | - | - | 193 | 29 | 222 | - | 222 | - | - | - | - | - | - | - | - | 5,096 |
| 3e4.7 | Utility Staff Cost | 225 | - | - | - | - | - | - | 258 | 39 | 297 | - | 297 | - | - | - | - | - | - | - | - | 3,866 |
| 3e4 | Subtotal Period 3e Period-Dependent Costs | 225 | - | - | - | - | - | - | 693 | 130 | 1,048 | - | 1,048 | - | - | - | - | - | - | - | - | 8,961 |
| 3e0 | TOTAL PERIOD 3e COST | 955 | - | 3 | 85 | - | - | 214 | 1,862 | 553 | 3,672 | - | 3,672 | - | 4,257 | - | - | - | 510,109 | 11,226 | - | 11,521 |
| PERIOD 3f - ISFSI Site Restoration | | | | | | | | | | | | | | | | | | | | | | |
| Period 3f Direct Decommissioning Activities | | | | | | | | | | | | | | | | | | | | | | |
| Period 3f Additional Costs | | | | | | | | | | | | | | | | | | | | | | |
| 3f2.1 | ISFSI Site Restoration | 1,186 | - | - | - | - | - | - | 42 | 184 | 1,412 | - | 1,412 | - | - | - | - | - | - | - | 3,120 | 160 |
| 3f2 | Subtotal Period 3f Additional Costs | 1,186 | - | - | - | - | - | - | 42 | 184 | 1,412 | - | 1,412 | - | - | - | - | - | - | - | 3,120 | 160 |
| Period 3f Collateral Costs | | | | | | | | | | | | | | | | | | | | | | |
| 3f3.1 | Small tool allowance | 2 | - | - | - | - | - | - | - | 0 | 3 | - | 3 | - | - | - | - | - | - | - | - | - |
| 3f3 | Subtotal Period 3f Collateral Costs | 2 | - | - | - | - | - | - | - | 0 | 3 | - | 3 | - | - | - | - | - | - | - | - | - |
| Period 3f Period-Dependent Costs | | | | | | | | | | | | | | | | | | | | | | |
| 3f4.1 | Insurance | - | - | - | - | - | - | - | 16 | 2 | 17 | - | 17 | - | - | - | - | - | - | - | - | - |
| 3f4.2 | Property taxes | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| 3f4.3 | Heavy equipment rental | 73 | - | - | - | - | - | - | - | 11 | 84 | - | 84 | - | - | - | - | - | - | - | - | - |
| 3f4.4 | Plant energy budget | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| 3f4.5 | Site O&M Cost | - | - | - | - | - | - | - | - | 6 | 46 | - | 46 | - | - | - | - | - | - | - | - | - |

Table C
Clinton Power Station
DECON Decommissioning Cost Estimate
(Thousands of 2007 Dollars)

| Activity Index | Activity Description | Decon Cost | Removal Cost | Packaging Costs | Transport Costs | On-Site Processing Costs | LLRW Disposal Costs | Other Costs | Total Contingency | Total Costs | NRC Lic. Term. Costs | Spent Fuel Management Costs | Site Restoration Costs | Processed Volume | | Burial Volumes | | Burial/Processed Wt., Lbs. | Craft Manhours | Utility and Contractor Manhours |
|---|--|------------|--------------|-----------------|-----------------|--------------------------|---------------------|-------------|-------------------|-------------|----------------------|-----------------------------|------------------------|------------------|------------|------------------|------------------|----------------------------|----------------|---------------------------------|
| | | | | | | | | | | | | | | Cu. Feet | Cu. Feet | Class A Cu. Feet | Class B Cu. Feet | | | |
| Period 3 rd Period-Dependent Costs (continued) | | | | | | | | | | | | | | | | | | | | |
| 33.4.6 | Security Staff Cost | - | - | - | - | - | - | 91 | 14 | 104 | - | 104 | - | - | - | - | - | - | - | 2,403 |
| 33.4.7 | Utility Staff Cost | - | - | - | - | - | - | 96 | 14 | 111 | - | 111 | - | - | - | - | - | - | - | 1,491 |
| 33.4 | Subtotal Period 3 rd Period-Dependent Costs | - | 73 | - | - | - | - | 243 | 47 | 363 | - | 363 | - | - | - | - | - | - | - | 3,894 |
| 33.0 | TOTAL PERIOD 3 rd COST | - | 1,262 | - | - | - | - | 285 | 231 | 1,777 | - | 1,777 | - | - | - | - | - | - | 3,120 | 4,054 |
| PERIOD 3 TOTALS | | - | 50,224 | 378 | 85 | - | 8,365 | 56,030 | 16,867 | 131,948 | 9,949 | 43,814 | 78,184 | - | 482 | 596,609 | 516,990 | 664,600 | - | 664,600 |
| TOTAL COST TO DECOMMISSION | | 14,680 | 128,652 | 13,444 | 8,914 | 22,229 | 41,768 | 434,071 | 122,323 | 786,061 | 547,591 | 155,245 | 85,225 | 482 | 36,744,250 | 2,053,353 | 4,455,077 | - | - | - |

| | | |
|--|-----------|---------------------------|
| TOTAL COST TO DECOMMISSION WITH 18.43% CONTINGENCY: | \$786,061 | thousands of 2007 dollars |
| TOTAL NRC LICENSE TERMINATION COST IS 69.66% OR: | \$547,591 | thousands of 2007 dollars |
| SPENT FUEL MANAGEMENT COST IS 19.75% OR: | \$155,245 | thousands of 2007 dollars |
| NON-NUCLEAR DEMOLITION COST IS 10.59% OR: | \$83,225 | thousands of 2007 dollars |
| TOTAL LOW-LEVEL RADIOACTIVE WASTE BURIED (EXCLUDING GTCC): | 197,021 | cubic feet |
| TOTAL GREATER THAN CLASS C RADWASTE VOLUME GENERATED: | 482 | cubic feet |
| TOTAL SCRAP METAL REMOVED: | 75,356 | tons |
| TOTAL CRAFT LABOR REQUIREMENTS: | 2,053,353 | man-hours |

End Notes:
 a/a - Indicates that this activity not charged as decommissioning expense.
 a - Indicates that this activity performed by decommissioning staff.
 0 - Indicates that this value is less than 0.5 but is non-zero.
 a cell containing " - " indicates a zero value

APPENDIX D
DETAILED COST ANALYSIS
DELAYED DECON

Table D
Clinton Power Station
Delayed DECON Decommissioning Cost Estimate
(Thousands of 2007 Dollars)

| Activity Index | Activity Description | Decon Cost | Removal Cost | Packaging Costs | Transport Costs | Off-Site Processing Costs | LLRW Disposal Costs | Other Costs | Total Contingency | Total Costs | NRC Lic. Term. Costs | Spent Fuel Management Costs | Site Restoration Costs | Processed Volume Cu. Feet | Burial Volumes | | | Burial / Processed Wt. Lbs. | Utility and Contractor Manhours | |
|--|--|------------|--------------|-----------------|-----------------|---------------------------|---------------------|-------------|-------------------|-------------|----------------------|-----------------------------|------------------------|---------------------------|------------------|------------------|------------------|-----------------------------|---------------------------------|---------|
| | | | | | | | | | | | | | | | Class A Cu. Feet | Class B Cu. Feet | Class C Cu. Feet | | | |
| PERIOD 1a - Shutdown through Transition | | | | | | | | | | | | | | | | | | | | |
| Period 1a Direct Decommissioning Activities | | | | | | | | | | | | | | | | | | | | |
| 1a.1.1 | SAFSTOR site characterization survey | - | - | - | - | - | - | 363 | 109 | 471 | 471 | - | - | - | - | - | - | - | - | - |
| 1a.1.2 | Prepare preliminary decommissioning cost | - | - | - | - | - | - | 118 | 18 | 136 | 136 | - | - | - | - | - | - | - | - | 1,300 |
| 1a.1.3 | Notification of Cessation of Operations | - | - | - | - | - | - | n/a | - | - | - | - | - | - | - | - | - | - | - | - |
| 1a.1.4 | Remove fuel & source material | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| 1a.1.5 | Notification of Permanent Defueling | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| 1a.1.6 | Deactivate plant systems & process waste | - | - | - | - | - | - | 181 | 27 | 209 | 209 | - | - | - | - | - | - | - | - | 2,000 |
| 1a.1.7 | Prepare and submit PSDAR | - | - | - | - | - | - | 118 | 18 | 136 | 136 | - | - | - | - | - | - | - | - | 1,300 |
| 1a.1.8 | Review plant dwgs & specs. | - | - | - | - | - | - | - | a | - | - | - | - | - | - | - | - | - | - | - |
| 1a.1.9 | Perform detailed rad survey | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| 1a.1.10 | Estimate by-product inventory | - | - | - | - | - | - | 91 | 14 | 104 | 104 | - | - | - | - | - | - | - | - | 1,000 |
| 1a.1.11 | End product description | - | - | - | - | - | - | 91 | 14 | 104 | 104 | - | - | - | - | - | - | - | - | 1,000 |
| 1a.1.12 | Detailed by-product inventory | - | - | - | - | - | - | 136 | 20 | 156 | 156 | - | - | - | - | - | - | - | - | 1,500 |
| 1a.1.13 | Define major work sequence | - | - | - | - | - | - | 91 | 14 | 104 | 104 | - | - | - | - | - | - | - | - | 1,000 |
| 1a.1.14 | Perform SER and EA | - | - | - | - | - | - | 281 | 42 | 323 | 323 | - | - | - | - | - | - | - | - | 3,100 |
| 1a.1.15 | Perform Site-Specific Cost Study | - | - | - | - | - | - | 454 | 68 | 522 | 522 | - | - | - | - | - | - | - | - | 5,000 |
| Activity Specifications | | | | | | | | | | | | | | | | | | | | |
| 1a.1.16.1 | Prepare plant and facilities for SAFSTOR | - | - | - | - | - | - | 446 | 67 | 513 | 513 | - | - | - | - | - | - | - | - | 4,920 |
| 1a.1.16.2 | Plant systems | - | - | - | - | - | - | 378 | 57 | 435 | 435 | - | - | - | - | - | - | - | - | 4,167 |
| 1a.1.16.3 | Plant structures and buildings | - | - | - | - | - | - | 283 | 42 | 325 | 325 | - | - | - | - | - | - | - | - | 3,120 |
| 1a.1.16.4 | Waste management | - | - | - | - | - | - | 181 | 27 | 209 | 209 | - | - | - | - | - | - | - | - | 2,000 |
| 1a.1.16.5 | Facility and site dormancy | - | - | - | - | - | - | 181 | 27 | 209 | 209 | - | - | - | - | - | - | - | - | 2,000 |
| 1a.1.16 | Total | - | - | - | - | - | - | 1,470 | 220 | 1,690 | 1,690 | - | - | - | - | - | - | - | - | 16,207 |
| Detailed Work Procedures | | | | | | | | | | | | | | | | | | | | |
| 1a.1.17.1 | Plant systems | - | - | - | - | - | - | 107 | 16 | 123 | 123 | - | - | - | - | - | - | - | - | 1,183 |
| 1a.1.17.2 | Facility closeout & dormancy | - | - | - | - | - | - | 109 | 16 | 125 | 125 | - | - | - | - | - | - | - | - | 1,200 |
| 1a.1.17 | Total | - | - | - | - | - | - | 216 | 32 | 249 | 249 | - | - | - | - | - | - | - | - | 2,383 |
| 1a.1.18 | Procure vacuum drying system | - | - | - | - | - | - | 9 | 1 | 10 | 10 | - | - | - | - | - | - | - | - | 100 |
| 1a.1.19 | Drain/de-energize non-cont. systems | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| 1a.1.20 | Drain & dry NSSS | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| 1a.1.21 | Drain/de-energize contaminated systems | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| 1a.1.22 | Decon/secure contaminated systems | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| 1a.1 | Subtotal Period 1a Activity Costs | - | - | - | - | - | - | 3,618 | 597 | 4,215 | 4,215 | - | - | - | - | - | - | - | - | 35,890 |
| Period 1a Period-Dependent Costs | | | | | | | | | | | | | | | | | | | | |
| 1a.4.1 | Insurance | - | - | - | - | - | - | 1,320 | 132 | 1,452 | 1,452 | - | - | - | - | - | - | - | - | - |
| 1a.4.2 | Property taxes | - | - | - | - | - | - | 6,312 | 631 | 6,943 | 6,943 | - | - | - | - | - | - | - | - | - |
| 1a.4.3 | Health physics supplies | - | - | - | - | - | - | - | 94 | 471 | 471 | - | - | - | - | - | - | - | - | - |
| 1a.4.4 | Heavy equipment rental | 377 | - | - | - | - | - | - | 52 | 401 | 401 | - | - | - | - | - | - | - | - | - |
| 1a.4.5 | Disposal of DAW generated | 349 | - | - | 6 | - | 38 | - | 12 | 70 | 70 | - | - | - | - | - | - | - | - | 21 |
| 1a.4.6 | Plant energy budget | - | - | - | - | - | - | 964 | 145 | 1,108 | 1,108 | - | - | - | - | - | - | - | - | - |
| 1a.4.7 | NRC Fees | - | - | - | - | - | - | 238 | 26 | 264 | 264 | - | - | - | - | - | - | - | - | - |
| 1a.4.8 | Emergency Planning Fees | - | - | - | - | - | - | 450 | 45 | 495 | 495 | - | - | - | - | - | - | - | - | - |
| 1a.4.9 | Site O&M Cost | - | - | - | - | - | - | 250 | 37 | 287 | 287 | - | - | - | - | - | - | - | - | - |
| 1a.4.10 | Spent Fuel Pool O&M | - | - | - | - | - | - | 738 | 111 | 849 | 849 | - | - | - | - | - | - | - | - | - |
| 1a.4.11 | Security Staff Cost | - | - | - | - | - | - | 5,955 | 893 | 6,848 | 6,848 | - | - | - | - | - | - | - | - | 157,471 |
| 1a.4.12 | Utility Staff Cost | - | - | - | - | - | - | 26,183 | 3,927 | 30,110 | 30,110 | - | - | - | - | - | - | - | - | 423,400 |

Table D
Clinton Power Station
Delayed DECON Decommissioning Cost Estimate
(Thousands of 2007 Dollars)

| Activity Index | Activity Description | Decon Cost | Removal Cost | Packaging Costs | Transport Costs | Off-Site Processing Costs | LLRW Disposal Costs | Other Costs | Total Contingency | Total Lc. Term. Costs | NRC Lc. Term. Costs | Spent Fuel Management Costs | Site Restoration Costs | Processed Volume Cu. Feet | Burial Volumes | | Burial / Processed Wt. Lbs. | Craft Manhours | Utility and Contractor Manhours |
|---|---|------------|--------------|-----------------|-----------------|---------------------------|---------------------|-------------|-------------------|-----------------------|---------------------|-----------------------------|------------------------|---------------------------|------------------|------------------|-----------------------------|----------------|---------------------------------|
| | | | | | | | | | | | | | | | Class A Cu. Feet | Class B Cu. Feet | | | |
| 1a.4 | Subtotal Period 1a Period-Dependent Costs | - | 726 | 14 | 6 | - | 38 | 42,429 | 6,106 | 49,319 | 47,975 | 1,343 | - | - | - | - | 13,531 | 21 | 580,871 |
| 1a.0 | TOTAL PERIOD 1a COST | - | 726 | 14 | 6 | - | 38 | 46,047 | 6,703 | 53,533 | 52,190 | 1,343 | - | - | - | - | 13,531 | 21 | 616,761 |
| PERIOD 1b - SAFSTOR Limited DECON Activities | | | | | | | | | | | | | | | | | | | |
| Period 1b Direct Decommissioning Activities | | | | | | | | | | | | | | | | | | | |
| Decontamination of Site Buildings | | | | | | | | | | | | | | | | | | | |
| 1b.1.1.1 | Reactor Building | 2,771 | - | - | - | - | - | - | 1,385 | 4,156 | 4,156 | - | - | - | - | - | - | - | - |
| 1b.1.1.2 | Auxiliary Building | 305 | - | - | - | - | - | - | 153 | 458 | 458 | - | - | - | - | - | - | - | 56,016 |
| 1b.1.1.3 | Control Building | 353 | - | - | - | - | - | - | 177 | 530 | 530 | - | - | - | - | - | - | - | 6,485 |
| 1b.1.1.4 | Diesel Generator Building | 103 | - | - | - | - | - | - | 51 | 154 | 154 | - | - | - | - | - | - | - | 7,503 |
| 1b.1.1.5 | Radiation Building | 1,185 | - | - | - | - | - | - | 597 | 1,782 | 1,782 | - | - | - | - | - | - | - | 2,182 |
| 1b.1.1.6 | Turbine Building | 1,069 | - | - | - | - | - | - | 534 | 1,603 | 1,603 | - | - | - | - | - | - | - | 25,369 |
| 1b.1.1.7 | Fuel Building | 800 | - | - | - | - | - | - | 400 | 1,199 | 1,199 | - | - | - | - | - | - | - | 22,689 |
| 1b.1.1 | Totals | 6,595 | - | - | - | - | - | - | 3,298 | 9,893 | 9,893 | - | - | - | - | - | - | - | 16,275 |
| 1b.1 | Subtotal Period 1b Activity Costs | 6,595 | - | - | - | - | - | - | 3,298 | 9,893 | 9,893 | - | - | - | - | - | - | - | 136,519 |
| Period 1b Additional Costs | | | | | | | | | | | | | | | | | | | |
| 1b.2.1 | Spent Fuel Pool Isolation | - | - | - | - | - | - | 9,133 | 1,370 | 10,503 | 10,503 | - | - | - | - | - | - | - | - |
| 1b.2 | Subtotal Period 1b Additional Costs | - | - | - | - | - | - | 9,133 | 1,370 | 10,503 | 10,503 | - | - | - | - | - | - | - | - |
| Period 1b Collateral Costs | | | | | | | | | | | | | | | | | | | |
| 1b.3.1 | Decon equipment | 726 | - | - | - | - | - | - | 109 | 834 | 834 | - | - | - | - | - | - | - | - |
| 1b.3.2 | Process liquid waste | 179 | - | - | - | - | 113 | - | 177 | 883 | 883 | - | - | - | - | - | - | - | 237 |
| 1b.3.3 | Small tool allowance | 103 | - | - | - | - | - | - | 15 | 119 | 119 | - | - | - | - | - | - | - | - |
| 1b.3 | Subtotal Period 1b Collateral Costs | 904 | 103 | 64 | 351 | - | 113 | - | 301 | 1,836 | 1,836 | - | - | - | - | - | - | - | 237 |
| Period 1b Period-Dependent Costs | | | | | | | | | | | | | | | | | | | |
| 1b.4.1 | Decon supplies | 2,110 | - | - | - | - | - | - | 528 | 2,638 | 2,638 | - | - | - | - | - | - | - | - |
| 1b.4.2 | Insurance | - | - | - | - | - | - | 333 | 33 | 366 | 366 | - | - | - | - | - | - | - | - |
| 1b.4.3 | Property taxes | - | - | - | - | - | - | 1,061 | 106 | 1,167 | 1,167 | - | - | - | - | - | - | - | - |
| 1b.4.4 | Health physics supplies | - | 573 | - | - | - | - | - | 143 | 716 | 716 | - | - | - | - | - | - | - | - |
| 1b.4.5 | Heavy equipment rental | - | 88 | - | - | - | - | - | 13 | 101 | 101 | - | - | - | - | - | - | - | - |
| 1b.4.6 | Disposal of DAW generated | - | - | - | 13 | - | 85 | - | 26 | 157 | 157 | - | - | - | - | - | - | - | - |
| 1b.4.7 | Plant energy budget | - | - | - | - | - | - | 243 | 36 | 279 | 279 | - | - | - | - | - | - | - | 46 |
| 1b.4.8 | NRC Fees | - | - | - | - | - | - | 65 | 7 | 72 | 72 | - | - | - | - | - | - | - | - |
| 1b.4.9 | Emergency Planning Fees | - | - | - | - | - | - | 113 | 9 | 125 | 125 | - | - | - | - | - | - | - | - |
| 1b.4.10 | Site O&M Cost | - | - | - | - | - | - | 63 | 9 | 72 | 72 | - | - | - | - | - | - | - | - |
| 1b.4.11 | Spent Fuel Pool O&M | - | - | - | - | - | - | 1,501 | 225 | 1,726 | 1,726 | - | - | - | - | - | - | - | 39,691 |
| 1b.4.12 | Security Staff Cost | - | - | - | - | - | - | 6,599 | 990 | 7,589 | 7,589 | - | - | - | - | - | - | - | 106,720 |
| 1b.4.13 | Utility Staff Cost | - | - | - | - | - | - | 10,164 | 2,157 | 14,884 | 14,884 | - | - | - | - | - | - | - | 146,411 |
| 1b.4 | Subtotal Period 1b Period-Dependent Costs | 2,110 | 661 | 32 | 13 | - | 85 | 10,164 | 2,157 | 15,223 | 14,884 | 339 | - | - | - | - | - | - | 46 |
| 1b.0 | TOTAL PERIOD 1b COST | 9,610 | 764 | 96 | 364 | - | 198 | 19,298 | 7,125 | 37,455 | 37,116 | 339 | - | - | - | - | - | - | 136,803 |

Table D
Clinton Power Station
Delayed DECON Decommissioning Cost Estimate
(Thousands of 2007 Dollars)

| Activity Index | Activity Description | Decon Cost | Removal Cost | Packaging Costs | Transport Costs | Off-Site Processing Costs | LLRW Disposal Costs | Other Costs | Total Contingency | Total Costs | NRC Lic. Term. Costs | Spent Fuel Management Costs | Site Restoration Costs | Processed Volume Cu. Feet | Burial Volumes | | | Burial / Processed Wt., Lbs. | Craft Manhours | Utility and Contractor Manhours | |
|---|---|------------|--------------|-----------------|-----------------|---------------------------|---------------------|-------------|-------------------|-------------|----------------------|-----------------------------|------------------------|---------------------------|------------------|------------------|------------------|------------------------------|----------------|---------------------------------|---------|
| | | | | | | | | | | | | | | | Class A Cu. Feet | Class B Cu. Feet | Class C Cu. Feet | | | | |
| PERIOD 1c - Preparations for SAFSTOR Dormancy | | | | | | | | | | | | | | | | | | | | | |
| Period 1c Direct Decommissioning Activities | | | | | | | | | | | | | | | | | | | | | |
| Ic.1.1 | Prepare support equipment for storage | - | 405 | - | - | - | - | - | 61 | 466 | 466 | - | - | - | - | - | - | - | - | 3,000 | - |
| Ic.1.2 | Install containment pressure equal lines | - | 35 | - | - | - | - | - | 5 | 41 | 41 | - | - | - | - | - | - | - | - | 700 | - |
| Ic.1.3 | Interim survey prior to dormancy | - | - | - | - | - | - | 733 | 220 | 953 | 953 | - | - | - | - | - | - | - | - | 14,885 | - |
| Ic.1.4 | Secure building accesses | - | - | - | - | - | - | - | 8 | 61 | 61 | - | - | - | - | - | - | - | - | - | 583 |
| Ic.1.5 | Prepare & submit interim report | - | - | - | - | - | - | - | 294 | 1,520 | 1,520 | - | - | - | - | - | - | - | - | 18,583 | 583 |
| Ic.1 | Subtotal Period 1c Activity Costs | - | 440 | - | - | - | - | 786 | 294 | 1,520 | 1,520 | - | - | - | - | - | - | - | - | 18,583 | 583 |
| Period 1c Collateral Costs | | | | | | | | | | | | | | | | | | | | | |
| Ic.3.1 | Process liquid waste | 133 | - | 47 | 260 | - | 84 | - | 131 | 655 | 655 | - | - | - | - | - | - | - | 904 | - | 176 |
| Ic.3.2 | Small tool allowance | - | 3 | - | - | - | - | - | 0 | 4 | 4 | - | - | - | - | - | - | - | - | - | - |
| Ic.3 | Subtotal Period 1c Collateral Costs | 133 | 3 | 47 | 260 | - | 84 | - | 132 | 659 | 659 | - | - | - | - | - | - | - | 904 | - | 176 |
| Period 1c Period-Dependent Costs | | | | | | | | | | | | | | | | | | | | | |
| Ic.4.1 | Insurance | - | - | - | - | - | - | 329 | 33 | 362 | 362 | - | - | - | - | - | - | - | - | - | - |
| Ic.4.2 | Property taxes | - | - | - | - | - | - | 1,049 | 105 | 1,154 | 1,154 | - | - | - | - | - | - | - | - | - | - |
| Ic.4.3 | Health physics supplies | 160 | - | - | - | - | - | - | 40 | 199 | 199 | - | - | - | - | - | - | - | - | - | - |
| Ic.4.4 | Heavy equipment rental | 87 | - | - | - | - | - | - | 13 | 100 | 100 | - | - | - | - | - | - | - | - | - | - |
| Ic.4.5 | Disposal of DAW generated | - | - | 4 | 1 | - | 9 | - | 3 | 17 | 17 | - | - | - | - | - | - | - | 168 | - | 5 |
| Ic.4.6 | Plant energy budget | - | - | - | - | - | - | 240 | 36 | 276 | 276 | - | - | - | - | - | - | - | - | - | - |
| Ic.4.7 | NRC Fees | - | - | - | - | - | - | 64 | 6 | 71 | 71 | - | - | - | - | - | - | - | - | - | - |
| Ic.4.8 | Emergency Planning Fees | - | - | - | - | - | - | 112 | 11 | 123 | - | - | - | - | - | - | - | - | - | 123 | - |
| Ic.4.9 | Site O&M Cost | - | - | - | - | - | - | 62 | 9 | 72 | 72 | - | - | - | - | - | - | - | - | - | - |
| Ic.4.10 | Spent Fuel Pool O&M | - | - | - | - | - | - | 184 | 28 | 212 | - | - | - | - | - | - | - | - | - | - | - |
| Ic.4.11 | Security Staff Cost | - | - | - | - | - | - | 1,485 | 223 | 1,707 | 1,707 | - | - | - | - | - | - | - | - | - | 39,260 |
| Ic.4.12 | Utility Staff Cost | - | - | - | - | - | - | 6,528 | 979 | 7,507 | 7,507 | - | - | - | - | - | - | - | - | - | 105,560 |
| Ic.4 | Subtotal Period 1c Period-Dependent Costs | - | 247 | 4 | 1 | - | 9 | 10,054 | 1,486 | 11,801 | 11,466 | - | - | - | - | - | - | - | 168 | - | 5 |
| Ic.0 | TOTAL PERIOD 1c COST | 133 | 690 | 51 | 262 | - | 93 | 10,839 | 1,912 | 13,980 | 13,645 | - | - | - | - | - | - | - | 1,072 | - | 18,774 |
| PERIOD 1 TOTALS | | 9,743 | 2,180 | 162 | 652 | - | 329 | 76,184 | 15,740 | 104,968 | 102,952 | - | - | - | - | - | - | - | 4,488 | - | 155,598 |
| PERIOD 2a - SAFSTOR Dormancy with Wet Spent Fuel Storage | | | | | | | | | | | | | | | | | | | | | |
| Period 2a Direct Decommissioning Activities | | | | | | | | | | | | | | | | | | | | | |
| 2a.1.1 | Quarterly Inspection | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| 2a.1.2 | Semi-annual environmental survey | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| 2a.1.3 | Prepare reports | - | - | - | - | - | - | 1,345 | 202 | 1,547 | - | - | - | - | - | - | - | - | - | 1,547 | - |
| 2a.1.4 | Bituminous roof replacement | - | - | - | - | - | - | 1,353 | 338 | 1,691 | - | - | - | - | - | - | - | - | - | 1,691 | - |
| 2a.1.5 | Maintenance supplies | - | - | - | - | - | - | 2,698 | 540 | 3,237 | - | - | - | - | - | - | - | - | - | 3,237 | - |
| 2a.1 | Subtotal Period 2a Activity Costs | - | - | - | - | - | - | 5,436 | 1,080 | 6,516 | - | - | - | - | - | - | - | - | - | - | - |
| Period 2a Collateral Costs | | | | | | | | | | | | | | | | | | | | | |
| 2a.3.1 | Spent Fuel Capital and Transfer | - | - | - | - | - | - | 16,000 | 2,400 | 18,400 | - | - | - | - | - | - | - | - | - | - | 18,400 |
| 2a.3 | Subtotal Period 2a Collateral Costs | - | - | - | - | - | - | 16,000 | 2,400 | 18,400 | - | - | - | - | - | - | - | - | - | - | 18,400 |
| Period 2a Period-Dependent Costs | | | | | | | | | | | | | | | | | | | | | |
| 2a.4.1 | Insurance | - | - | - | - | - | - | 5,455 | 546 | 6,001 | - | - | - | - | - | - | - | - | - | 6,001 | - |
| 2a.4.2 | Property taxes | - | - | - | - | - | - | 12,360 | 1,256 | 13,596 | - | - | - | - | - | - | - | - | - | - | 13,596 |
| PERIOD 2a TOTALS | | - | - | - | - | - | - | 33,811 | 4,282 | 38,093 | - | - | - | - | - | - | - | - | - | - | 38,093 |

Table D
Clinton Power Station
Delayed DECON Decommissioning Cost Estimate
(Thousands of 2007 Dollars)

| Activity Index | Activity Description | Decon Cost | Removal Cost | Packaging Costs | Transport Costs | Off-Site Processing Costs | LLRW Disposal Costs | Other Costs | Total Contingency | Total | NRC Lic. Term. Costs | Spent Fuel Management Costs | Site Restoration Costs | Processed Volume Cu. Feet | Burial Volumes | | | Burial / Processed Wt., Lbs. | Craft Manhours | Utility and Contractor Manhours | |
|--|---|------------|--------------|-----------------|-----------------|---------------------------|---------------------|-------------|-------------------|---------|----------------------|-----------------------------|------------------------|---------------------------|------------------|------------------|------------------|------------------------------|----------------|---------------------------------|-----------|
| | | | | | | | | | | | | | | | Class A Cu. Feet | Class B Cu. Feet | Class C Cu. Feet | | | | |
| Period 2a Period-Dependent Costs (continued) | | | | | | | | | | | | | | | | | | | | | |
| 2a.4.3 | Health physics supplies | - | 926 | - | - | - | - | - | 231 | 1,157 | - | 1,157 | - | - | - | - | - | - | - | - | - |
| 2a.4.4 | Disposal of DAW generated | - | - | 104 | 43 | - | 272 | - | 85 | 504 | - | 504 | - | - | - | - | - | - | - | - | - |
| 2a.4.5 | Plant energy budget | - | - | - | - | - | - | 2,074 | 311 | 2,385 | - | 2,385 | - | - | - | - | - | - | - | - | - |
| 2a.4.6 | NRC Fees | - | - | - | - | - | - | 2,921 | 232 | 3,153 | - | 2,953 | - | - | - | - | - | - | - | - | - |
| 2a.4.7 | Emergency Planning Fees | - | - | - | - | - | - | 2,191 | 215 | 2,366 | - | 2,366 | - | - | - | - | - | - | - | - | - |
| 2a.4.8 | Site O&M Cost | - | - | - | - | - | - | 2,689 | 403 | 3,092 | - | 3,092 | - | - | - | - | - | - | - | - | - |
| 2a.4.9 | Spent Fuel Pool O&M | - | - | - | - | - | - | 7,941 | 1,191 | 9,132 | - | 9,132 | - | - | - | - | - | - | - | - | - |
| 2a.4.10 | Security Staff Cost | - | - | - | - | - | - | 46,200 | 6,780 | 51,981 | - | 51,981 | - | - | - | - | - | - | - | - | 1,195,234 |
| 2a.4.11 | Utility Staff Cost | - | - | - | - | - | - | 56,198 | 8,430 | 64,628 | - | 64,628 | - | - | - | - | - | - | - | - | 830,491 |
| 2a.4 | Subtotal Period 2a Period-Dependent Costs | - | 926 | 104 | 43 | - | 272 | 136,388 | 19,660 | 157,393 | - | 157,393 | - | - | - | - | - | - | - | - | 97,849 |
| 2a.0 | TOTAL PERIOD 2a COST | - | 926 | 104 | 43 | - | 272 | 155,086 | 22,600 | 179,031 | - | 179,031 | - | - | - | - | - | - | - | - | 97,849 |
| PERIOD 2 TOTALS | | | | | | | | | | | | | | | | | | | | | |
| PERIOD 3a - Reactivate Site Following SAFSTOR Dormancy | | | | | | | | | | | | | | | | | | | | | |
| Period 3a Direct Decommissioning Activities | | | | | | | | | | | | | | | | | | | | | |
| 3a.1.1 | Prepare preliminary decommissioning cost | - | - | - | - | - | - | 118 | 18 | 136 | 136 | - | - | - | - | - | - | - | - | - | 1,300 |
| 3a.1.2 | Review plant dwgs & specs. | - | - | - | - | - | - | 417 | 63 | 480 | 480 | - | - | - | - | - | - | - | - | - | 4,600 |
| 3a.1.3 | Perform detailed rad survey | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| 3a.1.4 | End product description | - | - | - | - | - | - | 91 | 14 | 104 | 104 | - | - | - | - | - | - | - | - | - | 1,000 |
| 3a.1.5 | Detailed by-product inventory | - | - | - | - | - | - | 118 | 18 | 136 | 136 | - | - | - | - | - | - | - | - | - | 1,300 |
| 3a.1.6 | Define main work sequence | - | - | - | - | - | - | 102 | 102 | 782 | 782 | - | - | - | - | - | - | - | - | - | 7,500 |
| 3a.1.7 | Perform SFR and EA | - | - | - | - | - | - | 281 | 42 | 323 | 323 | - | - | - | - | - | - | - | - | - | 3,100 |
| 3a.1.8 | Perform Site-Specific Cost Study | - | - | - | - | - | - | 494 | 68 | 522 | 522 | - | - | - | - | - | - | - | - | - | 5,000 |
| 3a.1.9 | Prepare/submit License Termination Plan | - | - | - | - | - | - | 372 | 36 | 427 | 427 | - | - | - | - | - | - | - | - | - | 4,096 |
| 3a.1.10 | Receive NRC approval of termination plan | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| Activity Specifications | | | | | | | | | | | | | | | | | | | | | |
| 3a.1.11.1 | Re-activate plant & temporary facilities | - | - | - | - | - | - | 668 | 100 | 769 | 692 | - | - | - | - | - | - | - | - | - | 7,370 |
| 3a.1.11.2 | Plant systems | - | - | - | - | - | - | 378 | 57 | 435 | 391 | - | - | - | - | - | - | - | - | - | 4,167 |
| 3a.1.11.3 | Reactor internals | - | - | - | - | - | - | 644 | 97 | 741 | 741 | - | - | - | - | - | - | - | - | - | 7,100 |
| 3a.1.11.4 | Reactor vessel | - | - | - | - | - | - | 590 | 88 | 678 | 678 | - | - | - | - | - | - | - | - | - | 6,500 |
| 3a.1.11.5 | Sacrificial shield | - | - | - | - | - | - | 45 | 7 | 52 | 52 | - | - | - | - | - | - | - | - | - | 500 |
| 3a.1.11.6 | Moisture separators/reheaters | - | - | - | - | - | - | 91 | 14 | 104 | 104 | - | - | - | - | - | - | - | - | - | 1,000 |
| 3a.1.11.7 | Reinforced concrete | - | - | - | - | - | - | 145 | 22 | 167 | 83 | - | - | - | - | - | - | - | - | - | 1,600 |
| 3a.1.11.8 | Main Turbine | - | - | - | - | - | - | 189 | 28 | 218 | 218 | - | - | - | - | - | - | - | - | - | 2,088 |
| 3a.1.11.9 | Main Condensers | - | - | - | - | - | - | 181 | 27 | 209 | 209 | - | - | - | - | - | - | - | - | - | 2,000 |
| 3a.1.11.10 | Pressure suppression structure | - | - | - | - | - | - | 145 | 22 | 167 | 167 | - | - | - | - | - | - | - | - | - | 1,600 |
| 3a.1.11.11 | Drywell | - | - | - | - | - | - | 283 | 42 | 325 | 163 | - | - | - | - | - | - | - | - | - | 3,120 |
| 3a.1.11.12 | Plant structures & buildings | - | - | - | - | - | - | 417 | 63 | 480 | 480 | - | - | - | - | - | - | - | - | - | 4,600 |
| 3a.1.11.13 | Waste management | - | - | - | - | - | - | 82 | 12 | 94 | 47 | - | - | - | - | - | - | - | - | - | 900 |
| 3a.1.11.14 | Facility & site closeout | - | - | - | - | - | - | 4,098 | 607 | 4,655 | 4,242 | - | - | - | - | - | - | - | - | - | 44,633 |
| 3a.1.11 | Total | - | - | - | - | - | - | 218 | 33 | 250 | 250 | - | - | - | - | - | - | - | - | - | 2,400 |
| Planning & Site Preparations | | | | | | | | | | | | | | | | | | | | | |
| 3a.1.12 | Prepare dismantling sequence | - | - | - | - | - | - | 2,419 | 363 | 2,782 | 2,782 | - | - | - | - | - | - | - | - | - | - |
| 3a.1.13 | Plant prep. & temp. svees | - | - | - | - | - | - | 127 | 19 | 146 | 146 | - | - | - | - | - | - | - | - | - | 1,400 |
| 3a.1.14 | Design water clean-up system | - | - | - | - | - | - | 2,048 | 307 | 2,355 | 2,355 | - | - | - | - | - | - | - | - | - | - |
| 3a.1.15 | Rigging/Cont. Contrl Env/ps/tooling/etc. | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - |

Table D
Clinton Power Station
Delayed DECON Decommissioning Cost Estimate
(Thousands of 2007 Dollars)

| Activity Index | Activity Description | Decom Cost | Removal Cost | Packaging Costs | Transport Costs | Off-Site Processing Costs | LLRW Disposal Costs | Other Costs | Total Contingency | Total | NRC Lic. Term. Costs | Spent Fuel Management Costs | Site Restoration Costs | Processed Volume Cu. Feet | Class A | | Class B | | Burial / Processed Wt., Lbs. | Craft Manhours | Utility and Contractor Manhours |
|---|---|------------|--------------|-----------------|-----------------|---------------------------|---------------------|-------------|-------------------|--------|----------------------|-----------------------------|------------------------|---------------------------|----------|----------|----------|----------|------------------------------|----------------|---------------------------------|
| | | | | | | | | | | | | | | | Cu. Feet | Cu. Feet | Cu. Feet | Cu. Feet | | | |
| 3a.1.16 | Procure caskliners & containers | - | - | - | - | - | - | 112 | 17 | 128 | 128 | - | - | - | - | - | - | - | - | - | 1,230 |
| 3a.1 | Subtotal Period 3a Activity Costs | - | - | - | - | - | - | 11,501 | 1,725 | 13,227 | 12,813 | - | 413 | - | - | - | - | - | - | - | 77,559 |
| Period 3b Period-Dependent Costs | | | | | | | | | | | | | | | | | | | | | |
| 3a.4.1 | Insurance | - | - | - | - | - | - | 458 | 46 | 504 | 504 | - | - | - | - | - | - | - | - | - | - |
| 3a.4.2 | Property taxes | - | - | - | - | - | - | 999 | 100 | 1,099 | 1,099 | - | - | - | - | - | - | - | - | - | - |
| 3a.4.3 | Health physics supplies | 330 | - | - | - | - | - | - | 82 | 412 | 412 | - | - | - | - | - | - | - | - | - | - |
| 3a.4.4 | Heavy equipment rental | 349 | - | - | - | - | - | - | 52 | 401 | 401 | - | - | - | - | - | - | - | - | - | - |
| 3a.4.5 | Disposal of DAW generated | - | - | - | 5 | - | 32 | - | 10 | 89 | 89 | - | - | - | 570 | - | - | - | - | - | - |
| 3a.4.6 | Plant energy budget | - | - | - | - | - | - | - | 145 | 1,108 | 1,108 | - | - | - | - | - | - | - | - | - | - |
| 3a.4.7 | NRC Fees | - | - | - | - | - | - | 258 | 26 | 284 | 284 | - | - | - | - | - | - | - | - | - | - |
| 3a.4.8 | Site O&M Cost | - | - | - | - | - | - | 250 | 37 | 287 | 287 | - | - | - | - | - | - | - | - | - | - |
| 3a.4.9 | Security Staff Cost | - | - | - | - | - | - | 2,465 | 370 | 2,835 | 2,835 | - | - | - | - | - | - | - | - | - | - |
| 3a.4.10 | Utility Staff Cost | - | - | - | - | - | - | 16,145 | 2,422 | 18,566 | 18,566 | - | - | - | - | - | - | - | - | - | 65,179 |
| 3a.4 | Subtotal Period 3a Period-Dependent Costs | 678 | - | - | 5 | - | 32 | 21,539 | 3,290 | 25,556 | 25,556 | - | - | - | 570 | - | - | - | - | - | 258,629 |
| 3a.0 | TOTAL PERIOD 3a COST | 678 | - | - | 5 | - | 32 | 33,040 | 5,015 | 38,782 | 38,369 | - | 413 | - | 570 | - | - | - | - | - | 323,807 |
| PERIOD 3b - Decommissioning Preparations | | | | | | | | | | | | | | | | | | | | | |
| Period 3b Direct Decommissioning Activities | | | | | | | | | | | | | | | | | | | | | |
| Detailed Work Procedures | | | | | | | | | | | | | | | | | | | | | |
| 3b.1.1.1 | Plant systems | - | - | - | - | - | - | 429 | 64 | 494 | 444 | - | - | - | - | - | - | - | - | - | 4,733 |
| 3b.1.1.2 | Reactor internals | - | - | - | - | - | - | 963 | 54 | 417 | 417 | - | - | - | - | - | - | - | - | - | 4,000 |
| 3b.1.1.3 | Remaining buildings | - | - | - | - | - | - | 122 | 18 | 141 | 85 | - | - | - | - | - | - | - | - | - | 1,350 |
| 3b.1.1.4 | CRD housings & NIs | - | - | - | - | - | - | 91 | 14 | 104 | 104 | - | - | - | - | - | - | - | - | - | 1,000 |
| 3b.1.1.5 | Incore instrumentation | - | - | - | - | - | - | 91 | 14 | 104 | 104 | - | - | - | - | - | - | - | - | - | 1,000 |
| 3b.1.1.6 | Removal primary contamination | - | - | - | - | - | - | 181 | 27 | 209 | 209 | - | - | - | - | - | - | - | - | - | 2,000 |
| 3b.1.1.7 | Reactor vessel | - | - | - | - | - | - | 329 | 49 | 379 | 379 | - | - | - | - | - | - | - | - | - | 3,630 |
| 3b.1.1.8 | Facility closure | - | - | - | - | - | - | 109 | 16 | 125 | 63 | - | - | - | - | - | - | - | - | - | 1,200 |
| 3b.1.1.9 | Sacrificial shield | - | - | - | - | - | - | 109 | 16 | 125 | 125 | - | - | - | - | - | - | - | - | - | 1,200 |
| 3b.1.1.10 | Reinforced concrete | - | - | - | - | - | - | 91 | 14 | 104 | 52 | - | - | - | - | - | - | - | - | - | 1,000 |
| 3b.1.1.11 | Main Turbine | - | - | - | - | - | - | 189 | 28 | 217 | 217 | - | - | - | - | - | - | - | - | - | 2,080 |
| 3b.1.1.12 | Main Condensers | - | - | - | - | - | - | 189 | 28 | 217 | 218 | - | - | - | - | - | - | - | - | - | 2,088 |
| 3b.1.1.13 | Moisture separators & reheaters | - | - | - | - | - | - | 181 | 27 | 209 | 209 | - | - | - | - | - | - | - | - | - | 2,000 |
| 3b.1.1.14 | Radwaste building | - | - | - | - | - | - | 248 | 37 | 285 | 256 | - | - | - | - | - | - | - | - | - | 2,730 |
| 3b.1.1.15 | Reactor building | - | - | - | - | - | - | 248 | 37 | 285 | 285 | - | - | - | - | - | - | - | - | - | 2,730 |
| 3b.1.1 | Total | - | - | - | - | - | - | 2,970 | 445 | 3,415 | 3,088 | - | - | - | - | - | - | - | - | - | 32,741 |
| 3b.1 | Subtotal Period 3b Activity Costs | - | - | - | - | - | - | 2,970 | 445 | 3,415 | 3,088 | - | - | - | - | - | - | - | - | - | 32,741 |
| Period 3b Additional Costs | | | | | | | | | | | | | | | | | | | | | |
| 3b.2.1 | Site Characterization | - | - | - | - | - | - | 887 | 269 | 1,167 | 1,167 | - | - | - | - | - | - | - | - | - | - |
| 3b.2.2 | Hazardous liquid disposal | - | - | - | 7 | - | 411 | - | 104 | 523 | 523 | - | - | - | - | - | - | - | - | - | 89,546 |
| 3b.2.3 | Contaminated asbestos disposal | - | - | - | 8 | - | 5 | - | 2 | 15 | 15 | - | - | - | 60 | - | - | - | - | - | 1,800 |
| 3b.2.4 | Clean asbestos disposal | - | - | - | - | - | - | 2 | 0 | 2 | 2 | - | - | - | - | - | - | - | - | - | - |
| 3b.2 | Subtotal Period 3b Additional Costs | - | - | - | 15 | - | 416 | 900 | 376 | 1,707 | 1,707 | - | - | - | 1,631 | - | - | - | - | - | 91,346 |
| Period 3b Collateral Costs | | | | | | | | | | | | | | | | | | | | | |
| 3b.3.1 | Decon equipment | 726 | - | - | - | - | - | - | 109 | 834 | 834 | - | - | - | - | - | - | - | - | - | - |
| 3b.3.2 | DOC staff relocation expenses | - | - | - | - | - | - | 829 | 124 | 953 | 953 | - | - | - | - | - | - | - | - | - | - |
| 3b.3.3 | Pipe cutting equipment | - | - | - | - | - | - | - | 143 | 1,100 | 1,100 | - | - | - | - | - | - | - | - | - | - |

Table D
Clinton Power Station
Delayed DECON Decommissioning Cost Estimate
(Thousands of 2007 Dollars)

| Activity Index | Activity Description | Decom Cost | Removal Cost | Packaging Costs | Transport Costs | Off-Site Processing Costs | LLRW Disposal Costs | Other Costs | Total Contingency | Total | NRC Lic. Term. Costs | Spent Fuel Management Costs | Site Restoration Costs | Processed Volume Cu. Feet | Burial Volumes | | | Burial / Processed Wt. Lbs. | Utility and Contractor Manhours |
|--|---|------------|--------------|-----------------|-----------------|---------------------------|---------------------|-------------|-------------------|--------|----------------------|-----------------------------|------------------------|---------------------------|------------------|------------------|------------------|-----------------------------|---------------------------------|
| | | | | | | | | | | | | | | | Class A Cu. Feet | Class B Cu. Feet | Class C Cu. Feet | | |
| 3b.3 | Subtotal Period 3b Collateral Costs | 726 | 957 | - | - | - | - | 829 | 377 | 2,887 | 2,887 | - | - | - | - | - | - | - | - |
| Period 3b Period-Dependent Costs | | | | | | | | | | | | | | | | | | | |
| 3b.4.1 | Decon supplies | 22 | - | - | - | - | - | 254 | 6 | 28 | 28 | - | - | - | - | - | - | - | - |
| 3b.4.2 | Insurance | - | - | - | - | - | - | 501 | 25 | 280 | 280 | - | - | - | - | - | - | - | - |
| 3b.4.3 | Property taxes | - | - | - | - | - | - | 50 | 50 | 51 | 51 | - | - | - | - | - | - | - | - |
| 3b.4.4 | Health physics supplies | 182 | - | - | - | - | - | - | 46 | 228 | 228 | - | - | - | - | - | - | - | - |
| 3b.4.5 | Heavy equipment rental | 175 | - | - | - | - | - | - | 26 | 201 | 201 | - | - | - | - | - | - | - | - |
| 3b.4.6 | Disposal of DAW generated | - | - | 7 | 3 | - | 18 | - | 6 | 33 | 33 | - | - | 323 | - | - | 6,476 | 10 | - |
| 3b.4.7 | Plant energy budget | - | - | - | - | - | - | 483 | 72 | 556 | 556 | - | - | - | - | - | - | - | - |
| 3b.4.8 | NRC Fees | - | - | - | - | - | - | 130 | 13 | 143 | 143 | - | - | - | - | - | - | - | - |
| 3b.4.9 | Site O&M Cost | - | - | - | - | - | - | 125 | 19 | 144 | 144 | - | - | - | - | - | - | - | - |
| 3b.4.10 | Security Staff Cost | - | - | - | - | - | - | 1,236 | 185 | 1,421 | 1,421 | - | - | - | - | - | - | - | - |
| 3b.4.11 | DOC Staff Cost | - | - | - | - | - | - | 3,799 | 570 | 4,369 | 4,369 | - | - | - | - | - | - | - | 32,679 |
| 3b.4.12 | Utility Staff Cost | - | - | - | - | - | - | 8,094 | 1,214 | 9,309 | 9,309 | - | - | - | - | - | - | - | 58,560 |
| 3b.4 | Subtotal Period 3b Period-Dependent Costs | 22 | 357 | 7 | 3 | - | 18 | 14,622 | 2,232 | 17,261 | 17,261 | - | - | 323 | - | - | 6,476 | 10 | 220,907 |
| 3b.0 | TOTAL PERIOD 3b COST | 748 | 1,314 | 7 | 18 | - | 434 | 19,320 | 3,430 | 25,271 | 24,944 | - | 327 | - | 1,954 | - | 97,822 | 10 | 253,648 |
| PERIOD 3 TOTALS | | | | | | | | | | | | | | | | | | | |
| PERIOD 4a - Large Component Removal | | | | | | | | | | | | | | | | | | | |
| Period 4a Direct Decommissioning Activities | | | | | | | | | | | | | | | | | | | |
| Nuclear Steam Supply System Removal | | | | | | | | | | | | | | | | | | | |
| 4a.1.1.1 | Recirculation System Piping & Valves | 10 | 40 | 8 | 9 | - | 99 | - | 42 | 209 | 209 | - | - | 530 | - | - | 64,091 | 1,078 | - |
| 4a.1.1.2 | Recirculation Pumps & Motors | 10 | 38 | 13 | 29 | 18 | 263 | - | 89 | 460 | 460 | - | - | 2,473 | - | - | 187,000 | 1,145 | - |
| 4a.1.1.3 | CRDMs & NIS Removal | 42 | 158 | 321 | 82 | - | 203 | - | 196 | 962 | 962 | - | - | 6,985 | - | - | 131,119 | 4,212 | - |
| 4a.1.1.4 | Reactor Vessel Internals | 112 | 2,300 | 3,613 | 973 | - | 5,407 | 213 | 5,663 | 18,281 | 18,281 | - | - | 1,753 | 1,502 | 287 | 342,025 | 28,950 | 1,290 |
| 4a.1.1.5 | Vessel & Internals GTCC Disposal | - | - | - | - | - | - | - | 1,223 | 9,374 | 9,374 | - | - | - | - | - | 482 | 86,500 | - |
| 4a.1.1.6 | Reactor Vessel | - | 5,325 | 1,351 | 375 | - | 2,056 | 213 | 5,485 | 14,805 | 14,805 | - | - | 13,057 | - | - | 1,326,615 | 28,950 | 1,290 |
| 4a.1.1 | Totals | 175 | 7,861 | 5,307 | 1,468 | 18 | 16,180 | 425 | 12,657 | 44,091 | 44,091 | - | - | 24,798 | 1,502 | 287 | 2,137,350 | 64,336 | 2,580 |
| Removal of Major Equipment | | | | | | | | | | | | | | | | | | | |
| 4a.1.2 | Main Turbine/Generator | - | 307 | 885 | 180 | 2,586 | 152 | - | 618 | 4,729 | 4,729 | - | - | 54,728 | 1,613 | - | 2,607,544 | 6,446 | - |
| 4a.1.3 | Main Condensers | - | 1,051 | 952 | 194 | 2,781 | 163 | - | 845 | 5,985 | 5,985 | - | - | 58,848 | 1,735 | - | 2,803,815 | 22,050 | - |
| Cascading Costs from Clean Building Demolition | | | | | | | | | | | | | | | | | | | |
| 4a.1.4.1 | Reactor Building | - | 905 | - | - | - | - | - | 136 | 1,041 | 1,041 | - | - | - | - | - | - | 11,450 | - |
| 4a.1.4.2 | Auxiliary Building | - | 216 | - | - | - | - | - | 248 | 248 | 248 | - | - | - | - | - | - | 2,582 | - |
| 4a.1.4.3 | Radwaste Building | - | 500 | - | - | - | - | - | 75 | 575 | 575 | - | - | - | - | - | - | 6,493 | - |
| 4a.1.4.4 | Turbine Building | - | 508 | - | - | - | - | - | 76 | 585 | 585 | - | - | - | - | - | - | 6,771 | - |
| 4a.1.4.5 | Fuel Building | - | 237 | - | - | - | - | - | 36 | 273 | 273 | - | - | - | - | - | - | 2,912 | - |
| 4a.1.4 | Totals | - | 2,367 | - | - | - | - | - | 355 | 2,722 | 2,722 | - | - | - | - | - | - | 30,209 | - |
| Disposal of Plant Systems | | | | | | | | | | | | | | | | | | | |
| 4a.1.5.1 | Acid Feed & Handling | - | 26 | 1 | 1 | 21 | - | - | 10 | 59 | 59 | - | - | 488 | - | - | 19,822 | 533 | - |
| 4a.1.5.2 | Auxiliary Steam | - | 484 | 13 | 19 | 319 | - | - | 173 | 1,008 | 1,008 | - | - | 7,493 | - | - | 304,278 | 9,740 | - |
| 4a.1.5.3 | Breathing Air | - | 36 | - | - | - | - | - | 5 | 42 | 42 | - | - | - | - | - | - | 820 | - |
| 4a.1.5.4 | CO2 & Generator Purge | - | 16 | - | - | - | - | - | 2 | 18 | 18 | - | - | - | - | - | - | 349 | - |
| 4a.1.5.5 | Caustic Handling | - | 13 | 0 | 0 | 8 | - | - | 5 | 26 | 26 | - | - | 183 | - | - | 7,431 | 256 | - |
| 4a.1.5.6 | Chem Radwaste Reprocessing & Disposal | - | 351 | 39 | 36 | 94 | 168 | - | 153 | 841 | 841 | - | - | 2,211 | 1,211 | - | 249,902 | 7,339 | - |

Table D
Clinton Power Station
Delayed DECON Decommissioning Cost Estimate
(Thousands of 2007 Dollars)

| Activity Index | Activity Description | Decom Cost | Removal Cost | Packaging Costs | Transport Costs | Off-Site Processing Costs | LLRW Disposal Costs | Other Costs | Total Contingency | Total | NRC Lic. Term. Costs | Spent Fuel Management Costs | Site Restoration Costs | Processed Volume | Burial Volumes | | | Burial / Processed Wt. Lbs. | Craft Manhours | Utility and Contractor Manhours | |
|----------------|---|------------|--------------|-----------------|-----------------|---------------------------|---------------------|-------------|-------------------|-------|----------------------|-----------------------------|------------------------|------------------|----------------|----------|-----------|-----------------------------|----------------|---------------------------------|---|
| | | | | | | | | | | | | | | | Class A | Class B | Class C | | | | |
| | | | | | | | | | | | | | | Cu. Feet | Cu. Feet | Cu. Feet | | | | | |
| 4a.1.5.7 | Chilled Water - RCA | 1,035 | - | 27 | 40 | 679 | - | - | 369 | 2,149 | 2,149 | - | - | 15,914 | - | - | 646,286 | 20,760 | - | - | |
| 4a.1.5.8 | Chilled Water Non-RCA | 166 | - | - | - | - | - | - | 25 | 191 | - | - | 191 | - | - | - | - | 3,682 | - | - | |
| 4a.1.5.9 | Chlorination | 44 | - | - | - | - | - | - | 7 | 51 | - | - | 51 | - | - | - | 953 | - | - | - | |
| 4a.1.5.10 | Circulating Water - RCA | 161 | - | 16 | 24 | 400 | - | - | 105 | 706 | 706 | - | - | 9,379 | - | - | 380,877 | 3,419 | - | - | |
| 4a.1.5.11 | Circulating Water Non-RCA | 51 | - | - | - | - | - | - | 8 | 58 | - | - | 58 | - | - | - | - | 1,090 | - | - | |
| 4a.1.5.12 | Containment Aux & Fuel Bldg Equip Drains | 81 | - | 5 | 5 | 8 | 24 | - | 28 | 150 | 150 | - | - | 187 | 253 | - | 30,046 | 1,627 | - | - | |
| 4a.1.5.13 | Containment Aux & Fuel Bldg Floor Drains | 139 | - | 8 | 8 | 34 | 32 | - | 50 | 271 | 271 | - | - | 792 | 367 | - | 62,936 | 2,852 | - | - | |
| 4a.1.5.14 | Component Cooling Water Non-RCA | 119 | - | - | - | - | - | - | 18 | 137 | - | - | 137 | - | - | - | - | 2,622 | - | - | |
| 4a.1.5.15 | Condensate | 810 | - | 159 | 174 | 584 | 772 | - | 525 | 3,024 | 3,024 | - | - | 13,689 | 8,197 | - | 1,291,159 | 17,379 | - | - | |
| 4a.1.5.16 | Condensate Booster | 161 | - | 178 | 178 | 543 | 806 | - | 517 | 2,971 | 2,971 | - | - | 12,724 | 8,568 | - | 1,284,382 | 16,493 | - | - | |
| 4a.1.5.17 | Condensate Polishing | 619 | - | 46 | 45 | 188 | 188 | - | 241 | 1,327 | 1,327 | - | - | 4,398 | 2,104 | - | 357,430 | 12,843 | - | - | |
| 4a.1.5.18 | Condenser Vacuum | 179 | - | 17 | 25 | 430 | - | - | 115 | 767 | 767 | - | - | 10,094 | - | - | 409,927 | 3,731 | - | - | |
| 4a.1.5.19 | Containment Combustible Gas | 67 | - | 4 | 4 | 33 | 14 | - | 26 | 149 | 149 | - | - | 781 | 147 | - | 44,863 | 1,396 | - | - | |
| 4a.1.5.20 | Cycled Condensate | 555 | - | 41 | 40 | 181 | 163 | - | 217 | 1,197 | 1,197 | - | - | 4,242 | 1,929 | - | 327,937 | 11,485 | - | - | |
| 4a.1.5.21 | Drywell Cooling | 437 | - | 20 | 25 | 242 | 62 | - | 167 | 952 | 952 | - | - | 5,664 | 655 | - | 288,770 | 8,570 | - | - | |
| 4a.1.5.22 | Drywell Purge | 124 | - | 11 | 15 | 118 | 42 | - | 63 | 373 | 373 | - | - | 2,764 | 451 | - | 152,687 | 2,624 | - | - | |
| 4a.1.5.23 | ECCS Equipment Cooling | 65 | - | 2 | 4 | 51 | 3 | - | 25 | 150 | 150 | - | - | 1,190 | 32 | - | 51,154 | 1,312 | - | - | |
| 4a.1.5.24 | Extraction Steam | 424 | - | 54 | 63 | 236 | 271 | - | 224 | 1,272 | 1,272 | - | - | 5,531 | 2,875 | - | 482,498 | 9,036 | - | - | |
| 4a.1.5.25 | Feedwater | 464 | - | 88 | 100 | 331 | 445 | - | 301 | 1,730 | 1,730 | - | - | 7,772 | 4,722 | - | 739,273 | 9,995 | - | - | |
| 4a.1.5.26 | Feedwater Heater Drains Turbine Cycle | 1,109 | - | 112 | 126 | 507 | 527 | - | 515 | 2,897 | 2,897 | - | - | 11,899 | 5,704 | - | 985,459 | 23,395 | - | - | |
| 4a.1.5.27 | Feedwater Heater Misc. | 172 | - | 13 | 13 | 29 | 62 | - | 66 | 357 | 357 | - | - | 685 | 664 | - | 87,316 | 3,553 | - | - | |
| 4a.1.5.28 | Filtered Water | - | - | - | - | - | - | - | 1 | 4 | 4 | - | 4 | - | - | - | - | 86 | - | - | - |
| 4a.1.5.29 | Generator Hydrogen Seal Oil | 25 | - | 0 | 1 | 10 | - | - | 8 | 44 | 44 | - | - | 243 | - | - | 9,883 | 469 | - | - | |
| 4a.1.5.30 | Generator Stator Cooling | 16 | - | 0 | 1 | 9 | - | - | 6 | 32 | 32 | - | - | 307 | - | - | 8,423 | 339 | - | - | |
| 4a.1.5.31 | High Pressure Core Spray | 225 | - | 36 | 39 | 131 | 170 | - | 128 | 728 | 728 | - | - | 3,077 | 1,807 | - | 287,000 | 4,792 | - | - | |
| 4a.1.5.32 | Hydrogen | 22 | - | 0 | 0 | 7 | - | - | 7 | 36 | 36 | - | - | 168 | - | - | 6,815 | 403 | - | - | |
| 4a.1.5.33 | Laundry Equip & Flr Drains RW Reprocess | 189 | - | 14 | 14 | 90 | 49 | - | 77 | 433 | 433 | - | - | 2,116 | 646 | - | 132,817 | 3,941 | - | - | |
| 4a.1.5.34 | Leak Detection | 37 | - | 1 | 1 | 1 | 3 | - | 10 | 53 | 53 | - | - | 30 | 29 | - | 3,822 | 837 | - | - | |
| 4a.1.5.35 | Local Instrument Panels | 5 | - | - | - | - | - | - | 1 | 6 | 6 | - | 6 | - | - | - | - | 116 | - | - | - |
| 4a.1.5.36 | Low Pressure Core Spray | 86 | - | 21 | 21 | 65 | 97 | - | 61 | 352 | 352 | - | - | 1,535 | 1,028 | - | 154,545 | 1,855 | - | - | |
| 4a.1.5.37 | Machine Shop Equipment | 10 | - | 0 | 1 | 10 | - | - | 4 | 25 | 25 | - | - | 225 | - | - | 9,119 | 216 | - | - | |
| 4a.1.5.38 | Machine Shop Ventilation | 201 | - | 5 | 8 | 114 | 7 | - | 71 | 405 | 405 | - | - | 2,665 | 71 | - | 114,605 | 3,671 | - | - | |
| 4a.1.5.39 | Main Steam | 746 | - | 74 | 80 | 298 | 347 | - | 337 | 1,882 | 1,882 | - | - | 6,987 | 3,685 | - | 614,246 | 15,676 | - | - | |
| 4a.1.5.40 | Main Steam Isolation Valve | 19 | - | 1 | 1 | 1 | 4 | - | 6 | 33 | 33 | - | - | 23 | 47 | - | 5,157 | 381 | - | - | |
| 4a.1.5.41 | Make-up Demineralizer - RCA | 184 | - | 4 | 6 | 103 | - | - | 63 | 360 | 360 | - | - | 2,419 | - | - | 98,255 | 3,595 | - | - | |
| 4a.1.5.42 | Make-up Demineralizer Non-RCA | 208 | - | - | - | - | - | - | 31 | 239 | 239 | - | - | 239 | - | - | 4,416 | - | - | - | |
| 4a.1.5.43 | Makeup Condensate Storage | 216 | - | 15 | 14 | 22 | 67 | - | 2 | 19 | 19 | - | - | 518 | 715 | - | 85,161 | 4,359 | - | - | |
| 4a.1.5.44 | Misc. Building Drains | 16 | - | - | - | - | - | - | 2 | 19 | 19 | - | - | - | - | - | - | 357 | - | - | - |
| 4a.1.5.45 | Miscellaneous Ventilation | 30 | - | - | - | - | - | - | 4 | 34 | 34 | - | - | - | - | - | - | 643 | - | - | - |
| 4a.1.5.46 | Nuclear Boiler | 15 | - | 1 | 1 | 1 | 3 | - | 5 | 24 | 24 | - | - | 17 | 30 | - | 3,359 | 324 | - | - | |
| 4a.1.5.47 | Oil Transfer | 90 | - | 4 | 6 | 104 | - | - | 39 | 243 | 243 | - | - | 2,429 | - | - | 98,662 | 1,834 | - | - | |
| 4a.1.5.48 | Reactor Core Isolation Cooling | 194 | - | 15 | 15 | 77 | 57 | - | 78 | 436 | 436 | - | - | 1,796 | 698 | - | 127,607 | 4,075 | - | - | |
| 4a.1.5.49 | Refrigeration Piping | 17 | - | - | - | - | - | - | 3 | 20 | 20 | - | - | - | - | - | - | 388 | - | - | - |
| 4a.1.5.50 | Sanitizers | 151 | - | - | - | - | - | - | 23 | 174 | 174 | - | - | - | - | - | - | 3,202 | - | - | - |
| 4a.1.5.51 | Screen Houses & MU Pump House Ventilation | 31 | - | - | - | - | - | - | 5 | 36 | 36 | - | - | 413 | - | - | 16,763 | 529 | - | - | |
| 4a.1.5.52 | Standby Liquid Control | 26 | - | 1 | 1 | 18 | - | - | 2 | 19 | 19 | - | - | - | - | - | - | 356 | - | - | - |
| 4a.1.5.53 | Swirlgear Heat Removal | 16 | - | - | - | - | - | - | 2 | 19 | 19 | - | - | - | - | - | - | 529 | - | - | - |
| 4a.1.5.54 | Turbine Building Closed Cooling Water | 148 | - | 4 | 5 | 90 | - | - | 52 | 289 | 289 | - | - | 2,106 | - | - | 85,531 | 2,948 | - | - | |
| 4a.1.5.55 | Turbine Electrohydraulic Control | 9 | - | 0 | 4 | 4 | - | - | 3 | 16 | 16 | - | - | 84 | - | - | 3,405 | 185 | - | - | |
| 4a.1.5.56 | Turbine Gen Misc Drains & Vents | 45 | - | 2 | 2 | 6 | 9 | - | 15 | 80 | 80 | - | - | 136 | 96 | - | 14,138 | 900 | - | - | |
| 4a.1.5.57 | Turbine Gland Seal Steam | 300 | - | 40 | 50 | 453 | 130 | - | 187 | 1,161 | 1,161 | - | - | 10,629 | 1,384 | - | 555,788 | 6,310 | - | - | |
| 4a.1.5.58 | Turbine Oil | 48 | - | 4 | 4 | 37 | 18 | - | 23 | 137 | 137 | - | - | 866 | 199 | - | 52,601 | 1,021 | - | - | |

Table D
Clinton Power Station
Delayed DECON Decommissioning Cost Estimate
(Thousands of 2007 Dollars)

| Activity Index | Activity Description | Decon Cost | Removal Cost | Packaging Costs | Transport Costs | Off-Site Processing Costs | LLRW Disposal Costs | Other Costs | Total Contingency | Total Lic. Term. Costs | Spent Fuel Management Costs | Site Restoration Costs | Processed Volume Cu. Feet | Burial Volumes | | | Burial / Processed Wt. Lbs. | Craft Manhours | Utility and Contractor Manhours | |
|---|---|------------|--------------|-----------------|-----------------|---------------------------|---------------------|-------------|-------------------|------------------------|-----------------------------|------------------------|---------------------------|------------------|------------------|------------------|-----------------------------|----------------|---------------------------------|---------|
| | | | | | | | | | | | | | | Class A Cu. Feet | Class B Cu. Feet | Class C Cu. Feet | | | | |
| Disposal of Plant Systems (continued) | | | | | | | | | | | | | | | | | | | | |
| 4a.1.5.59 | Turbine-Gen Aux. & Misc Devices | - | 214 | 51 | 62 | 289 | 250 | - | 174 | 1,041 | - | - | 6,779 | 2,656 | - | - | 513,573 | 4,683 | - | |
| 4a.1.5 | Totals | - | 12,060 | 1,131 | 1,280 | 6,974 | 4,792 | - | 5,473 | 31,710 | - | 1,048 | 163,551 | 51,880 | - | - | 11,205,730 | 251,495 | - | |
| Scaffolding in support of decommissioning | | | | | | | | | | | | | | | | | | | | |
| 4a.1.6 | Scaffolding in support of decommissioning | - | 2,745 | 50 | 11 | 140 | 17 | - | 718 | 3,682 | - | - | 2,969 | 185 | - | - | 150,174 | 63,258 | - | |
| 4a.1 | Subtotal Period 4a Activity Costs | 175 | 26,391 | 8,324 | 3,134 | 12,499 | 21,305 | 425 | 20,667 | 92,919 | - | 1,048 | 290,345 | 80,211 | 1,502 | 287 | 482 | 18,904,620 | 437,793 | 2,580 |
| Period 4a Additional Costs | | | | | | | | | | | | | | | | | | | | |
| 4a.2.1 | Disposal of stored turbine rotors | - | 17 | 100 | 40 | 743 | - | - | 130 | 1,030 | - | - | 15,719 | - | - | - | 707,358 | 352 | - | |
| 4a.2 | Subtotal Period 4a Additional Costs | - | 17 | 100 | 40 | 743 | - | - | 130 | 1,030 | - | - | 15,719 | - | - | - | 707,358 | 352 | - | |
| Period 4a Collateral Costs | | | | | | | | | | | | | | | | | | | | |
| 4a.3.1 | Process liquid waste | 55 | - | 20 | 111 | - | 36 | - | 55 | 278 | - | - | - | 386 | - | - | - | 23,185 | 75 | - |
| 4a.3.2 | Small tool allowance | - | 325 | - | - | - | - | - | 49 | 373 | - | - | - | - | - | - | - | - | - | |
| 4a.3 | Subtotal Period 4a Collateral Costs | 55 | 325 | 20 | 111 | - | 36 | - | 104 | 652 | - | - | - | 386 | - | - | - | 23,185 | 75 | - |
| Period 4a Period-Dependent Costs | | | | | | | | | | | | | | | | | | | | |
| 4a.4.1 | Decon supplies | 60 | - | - | - | - | - | - | 15 | 75 | - | - | - | - | - | - | - | - | - | |
| 4a.4.2 | Insurance | - | - | - | - | - | - | 690 | 759 | 759 | - | - | - | - | - | - | - | - | - | |
| 4a.4.3 | Property taxes | - | - | - | - | - | - | 1,361 | 1,347 | 1,347 | - | - | - | - | - | - | - | - | - | |
| 4a.4.4 | Health physics supplies | 2,037 | - | - | - | - | - | - | 509 | 2,547 | - | - | - | - | - | - | - | - | - | |
| 4a.4.5 | Heavy equipment rental | 2,320 | - | - | - | - | - | - | 348 | 2,668 | - | - | - | - | - | - | - | - | - | |
| 4a.4.6 | Disposal of DAW generated | - | - | 177 | 73 | - | 464 | - | 145 | 859 | - | - | - | 8,323 | - | - | 166,794 | 254 | - | |
| 4a.4.7 | Plant energy budget | - | - | - | - | - | - | 1,246 | 187 | 1,433 | - | - | - | - | - | - | - | - | - | |
| 4a.4.8 | NRC Fees | - | - | - | - | - | - | 468 | 47 | 515 | - | - | - | - | - | - | - | - | - | |
| 4a.4.9 | Site O&M Cost | - | - | - | - | - | - | 340 | 51 | 391 | - | - | - | - | - | - | - | - | - | |
| 4a.4.10 | Radwaste Processing Equipment/Services | - | - | - | - | - | - | 506 | 76 | 582 | - | - | - | - | - | - | - | - | - | |
| 4a.4.11 | Security Staff Cost | - | - | - | - | - | - | 3,356 | 503 | 3,860 | - | - | - | - | - | - | - | - | - | |
| 4a.4.12 | DOC Staff Cost | - | - | - | - | - | - | 12,669 | 1,900 | 14,569 | - | - | - | - | - | - | - | - | - | |
| 4a.4.13 | Utility Staff Cost | - | - | - | - | - | - | 22,201 | 3,350 | 25,531 | - | - | - | - | - | - | - | - | - | |
| 4a.4 | Subtotal Period 4a Period-Dependent Costs | 60 | 4,357 | 177 | 73 | - | 464 | 42,838 | 7,317 | 55,286 | - | 150 | - | 8,323 | - | - | 166,794 | 254 | - | |
| 4a.0 | TOTAL PERIOD 4a COST | 291 | 31,090 | 8,621 | 3,357 | 13,241 | 21,805 | 43,263 | 28,218 | 149,887 | - | 1,235 | 296,064 | 88,920 | 1,502 | 287 | 482 | 19,801,950 | 438,475 | 642,290 |
| PERIOD 4b - Site Decontamination | | | | | | | | | | | | | | | | | | | | |
| Period 4b Direct Decommissioning Activities | | | | | | | | | | | | | | | | | | | | |
| 4b.1.1 | Remove spent fuel rods | 452 | 45 | 92 | 104 | - | 572 | - | 405 | 1,668 | - | - | - | 6,066 | - | - | 544,292 | 1,017 | - | |
| Disposal of Plant Systems | | | | | | | | | | | | | | | | | | | | |
| 4b.1.2.1 | Component Cooling Water - RCA | - | 178 | 4 | 6 | 101 | - | - | 61 | 350 | - | - | 2,361 | - | - | - | 95,865 | 3,548 | - | |
| 4b.1.2.2 | Containment Monitoring | - | 50 | 1 | 1 | 4 | 4 | - | 15 | 76 | - | - | 98 | 44 | - | - | 7,962 | 1,115 | - | |
| 4b.1.2.3 | Control Rod Drive | - | 357 | 19 | 19 | 57 | 88 | - | 124 | 684 | - | - | 1,333 | 830 | - | - | 137,526 | 7,399 | - | |
| 4b.1.2.4 | Diesel Fuel Oil | - | 59 | - | - | - | - | - | 9 | 68 | - | - | - | - | - | - | - | 1,256 | - | |
| 4b.1.2.5 | Diesel General | - | 52 | - | - | - | - | - | 8 | 60 | - | - | - | - | - | - | - | 1,133 | - | |
| 4b.1.2.6 | Diesel-Generator Room Ventilation | - | 77 | - | - | - | - | - | 12 | 88 | - | - | - | - | - | - | - | 88 | - | |
| 4b.1.2.7 | Drains-Laundry to Radwaste | - | 15 | - | 1 | 1 | 4 | - | 5 | 27 | - | - | 34 | 39 | - | - | 4,837 | 302 | - | |
| 4b.1.2.8 | Electrical - Clean Non-RCA | 1,545 | - | - | - | - | - | - | 232 | 1,777 | - | - | - | - | - | - | - | - | - | |
| 4b.1.2.9 | Electrical - Clean RCA | 6,131 | - | 125 | 188 | 3,190 | - | 2,052 | 11,657 | 11,657 | - | - | 74,814 | - | - | - | 3,038,244 | 126,548 | - | |
| 4b.1.2.10 | Electrical - Contaminated | 909 | - | 16 | 23 | 335 | - | 385 | 1,591 | 1,591 | - | - | 7,867 | 209 | - | - | 338,266 | 19,043 | - | |
| 4b.1.2.11 | Equip Drain Radwaste Reprocessing | 1,018 | - | 69 | 67 | 307 | 271 | - | 385 | 2,118 | - | - | 7,207 | 3,254 | - | - | 551,230 | 21,073 | - | |
| 4b.1.2.12 | Fire Protection - RCA | - | 616 | 15 | 23 | 385 | - | - | 217 | 1,255 | - | - | 9,018 | - | - | - | 366,214 | 12,406 | - | |

Table D
Clinton Power Station
Delayed DECON Decommissioning Cost Estimate
(Thousands of 2007 Dollars)

| Activity Index | Activity Description | Decon Cost | Removal Cost | Packaging Costs | Transport Costs | Off-Site Processing Costs | LLRW Disposal Costs | Other Costs | Total Contingency | Total | NRC Lic. Term. Costs | Spent Fuel Management Costs | Site Restoration Costs | Processed Volume | Burial Volumes | | | Burial / Processed Wt. Lbs. | Craft Manhours | Utility and Contractor Manhours | |
|---------------------------------------|---|------------|--------------|-----------------|-----------------|---------------------------|---------------------|-------------|-------------------|--------|----------------------|-----------------------------|------------------------|------------------|----------------|----------|---------|-----------------------------|----------------|---------------------------------|---|
| | | | | | | | | | | | | | | | Class A | Class B | Class C | | | | |
| | | | | | | | | | | | | | | Cu. Feet | Cu. Feet | Cu. Feet | | | | | |
| Disposal of Plant Systems (continued) | | | | | | | | | | | | | | | | | | | | | |
| 4b.1.2.13 | Flare Protection Non-RCA | - | 154 | - | - | 235 | 227 | - | 23 | 177 | - | - | 177 | - | - | - | - | - | - | 3,416 | - |
| 4b.1.2.14 | Floor Drain Radwaste Reprocessing | - | 634 | - | 54 | - | 227 | - | 264 | 1,468 | - | - | - | 5,507 | - | - | - | - | 439,585 | 13,131 | - |
| 4b.1.2.15 | Fuel Handling & Transfer | - | 22 | - | 2 | 7 | 9 | - | 9 | 82 | - | - | - | 173 | 99 | - | - | - | 15,919 | 465 | - |
| 4b.1.2.16 | Fuel Pool Cooling & Cleanup | - | 783 | - | 92 | 277 | 417 | - | 365 | 2,026 | - | - | - | 6,503 | 4,489 | - | - | - | 660,961 | 16,306 | - |
| 4b.1.2.17 | Fuel Support | - | 88 | - | 12 | 47 | 52 | - | 45 | 255 | - | - | - | 1,100 | 356 | - | - | - | 94,553 | 1,906 | - |
| 4b.1.2.18 | HVAC - Auxiliary Building | - | 28 | - | 2 | 23 | 3 | - | 12 | 69 | - | - | - | 540 | 36 | - | - | - | 25,200 | 583 | - |
| 4b.1.2.19 | HVAC - Containment Building | - | 661 | - | 33 | 45 | 477 | - | 270 | 1,579 | - | - | - | 11,185 | 985 | - | - | - | 542,563 | 12,668 | - |
| 4b.1.2.20 | HVAC - Control Room | - | 242 | - | - | - | - | - | 36 | 279 | - | - | 279 | - | - | - | - | - | - | 5,686 | - |
| 4b.1.2.21 | HVAC - Fuel Building | - | 283 | - | 8 | 11 | 161 | - | 100 | 574 | - | - | - | 3,782 | 107 | - | - | - | 163,158 | 5,156 | - |
| 4b.1.2.22 | HVAC - Laboratory | - | 456 | - | 13 | 18 | 257 | - | 161 | 921 | - | - | - | 6,035 | 181 | - | - | - | 261,272 | 8,390 | - |
| 4b.1.2.23 | HVAC - Off Gas Building | - | 115 | - | 6 | 7 | 64 | - | 45 | 255 | - | - | - | 1,499 | 192 | - | - | - | 78,082 | 2,299 | - |
| 4b.1.2.24 | HVAC - Radwaste Building | - | 644 | - | 21 | 30 | 395 | - | 236 | 1,363 | - | - | - | 9,269 | 389 | - | - | - | 411,319 | 11,921 | - |
| 4b.1.2.25 | HVAC - Service Building | - | 52 | - | - | - | - | - | 8 | 60 | - | - | 60 | - | - | - | - | - | - | 1,145 | - |
| 4b.1.2.26 | HVAC - Turbine Building | - | 532 | - | 15 | 22 | 316 | - | 190 | 1,097 | - | - | - | 7,421 | 211 | - | - | - | 320,323 | 9,709 | - |
| 4b.1.2.27 | Hoists Cranes & Elevators | - | 6 | - | - | - | - | - | 1 | 7 | - | - | 7 | - | - | - | - | - | - | 123 | - |
| 4b.1.2.28 | Instrument Air - RCA | - | 374 | - | 5 | 7 | 115 | - | 112 | 613 | - | - | - | 2,708 | - | - | - | - | 109,971 | 7,089 | - |
| 4b.1.2.29 | Instrument Air Non-RCA | - | 17 | - | - | - | - | - | 3 | 20 | - | - | 20 | - | - | - | - | - | - | 389 | - |
| 4b.1.2.30 | Off Gas | - | 154 | - | 9 | 10 | 64 | - | 59 | 328 | - | - | - | 1,490 | 352 | - | - | - | 91,689 | 3,152 | - |
| 4b.1.2.31 | Plant Service Water - RCA | - | 176 | - | 5 | 8 | 130 | - | 65 | 384 | - | - | - | 3,043 | - | - | - | - | 123,583 | 3,532 | - |
| 4b.1.2.32 | Plant Service Water Non-RCA | - | 156 | - | - | - | - | - | 23 | 180 | - | - | 180 | - | - | - | - | - | - | 3,494 | - |
| 4b.1.2.33 | Portable Water | - | 11 | - | - | - | - | - | 2 | 12 | - | - | 12 | - | - | - | - | - | - | 231 | - |
| 4b.1.2.34 | Process Radiation Monitoring | - | 84 | - | 4 | 3 | 11 | - | 27 | 142 | - | - | - | 253 | 142 | - | - | - | 23,024 | 1,694 | - |
| 4b.1.2.35 | Process Sampling | - | 414 | - | 19 | 14 | 32 | - | 129 | 678 | - | - | - | 758 | 722 | - | - | - | 95,460 | 8,370 | - |
| 4b.1.2.36 | Reactor Recirculation | - | 42 | - | 4 | 6 | 21 | - | 18 | 95 | - | - | - | 140 | 923 | - | - | - | 25,687 | 876 | - |
| 4b.1.2.37 | Reactor Water Clean-up | - | 297 | - | 20 | 21 | 48 | - | 102 | 549 | - | - | - | 1,133 | 1,086 | - | - | - | 141,994 | 5,295 | - |
| 4b.1.2.38 | Residual Heat Removal | - | 481 | - | 87 | 89 | 278 | - | 285 | 1,623 | - | - | - | 6,326 | 4,271 | - | - | - | 648,075 | 10,242 | - |
| 4b.1.2.39 | Screen Wash | - | 6 | - | - | - | - | - | 1 | 7 | - | - | 7 | - | - | - | - | - | - | 132 | - |
| 4b.1.2.40 | Service Air - RCA | - | 230 | - | 4 | 6 | 106 | - | 75 | 421 | - | - | - | 2,476 | - | - | - | - | 100,556 | 4,507 | - |
| 4b.1.2.41 | Service Air Non-RCA | - | 14 | - | - | - | - | - | 2 | 16 | - | - | 16 | - | - | - | - | - | - | 309 | - |
| 4b.1.2.42 | Shutdown Service Water - RCA | - | 92 | - | 2 | 4 | 63 | - | 33 | 195 | - | - | - | 1,481 | - | - | - | - | 60,155 | 1,829 | - |
| 4b.1.2.43 | Shutdown Service Water Non-RCA | - | 99 | - | - | - | - | - | 15 | 114 | - | - | 114 | - | - | - | - | - | - | 2,196 | - |
| 4b.1.2.44 | Solid Radwaste Reprocessing & Disposal | - | 509 | - | 33 | 157 | 132 | - | 192 | 1,057 | - | - | - | 3,684 | 1,568 | - | - | - | 275,491 | 10,528 | - |
| 4b.1.2.45 | Standby Gas Treatment | - | 60 | - | 2 | 22 | 4 | - | 20 | 109 | - | - | - | 513 | 39 | - | - | - | 24,299 | 1,226 | - |
| 4b.1.2.46 | Suppression Pool Cleanup & Transfer | - | 96 | - | 9 | 26 | 43 | - | 41 | 224 | - | - | - | 615 | 453 | - | - | - | 65,567 | 2,006 | - |
| 4b.1.2.47 | Suppression Pool Make-up | - | 44 | - | 7 | 8 | 32 | - | 27 | 154 | - | - | - | 742 | 383 | - | - | - | 64,491 | 947 | - |
| 4b.1.2.48 | Turb OG RW Cntrl & DG Equip Drains | - | 181 | - | 11 | 10 | 18 | - | 63 | 330 | - | - | - | 425 | 512 | - | - | - | 62,620 | 3,649 | - |
| 4b.1.2.49 | Turb OG RW Cntrl & DG Bldg Floor Drains | - | 295 | - | 20 | 19 | 91 | - | 111 | 610 | - | - | - | 2,128 | 890 | - | - | - | 157,436 | 6,080 | - |
| 4b.1.2 | Totals | - | 19,502 | - | 746 | 873 | 7,840 | - | 6,574 | 37,799 | - | - | 2,862 | 183,862 | 25,018 | - | - | - | 9,623,137 | 398,872 | - |
| 4b.1.3 | Scaffolding in support of decommissioning | - | 4,118 | - | 74 | 17 | 210 | - | 1,078 | 5,523 | - | - | - | 4,453 | 277 | - | - | - | 225,261 | 94,887 | - |
| Decommissionation of Site Buildings | | | | | | | | | | | | | | | | | | | | | |
| 4b.1.4.1 | Reactor Building | 2,504 | 3,131 | 412 | 464 | 330 | 1,843 | - | 2,656 | 11,341 | - | - | - | 7,734 | 24,635 | - | - | - | 2,570,182 | 113,912 | - |
| 4b.1.4.2 | Auxiliary Building | 293 | 171 | 29 | 38 | 50 | 87 | - | 895 | 895 | - | - | - | 1,171 | 1,733 | - | - | - | 917,879 | 9,073 | - |
| 4b.1.4.3 | Control Building | 338 | 130 | 29 | 38 | 2 | 91 | - | 253 | 862 | - | - | - | 56 | 1,825 | - | - | - | 184,549 | 9,146 | - |
| 4b.1.4.4 | Diesel Generator Building | 98 | 34 | 8 | 10 | - | 25 | - | 66 | 242 | - | - | - | 300 | 500 | - | - | - | 49,982 | 2,594 | - |
| 4b.1.4.5 | Radwaste Building | 1,148 | 513 | 105 | 140 | 45 | 330 | - | 823 | 3,105 | - | - | - | 1,067 | 6,612 | - | - | - | 701,151 | 32,401 | - |
| 4b.1.4.6 | Turbine Building | 1,027 | 539 | 97 | 129 | 117 | 298 | - | 769 | 2,976 | - | - | - | 2,735 | 5,944 | - | - | - | 689,469 | 30,575 | - |
| 4b.1.4.7 | Fuel Building | 738 | 700 | 33 | 43 | 110 | 94 | - | 594 | 2,312 | - | - | - | 2,574 | 1,829 | - | - | - | 284,744 | 28,187 | - |
| 4b.1.4 | Totals | 6,147 | 5,218 | 714 | 863 | 654 | 2,767 | - | 5,369 | 21,732 | - | - | - | 15,337 | 43,078 | - | - | - | 4,707,935 | 226,888 | - |
| 4b.1 | Subtotal Period 4b Activity Costs | 6,599 | 28,882 | 1,625 | 1,857 | 8,704 | 5,629 | - | 13,425 | 66,722 | - | - | 2,862 | 203,652 | 74,439 | - | - | - | 15,100,620 | 722,664 | - |

Table D
Clinton Power Station
Delayed DECON Decommissioning Cost Estimate
(Thousands of 2007 Dollars)

| Activity Index | Activity Description | Decon Cost | Removal Cost | Packaging Costs | Transport Costs | Off-Site Processing Costs | LLRW Disposal Costs | Other Costs | Total Contingency | Total Lic. Term. Costs | NRC Management Costs | Site Restoration Costs | Processed Volume | | | Burial Volumes | | | Burial / Processed Wt., Lbs. | Craft Manhours | Utility and Contractor Manhours | | |
|---|---|------------|--------------|-----------------|-----------------|---------------------------|---------------------|-------------|-------------------|------------------------|----------------------|------------------------|------------------|----------|----------|------------------|------------------|------------------|------------------------------|----------------|---------------------------------|------------------|------------------|
| | | | | | | | | | | | | | Cu. Feet | Cu. Feet | Cu. Feet | Class A Cu. Feet | Class B Cu. Feet | Class C Cu. Feet | | | | Class A Cu. Feet | Class B Cu. Feet |
| Period 4b Collateral Costs | | | | | | | | | | | | | | | | | | | | | | | |
| 4b.3.1 | Process liquid waste | 218 | - | 80 | 439 | - | 142 | - | 218 | 1,097 | 1,097 | - | - | - | - | - | - | - | - | - | - | - | |
| 4b.3.2 | Small tool allowance | - | 540 | - | - | - | - | - | 81 | 621 | 621 | - | - | - | - | - | - | - | - | - | - | 297 | |
| 4b.3.3 | Decommissioning Equipment Disposition | - | - | 100 | 27 | 284 | 35 | - | 65 | 511 | 511 | - | - | - | - | - | - | - | - | - | - | - | |
| 4b.3 | Subtotal Period 4b Collateral Costs | 218 | 540 | 180 | 466 | 284 | 177 | - | 365 | 2,229 | 2,229 | - | - | - | - | - | - | - | - | - | - | - | |
| Period 4c Period-Dependent Costs | | | | | | | | | | | | | | | | | | | | | | | |
| 4c.4.1 | Decon supplies | 2,169 | - | - | - | - | - | - | 542 | 2,711 | 2,711 | - | - | - | - | - | - | - | - | - | - | - | |
| 4c.4.2 | Insurance | - | - | - | - | - | - | 799 | 80 | 878 | 878 | - | - | - | - | - | - | - | - | - | - | - | |
| 4c.4.3 | Property taxes | - | - | - | - | - | - | 1,574 | 187 | 1,762 | 1,762 | - | - | - | - | - | - | - | - | - | - | - | |
| 4c.4.4 | Health physics supplies | - | 3,103 | - | - | - | - | - | 776 | 3,879 | 3,879 | - | - | - | - | - | - | - | - | - | - | - | |
| 4c.4.5 | Heavy equipment rental | - | 2,663 | - | - | - | - | - | 399 | 3,063 | 3,063 | - | - | - | - | - | - | - | - | - | - | - | |
| 4c.4.6 | Disposal of DAW generated | - | - | 257 | 106 | - | 675 | - | 210 | 1,249 | 1,249 | - | - | - | - | - | - | - | - | - | - | - | |
| 4c.4.7 | Plant energy budget | - | - | - | - | - | - | 1,139 | 171 | 1,309 | 1,309 | - | - | - | - | - | - | - | - | - | - | - | |
| 4c.4.8 | NRC Fees | - | - | - | - | - | - | 54 | 54 | 596 | 596 | - | - | - | - | - | - | - | - | - | - | - | |
| 4c.4.9 | Site O&M Cost | - | - | - | - | - | - | 394 | 59 | 453 | 453 | - | - | - | - | - | - | - | - | - | - | - | |
| 4c.4.10 | Radwaste Processing Equipment/Services | - | - | - | - | - | - | 586 | 88 | 673 | 673 | - | - | - | - | - | - | - | - | - | - | - | |
| 4c.4.11 | Security Staff Cost | - | - | - | - | - | - | 3,883 | 582 | 4,465 | 4,465 | - | - | - | - | - | - | - | - | - | - | - | |
| 4c.4.12 | DOC Staff Cost | - | - | - | - | - | - | 14,266 | 2,140 | 16,406 | 16,406 | - | - | - | - | - | - | - | - | - | - | - | |
| 4c.4.13 | Utility Staff Cost | - | - | - | - | - | - | 24,393 | 3,659 | 28,052 | 28,052 | - | - | - | - | - | - | - | - | - | - | - | |
| 4c.4 | Subtotal Period 4c Period-Dependent Costs | 2,169 | 5,767 | 257 | 106 | - | 675 | 47,574 | 8,918 | 65,467 | 65,467 | - | - | - | - | - | - | - | - | - | - | - | |
| 4c.0 | TOTAL PERIOD 4c COST | 8,986 | 35,188 | 2,063 | 2,429 | 8,988 | 6,481 | 47,574 | 22,708 | 134,418 | 131,555 | 2,862 | 209,652 | 88,434 | - | - | - | - | - | - | 15,738,050 | 729,418 | 710,536 |
| PERIOD 4e - License Termination | | | | | | | | | | | | | | | | | | | | | | | |
| Period 4e Direct Decommissioning Activities | | | | | | | | | | | | | | | | | | | | | | | |
| 4e.1.1 | ORISE confirmatory survey | - | - | - | - | - | - | 141 | 42 | 183 | 183 | - | - | - | - | - | - | - | - | - | - | - | |
| 4e.1.2 | Terminate license | - | - | - | - | - | - | - | - | a | - | - | - | - | - | - | - | - | - | - | - | - | |
| 4e.1 | Subtotal Period 4e Activity Costs | - | - | - | - | - | - | 141 | 42 | 183 | 183 | - | - | - | - | - | - | - | - | - | - | - | |
| Period 4e Additional Costs | | | | | | | | | | | | | | | | | | | | | | | |
| 4e.2.1 | Final Site Survey | - | - | - | - | - | - | 11,020 | 3,306 | 14,326 | 14,326 | - | - | - | - | - | - | - | - | - | - | - | |
| 4e.2 | Subtotal Period 4e Additional Costs | - | - | - | - | - | - | 11,020 | 3,306 | 14,326 | 14,326 | - | - | - | - | - | - | - | - | - | - | - | |
| Period 4e Collateral Costs | | | | | | | | | | | | | | | | | | | | | | | |
| 4e.3.1 | DOC staff relocation expenses | - | - | - | - | - | - | 829 | 124 | 953 | 953 | - | - | - | - | - | - | - | - | - | - | - | |
| 4e.3 | Subtotal Period 4e Collateral Costs | - | - | - | - | - | - | 829 | 124 | 953 | 953 | - | - | - | - | - | - | - | - | - | - | - | |
| Period 4e Period-Dependent Costs | | | | | | | | | | | | | | | | | | | | | | | |
| 4e.4.1 | Insurance | - | - | - | - | - | - | 74 | 7 | 82 | 82 | - | - | - | - | - | - | - | - | - | - | - | |
| 4e.4.2 | Property taxes | - | - | - | - | - | - | 745 | 74 | 819 | 819 | - | - | - | - | - | - | - | - | - | - | - | |
| 4e.4.3 | Health physics supplies | - | 1,032 | - | - | - | - | - | 258 | 1,290 | 1,290 | - | - | - | - | - | - | - | - | - | - | - | |
| 4e.4.4 | Disposal of DAW generated | - | - | - | 3 | - | 21 | - | 7 | 40 | 40 | - | - | - | - | - | - | - | - | - | - | - | |
| 4e.4.5 | Plant energy budget | - | - | 8 | - | - | - | - | 144 | 165 | 165 | - | - | - | - | - | - | - | - | - | - | - | |
| 4e.4.6 | NRC Fees | - | - | - | - | - | - | 956 | 26 | 282 | 282 | - | - | - | - | - | - | - | - | - | - | - | |
| 4e.4.7 | Site O&M Cost | - | - | - | - | - | - | 186 | 28 | 214 | 214 | - | - | - | - | - | - | - | - | - | - | - | |
| 4e.4.8 | Security Staff Cost | - | - | - | - | - | - | 705 | 106 | 811 | 811 | - | - | - | - | - | - | - | - | - | - | - | |
| 4e.4.9 | DOC Staff Cost | - | - | - | - | - | - | 3,905 | 586 | 4,490 | 4,490 | - | - | - | - | - | - | - | - | - | - | - | |
| 4e.4.10 | Utility Staff Cost | - | - | - | - | - | - | 5,167 | 775 | 5,942 | 5,942 | - | - | - | - | - | - | - | - | - | - | - | |
| 4e.4 | Subtotal Period 4e Period-Dependent Costs | - | 1,032 | 8 | 3 | - | 21 | 11,182 | 1,888 | 14,135 | 14,135 | - | - | - | - | - | - | - | - | - | - | - | |
| 4e.0 | TOTAL PERIOD 4e COST | - | 1,032 | 8 | 3 | - | 21 | 23,172 | 5,361 | 29,597 | 29,597 | - | - | - | - | - | - | - | - | - | - | - | |

Table D
Clinton Power Station
Delayed DECON Decommissioning Cost Estimate
(Thousands of 2007 Dollars)

| Activity Index | Activity Description | Decon Cost | Removal Cost | Packaging Costs | Transport Costs | Off-Site Processing Costs | LLRW Disposal Costs | Other Costs | Total Contingency | Total | NRC Lic. Term. Costs | Spent Fuel Management Costs | Site Restoration Costs | Processed Volume Cu. Feet | Burial Volumes | | | Burial / Processed Wt. Lbs. | Craft Manhours | Utility and Contractor Manhours | |
|---|---|------------|--------------|-----------------|-----------------|---------------------------|---------------------|-------------|-------------------|---------|----------------------|-----------------------------|------------------------|---------------------------|------------------|------------------|------------------|-----------------------------|----------------|---------------------------------|-----------|
| | | | | | | | | | | | | | | | Class A Cu. Feet | Class B Cu. Feet | Class C Cu. Feet | | | | |
| PERIOD 4 TOTALS | | 9,276 | 67,310 | 10,693 | 5,790 | 22,229 | 28,308 | 114,009 | 56,287 | 313,902 | 309,805 | - | 4,097 | 505,717 | 177,739 | 1,502 | 287 | 482 | 35,547,720 | 1,392,045 | 1,502,037 |
| PERIOD 5b - Site Restoration | | | | | | | | | | | | | | | | | | | | | |
| Period 5b Direct Decommissioning Activities | | | | | | | | | | | | | | | | | | | | | |
| Demolition of Remaining Site Buildings | | | | | | | | | | | | | | | | | | | | | |
| 5b.1.1.1 | Reactor Building | - | 5,134 | - | - | - | - | - | 770 | 5,904 | - | - | 5,904 | - | - | - | - | - | - | 65,001 | - |
| 5b.1.1.2 | Auxiliary Building | - | 1,945 | - | - | - | - | - | 292 | 2,236 | - | - | 2,236 | - | - | - | - | - | - | 23,242 | - |
| 5b.1.1.3 | Circulating Water Screenhouse | - | 3,165 | - | - | - | - | - | 475 | 3,640 | - | - | 3,640 | - | - | - | - | - | - | 38,383 | - |
| 5b.1.1.4 | Control Building | - | 4,641 | - | - | - | - | - | 696 | 5,337 | - | - | 5,337 | - | - | - | - | - | - | 56,578 | - |
| 5b.1.1.5 | Diesel Generator Building | - | 1,618 | - | - | - | - | - | 243 | 1,860 | - | - | 1,860 | - | - | - | - | - | - | 20,234 | - |
| 5b.1.1.6 | Make-Up Water Pump House | - | 344 | - | - | - | - | - | 52 | 396 | - | - | 396 | - | - | - | - | - | - | 5,100 | - |
| 5b.1.1.7 | Miscellaneous Site Work | - | 1,504 | - | - | - | - | - | 226 | 1,729 | - | - | 1,729 | - | - | - | - | - | - | 21,227 | - |
| 5b.1.1.8 | Miscellaneous Structures | - | 2,442 | - | - | - | - | - | 366 | 2,808 | - | - | 2,808 | - | - | - | - | - | - | 44,561 | - |
| 5b.1.1.9 | Radwaste Building | - | 4,502 | - | - | - | - | - | 675 | 5,177 | - | - | 5,177 | - | - | - | - | - | - | 58,440 | - |
| 5b.1.1.10 | Service Building | - | 353 | - | - | - | - | - | 53 | 406 | - | - | 406 | - | - | - | - | - | - | 5,585 | - |
| 5b.1.1.11 | Transformer and Tank Pads | - | 147 | - | - | - | - | - | 22 | 169 | - | - | 169 | - | - | - | - | - | - | 2,463 | - |
| 5b.1.1.12 | Turbine Building | - | 4,693 | - | - | - | - | - | 704 | 5,397 | - | - | 5,397 | - | - | - | - | - | - | 63,415 | - |
| 5b.1.1.13 | Turbine Pedestal | - | 1,080 | - | - | - | - | - | 162 | 1,243 | - | - | 1,243 | - | - | - | - | - | - | 12,474 | - |
| 5b.1.1.14 | Fuel Building | - | 2,159 | - | - | - | - | - | 324 | 2,483 | - | - | 2,483 | - | - | - | - | - | - | 26,720 | - |
| 5b.1.1 | Totals | - | 33,727 | - | - | - | - | - | 5,059 | 38,786 | - | - | 38,786 | - | - | - | - | - | - | 443,422 | - |
| Site Closeout Activities | | | | | | | | | | | | | | | | | | | | | |
| 5b.1.2 | Back-Fill Site | - | 57 | - | - | - | - | - | 9 | 66 | - | - | 66 | - | - | - | - | - | - | 201 | - |
| 5b.1.3 | Grade & landscape site | - | 1,408 | - | - | - | - | - | 211 | 1,619 | - | - | 1,619 | - | - | - | - | - | - | 4,449 | - |
| 5b.1.4 | Final report to NRC | - | - | - | - | - | - | - | 21 | 163 | 163 | - | - | - | - | - | - | - | - | - | 1,560 |
| 5b.1 | Subtotal Period 5b Activity Costs | - | 35,192 | - | - | - | - | 141 | 5,300 | 40,634 | 163 | - | 40,471 | - | - | - | - | - | - | 448,071 | 1,560 |
| Period 5b Additional Costs | | | | | | | | | | | | | | | | | | | | | |
| 5b.2.1 | Concrete Crushing | - | 1,281 | - | - | - | - | 8 | 183 | 1,482 | - | - | 1,482 | - | - | - | - | - | - | 7,355 | - |
| 5b.2.2 | Screenhouse Cofferdam | - | 934 | - | - | - | - | - | 140 | 1,074 | - | - | 1,074 | - | - | - | - | - | - | 10,159 | - |
| 5b.2.3 | Discharge Flume Backfill | - | 3,741 | - | - | - | - | - | 561 | 4,302 | - | - | 4,302 | - | - | - | - | - | - | 23,931 | - |
| 5b.2.4 | Unit 2 Excavation Backfill | - | 1,226 | - | - | - | - | - | 184 | 1,410 | - | - | 1,410 | - | - | - | - | - | - | 13,128 | - |
| 5b.2 | Subtotal Period 5b Additional Costs | - | 7,183 | - | - | - | - | 8 | 1,079 | 8,269 | - | - | 8,269 | - | - | - | - | - | - | 54,573 | - |
| Period 5b Collateral Costs | | | | | | | | | | | | | | | | | | | | | |
| 5b.3.1 | Small tool allowance | - | 386 | - | - | - | - | - | 58 | 444 | - | - | 444 | - | - | - | - | - | - | - | - |
| 5b.3 | Subtotal Period 5b Collateral Costs | - | 386 | - | - | - | - | - | 58 | 444 | - | - | 444 | - | - | - | - | - | - | - | - |
| Period 5b Period-Dependent Costs | | | | | | | | | | | | | | | | | | | | | |
| 5b.4.1 | Insurance | - | - | - | - | - | - | 226 | 23 | 249 | - | - | 249 | - | - | - | - | - | - | - | - |
| 5b.4.2 | Property taxes | - | - | - | - | - | - | 1,264 | 126 | 1,391 | - | - | 1,391 | - | - | - | - | - | - | - | - |
| 5b.4.3 | Heavy equipment rental | - | 5,246 | - | - | - | - | - | 787 | 6,033 | - | - | 6,033 | - | - | - | - | - | - | - | - |
| 5b.4.4 | Plant energy budget | - | - | - | - | - | - | 218 | 33 | 251 | - | - | 251 | - | - | - | - | - | - | - | - |
| 5b.4.5 | Site O&M Cost | - | - | - | - | - | - | 566 | 85 | 651 | - | - | 651 | - | - | - | - | - | - | - | - |
| 5b.4.6 | Security Staff Cost | - | - | - | - | - | - | 2,145 | 322 | 2,466 | - | - | 2,466 | - | - | - | - | - | - | - | 56,709 |
| 5b.4.7 | DOC Staff Cost | - | - | - | - | - | - | 11,330 | 1,689 | 13,029 | - | - | 13,029 | - | - | - | - | - | - | - | 160,074 |
| 5b.4.8 | Utility Staff Cost | - | - | - | - | - | - | 6,331 | 990 | 7,280 | - | - | 7,280 | - | - | - | - | - | - | - | 92,151 |
| 5b.4 | Subtotal Period 5b Period-Dependent Costs | - | 5,246 | - | - | - | - | 22,080 | 4,024 | 31,350 | - | - | 31,350 | - | - | - | - | - | - | - | 309,534 |
| 5b.0 | TOTAL PERIOD 5b COST | - | 48,007 | - | - | - | - | 22,229 | 10,461 | 80,697 | 163 | - | 80,534 | - | - | - | - | - | - | 502,644 | 311,094 |

Table D
Clinton Power Station
Delayed DECON Decommissioning Cost Estimate
(Thousands of 2007 Dollars)

| Activity Index | Activity Description | Decon Cost | Removal Cost | Packaging Costs | Transport Costs | Off-Site Processing Costs | LLRW Disposal Costs | Other Costs | Total Contingency | Total Costs | NRC Lic. Term. Costs | Spent Fuel Management Costs | Site Restoration Costs | Processed Volume Cu. Feet | Burial Volumes | | | Burial / Processed Wt., Lbs. | Craft Manhours | Utility and Contractor Manhours |
|----------------------------|----------------------|------------|--------------|-----------------|-----------------|---------------------------|---------------------|-------------|-------------------|-------------|----------------------|-----------------------------|------------------------|---------------------------|------------------|------------------|------------------|------------------------------|----------------|---------------------------------|
| | | | | | | | | | | | | | | | Class A Cu. Feet | Class B Cu. Feet | Class C Cu. Feet | | | |
| PERIOD 5 TOTALS | | | 48,007 | | | | | 22,229 | 10,461 | 80,697 | 163 | | 80,534 | | | | | | 502,644 | 311,094 |
| TOTAL COST TO DECOMMISSION | | 19,767 | 120,414 | 10,977 | 6,487 | 22,229 | 29,376 | 419,868 | 113,532 | 742,651 | 476,232 | 181,048 | 85,372 | 505,717 | 482 | 287 | 482 | 35,929,510 | 2,050,463 | 5,402,447 |

| | | |
|---|-----------|---------------------------|
| TOTAL COST TO DECOMMISSION WITH 18.05% CONTINGENCY: | \$742,651 | thousands of 2007 dollars |
| TOTAL NRC LICENSE TERMINATION COST IS 64.13% OR: | \$476,232 | thousands of 2007 dollars |
| SPENT FUEL MANAGEMENT COST IS 24.38% OR: | \$181,048 | thousands of 2007 dollars |
| NON-NUCLEAR DEMOLITION COST IS 11.5% OR: | \$85,372 | thousands of 2007 dollars |
| TOTAL LOW-LEVEL RADIOACTIVE WASTE VOLUME BURIED (EXCLUDING GTCC): | 191,424 | cubic feet |
| TOTAL GREATER THAN CLASS C RADWASTE VOLUME GENERATED: | 482 | cubic feet |
| TOTAL SCRAP METAL REMOVED: | 75,356 | tons |
| TOTAL CRAFT LABOR REQUIREMENTS: | 2,050,463 | man-hours |

End Notes:
na - indicates that this activity not charged as decommissioning expense.
a - indicates that this activity performed by decommissioning staff.
0 - indicates that this value is less than 0.5 but is non-zero.
a cell containing " - " indicates a zero value

APPENDIX E
DETAILED COST ANALYSIS
SAFSTOR

Table E
Clinton Power Station
SAFSTOR Decommissioning Cost Estimate
(Thousands of 2007 Dollars)

| Activity Index | Activity Description | Decon Cost | Removal Cost | Packaging Costs | Transport Costs | Off-Site Processing Costs | LLRW Disposal Costs | Other Costs | Total Contingency | Total Costs | NRC Lic. Term. Costs | Spent Fuel Management Costs | Site Restoration Costs | Processed Volume Cu. Feet | Bridal Volumes | | | Bridal / Processed Wt. Lbs. | Craft Manhours | Utility and Contractor Manhours | |
|--|--|------------|--------------|-----------------|-----------------|---------------------------|---------------------|-------------|-------------------|-------------|----------------------|-----------------------------|------------------------|---------------------------|----------------|---------|---------|-----------------------------|----------------|---------------------------------|--------|
| | | | | | | | | | | | | | | | Class A | Class B | Class C | | | | |
| PERIOD 1a - Shutdown through Transition | | | | | | | | | | | | | | | | | | | | | |
| Period 1a Direct Decommissioning Activities | | | | | | | | | | | | | | | | | | | | | |
| 1a.1.1 | SAFSTOR site characterization survey | - | - | - | - | - | - | 363 | 109 | 471 | 471 | - | - | - | - | - | - | - | - | - | - |
| 1a.1.2 | Prepare preliminary decommissioning cost | - | - | - | - | - | - | 118 | 18 | 136 | 136 | - | - | - | - | - | - | - | - | - | 1,300 |
| 1a.1.3 | Notification of Cessation of Operations | - | - | - | - | - | - | - | a | a | - | - | - | - | - | - | - | - | - | - | - |
| 1a.1.4 | Remove fuel & source material | - | - | - | - | - | - | - | n/a | n/a | - | - | - | - | - | - | - | - | - | - | - |
| 1a.1.5 | Notification of Permanent Defueling | - | - | - | - | - | - | - | a | a | - | - | - | - | - | - | - | - | - | - | - |
| 1a.1.7 | Prepare and submit PSDAR | - | - | - | - | - | - | 181 | 27 | 209 | 209 | - | - | - | - | - | - | - | - | - | 2,000 |
| 1a.1.8 | Review plant dwgs & specs | - | - | - | - | - | - | 118 | 18 | 136 | 136 | - | - | - | - | - | - | - | - | - | 1,300 |
| 1a.1.9 | Perform detailed rad survey | - | - | - | - | - | - | - | a | a | - | - | - | - | - | - | - | - | - | - | - |
| 1a.1.10 | Estimate by-product inventory | - | - | - | - | - | - | 91 | 14 | 104 | 104 | - | - | - | - | - | - | - | - | - | 1,000 |
| 1a.1.11 | End product description | - | - | - | - | - | - | 91 | 14 | 104 | 104 | - | - | - | - | - | - | - | - | - | 1,000 |
| 1a.1.12 | Detailed by-product description | - | - | - | - | - | - | 136 | 20 | 156 | 156 | - | - | - | - | - | - | - | - | - | 1,500 |
| 1a.1.13 | Define major work sequence | - | - | - | - | - | - | 91 | 14 | 104 | 104 | - | - | - | - | - | - | - | - | - | 1,000 |
| 1a.1.14 | Perform SER and EA | - | - | - | - | - | - | 281 | 42 | 323 | 323 | - | - | - | - | - | - | - | - | - | 3,100 |
| 1a.1.15 | Perform Site-Specific Cost Study | - | - | - | - | - | - | 454 | 68 | 522 | 522 | - | - | - | - | - | - | - | - | - | 5,000 |
| Activity Specifications | | | | | | | | | | | | | | | | | | | | | |
| 1a.1.16.1 | Prepare plant and facilities for SAFSTOR | - | - | - | - | - | - | 446 | 67 | 513 | 513 | - | - | - | - | - | - | - | - | - | 4,920 |
| 1a.1.16.2 | Plant systems | - | - | - | - | - | - | 378 | 57 | 435 | 435 | - | - | - | - | - | - | - | - | - | 4,167 |
| 1a.1.16.3 | Plant structures and buildings | - | - | - | - | - | - | 283 | 42 | 325 | 325 | - | - | - | - | - | - | - | - | - | 3,120 |
| 1a.1.16.4 | Waste management | - | - | - | - | - | - | 181 | 27 | 209 | 209 | - | - | - | - | - | - | - | - | - | 2,000 |
| 1a.1.16.5 | Facility and site dormancy | - | - | - | - | - | - | 181 | 27 | 209 | 209 | - | - | - | - | - | - | - | - | - | 2,000 |
| 1a.1.16 | Total | - | - | - | - | - | - | 1,470 | 220 | 1,690 | 1,690 | - | - | - | - | - | - | - | - | - | 16,207 |
| Detailed Work Procedures | | | | | | | | | | | | | | | | | | | | | |
| 1a.1.17.1 | Plant systems | - | - | - | - | - | - | 107 | 16 | 123 | 123 | - | - | - | - | - | - | - | - | - | 1,183 |
| 1a.1.17.2 | Facility closure & dormancy | - | - | - | - | - | - | 109 | 16 | 125 | 125 | - | - | - | - | - | - | - | - | - | 1,200 |
| 1a.1.17 | Total | - | - | - | - | - | - | 216 | 32 | 249 | 249 | - | - | - | - | - | - | - | - | - | 2,383 |
| 1a.1.18 | Pressure vacuum drying system | - | - | - | - | - | - | 9 | 1 | 10 | 10 | - | - | - | - | - | - | - | - | - | 100 |
| 1a.1.19 | Design/procure non-cont. systems | - | - | - | - | - | - | a | a | a | - | - | - | - | - | - | - | - | - | - | - |
| 1a.1.20 | Design/procure contaminated systems | - | - | - | - | - | - | a | a | a | - | - | - | - | - | - | - | - | - | - | - |
| 1a.1.21 | Design/procure contaminated systems | - | - | - | - | - | - | a | a | a | - | - | - | - | - | - | - | - | - | - | - |
| 1a.1.22 | Decommission contaminated systems | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| 1a.1 | Subtotal Period 1a Activity Costs | - | - | - | - | - | - | 3,618 | 597 | 4,215 | 4,215 | - | - | - | - | - | - | - | - | - | 35,890 |
| Period 1a Collateral Costs | | | | | | | | | | | | | | | | | | | | | |
| 1a.3.1 | Spent Fuel Capital and Transfer | - | - | - | - | - | - | 39,540 | 5,931 | 45,471 | - | 45,471 | - | - | - | - | - | - | - | - | - |
| 1a.3 | Subtotal Period 1a Collateral Costs | - | - | - | - | - | - | 39,540 | 5,931 | 45,471 | - | 45,471 | - | - | - | - | - | - | - | - | - |
| Period 1a Period-Dependent Costs | | | | | | | | | | | | | | | | | | | | | |
| 1a.4.1 | Insurance | - | - | - | - | - | - | 1,320 | 132 | 1,452 | 1,452 | - | - | - | - | - | - | - | - | - | - |
| 1a.4.2 | Property taxes | - | - | - | - | - | - | 6,312 | 631 | 6,943 | 6,943 | - | - | - | - | - | - | - | - | - | - |
| 1a.4.3 | Health physics supplies | - | - | - | - | - | - | 377 | 94 | 471 | 471 | - | - | - | - | - | - | - | - | - | - |
| 1a.4.4 | Heavy equipment rental | - | - | - | - | - | - | - | 52 | 401 | 401 | - | - | - | - | - | - | - | - | - | - |
| 1a.4.5 | Disposal of DAW generated | - | - | - | - | - | - | 38 | 12 | 70 | 70 | - | - | - | - | - | - | - | - | - | 21 |
| 1a.4.6 | Plant energy budget | - | - | - | - | - | - | 964 | 145 | 1,108 | 1,108 | - | - | - | - | - | - | - | - | - | - |
| 1a.4.7 | NRC Fees | - | - | - | - | - | - | 258 | 26 | 284 | 284 | - | - | - | - | - | - | - | - | - | - |
| 1a.4.8 | Emergency Planning Fees | - | - | - | - | - | - | 450 | 45 | 495 | - | - | - | - | - | - | - | - | - | - | - |
| 1a.4.9 | Site O&M Cost | - | - | - | - | - | - | 250 | 37 | 287 | 287 | - | - | - | - | - | - | - | - | - | - |

Table E
Clinton Power Station
SAFSTOR Decommissioning Cost Estimate
(Thousands of 2007 Dollars)

| Activity Index | Activity Description | Decon Cost | Removal Cost | Packaging Costs | Transport Costs | Off-Site Processing Costs | LLRW Disposal Costs | Other Costs | Total Contingency | Total Lic. Term. Costs | Spent Fuel Management Costs | Site Restoration Costs | Processed Volume Cu. Feet | Bridal Volumes | | | Bridal / Processed Wt. Lbs. | Craft Manhours | Utility and Contractor Manhours | |
|---|---|------------|--------------|-----------------|-----------------|---------------------------|---------------------|-------------|-------------------|------------------------|-----------------------------|------------------------|---------------------------|------------------|------------------|------------------|-----------------------------|----------------|---------------------------------|---------|
| | | | | | | | | | | | | | | Class A Cu. Feet | Class B Cu. Feet | Class C Cu. Feet | | | | |
| Period 1a Period-Dependent Costs (continued) | | | | | | | | | | | | | | | | | | | | |
| Ia.4.10 | Spent Fuel Pool O&M | - | - | - | - | - | - | 738 | 111 | 849 | - | - | - | - | - | - | - | - | - | |
| Ia.4.11 | ISFSI Operating Costs | - | - | - | - | - | - | 82 | 12 | 94 | - | - | - | - | - | - | - | - | - | |
| Ia.4.12 | Security Staff Cost | - | - | - | - | - | - | 5,955 | 893 | 6,848 | - | - | - | - | - | - | - | - | 157,471 | |
| Ia.4.13 | Utility Staff Cost | - | - | - | - | - | - | 26,183 | 3,927 | 30,110 | - | - | - | - | - | - | - | - | 423,400 | |
| Ia.4 | Subtotal Period 1a Period-Dependent Costs | - | 726 | 14 | 6 | - | 38 | 42,511 | 6,118 | 49,413 | 47,975 | 1,438 | - | - | 675 | - | - | 13,531 | 21 | 860,871 |
| Ia.0 | TOTAL PERIOD 1a COST | - | 726 | 14 | 6 | - | 38 | 85,669 | 12,646 | 98,069 | 52,190 | 46,909 | - | - | 675 | - | - | 13,531 | 21 | 616,761 |
| PERIOD 1b - SAFSTOR Limited DECON Activities | | | | | | | | | | | | | | | | | | | | |
| Period 1b Direct Decommissioning Activities | | | | | | | | | | | | | | | | | | | | |
| Decontamination of Site Buildings | | | | | | | | | | | | | | | | | | | | |
| Ib.1.1.1 | Reactor Building | 2,771 | - | - | - | - | - | - | 1,385 | 4,156 | 4,156 | - | - | - | - | - | - | - | - | 56,016 |
| Ib.1.1.2 | Auxiliary Building | 305 | - | - | - | - | - | - | 153 | 458 | 458 | - | - | - | - | - | - | - | - | 6,485 |
| Ib.1.1.3 | Control Building | 353 | - | - | - | - | - | - | 177 | 530 | 530 | - | - | - | - | - | - | - | - | 7,503 |
| Ib.1.1.4 | Diesel Generator Building | 103 | - | - | - | - | - | - | 51 | 154 | 154 | - | - | - | - | - | - | - | - | 2,182 |
| Ib.1.1.5 | Fuel Building | 800 | - | - | - | - | - | - | 400 | 1,199 | 1,199 | - | - | - | - | - | - | - | - | 16,275 |
| Ib.1.1.6 | Radwaste Building | 1,195 | - | - | - | - | - | - | 597 | 1,792 | 1,792 | - | - | - | - | - | - | - | - | 25,369 |
| Ib.1.1.7 | Turbine Building | 1,069 | - | - | - | - | - | - | 534 | 1,603 | 1,603 | - | - | - | - | - | - | - | - | 22,689 |
| Ib.1.1 | Totals | 6,595 | - | - | - | - | - | - | 3,298 | 9,893 | 9,893 | - | - | - | - | - | - | - | - | 136,519 |
| Ib.1 | Subtotal Period 1b Activity Costs | 6,595 | - | - | - | - | - | - | 3,298 | 9,893 | 9,893 | - | - | - | - | - | - | - | - | 136,519 |
| Period 1b Additional Costs | | | | | | | | | | | | | | | | | | | | |
| Ib.2.1 | Spent Fuel Pool Isolation | - | - | - | - | - | - | 9,133 | 1,370 | 10,503 | 10,503 | - | - | - | - | - | - | - | - | - |
| Ib.2 | Subtotal Period 1b Additional Costs | - | - | - | - | - | - | 9,133 | 1,370 | 10,503 | 10,503 | - | - | - | - | - | - | - | - | - |
| Period 1b Collateral Costs | | | | | | | | | | | | | | | | | | | | |
| Ib.3.1 | Decon equipment | 726 | - | - | - | - | - | - | 109 | 834 | 834 | - | - | - | - | - | - | - | - | 237 |
| Ib.3.2 | Process liquid waste | 179 | - | - | - | - | 113 | - | 177 | 863 | 863 | - | - | - | - | - | - | - | - | - |
| Ib.3.3 | Small fuel allowance | - | 103 | - | - | - | - | 3,000 | 5 | 3,450 | 119 | - | - | - | - | - | - | - | - | - |
| Ib.3.4 | Spent Fuel Capital and Transfer | - | - | - | - | - | - | - | 450 | 3,450 | 3,450 | - | - | - | - | - | - | - | - | - |
| Ib.3 | Subtotal Period 1b Collateral Costs | 904 | 103 | 64 | 351 | - | 113 | 3,000 | 751 | 5,286 | 1,836 | 3,450 | - | - | - | - | - | - | - | 237 |
| Period 1b Period-Dependent Costs | | | | | | | | | | | | | | | | | | | | |
| Ib.4.1 | Decon supplies | 1,899 | - | - | - | - | - | - | 475 | 2,374 | 2,374 | - | - | - | - | - | - | - | - | - |
| Ib.4.2 | Insurance | - | - | - | - | - | - | 333 | 33 | 366 | 366 | - | - | - | - | - | - | - | - | - |
| Ib.4.3 | Property taxes | - | - | - | - | - | - | 1,061 | 106 | 1,167 | 1,167 | - | - | - | - | - | - | - | - | - |
| Ib.4.4 | Health physics supplies | 573 | - | - | - | - | - | - | 143 | 716 | 716 | - | - | - | - | - | - | - | - | - |
| Ib.4.5 | Heavy equipment rental | 88 | - | - | - | - | - | - | 13 | 101 | 101 | - | - | - | - | - | - | - | - | - |
| Ib.4.6 | Disposal of DAW generated | - | - | 32 | 13 | - | 85 | - | 26 | 157 | 157 | - | - | - | - | - | - | - | - | 46 |
| Ib.4.7 | Plant energy budget | - | - | - | - | - | - | 243 | 36 | 279 | 279 | - | - | - | 1,524 | - | - | - | - | - |
| Ib.4.8 | NRC Fees | - | - | - | - | - | - | 65 | 7 | 72 | 72 | - | - | - | - | - | - | - | - | - |
| Ib.4.9 | Emergency Planning Fees | - | - | - | - | - | - | 113 | 11 | 125 | 125 | - | - | - | - | - | - | - | - | - |
| Ib.4.10 | Site O&M Cost | - | - | - | - | - | - | 63 | 9 | 72 | 72 | - | - | - | - | - | - | - | - | - |
| Ib.4.11 | Spent Fuel Pool O&M | - | - | - | - | - | - | 186 | 28 | 214 | 214 | - | - | - | - | - | - | - | - | - |
| Ib.4.12 | ISFSI Operating Costs | - | - | - | - | - | - | 21 | 3 | 24 | 24 | - | - | - | - | - | - | - | - | 39,691 |
| Ib.4.13 | Security Staff Cost | - | - | - | - | - | - | 1,501 | 225 | 1,726 | 1,726 | - | - | - | - | - | - | - | - | 106,720 |
| Ib.4.14 | Utility Staff Cost | - | - | - | - | - | - | 6,599 | 990 | 7,589 | 7,589 | - | - | - | - | - | - | - | - | 146,411 |
| Ib.4 | Subtotal Period 1b Period-Dependent Costs | 1,899 | 661 | 32 | 13 | - | 85 | 10,185 | 2,107 | 14,983 | 14,920 | 382 | - | - | 1,524 | - | - | 30,535 | 46 | 146,411 |
| Ib.0 | TOTAL PERIOD 1b COST | 9,399 | 764 | 96 | 364 | - | 198 | 22,318 | 7,525 | 40,665 | 36,853 | 3,812 | - | - | 2,741 | - | - | 103,560 | 136,803 | 146,411 |

Table E
Clinton Power Station
SAFSTOR Decommissioning Cost Estimate
(Thousands of 2007 Dollars)

| Activity Index | Activity Description | Decon Cost | Removal Cost | Packaging Costs | Transport Costs | Off-Site Processing Costs | LLRW Disposal Costs | Other Costs | Total Contingency | Total Costs | NRC Lic. Term. Costs | Spent Fuel Management Costs | Site Restoration Costs | Processed Volume Cu. Feet | Bridal Volumes | | | Bridal / Processed Wt. Lbs. | Craft Manhours | Utility and Contractor Manhours | |
|--|---|------------|--------------|-----------------|-----------------|---------------------------|---------------------|-------------|-------------------|-------------|----------------------|-----------------------------|------------------------|---------------------------|------------------|------------------|------------------|-----------------------------|----------------|---------------------------------|---------|
| | | | | | | | | | | | | | | | Class A Cu. Feet | Class B Cu. Feet | Class C Cu. Feet | | | | |
| PERIOD 1c - Preparations for SAFSTOR Dormancy | | | | | | | | | | | | | | | | | | | | | |
| Period 1c Direct Decommissioning Activities | | | | | | | | | | | | | | | | | | | | | |
| Ic.1.1 | Prepare support equipment for storage | - | 405 | - | - | - | - | - | 61 | 466 | 466 | - | - | - | - | - | - | - | - | 3,000 | - |
| Ic.1.2 | Install containment pressure equal. lines | - | 35 | - | - | - | - | - | 5 | 41 | 41 | - | - | - | - | - | - | - | - | 700 | - |
| Ic.1.3 | Interim survey prior to dormancy | - | - | - | - | - | - | 733 | 220 | 953 | 953 | - | - | - | - | - | - | - | - | 14,893 | - |
| Ic.1.4 | Secure building accesses | - | - | - | - | - | - | - | a | - | - | - | - | - | - | - | - | - | - | - | - |
| Ic.1.5 | Prepare & submit interim report | - | - | - | - | - | - | 53 | 8 | 61 | 61 | - | - | - | - | - | - | - | - | - | 583 |
| Ic.1 | Subtotal Period 1c Activity Costs | - | 440 | - | - | - | - | 786 | 294 | 1,520 | 1,520 | - | - | - | - | - | - | - | - | 18,593 | 583 |
| Period 1c Collateral Costs | | | | | | | | | | | | | | | | | | | | | |
| Ic.3.1 | Process liquid waste | 133 | - | 47 | 260 | - | 84 | - | 131 | 655 | 655 | - | - | - | - | 904 | - | - | - | 54,218 | 176 |
| Ic.3.2 | Small tool allowance | - | 3 | - | - | - | - | 3,000 | 450 | 3,450 | - | 3,450 | - | - | - | - | - | - | - | - | - |
| Ic.3.3 | Spent Fuel Capital and Transfer | - | - | - | - | - | - | - | 582 | 4,109 | 659 | 3,450 | - | - | - | 904 | - | - | - | - | - |
| Ic.3 | Subtotal Period 1c Collateral Costs | 133 | 3 | 47 | 260 | - | 84 | 3,000 | 582 | 4,109 | 659 | 3,450 | - | - | - | 904 | - | - | - | 54,218 | 176 |
| Period 1c Period-Dependent Costs | | | | | | | | | | | | | | | | | | | | | |
| Ic.4.1 | Insurance | - | - | - | - | - | - | 329 | 33 | 362 | 362 | - | - | - | - | - | - | - | - | - | - |
| Ic.4.2 | Property taxes | - | - | - | - | - | - | 1,049 | 105 | 1,154 | 1,154 | - | - | - | - | - | - | - | - | - | - |
| Ic.4.3 | Health physics supplies | - | 160 | - | - | - | - | - | 40 | 199 | 199 | - | - | - | - | - | - | - | - | - | - |
| Ic.4.4 | Heavy equipment rental | - | 87 | - | - | - | - | - | 13 | 100 | 100 | - | - | - | - | - | - | - | - | - | - |
| Ic.4.5 | Disposal of DAW generated | - | - | 4 | 1 | - | 9 | - | 3 | 17 | 17 | - | - | - | - | 168 | - | - | - | 3,374 | 5 |
| Ic.4.6 | Plant energy budget | - | - | - | - | - | - | 240 | 36 | 276 | 276 | - | - | - | - | - | - | - | - | - | - |
| Ic.4.7 | NRC Fees | - | - | - | - | - | - | 64 | 6 | 71 | 71 | - | - | - | - | - | - | - | - | - | - |
| Ic.4.8 | Emergency Planning Fees | - | - | - | - | - | - | 112 | 11 | 123 | - | - | - | - | - | - | - | - | - | - | - |
| Ic.4.9 | Site O&M Cost | - | - | - | - | - | - | 62 | 9 | 72 | 72 | - | - | - | - | - | - | - | - | - | - |
| Ic.4.10 | Spent Fuel Foot O&M | - | - | - | - | - | - | 184 | 28 | 212 | - | - | - | - | - | - | - | - | - | - | - |
| Ic.4.11 | SFSL Operating Costs | - | - | - | - | - | - | 20 | 3 | 24 | - | - | - | - | - | - | - | - | - | - | - |
| Ic.4.12 | Security Start Cost | - | - | - | - | - | - | 1,465 | 223 | 1,707 | 1,707 | - | - | - | - | - | - | - | - | - | 39,260 |
| Ic.4.13 | Utility Start Cost | - | - | - | - | - | - | 6,928 | 939 | 7,907 | 7,907 | - | - | - | - | - | - | - | - | - | 103,360 |
| Ic.4 | Subtotal Period 1c Period-Dependent Costs | - | 247 | 4 | 1 | - | 9 | 10,074 | 1,469 | 11,824 | 11,466 | 358 | - | - | - | 168 | - | - | - | 3,374 | 5 |
| Ic.0 | TOTAL PERIOD 1c COST | 133 | 680 | 51 | 262 | - | 93 | 13,860 | 2,365 | 17,453 | 13,645 | 3,808 | - | - | - | 1,072 | - | - | - | 57,592 | 18,774 |
| | PERIOD 1 TOTALS | 9,532 | 2,180 | 162 | 632 | - | 329 | 121,847 | 22,536 | 157,217 | 102,688 | 54,530 | - | - | - | 4,488 | - | - | - | 174,703 | 155,598 |
| PERIOD 2a - SAFSTOR Dormancy with Wet Spent Fuel Storage | | | | | | | | | | | | | | | | | | | | | |
| Period 2a Direct Decommissioning Activities | | | | | | | | | | | | | | | | | | | | | |
| 2a.1.1 | Quarterly Inspection | - | - | - | - | - | - | - | a | - | - | - | - | - | - | - | - | - | - | - | - |
| 2a.1.2 | Semi-annual environmental survey | - | - | - | - | - | - | - | a | - | - | - | - | - | - | - | - | - | - | - | - |
| 2a.1.3 | Prepare reports | - | - | - | - | - | - | 500 | 75 | 575 | - | 575 | - | - | - | - | - | - | - | - | - |
| 2a.1.4 | Bituminous roof replacement | - | - | - | - | - | - | 503 | 126 | 629 | - | 629 | - | - | - | - | - | - | - | - | - |
| 2a.1.5 | Maintenance supplies | - | - | - | - | - | - | 1,003 | 201 | 1,203 | - | 1,203 | - | - | - | - | - | - | - | - | - |
| 2a.1 | Subtotal Period 2a Activity Costs | - | - | - | - | - | - | 1,003 | 201 | 1,203 | - | 1,203 | - | - | - | - | - | - | - | - | - |
| Period 2a Collateral Costs | | | | | | | | | | | | | | | | | | | | | |
| 2a.3.1 | Spent Fuel Capital and Transfer | - | - | - | - | - | - | 45,000 | 6,750 | 51,750 | - | 51,750 | - | - | - | - | - | - | - | - | - |
| 2a.3 | Subtotal Period 2a Collateral Costs | - | - | - | - | - | - | 45,000 | 6,750 | 51,750 | - | 51,750 | - | - | - | - | - | - | - | - | - |

Table E
Clinton Power Station
SAFSTOR Decommissioning Cost Estimate
(Thousands of 2007 Dollars)

| Activity Index | Activity Description | Decon Cost | Removal Cost | Packaging Costs | Transport Costs | Off-Site Processing Costs | LLRW Disposal Costs | Other Costs | Total Contingency | Total Costs | NRC Lic. Term. Costs | Spent Fuel Management Costs | Site Restoration Costs | Processed Volume - Cu. Feet | Bridal Volumes | | | Bridal / Processed Wt. Lbs. | Craft Manhours | Utility and Contractor Manhours | | |
|--|--|------------|--------------|-----------------|-----------------|---------------------------|---------------------|-------------|-------------------|-------------|----------------------|-----------------------------|------------------------|-----------------------------|--------------------|--------------------|--------------------|-----------------------------|----------------|---------------------------------|---------|---------|
| | | | | | | | | | | | | | | | Class A - Cu. Feet | Class B - Cu. Feet | Class C - Cu. Feet | | | | | |
| Period 2a - Period-Dependent Costs | | | | | | | | | | | | | | | | | | | | | | |
| 2a.4.1 | Insurance | - | - | - | - | - | - | 2,028 | 203 | 2,230 | - | - | - | - | - | - | - | - | - | - | - | |
| 2a.4.2 | Property taxes | - | - | - | - | - | - | 5,603 | 560 | 6,163 | - | - | - | - | - | - | - | - | - | - | - | |
| 2a.4.3 | Health physics supplies | - | 344 | - | - | - | - | - | 86 | 430 | - | - | - | - | - | - | - | - | - | - | - | |
| 2a.4.4 | Disposal of DAW generated | - | - | 39 | 16 | - | 101 | - | 32 | 187 | - | - | 1,815 | - | - | - | - | - | - | 36,370 | 55 | |
| 2a.4.5 | Plant energy budget | - | - | - | - | - | - | 771 | 116 | 887 | - | - | - | - | - | - | - | - | - | - | - | |
| 2a.4.6 | NRC Fees | - | - | - | - | - | - | 863 | 86 | 949 | - | - | - | - | - | - | - | - | - | - | - | |
| 2a.4.7 | Emergency Planning Fees | - | - | - | - | - | - | 799 | 80 | 879 | - | - | - | - | - | - | - | - | - | - | - | |
| 2a.4.8 | Site O&M Cost | - | - | - | - | - | - | 999 | 150 | 1,149 | - | - | - | - | - | - | - | - | - | - | - | |
| 2a.4.9 | Spent Fuel Pool O&M | - | - | - | - | - | - | 2,952 | 443 | 3,394 | - | - | - | - | - | - | - | - | - | - | - | |
| 2a.4.10 | ISFSI Operating Costs | - | - | - | - | - | - | 328 | 49 | 378 | - | - | - | - | - | - | - | - | - | - | - | |
| 2a.4.11 | Security Staff Cost | - | - | - | - | - | - | 16,801 | 2,520 | 19,321 | - | - | - | - | - | - | - | - | - | - | 444,257 | |
| 2a.4.12 | Utility Staff Cost | - | - | - | - | - | - | 20,888 | 3,133 | 24,021 | - | - | - | - | - | - | - | - | - | - | 308,686 | |
| 2a.4 | Subtotal Period 2a, Period-Dependent Costs | - | 344 | 39 | 16 | - | 101 | 52,031 | 7,458 | 59,989 | - | - | - | - | - | - | - | - | - | 36,370 | 55 | 752,943 |
| 2a.0 | TOTAL PERIOD 2a COST | - | 344 | 39 | 16 | - | 101 | 98,034 | 14,408 | 112,942 | - | - | - | - | - | - | - | - | - | 36,370 | 55 | 752,943 |
| PERIOD 2b - SAFSTOR Dormancy with Dry Spent Fuel Storage | | | | | | | | | | | | | | | | | | | | | | |
| Period 2b Direct Decommissioning Activities | | | | | | | | | | | | | | | | | | | | | | |
| 2b.1.1 | Quarterly Inspection | - | - | - | - | - | - | - | a | a | - | - | - | - | - | - | - | - | - | - | - | - |
| 2b.1.2 | Semi-annual environmental survey | - | - | - | - | - | - | - | a | a | - | - | - | - | - | - | - | - | - | - | - | - |
| 2b.1.3 | Prepare reports | - | - | - | - | - | - | 845 | 127 | 972 | - | - | - | - | - | - | - | - | - | - | - | - |
| 2b.1.4 | Bituminous roof replacement | - | - | - | - | - | - | 850 | 212 | 1,062 | - | - | - | - | - | - | - | - | - | - | - | - |
| 2b.1.5 | Maintenance supplies | - | - | - | - | - | - | 1,695 | 339 | 2,034 | - | - | - | - | - | - | - | - | - | - | - | - |
| 2b.1 | Subtotal Period 2b Activity Costs | - | - | - | - | - | - | 8,000 | 1,200 | 9,200 | - | - | - | - | - | - | - | - | - | - | - | - |
| Period 2b Collateral Costs | | | | | | | | | | | | | | | | | | | | | | |
| 2b.3.1 | Spent Fuel Capital and Transfer | - | - | - | - | - | - | 8,000 | 1,200 | 9,200 | - | - | - | - | - | - | - | - | - | - | - | - |
| 2b.3 | Subtotal Period 2b Collateral Costs | - | - | - | - | - | - | 8,000 | 1,200 | 9,200 | - | - | - | - | - | - | - | - | - | - | - | - |
| 2b.0 | TOTAL PERIOD 2b COST | - | - | - | - | - | - | 16,000 | 2,400 | 18,400 | - | - | - | - | - | - | - | - | - | - | - | - |
| PERIOD 2c - SAFSTOR Dormancy without Spent Fuel Storage | | | | | | | | | | | | | | | | | | | | | | |
| Period 2c Direct Decommissioning Activities | | | | | | | | | | | | | | | | | | | | | | |
| 2c.1.1 | Quarterly Inspection | - | - | - | - | - | - | 3,172 | 317 | 3,489 | - | - | - | - | - | - | - | - | - | - | - | - |
| 2c.1.2 | Semi-annual environmental survey | - | - | - | - | - | - | 6,757 | 676 | 7,433 | - | - | - | - | - | - | - | - | - | - | - | - |
| 2c.1.3 | Prepare reports | - | - | - | - | - | - | 496 | 124 | 620 | - | - | - | - | - | - | - | - | - | - | - | - |
| 2c.1.4 | Disposal of DAW generated | - | - | 61 | 25 | - | 161 | - | 50 | 297 | - | - | 2,578 | - | - | - | - | - | - | - | - | 88 |
| 2c.1.5 | Plant energy budget | - | - | - | - | - | - | 652 | 98 | 749 | - | - | - | - | - | - | - | - | - | - | - | - |
| 2c.1.6 | NRC Fees | - | - | - | - | - | - | 1,458 | 146 | 1,604 | - | - | - | - | - | - | - | - | - | - | - | - |
| 2c.1.7 | Emergency Planning Fees | - | - | - | - | - | - | 1,351 | 135 | 1,487 | - | - | - | - | - | - | - | - | - | - | - | - |
| 2c.1.8 | Site O&M Cost | - | - | - | - | - | - | 1,689 | 253 | 1,943 | - | - | - | - | - | - | - | - | - | - | - | - |
| 2c.1.9 | ISFSI Operating Costs | - | - | - | - | - | - | 555 | 83 | 638 | - | - | - | - | - | - | - | - | - | - | - | - |
| 2c.1.10 | Security Staff Cost | - | - | - | - | - | - | 14,400 | 2,160 | 16,560 | - | - | - | - | - | - | - | - | - | - | - | 380,777 |
| 2c.1.11 | Utility Staff Cost | - | - | - | - | - | - | 13,994 | 2,099 | 16,093 | - | - | - | - | - | - | - | - | - | - | - | 225,646 |
| 2c.1 | Subtotal Period 2c, Period-Dependent Costs | - | 496 | 61 | 25 | - | 161 | 44,028 | 6,141 | 50,913 | - | - | - | - | - | - | - | - | - | - | - | 57,682 |
| 2c.0 | TOTAL PERIOD 2c COST | - | 496 | 61 | 25 | - | 161 | 53,723 | 7,681 | 62,147 | - | - | - | - | - | - | - | - | - | - | - | 57,682 |
| PERIOD 2d - SAFSTOR Dormancy without Spent Fuel Storage | | | | | | | | | | | | | | | | | | | | | | |
| Period 2d Direct Decommissioning Activities | | | | | | | | | | | | | | | | | | | | | | |
| 2d.1.1 | Quarterly Inspection | - | - | - | - | - | - | 3,172 | 317 | 3,489 | - | - | - | - | - | - | - | - | - | - | - | - |
| 2d.1.2 | Semi-annual environmental survey | - | - | - | - | - | - | 6,757 | 676 | 7,433 | - | - | - | - | - | - | - | - | - | - | - | - |
| 2d.1.3 | Prepare reports | - | - | - | - | - | - | 496 | 124 | 620 | - | - | - | - | - | - | - | - | - | - | - | - |
| 2d.1.4 | Disposal of DAW generated | - | - | - | - | - | - | 845 | 127 | 972 | - | - | - | - | - | - | - | - | - | - | - | - |
| 2d.1.5 | Maintenance supplies | - | - | - | - | - | - | 1,695 | 339 | 2,034 | - | - | - | - | - | - | - | - | - | - | - | - |
| 2d.1 | Subtotal Period 2d Activity Costs | - | - | - | - | - | - | 8,000 | 1,200 | 9,200 | - | - | - | - | - | - | - | - | - | - | - | - |
| 2d.0 | TOTAL PERIOD 2d COST | - | - | - | - | - | - | 8,000 | 1,200 | 9,200 | - | - | - | - | - | - | - | - | - | - | - | - |

Table E
Clinton Power Station
SAFSTOR Decommissioning Cost Estimate
(Thousands of 2007 Dollars)

| Activity Index | Activity Description | Decon Cost | Removal Cost | Packaging Costs | Transport Costs | Off-Site Processing Costs | LLRW Disposal Costs | Other Costs | Total Contingency | Total Costs | NRC Lic. Term. Costs | Spent Fuel Management Costs | Site Restoration Costs | Processed Volume - Cu. Feet | Bridal Volumes | | | Bridal / Processed Wt. Lbs. | Craft Manhours | Utility and Contractor Manhours | | |
|--|--|------------|--------------|-----------------|-----------------|---------------------------|---------------------|-------------|-------------------|-------------|----------------------|-----------------------------|------------------------|-----------------------------|--------------------|--------------------|--------------------|-----------------------------|----------------|---------------------------------|-----------|-----------|
| | | | | | | | | | | | | | | | Class A - Cu. Feet | Class B - Cu. Feet | Class C - Cu. Feet | | | | | |
| 2c.1.5 | Maintenance supplies | - | - | - | - | - | - | 5,364 | 1,341 | 6,706 | 6,706 | - | - | - | - | - | - | - | - | - | - | |
| 2c.1 | Subtotal Period 2c. Activity Costs | - | - | - | - | - | - | 10,697 | 2,141 | 12,839 | 12,839 | - | - | - | - | - | - | - | - | - | - | |
| Period 2c. Period-Dependent Costs | | | | | | | | | | | | | | | | | | | | | | |
| 2c.4.1 | Insurance | - | - | - | - | - | - | 19,538 | 1,954 | 21,492 | 21,492 | - | - | - | - | - | - | - | - | - | - | |
| 2c.4.2 | Property taxes | - | - | - | - | - | - | 42,647 | 4,265 | 46,912 | 46,912 | - | - | - | - | - | - | - | - | - | - | |
| 2c.4.3 | Health physics supplies | - | - | - | - | - | - | - | 736 | 3,682 | 3,682 | - | - | - | - | - | - | - | - | - | - | |
| 2c.4.4 | Disposal of DAW generated | - | 2,946 | - | - | - | - | - | 309 | 1,833 | 1,833 | - | - | - | - | - | - | - | - | - | - | |
| 2c.4.5 | Plant energy budget | - | - | 378 | 156 | - | 991 | - | 617 | 4,729 | 4,729 | - | - | - | - | - | - | - | - | - | 542 | |
| 2c.4.6 | NRC Fees | - | - | - | - | - | - | 4,112 | 920 | 10,124 | 10,124 | - | - | - | - | - | - | - | - | - | - | |
| 2c.4.7 | Site O&M Cost | - | - | - | - | - | - | 9,203 | 920 | 10,124 | 10,124 | - | - | - | - | - | - | - | - | - | - | |
| 2c.4.8 | Security Staff Cost | - | - | - | - | - | - | 10,662 | 1,599 | 12,261 | 12,261 | - | - | - | - | - | - | - | - | - | - | |
| 2c.4.9 | Utility Staff Cost | - | - | - | - | - | - | 50,493 | 7,574 | 58,066 | 58,066 | - | - | - | - | - | - | - | - | - | 1,335,171 | |
| 2c.4 | Subtotal Period 2c. Period-Dependent Costs | - | 2,946 | 378 | 156 | - | 991 | 185,412 | 25,288 | 215,169 | 215,169 | - | - | - | - | - | - | - | - | - | 778,850 | |
| 2c.0 | TOTAL PERIOD 2c. COST | - | 2,946 | 378 | 156 | - | 991 | 196,109 | 27,429 | 228,008 | 228,008 | - | - | - | - | - | - | - | - | - | 542 | 2,114,021 |
| PERIOD 2 TOTALS | | | | | | | | | | | | | | | | | | | | | | |
| - | | 3,786 | 478 | 197 | - | 1,253 | 347,866 | 49,518 | 403,097 | 403,097 | 403,097 | 175,089 | - | - | - | - | - | - | - | - | 685 | 3,473,387 |
| PERIOD 3a - Reactivate Site Following SAFSTOR Dormancy | | | | | | | | | | | | | | | | | | | | | | |
| Period 3a Direct Decommissioning Activities | | | | | | | | | | | | | | | | | | | | | | |
| 3a.1.1 | Prepare preliminary decommissioning cost | - | - | - | - | - | - | 118 | 18 | 136 | 136 | - | - | - | - | - | - | - | - | - | - | 1,300 |
| 3a.1.2 | Review plant dwgs & specs. | - | - | - | - | - | - | 417 | 63 | 480 | 480 | - | - | - | - | - | - | - | - | - | - | 4,167 |
| 3a.1.3 | Perform detailed rad survey | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | 4,600 |
| 3a.1.4 | End product description | - | - | - | - | - | - | 91 | 14 | 104 | 104 | - | - | - | - | - | - | - | - | - | - | 1,000 |
| 3a.1.5 | Detailed by-product inventory | - | - | - | - | - | - | 118 | 18 | 136 | 136 | - | - | - | - | - | - | - | - | - | - | 1,300 |
| 3a.1.6 | Define major work sequence | - | - | - | - | - | - | 680 | 102 | 782 | 782 | - | - | - | - | - | - | - | - | - | - | 7,500 |
| 3a.1.7 | Perform SER and EA | - | - | - | - | - | - | 281 | 42 | 323 | 323 | - | - | - | - | - | - | - | - | - | - | 3,000 |
| 3a.1.8 | Perform Site-Specific Cost Study | - | - | - | - | - | - | 404 | 66 | 322 | 322 | - | - | - | - | - | - | - | - | - | - | 5,000 |
| 3a.1.9 | Prepare/submit License Termination Plan | - | - | - | - | - | - | 372 | 56 | 427 | 427 | - | - | - | - | - | - | - | - | - | - | 4,096 |
| 3a.1.10 | Receive NRC approval of termination plan | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| Activity Specifications | | | | | | | | | | | | | | | | | | | | | | |
| 3a.1.11.1 | Re-activate plant & temporary facilities | - | - | - | - | - | - | 668 | 100 | 769 | 692 | - | 77 | - | - | - | - | - | - | - | - | 7,370 |
| 3a.1.11.2 | Plant systems | - | - | - | - | - | - | 378 | 57 | 435 | 391 | - | 43 | - | - | - | - | - | - | - | - | 4,167 |
| 3a.1.11.3 | Reactor internals | - | - | - | - | - | - | 644 | 97 | 741 | 741 | - | - | - | - | - | - | - | - | - | - | 7,100 |
| 3a.1.11.4 | Reactor vessel | - | - | - | - | - | - | 590 | 88 | 678 | 678 | - | - | - | - | - | - | - | - | - | - | 6,500 |
| 3a.1.11.5 | Sacrificial shield | - | - | - | - | - | - | 45 | 7 | 52 | 52 | - | - | - | - | - | - | - | - | - | - | 500 |
| 3a.1.11.6 | Moisture separators/reheaters | - | - | - | - | - | - | 91 | 14 | 104 | 104 | - | - | - | - | - | - | - | - | - | - | 1,000 |
| 3a.1.11.7 | Reinforced concrete | - | - | - | - | - | - | 145 | 22 | 167 | 83 | - | 83 | - | - | - | - | - | - | - | - | 1,600 |
| 3a.1.11.8 | Main Turbine | - | - | - | - | - | - | 189 | 28 | 218 | 218 | - | - | - | - | - | - | - | - | - | - | 2,088 |
| 3a.1.11.9 | Main Condensers | - | - | - | - | - | - | 189 | 28 | 218 | 218 | - | - | - | - | - | - | - | - | - | - | 2,088 |
| 3a.1.11.10 | Pressure suppression structure | - | - | - | - | - | - | 181 | 27 | 209 | 209 | - | - | - | - | - | - | - | - | - | - | 2,000 |
| 3a.1.11.11 | Drywell | - | - | - | - | - | - | 145 | 22 | 167 | 167 | - | - | - | - | - | - | - | - | - | - | 1,600 |
| 3a.1.11.12 | Plant structures & buildings | - | - | - | - | - | - | 283 | 42 | 325 | 163 | - | 163 | - | - | - | - | - | - | - | - | 3,120 |
| 3a.1.11.13 | Waste management | - | - | - | - | - | - | 417 | 63 | 480 | 480 | - | - | - | - | - | - | - | - | - | - | 4,600 |
| 3a.1.11.14 | Facility & site dosout | - | - | - | - | - | - | 82 | 12 | 94 | 47 | - | 47 | - | - | - | - | - | - | - | - | 900 |
| 3a.1.11 | Total | - | - | - | - | - | - | 4,048 | 607 | 4,655 | 4,242 | - | 413 | - | - | - | - | - | - | - | - | 44,633 |
| Planning & Site Preparations | | | | | | | | | | | | | | | | | | | | | | |
| 3a.1.12 | Prepare dismantling sequence | - | - | - | - | - | - | 218 | 33 | 250 | 250 | - | - | - | - | - | - | - | - | - | - | 2,400 |
| 3a.1.13 | Plant prep. & temp. evacs | - | - | - | - | - | - | 2,419 | 363 | 2,782 | 2,782 | - | - | - | - | - | - | - | - | - | - | - |

Table E
Clinton Power Station
SAFSTOR Decommissioning Cost Estimate
(Thousands of 2007 Dollars)

| Activity Index | Activity Description | Decon Cost | Removal Cost | Packaging Costs | Transport Costs | Off-Site Processing Costs | LLRW Disposal Costs | Other Costs | Total Contingency | Total Costs | NRC Lic. Term. Costs | Spent Fuel Management Costs | Site Restoration Costs | Processed Volume Cu. Feet | Bridal Volumes | | | Bridal / Processed Wt. Lbs. | Craft Manhours | Utility and Contractor Manhours | | | |
|---|--|------------|--------------|-----------------|-----------------|---------------------------|---------------------|-------------|-------------------|-------------|----------------------|-----------------------------|------------------------|---------------------------|------------------|------------------|------------------|-----------------------------|----------------|---------------------------------|-------|--------|---------|
| | | | | | | | | | | | | | | | Class A Cu. Feet | Class B Cu. Feet | Class C Cu. Feet | | | | | | |
| 3a.1.1.4 | Design water clean-up system | - | - | - | - | - | - | 127 | 19 | 146 | 146 | - | - | - | - | - | - | - | - | - | 1,400 | | |
| 3a.1.1.5 | Rigging/Cost. Core Evaporator/cooling/etc. | - | - | - | - | - | - | 2,048 | 307 | 2,355 | 2,355 | - | - | - | - | - | - | - | - | - | - | 1,230 | |
| 3a.1.1.6 | Presence cash/liners & containers | - | - | - | - | - | - | 112 | 17 | 128 | 128 | - | - | - | - | - | - | - | - | - | - | 77,550 | |
| 3a.1 | Subtotal Period 3a Activity Costs | - | - | - | - | - | - | 11,501 | 1,725 | 13,227 | 12,813 | - | 413 | - | - | - | - | - | - | - | - | - | |
| 3a.3 | Subtotal Period 3a Collateral Costs | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | |
| 3a.4.1 | Period-Dependent Costs | - | - | - | - | - | - | 458 | 46 | 504 | 504 | - | - | - | - | - | - | - | - | - | - | - | |
| 3a.4.2 | Insurance | - | - | - | - | - | - | 999 | 100 | 1,099 | 1,099 | - | - | - | - | - | - | - | - | - | - | - | |
| 3a.4.3 | Property taxes | - | - | - | - | - | - | - | 82 | 412 | 412 | - | - | - | - | - | - | - | - | - | - | - | |
| 3a.4.4 | Health physics supplies | 330 | - | - | - | - | - | - | 52 | 401 | 401 | - | - | - | - | - | - | - | - | - | - | - | |
| 3a.4.5 | Heavy equipment rental | 349 | - | - | - | - | - | - | 10 | 59 | 59 | - | - | - | - | - | - | - | - | - | - | - | |
| 3a.4.6 | Disposal of DAW generated | - | - | 12 | 5 | - | 32 | - | 145 | 1,108 | 1,108 | - | - | - | - | - | - | - | - | - | - | 17 | |
| 3a.4.7 | Plant energy budget | - | - | - | - | - | - | 964 | 26 | 284 | 284 | - | - | - | - | - | - | - | - | - | - | - | |
| 3a.4.8 | Plant energy budget | - | - | - | - | - | - | 258 | 26 | 284 | 284 | - | - | - | - | - | - | - | - | - | - | - | |
| 3a.4.9 | Site O&M Cost | - | - | - | - | - | - | 250 | 37 | 287 | 287 | - | - | - | - | - | - | - | - | - | - | - | |
| 3a.4.10 | Security Staff Cost | - | - | - | - | - | - | 2,465 | 370 | 2,835 | 2,835 | - | - | - | - | - | - | - | - | - | - | - | |
| 3a.4.11 | Utility Staff Cost | - | - | - | - | - | - | 16,145 | 2,422 | 18,566 | 18,566 | - | - | - | - | - | - | - | - | - | - | - | |
| 3a.4 | Subtotal Period 3a Period-Dependent Costs | - | 678 | 12 | 5 | - | 32 | 21,539 | 3,290 | 25,556 | 25,556 | - | - | 570 | - | - | - | - | - | - | - | 17 | 323,807 |
| 3a.0 | TOTAL PERIOD 3a COST | - | 678 | 12 | 5 | - | 32 | 33,040 | 5,015 | 38,782 | 38,369 | - | 413 | - | - | - | - | - | - | - | - | 17 | 401,366 |
| PERIOD 3b - Decommissioning Preparations | | | | | | | | | | | | | | | | | | | | | | | |
| Period 3b Direct Decommissioning Activities | | | | | | | | | | | | | | | | | | | | | | | |
| Detailed Work Procedures | | | | | | | | | | | | | | | | | | | | | | | |
| 3b.1.1.1 | Plant systems | - | - | - | - | - | - | 429 | 64 | 494 | 444 | - | - | - | - | - | - | - | - | - | - | - | 4,733 |
| 3b.1.1.2 | Reactor internals | - | - | - | - | - | - | 363 | 54 | 417 | 417 | - | - | - | - | - | - | - | - | - | - | - | 4,000 |
| 3b.1.1.3 | Remaining buildings | - | - | - | - | - | - | 122 | 18 | 141 | 135 | - | - | - | - | - | - | - | - | - | - | - | 1,580 |
| 3b.1.1.4 | CRD housings & NIS | - | - | - | - | - | - | 91 | 14 | 104 | 104 | - | - | - | - | - | - | - | - | - | - | - | 1,000 |
| 3b.1.1.5 | Incore instrumentation | - | - | - | - | - | - | 181 | 27 | 209 | 209 | - | - | - | - | - | - | - | - | - | - | - | 1,000 |
| 3b.1.1.6 | Remove primary containment | - | - | - | - | - | - | 329 | 49 | 379 | 379 | - | - | - | - | - | - | - | - | - | - | - | 3,620 |
| 3b.1.1.7 | Reactor | - | - | - | - | - | - | 109 | 16 | 125 | 125 | - | - | - | - | - | - | - | - | - | - | - | 1,200 |
| 3b.1.1.8 | Fueler chestout | - | - | - | - | - | - | 109 | 16 | 125 | 125 | - | - | - | - | - | - | - | - | - | - | - | 1,200 |
| 3b.1.1.9 | Sacrificial shield | - | - | - | - | - | - | 91 | 14 | 104 | 52 | - | - | - | - | - | - | - | - | - | - | - | 2,080 |
| 3b.1.1.10 | Reinforced concrete | - | - | - | - | - | - | 189 | 28 | 217 | 217 | - | - | - | - | - | - | - | - | - | - | - | 2,080 |
| 3b.1.1.11 | Main Turbine | - | - | - | - | - | - | 189 | 28 | 217 | 217 | - | - | - | - | - | - | - | - | - | - | - | 2,088 |
| 3b.1.1.12 | Main Condensers | - | - | - | - | - | - | 181 | 27 | 209 | 209 | - | - | - | - | - | - | - | - | - | - | - | 2,000 |
| 3b.1.1.13 | Moisture separators & reheaters | - | - | - | - | - | - | 248 | 37 | 285 | 256 | - | - | - | - | - | - | - | - | - | - | - | 2,730 |
| 3b.1.1.14 | Radiation building | - | - | - | - | - | - | 248 | 37 | 285 | 256 | - | - | - | - | - | - | - | - | - | - | - | 2,730 |
| 3b.1.1.15 | Reactor building | - | - | - | - | - | - | 2,970 | 445 | 3,415 | 3,088 | - | - | - | - | - | - | - | - | - | - | - | 32,741 |
| 3b.1.1 | Total | - | - | - | - | - | - | 2,970 | 445 | 3,415 | 3,088 | - | - | - | - | - | - | - | - | - | - | - | 32,741 |
| 3b.1 | Subtotal Period 3b Activity Costs | - | - | - | - | - | - | 2,970 | 445 | 3,415 | 3,088 | - | - | - | - | - | - | - | - | - | - | - | 32,741 |
| Period 3b Additional Costs | | | | | | | | | | | | | | | | | | | | | | | |
| 3b.2.1 | Site Characterization | - | - | - | - | - | - | 897 | 269 | 1,167 | 1,167 | - | - | - | - | - | - | - | - | - | - | - | - |
| 3b.2.2 | hazardous liquid disposal | - | - | - | 7 | - | 411 | - | 104 | 523 | 523 | - | - | - | - | - | - | - | - | - | - | - | 89,546 |
| 3b.2.3 | Contaminated asbestos disposal | - | - | - | 8 | - | 5 | - | 2 | 15 | 15 | - | - | - | - | - | - | - | - | - | - | - | 1,800 |
| 3b.2.4 | Clean asbestos disposal | - | - | - | - | - | - | 2 | 0 | 2 | 2 | - | - | - | - | - | - | - | - | - | - | - | - |
| 3b.2 | Subtotal Period 3b Additional Costs | - | - | - | 15 | - | 416 | 900 | 376 | 1,707 | 1,707 | - | - | - | - | - | - | - | - | - | - | - | 91,346 |

Table E
Clinton Power Station
SAFSTOR Decommissioning Cost Estimate
(Thousands of 2007 Dollars)

| Activity Index | Activity Description | Decon Cost | Removal Cost | Packaging Costs | Transport Costs | Off-Site Processing Costs | LLRW Disposal Costs | Other Costs | Total Contingency | Total Costs | NRC Lic. Term. Costs | Spent Fuel Management Costs | Site Restoration Costs | Processed Volume Cu. Feet | Bridal Volumes | | | Bridal/Processed Wt. Lbs. | Craft Manhours | Utility and Contractor Manhours | |
|--|---|------------|--------------|-----------------|-----------------|---------------------------|---------------------|-------------|-------------------|-------------|----------------------|-----------------------------|------------------------|---------------------------|------------------|------------------|------------------|---------------------------|----------------|---------------------------------|---------|
| | | | | | | | | | | | | | | | Class A Cu. Feet | Class B Cu. Feet | Class C Cu. Feet | | | | |
| Period 3b Collateral Costs | | | | | | | | | | | | | | | | | | | | | |
| 3b.3.1 | Decon equipment | 726 | - | - | - | - | - | - | 109 | 834 | 834 | - | - | - | - | - | - | - | - | - | - |
| 3b.3.2 | DOC staff relocation expenses | - | - | - | - | - | - | 829 | - | 829 | - | - | - | - | - | - | - | - | - | - | - |
| 3b.3.3 | Pipe cutting equipment | - | 957 | - | - | - | - | - | 143 | 1,100 | 1,100 | - | - | - | - | - | - | - | - | - | - |
| 3b.3 | Subtotal Period 3b Collateral Costs | 726 | 957 | - | - | - | - | 829 | 377 | 2,887 | 2,887 | - | - | - | - | - | - | - | - | - | - |
| Period 3b Period-Dependent Costs | | | | | | | | | | | | | | | | | | | | | |
| 3b.4.1 | Decon supplies | 22 | - | - | - | - | - | - | 6 | 28 | 28 | - | - | - | - | - | - | - | - | - | - |
| 3b.4.2 | Insurance | - | - | - | - | - | - | 254 | 25 | 280 | 280 | - | - | - | - | - | - | - | - | - | - |
| 3b.4.3 | Property taxes | - | - | - | - | - | - | 501 | 50 | 551 | 551 | - | - | - | - | - | - | - | - | - | - |
| 3b.4.4 | Health physics supplies | - | 182 | - | - | - | - | - | 46 | 228 | 228 | - | - | - | - | - | - | - | - | - | - |
| 3b.4.5 | Heavy equipment rental | - | 175 | - | - | - | - | - | 26 | 201 | 201 | - | - | - | - | - | - | - | - | - | - |
| 3b.4.6 | Disposal of DAW generated | - | - | 7 | 3 | - | 18 | - | 6 | 33 | 33 | - | - | - | - | - | - | - | 6,476 | 10 | - |
| 3b.4.7 | Plant energy budget | - | - | - | - | - | - | 483 | 72 | 556 | 556 | - | - | - | - | - | - | - | - | - | - |
| 3b.4.8 | NRC Fees | - | - | - | - | - | - | 130 | 13 | 143 | 143 | - | - | - | - | - | - | - | - | - | - |
| 3b.4.9 | Site O&M Cost | - | - | - | - | - | - | 125 | 19 | 144 | 144 | - | - | - | - | - | - | - | - | - | - |
| 3b.4.10 | Security Staff Cost | - | - | - | - | - | - | 1,236 | 185 | 1,421 | 1,421 | - | - | - | - | - | - | - | - | - | 32,679 |
| 3b.4.11 | DOC Staff Cost | - | - | - | - | - | - | 3,799 | 570 | 4,369 | 4,369 | - | - | - | - | - | - | - | - | - | 129,669 |
| 3b.4.12 | Utility Staff Cost | - | - | - | - | - | - | 8,094 | 1,214 | 9,309 | 9,309 | - | - | - | - | - | - | - | - | - | 220,907 |
| 3b.4 | Subtotal Period 3b Period-Dependent Costs | 22 | 357 | 7 | 3 | - | 18 | 14,622 | 2,232 | 17,261 | 17,261 | - | - | - | - | - | - | - | 6,476 | 10 | - |
| 3b.0 | TOTAL PERIOD 3b COST | 748 | 1,314 | 7 | 18 | - | 454 | 19,320 | 3,430 | 25,271 | 24,944 | - | 327 | - | - | - | - | - | 97,822 | 10 | 253,648 |
| 3b.0 | TOTAL PERIOD 3b COST | 748 | 1,992 | 19 | 23 | - | 466 | 52,360 | 8,445 | 64,053 | 63,313 | - | 740 | - | - | - | - | - | 109,241 | 27 | 655,014 |
| PERIOD 3 TOTALS | | | | | | | | | | | | | | | | | | | | | |
| PERIOD 4a - Large Component Removal | | | | | | | | | | | | | | | | | | | | | |
| Period 4a Direct Decommissioning Activities | | | | | | | | | | | | | | | | | | | | | |
| Nuclear Steam Supply System Removal | | | | | | | | | | | | | | | | | | | | | |
| 4a.1.1.1 | Recirculation System Piping & Valves | 10 | 40 | 8 | 6 | 31 | 50 | - | 34 | 179 | 179 | - | - | 265 | - | - | - | 61,459 | 1,078 | - | - |
| 4a.1.1.2 | CRDAs & NR Bumps & Motors | 10 | 38 | 13 | 20 | 107 | 132 | - | 66 | 389 | 389 | - | - | 1,467 | - | - | - | 151,400 | 1,114 | - | - |
| 4a.1.1.3 | CRDAs & NR Bumpouts | 42 | 155 | 921 | 82 | - | 203 | - | 156 | 662 | 662 | - | - | - | - | - | - | 131,110 | 4,312 | - | - |
| 4a.1.1.4 | Reactor Vessel Internals | 63 | 2,203 | 3,456 | 687 | - | 3,966 | 197 | 4,727 | 15,279 | 15,279 | - | - | - | - | - | - | 3,474,905 | 26,617 | 1,197 | - |
| 4a.1.1.5 | Vessel & Internals GTCC Disposal | - | 5,228 | 1,242 | 375 | - | 8,132 | - | 9,374 | 9,374 | 9,374 | - | - | - | - | - | - | 482 | 86,500 | - | - |
| 4a.1.1.6 | Reactor Vessel | - | - | - | - | - | 2,056 | 197 | 5,383 | 14,481 | 14,481 | - | - | - | - | - | - | 13,057 | 26,617 | 1,197 | - |
| 4a.1.1.1 | Totals | 125 | 7,667 | 5,041 | 1,130 | 138 | 14,530 | 394 | 11,590 | 40,664 | 40,664 | - | - | 1,752 | 23,956 | 1,502 | 287 | 482 | 2,140,598 | 59,669 | 2,393 |
| Removal of Major Equipment | | | | | | | | | | | | | | | | | | | | | |
| 4a.1.2 | Main Turbine/Generator | - | 307 | 903 | 161 | 2,722 | - | - | 600 | 4,693 | 4,693 | - | - | 57,609 | - | - | - | - | 2,592,393 | 6,446 | - |
| 4a.1.3 | Main Condensers | - | 1,051 | 971 | 173 | 2,927 | - | - | 825 | 5,947 | 5,947 | - | - | 61,945 | - | - | - | - | 2,757,524 | 22,050 | - |
| Cascading Costs from Clean Building Demolition | | | | | | | | | | | | | | | | | | | | | |
| 4a.1.4.1 | Reactor Building | - | 905 | - | - | - | - | - | 136 | 1,041 | 1,041 | - | - | - | - | - | - | - | - | 11,450 | - |
| 4a.1.4.2 | Auxiliary Building | - | 216 | - | - | - | - | - | 32 | 248 | 248 | - | - | - | - | - | - | - | - | 2,582 | - |
| 4a.1.4.3 | Fuel Building | - | 237 | - | - | - | - | - | 36 | 273 | 273 | - | - | - | - | - | - | - | - | 2,912 | - |
| 4a.1.4.4 | Radiaste Building | - | 500 | - | - | - | - | - | 75 | 575 | 575 | - | - | - | - | - | - | - | - | 6,483 | - |
| 4a.1.4.5 | Turbine Building | - | 508 | - | - | - | - | - | 76 | 585 | 585 | - | - | - | - | - | - | - | - | 6,771 | - |
| 4a.1.4 | Totals | - | 2,367 | - | - | - | - | - | 355 | 2,722 | 2,722 | - | - | - | - | - | - | - | - | 30,209 | - |
| Disposal of Plant Systems | | | | | | | | | | | | | | | | | | | | | |
| 4a.1.5.1 | Acid Feed & Handling | - | 26 | 1 | 1 | 21 | - | - | 10 | 59 | 59 | - | - | 488 | - | - | - | - | - | 19,822 | 533 |
| 4a.1.5.2 | Auxiliary Steam | - | 484 | 13 | 19 | 319 | - | - | 173 | 1,008 | 1,008 | - | - | 7,493 | - | - | - | - | - | 304,278 | 9,740 |
| 4a.1.5.3 | Breathing Air | - | 36 | - | - | - | - | - | 5 | 42 | 42 | - | - | - | - | - | - | - | - | - | 820 |

Table E
Clinton Power Station
SAFSTOR Decommissioning Cost Estimate
(Thousands of 2007 Dollars)

| Activity Index | Activity Description | Decon Cost | Removal Cost | Packaging Costs | Transport Costs | Off-Site Processing Costs | LLRW Disposal Costs | Other Costs | Total Contingency | Total Costs | NRC Lic. Term. Costs | Spent Fuel Management Costs | Site Restoration Costs | Processed Volume Cu. Feet | Bridal Volumes | | | Bridal/Processed Wt. Lbs. | Craft Manhours | Utility and Contractor Manhours | | |
|----------------|--|------------|--------------|-----------------|-----------------|---------------------------|---------------------|-------------|-------------------|-------------|----------------------|-----------------------------|------------------------|---------------------------|----------------|---------|---------|---------------------------|----------------|---------------------------------|------------|--|
| | | | | | | | | | | | | | | | Class A | Class B | Class C | | | | | |
| 4a.1.5.4 | Disposal of Plant Systems (continued) | | | | | | | | | | | | | | | | | | | | | |
| 4a.1.5.4 | CO2 & Generator Purge | 16 | | | | | | | 2 | 18 | | | 18 | | | | | | | | 349 | |
| 4a.1.5.5 | Casite Handling | 13 | | | | | | | 5 | 26 | 26 | | | 183 | | | | | | | 256 | |
| 4a.1.5.6 | Chem Radioactive Reprocessing & Disposal | 351 | | | | | | | 145 | 810 | 810 | | | 3,354 | 1,375 | | | | | | 7,319 | |
| 4a.1.5.7 | Chilled Water - RCA | 1,035 | | | | | | | 369 | 2,149 | 2,149 | | | 15,914 | | | | | | | 20,760 | |
| 4a.1.5.8 | Chilled Water Non-RCA | 166 | | | | | | | 25 | 191 | | | 191 | | | | | | | | 3,682 | |
| 4a.1.5.9 | Chlorination | 44 | | | | | | | 7 | 51 | | | 51 | | | | | | | | 953 | |
| 4a.1.5.10 | Circulating Water - RCA | 161 | | | | | | | 105 | 706 | 706 | | | 9,379 | | | | | | | 3,419 | |
| 4a.1.5.11 | Circulating Water Non-RCA | 51 | | | | | | | 8 | 58 | | | 58 | | | | | | | | 1,090 | |
| 4a.1.5.12 | Grummt Aux & Fuel Bldg Equip Drains | 81 | | | | | | | 27 | 146 | 146 | | | 325 | 180 | | | | | | 29,340 | |
| 4a.1.5.13 | Grummt Aux & Fuel Bldg Floor Drains | 139 | | | | | | | 47 | 262 | 262 | | | 1,145 | 168 | | | | | | 2,845 | |
| 4a.1.5.14 | Component Cooling Water Non-RCA | 119 | | | | | | | 18 | 137 | | | 137 | | | | | | | | 2,622 | |
| 4a.1.5.15 | Condensate | 810 | | | | | | | 459 | 2,787 | 2,787 | | | 22,921 | 3,507 | | | | | | 12,454,444 | |
| 4a.1.5.16 | Condensate Booster | 766 | | | | | | | 456 | 2,750 | 2,750 | | | 21,259 | 4,224 | | | | | | 16,349 | |
| 4a.1.5.17 | Condensate Polishing | 619 | | | | | | | 228 | 1,277 | 1,277 | | | 10,094 | 1,088 | | | | | | 348,255 | |
| 4a.1.5.18 | Condenser Vacuum | 179 | | | | | | | 115 | 767 | 767 | | | 10,084 | 1,088 | | | | | | 409,927 | |
| 4a.1.5.19 | Containment Combustible Gas | 67 | | | | | | | 24 | 141 | 141 | | | 1,069 | | | | | | | 43,421 | |
| 4a.1.5.20 | Cycled Condensate | 555 | | | | | | | 204 | 1,150 | 1,150 | | | 5,945 | 910 | | | | | | 319,550 | |
| 4a.1.5.21 | Drywell Cooling | 437 | | | | | | | 157 | 919 | 919 | | | 3,655 | | | | | | | 282,437 | |
| 4a.1.5.22 | Drywell Purge | 124 | | | | | | | 56 | 351 | 351 | | | 3,655 | | | | | | | 148,412 | |
| 4a.1.5.23 | ECCS Equipment Cooling | 65 | | | | | | | 25 | 148 | 148 | | | 1,252 | | | | | | | 50,856 | |
| 4a.1.5.24 | Extraction Steam | 424 | | | | | | | 205 | 1,205 | 1,205 | | | 8,276 | 1,486 | | | | | | 469,355 | |
| 4a.1.5.25 | Feedwater | 464 | | | | | | | 265 | 1,605 | 1,605 | | | 12,765 | 2,191 | | | | | | 714,912 | |
| 4a.1.5.26 | Feedwater Heater Drains Turbine Cycle | 1,109 | | | | | | | 476 | 2,757 | 2,757 | | | 17,466 | 2,804 | | | | | | 998,507 | |
| 4a.1.5.27 | Feedwater Heater Misc. | 172 | | | | | | | 62 | 342 | 342 | | | 1,223 | 389 | | | | | | 3,542 | |
| 4a.1.5.28 | Filtered Water | 4 | | | | | | | 1 | 4 | | | 4 | | | | | | | | 88 | |
| 4a.1.5.29 | Generator Hydrogen Seal Oil | 25 | | | | | | | 8 | 44 | 44 | | | 243 | | | | | | | 9,883 | |
| 4a.1.5.30 | Generator Stator Cooling | 16 | | | | | | | 6 | 32 | 32 | | | 207 | | | | | | | 489 | |
| 4a.1.5.31 | High Pressure Core Spray | 225 | | | | | | | 112 | 672 | 672 | | | 5,250 | 702 | | | | | | 8,423 | |
| 4a.1.5.32 | Hydrogen | 22 | | | | | | | 7 | 36 | 36 | | | 168 | | | | | | | 4,755 | |
| 4a.1.5.33 | Laundry Equip & Flr Drains RW Reprocess | 189 | | | | | | | 72 | 416 | 416 | | | 2,742 | 231 | | | | | | 6,615 | |
| 4a.1.5.34 | Leak Detection | 37 | | | | | | | 10 | 51 | 51 | | | 86 | | | | | | | 3,930 | |
| 4a.1.5.35 | Local Instrument Panels | 8 | | | | | | | 1 | 6 | 6 | | | | | | | | | | 836 | |
| 4a.1.5.36 | Local Pressure Core Spray | 86 | | | | | | | 51 | 316 | 316 | | | 2,907 | 329 | | | | | | 147,560 | |
| 4a.1.5.37 | Machine Shop Equipment | 10 | | | | | | | 4 | 25 | 25 | | | 2,825 | | | | | | | 1,898 | |
| 4a.1.5.38 | Machine Shop Ventilation | 201 | | | | | | | 70 | 401 | 401 | | | 2,806 | | | | | | | 9,119 | |
| 4a.1.5.39 | Main Steam | 746 | | | | | | | 313 | 1,797 | 1,797 | | | 10,374 | 1,946 | | | | | | 113,939 | |
| 4a.1.5.40 | Main Steam Isolation Valve | 19 | | | | | | | 6 | 32 | 32 | | | 44 | | | | | | | 597,645 | |
| 4a.1.5.41 | Make-up Demineralizer - RCA | 184 | | | | | | | 63 | 360 | 360 | | | 2,419 | 36 | | | | | | 5,045 | |
| 4a.1.5.42 | Make-up Demineralizer Non-RCA | 208 | | | | | | | 31 | 239 | 239 | | | 991 | 474 | | | | | | 98,255 | |
| 4a.1.5.43 | Make-up Condensate Storage | 216 | | | | | | | 74 | 399 | 399 | | | 239 | | | | | | | 4,416 | |
| 4a.1.5.44 | Misc. Building Drains | 16 | | | | | | | 2 | 19 | 19 | | | | | | | | | | 82,690 | |
| 4a.1.5.45 | Miscellaneous Ventilation | 30 | | | | | | | 4 | 34 | 34 | | | | | | | | | | 337 | |
| 4a.1.5.46 | Nuclear Boiler | 15 | | | | | | | 5 | 24 | 24 | | | 34 | | | | | | | 643 | |
| 4a.1.5.47 | Oil Transfer | 90 | | | | | | | 39 | 243 | 243 | | | 2,429 | 21 | | | | | | 3,277 | |
| 4a.1.5.48 | Reactor Core Isolation Cooling | 194 | | | | | | | 73 | 417 | 417 | | | 2,491 | 275 | | | | | | 98,662 | |
| 4a.1.5.49 | Refrigeration Piping | 17 | | | | | | | 23 | 174 | 174 | | | | | | | | | | 124,231 | |
| 4a.1.5.50 | Sanitary | 151 | | | | | | | 23 | 174 | 174 | | | | | | | | | | 388 | |
| 4a.1.5.51 | Screen House & MU Pump House Ventilation | 31 | | | | | | | 5 | 36 | 36 | | | | | | | | | | 3,202 | |
| 4a.1.5.52 | Standby Liquid Control | 26 | | | | | | | 9 | 55 | 55 | | | 413 | | | | | | | 736 | |
| 4a.1.5.53 | Switchgear Heat Removal | 16 | | | | | | | 2 | 19 | 19 | | | | | | | | | | 529 | |
| 4a.1.5.54 | Turbine Building Closed Cooling Water | 148 | | | | | | | 52 | 299 | 299 | | | 2,106 | | | | | | | 16,763 | |
| 4a.1.5.55 | Turbine Electrohydraulic Control | 9 | | | | | | | 3 | 16 | 16 | | | 84 | | | | | | | 85,531 | |
| 4a.1.5.56 | Turbine Gen Misc Drains & Vents | 45 | | | | | | | 14 | 74 | 74 | | | 323 | | | | | | | 2,948 | |
| | | | | | | | | | | | | | | | | | | | | | 3,405 | |
| | | | | | | | | | | | | | | | | | | | | | 13,132 | |

Table E
Clinton Power Station
SAFSTOR Decommissioning Cost Estimate
(Thousands of 2007 Dollars)

| Activity Index | Activity Description | Decon Cost | Removal Cost | Packaging Costs | Transport Costs | Off-Site Processing Costs | LLRW Disposal Costs | Other Costs | Total Contingency | Total Costs | NRC Lic. Term. Costs | Spent Fuel Management Costs | Site Restoration Costs | Processed Volume Cu. Feet | Braid Volumes | | | Braid/Processed Wt. Lbs. | Craft Manhours | Utility and Contractor Manhours | |
|---|---|------------|--------------|-----------------|-----------------|---------------------------|---------------------|-------------|-------------------|-------------|----------------------|-----------------------------|------------------------|---------------------------|------------------|------------------|------------------|--------------------------|----------------|---------------------------------|---------|
| | | | | | | | | | | | | | | | Class A Cu. Feet | Class B Cu. Feet | Class C Cu. Feet | | | | |
| Disposal of Plant Systems (continued) | | | | | | | | | | | | | | | | | | | | | |
| 4a.1.5.57 | Turbine Gland Seal Steam | - | 300 | 22 | 34 | 570 | - | - | 168 | 1,092 | 1,092 | - | - | 13,358 | - | - | - | 542,467 | 6,268 | - | |
| 4a.1.5.58 | Turbine Oil | - | 48 | 2 | 3 | 53 | - | - | 21 | 127 | 127 | - | - | 1,250 | - | - | - | 50,775 | 1,016 | - | |
| 4a.1.5.59 | Turbine-Gen Aux & Misc Devices | - | 214 | 20 | 30 | 513 | - | - | 137 | 914 | 914 | - | - | 12,031 | - | - | - | 488,573 | 4,614 | - | |
| 4a.1.5 | Totals | - | 12,060 | 727 | 931 | 9,396 | 2,077 | - | 5,065 | 30,257 | 29,209 | - | 1,048 | 220,355 | 22,355 | - | - | 10,927,060 | 250,572 | - | |
| 4a.1.6 | Scaffolding in support of decommissioning | - | 2,745 | 50 | 11 | 140 | 17 | - | 718 | 3,682 | 3,682 | - | - | 2,969 | 185 | - | - | 150,174 | 63,258 | - | |
| 4a.1 | Subtotal Period 4a Activity Costs | 125 | 26,197 | 7,692 | 2,426 | 15,323 | 16,653 | 394 | 19,153 | 87,965 | 86,917 | - | 1,048 | 344,629 | 46,496 | 1,502 | 287 | 482 | 18,597,750 | 432,203 | 2,393 |
| Period 4a Additional Costs | | | | | | | | | | | | | | | | | | | | | |
| 4a.2.1 | Disposal of stored turbine rotors | - | 17 | 100 | 40 | 743 | - | - | 130 | 1,030 | 1,030 | - | - | 15,719 | - | - | - | 707,358 | 352 | - | |
| 4a.2 | Subtotal Period 4a Additional Costs | - | 17 | 100 | 40 | 743 | - | - | 130 | 1,030 | 1,030 | - | - | 15,719 | - | - | - | 707,358 | 352 | - | |
| Period 4a Collateral Costs | | | | | | | | | | | | | | | | | | | | | |
| 4a.3.1 | Process liquid waste | 21 | - | 9 | 48 | - | 15 | - | 22 | 115 | 115 | - | - | - | 166 | - | - | - | 9,977 | 32 | - |
| 4a.3.2 | Small tool allowance | - | 321 | - | - | - | - | - | 48 | 369 | 332 | - | - | 37 | - | - | - | - | - | - | - |
| 4a.3 | Subtotal Period 4a Collateral Costs | 21 | 321 | 9 | 48 | - | 15 | - | 70 | 484 | 447 | - | - | 37 | 166 | - | - | - | 9,977 | 32 | - |
| Period 4a Period-Dependent Costs | | | | | | | | | | | | | | | | | | | | | |
| 4a.4.1 | Decon supplies | 57 | - | - | - | - | - | - | 14 | 71 | 71 | - | - | - | - | - | - | - | - | - | - |
| 4a.4.2 | Insurance | - | - | - | - | - | - | 649 | 65 | 713 | 713 | - | - | - | - | - | - | - | - | - | - |
| 4a.4.3 | Property taxes | - | - | - | - | - | - | 1,279 | 128 | 1,406 | 1,266 | - | 141 | - | - | - | - | - | - | - | - |
| 4a.4.4 | Health physics supplies | - | 1,987 | - | - | - | - | - | 497 | 2,484 | 2,484 | - | - | - | - | - | - | - | - | - | - |
| 4a.4.5 | Heavy equipment rental | - | 2,180 | - | - | - | - | - | 327 | 2,507 | 2,507 | - | - | - | - | - | - | - | - | - | - |
| 4a.4.6 | Disposal of DAW generated | - | - | 174 | 72 | - | 467 | - | 143 | 846 | 846 | - | - | - | 8,196 | - | - | - | 161,251 | 250 | - |
| 4a.4.7 | Plant energy budget | - | - | - | - | - | - | 1,171 | 176 | 1,347 | 1,347 | - | - | - | - | - | - | - | - | - | - |
| 4a.4.8 | NRC Fees | - | - | - | - | - | - | 440 | 44 | 484 | 484 | - | - | - | - | - | - | - | - | - | - |
| 4a.4.9 | Site O&M Cost | - | - | - | - | - | - | 320 | 48 | 368 | 368 | - | - | - | - | - | - | - | - | - | - |
| 4a.4.10 | Stewards Processing Equipment/Services | - | - | - | - | - | - | 476 | 47 | 547 | 547 | - | - | - | - | - | - | - | - | - | - |
| 4a.4.11 | Security Staff Cost | - | - | - | - | - | - | 3,104 | 473 | 3,627 | 3,627 | - | - | - | - | - | - | - | - | - | - |
| 4a.4.12 | UIC Staff Cost | - | - | - | - | - | - | 1,136 | 136 | 1,269 | 1,269 | - | - | - | - | - | - | - | - | - | - |
| 4a.4.13 | Utility Staff Cost | - | - | - | - | - | - | 30,381 | 3,129 | 33,510 | 33,510 | - | - | - | - | - | - | - | - | - | - |
| 4a.4 | Subtotal Period 4a Period-Dependent Costs | 57 | 4,167 | 174 | 72 | - | 457 | 40,252 | 6,900 | 52,079 | 51,938 | - | 141 | - | 8,196 | - | - | - | 164,251 | 250 | - |
| 4a.0 | TOTAL PERIOD 4a COST | 203 | 30,702 | 7,976 | 2,586 | 16,066 | 17,126 | 40,647 | 26,253 | 141,558 | 140,332 | - | 1,225 | 360,348 | 54,858 | 1,502 | 287 | 482 | 19,479,330 | 432,838 | 603,489 |
| PERIOD 4b - Site Decontamination | | | | | | | | | | | | | | | | | | | | | |
| Period 4b Direct Decommissioning Activities | | | | | | | | | | | | | | | | | | | | | |
| 4b.1.1 | Remove spent fuel racks | 452 | 45 | 92 | 104 | - | 572 | - | 405 | 1,668 | 1,668 | - | - | - | 6,066 | - | - | - | 544,292 | 1,017 | - |
| Disposal of Plant Systems | | | | | | | | | | | | | | | | | | | | | |
| 4b.1.2.1 | Component Cooling Water - RCA | - | 178 | 4 | 6 | 101 | - | - | 61 | 350 | 350 | - | - | 2,361 | - | - | - | 95,865 | 3,548 | - | |
| 4b.1.2.2 | Containment Monitoring | - | 50 | 0 | 0 | 8 | - | - | 14 | 73 | 73 | - | - | 185 | - | - | - | 7,495 | 1,113 | - | |
| 4b.1.2.3 | Control Rod Drive | - | 357 | 14 | 15 | 88 | 53 | - | 119 | 645 | 645 | - | - | 2,064 | 559 | - | - | 133,952 | 7,387 | - | |
| 4b.1.2.4 | Diesel Fuel Oil | - | 59 | - | - | - | - | - | 9 | 68 | 68 | - | 68 | - | - | - | - | 1,256 | 1,256 | - | |
| 4b.1.2.5 | Diesel Generator | - | 52 | - | - | - | - | - | 8 | 60 | 60 | - | - | - | - | - | - | - | 1,183 | - | |
| 4b.1.2.6 | Diesel Generator Room Ventilation | - | 77 | - | - | - | - | - | 12 | 88 | 88 | - | - | - | - | - | - | - | 1,817 | - | |
| 4b.1.2.7 | Drains-Laundry to Radwaste | - | 15 | 1 | 1 | 3 | 2 | - | 5 | 26 | 26 | - | - | 65 | 23 | - | - | 4,677 | 301 | - | |
| 4b.1.2.8 | Electrical - Clean Non-RCA | - | 1,545 | - | - | - | - | - | 232 | 1,777 | 1,777 | - | 1,777 | - | - | - | - | - | 33,545 | - | |
| 4b.1.2.9 | Electrical - Clean RCA | - | 6,131 | 125 | 188 | 3,190 | - | - | 2,052 | 11,687 | 11,687 | - | - | 74,814 | - | - | - | 3,038,244 | 126,548 | - | |
| 4b.1.2.10 | Electrical - Contaminated | - | 909 | 13 | 21 | 353 | - | - | 285 | 1,581 | 1,581 | - | - | 8,281 | - | - | - | 336,300 | 19,037 | - | |
| 4b.1.2.11 | Equip Drain Radwaste Reprocessing | - | 1,018 | 44 | 51 | 423 | 142 | - | 365 | 2,043 | 2,043 | - | - | 9,913 | 1,584 | - | - | 537,960 | 21,022 | - | |

Table E
Clinton Power Station
SAFSTOR Decommissioning Cost Estimate
(Thousands of 2007 Dollars)

| Activity Index | Activity Description | Decon Cost | Removal Cost | Packaging Costs | Transport Costs | Off-Site Processing Costs | LLRW Disposal Costs | Other Costs | Total Contingency | Total Costs | NRC Lic. Term. Costs | Spent Fuel Management Costs | Site Restoration Costs | Processed Volume Cu. Feet | Bridal Volumes | | | Bridal/Processed Wt. Lbs. | Craft Manhours | Utility and Contractor Manhours | |
|----------------|---|------------|--------------|-----------------|-----------------|---------------------------|---------------------|-------------|-------------------|-------------|----------------------|-----------------------------|------------------------|---------------------------|------------------|------------------|------------------|---------------------------|----------------|---------------------------------|--|
| | | | | | | | | | | | | | | | Class A Cu. Feet | Class B Cu. Feet | Class C Cu. Feet | | | | |
| db-1.2.12 | Disposal of Plant Systems (continued) | | | | | | | | | | | | | | | | | | | | |
| db-1.2.12 | Flow Protection - RCA | | 616 | 15 | 23 | 385 | | | 217 | 1,255 | 1,255 | | | 9,018 | | | | 366,214 | 12,406 | | |
| db-1.2.13 | Flow Protection Non-RCA | | 654 | | | | | | 23 | 1,177 | | | 177 | | | | | 429,512 | 3,416 | | |
| db-1.2.14 | Floor Drain Radwaste Reprocessing | | 634 | 37 | 42 | 323 | 128 | | 249 | 1,413 | 1,413 | | | 7,582 | 1,406 | | | 13,094 | 13,094 | | |
| db-1.2.15 | Fuel Handling & Transfer | | 22 | 1 | 2 | 11 | 5 | | 9 | 50 | 50 | | | 262 | 54 | | | 15,494 | 464 | | |
| db-1.2.16 | Fuel Pool Cooling & Cleanup | | 783 | 54 | 63 | 480 | 189 | | 330 | 1,898 | 1,898 | | | 11,250 | 2,020 | | | 636,883 | 16,214 | | |
| db-1.2.17 | Fuel Support | | 88 | 7 | 9 | 70 | 26 | | 41 | 242 | 242 | | | 1,649 | 278 | | | 91,923 | 1,898 | | |
| db-1.2.18 | HVAC - Auxiliary Building | | 28 | 1 | 2 | 26 | | | 11 | 68 | 68 | | | 612 | 68 | | | 24,559 | 592 | | |
| db-1.2.19 | HVAC - Containment Building | | 661 | 21 | 33 | 560 | | | 256 | 1,532 | 1,532 | | | 13,132 | | | | 533,296 | 12,643 | | |
| db-1.2.20 | HVAC - Control Room | | 242 | | | | | | 36 | 279 | | | 279 | | | | | 5,686 | 5,686 | | |
| db-1.2.21 | HVAC - Fuel Building | | 283 | 6 | 10 | 170 | | | 99 | 569 | 569 | | | 3,993 | | | | 162,145 | 5,153 | | |
| db-1.2.22 | HVAC - Laboratory | | 456 | 10 | 16 | 273 | | | 158 | 913 | 913 | | | 6,392 | | | | 259,566 | 8,385 | | |
| db-1.2.23 | HVAC - OF Gas Building | | 115 | 3 | 5 | 80 | | | 42 | 245 | 245 | | | 1,876 | | | | 76,166 | 2,292 | | |
| db-1.2.24 | HVAC - Radwaste Building | | 644 | 16 | 25 | 428 | | | 231 | 1,345 | 1,345 | | | 10,038 | | | | 407,637 | 11,910 | | |
| db-1.2.25 | HVAC - Service Building | | 52 | | | | | | 8 | 60 | 60 | | | 60 | | | | 1,145 | 1,145 | | |
| db-1.2.26 | HVAC - Turbine Building | | 532 | 13 | 20 | 334 | | | 187 | 1,087 | 1,087 | | | 7,839 | | | | 318,337 | 9,704 | | |
| db-1.2.27 | Hoists Cranes & Elevators | | 6 | | | | | | 1 | 7 | 7 | | | 7 | | | | 123 | 123 | | |
| db-1.2.28 | Instrument Air - RCA | | 374 | 5 | 7 | 115 | | | 112 | 613 | 613 | | | 2,708 | | | | 109,971 | 7,089 | | |
| db-1.2.29 | Instrument Air Non-RCA | | 17 | | | | | | 3 | 20 | 20 | | | 2,172 | | | | 88,201 | 3,189 | | |
| db-1.2.30 | Off Gas | | 154 | 4 | 5 | 93 | | | 54 | 309 | 309 | | | 2,172 | | | | 123,583 | 3,532 | | |
| db-1.2.31 | Plant Service Water - RCA | | 176 | 5 | 8 | 130 | | | 23 | 180 | 180 | | | 3,043 | | | | 3,494 | 3,494 | | |
| db-1.2.32 | Plant Service Water Non-RCA | | 156 | | | | | | 2 | 12 | 12 | | | 180 | | | | 231 | 231 | | |
| db-1.2.33 | Potable Water | | 11 | | | | | | 2 | 12 | 12 | | | 529 | | | | 21,497 | 1,687 | | |
| db-1.2.34 | Process Radiation Monitoring | | 84 | 1 | 1 | 23 | | | 25 | 134 | 134 | | | 2,157 | | | | 57,602 | 5,330 | | |
| db-1.2.35 | Process Sampling | | 414 | 3 | 5 | 92 | | | 119 | 634 | 634 | | | 2,866 | 139 | | | 25,061 | 874 | | |
| db-1.2.36 | Reactor Recirculation | | 42 | 3 | 3 | 11 | 15 | | 17 | 91 | 91 | | | 1,738 | 766 | | | 139,001 | 5,284 | | |
| db-1.2.37 | Reactor Water Clean-up | | 257 | 15 | 17 | 74 | 72 | | 97 | 533 | 533 | | | 11,630 | 1,672 | | | 622,251 | 10,146 | | |
| db-1.2.38 | Residual Heat Removal | | 481 | 47 | 58 | 496 | 157 | | 247 | 1,487 | 1,487 | | | 7 | | | | 100,566 | 4,307 | | |
| db-1.2.39 | Screen Wash | | 6 | | | | | | 1 | 7 | 7 | | | 2,476 | | | | 60,155 | 1,369 | | |
| db-1.2.40 | Service Air - RCA | | 230 | 4 | 6 | 106 | | | 75 | 421 | 421 | | | 1,481 | | | | 1,829 | 1,829 | | |
| db-1.2.41 | Service Air Non-RCA | | 14 | | | | | | 2 | 16 | 16 | | | 1,481 | | | | 2,594 | 2,594 | | |
| db-1.2.42 | Shutdown Service Water - RCA | | 92 | 2 | 4 | 63 | | | 33 | 195 | 195 | | | 5,626 | 756 | | | 23,913 | 1,294 | | |
| db-1.2.43 | Shutdown Service Water Non-RCA | | 99 | | | | | | 185 | 1,020 | 1,020 | | | 889 | | | | 63,215 | 1,997 | | |
| db-1.2.44 | Solid Radioactive Waste - RCA | | 500 | 22 | 25 | 214 | 68 | | 116 | 1,077 | 1,077 | | | 1,086 | 213 | | | 62,702 | 942 | | |
| db-1.2.45 | Solid Radioactive Waste - Disposal | | 60 | | | | | | 38 | 212 | 212 | | | 1,117 | 193 | | | 60,852 | 3,642 | | |
| db-1.2.46 | Suppression Pool Cleanup & Transfer | | 96 | 6 | 6 | 46 | 20 | | 24 | 145 | 145 | | | 764 | 321 | | | 153,049 | 6,062 | | |
| db-1.2.47 | Suppression Pool Makeup | | 44 | | | | | | 104 | 585 | 585 | | | 3,905 | 366 | | | 9,457,092 | 399,374 | | |
| db-1.2.48 | Turb OG RW Ctrl & DG Bldg Equip Demos | | 181 | 8 | 8 | 33 | 33 | | 60 | 321 | 321 | | | 2,111 | 10,382 | | | 225,261 | 94,887 | | |
| db-1.2.49 | Turb OG RW Ctrl & DG Bldg Equip Demos | | 295 | 12 | 13 | 128 | | | 104 | 585 | 585 | | | 2,862 | 211,112 | | | 153,049 | 6,062 | | |
| db-1.2 | Totals | | 19,502 | 529 | 705 | 9,002 | 959 | | 6,375 | 37,073 | 34,210 | | | 2,862 | 211,112 | 10,382 | | 9,457,092 | 399,374 | | |
| db-1.3 | Scarfolding in support of decommissioning | | 4,118 | 74 | 17 | 210 | 26 | | 1,078 | 5,523 | 5,523 | | | 4,453 | 277 | | | 225,261 | 94,887 | | |
| db-1.3 | Decommissioning of Site Buildings | | 2,497 | 3,066 | 404 | 454 | 1,817 | | 2,627 | 11,196 | 11,196 | | | 7,734 | 24,125 | | | 2,519,185 | 112,645 | | |
| db-1.4.1 | Reactor Building | | 285 | 113 | 16 | 21 | 50 | 45 | 194 | 723 | 723 | | | 1,171 | 895 | | | 134,128 | 7,994 | | |
| db-1.4.2 | Auxiliary Building | | 329 | 67 | 14 | 19 | 2 | 46 | 197 | 675 | 675 | | | 56 | 915 | | | 93,484 | 7,972 | | |
| db-1.4.3 | Control Building | | 95 | 17 | 4 | 5 | 12 | | 56 | 191 | 191 | | | 2,574 | 959 | | | 24,981 | 2,272 | | |
| db-1.4.4 | Diesel Generator Building | | 729 | 632 | 20 | 25 | 110 | 50 | 557 | 2,122 | 2,122 | | | 1,067 | 3,336 | | | 197,780 | 27,889 | | |
| db-1.4.5 | Fuel Building | | 1,114 | 288 | 54 | 71 | 45 | 167 | 693 | 2,432 | 2,432 | | | 2,735 | 3,035 | | | 373,533 | 28,179 | | |
| db-1.4.6 | Radwaste Building | | 997 | 339 | 52 | 68 | 117 | 152 | 654 | 2,379 | 2,379 | | | 15,337 | 33,515 | | | 408,574 | 26,826 | | |
| db-1.4.7 | Turbine Building | | 6,046 | 4,522 | 564 | 663 | 2,289 | | 4,980 | 19,718 | 19,718 | | | 230,902 | 50,241 | | | 3,751,664 | 213,778 | | |
| db-1.4 | Totals | | 6,498 | 28,186 | 1,259 | 1,489 | 3,846 | | 12,837 | 63,982 | 61,119 | | | 2,862 | 230,902 | 50,241 | | 14,008,310 | 709,055 | | |

Table E
Clinton Power Station
SAFSTOR Decommissioning Cost Estimate
(Thousands of 2007 Dollars)

| Activity Index | Activity Description | Decon Cost | Removal Cost | Packaging Costs | Transport Costs | Off-Site Processing Costs | LLRW Disposal Costs | Other Costs | Total Contingency | Total Costs | NRC Lic. Term. Costs | Spent Fuel Management Costs | Site Restoration Costs | Processed Volume Cu. Feet | Bridal Volumes | | | Bridal / Processed Wt. Lbs. | Craft Manhours | Utility and Contractor Manhours | |
|---|---|------------|--------------|-----------------|-----------------|---------------------------|---------------------|-------------|-------------------|-------------|----------------------|-----------------------------|------------------------|---------------------------|------------------|------------------|------------------|-----------------------------|----------------|---------------------------------|--|
| | | | | | | | | | | | | | | | Class A Cu. Feet | Class B Cu. Feet | Class C Cu. Feet | | | | |
| Period 4b Additional Costs | | | | | | | | | | | | | | | | | | | | | |
| 4b-2.1 | ISFSI License Termination | - | 723 | 2 | 85 | - | 214 | 1,162 | 421 | 2,607 | - | 2,607 | - | - | - | - | - | 510,082 | 11,114 | 2,560 | |
| 4b-2 | Subtotal Period 4b Additional Costs | - | 723 | 2 | 85 | - | 214 | 1,162 | 421 | 2,607 | - | 2,607 | - | - | - | - | - | 510,082 | 11,114 | 2,560 | |
| Period 4b Collateral Costs | | | | | | | | | | | | | | | | | | | | | |
| 4b-3.1 | Process liquid waste | 83 | - | 35 | 193 | - | 62 | - | 90 | 463 | 463 | - | - | - | - | - | - | 40,127 | 130 | - | |
| 4b-3.2 | Small tool allowances | - | 597 | - | - | - | - | - | 81 | 618 | 618 | - | - | - | - | - | - | 303,507 | 88 | - | |
| 4b-3.3 | Decommissioning Equipment Disposition | - | - | 100 | 27 | 284 | 35 | - | 65 | 511 | 511 | - | - | 6,000 | 6,000 | - | - | 343,633 | 219 | - | |
| 4b-3 | Subtotal Period 4b Collateral Costs | 83 | 597 | 135 | 219 | 284 | 97 | - | 235 | 1,591 | 1,591 | - | - | 6,000 | 6,000 | 1,042 | - | 343,633 | 219 | - | |
| Period 4b Period-Dependent Costs | | | | | | | | | | | | | | | | | | | | | |
| 4b-4.1 | Decon supplies | 1,958 | - | - | - | - | - | - | 490 | 2,448 | 2,448 | - | - | - | - | - | - | - | - | - | |
| 4b-4.2 | Insurance | - | - | - | - | - | - | 799 | 80 | 878 | 878 | - | - | - | - | - | - | - | - | - | |
| 4b-4.3 | Property taxes | - | - | - | - | - | - | 1,574 | 157 | 1,732 | 1,732 | - | - | - | - | - | - | - | - | - | |
| 4b-4.4 | Health physics supplies | - | 3,094 | - | - | - | - | - | 774 | 3,868 | 3,868 | - | - | - | - | - | - | - | - | - | |
| 4b-4.5 | Heavy equipment rental | - | 2,063 | - | - | - | - | - | 399 | 3,063 | 3,063 | - | - | - | - | - | - | - | - | - | |
| 4b-4.6 | Disposal of DAW generated | - | - | 253 | 104 | - | 664 | - | 207 | 1,228 | 1,228 | - | - | - | - | - | - | 238,427 | 363 | - | |
| 4b-4.7 | Plant energy budget | - | - | - | - | - | - | 1,139 | 171 | 1,309 | 1,309 | - | - | - | - | - | - | - | - | - | |
| 4b-4.8 | NRC Fees | - | - | - | - | - | - | 542 | 54 | 596 | 596 | - | - | - | - | - | - | - | - | - | |
| 4b-4.9 | Site O&M Cost | - | - | - | - | - | - | 394 | 59 | 453 | 453 | - | - | - | - | - | - | - | - | - | |
| 4b-4.10 | Radwaste Processing Equipment/Services | - | - | - | - | - | - | 586 | 88 | 673 | 673 | - | - | - | - | - | - | - | - | - | |
| 4b-4.11 | Security Staff Cost | - | - | - | - | - | - | 3,883 | 582 | 4,465 | 4,465 | - | - | - | - | - | - | - | - | 102,679 | |
| 4b-4.12 | DOC Staff Cost | - | - | - | - | - | - | 14,266 | 2,140 | 16,406 | 16,406 | - | - | - | - | - | - | - | - | 220,143 | |
| 4b-4.13 | Utility Staff Cost | - | - | - | - | - | - | 24,393 | 3,659 | 28,052 | 28,052 | - | - | - | - | - | - | - | - | 387,714 | |
| 4b-4 | Subtotal Period 4b Period-Dependent Costs | 1,958 | 5,757 | 253 | 104 | - | 664 | 47,574 | 8,860 | 65,171 | 65,171 | - | - | - | - | - | - | 238,427 | 363 | 710,536 | |
| 4b-0 | TOTAL PERIOD 4b COST | 8,539 | 35,203 | 1,650 | 1,897 | 10,150 | 4,821 | 48,736 | 22,354 | 133,351 | 127,851 | 2,607 | 2,862 | 236,902 | 67,436 | - | - | 15,100,450 | 720,751 | 715,096 | |
| PERIOD 4c - License Termination | | | | | | | | | | | | | | | | | | | | | |
| Period 4c Direct Decommissioning Activities | | | | | | | | | | | | | | | | | | | | | |
| 4c-1.1 | DRSE confirmatory survey | - | - | - | - | - | - | 141 | 42 | 183 | 183 | - | - | - | - | - | - | - | - | - | |
| 4c-1.2 | Termination license | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | |
| 4c-1 | Subtotal Period 4c Activity Costs | - | - | - | - | - | - | 141 | 42 | 183 | 183 | - | - | - | - | - | - | - | - | - | |
| Period 4c Additional Costs | | | | | | | | | | | | | | | | | | | | | |
| 4c-2.1 | Final Site Survey | - | - | - | - | - | - | 11,020 | 3,306 | 14,326 | 14,326 | - | - | - | - | - | - | - | 230,140 | - | |
| 4c-2 | Subtotal Period 4c Additional Costs | - | - | - | - | - | - | 11,020 | 3,306 | 14,326 | 14,326 | - | - | - | - | - | - | - | 230,140 | - | |
| Period 4c Collateral Costs | | | | | | | | | | | | | | | | | | | | | |
| 4c-3.1 | DOC staff relocation expenses | - | - | - | - | - | - | 829 | 124 | 953 | 953 | - | - | - | - | - | - | - | - | - | |
| 4c-3 | Subtotal Period 4c Collateral Costs | - | - | - | - | - | - | 829 | 124 | 953 | 953 | - | - | - | - | - | - | - | - | - | |
| Period 4c Period-Dependent Costs | | | | | | | | | | | | | | | | | | | | | |
| 4c-4.1 | Insurance | - | - | - | - | - | - | 74 | 7 | 82 | 82 | - | - | - | - | - | - | - | - | - | |
| 4c-4.2 | Property taxes | - | - | - | - | - | - | 745 | 74 | 819 | 819 | - | - | - | - | - | - | - | - | - | |
| 4c-4.3 | Health physics supplies | - | 1,032 | - | - | - | - | - | 258 | 1,290 | 1,290 | - | - | - | - | - | - | - | - | - | |
| 4c-4.4 | Disposal of DAW generated | - | - | 8 | 3 | - | 21 | - | 7 | 40 | 40 | - | - | - | - | - | - | 7,712 | 12 | - | |
| 4c-4.5 | Plant energy budget | - | - | - | - | - | - | 144 | 22 | 165 | 165 | - | - | - | - | - | - | - | - | - | |
| 4c-4.6 | NRC Fees | - | - | - | - | - | - | 256 | 26 | 282 | 282 | - | - | - | - | - | - | - | - | - | |
| 4c-4.7 | Site O&M Cost | - | - | - | - | - | - | 186 | 28 | 214 | 214 | - | - | - | - | - | - | - | - | - | |
| 4c-4.8 | Security Staff Cost | - | - | - | - | - | - | 705 | 106 | 811 | 811 | - | - | - | - | - | - | - | - | 18,651 | |
| 4c-4.9 | DOC Staff Cost | - | - | - | - | - | - | 3,905 | 586 | 4,490 | 4,490 | - | - | - | - | - | - | - | - | 56,731 | |
| 4c-4.10 | Utility Staff Cost | - | - | - | - | - | - | 5,167 | 775 | 5,942 | 5,942 | - | - | - | - | - | - | - | - | 73,829 | |

Table E
Clinton Power Station
SAFSTOR Decommissioning Cost Estimate
(Thousands of 2007 Dollars)

| Activity Index | Activity Description | Decon Cost | Removal Cost | Packaging Costs | Transport Costs | Off-Site Processing Costs | LLRW Disposal Costs | Other Costs | Total Contingency | Total Costs | NRC Lic. Term. Costs | Spent Fuel Management Costs | Site Restoration Costs | Processed Volume Cu. Feet | Class A | | | Class B | | | Class C | | | Bridal/Processed Wt. Lbs. | Craft Manhours | Utility and Contractor Manhours |
|----------------|---|------------|--------------|-----------------|-----------------|---------------------------|---------------------|-------------|-------------------|-------------|----------------------|-----------------------------|------------------------|---------------------------|----------|----------|----------|----------|------------|-----------|-----------|----------|----------|---------------------------|----------------|---------------------------------|
| | | | | | | | | | | | | | | | Cu. Feet | Cu. Feet | Cu. Feet | Cu. Feet | Cu. Feet | Cu. Feet | Cu. Feet | Cu. Feet | Cu. Feet | | | |
| 4e.4 | Subtotal Period 4e Period-Dependent Costs | - | 1,032 | 8 | 3 | - | 21 | 11,182 | 1,888 | 14,135 | 14,135 | - | - | - | - | 385 | - | - | - | - | - | - | 7,712 | 12 | 149,211 | |
| 4e.0 | TOTAL PERIOD 4e COST | - | 1,032 | 8 | 3 | - | 21 | 23,172 | 5,361 | 29,597 | 29,597 | - | - | - | - | 385 | - | - | - | - | - | - | 7,712 | 230,152 | 149,211 | |
| | PERIOD 4 TOTALS | 8,742 | 66,937 | 9,633 | 4,486 | 26,216 | 21,969 | 112,554 | 53,968 | 304,506 | 297,811 | 2,807 | 4,088 | 597,250 | 122,679 | 1,502 | 287 | 482 | 34,587,500 | 1,383,740 | 1,465,796 | | | | | |
| | PERIOD 5b - Site Restoration | | | | | | | | | | | | | | | | | | | | | | | | | |
| | Period 5b Direct Decommissioning Activities | | | | | | | | | | | | | | | | | | | | | | | | | |
| | Demolition of Remaining Site Buildings | | | | | | | | | | | | | | | | | | | | | | | | | |
| | 5b.1.1.1 Reactor Building | - | 5,134 | - | - | - | - | - | 770 | 5,904 | - | - | 5,904 | - | - | - | - | - | - | - | - | - | - | 65,001 | - | |
| | 5b.1.1.2 Auxiliary Building | - | 1,945 | - | - | - | - | - | 292 | 2,236 | - | - | 2,236 | - | - | - | - | - | - | - | - | - | - | 23,242 | - | |
| | 5b.1.1.3 Circulating Water Screenhouse | - | 3,165 | - | - | - | - | - | 475 | 3,640 | - | - | 3,640 | - | - | - | - | - | - | - | - | - | - | 38,383 | - | |
| | 5b.1.1.4 Control Building | - | 4,641 | - | - | - | - | - | 696 | 5,337 | - | - | 5,337 | - | - | - | - | - | - | - | - | - | - | 56,578 | - | |
| | 5b.1.1.5 Diesel Generator Building | - | 1,618 | - | - | - | - | - | 243 | 1,860 | - | - | 1,860 | - | - | - | - | - | - | - | - | - | - | 20,234 | - | |
| | 5b.1.1.6 Fuel Building | - | 2,159 | - | - | - | - | - | 324 | 2,483 | - | - | 2,483 | - | - | - | - | - | - | - | - | - | - | 26,720 | - | |
| | 5b.1.1.7 Make-Up Water Pump House | - | 344 | - | - | - | - | - | 52 | 396 | - | - | 396 | - | - | - | - | - | - | - | - | - | - | 5,100 | - | |
| | 5b.1.1.8 Miscellaneous Site Work | - | 1,504 | - | - | - | - | - | 226 | 1,729 | - | - | 1,729 | - | - | - | - | - | - | - | - | - | - | 21,227 | - | |
| | 5b.1.1.9 Miscellaneous Structures | - | 2,442 | - | - | - | - | - | 366 | 2,808 | - | - | 2,808 | - | - | - | - | - | - | - | - | - | - | 44,561 | - | |
| | 5b.1.1.10 Radwaste Building | - | 4,502 | - | - | - | - | - | 675 | 5,177 | - | - | 5,177 | - | - | - | - | - | - | - | - | - | - | 58,440 | - | |
| | 5b.1.1.11 Service Building | - | 353 | - | - | - | - | - | 53 | 406 | - | - | 406 | - | - | - | - | - | - | - | - | - | - | 5,585 | - | |
| | 5b.1.1.12 Transformer and Tank Pads | - | 147 | - | - | - | - | - | 22 | 169 | - | - | 169 | - | - | - | - | - | - | - | - | - | - | 2,463 | - | |
| | 5b.1.1.13 Turbine Building | - | 4,693 | - | - | - | - | - | 704 | 5,397 | - | - | 5,397 | - | - | - | - | - | - | - | - | - | - | 68,415 | - | |
| | 5b.1.1.14 Turbine Pedestal | - | 1,080 | - | - | - | - | - | 162 | 1,243 | - | - | 1,243 | - | - | - | - | - | - | - | - | - | - | 12,474 | - | |
| | 5b.1.1 Totals | - | 33,727 | - | - | - | - | - | 5,059 | 38,786 | - | - | 38,786 | - | - | - | - | - | - | - | - | - | - | 445,422 | - | |
| | Site Closeout Activities | | | | | | | | | | | | | | | | | | | | | | | | | |
| | 5b.1.2 Backfill Site | - | 57 | - | - | - | - | - | 9 | 66 | - | - | 66 | - | - | - | - | - | - | - | - | - | - | 201 | - | |
| | 5b.1.3 Grade & landscape site | - | 1,405 | - | - | - | - | - | 211 | 1,619 | - | - | 1,619 | - | - | - | - | - | - | - | - | - | - | 4,449 | - | |
| | 5b.1.4 Grunt report to NRC | - | - | - | - | - | - | - | -21 | 163 | 163 | - | - | - | - | - | - | - | - | - | - | - | - | - | 1,560 | |
| | 5b.1 Subtotal Period 5b Activity Costs | - | 35,192 | - | - | - | - | 141 | 5,300 | 40,634 | 163 | - | 40,471 | - | - | - | - | - | - | - | - | - | - | 445,071 | 1,560 | |
| | Period 5b Additional Costs | | | | | | | | | | | | | | | | | | | | | | | | | |
| | 5b.2.1 Concrete Cracking | - | 1,281 | - | - | - | - | 8 | 193 | 1,482 | - | - | 1,482 | - | - | - | - | - | - | - | - | - | - | 7,355 | - | |
| | 5b.2.2 SFPSI Site Restoration | - | 1,158 | - | - | - | - | 42 | 180 | 1,338 | - | - | 1,338 | - | - | - | - | - | - | - | - | - | - | 3,069 | 160 | |
| | 5b.2.3 Screenhouse Cofferdam | - | 834 | - | - | - | - | - | 140 | 1,074 | - | - | 1,074 | - | - | - | - | - | - | - | - | - | - | 10,159 | - | |
| | 5b.2.4 Discharge Flume Backfill | - | 3,741 | - | - | - | - | - | 561 | 4,302 | - | - | 4,302 | - | - | - | - | - | - | - | - | - | - | 23,931 | - | |
| | 5b.2.5 Unit 2 Excavation Backfill | - | 1,226 | - | - | - | - | - | 184 | 1,410 | - | - | 1,410 | - | - | - | - | - | - | - | - | - | - | 13,128 | - | |
| | 5b.2 Subtotal Period 5b Additional Costs | - | 8,341 | - | - | - | - | 49 | 1,259 | 9,649 | - | - | 9,649 | - | - | - | - | - | - | - | - | - | - | 57,642 | 160 | |
| | Period 5b Collateral Costs | | | | | | | | | | | | | | | | | | | | | | | | | |
| | 5b.3.1 Small tool allowance | - | 388 | - | - | - | - | - | 58 | 446 | - | - | 446 | - | - | - | - | - | - | - | - | - | - | - | - | |
| | 5b.3 Subtotal Period 5b Collateral Costs | - | 388 | - | - | - | - | - | 58 | 446 | - | - | 446 | - | - | - | - | - | - | - | - | - | - | - | - | |
| | Period 5b Period-Dependent Costs | | | | | | | | | | | | | | | | | | | | | | | | | |
| | 5b.4.1 Insurance | - | - | - | - | - | - | 226 | 23 | 249 | - | - | 249 | - | - | - | - | - | - | - | - | - | - | - | - | |
| | 5b.4.2 Property taxes | - | - | - | - | - | - | 1,264 | 126 | 1,391 | - | - | 1,391 | - | - | - | - | - | - | - | - | - | - | - | - | |
| | 5b.4.3 Heavy equipment rental | - | 5,246 | - | - | - | - | - | 787 | 6,033 | - | - | 6,033 | - | - | - | - | - | - | - | - | - | - | - | - | |
| | 5b.4.4 Plant energy budget | - | - | - | - | - | - | 218 | 33 | 251 | - | - | 251 | - | - | - | - | - | - | - | - | - | - | - | - | |
| | 5b.4.5 Site O&M Cost | - | - | - | - | - | - | 566 | 85 | 651 | - | - | 651 | - | - | - | - | - | - | - | - | - | - | - | - | |
| | 5b.4.6 Security Staff Cost | - | - | - | - | - | - | 2,145 | 322 | 2,466 | - | - | 2,466 | - | - | - | - | - | - | - | - | - | - | - | 56,709 | |
| | 5b.4.7 DOC Staff Cost | - | - | - | - | - | - | 11,330 | 1,899 | 13,029 | - | - | 13,029 | - | - | - | - | - | - | - | - | - | - | - | 160,674 | |
| | 5b.4.8 Utility Staff Cost | - | - | - | - | - | - | 6,331 | 950 | 7,280 | - | - | 7,280 | - | - | - | - | - | - | - | - | - | - | - | 92,151 | |

Table E
Clinton Power Station
SAFSTOR Decommissioning Cost Estimate
(Thousands of 2007 Dollars)

| Activity Index | Activity Description | Decon Cost | Removal Cost | Packaging Costs | Transport Costs | Off-Site Processing Costs | LLRW Disposal Costs | Other Costs | Total Contingency | Total Costs | NRC Lic. Term. Costs | Spent Fuel Management Costs | Site Restoration Costs | Processed Volume Cu. Feet | Burial Volumes | | | GTCC Cu. Feet | Burial/Processed Wt. Lbs. | Craft Manhours | Utility and Contractor Manhours | |
|----------------|---|------------|--------------|-----------------|-----------------|---------------------------|---------------------|-------------|-------------------|-------------|----------------------|-----------------------------|------------------------|---------------------------|------------------|------------------|------------------|---------------|---------------------------|----------------|---------------------------------|---------|
| | | | | | | | | | | | | | | | Class A Cu. Feet | Class B Cu. Feet | Class C Cu. Feet | | | | | |
| 5b.4 | Subtotal Period 5b Period-Dependent Costs | - | 5,246 | - | - | - | - | 22,080 | 4,024 | 31,350 | - | - | 31,350 | - | - | - | - | - | - | - | 309,534 | |
| 5b.0 | TOTAL PERIOD 5b COST | - | 49,167 | - | - | - | - | 22,271 | 10,641 | 82,079 | 163 | 1,380 | 80,637 | - | - | - | - | - | - | - | 505,713 | 311,254 |
| | PERIOD 5 TOTALS | - | 49,167 | - | - | - | - | 22,271 | 10,641 | 82,079 | 163 | 1,380 | 80,637 | - | - | - | - | - | - | - | 505,713 | 311,254 |
| | TOTAL COST TO DECOMMISSION | 19,021 | 124,062 | 10,292 | 5,338 | 26,216 | 24,017 | 656,869 | 145,108 | 1,010,952 | 691,981 | 233,606 | 85,365 | 597,250 | 152,139 | 1,502 | 287 | 482 | 35,321,280 | 2,045,763 | 6,814,027 | |

| | | |
|---|-------------|---------------------------|
| TOTAL COST TO DECOMMISSION WITH 16.76% CONTINGENCY: | \$1,010,952 | thousands of 2007 dollars |
| TOTAL NRC LICENSE TERMINATION COST IS 68.45% OR: | \$691,981 | thousands of 2007 dollars |
| SPENT FUEL MANAGEMENT COST IS 23.11% OR: | \$233,606 | thousands of 2007 dollars |
| NON-NUCLEAR DEMOLITION COST IS 8.44% OR: | \$85,365 | thousands of 2007 dollars |
| TOTAL LOW-LEVEL RADIOACTIVE WASTE VOLUME BURIED (EXCLUDING GTCC): | 153,929 | cubic feet |
| TOTAL GREATER THAN CLASS C RADWASTE VOLUME GENERATED: | 482 | cubic feet |
| TOTAL SCRAP METAL REMOVED: | 75,356 | tons |
| TOTAL CRAFT LABOR REQUIREMENTS: | 2,045,763 | man-hours |

End Notes:
 n/a - indicates that this activity not charged as decommissioning expense.
 a - indicates that this activity performed by decommissioning staff.
 0 - indicates that this value is less than 0.0 but is non-zero.
 a cell containing "-" indicates a zero value

ATTACHMENT 2

Clinton Power Station Radiological Decommissioning Projected SAFSTOR Cash Flow (dollars, thousands)

| Year | Radiological Decommissioning Cost (July 31, 2009 dollars) | Radiological Decommissioning Cost less Decommissioning Period Credit |
|------|--|---|
| 2026 | \$14,402 | \$14,402 |
| 2027 | \$81,329 | \$79,734 |
| 2028 | \$14,299 | \$13,744 |
| 2029 | \$5,725 | \$5,395 |
| 2030 | \$5,725 | \$5,289 |
| 2031 | \$5,725 | \$5,185 |
| 2032 | \$5,740 | \$5,097 |
| 2033 | \$5,725 | \$4,984 |
| 2034 | \$5,725 | \$4,886 |
| 2035 | \$5,725 | \$4,790 |
| 2036 | \$5,740 | \$4,709 |
| 2037 | \$5,725 | \$4,604 |
| 2038 | \$5,741 | \$4,527 |
| 2039 | \$5,725 | \$4,425 |
| 2040 | \$5,740 | \$4,350 |
| 2041 | \$5,725 | \$4,254 |
| 2042 | \$5,725 | \$4,170 |
| 2043 | \$5,725 | \$4,088 |
| 2044 | \$5,740 | \$4,019 |
| 2045 | \$5,725 | \$3,930 |
| 2046 | \$5,725 | \$3,853 |
| 2047 | \$5,725 | \$3,777 |
| 2048 | \$5,740 | \$3,713 |
| 2049 | \$5,725 | \$3,630 |
| 2050 | \$5,725 | \$3,559 |
| 2051 | \$5,725 | \$3,489 |
| 2052 | \$5,740 | \$3,430 |
| 2053 | \$5,725 | \$3,354 |
| 2054 | \$5,725 | \$3,288 |
| 2055 | \$5,725 | \$3,224 |
| 2056 | \$5,740 | \$3,169 |
| 2057 | \$5,725 | \$3,098 |
| 2058 | \$5,725 | \$3,038 |
| 2059 | \$5,725 | \$2,978 |
| 2060 | \$5,740 | \$2,928 |
| 2061 | \$5,725 | \$2,862 |
| 2062 | \$5,725 | \$2,806 |
| 2063 | \$5,725 | \$2,751 |
| 2064 | \$5,740 | \$2,705 |
| 2065 | \$5,725 | \$2,645 |
| 2066 | \$5,725 | \$2,593 |
| 2067 | \$5,725 | \$2,542 |

ATTACHMENT 2**Clinton Power Station
Radiological Decommissioning Projected SAFSTOR Cash Flow (continued)**
(dollars, thousands)

| Year | Radiological Decommissioning Cost (July 31, 2009 dollars) | Radiological Decommissioning Cost less Decommissioning Period Credit |
|--------------|--|---|
| 2068 | \$5,740 | \$2,499 |
| 2069 | \$5,725 | \$2,443 |
| 2070 | \$5,725 | \$2,395 |
| 2071 | \$5,725 | \$2,348 |
| 2072 | \$5,740 | \$2,309 |
| 2073 | \$5,725 | \$2,257 |
| 2074 | \$5,725 | \$2,213 |
| 2075 | \$5,725 | \$2,169 |
| 2076 | \$5,740 | \$2,133 |
| 2077 | \$5,725 | \$2,085 |
| 2078 | \$5,725 | \$2,044 |
| 2079 | \$5,725 | \$2,004 |
| 2080 | \$5,725 | \$1,965 |
| 2081 | \$18,231 | \$6,135 |
| 2082 | \$45,423 | \$14,985 |
| 2083 | \$108,023 | \$34,939 |
| 2084 | \$100,273 | \$31,796 |
| 2085 | \$86,981 | \$27,040 |
| 2086 | \$31,733 | \$9,672 |
| 2087 | \$77 | \$23 |
| 2088 | \$77 | \$23 |
| 2089 | \$1 | \$0 |
| Total | \$798,737 | \$409,492 |
| | Total Decommissioning Period Credit: | \$389,245 |

ATTACHMENT 3

**Clinton Power Station
NRC Funding Assurance Calculations**

July 31, 2009
(dollars, thousands)

| | NRC Generic Formula | CPS Site-Specific SAFSTOR Decommissioning Cost Estimate |
|---|------------------------------------|--|
| Required Minimum at July 31, 2009 (A) | \$576,567 | \$798,737 |
| Trust Fund Amount at July 31, 2009 (B) | \$320,699 | \$320,699 |
| Shutdown Date | 9/29/2026 | 9/29/2026 |
| Years to Shutdown (C) | 17.175 | 17.175 |
| Earnings Credit to shutdown (D) = (B) x ((1 + 2%) ^ (C) - 1) | \$129,919 | \$129,919 |
| Projected Trust Fund Amount at shutdown (E) = (B) + (D) | \$450,618 | \$450,618 |
| Decommissioning Period Earnings Credit (F) | \$33,500 | \$389,245 |
| Total Projected Trust Fund Amount (G) = (E) + (F) | \$484,118 | \$839,863 |
| Difference (H) = (G) - (A) | (\$92,449) | \$41,126 |
| Prepayment Difference – Surplus/(Shortfall) (J) = (H) / (1 + 2%) ^ (C) | (\$65,795) | \$29,269 |