

KEPCO Overview

Overview

Organization

Present Korean Nuclear Industry

Operation/Construction/Development

Lessons Learned & Prospects

KEPCO - Korea Electric Power Corporation

122 years of advancing with electric power

- 60 billion \$ assets
- 30 billion \$ sales
- 46,000 employees
- 6 power generating subsidiaries
- 4 engineering affiliates

Transmission
Distribution

Nuclear Power

Thermal Power

Operations &
Maintenance

Environment

New &
Renewable Energy

Construction

Initial Pre-application Meeting

KEPCO Group

- Leader in Power Plant Engineering

- Korea's leading provider of design, engineering and operation of nuclear, fossil and hydro-electric plants
- 40 years of experience with 20 nuclear power plants
- 100% market share in nuclear power plant design, fuel supply, operation & maintenance in Korea
- Leadership in R&D investment in nuclear industry
- State-of-the-art technology for electricity generation especially nuclear power plants
- Strong position to capture the growing market in Korea and overseas

Owner of Power Plants in Korea

Nuclear	Oil	LNG	Coal	Hydro
				
20 units	62units	16units	44units	26units
142,000 GWh (18 GW)	16,000GWh (7 GW)	79,000GWh (18 GW)	156,000GWh (24 GW)	5,000GWh (6 GW)
36%	4%	20%	39%	1%

Total : 168 units / 398,000 GWh

Initial Pre-application Meeting

KEPCO as a Global Company




Initial Pre-application Meeting



-  Participation in the privatization project of Electric power generation_ **RUSSIA**
-  Combined-thermal IPP business _ **AGERBAIJAN**
-  Combined cycle power plant(870MW) _ **LEBANON**
-  Consulting on enhancing power distribution performance_ **LIBYA**
-  Gas-fired power plant(2,250MW)
Egbin coal-fired power plant(1,320MW)
Oil field development(2billion barrels)_ **NIGERIA**
-  CFBC plant in Wuzhi(112MW)
Wind power plant in Gansu(49MW)
Wind power plant in Mongolia(369MW)
Coal-fired power plant in Shanxi(13,439MW)_ **CHINA**
-  Consulting on electric power facilities
Commissioned by Dakan Electric Power Distribution_ **MONGOLIA**
-  Coal-fired power plant in Malaya(650MW)
Combined cycle plant in Ilijan(1,200MW)
Coal-fired power plant in Naga(205MW)
Coal-fired power Plant in Sebu(200MW)_ **PHILIPPINES**
-  Automation of electric power distribution_ **INDONESIA**
-  Consulting on construction of plant in the electric power grid_ **INDONESIA**
-  Power plant M&A_ **USA**




Organization – KEPCO & Affiliates



Initial Pre-application Meeting

Organization – DC Application




KEPCO : Korea Electric Power Corporation
KHNP : Korea Hydro & Nuclear Power Co., LTD
KOPEC: Korea Power Engineering Co., LTD
KNF : Korea Nuclear Fuel
KAERI : Korea Atomic Energy Research Institute


Initial Pre-application Meeting

Locations

Initial Pre-application Meeting



Nuclear Regulation in Korea



NEPIO : Nuclear Energy Program Implementing Office

MOST : Ministry of Science & Technology

MEST : Ministry of Education, Science & Technology

KAERI : Korea Atomic Energy Research Institute

KINS : Korea Institute of Nuclear Safety

KINAC : Korea Institute of Nuclear Nonproliferation
& Control

Initial Pre-application Meeting

Robust Supply Chain

Main Equipment



Manufacturing
main equipments



Annual Production Capacity :
4 units



BOP Equipment

Manufacturing BOP equipment (185 items)

- ▶ Over 300 suppliers in Korea

Construction Capability

OPR-1000 Project



APR-1400 Project




Seven qualified & experienced Korean construction companies with capability to build NPPs independently

Initial Pre-application Meeting

Operating NPPs in KOREA

Site	Reactor Type	Capacity (MWe)	Owner	NSSS Supplier	Commercial Operation
Kori	PWR	587	KEPCO/ KHNP	Westinghouse	1978
		650			1983
		950			1985
		950			1986
Wolsong	PHWR	679	KEPCO/ KHNP	AECL	1983
		700		AECL	1997
		700		AECL/KHI	1998
		700		AECL/KHI	1999
Yonggwang	PWR	950	KEPCO/ KHNP	Westinghouse	1986
		950		Westinghouse	1987
		1000(OPR)		KHIC/ABB-CE	1995
		1000(OPR)		KHIC/ABB-CE	1996
		1000(OPR)		KHIC/KOPEC	2002
		1000(OPR)		KHIC/KOPEC	2002
Ulchin	PWR	950	KEPCO/ KHNP	Framatome	1988
		950		Framatome	1989
		1000(OPR)		KHIC	1998
		1000(OPR)		KHIC	1999
		1000(OPR)		DHIC/KOPEC	2004
		1000(OPR)		DHIC/KOPEC	2005

Operation Performance - Capacity factor



3-Year Average(%)	KEPCO	World Average
	92.2	82.4

of Unplanned Scram : **0.8/yr** (2006 – 2008)

Initial Pre-application Meeting


NPPs under Construction in KOREA

Plant	Reactor Type	Capacity (MWe)	Licensing Status	Commercial Operation
Shin-Kori 1&2	PWR (OPR1000)	1000	OL issued (July 2005 CP)	Dec. 2010, 2011 (planned)
Shin-Wolsong 1&2	PWR (OPR1000)	1000	June 2007 CP	Jan. 2012, 2013 (planned)
Shin-Kori 3&4	PWR (APR1400)	1400	April 2008 CP	Mid. of 2013, 2014 (planned)
Shin-Ulchin 1&2	PWR (APR1400)	1400	CP issued	End of 2015, 2016 (planned)


OL : Operation License
CP : Construction Permit

Nuclear Power Development Process

- Step by Step Approach



Evolution of Nuclear Power Plant Design



Initial Pre-application Meeting


Construction Status – APR1400

Shin-Kori Units 3&4 Project



- **Reactor Type: PWR (APR1400)**
- **Capacity: 1,400MW X 2 units**
- **Construction Period: Sep. 2007 – Sep. 2014 (from Site Grading to COD of Unit 4)**
 - **Construction Progress Rate: 40%**
- ◆ **Contractor**
 - **NSSS Supplier: Doosan Heavy Industries & Construction Co.**
 - **Architect Engineering (A/E): Korea Power Engineering Co. (KOPEC)**
 - **Construction: Hyundai/Doosan/SK Consortium**

● Project Milestone




Initial Pre-application Meeting

Construction Status – APR1400

Shin-Ulchin Units 1&2 Project




- **Reactor Type: PWR (APR1400)**
- **Capacity: 1,400MW X 2 units**
- **Construction Period: Aug. 2009 – Dec. 2016 (Site Grading - COD of Unit 2)**
- **Contractor**
 - Completed Preliminary Work Contract
 - Main Contract is under Negotiation
- **Project Milestone**




Initial Pre-application Meeting

Preserving State-of-the-art Technology



Continuous investment with enhancing safety feature after TMI & Chernobyl accident but limited construction




Continuous construction & Technology development


- Human resources for EPC
- Manufacturing
- Construction technology
- R&D, Test Facilities

Prospects of Nuclear Power in Korea

Installed Capacity



Electricity Generation



General Design Overview

Design Development

NSSS Design

Secondary System Design

Containment Design

MMIS

Plant Layout

Safety Analysis

Summary


Design Development

What is APR1400 ?

- **Evolutionary PWR – 1,400 MWe**
- **2 Loop / 4 Pump NSSS**
- **Prestressed Containment Building**

Design Development

Advanced Power Reactor 1400



Initial Pre-application Meeting

Design Development



Initial Pre-application Meeting

Design Development

APR1400 Development Strategy

- **Uprate power to 4,000 MWth (1,450 MWe) based on OPR1000's 2,825 MWth (1,050 MWe) technology**
- **Incorporate Advanced Design Features to enhance safety and operational flexibility**
- **Meet the Utility Requirements (domestic & world-wide)**
 - Proven Technology
 - Constructability
 - Maintainability
 - Regulatory Stabilization

Initial Pre-application Meeting

Design Development

**EPRI URD
System 80+**



**ADF/PDF
Latest Codes
& Standards**

* OPR1000 :
Optimized Power
Reactor 1000

Improved OPR1000
1,000 MWe

*APR1400 :
Advanced Power
Reactor 1400

- In Operation - YGN #5,6 ('02/'02) - UCN #5,6 ('04/'05)
- Under Construction - SKN #1,2 - SWN #1,2

OPR1000
1,000 MWe

- In Operation - YGN #3,4 ('95/'96) - UCN #3,4 ('98/'99)


NSSS Design
Palo Verde #2 (CE,1300MWe)

Core Design
ANO #2 (CE,1000MWe)

Initial Pre-application Meeting

Design Development

Evolution of Advanced NPPs



Design Development

Development Phases

Phase I ('92.12 – '94.12): Conceptual Design

- Reactor Type Selection
- Development of Top-Tier Design Requirements
- Comparative Study on Major Systems and Components

Phase II ('95.3 – '99.2): Basic Design

- Development of Detailed Design Requirements
- Development of Design Specifications for NSSS Major Components
- Preparation of Standard Safety Analysis Report

Phase III ('99.3 – '01.12): Optimization and Licensing

- Design Optimization
- Detailed Design of Long-Lead Items
- Licensing of the Standard Design

Initial Pre-application Meeting

Design Development

Licensing of Standard Design

- **Pre-Application Safety Review : Dec. 99 - June 01**
 - SSAR (Standard Safety Analysis Report)
 - CDM (Certified Design Material inclusive of ITAAC)
 - EOG (Emergency Operating Guidelines)
- **Application for Standard Design Approval : July 2001**
- **Requests for Additional Information : 2,251**
 - Man-machine interface and digital I&C system design
 - Performance of safety injection system based on DVI
 - Design features related to severe accident mitigation
- **Issuance of Standard Design Approval : *May 2002***


Initial Pre-application Meeting

APR1400 Licensing

Standard Design Approval by KINS in 2002



Standard Safety Analysis Report




Standard Design Approval of APR1400

Initial Pre-application Meeting

Design Development

Organizations for APR1400 Development



- KOPEC : Korea Power Engineering Company
- Doosan : Doosan Heavy Industries & Construction
- CARR : Center for Advanced Reactor Research
- KNF : Korea Nuclear Fuel Company
- KAERI : Korea Atomic Energy Research Institute

Initial Pre-application Meeting

Design Development

Design Principles and Goals

Design Principles

Adoption of ADF based on proven technology

- Thermal Margin (is greater than) > 10 %
- Direct Vessel Injection of Safety Injection System
- Passive Flow Regulator or Fluidic Device in Safety Injection Tank
- In-containment Refueling Water Storage Tank
- Fully Digitalized I&C and Operator-Friendly Man-Machine Interface

Enhanced Plant Safety and Cost Effectiveness

- Improved Severe Accident Mitigation System
- Reinforced Seismic Design Basis (0.3 g)
- Extended plant design lifetime (60 years)
- Reduced construction time (48 months for Nth unit)

Improved O & M Convenience

- Extended operator response time
- Reduced occupational exposure
- Easier In-Service Inspection and maintenance for components

Design Goals

Safety

- Core Damage Frequency less than $10^{-5}/\text{yr}$
- Containment Failure Frequency less than $10^{-6}/\text{yr}$
- Seismic Design Basis : 0.3 g
- Occupational radiation exposure < 1 man·Sv/Ry

Performance

- Thermal Margin (is greater than) > 10 %
- Plant Availability > 90 %
- Unplanned Trip (less than) < 0.8/Ry

Economy

- Plant Capacity (Gross) : 1,455 Mwe
- Plant Lifetime : 60 years
- Refueling Cycle \geq 18 months
- Construction Period : 48 months (Nth Unit)



Initial Pre-application Meeting

Design Development

Design Parameters

Parameters

APR1400

Thermal/ Elec. Power
Design Life
Seismic Acceleration

4,000 MWt / 1,450 MWe
60 Years
0.3 g

Operating Parameters

- Thot / Tcold
- Operating Pressure
- RCS Flow Rate
- Main Steam Pressure (@Full Power)
- Main Steam Flow Rate

615 / 555 °F
2250 psia
1.66 x 10⁶ lb/hr
1000 psia
8.975 x 10⁶ lb/hr

Safety Parameters

- CDF
- Containment Failure Frequency
- Thermal Margin
- Emergency Core Cooling System

2.25 x 10⁻⁶ < 10⁻⁵/RY
7.19 x 10⁻⁷ < 10⁻⁶/RY
>10%
4-train, DVI,
Fluidic Device in SIT



Performance Requirements

- Plant availability
- Unplanned trip
- Refueling cycle

More than 90 %
Less than 0.8/year
18 ~ 24 months

NSSS Design


RCS Configuration



Initial Pre-application Meeting

NSSS Design

Reactor Core




- Number of assemblies : 241
- Thermal margin : above 10 %
- Refueling cycle : over 18 months
- Batch average burn-up : 55,000 MWD/MTU
- Enhanced operational flexibility
 - Daily load follow operation capability
 - MOX loading capability up to 1/3 core

Initial Pre-application Meeting

NSSS Design

Fuel Assembly – Plus7™




- Enhanced thermal margin
- High burn-up
- Improved neutron economy
- Improved seismic resistance
- Reduced grid-to-rod fretting wear susceptibility
- Increased debris filtering efficiency
- Improved fuel productivity

Initial Pre-application Meeting

NSSS Design

Reactor Vessel & Internal



Enhanced RV integrity

- No weld seam in fuel region shell
- Using low Copper contents material

Reduced radiation exposure

- Reduced Cobalt contents in base material

Integrated Inner Barrel Assembly

- Welded IBA to UGS upper flange
 - Eliminate tie rods, round nuts, snubber flange & Block



Integrated Lower Internal Assembly

- Integrated core support barrel, core shroud, and lower support structure in one assembly

Initial Pre-application Meeting

NSSS Design

Integrated Head Assembly (IHA)



Integrated Components

- Head area cable tray system, CEDM air handling unit, cooling duct, cooling manifold and head lift rig, etc.


IHA Reduces

- Refueling Time
- Occupational Radiation Exposure
- Component Storage Area
- Seismic Load

Initial Pre-application Meeting

NSSS Design

Reactor Coolant Pump



Vertical pump

Motor-driven centrifugal pump




Bottom suction & horizontal discharge

Single stage impeller

Initial Pre-application Meeting

NSSS Design

Pressurizer with POSRV



Increased Volume

- Total volume : 2,400 ft³
- Enhancing coping capability against plant transients


Pilot Operated Safety Relief Valve

- Performing over-pressure protection and safety depressurization
- Main valve open by pilot valve actuation
- Steam/Water/Two-Phase discharge
- No drift of the opening set-point
- Reliable valve operation without chattering and leakage
- Low susceptibility for valve stuck-open

Initial Pre-application Meeting

NSSS Design

Steam Generator



Design Parameters

- Integral Economizer
- Number of tubes : 13,102 / SG
- Plugging margin : 10 %
- Tube material : Inconel 690

Improved Tube Support Bars and Plate

- Increased anti-vibration bars
 - Reducing flow-induced tube vibration


Modified SG Inlet Nozzle Angle

- Increasing space to install SG nozzle dam
 - Improving stability in mid-loop operation

Initial Pre-application Meeting

NSSS Design Features

Safety Injection System



Simplified Design

- Mechanically independent 4 train
- 1 SIP/train
- 1 SIT/train
- No low pressure pumps
- One injection mode



Direct Vessel Injection

- No safety injection water spillage in cold-leg break LOCA
- Increase the reliability of the injection during LOCA

Initial Pre-application Meeting

NSSS Design Features

Safety Injection Tank with Fluidic Device



Safety Injection Tank

- Design pressure : 700 psig
- Volume : 18000 gal (1 ea)



Fluidic Device

- Extend injection duration of SIT
- Playing a role of low pressure SIP
- Flow rate depends on the Stand Pipe height and resistance of Supply Port & Control Port

Initial Pre-application Meeting

Secondary System Design

Main Feedwater / Main Steam System



Main Feedwater System

- Normal Full Power Operation
 - 90% flow to economizer
 - 10% flow to downcomer
- MFIV to isolate SG


Main Steam System

- 5 MSSVs & 1 MSADV per steam line
- MSIV to isolate SG
- 8 SBVs to dump excess steam to condenser

Initial Pre-application Meeting

Secondary System Design

Auxiliary Feedwater System



Design Characteristics

- Redundantly actuated by ESFAS and Diverse Protection System


System Configuration

- 2 × 100 % motor driven pumps
- 2 × 100 % turbine driven pumps
- 2 × 100 % dedicated tanks housed in auxiliary building

Initial Pre-application Meeting

Secondary System Design

Turbine Generator



Turbine


- 1 HP TBN & 3 LP TBNs
- Type : Tandem-compound
- Turbine speed : 1,800 rpm
- Output : 1,455 MWe
- Last stage blade : 52 inch

Generator

- Cooling
 - Stator winding : Water
 - Stator core, Rotor : Hydrogen
- Voltage : 24 kV, 3 Phase
- Frequency : 60 Hz

Secondary System Design


AC Power System



Initial Pre-application Meeting

Containment Design

Cylindrical Containment with IRWST



Pre-stressed concrete structure

- Height: 229.5 ft, Diameter: 150 ft, Thickness: 4 ft
- Design Pressure: 60 psig


Steel-lined inner surface for leak-tightness

In-containment Refueling Water Storage Tank (IRWST)

- Eliminates switch-over operation during LOCA
- Heat sink for feed and bleed operation
- Minimizes contamination of Reactor Containment Building

Containment Design

Containment Protection System



Containment Spray System


- Design characteristics
 - 2 pumps (Backed up by 2 SCPs)
 - Water source : IRWST

Containment Hydrogen Control System

- Functions
 - Maintaining hydrogen concentration below design criterion
- Design characteristics
 - 30 Passive Autocatalytic Recombiners(PAR)
 - 10 Glow plug type igniters

Containment Design

Severe Accident Mitigation System



Reactor Cavity Flooding System

- Flooding reactor cavity to cool molten core
- Water Source : IRWST
- Water driving force : Gravity
- Designed in accordance with SECY-93-087
- Cavity floor area > 0.02 m²/MW_t


In-Vessel Retention – ERVC strategy

- Submerging reactor vessel lower head to cool and to retain molten core in reactor vessel
- Water source : IRWST
- Water driving force : SCP, BAMP

Initial Pre-application Meeting

MMIS

MMIS Overview



Initial Pre-application Meeting

MMIS


Major Characteristics

- Fully Digitalized Control System
- Remote Multiplexer for both Safety and Non-Safety Related Control Systems
- Redundant Compact Workstations
- Large Display Panel
- Safety Console to Backup Workstations
- Computerized Procedure System for Normal and Emergency Operations

Plant Layout


Slide-along Arrangement (2 units)

- **Reactor Containment Building (RCB)**
 - Pre-stressed cylindrical wall and hemispherical dome concrete structure
 - Wrapped around by auxiliary building
- **Auxiliary Building (AB)**
 - Quadrant arrangement to enhance safety
 - Accommodating MCR, Emergency D/G, Fuel handling facilities
- **Compound Building (CB)**
 - Accessible from both units
 - Housing common facilities of Access control, Radwaste treatment, Hot machine shop, etc
- **Turbine Building (TB)**
 - Steel structure with reinforced concrete turbine pedestal
 - Common tunnel for all underground facilities



Plant Layout

Quadrant Arrangement of Safety Components



SIP (Safety Injection Pump) SCP (Shutdown Cooling Pump) CSP (Containment Spray Pump) CCWP (Component Cooling Water Pump)

Initial Pre-application Meeting


Plant Layout

Fire and Flood Protection Design

Quadrant D

Quadrant B

-  Flood Barrier
-  Fire Barrier(3Hr)
-  Fire (3Hr) & Flood Barrier




Quadrant C

Quadrant A

Initial Pre-application Meeting

Plant Layout

Radiation Protection Design



Initial Pre-application Meeting

Safety Analysis


Deterministic Analysis

Design Basis Accidents (DBAs)

- Pre-approved Conservative Analysis Methodology
- All Chapter 15 Accidents meet Acceptance Criteria with adequate Margin

Beyond Design Basis Accidents (BDBA s)

- Best Estimate Analysis Methodology
- APR1400 BDBAs
 - MSGTR (Multiple Steam Generator Tube Rupture)
 - TLOFW (Total Loss of Feedwater Flow)
 - ATWS (Anticipated Transient Without Scram)
 - CMF (Common Mode Failure)




Safety Analysis

Deterministic Analysis


Shutdown Risk Evaluation

- DBA & BDBA occurred during Operating Modes 2~6
- Quantitative Evaluation has been performed
- APR1400 Safety Analysis during Shutdown Mode
 - Loss of Residual Heat Removal during Reduced Inventory Operation
 - Loss of Residual Heat Removal during Refueling Operation
 - Rapid Boron Dilution
 - Non-LOCA
 - LOCA/MSLB Mass & Energy Release Analysis



Safety Analysis

PSA



No significant vulnerability

- For all considered initiating events, the risk is not significant.

Reduced the risk

- 4-train safety systems
- Quadrant separation
- Advanced design features

Lower risk of APR1400

- The CDF is 1/3~1/4 of conventional PWR
- The CFF is 1/4~1/5 of conventional PWR

Initial Pre-application Meeting

Summary

Enhanced Safety

- **Increased thermal margin**
- **Physically separated quadrant arrangement of safety systems**
- **Adoption of new design features confirmed through design validation program**
- **Reinforced seismic design basis**

Improved Cost Effectiveness

- **Increased capacity factor and reduced unplanned trips**
- **Reduced construction time by advanced technologies**
- **Extended plant design life**

Convenient Operation & Maintenance

- **Full digitalized I&C system and operator-friendly man-machine interface**
- **Increased operator action time**
- **Reduced occupational radiation exposure**

Unique Design Features

New Design Features

SIS and Supporting Experiments

PLUS7 Advanced Fuel

Digital I&C and MMIS

Human Factors Engineering Program

Severe Accident Mitigation

Summary

New Design Features of APR1400 (1)

- ❑ **APR1400 is an evolutionary PWR**

- ❑ **Design features of System80+ that are improved from the operating plants are maintained and improved**
 - 4 train safety injection system
 - IRWST
 - Digital I&C
 - Severe accident mitigation evaluation

New Design Features of APR1400 (2)


Design features that are different from System 80+

- Prestressed concrete cylindrical containment
- Fluidic device in SIT to further enhance safety injection system performance
- Improved digital I&C and advanced control room design
- Plus 7 fuel
- Use of PAR/igniter for Hydrogen mitigation
- Design enhancement to better execute SAM strategies such as ERVC

Comparison with System 80+

- **Thermal Power**
 - System80+ : 3,931 MWt
 - APR1400 : 4,000 MWt

- **RCS Depressurization Equipment**
 - System80+ : 3 spring loaded PSV + 2 SDS
 - APR1400 : 4 POSRV



- **RV Upper Structure**
 - System80+ : Conventional
 - APR1400 : IHA

- **Safety Injection System**
 - System80+ : 4 train ECCS + DVI
 - APR1400 : 4 train ECCS + DVI + Fluidic Device



Initial Pre-application Meeting

Safety Injection System and Supporting Experiments

- ❑ **4 train direct vessel injection system**
 - 4 safety injection tanks and pumps
 - Passive flow regulator in safety injection tank (fluidic device)
- ❑ **Test performed**
 - MIDAS test: ECC bypass during LBLOCA reflood phase
 - ATLAS test: LBLOCA integral test
 - VAPER test: full-scale performance test of the fluidic device
- ❑ **ECCS performance evaluation using BE + uncertainty quantification (RELAP5/Mod3.3) at the request of KINS**

Safety Injection System (1)

Direct Vessel Injection (DVI)




Direct Vessel Injection

- Unique T/H phenomena of ECC water
- ECC water bypass and downcomer boiling during LBLOCA

Safety Injection System (2)


Fluidic Device (FD)




Fluidic Device

- Extend injection duration of SIT
- Based on vortex flow resistance
 - Standpipe: low resistance
 - Control port: high resistance
- Effect: Low pressure SIP removal

VAPOR: Performance Verification of Fluidic Device




- ❑ **Scale : Full Dimension (18,000gallon), Full Pressure (600psia)**
- ❑ **K-factors for high/low flow are measured using tests**
 - Plant K-factors are calculated according to the pipe size



Initial Pre-application Meeting

MIDAS Tests

Multi-dimensional Investigation in Downcomer Annulus Simulation




Examine/measure ECC bypass in reflow phase of cold-leg large break LOCA

- 1/5 linear scale (UPTF:1/4.08 linear scale)
- Steam-water (superheated and saturated steam) tests

ATLAS tests (1)

Integral Test Loop of APR1400



- State-of-the-art integral loop test facility
- Scale: 1/2-height & 1/144-area of APR1400
- Test data useful for code benchmarking

Initial Pre-application Meeting

ATLAS tests (2)

ATLAS LBLOCA Reflood Tests



Phase Classification	Objectives	Test No.
<u>Phase 1 :</u>	Parametric effects on downcomer boiling at late reflood phase	Test No.1 ~ No.7
<u>Phase 2 :</u>	APR 1400 LBLOCA reflood test	Test No.8 ~ No.15

Test ID	Experimental conditions
Test No.9	APR1400 reflood test under conservative conditions (ANS-73*120%, lowest back pressure)
Test No.11	APR1400 reflood test under realistic conditions (ANS-79*102%, realistic back pressure)
Test No.15 (SET)	Typical reflood test with low reflooding rate

ATLAS tests (3)

LBLOCA Reflood Test


ATLAS - LBLOCA TEST



Initial Pre-application Meeting

ECCS Performance Evaluation using BE + uncertainty quantification



RELAP5/Mod3.3 + CONTEMPT (Base code), REM (Methodology)



Initial Pre-application Meeting

IRWST Design and Sparger

In-containment Refueling Water Storage Tank (IRWST)





Functions

- Borated Water Source for Refueling Pool
- Safety-Grade Water Source for Safety Injection and Containment Spray
- Heat Sink for Feed and Bleed Operation and Rapid RCS Depressurization
- Water Source for Reactor Cavity Flooding and External Reactor Vessel Cooling Systems

Eliminates switch-over operation during LOCA
Minimizes contamination of Reactor Containment Building

IRWST/Sparger Performance



Blowdown & Condensation Loop




- Measure air, steam, and water blowdown load on SDVS & IRWST structures
- Investigate thermal mixing between discharged fluid and water in IRWST

IRWST/Sparger Tests

Test data used for code validation



Dynamic Load Test



Thermal Mixing Test

Initial Pre-application Meeting

PLUS7 Advanced Fuel (1)

Fuel Assembly

**PLUS7
(16 x 16)**

**Fuel Rods : 236
Guide Tubes : 4
Instr. Tube : 1
Top Nozzle : 1
Bot. Nozzle : 1
Zry S/G : 10
Inconel S/G : 1**



Enhanced Thermal Margin

High Burn up

Improved Neutron Economy

Improved Seismic Resistance

**Reduced Grid-to-Rod Fretting Wear
Susceptibility**

Increased Debris Filtering Efficiency

Improved Fuel Productivity

PLUS7 Advanced Fuel (2)

Fuel Assembly – PLUS7

- ❑ **NPP for Use**
 - YGN 3,4,5,6 / UCN 3,4,5,6/ S-Kori 1,2/ SWN 1,2 (OPR1000)
 - Shin-Kori 3,4 (APR1400)
- ❑ **History**
 - Development Program Initiation : April 1999
 - Design & Out-of-pile Verification : March 2002
 - LTA In-Reactor Verification : September 2005
 - License and Region Application : July 2006
- ❑ **Proven in Operation**
 - 16 Batch Reloads for 8 Units

PLUS7 Advanced Fuel (3)

CHF Correlation

- CHF Test**
 - Heat Transfer Research Facility at Columbia Univ., New York
- Test Bundles**
 - Two 6x6 typical cell & thimble cell bundles
 - 11 mid-grids (9 Mixing vane grids)
- Measured CHF Data : Total 219 CHF data**
- Development of CHF Correlation**
 - The functional form : the same as CE-1 CHF correlation
 - The coefficients : determined based on the PLUS7 CHF data
- KINS licensed the CHF correlation (2004. 05)**

Digital I&C and MMIS (1)

APR1400 MMIS Major Design Feature



- Computer-based Advanced MCR
- Fully Digitalized NSSS and BOP I&C Systems
- PLC for safety and DCS for non-safety I&C Systems
- Human Factors Engineering Verification & Validation
- Computerized Operating Procedures

Initial Pre-application Meeting

Digital I&C and MMIS (2)

Advanced Control Room



- Major components
 - Redundant compact workstation with soft control
 - Large display panel
 - Advanced alarm system
 - Safety console
 - Backup for common mode failure
 - Computerized procedure system

Initial Pre-application Meeting


Digital I&C and MMIS (5)

APR1400 MMIS Major Design Feature

- **Monitoring System**
 - IPS (Information Processing System)
 - QIAS (Qualified Indication and Alarm System)
- **Control System**
 - ESF-CCS (Engineered Safety Feature-Component Control System)
 - P-CCS (Process-Component Control System)
 - PCS (Power Control System)
- **Protection System**
 - PPS (Plant Protection System)
 - CPCS (Core Protection Calculator System)
 - DPS (Diverse Protection System)

Digital I&C and MMIS (4)

APR1400 MMIS Architecture



Initial Pre-application Meeting


Digital I&C and MMIS (6)

Soft Control

- Replaces the conventional dedicated pushbuttons and M/A stations
- Allows operators to conveniently access all components for safety systems as well as non-safety systems during normal operation
- Safety related Soft Control is implemented on the ESF-CCS FPDs
- Non-safety related Soft Control is implemented on the information FPDs by selecting the corresponding control template on a display screen window

Digital I&C and MMIS (7)


Control System



Human Factors Engineering Program (1)

HFE Verification and Validation (V&V)

- HFE Program Review Model- NUREG-0711 requests HFE V&V to ensure
 - that the design conforms to HFE design principles.
 - that operator performance and reliability are acceptably supported in order to achieve safe operation of the plant.




Initial Pre-application Meeting

Human Factors Engineering Program (2)

Integrated System Validation (ISV)


□ HFE Program Review Model- NUREG-0711

- To ensure that the HSI inventory and characterization accurately describes all HSI displays, controls, and related equipment.
- To ensure that the HSI provides all alarms, information, and control capabilities required for personnel tasks.
- To ensure that the characteristic and design of the HSI conform to HFE guideline
- To ensure that the HSI designs are effectively, safely operated by plant operators within all performance requirements.



Human Factors Engineering Program (3)


Integrated System Validation (ISV)



Initial Pre-application Meeting

Human Factors Engineering Program (4)

HFE Evaluation Activities (V&V)



Initial Pre-application Meeting

Severe Accident Mitigation (1)

- ❑ **Severe accident mitigation features are evaluated based on SECY93-087 as a part of standard DA in Korea**
 - SSAR Chap 19.2
 - System 80+ approach was adopted for most cases
- ❑ **HPME**
 - Safety depressurization system that depressurize to 250 psi
 - Cavity design: convoluted flow path, corium chamber
 - Evaluation using MAAP4 and TCE model/Contain1.2
- ❑ **H2 Mitigation**
 - PARs with igniters to meet the 10CFR50.34f
 - Evaluation using MAAP4 with GOTHIC code

Severe Accident Mitigation (2)

❑ Steam explosion

- Tracer2 code used for the steam explosion load consideration

❑ Debris cooling and containment response

- Cavity flooding system is provided with the gravity feed from IRWST
- Corium concrete attack is evaluated using MAAP4 and MELCOR

Severe Accident Mitigation (3)

❑ Equipment Survivability

- Equipment important to severe accident management is examined against accident environment including hydrogen burn

❑ Severe Accident Management Guidance

- All nuclear power plants in Korea have implemented SAMG
- It is based on EPRI TBR and WOG SAMG
- For APR1400, we strengthened the capability of external cooling of RPV by making design improvement

Summary

- New Advanced Design Features have been Successfully Incorporated into APR1400 Design.**
- Advanced Design Features have been validated through rigorous Validation Programs.**
- Plant Safety and Operation & Maintenance have been Enhanced with Advanced Design Features.**

High Performance Fuel

Nuclear Fuel Supply System

Fuel Supply History

Fuel Performance


Fuel Fabrication Plants

Tube Mill

Fuel Technology


Nuclear Fuel Supply System

Nuclear Fuel Cycle



Initial Pre-application Meeting


Fuel Supply History



Now

Initial Pre-application Meeting

PLUS7™ & ACE7™ Fuel Supply



Now

- ❑ The irradiation data , experiences and VOC will be feedback continuously to upgrade PLUS7 and ACE7


Initial Pre-application Meeting

Fuel Supply History

Fuel Fabrication


Capacity : 550 MTU/yr (max. 700MTU/yr)

P
W
R





Capacity : 400 MTU/yr (max. 600MTU/yr)

P
H
W
R



Initial Pre-application Meeting

Fuel Fabrication Plants



Initial Pre-application Meeting

Zircaloy Tube Mill (TSA)

❑ **TSA : Techno Special Alloy**

❑ **Area : 16,529 m²**

❑ **Capacities : 1,400 km/yr**

❑ **Operated from Nov. 2008**



❑ **Current Products : All tubes for PWR**

- Fuel Tubes : 6 Types
- Thimble Tubes : 7 Types
- Instrument Tubes : 5 Types
- Sleeve/Flange : 7 Types

❑ **Future Products : Tubes for CANDU, CANFLEX-NU or ACR**

Fuel Technology History

Development Roadmap

4th Gen. Fuel

Technology Export ('16~)

Patented Tech.

- Gen IV Fuel
- Hydrogen Fuel (TRISO)

3rd Gen. Fuel

Technology Innovation ('05~'15)

Patented Tech.

- HIPER Fuel
- New Design Code

2nd Gen. Fuel

Technology Development ('99~'04)

Improved Tech.

- Joint R&D with W
- PLUS7 & ACE7 Fuel

1st Gen. Fuel

Technology Initiative (80's ~ 90's)

Established Tech.

- Import Proven Tech

Import Fuel (70's ~ 80's)

Initial Pre-application Meeting

PLUS7™ Overview

CE 16x16 type


- [OPR 1000] YGN 3/4/5/6 UCN 3/4/5/6 SKN 1/2 SWN 1/2
- [APR 1400] SKN 3/4 SKN 5/6 SUN 1/2

Performance

- Batch Average Discharge Burnup > 55 GWD/MTU
- Overpower Margin Increase to Current Fuel > 10%
- Integrity Maintenance even at 0.3g Seismic Load
- No Debris-Induced and Rod Fretting Wear-Induced Failure

PLUS7™ Main Design Features

Initial Pre-application Meeting



Summary

- 1) Nuclear Fuel supplier
 - 20 existing NPP (PWR, PHWR)
- 2) Develop advanced Fuel
 - cladding tube, hardware, software

Equipment Manufacturing

DOOSAN Manufacturing Facilities

Supply Experience

Key Manufacturing Operation

Quality Assurance

An aerial photograph of a large industrial manufacturing complex, likely a Doosan facility, is shown in the background. The image is partially obscured by a semi-transparent yellow rectangular overlay. The text 'DOOSAN' is faintly visible on one of the buildings in the background.

- **DOOSAN Manufacturing Facilities**


HISTORY

- 1962 : Established by Hyundai Yanghaeng
- 1980 : Become a State-own Company named Korea Heavy Industries & Construction Co., Ltd. (HANJUNG)
- 1981 : ASME Certificate (N, NPT) acquired
- 1982 : Changwon Integrated Machinery Plant Completed
- 1999 : Acquisition of Power Business from SAMSUNG and HYUNDAI
- 2001 : Privatized and Renamed to DOOSAN Heavy Industries & Construction Co., Ltd.

Initial Pre-application Meeting

One-Stop Manufacturing Facility for Nuclear Major Components

DOOSAN has an integrated manufacturing facility which is capable of raw material production to final assembly of components for Power Plants



- *DOOSAN Chang Won Plant*
 - Ground Area : 4,429,000 m²
 - Roofed Area : 425,000 m²

- Facilities
 - Main Office
 - Dock Facilities
 - R&D Center

- Manufacturing Shops

- Boiler
- Steam Turbine
- Gas Turbine
- Generator
- Nuclear
- Casting
- Forging
- Heavy Fabrication
- Defense Industries
- I&C

Forging and foundry shops



- (1) Forging Press : 13,000 tons
- (2) Forging Press : 4,200 tons
- (3) Forging Press : 1,600 tons
- (4) Forging Manipulator : Max. 400 tons



- (1) Electric Arc Furnace : 100/120 tons
- (2) Electric Arc Furnace : 30/35 tons
- (3) Vacuum Ladle Refining & Holding Furnace : 20/155 tons
- (4) Vacuum Stream Degassing Equipment : 30/530 tons

Initial Pre-application Meeting


Heavy machinery shops



- (11) Horizontal Lathe : 3,000 Dia. x 18,000 L x 250 t
- (11) Vertical Boring Machine : 10,000 x 2,200 H x 400 t
- (11) Horizontal Boring Machine : 400 Dia. x 3,800
- (9) Plano Miller Machine : 7,100 x 7,000 x 500 t

- (10) Horizontal Lathe : 1,000 Dia. x 4,000 L x 5 tons
- (9) Vertical Boring Machine : 2,800 Dia. x 2,500 x 25 tons
- (4) Horizontal Boring Machine : 125 Dia. x 1,250 x 1,600


Nuclear shops



- (1) 800 tons Over Head Crane
- (1) Semi Gantry Welding Machine
- (7) SAW Strip Cladding Machine : 4", 2", 1"
- (1) 3 Spindle Deep Hole Drilling Machine : 19'8"(X) x 11'10"(Y) x 3'7"(Z)
- (1) Vertical Boring Machine : 72'2" Dia x 26'3" H x 500 tons
- (1) Horizontal Boring Machine : 49'2"(X) x 26'3"(Y) x 8'10"(Z)

Initial Pre-application Meeting

Dedicated dock facilities



- Gantry Crane : 500 tons X 2 sets
→ 1,000 tons
- Transporter :
Multi-wheel Loader 560 tons (1),
450 tons (1), 250 tons (1), 150 tons (3)
- Crawler Crane : 400 tons (2)


Initial Pre-application Meeting

- **Supply Experience**

Initial Pre-application Meeting

Experiences In Replacement NPPs

Initial Pre-application Meeting



- RSG: Replacement Steam Generator
- RPZR: Replacement Pressurizer
- RRVH: Replacement Reactor Vessel Head

Major Experiences of Supplying Nuclear Components

◆ Ulchin #5 Reactor Vessel



◆ Shin Kori #1 Steam Generator



◆ Qinshan #1 Steam Generator



◆ Qinshan Phase II #3 Reactor Vessel



Initial Pre-application Meeting

Major Experiences of Supplying Nuclear Components

- ◆ Arkansas Nuclear One #2 Pressurizer



- ◆ Sequoyah #1 Steam Generator



- ◆ Watts Bar #1 Steam Generator



- ◆ Palo Verde #3 Reactor Vessel Head



Initial Pre-application Meeting

Korean New Nuclear Power Plants Equipments under manufacturing

Project	Type	Capacity	Contract Date	COD
Shin Kori 1&2	OPR1000	1,000MWe x 2	2002.08.09	2010.12 / 2011.12
Shin Wolsong 1&2	OPR1000	1,000MWe x 2	2002.08.09	2011.10 / 2012.10
Shin Kori 3&4	APR1400	1,400MWe x 2	2006.08.31	2013.09 / 2014.09
Shin Ulchin 1&2	APR1400	1,400MWe x 2	2009.07.31	2015.12 / 2016.12

Shin Kori 1&2



Shin Wolsong 1&2



Shin Kori 3&4




*OPR1000 : Optimized Power Reactor , APR1400 : Advanced Power Reactor

Initial Pre-application Meeting

AP1000 & Other Components under manufacturing

Project	Owner	Products	Unit
China, AP1000	CNNC /CPI	RV,SG, RVI,IHP	2
USA, AP1000	Southern SCANA Progress	RV,SG	6
Palo Verde	APS	RRVH, CEDM	3
Sequoyah	TVA	RSG	1
ANO Waterford Indian Point	Entergy	RVH	4
TEPCO	RFS	Cask	100*



* : EA

Initial Pre-application Meeting

Appreciation Awards from Customers



In Commemoration and Appreciation for the participation of DOOSAN in the Entergy Waterford 3 Replacement RVH Project




In appreciation of your leadership and lasting contribution to Palo Verde Nuclear Generating Station RVH Replacement Project

Initial Pre-application Meeting

- **Key Manufacturing Operation**


RV Manufacturing Sequence

Initial Pre-application Meeting



Key Manufacturing Operations - Reactor Vessel

Initial Pre-application Meeting



Closure Head Assembly



Upper Vessel Assembly




Lower Vessel Assembly

Reactor Vessel – Closure Head Assembly

1. Closure Head Cladding



2. J-Groove Hole M/C



3. CRDM Nozzle Shrink Fitting



4. CEDM NOZZLE WELDING




Initial Pre-application Meeting

Reactor Vessel – Upper Vessel Assembly

1. UPPER + INTERMEDIATE SHELL GIRTH SEAM WD



2. UPPER SHELL CLADDING



3. UPPER SHELL TO INLET NOZ. ASS'Y



4. UPPER VESSEL TO VESSEL FLANGE ASS'Y



Initial Pre-application Meeting

Reactor Vessel – Lower Vessel Assembly

1. BOTTOM HEAD CLADDING



2. J-GROOVE MACHINING



3. LOWER SHELL TO BOTTOM HEAD ASS'Y



4. INSTRUMENT TUBE INSTALLATION & FINAL M/C



Initial Pre-application Meeting

Key Manufacturing Operations - Reactor Vessel Internal

Initial Pre-application Meeting



**CS
Machining**



**LSS
Beam
Welding**



**LSS
Support
Plate
Welding**



**Core
Shroud
to
LSS
Welding**

- CS : Core Shroud
- LSS : Lower Support Structure



**UGS Tube
Rolling**



**UGS
Machining**



**CSB
Cylinder
Welding**




**CSB
Assembly**



- UGS : Upper Guide Structure
- CSB : Core Support Structure

SG Manufacturing Sequence



Initial Pre-application Meeting

Key Manufacturing Operations (in the Shop) – Steam Generator



Top Head Assembly



Upper Vessel Assembly



Primary Head Assembly

Initial Pre-application Meeting

Steam Generator – Tubesheet

1. TUBESHEET CLADDING



2. TUBESHEET TO LOWER SHELL WELDING



3. TUBESHEET DRILLING



4. LOWER TO UPPER SHELL WELDING



Semi-Gantry
WD M/C

Initial Pre-application Meeting


Steam Generator – Tubing



Tube Vertical Support+
Tube Installation



Tube Installation



Eggcrate Installation



Tube-to-Tubesheet
Welding



Hydraulic Expansion

- All critical operations requiring cleanliness are performed in the tubing room.
- Foreign material control is strictly performed in accordance with approved FME (Foreign Material Exclusion) Control Procedure.

Initial Pre-application Meeting

- **Quality Assurance**

Quality Assurance – Quality Policy and Objectives

Policy


- ▶ Complete customer's contractual requirements
- ▶ Conform to the applicable codes & standards
- ▶ Meet jurisdictional regulations
- ▶ Achieve "Zero Defect"

Objectives

Each Business Group establish their measurable Quality Objectives to include followings, as applicable

- ▶ Customer Satisfaction
- ▶ Product Conformity
- ▶ Process Conformity
- ▶ Supplier related Conformity

Quality Assurance - Hierarchy



Initial Pre-application Meeting

Quality Assurance – Certificates

Category		Certificates	Quantity
ASME	Nuclear	N, NPT, NS, N3, NA,	7
	Non-nuclear	U, U2, S, A, PP, H, R	7
KEPIC*		MN, SN, EN, DN	7
ISO		9001:2008, 14001:2004	3
PED		H, H1 Module	2
Others		OHSAS, Shipping Registers, etc.	23
Total			49

*KEPIC : Korea Electric Power Industry Code

Quality Assurance – Experiences

Codes & Standards	Projects	QA Program
<ul style="list-style-type: none"> ▪ ASME Section III ▪ 10 CFR 50 Appendix B ▪ ASME NQA-1 	<ul style="list-style-type: none"> ▪ YGN #1,2,3,4,5,6 (Domestic) ▪ UCN #3,4,5,6 (Domestic) ▪ Sequoyah #1 RSG (USA) ▪ Watts Bar #1 RSG (USA) ▪ AP 1000 USA/ China 	<ul style="list-style-type: none"> ▪ ASME III / KEPIC QA Manual
<ul style="list-style-type: none"> ▪ RCC-M (IAEA 50-C-QA) 	<ul style="list-style-type: none"> ▪ UCN #1,2 (Domestic) ▪ QSN Phase II (China) 	<ul style="list-style-type: none"> ▪ RCCM QA Manual
<ul style="list-style-type: none"> ▪ CSA Z299 Series 	<ul style="list-style-type: none"> ▪ WSN #2,3,4 (Domestic) ▪ QSN Phase III (China) 	<ul style="list-style-type: none"> ▪ ASME III QA Manual + CSA Addendum
<ul style="list-style-type: none"> ▪ KEPIC 	<ul style="list-style-type: none"> ▪ SKN #1,2,3,4 (Domestic) ▪ SWN #1,2 (Domestic) 	<ul style="list-style-type: none"> ▪ ASME III / KEPIC QA Manual
<ul style="list-style-type: none"> ▪ ISO 9001 : 2000 	<ul style="list-style-type: none"> ▪ Tokyo Electric NEO Model Cask (Japan) 	<ul style="list-style-type: none"> ▪ ISO 9001 Quality Management System

Initial Pre-application Meeting

Construction Activities

Construction Schedules

Advanced Construction Technologies

Demonstration of 4D Simulation

Pictures of SKN Unit 3 Construction

APR1400 Projects on Construction



Shin-Kori Units 3&4

Site Grading: Apr. 2007
First Concrete: Oct. 2008
Fuel Load: Jan. 2013
Current status: Erected CLP 19 Rings




Shin-Ulchin Units 1&2

Site Grading: Aug. 2009
First Concrete: Mar. 2011
Fuel Load: Apr. 2015
Current status: Under Site Grading



Project Key Milestone Dates


<u>Key Milestones</u>	<u>Month after 1st Concrete</u>
• Submit PSAR	D-29
• Construction Permit	D -7
• Start of Excavation	D -7
• First Concrete	D+0
• Set Reactor Vessel	22
• Submit FSAR	31
• Energize Start-up Transformer	33
• RCS Cold Hydro Test	43
• Hot functional Test	47
• Operation License	51
• Fuel Loading	51



Reference :Shin-Kori NPP unit 3


Unit : Month

Critical Paths



Reference :Shin-Kori NPP unit 3

Schedule Reduction with Increased Experience



As a result of 30 years of uninterrupted construction, construction schedule has been reduced by nearly 20%.

Advanced Construction Technologies

Pre-fabrication & Modularization


- Reinforcing Bar of Basemat
- Structural Steel
- MSIV Room Piping & Valve
- **RCB Exterior Wall 3-tiered CLP Module**
- **Installation of Single or 2 Pieces-Dome Liner Plate**
- **MCR Ceiling Structural Steel, etc**

Other Advanced & Optimized Process

- **Steel Deck Plate Method**
- **Automatic Welding of Reactor Coolant Loop**
- **Concurrent Installation of RC Loop Pipe & RV Internals**
- **Shortened Installation Period of TBN LP Hood & IHA**
- **Improvement of TBN Sole Plate Chipping**
- **Shortened Post-Tensioning Period**
- **3D CAD Models for Construction**
- **4D Simulation, etc**

RCB Exterior Wall 3-tiered CLP Module

- **Lifting 3-tiered CLP Ring Module vs. the conventional method of lifting 2-Ring Module**
 - **Shortens activity duration**
 - **Improves safety and quality**




Shin-Kori Unit 3

Single or 2 Piece-Dome Liner Plate Erection


■ Erection of a Single or 2 Piece-Dome Liner Plate vs. the traditional 3 Piece-Dome Liner Plate lifting method

- Shortens activity duration
- Improves Safety and Constructability




Automatic Welding of Reactor Coolant Loop

- **Automatic Welding of the Reactor Coolant Loop vs. the Conventional Manual Welding**
 - **Shortens activity duration**
 - **Improves quality and productivity**




Remote Automatic Welding System




Narrow Groove Welding Configuration

Deck Plate Method

- **Steel Deck Plate Method instead of the conventional reinforced concrete slab**
 - **No form and shoring support required**
 - **Improved constructability for mechanical and electrical work**






Form and Shoring Support Method



Deck Plate Method

Modularization Technology

- **Modularized Main Control Room (MCR) Ceiling Structural Steel with pre-installed HVAC Duct, Elec. Conduit and Process Pipe**
 - Shortens activity duration
 - Remove activities on critical paths
 - Improves safety and quality




3D CAD Models for Construction

- Introduction to 3D CAD for construction work
 - Helps visualize a shape to be done with drawings
 - Helps construction team coordinate the flow of work and space use on site




4D Simulation


- Integration of CAD and schedule for providing optimized construction schedule, visualization, and information management
 - Improves constructability
 - Shortens the construction period



3D CAD



Schedule



4D System

Demonstration of 4D Simulation



Pictures of SKN Unit 3 Construction

