

POWER AUTHORITY OF THE STATE OF NEW YORK

10 COLUMBUS CIRCLE NEW YORK, N.Y. 10019

(212) 397-6200

TRUSTEES

JOHN S. DYSON  
CHAIRMAN

GEORGE L. INGALLS  
VICE CHAIRMAN

RICHARD M. FLYNN

JAMES L. LAROCKA

ROLLAND E. KIDDER



April 18, 1983

IPN-83-25

LEROY W. SINCLAIR  
PRESIDENT & CHIEF  
OPERATING OFFICER

WALTER T. KICINSKI  
FIRST EXECUTIVE  
VICE PRESIDENT &  
CHIEF ADMINISTRATIVE  
OFFICER

JOSEPH R. SCHMIEDER  
EXECUTIVE VICE  
PRESIDENT & CHIEF  
ENGINEER

STEPHEN L. BAUM  
SENIOR VICE PRESIDENT  
& GENERAL COUNSEL

Director of Nuclear Reactor Regulation  
U. S. Nuclear Regulatory Commission  
Washington, D. C. 20555

Attention: Mr. Darrell G. Eisenhut, Director  
Division of Licensing  
Office of Nuclear Reactor Regulation

Subject: Indian Point 3 Nuclear Power Plant  
Docket No. 50-286  
Post - TMI Requirements

Dear Sir:

This letter serves to respond to Mr. S. A. Varga's letter dated March 18, 1983 which transmitted to us an Order confirming licensee commitments on selected post-TMI related issues. The Authority's review of the Confirmatory Order indicates that the status of three items, II.B.2, III.D.3.4, and II.D.1.2 needs to be clarified.

Regarding Item II.B.2, Plant Shielding, the Order states that a substantial amount of work will be completed during the current refueling outage and that about fifteen (15) out of a total of approximately thirty-seven (37) valves will not be completed (shielded, relocated, or motorized) until startup from the next (cycle 4/5) refueling outage. As stated in the Authority's letter dated February 15, 1983 (IPN-83-13), a minimum of fifteen (15) valves will be completed during the current outage, with the balance to be completed prior to startup from the cycle 4/5 refueling outage. The Authority is attempting to complete twenty-two (22) valves during the current outage, subject to the availability of the necessary manpower and materials. As was discussed with NRC Region I personnel during their recently completed Inspection (No. 83-05) concerning this item, the Authority is continuing to evaluate the necessity of shielding, relocating, or motorizing additional valves beyond the thirty-seven (37) referenced in the Confirmatory Order. Any modifications required to automate and (or) facilitate access to the additional valves will be completed prior to startup from the cycle 4/5 refueling outage.

A046

8304210384 830418  
PDR ADOCK 05000286  
P PDR

Regarding Item II.D.1.2, RV & SV Test Programs, it should be noted that the Authority intends to submit the results of a plant-specific analysis of the RV & SV discharge piping by May 31, 1983, as per the commitment made in IPN-83-13.

Regarding Item III.D.3.4, Control Room Habitability, the Order incorrectly states that "qualified" chemical monitors would be installed prior to startup from the next (cycle 4/5) refueling outage. As stated in the Authority's letter dated February 15, 1983 (IPN-83-13), standard grade monitors are being provided to satisfy the requirements of this Item.

Should you or your staff have any questions regarding this matter, please contact Mr. P. Kokolakis of my staff.

Very truly yours,

*C. M. Walounding*

J. P. Bayne  
Executive Vice President  
Nuclear Generation

*Jn*

State of New York  
County of ~~New York~~  
*Westchester*

Subscribed and sworn to before  
me this, *8th* day of *APRIL* 1983.

*Linda Della Donna*

Notary Public *Donna*  
NOTARY PUBLIC, State of New York  
No. 60665985  
Qualified in Westchester County  
Term Expires March 30, 1984

cc: Resident Inspector's Office  
Indian Point Unit 3  
U. S. Nuclear Regulatory Commission  
P. O. Box 66  
Buchanan, New York 10511