REACTOR VESSEL MATERIAL SURVEILLANCE PROGRAM FOR INDIAN POINT UNIT NO. 2 ANALYSIS OF CAPSULE V

.

FINAL REPORT SwRI Project No. 17-2108 (Revised)

Prepared for

Consolidated Edison Company of New York, Inc. 4 Irving Place New York, New York 10003

March 1990



p

9004200464 900330 PDR ADOCK 05000247 PNU

RESEARCH INSTITUTE SOUTHWEST

SAN ANTONIO WASHINGTON, DC HOUSTON DETROIT DALLAS/FT. WORTH

REACTOR VESSEL MATERIAL SURVEILLANCE PROGRAM FOR INDIAN POINT UNIT NO. 2 ANALYSIS OF CAPSULE V

FINAL REPORT SwRI Project No. 17-2108 (Revised)

Prepared for

Consolidated Edison Company of New York, Inc. 4 Irving Place New York, New York 10003

March 1990

Written by

Ŀ

F. A. Iddings D. G. Cadena Mark Williams (Consultant)

Approved by

J. L. Jackson

Director V ' Department of NDE Science and Research Southwest Research Institute

ABSTRACT

ł

Capsule V, the fourth vessel material surveillance capsule removed from the Indian Point Unit No. 2 nuclear power plant, has been tested, and the results have been evaluated. The (October 1988) analysis of the data (1) confirmed the decrease in fluence rate from the low leakage core vs cycles prior to Cycle 6, and (2) indicated that the pressure vessel weld and plate materials will retain adequate shelf toughness throughout the 32 EFPY design life-time using the new Regulatory Guide 1.99, Revision 2. This revision of the original Final Report (October 1988) demonstrates that operation at "stretch power" may considerably reduce the benefits of the low leakage core by the end of 32 EFPY. However, the reactor pressure vessel should continue to meet Regulatory Guide 1.99, Revision 2 and PTS requirements through 32 EFPY.

TABLE OF CONTENTS

,

	<u> </u>	<u>age</u>
LIST OI LIST OI	F FIGURES	iv v
I. .	SUMMARY OF RESULTS AND CONCLUSIONS	I-1
П.	BACKGROUND	II-1
Ш.	DESCRIPTION OF MATERIAL SURVEILLANCE PROGRAM	Ш-1
IV.	TESTING OF SPECIMENS FROM CAPSULE V	IV-1
	A.Shipment, Opening, and Inspection of CapsuleIB.Neutron DosimetryIC.Mechanical Property TestsID.Chemical Analysis ResultsI	(V-1 (V-2 V-13 V-25
V.	RESULTS OF ANALYSIS	V-1
VI.	HEATUP AND COOLDOWN LIMIT CURVES FOR NORMAL OPERATION OF INDIAN POINT UNIT NO. 2	VI-1
VII.	REFERENCES	/II-1
APPEN	DIX A - Tensile Test Data Records	۰.

LIST OF FIGURES

6

<u>Figure</u>	Page
Ш-1	Arrangement of Surveillance Capsules in the Pressure Vessel
III-2	Indian Point Unit 2 Reactor Geometry III-3
III-3	Vessel Material Surveillance Specimens III-5
III-4	Arrangement of Specimens in Capsule V III-6
III-5	Surveillance Capsule Geometry III-7
IV-1	Uranium and Neptunium Containers as Removed from Dosimeter Block IV-3
IV-2	Radiation Response of Indian Point Unit 2 Shell Plate B2002-2 IV-18
IV-3	Radiation Response of Indian Point No. 2 Weld Metal
IV-4	Radiation Response of Indian Point No. 2 Heat Affected Zone Material
IV-5	Radiation Response of Indian Point No. 2 Correlation Monitor Material
V-1	Predicted Decrease in Shelf Energy as a Function of Copper Content and Fluence
VI-1	Indian Point Unit No. 2 Reactor Coolant Heat Up Limitations Applicable for Periods Up to 32 Effective Full Power Years (With Criticality Limit)
VI-2	Indian Point Unit No. 2 Coolant Cooldown Limitations Applicable for Periods Up to 32 Effective Full Power Years
VI-3	Indian Point Unit No. 2 Reactor Coolant Heatup Limitations Applicable for Periods Up to 32 Effective Full Power Years (With Leak Test Limit)
VI-4	Indian Point Unit No. 2 Coolant Cooldown Limitations Applicable for Periods Up to 15 Effectuve Full Power Years VI-6
VI-5	Indian Point Unit No. 2 Coolant Cooldown Limitations Applicable for Periods Up to 20 Effective Full Power Years
VI-6	Indian Point Unit No. 2 Coolant Coodown Limitations Applicable for Periods Up to 32 Effective Full Power Years

LIST OF TABLES

<u>Table</u>	Page
III-1	Indian Point Unit No. 2 Reactor Vessel Surveillance Materials
III-2	Capsule V Neutron Flux Dosimeters III-8
IV-1	Summary of Reactor Operations IV-5
IV-2	Results of Discrete Ordinates Sn Transport Analysis
IV-3	Dosimeter Activities and Measured Fluence Rate in Capsule V
IV-4	Thermal Neutron Fluence Rate in Indian Point 2, Capsule V
IV-5	Charpy Impact Data With Photos of Fracture Faces
IV-6	Charpy Impact Data With Photos of Fracture Faces (Cont'd) IV-15
IV-7	Charpy Impact Data With Photos of Fracture Faces (Cont'd) IV-16
IV-8	Charpy Impact Data With Photos of Fracture Faces (Cont'd) IV-17
IV-9	Summary of RT _{NDT} Shifts and Upper Shelf Energy Reduction (C _v) for Materials in Capsule V
IV-10	Tensile Test Data Records IV-24
IV-11	Summary of Chemistry Values for Indian Point Unit No. 2 Materials IV-25
IV-12	Chemistry Factors for Indian Point-2 Materials Based on Reg. Guide 1.99, Rev. 2
V-1	Adjusted RT _{NDT} Values for Indian Point-2
V-2	Comparison of Measured and Calculated RT _{NDT} Values for Indian Point-2 Capsule V Materials V-6
V-3	Reactor Vessel Surveillance Capsule Removal Schedule V-8
V-4	Comparison of End of Cycle 8 Fluence Values from Transport Calcula- tions and Capsule V Dosimetry Analysis V-9

L SUMMARY OF RESULTS AND CONCLUSIONS

The analysis of the fourth material surveillance capsule removed from the Indian Point Unit No. 2 reactor pressure vessel led to the following conclusions:

- (1) Based upon the analysis of dosimetry data at the end of Cycle 8, the fast neutron flux (E > 1 MeV) at Capsule V location was $1.59 \times 10^{10} \text{ n/cm}^{-2} \text{ sec}^{-1}$.
- (2) The surveillance specimens of the core beltline plate materials experienced shifts in RT_{NDT} (from Charpy Impact curves) over the range of 80°F (46 ft-lb value for Plate B2002-2) to 239°F (50 ft-lb value for Weld) as a result of fast neutron exposure up to the 1987 refueling outage.
- (3) Based on a calculated neutron spectral distribution, Capsule V received a fast fluence of $5.3 \times 10^{18} \text{ n/cm}^2$ (E > 1 MeV) at its radial center line at the end of Cycle 8 operation in 8.6 EFPYs.
- (4) From the previous capsule, Z, the estimated maximum neutron fluence of $3.33 \times 10^{18*}$ neutrons/cm² (E > 1 MeV) was received by the vessel wall in 5.17 effective full power years (EFPY) through Cycle 5, which is equal to a fluence rate of 6.44 x 10^{17*} per EFPY. At the end of Cycle 8 (8.6 EFPY) the neutron fluence at the vessel wall was 4.45×10^{18} n/cm^2 . This gives 3.26×10^{17} n/cm^2 per EFPY for Cycles 6 through 8. The use of a low leakage core loading pattern beginning with Cycle 6 reduced the fluence rate on the pressure vessel wall by 50.6%, based upon data from surveillance capsules.

(5) The core beltline plate (B2002-3) exhibited the largest calculated adjusted RT_{NDT} (ART) change and is projected to control the heatup and cooldown limitations throughout the design lifetime of the pressure vessel.

[&]quot;Revised from Capsule Z report using the latest plant specific lead factors.

(6) The Indian Point Unit No. 2 vessel plate (B2002-3) located in the core beltline region is the controlling material and is projected to retain sufficient toughness to meet the current 50 ft-lb Charpy upper shelf requirements of 10CFR50 Appendix G throughout the design life of the pressure vessel using Revision 2 requirements of Regulatory Guide 1.99.

(7) Based on Regulatory Guide 1.99, Rev. 2, trend curves, the projected maximum ART for the Indian Point Unit No. 2 vessel plate beltline materials at the 1/4T and 3/4T positions after 32 EFPY of operation are 240°F and 194°F, respectively. These values were used as the bases for computing heatup and cooldown limit curves to be used for up to 32 EFPY of operation. Estimated fluences for calculating 15, 20, and 32 EFPY values of ART are based upon assuming Indian Point Unit No. 2 operation at "stretch power" of 3071.4 MWL and vessel T_{ave} of 579.7°F starting from Cycle 10.

IL BACKGROUND

The allowable loadings on nuclear pressure vessels are determined by applying the rules in Appendix G, "Fracture Toughness Requirements," of 10CFR50 (1). In the case of pressure-retaining components made of ferritic materials, the allowable loadings depend on the reference stress intensity factor (K_{IR}) curve indexed to the reference nil ductility temperature (RT_{NDT}) presented in Appendix G, "Protection Against Non-Ductile Failure," of Section III of the ASME Code (2). Further, the materials in the beltline region of the reactor vessel must be monitored for radiation-induced changes in RT_{NDT} per the requirements of Appendix H, "Reactor Vessel Material Surveillance Program Requirements," of 10CFR50.

The RT_{NDT} must be established for all materials, including weld metal and heat-affected zone (HAZ) material as well as base plates and forgings, which comprise the reactor coolant pressure boundary.

It is well established that ferritic materials undergo an increase in strength and hardness and a decrease in ductility and toughness when exposed to neutron fluences in excess of 10^{17} neutrons per cm² (E > 1 MeV) (<u>3,4</u>). Also, it has been established that tramp elements, particularly copper and nickel, affect the radiation embrittlement response of ferritic materials (<u>5-7</u>). The relationship between increase in RT_{NDT} and copper and nickel content is defined in Regulatory Guide 1.99, Rev. 2. Estimates of shifts in RT_{NDT} in this report are based on the May 1988 version of Revision 2 of Regulatory Guide 1.99 (8).

In general, the only ferritic pressure boundary materials in a nuclear plant which are expected to receive a fluence sufficient to affect RT_{NDT} are those materials which are located in the core beltline region of the reactor pressure vessel. Therefore, material surveillance programs include specimens machined from the plate or forging material and weldments which are located in the core beltline region of high neutron flux density to provide the data required to assess the degree of neutron

embrittlement. ASTM E 185 (9) describes the recommended practice for monitoring and evaluating the radiation-induced changes occurring in the mechanical properties of pressure vessel beltline materials.

Westinghouse has provided such a surveillance program for the Indian Point Unit No. 2 nuclear power plant (10). The encapsulated C_v specimens are located on the O.D. surface of the thermal shield where the fast neutron flux density is 1.08 times that at the adjacent vessel wall surface (at 4° for Capsule V, see Table IV-2) (17). Therefore, the increases (shifts) in transition temperatures of the materials in the pressure vessel are slightly less than the corresponding shifts observed in the surveillance specimens. However, because of azimuthal variations in neutron flux density, capsule fluences may lead or lag the maximum vessel fluence in a corresponding exposure period. The capsules also contain several dosimeter materials for experimentally determining the average neutron flux density at each capsule location during the exposure period.

The Indian Point Unit No. 2 material surveillance capsules also include tensile specimens as recommended by ASTM E 185. At the present time, irradiated tensile properties are used only to indicate that the materials tested continue to meet the requirements of the appropriate material specification. In addition, the material surveillance capsules contain wedge opening loading (WOL) fracture mechanics specimens. Current technology limits the testing of these specimens at temperatures well below the minimum service temperature to obtain valid fracture mechanics data per ASTM E 399 (<u>11</u>), "Standard Method of Test for Plane-Strain Fracture Toughness of Metallic Materials." Currently, the NRC suggests storing these specimens until an acceptable testing procedure has been defined for determining the J_{Ic} fracture toughness (<u>12</u>).

This report describes the results obtained from testing the contents of Capsule V. These data and those obtained previously from Capsules T, Y, and Z (<u>13-15</u>) are analyzed to estimate the radiation-induced changes in the mechanical properties of the pressure vessel at the end of Cycle 8 as well as predicting the changes expected to occur at selected times in the future operation of the Indian Point Unit No. 2 power plant. The future projections are based on the continued use of a low leakage core loading pattern, put in service at the start of Cycle 6, which involves placing burnt assemblies at

II-2

the periphery and minimal fresh assemblies instead of all fresh assemblies at the periphery so that the peak vessel wall neutron flux is reduced by approximately 45 to 50 percent. Use of "stretch power" and higher vessel T_{avg} beginning with Cycle 10 increases the neutron flux by approximately 25 percent.

III. DESCRIPTION OF MATERIAL SURVEILLANCE PROGRAM

The Indian Point Unit No. 2 material surveillance program is described in detail in WCAP 7323 (10), dated May 1969. Eight materials surveillance capsules (five Type I and three Type II) were placed in the reactor vessel between the thermal shield and the vessel wall before startup (see Figures III-1 and III-2). The vertical center of each capsule is opposite the vertical center of the core. The neutron flux density at each 4° capsule location slightly exceeds 1.00 times the maximum flux density on the vessel I.D. (17). However, the peak vessel exposure rate has been significantly reduced since the introduction of a low leakage core loading pattern in Cycle 6.

Capsule V, a Type II capsule, was removed during the 1987 refueling outage. The Type II capsules each contain Charpy V-notch, tensile, and WOL specimens machined from the three SA533 Gr B, Cl 1 beltline shell plates. Westinghouse confirmed that the nozzle shell has three plates; the intermediate shell has three plates and the lower shell has two plates as provided in the capsule report. Plate numbers confirmed as B2003-1 and B2003-2, plus Charpy V-notch specimens machined from a correlation monitor heat of steel. The chemistries and heat treatments of the vessel surveillance materials are summarized in Table III-1. All test specimens were machined from the test materials at the quarter-thickness (1/4T) location. The longitudinal base metal C_v specimens were oriented with their long axis parallel to the primary rolling direction and with V-notches perpendicular to the major plate surfaces. Tensile specimens were machined with the longitudinal axis parallel to the plate primary rolling direction and to the major plate surfaces. All mechanical test specimens (see Figure III-3) were taken at least one plate thickness from the quenched edges of the plate material.







Ĩ

Figure III-2. Indian Point Unit 2 reactor geometry (Reference 17)

Table III-1

INDIAN POINT UNIT NO. 2 REACTOR VESSEL SURVEILLANCE MATERIALS (10)

Heat Treatment History

Shell Plate Material:

Heated to 1550-1600°F for 4 hours, water quenched. Tempered at 1225°F for 4 hours, air cooled. Stress relieved at 1150°F for 40 hours, furnace cooled to 600°F

Weldment:

Stress relieved at 1150°F for 19.75 hours, furnace cooled to 600°F

Correlation Monitor:

1650°F, 4 hours, water quenched to 300°F 1200°F, 6 hours, air cooled.

Chemical Composition (Percent)

Material	<u> </u>	<u>Mn</u>	_ <u>P_</u>	<u> </u>	Si	Ni	Mo	Cu
Plate B2002-1	0.20	1.28	0.010	0.019	0.25	0.58	0.46	0.25
Plate B2002-2	0.22	1.30	0.014	0.018	0.22	0.46	0.50	0.14
Plate B2002-3	0.22	1.29	0.011	0.020	0.25	0.57	0.46	0.14
Correlation Monitor	0.24	1.34	0.011	0.023	0.23	(a)	0.51	(a)
Weld Metal	(a)	(a)	(a)	(a)	(a)	(a)	(a)	(a)

(a) Not reported in WCAP 7323 (10).

This additional information on the weld was obtained from Westinghouse in a telecon on February 2, 1990, in response to an NRC inquiry concerning the conditions under which the surveillance weld was made:

The surveillance weld is part of the longitudinal reactor weld. The W5214 is a part of the heat number for the weld wire used in making the submerged arc weld. The complete heat number is W5214 N7048A. The weld wire type is RAC03+NI200. Cu, Ni, and Cr were not analyzed in the wire analysis. No chemistry was performed on the as-deposited weld metal. The flux used was Linde #92; lot number 3600.

In addition, the NRC requested a clarification on the number of plates used to form the lower shell section. Westinghouse confirmed that the nozzle shell has three plates; the intermediate shell has three plates; and the lower shell has two plates as provided in the capsule report. Plate numbers confirmed as B2003-1 and B2003-2.

Capsule V contained 32 Charpy V-notched specimens, 4 tensile specimens (2 from weld metal and 2 from plate), and 4 base plate WOL specimens. The specimen numbering system and location within Capsule V is shown in Figures III-4 and III-5.



(a) Charpy V-notch Impact Specimen



(b) Tensile Specimen



(c) Wedge Opening Loading Specimen





Figure III-4. Arrangement of specimens in Capsule V



NOTE: ALL DIMENSIONS ARE IN CENTIMETERS

Figure III-5. Surveillance capsule geometry

(Reference 17)

Capsule V also contained the following dosimeters for determining the neutron flux density:

Table III-2

CAPSULE V NEUTRON FLUX DOSIMETERS

Target Element	Form	<u>Quantity</u>
· .		
Copper	Bare wire	2
Nickel	Bare wire	1
Cobalt (in aluminum)	Bare wire	3
Cobalt (in aluminum)	Cd shielded wire	3
Uranium	Oxide	1
Neptunium	Oxide	1

In addition, ends were cut from 10 tested Charpy specimens to serve as iron dosimeters.

Three eutectic alloy thermal monitors had been inserted in holes in the steel spacers in Capsule V. Two (located at the top and bottom) were 2.5% Ag and 97.5% Pb with a melting point of 579°F. The other (located at the center of the capsule) was 1.75% Ag, 0.75% Sn, and 97.5% Pb having a melting point of 590°F.

IV. TESTING OF SPECIMENS FROM CAPSULE V

The capsule shipment, capsule opening, specimen testing, and reporting of results were carried out in accordance with the Project Plan for Indian Point Unit No. 2 Reactor Vessel Irradiation Surveillance Program. The SwRI Nuclear Projects Operating Procedures called out in this plan include:

- XIII-MS-104-1, "Shipment of Westinghouse PWR Vessel Material Surveillance Capsule Using SwRI Cask and Equipment"
- (2) XI-MS-101-1, "Determination of Specific Activity and Analysis of Radiation Detector Specimens"

(3) XI-MS-103-1, "Conducting Tension Tests on Metallic Specimens"

- (4) XI-MS-104-1, "Charpy Impact Tests on Metallic Specimens"
- (5) XIII-MS-103-1, "Opening Radiation Surveillance Capsules and Handling and Storing Specimens"

Copies of the above documents are on file at SwRI.

ļ

A. Shipment, Opening, and Inspection of Capsule

Southwest Research Institute utilized Nuclear Projects Operating Procedure XIII-MS-104-1, as incorporated in approved Consolidated Edison Co. procedures, for the shipment of Capsule V to the SwRI laboratories. On March 30, 1988, SwRI personnel severed the capsule from its extension tube, sectioned the extension tube into several lengths, supervised the loading of the capsule and extension tube materials into the shipping cask, and transported the cask to San Antonio, Texas. The capsule arrived at the SwRI Radiation Laboratory on April 5, 1988, and unloading of the capsule commenced the next day. The capsule was opened and the contents identified and stored in accordance with Procedure XIII-MS-103-1. The long seam welds were milled off using a Bridgeport vertical milling machine. Before milling the long seam weld beads, transverse saw cuts were made to remove the capsule ends. After the long seam welds had been milled off, the top half of the capsule shell was removed. The specimens and spacer blocks were carefully removed and placed in indexed receptacles identifying each capsule location. After the disassembly had been completed, each specimen was carefully checked to insure agreement with the identification and location as listed in WCAP 7323 (10). The following discrepancies were found and corrected:

Two Charpies were both marked R-55 on one end and R-56 on the other end. The Charpy that was in the R-55 position was remarked properly on the other end and the R-56 Charpy was also remarked by crossing out the R-55 and remarking the end as R-56.

The thermal monitors and neutron dosimeter wires were removed from the holes in the spacers. The thermal monitors, contained in quartz vials, were examined. No evidence of melting was observed, thus indicating that the maximum temperature during exposure of Capsule V did not exceed 579°F. All neutron dosimeters were in the positions called out in WCAP 7323 and were correctly accounted for. However, the Neptunium container had an appearance that had not been encountered before. The Uranium and Neptunium containers are shown in Figure IV-1. The deformed condition of the Neptunium container caused the loss of most of the sample during opening.

B. Neutron Dosimetry

ł

The dosimeter wires were weighed on a Mettler microbalance, and the Charpy slices were weighed on a Mettler digital balance. The gamma activities of the dosimeters were determined in accordance with Procedure XI-MS-101-1 using an IT-5400 multichannel analyzer and an intrinsic Ge coaxial detector system. The calibration of the equipment was accomplished with 54 Mn, 60 Co, and





¹³⁷Cs radioactivity standards obtained from the U.S. Department of Commerce National Bureau of Standards. All activities were corrected to the time-of-removal (TOR) at reactor shutdown.

Infinitely dilute saturated activities (A_{SAT}) were calculated for each of the dosimeters because A_{SAT} is directly related to the product of the energy-dependent microscopic activation cross section and the neutron flux density. The relationship between A_{TOR} and A_{SAT} is given by:

$$\frac{A_{\text{TOR}}}{A_{\text{SAT}}} = \sum_{m=1}^{m=n} P_m \left(1 - e^{\lambda T} m\right) e^{-\lambda t} m$$

where: λ = decay constant for the activation product, day ⁻¹;

 $t_m = decay time after operating period m, days;$

T_m = operating days;

 P_m = average fraction of full power during operating period.

The values of T_m and P_m up to the 1987 refueling shutdown for Indian Point Unit No. 2 are presented in Table IV-1. The calculation of the neutronic factors is described below.

Westinghouse performed a two-dimensional ordinates S_n transport analysis to determine the neutron fluxes and energy spectrum within the reactor vessel and surveillance capsule of Indian Point Unit 2. This analysis was undertaken to calculate the spectrum averaged cross sections for the threshold and the fission detectors, the lead factors for use in relative neutron exposure of the pressure vessel to that of the surveillance capsule and iron atom displacement (DPA).

Westinghouse undertook two distinct calculations for the Indian Point Unit 2 reactor pressure vessel. First was a single computation in the conventional forward mode to obtain relative neutron energy distributions throughout the reactor geometry as well as through the vessel wall. This transport calculation was carried out in R, Θ geometry using the DOT two- dimensional discrete ordinates code and the SAILOR cross-section library. The SAILOR library is a 47 group ENDFB-IV based data set produced specifically for light water reactor applications. In this calculation P₃ anisotropic scattering

• •

6

Ì

SUMMARY OF REACTOR OPERATIONS INDIAN POINT UNIT NO. 2

Operating Period	Da Start	ites Stop	Operating Days (T _m)	Shutdown Days	Fraction of Full Power (P _m)
1	08/15/73	08/24/73	10		0.4377
0	08/25/73	08/25/73	• 19	1	0 4532
2	08/28/73	09/01/13	13	13	0.4002
. 3	09/21/73	09/28/73	8		0.3161
-	09/29/73	09/30/73	_	2	•• ·
4	10/01/73	10/12/73	12		0.3088
_	10/13/73	01/25/74	-	105	
5	01/26/74	01/29/74	4	 E 1	0.2412
ß	01/30/74	$\frac{03}{21}/14}{04}/18/74}$	- 28	51	0.5438
Ņ	03/22/14	04/18/74	20	10	0.0100
7	04/29/74	05/03/74	5		0.4962
	05/04/74	05/04/74		1	·
8	05/05/74	05/10/74	6		0.4743
	05/11/74	05/12/74		2	
9	05/13/74	05/13/74	1		0.0730
	05/14/74	05/20/74	-	7	
10	05/21/74	06/14/74	25		. 0.0053
11	06/15/74	06/16/74	26	2	0 7691
.11	00/11/14	07/22/14			0.1001
12	07/24/74	07/26/74	3		0.7593
	07/27/74	08/05/74	· ••	10	
13	08/06/74	09/06/74	32		0.6653
	09/07/74	09/09/74		3	
14	09/10/74	09/30/74	21		0.7429
	10/01/74	10/11/74	-	11	
15	10/12/74	11/09/74	29		0.8637
10	11/10/74	11/10/74		1 -	
10	11/11/14	12/06/74	20		0.8300
17	12/07/14	12/07/74		1	0 8495
11	01/02/75	01/04/75	20	3	
18	01/05/75	01/05/75	1		0.5450
**	01/06/75	01/06/75		1	
19	01/07/75	01/31/75	25	-	0.8810
	02/01/75	02/02/75		2	
20	02/03/75	02/28/75	26		0.9408
	03/01/75	04/03/75	-	34	
21	04/04/75	05/02/75	29		0.7632
00	05/03/75	05/03/75		Ļ	
22	00/04/10	07/28/78	00		0.9114
23	01/29/15	08/10/75		15	0.7108
20	09/13/75	09/13/75	-	1	
24	09/14/75	10/16/75	33		0.7962
	10/17/75	10/29/75		13	
25	10/30/75	11/14/75	16		0.7467
	11/15/75	11/15/75		1	
26	11/16/75	01/04/76	50		0.8427
~~	01/05/76	01/05/76	-	1	
27	01/06/76	01/29/76	24		0.8703
98	01/03/76	02/04/76	 EE	b	 0 0199
20	02/00/76	09/26/76	50	180	0.3122
29	09/27/76	09/27/76			0.0680
	09/28/76	09/28/76	÷.	1	
30	09/29/76	10/29/76	31	- 	0.8423
	10/30/76	12/10/76		42	

IV-5

• :;

SUMMARY OF REACTOR OPERATIONS INDIAN POINT UNIT NO. 2 (CONT'D)

Operating Period	De Start	ates Stop	Operating Days (T _m)	Shutdown Days	Fraction of Full Power (P _m)
31	12/11/76	01/27/77	48	-	0.8396
39	01/28/77	01/29/77	 2	2	0 7250
02	02/02/77	02/05/77	5	4	0.1250
33	02/06/77	03/11/77	34		0.8825
	03/12/77	03/14/77		. 3	
34	03/15/77	04/10/77	27	-	0.9242
95	04/11/77	05/13/77		33	
30	00/14/77	07/02/77	50		0.8936
36	08/06/77	08/19/77	14		0.6372
	08/20/77	08/21/77		2	
37	08/22/77	02/13/78	176		0.9022
	02/14/78	05/24/78		100	
38	05/25/78	07/28/78	65		0.8960
90	07/29/78	07/30/78		2	
39	07/31/78	09/10/78	41	> 20	0.9820
40 ·	10/06/78	10/05/78	 49 -	20	0.9360
10	11/24/78	12/02/78		9	
41	12/03/78	06/15/79	195		0.9690
	06/16/79	09/14/79		- 91	
42	09/15/79	11/27/79	74		0.8120
	11/28/79	11/29/79		2	••• ·
43	11/30/79	12/02/79	3		0.1840
44	12/03/79	12/07/79		8	0.8710
44	01/12/78	02/09/80		29	0.0710
45	02/10/80	02/14/80	5		0.4200
	02/15/80	02/18/80		4	
46	02/19/80	06/03/80	106	 ,	0.9310
	06/04/80	06/11/80		8	••
47	06/12/80	08/10/80	60		0.9310
40	08/11/80	08/13/80	 CE	3	
40	10/18/80	10/17/00	03		0.9400
49	05/22/81	07/10/81	50		0.7120
	07/11/81	07/11/81	-	1	••
50	07/12/81	08/21/81	41		0.9640
	08/22/81	09/15/81		25	
51	09/16/81	10/05/81	20	-	0.9040
50	10/06/81	10/15/81		10	
52	10/16/81	11/11/81	27		0.9710
53	11/93/81	04/02/82	131	11 	0 9590
00	04/03/82	04/03/82	-	1	
54	04/04/82	05/17/82	44	· -	0.9230
	05/18/82	05/23/82		6	
55	05/24/82	08/12/82	81		0.9520
	08/13/82	08/14/82		2	
56	08/15/82	09/02/82	19		0.7890
57	09/03/82	09/07/82		5	0.7090
01	09/08/82 09/18/89	03/11/82	10	106	0.7960
58	01/02/83	01/05/83		100	0.3485
	01/06/83	01/06/83		1	
59	01/07/83	01/08/83	2		0.0355
	01/09/83	01/10/83		2	••
60	01/11/83	01/31/83	21		0.7393
	02/01/83	02/11/83		11	

IV-6

ŢŦ

SUMMARY OF REACTOR OPERATIONS INDIAN POINT UNIT NO. 2 (CONT'D)

Operating	D٤	ites	Operating Days	Shutdown	Fraction of Full Power
Period	Start	Stop	(T _m)	Days	(P _m)
61	00/10/02	00/10/00			0.0000
01	02/12/03	02/13/83	2	1	0.0050
62	02/15/83	02/18/83	4		0.1025
	02/19/83	02/19/83	-	1	
63	02/20/83	08/27/83	. 189	••	0.9619
	08/28/83	08/28/83		1	••
64	* 08/29/83	10/04/83	37		0.9572
	10/05/83	10/25/83		21	
65	10/26/83	01/05/84	72	-	0.9248
00	01/06/84	01/07/84		2	••
66	01/08/84	02/11/84	35		0.9228
07	02/12/84	02/26/84	-	15	
67	02/27/84	00/01/84	96		0.9100
60	06/02/84	10/20/84		141	0.8706
00	10/21/04	11/30/04	41		0.0100
60	12/01/04	12/01/04		1	0.9147
05	12/02/04	12/15/04	10	7	0.3147
70	12/20/04	12/20/04			0.0060
	12/21/04	12/20/04	4 ·	. 3	
71	01/01/85	09/20/85	263		0.9509
• •	09/21/85	09/22/85	. 200	2	
72	09/23/85	10/21/85	29	-	0.6813
•=	10/22/85	10/23/85	-	2	••
73	10/24/85	01/13/86	82		0.9298
	01/14/86	05/24/86		131	
74	05/25/86	05/28/86	4		0.1688
	05/29/86	05/29/86	-	1	
75	05/30/86	05/31/86	2		0.2885
	06/01/86	06/06/86	-	6	
76	06/07/86	06/09/86	3		0.1020
	06/10/86	06/10/86		1	
77	06/11/86	10/20/86	132		0.9339
	10/21/86	10/22/86		2	
78	10/23/86	10/23/86	1		0.0710
	10/24/86	10/26/86		3	••
79	10/27/86	11/06/86	11	'	0.9146
	11/07/86	11/08/86		2	
80	11/09/86	11/15/86	7	••	0.7864
	11/16/86	11/16/86		1	•••••
81	11/17/86	01/30/87	75		0.9393
00	01/31/77	02/06/87	·	7	
82	02/07/87	02/10/87	4		0.7058
00	02/11/87	02/12/8/		Z	0.0904
53	02/13/87	00/21/81	130		0.9804
84	00/28/87	10/23/81		2	 0.0810
04	00/30/87	10/04/07	51		0.3010

and S₈ order of angular quadrature was used. The reference forward calculations were normalized to a core mid-plane power density characteristic of operation at a thermal power level of 2758 MWt.

The second calculation consisted of a series of adjoint analysis relating the fast neutron flux (E > 1.0 MeV) at surveillance capsule positions and several azimuthal locations on the pressure vessel inner radius to neutron source distributions within the reactor core. All adjoint analyses were also carried out using an S₈ order of angular quadrature and P₃ anisotropic scattering using the 47 group SAILOR Library as described above.

The core power distributions for each cycle used in fast neutron exposure evaluation were taken from Indian Point Unit 2 nuclear design reports.

The pertinent factors (i) calculated spectrum averaged reaction cross sections and (ii) calculated cycle dependent fluence lead factors obtained from these transport calculations are summarized in Table IV-2. The calculated spectrum averaged reaction cross sections are employed in the analysis of fast neutron monitors activity data for the prediction of fast neutron flux/fluence (E > 1.0 MeV) at surveillance capsule location and the calculated lead factors for the prediction of reactor vessel flux/fluence (E > 1.0 MeV) from the surveillance. Neutron Cycle 5 lead factor results given in Table IV-2 are representative of a standard loading pattern cycle as Indian Point Unit 2 employed this loading pattern from Cycle 1 through Cycle 5. Cycle 8 results are for the low leakage loading pattern as the low leakage loading pattern was implemented at Indian Point Unit 2 starting from Cycle 6.

The primary result desired from the dosimeter analysis is the total neutron fluence (E >1 MeV) which the surveillance specimens and pressure vessel have received. The average flux at full power is given by:

$$\phi = A_{SAT} / N_o^{\sigma}$$

Bq

5

Ì

=Saturated activity (rate of decay = rate of production) in disintegration/sec or A_{SAT} energy dependent neutron flux, n/cm² sec where ϕ

> spectrum-averaged activation cross section, cm²; and σ

 N_0 = number of target atoms per mg.

The total neutron fluence is then equal to the product of the average neutron flux and the equivalent reactor operating time at full power.

RESULTS OF DISCRETE ORDINATES Sn TRANSPORT ANALYSIS (<u>17</u>) INDIAN POINT UNIT NO. 2

A.

Calculated Spectrum-Averaged Reaction Cross Sections (σ_{eff}) for Analysis of Fast Neutron Monitors (E > 1.0 MeV)

Reaction	(barns)	
	4°	40°
$^{54}\mathrm{Fe(n,p)}^{54}\mathrm{Mn}$	0.0887	0.067
⁵⁸ Ni(n,p) ⁵⁸ Co	0.116	0.0914
$63_{\mathrm{Cu(n,a)}}60_{\mathrm{Co}}$	0.00119	0.000694
²³⁸ U(n,f) ¹³⁷ Cs	0.372	0.343
²³⁷ Np(n,f) ¹³⁷ Cs	2.63	2.84

B.

Calculated Fluence Lead Factors^(a) for Indian Point-2 Cycles 5 and 8

<u>Cycle</u>		<u>4°</u>	<u>40°</u>
5		1.08	3.42
8	•.	1.19	3.40

${}^{(a)}L.F = \frac{EOC \text{ Fluence at Surveillance Location}}{EOC \text{ Fluence at RPV O-T Location} }$

In Capsule V, the Correlation Monitor and B2002-2 shell plate Charpy specimens were located in the specimen layer nearest to the vessel wall and the weld metal, heat-affected zone (HAZ) Charpy specimens were located in the specimen layer nearest to the core. Since there is a radial dependence of the fast neutron flux in the vessel, the neutron exposure received by the Correlation Monitor and B2002-2 shell plate Charpy specimens is expected to be lower than that received by the weld metal and HAZ Charpy specimens. The dosimetry program is capable of providing information on the radial dependence of the fast flux because the Charpy ends used for iron dosimetry were taken from both of the Charpy specimen layers (nearest to and farthest from the core).

Since Indian Point Unit No. 2 operated for 8.6 effective full power years (EFPYs) up to the 1987 refueling outage, the calculated fluence rates for Capsule V from dosimetry measurements are as

IV-9

12 M M M M

A star and

presented in Table IV-3. Thermal neutron flux (fluence rate) values from Capsule V are presented in Table IV-4.

Table IV-3

DOSIMETER ACTIVITIES AND MEASURED FLUENCE RATE IN CAPSULE V

Position	Dosimeter ID	ATOR (Bq/Mg)	A _{SAT} (Bq/Mg)	Meas (ured ϕ (> 1 MeV) ^(a) n cm ⁻ 2 sec ⁻¹)
R=211.18 (C	ore Side of Charpy C	<u>Compartment)</u> :			
	Ni	16025.4	16860.0		2.08E10
Bottom	Cu	76.8	138.6		1.76E10
Тор	Cu	79.1	142.8		1.82E10
Bottom	Fe W-9	670.2	842.4		1.52E10
Bottom	Fe W-12	681.1	856.1		1.54E10
Bottom	Fe H-12	717.7	902.1		1.63E10
Bottom	Fe W-13	667.7	839.1		1.51E10
Тор	Fe H-16	751.3	944.1 [°]		1.70E10
D off of				Ave:	$1.70E10 \pm 1.9E9$
<u>R=211.68</u> :					
	238 U	239.1	1398.3	,	2.47E10
	237 Np	(9820)	(5740)		(1.31E11)
	NOTE: Np Res was recovered	sults are not reliab (see comments in	le because an inad text)	equate sam	ple
R = 212.18 (V	essel Side of Charpy	Compartment):			
Bottom	Fe 2-41	571.9	718.8		1.30E10
Bottom	Fe 2-44	582.0	731.5		1.32E10
Bottom	Fe R-52	615.6	773.8		1.39E10
Bottom	Fe 2-45	565.8	711.2		1.28E10
Тор	Fe R-56	622.3	782.2		1.41E10
•				Ave:	$1.34E10 \pm 6.0E8$

^(a)Measured ϕ (> 1 MeV) = $\frac{A_{SAT}}{N_o \sigma_{eff}}$ = $\frac{(A_{TOR}/h)}{N_o \sigma_{eff}}$

Table IV-3 (Cont'd)

DOSIMETER ACTIVITIES AND MEASURED FLUENCE RATE IN CAPSULE V

Radial Position	Dosimeter ID	Dosimeter ϕ (> 1 MeV) n/cm ² sec	Gradient Factor	Centerline ϕ (> 1 MeV) n/cm ² sec	
211.18	Ni Cu (bottom)	2.08E10 1.76E10	0.953 0.956	1.98E10 1.68E10	
	Cu (Top), Fe W-9 Fe W-12	1.82E10 1.52E10 1.54E10	0.956 0.951 0.951	1.74E10 1.45E10 1.46E10	
	Fe H-12 FeW-13	1.63E10 1.51E10 1.51E10	0.951 0.951 0.951	1.46E10 1.55E10 1.44E10	
211.68	Fe H-16 238 _U (a)	1.70E10 2.47E10	0.951 1.050	1.62E10 2.60E10	
	237 _{Np} (a)	1.37E11	1.049	1.44E11	
212.18	Fe 2-41 Fe 2-44 Fe R-52 Fe 2-45	1.30E10 1.32E10 1.39E10 1.28E10	$1.152 \\ 1.152 \\ 1.152 \\ 1.152 \\ 1.152$	1.50E10 1.52E10 1.60E10 1.47E10	
	Fe R-56	1.41E10	1.152	1.62E10	. ,

Determination of Fluence Rate at Centerline of Surveillance Capsule V, Indian Point-2

Average ^(a) Fluence Rate = 1.59E10±1.5E9 at Center of Capsule V

 $^{\rm (a)238}{\rm U}$ and $^{237}{\rm Np}$ results not included in average

(Cs-137 half life allows influence from high leakage cores in cycles 1 through 5)

 \pm Value is 1 σ from variation of individual values included in the average

	⁵⁹ Co Ba	re	⁵⁹ Co Cd Covered				
Axial Location	A _{TOR} , Bq/Mg	A _{SAT} , ^(a) Bq/Mg	A _{TOB} , Bq/Mg	A _{SAT} , ^(a) Bq/Mg	Thermal Flux n/cm ² -s		
Тор	3.22E6	5.81E6	1.37E6	2.47E6	8.81E9		
Middle	3.10E6	5.60E6	1.39E6	2.51E6	8.15E9		
Bottom	3.49E6	6.30E6	1.28E6	2.31E6	1.05E10		
Average	3.27E6	5.90E6	1.35E6	2.43E6	9.15E9		

THERMAL NEUTRON FLUENCE RATE IN INDIAN POINT 2, CAPSULE V

(a) 60 Co saturation factor = h = .554; A_{SAT} = A_{TOR/h}

The variations in the peak vessel flux values ($\pm 9.4\%$ from variations in individual values) determined from the several dosimeter materials may be attributed to the uncertainties in measurements and calculations (in the calculated spectra and in the reaction cross sections). Uranium dosimeter values are higher than others because the Cs-137 product half-life is 30.1 yr and retains some activity from the earlier higher leakage cores.

Neptunium dosimeter values are not dependable because insufficient material was recovered from the capsule. The aluminum shell containing the Neptunium was brittle and cracked open on the lathe while being opened. Most of the Neptunium oxide was not recoverable.

Averaging the results obtained from the Capsule V iron, copper, and nickel neutron dosimeters, the peak neutron flux incident on the center of Capsule V is calculated from Table IV-3 to be $1.59 \times 10^{10} \text{ n/cm}^2 \text{ sec}$, (E > 1 MeV). This is to be compared to $3.42 \times 10^{10} \text{ n/cm}^2 \text{ sec}$ (E > 1 MeV) as reported in the "Analysis of Capsule Z,:" April 1984 (<u>15</u>).

C. Mechanical Property Tests

The irradiated Charpy V-notch specimens were tested on a calibrated^{**} SATEC Model SI-1K 240 ft-lb, 16 ft/sec impact machine in accordance with Procedure XI-MS-104-1. The test temperatures, selected to develop the ductile-brittle transition and upper shelf regions, were obtained using a liquid conditioning bath monitored with a Fluke Model 2168A digital thermometer. The Charpy V-notch impact data obtained by SwRI on the specimens contained in Capsule V are presented in Tables IV-5 through IV-8. The shifts in the Charpy V-notch transition temperatures determined for the three vessel plates and the correlation monitor are shown in Figures IV-2 through IV-5. The Capsule T (14), Capsule Y (13), and Capsule Z (15) results, included in the figures for comparison, show that Capsule V is a low lead factor, low flux capsule, as expected.

A summary of the shifts in RT_{NDT} determined at the 46 ft-lb level as specified in NUREG-0800 (<u>18</u>) and Appendix G to 10CFR50 (<u>1</u>), and the reduction in C_v upper shelf energies for each material, is presented in Table IV-9.

^{**}Inspected and calibrated using specimens and procedures obtained from the Army Materials and Mechanics Research Center.

CHARPY IMPACT DATA WITH PHOTOS OF FRACTURE FACES

MATERIAL - (WELD)

6

Date June 2, 1988

SPECIMEN NO.	TEMP °F	ENERGY FT-LBS	LATERAL EXPANSION	FRACTURE APPEARANCE	PHOTOGRAPH
W- 9	74°F	24.0	.019	. 0	
W-10	+130	26.5	.023	20	
W-11	+180	40.5	.035	40	
W-12	+220	53.0	. 048	65	
W-13	+260	62.5	. 054	95	
W-14	+300	76.0	064	95	
W-16	+325	72.5	.065	95	
W-15	+350	76.0	.067	100	
		-			

IV-14

CHARPY IMPACT DATA WITH PHOTOS OF FRACTURE FACES (CONT'D)

MATERIAL - B-2002-2

6

Project No. <u>17-2108-001</u> Date June 2, 1988

	SPECIMEN NO.	TEMP °F	ENERGY FT-LBS	LATERAL EXPANSION	FRACTURE APPEARANCE	PHOTOGRAPH
	2-41	74°F	17.5	.016	5	
	2-42	+120	50.0	.042	15	
ſ	2-48	+150	60.5	.046	20	
	2-44	+180	93.0	.059	60	
	2-43	+220	111.0	.080	90	
	2-45	+260	109.5	.078	100	
	2-46	+300	. 116.0	.075	100	
	2-47	+330	106.0	.067	100	
	(

IV-15

TABLE IV-7

CHARPY IMPACT DATA WITH PHOTOS OF FRACTURE FACES (CONT'D)

MATERIAL - (Reference)

.

.

Project No. <u>17-2108-001</u> Date June 2, 1988

	SPECIMEN NO.	TEMP °F	ENERGY FT-LBS	LATERAL EXPANSION	FRACTURE APPEARANCE	PHOTOGRAPH
	R-49	74°F	13.5	.014	5	
	R-50	+130	32.0	.041	20	
	R-56	+150	32.5	.033	30	
ļ	R-51	+180	50.0	.044	75	
	R-52	+230	62.0	.058	95	
	R-53	.+270 •	67.5	059	100	
	R-54	+320	70.5	.064	100	
	R-55	+350	72.0	.062	100	
- 1			_			

TABLE IV-8

CHARPY IMPACT DATA WITH PHOTOS OF FRACTURE FACES (CONT'D)

Project No. 17-2108-001 Date June 2, 1988

MATERIAL - (HAZ)

SPECIMEN NO.	TEMP °F	ENERGY FT-LBS	LATERAL EXPANSION	FRACTURE APPEARANCE	PHOTOGRAPH
H-11	0	30.5	• .023	25	
н-10	+30	85.0	.052	60	
H - 9	RT	53.5	.040	50	
H-12	+110	53.5	.047	80	
H-13	.+150	65.0	.053	80	
H-14	+220	93.5	.068	100	
H-16	+250	78.0	.067	40	
H-15	+280	122.5	.077	100	
PLATE B2002-2





WELD METAL

-





IV-19

HAZ MATERIAL





CORRELATION MONITOR





SUMMARY OF $\mathrm{RT}_{\mathrm{NDT}}$ SHIFTS AND UPPER SHELF ENERGY REDUCTION (C_v) FOR MATERIALS IN CAPSULE V

Type of	Fluence <u>Neutron</u>	Mea	sured RT _{NDT} (°	F)
Material	cm ²	50 Ft-Lbs	30 Ft-Lbs	35 mils*
Weld	5.59E18	239	204	230
		77 Ft-Lbs	46 Ft-Lbs	·
Plate B2002-2	4.57E18	85	80	97
HAZ	5.59E18	190	162	184
Correlation Monitor	4.57E18	NA**	104	108

Summary of Fluence and Measured RT_{NDT} Values for Test Specimens in Capsule V

B. Decrease in Upper Shelf Energy (C_v)

A.

Material	Initial Shelf <u>Ft-lb</u>	Capsule V*** <u>Ft-lb</u>	C _v <u>Ft-lb</u>	<u>% Decrease</u>
B2002-2	117	111	6	5
Weld Metal	118	75	43	36
HAZ	100	98	2 (nil)	2
Correlation Monitor	118	70	48	41

*35 mil + 20°F included in table.

**The upper shelf energy for this capsule was below 77 ft lbs.

*** Average of 3 Charpy measurements at $\approx 100\%$ ductile failure.

Table IV-9 (Cont'd)

SUMMARY OF $\rm RT_{\rm NDT}$ SHIFTS AND UPPER SHELF ENERGY REDUCTION $\rm (C_v)$ FOR MATERIALS IN CAPSULE V

	Shell Plate 1	<u>32002-2</u>		Weld Meta	1
<u>Sample</u>	<u>Ft-Lb</u>	% Ductility*	<u>Sample</u>	<u>Ft-Lb</u>	<u>% Ductility</u>
2-45	109.5	100	W-14	76.0	95
2-46	116.0	100	W-16	72.5	95
2-47	<u>106.5</u>	100	W-15	<u>76.0</u>	100
Ave.**	111.0		Ave.**	75.0	
	Heat-Affecte	<u>d Zone</u>	<u>Co</u>	rrelation Mo	onitor
<u>Sample</u>	<u>Ft-Lb</u>	<u>% Ductility*</u>	Sample	Ft-Lb	% Ductility

Charpy Impact Data for Decrease in Upper Shelf Energy

100

40

100

H-14

H-16

H-15

93.5

78.0

122.5

Ave.** 98.0 Ave.** 70.0 *Fracture Appearance Ave.** Average of 3 highest values with $\approx 100\%$ ductility

R-53

R-54

R-55

67.5

70.5

72.0

100

100

100

Tensile tests were carried out in accordance with Procedure XI-MS-103-1 using a 22-kip capacity MTS Model 810 Material Test System equipped with an Instron Catalogue No. G-51-13A 2-inch strain gage extensometer and Hewlett Packard Model 7004B X-Y autographic recording equipment. Tensile tests on the plate material and the weld metal were run at room temperature at a strain rate of 0.005 in/in/min. through the 0.2% offset yield strength using servo-control and ramp generator. The results, along with the room temperature tensile data reported by Westinghouse on the unirradiated materials (10), are presented in Table IV-10. The load-strain records are included in Appendix B.

TENSILE TEST DATA RECORDS Capsule V DATA^(a)

Test <u>Material</u>	Spe. <u>No.</u>	Temp (F)	0.2%YS <u>(ksi)</u>	UTS (ksi)	Fracture Load (lb)	Fracture Stress <u>(ksi)</u>	Uniform Elongation (%)	Total Elongation (%)	Reduction in Area <u>(%)</u>
Irradiated(a)							•		
Plate	2-2	76	65.3	86.3	2940	157.9	24.6	25.5	62.4
B2002-2	2-7	550	66.4	90.4	3170	250.4	17.9	17.4	74.0
Weld	W-3	76	92.7	106.9	3460	188.2	21.0	22.0	61.6
	W-4	550	82.5	100.2	3460	174.3	19.6	20.7	58.2
Unirradiated ^{(b}))								
Plate		Room	62.4	83.8	. (c)	(c)	(c)	27.1	70.0
. D2002-2		Room	66.8	90.5	(c)	(c)	(c)	28.2	69.6
		600	53.5	78.8	(c)	(c)	· (c)	22.7	64.4
		600	54.7	81.4	(c)	(c)	(c)	24.7	64.4
Weld		Room	64.5	80.7	(c)	(c)	(c)	28.5	73.9
		Room	65.0	81.0	(c)	(c)	(c)	26.9	71.5
		600	. 56.6	79.8	(c)	(c)	(c)	24.4	62.0
		600	56.6	79.2	(c)	(c)	(c)	24.0	66.9

(b)_{WCAP 7323}

(c)_{Data not} reported in WCAP 7323

Testing of the WOL specimens was deferred at the request of Consolidated Edison Company. The specimens are in storage at the SwRI radiation laboratory.

D. Chemical Analysis Results

Check analyses for copper and nickel content of the ten broken Charpy V-notch specimens used for iron dosimetry and the three tested tensile specimens were run using ASTM Method E 322 (<u>19</u>). The results listed in Table IV-11 and IV-12 were obtained. For completeness, the list includes chemistry data from prior analyses of these and other surveillance samples of reactor vessel materials.

Table IV-11

SUMMARY OF CHEMISTRY VALUES FOR INDIAN POINT UNIT NO. 2 MATERIALS

<u>Material</u>

Plate B2002-1

Plate B2002-2

Source of Data	<u>Cu W%</u>	<u>Ni W%</u>
WCAP 7323	(.25)*	(.58)*
Capsule-Z: C., Specimen 1-33	.22	.62
Capsule-Z: C, Specimen 1-38	.19	.71
Capsule-Z: Tensile Specimen 1-5	(.29)*	.61
Capsule-T: C, Specimen 1-2	.17	
Capsule-T: C _v Specimen 1-3	.15	
Capsule-T: Tensile Specimen 1-1	.21	
Average	.19	.65
WCAP 7323	(.14)*	(.46)*
Capsule-V: C, Specimen 2-44	.17	.46
Capsule-V: C _v Specimen 2-44	.15	.41
Capsule-V: Tensile Specimen 2-6	(.06)*	(.27)*
Capsule-V: Tensile Specimen 2-7	(.08)*	.42
Capsule-Z: C _v Specimen 2-33	.19	.47
Capsule-Z: C, Specimen 2-36	.17	.46
Capsule-Z: C _v Specimen 2-40	.20	.50
Capsule-Z: Tensile Specimen 2-5	.15	.52
Capsule-T: C, Specimen 2-2	.18	
Capsule-T: C, Specimen 2-3	.17	**
Capsule-T: Ténsile Specimen 2-1	.13	
Average	.17	.46

Table IV-11 (Cont'd)

SUMMARY OF CHEMISTRY VALUES FOR INDIAN POINT UNIT NO. 2 MATERIALS

Material	Source of Data	<u>Cu W%</u>	<u>Ni W%</u>
Plate B2002-3	WCAP 7328	(14)*	(57)*
<u></u>	Capsule-Z: C. Specimen 3-33	.30	.64
	Capsule-Z: C. Specimen 3-38	.27	.59
	Capsule-Z: Tensile Specimen 3-5	.23	.58
	Capsule-Y: C., Specimen 3-41	.21	
	Capsule-Y: C., Specimen 3-45	.22	
	Capsule-Y: Tensile Specimen 3-6	(.11)*	
	Capsule-Y: Tensile Specimen 3-7	(.10)*	
	Capsule-T: C., Specimen 3-2	.27	
	Capsule-T: C, Specimen 3-3	.23	
	Capsule-T: Tensile Specimen 3-1	(.09)*	
	Average	.25	.60
HAZ	Capsule-V: C _v Specimen H-16	.08	1.2
	Capsule-V: C _v Specimen H-12	.06	1.2
	Capsule-Y: C _v Specimen H-21	.15	
	Capsule-Y: C_v Specimen H-23	.20	
· ·	Average	.12	1.2
Weld	Capsule-V: C _v Specimen W-13	.23	1.02
	Capsule-V: C _v Specimen W-12	.20	1.06
	Capsule-V: Tensile Specimen W-3	.20	(.69)*
	Capsule-V: C _v Tensile Specimen W-4	(.12)*	1.00
_	Capsule-Y: C, Specimen W-17	.19	
	Capsule-Y: C _v Specimen W-19	.22	
	Capsule-Y: Tensile Specimen W-5	.18	
	Capsule-Y: Tensile Specimen W-6	.20	
.*	Average	.20	1.03
Correlation Monitor	Capsule-V: C _v Specimen R-56	.20	.18
	Capsule-V: C _v Specimen R-52	.18	.27
	Capsule-Z: C _v Specimen R-33	.35	.28
	Capsule-Z: C _v Specimen R-36	.31	.27
· · ·	Capsule-Z: C _v Specimen R-40	.21	.21
	Capsule-Y: C _v Specimen R-60	.17	
	Capsule-Y: C _v Specimen R-62	.19	
	Capsule-T: C_v Specimen R-2	.25	
	Average	.23	.24

*Values in parentheses discarded because of excessive deviation or were WCAP values. Surveillance specimen WCAP values not used since chemical analyses were available.

CHEMISTRY FACTORS FOR INDIAN POINT-2 MATERIALS BASED ON REG. GUIDE 1.99, REV. 2

<u>MaterialW% Cu</u>	<u>W% Ni</u>	Chemistry F	Reg. Guide 1.99, Rev. 2 actor (°F)
Plate B2002-1	.19	.65	151
Plate B2002-2	.17	.46	115
Plate B2002-3	.25	.60	176
Surveillance HAZ	.12	1.2	86
Surveillance Weld Mat.	.20	1.03	226
Correlation Monitor	.23	.24	130

V. RESULTS OF ANALYSIS

The analysis of data obtained from surveillance program specimens has the following goals:

- (1) Estimate the period of time over which the properties of the vessel beltline materials will meet the fracture toughness requirements of Appendix G of 10CFR50. This requires a projection of the measured reduction in C_v upper shelf energy to the vessel wall using knowledge of the energy and spatial distribution of the neutron flux and the dependence of C_v upper shelf energy on the neutron fluence.
- (2) Develop heatup and cooldown curves to describe the operational limitations for selected periods of time. This requires a projection of the measured shift in RT_{NDT} to the vessel wall using knowledge of the dependence of the shift in RT_{NDT} on the neutron fluence and the energy and spatial distribution of the neutron flux.

The energy and spatial distribution of the neutron flux for Indian Point Unit No. 2 was calculated for Capsule V with a discrete ordinates transport by the Power Systems Division of Westinghouse Electric Corporation (<u>17</u>). Results from this analysis establish the means for the interpretation of surveillance capsule dosimetry and for the subsequent projection of neutron exposure results to the pressure vessel wall. Furthermore, the results of the evaluations are appropriate for absolute comparison with measurement.

The calculation of fluence up to Cycle 9 assumes a fluence rate of $6.44 \times 10^{17} n/cm^2$ per EFPY through Cycles 1 to 5 in 5.17 EFPYs and a fluence rate of $3.26 \times 10^{17} n/cm^2$ per EFPY through cycles 6 to 9 in 4.46 EFPYS. Up to Cycle 5 Indian Point 2 used a standard loading pattern and the fluence rate is based upon Capsule Z measurements (<u>15</u>) and starting from Cycle 6 Indian Point Unit 2 has been using a low leakage loading pattern and the fluence rate is based upon Capsule V measurements.

The projected fluence starting from Cycle 10 assumes Indian Point Unit 2 operation at 3071.4 MWt instead of 2758 MWt power level and at vessel T_{avg} of 579.7°F instead of 549°F. For the calculation of flux with an increase in $T_{avg'}$ it was assumed that a 1°F increase in vessel T_{avg} would increase vessel flux by 0.5%.

A method for estimating the increase in RT_{NDT} as a function of neutron fluence and chemistry is given in Regulatory Guide 1.99, Revision 2 (8). However, the Guide also permits interpolation between credible surveillance data and chemistry factors and extrapolation by extending the response curves parallel to the guide trend curves. The low flux leakage core loading produced a 48.9% reduction in fast neutronflux (E > 1 MeV) for Cycles 6 through 8 as compared to the first 5 cycles. Revision 2 results from Capsule V are included in this section.

The B2002-3 plate continues to be the controlling material as can be seen in Table V-1. A longterm projection of vessel RT_{NDT} has been made from Cycle 8 and beyond using a low leakage core loading pattern which significantly reduces the pressure vessel fluence rate from that produced by the Design Basic Core (<u>17</u>). Table V-2 is a comparison of measured and calculated RT_{NDT} values. This revision of the original Final Report (October 1988) demonstrates that operation at "stretch power" may considerably reduce the benefits of the low leakage core by the end of 32 EFPY. However, the reactor pressure vessel should continue to meet Regulatory Guide 1.99, Revision 2, and PTS requirements through 32 EFPY.

A method for estimating the adjusted RT_{NDT} and the reduction in C_v upper shelf energy as a function of neutron fluence is also given in Regulatory Guide 1.99, Revision 2 (8). The shelf energy responses of the pressure vessel surveillance materials from all four capsules are reasonably consistent and fall below the predictive trend curves of Regulatory Guide 1.99, Revision 2, for nominal weld chemistries of 0.20% Cu and 1.03% Ni and plate chemistries of 0.25% Cu and 0.60% Ni. Extrapolation to 1.39 x 10¹⁹ n/cm² for 32 EFPY predicts that all Indian Point Unit 2 materials will be below upper limit values for either RT_{NDT} or decrease in shelf energy.

Results are obtained using Revision 2 of Regulatory Guide 1.99 for Capsule V materials in Figure V-1. Extrapolation to 32 EFPY fluence of 1.39 x 10^{19} n/cm² on Figure V-1 gives predicted values below upper limit for weld metal and plate controlling materials.

The current Indian Point Unit No. 2 reactor vessel surveillance program removal schedule conforms to ASTM E 185-79 (9) and is summarized in Table V-3. There are four capsules remaining in the vessel, of which three are standbys.

Table V-4 provides a comparison of End of Cycle 8 (EOC8) fluence values from transport calculations with Capsule V dosimetry analysis and a comparison of projected fluence rates with transport calculations for Cycle 9. These comparisons, comparisons calculated with experimental values, show excellent agreement. EOC8 values differ by only two percent and the fluence rates for Cycle 9 differ by only about 10 percent.

The flux derived from Capsule V, 1.59E10±1.5E9 compared with the transport calculation for the same case agrees within the measurement uncertainties as shown in Table V-4.

	Material	Location	Initial RT _{NDT}	Fluence ^(a) (>1 MeV) DPA	RT _{NDT} Rev. 2	ART (Adjusted RT _{NDT}) <u>Rev. 2</u>	<u>Margin</u>	RT _{PTS}
EOC8	B2002-3	ОТ	21•F	4 45E18	136	205*		
[8.6	(Plate)	1/4T	21	2.9E18	116	185		
EFPY]	()	3/4T	21	1.1E18	77	146		
								•
	HAZ	OT	0 · F	4.5E18	67	115		
		1/4'I'	0	2.9E18	57	105		
		3/41	0	1.1E18	38	86		
	Weld ^(b)	ОТ	-56°F	4.5E18	175	185		
		1/4T	-56	2.9E18	149	159		
		3/4T	-56	1.1E18	99	109		
				•				
15 EFPY	B2002-3	OT	21•F	6.99E18	158	227*		
	(Plate)	1/41	21	4.54E18	137	206		
		3/41	21	1.75E18	95	164		
	HAZ	ОТ	0°F	6.99E18	77	125		
		1/4T	0	4.54E18	67	115		
		3/4T	0 .	1.75E18	46	94		•
	(h)							
	Weld ^(b)	OT	-56°F	6.99E18	203	214		
		1/4T	-56	4.54E18	176	187		
		3/41	-00	1.75E18	122	132	•	
20 EFPY	B2002-3	ОТ	21•F	9.03E18	171	240*		•
	(Plate)	1/4T	21	5.87E18	150	219		
	. ,	3/4T	21	2.26E18	105	174		
			A B					
	HAZ	OT	0 • F	9.03E18	84	132		
		1/4T	0	5.87E18	73	121		
		3/41	0	2.26E18	52	100		
	Weld ^(b)	OT	-56°F	9.03E18	220	230		
		1/4T	-56	5.87E18	192	203		
		3/4T	-56	2.26E18	136	146		
	D 0000 0	05	01 e F	1.007310	100	0.01 *	40	044
32 EFPY	B2002-3		21°F	1.39619	192	261*	48	244
	(Plate)	1/41 9/40	21	9.041.18	1/1	240	48	225
		3/41	41	J.40 <u>C</u> 10	120	134	40	199
	HAZ	OT	0°F	1.39E19	94	142		
		1/4T	0	9.04E18	83	131		
		3/4T	0	3.48E18	61	109		
	•••• • •(h)		F	4.00540	o			10-
	Weld	OT 1/17	-56°F	1.39E19	247	257	66	181
		1/41	-56	9.04E18	220	230	66	162
		3/41	-00	J.48E18	100	170	66	127

ADJUSTED RT_NDT VALUES FOR INDIAN POINT-2

(a) The actual 3/4T and 1/4T fluence used in Rev. 2 results were based on DPA attenuations, conservatively estimated to be 0.65 and 0.25, respectively (see Table V-2). Thus based on this approach the fluence at 3/4T and 1/4T locations is equal to the 0-T fluence multiplied by DPA attenuation factors.

(b) Composition of weld No. 9-042 assumed to correspond to the surveillance data 0.20 percent Cu and 1.03 percent Ni, chemistry factor is 226 F, for Rev. 2 analysis.

* Plate is controlling material, 0.25 percent Cu and 0.6 percent Ni and chemistry factor is 176 for Rev. 2 analysis.

Table V-1 (Cont'd)

RELATIVE RADIAL VARIATION OF DISPLACEMENT PER ATOM (DPA) AND FLUX (E > 1 MeV) ATTENUATION WITHIN RPV, AT LOCATION OF MAXIMUM INCIDENT FLUX

	Relative	Relative
Radius	Flux	DPA
<u>(cm)</u>	<u>Attenuation</u> *	<u>Attenuation</u>
$220.27^{(1)}$	1.00	1.00
220.64	0.977	0.983
221.66	0.885	0.915
222.99	0.756	0.820
224.31 ·	0.637	0.730
225.63	0.534	0.647
225.75 ^(a)	0.526	0.640
226.95	0.443	0.573
228.28	0.367	0.507
229.60	0.303	0.449
230.92	0.250	0.397
232.25	0.206	0.349
233.57	0.169	0.307
234.89	0.138	0.269
236.22	0.113	0.233
236.70 ^(b)	0.105	0.221
237.54	0.0912	0.201
238.86	0.0736	0.170
240.19	0.0584	0.141
241.51	0.0454	0.113
$242.17^{(2)}$	0.0422	0.106

NOTES: (1)

1) Base Metal Inner Radius

(2) Base Metal Outer Radius

(a) 1/4T Location

(b) 3/4T Location

*Flux at each position from transport calculations normalized to inner vessel wall (flux from transport calc./flux at inner vessel wall)

		Reg. Guide 1.99		
Material	Measured ^(a)	Rev. 2	Rev. 2 + Margin	
Plate B2002-2	80	73	121	
Weld	204	175	241	
HAZ	162	125 ^(b) 67 ^(b)	191 ^(b) 115 ^(b)	
Correlation Monitor	104	104 ^(c)	152	

COMPARISON OF MEASURED AND CALCULATED RT_{NDT} VALUES FOR INDIAN POINT-2 CAPSULE V MATERIALS

(a) 30 Ft-Lbs or 46 Ft-Lbs Value, as appropriate, see Figures IV-2, 3, 4, and 5; Table IV-9

(b) Based on Weld and Base Plate Calculations, respectively

.

(c) Based on averaged values from plate (B2002-2 and B2002-3) since chemical values not reported in WCAP 7323.

REACTOR VESSEL SURVEILLANCE CAPSULE REMOVAL SCHEDULE (21) INDIAN POINT UNIT NO. 2

<u>Capsu</u> <u>No.</u>	<u>le Ident.</u> <u>Code</u>	WOL <u>Material</u>	Removal Time	Equivalent Vessel Fluence
1	Т	Three Plates	1.08 EFPY ^(a)	3.4 EFPY at I.D.
2 '	Y	Weld & B2002-3	2.34 EFPY ^(b)	11 EFPY at I.D.
3	Z	Three Plates	5.17 EFPY ^(c)	29 EFPY at I.D.
4	v	Weld & B2002-2	8.6 EFPY ^(d)	8.92 EFPY at I.D.

(a) Removed after core cycle 1.

(b) Removed after core cycle 3.

(c) Removed after core cycle 5.

(d) Removed after core cycle 8.

Note:

Fifth capsule is scheduled for removal at the end of Cycle 16.

The remaining capsules within the reactor vessel are:

Code	WOL Material
S	Weld & B2002-1
U	Three Plates
W	Three Plates
x	Three Plates

COMPARISON OF END OF CYCLE 8 FLUENCE VALUES FROM TRANSPORT CALCULATIONS AND CAPSULE V DOSIMETRY ANALYSIS

Location	Transport Calculation (n/cm ²)	Dosimetry Results (n/cm ²)	C/E•
4 S. C.	5.19E18	5.30E18	0.98
40 S. C.	1.48E19	1.51E19	0.98
RPV O-T	4.35E18	4.45E18	0.98

COMPARISON OF PROJECTED FLUENCE RATES WITH TRANSPORT CALCULATIONS FOR CYCLE 9

Location	Transport Calculation (n/cm ² sec)	Dosimetry** Results (n/cm ² sec)	C/E*
4 S. C.	1.75E10	1.57E10	1.11
40 S. C.	3.77E10	3.42E10	1.10
RPV O-T	1.13E10	1.03E10	1.10

 \bullet C/E is calculated/experimental.

**Capsule V values used as the "projected" dosimetry results.

VI. HEATUP AND COOLDOWN LIMIT CURVES FOR NORMAL OPERATION OF INDIAN POINT UNIT NO. 2

Indian Point Unit No. 2 is a 3071.4 Mwt pressurized water reactor operated by Consolidated Edison Company. The unit has been provided with a reactor vessel material surveillance program as required by 10CFR50, Appendix H.

The fourth surveillance capsule (Capsule V) was removed during the 1987 refueling outage. This capsule was tested by Southwest Research Institute, the results being described in the earlier sections of this report. In summary, these results show a marked decrease in fluence as compared to three capsules (Capsules T, Y, and Z) and continue to indicate that the plate material will control the value of RT_{NDT} over the plant design lifetime.

The adjusted RT_{NDT} (Regulatory Guide 1.99, Rev. 2, May 1988) after 32 effective full power years (EFPY) of operation is predicted to be 240°F at the 1/4T and 194°F at the 3/4T vessel wall locations, as controlled by plate material. The Unit No. 2 heatup and cooldown limit curves for up to 32 EFPY of operation have been computed on the basis of the above values of adjusted RT_{NDT} using Code procedures (2) and the following pressure vessel constants:

Vessel Inner Radius, r _i	= 86.50 in.
Vessel Outer Radius, r _o	= 95.28 in.
Operating Pressure, P ₀	= 2235 psig
Initial Temperature, T _o	$= 70^{\circ} F$
Final Temperature, T _f	= 550°F
Effective Coolant Flow Rate, Q	= $136.3 \times 10^6 \text{ lb}_{\text{m}}/\text{hr}$
Effective Flow Area, A	= 26.719 ft^2
Effective Hydraulic Diameter, D	= 15.051 in.

Heatup curves were computed for heatup rates of 0°F, 20°F/hr, 40°F/hr, 60°F/hr, and 100°F/hr.

The Unit No. 2 heatup, cooldown, and leak test curves for up to 32 EFPY are given in Figures VI-1, VI-2, VI-3, VI-4, VI-5, and VI-6.



Figure VI-1. Indian Point Unit No. 2 reactor coolant heatup limitations applicable for periods up to 15 effective full power years (with criticality limit)



Figure VI-2. Indian Point Unit No. 2 reactor coolant heatup limitations applicable for periods up to 20 effective full power years (with criticality limit)



Figure VI-3. Indian Point Unit No. 2 reactor coolant heatup limitations applicable for periods up to 32 effective full power years (with criticality limit)



Figure VI-4. Indian Point Unit No. 2 reactor coolant cooldown limitations applicable for periods up to 15 effective full power years (with criticality limit)



Figure VI-5. Indian Point Unit No. 2 reactor coolant cooldown limitations applicable for periods up to 20 effective full power years (with criticality limit)



Figure VI-6. Indian Point Unit No. 2 reactor coolant cooldown limitations applicable for periods up to 32 effective full power years (with criticality limit)

VIL REFERENCES

- Title 10, Code of Federal Regulations, Part 50, "Licensing of Production and Utilization Facilities."
- 2. ASME Boiler and Pressure Vessel Code, Section III, "Nuclear Power Plant Components."
- ASTM E 208-81, "Standard Method for Conducting Drop-Weight Test to Determine Nil-Ductility Transition Temperature of Ferritic Steels," 1982 Annual Book of ASTM Standards.
- 4. Steele, L. E., and Serpan, C. Z., Jr., "Analysis of Reactor Vessel Radiation Effects Surveillance Programs," ASTM STP 481, December 1970.
- Steele, L. E., "Neutron Irradiation Embrittlement of Reactor Pressure Vessel Steels," International Atomic Energy Agency, Technical Reports Series No. 163, 1975.
- 6. ASME Boiler and Pressure Vessel Code, Section XI, "Rules for Inservice Inspection of Nuclear Power Plant Components," 1974 Edition.
- Randall, P. N., "NRC Perspective of Safety and Licensing Issues Regarding Reactor Vessel Steel Embrittlement - Criteria for Trend Curve Development," presented at the American Nuclear Society Annual Meeting, Detroit, Michigan, June 14, 1983.
- Office of Standards Development, U.S. Nuclear Regulatory Commission, Regulatory Guide
 1.99, Revision 2, May 1988.
- ASTM E 185-79, "Standard Recommended Practice for Surveillance Tests for Nuclear Reactor Vessels," 1981 Annual Book of ASTM Standards.

 "Indian Point Unit No. 2 Reactor Vessel Radiation Surveillance Program," WCAP-7323, May 1969.

- ASTM E 399-81, "Standard Method of Test for Plane-Strain Fracture Toughness of Metallic Materials," 1982 Annual Book of ASTM Standards.
- ASTM E 813-81, "Standard Test Method for J_{Ic}, a Measure of Fracture Toughness," 1982
 Annual Book of ASTM Standards.
- Norris, E. B., "Reactor Vessel Material Surveillance Program for Indian Point Unit No. 2; Analysis of Capsule Y," SwRI Report 02-5212, November 16, 1980.
- Norris, E. B., "Reactor Vessel Material Surveillance Program for Indian Point Unit No. 2; Analysis of Capsule T," Final Report 02-4531, June 30, 1977, and Supplement to Final Report 02-4531, December 1980.
- Norris, E. B., "Reactor Vessel Material Surveillance Program for Indian Point Unit No. 2; Analysis of Capsule Z," SwRI Report 06-7379, April 1984.
- Anderson, S. L., "Analysis of Neutron Flux Levels and Surveillance Capsule Lead Factors for the Indian Point Unit No. 2 Reactor Using a Low Leakage Core," July 1982.
- Anderson, S. L., "Plant Specific Fast Neutron Exposure Evaluation of the Indian Point Unit 2 Reactor Pressure Vessel and Surveillance Capsules Fuel Cycles 1 through 9," Westinghouse Electric Corp., Power Systems Division, July 1988.
- U.S. NRC Standard Review Plan, NUREG-0800, Section 5.3.2, Pressure-Temperature Limits, Revision 1, July 1981.

- 19. ASTM E 322, "Standard Method for Spectrochemical Analysis of Low Alloy Steels and Cast Irons Using an X-ray Fluorescence Spectrometer."
- 20. Letter dated March 29, 1978, from W. J. Cahill, Jr. (Consolidated Edison) to R. W. Reid (NRC), "Indian Point Unit No. 2 Reactor Vessel Material Surveillance Program."
- 21. Indian Point Unit No. 2 Technical Specifications.



Figure V-1. Predicted decrease in shelf energy as a function of copper content and fluence (Adapted from Regulatory Guide 1.99, Revision 2; Data from Table IV-9)

V-7

APPENDIX A

TENSILE TEST DATA RECORDS

Photograph of Specimens After Testing

Specimens: W-3 W-4 2-6 2-7



Southwest Research Institute

Department of Materials Sciences

TENSILE TEST DATA SHEET

Specimen No. <u>N3</u>	Project No. 17-2108
Test Temperature_ <u>RT</u>	Machine Ident. <u>4</u>
Strain Rate <u>005"/IN/MIN</u>	Date of Test_ <u>6/15/08</u>
Initial Diameter <u>247</u> Initial Area <u>04789</u> Initial Gage Length <u>1.0</u> Specimen Temperature: Top T.C. Middle T.C. <u>759</u> Bottom T.C. Witnued by Sum Q.A JLD	Final Diameter $$
U.T.S. = Maximum Load/Initial Area	=
0.2% Y.S. = 0.2% Offset Load/Initial Area	=92,712
Frature Stress = Fracture Load/Final Area	= / 88,248
% R.A. = 100 (Init. Area-Final Area)/Init.	Area = 61.62
% Total Elong. = 100 (Final G.LInit. G.L.)/Init. G.L. =
% Uniform Elong. = 100 (Eleng. to Max. Load	1)/Init. G.L. = <u>20.99</u>

Test Performed by: T.MASDEN R. ATIYE4 Calculations Performed by: <u>Im March</u>(Date) <u>6/17/85</u> Calculations Checked by: <u>David & Conver</u>(Date) <u>6/21/98</u>





.7 1323

Southwest Research Institute

Department of Materials Sciences

TENSILE TEST DATA SHEET

Specimen No	W4
Test Temperatu	re_ <u>550°F</u>
Strain Rate	.005 / FN / MIN

Project No. 17-2108 Machine Ident.<u>4</u> Date of Test 6/16/88

Initial Diameter	.246
Initial Area	.047505
Initial Gage Leng	gth
Specimen Tempera	ture:
Top T.C.	<u>553°F</u>
Middle T.C.	NA
Bottom T.C.	553°F

Final Diameter	.159
Final Area	019846
Final Gage Length	1,207
Maximum Load	4760
0.2% Offset Load	3920
Fracture Load	3460
Elong. to Max. Load	195546

U.T.S. = Maximum Load/Initial Area	=	100,200
0.2% Y.S. = 0.2% Offset Load/Initial Area		82,518
Frature Stress = Fracture Load/Final Area	-	174,342
% R.A. = 100 (Init. Area-Final Area)/Init. Area	=	58.22
<pre>% Total Elong. = 100 (Final G.LInit. G.L.)/Init. G.L.</pre>	2	20.70
" Uniform Elong. = 100 (Elong. to Max. Load)/Init. G.L.	2	19,55

Test Performed by: TMASDEN / R. ATIYEN Calculations Performed by: for March (Bate) 6/19/39 Calculations Checked by: During Qoura (Date) 6/21/33


4760-

SPEC # W4 G/16/58 LOAD/H.D. 550"F SEE 2.7 FOR CAL. glia brig 1411 10 1.1 9.49 Kin a contraction and second - 3160 . . . • ÷]. (2252) чij. Ī +11- 500 , 1500 (57

1323 47

Southwest Research Institute

Department of Materials Sciences

TENSILE TEST DATA SHEET

Specimen No. 2-6	Project No. 17-2108
Test Temperature \mathcal{RT}	Machine Ident. <u>4</u>
Strain Rate <u>.005 / EN/MIN</u>	Date of Test <u>6/15/88</u>
Initial Diameter	Final Diameter $.154$ Final Area $.0/862$ Final Gage Length 1.255 Maximum Load 4270 0.2% Offset Load $.3230$ Fracture Load $.2940$ Elong. to Max. Load $.24578$
U.T.S. = Maximum Load/Initial Area	=
C.2% Y.S. = O.2% Offset Load/Initial Area	= 65,305
Frature Stress = Fracture Load/Final Area	= 157,895
% R.A. = 100 (Init. Area-Final Area)/Init.	Area = <u>62.35-3</u>
% Total Elong. = 100 (Final G.LInit. G.L	.)/Init. G.L. = <u>25.5</u>
%_Uniform_Elong. = 100 (Elong. to Max. Load	d)/Init. G.L. = 24.578

Test Performed by: TMASDEN | RATIYEN Calculations Performed by: for Marking (Date) 6/19/88 Calculations Checked by: David Conna & (Date) 6/2



K+E (0 × 10 TO 3, INCH + 35 (19 NICHES

		SPEC	# 2-6	
		J2.7	1.00	
		554	#W3 For 2	CAL
			<i>µ1</i> , <i>v</i> ,	
			· · ·	
				· · ·
				1
33				1
.2 13:				
•				
È.	2			
1, 1	γ			;
100				
5				
12 NCH				:
•				:
2555 P				·
10 TX 10 TX		2991	· · · · · ·	
₩				
X			··· '	
				·· · . :
	11-51 1351 12	me Qt of the		
• •				
	·			6

.

Southwest Research Institute

Department of Materials Sciences

TENSILE TEST DATA SHEET

Specimen No. 2-7	Project No. <u>17-2103</u>
Test Temperature 550°F	Machine Ident. <u> </u>
Strain Rate	Date of Test <u>6/16/88</u>
Initial Diameter 249 Initial Area 04867 Initial Gage Length 1.2 Specimen Temperature: Top T.C. $551°F$ Middle T.C. NA Bottom T.C. $543°F$ W.Ammullo Aumi D.A. QAD	Final Diameter $./27$ Final Area $$
U.T.S. = Maximum Load/Initial Area	=
0.2% Y.S. = 0.2% Offset Load/Initial Area	= 66,365
Frature Stress = Fracture Load/Final Area	=250,395
% R.A. = 100 (Init. Area-Final Area)/Init.	Area = $73,98$
% Total Elong. = 100 (Final G.LInit. G.L	.)/Init. G.L. = <u>17,40</u>
% Uniform Elong. = 100 (Elong. to Max. Load	1)/Init. G.L. = <u>17,868</u>

Test Performed by: THASDEN RATIYEH Calculations Performed by: Jon Mand (Date) 6/19/33 vagoate)_ 6/21/88 Op Calculations Checked by: David 0_





÷.

01 MON 09:15 ID:NS&L

TEL NO:

#167 P02

ROM: CBI TECH SUCS BHAM TO:



FEB 2, 1990 3:02PM #730 P.02

Chicago Bridge & Iron

Yechnical Services Company

One Perimeter Fark South Suite 400-8 Birmingham, Alabama - 35243

> Phone 205 969 9200 FACE 205 969 9205

February 2, 1990

INRC

Consolidated Edison Company of New York Indian Point Unit 2 Nuclear Station Broadway and Bleakley Avenue Buchanan, NY 10511

Attention: Melisea Driscoll Reactor Engineer

REFERENCE: SPENT FUEL STORAGE PACKS INDIAN POINT UNIT 2 HOLTEC P.O. 61000-302 CBI CONTRACT 881161

SUBJECT: CONTRACT DRAWING REPRODUCTION

Dear Mellssa:

CBI Contract Drawings 14 and 16 may be reproduced for the purpose of review of Bosten amendment request.

Yours very truly,

Richard L. Bentley

Richard L. Bentley Engineering Supervisor

RLB/af

Enclosure

cc: Dr. Kris Singh, President Holtec International 139A Gaither Drive Mt. Laurel, NJ 08054

ATTACHMENT I

ADDITIONAL INFORMATION REGARDING STRUCTURAL SEISMIC ASPECTS OF INDIAN POINT INCREASE IN SPENT FUEL POOL STORAGE CAPACITY

CONSOLIDATED EDISON COMPANY OF NEW YORK, INC. INDIAN POINT UNIT NO. 2 DOCKET NO. 50-247 JANUARY, 1990

I. SPENT FUEL POOL ANALYSIS

1. Provide sketches and/or drawings of the pool showing elevations, basemat and pool wall thicknesses, water levels, and safety related components (such as piping in the pool, and their clearances from the racks.

RESPONSE

The following sketches and drawings are provided in response to the above request:

Sketches:

- 1 Spent Fuel Pool showing location of spent fuel pool cooling piping in pool.
- 2 Details of portion of spent fuel pool cooling piping in spent fuel pool with clearance to racks.

Drawings:

- 9321-F-2514 Fuel Storage Building General Arrangement Plans and Elevations.
- 9321-F-1196 Fuel Storage Building Concrete Details Sheet 1.
- 9321-F-1197 Fuel Storage Building Concrete Details Sheet 2.
- 9321-F-1198 Fuel Storage Building Concrete Details Sheet 3.
- 9321-F-1199 Fuel Storage Building Concrete Details Sheet 4.
- 9321-F-1200 Fuel Storage Building Concrete Details Sheet 5.
- 9321-F-1301 Fuel Storage Building Tank Liner Plates Sheet 1.
- 9321-F-1302 Fuel Storage Building Tank Liner Plates Sheet 2.

The drawings listed above show the pool elevations, basemat and pool wall thicknesses. Drawing 9321-F-2514 shows the pool water level in the section of the drawing labeled 'Elevation @ Section "A-A"'. The water level given is the normal water level, 93'8", and can vary during operation by ± 6 ". Sketch 1 provides an overview of the spent fuel pool indicating the location of the portion of the spent fuel pool cooling piping located in the pool. Sketch 2 provides the details of the clearance between this pipe and the rack below it. This section of pipe is the only safety-related equipment, except for the storage racks, in the spent fuel pool.



SKETCH 1

.



I. SPENT FUEL POOL ANALYSIS

2. Provide information on how the additional weight of high density racks (HDRs) and impacts on floor and walls under the postulated seismic events are incorporated in the design of the pool structure. Provide information related to pool structure seismic responses (including hydrodynamic loads) due to the proposed reracking, controlling load combinations and stresses at critical structural sections.

RESPONSE

The Spent Fuel Pool is designed as a Seismic Category I structure. This structure was reanalyzed, with the new racks assumed to be installed, to determine compliance with ACI-318(77), and SRP 3.8 of NUREG-0800. The details of the pool structure, applicable loadings, and summarized results are given in the following.

The IP-2 Spent Fuel Pool is a reinforced concrete structure built on a rock foundation. The pool slab is 45 feet by 42 feet in plan and three feet in thickness. Referring to Figure 1, the pool floor is at elevation 54'-7". The load bearing (external) walls are 48" thick for the bottom 16'-2" above pool slab, and increase to 75" thickness over a 2'-5" height. the The thickness of the walls remains uniform (6'-3") for the remainder of the 20' of the top portion of the pool. The bottom 24'-5" (up to elevation 79'-0") of the pool walls and slab are below grade. Thus, from a structural standpoint, the pool slab and bottom 24'-5" of the pool walls are supported by a semi-infinite elastic continuum. The pool is filled with borated water up to the height of 39'-1". The size and location of reinforcement bars parallel to the plane of section are shown in Figure 2 for Section A-A and Figure 4 for Section B-B. It is noted that the top of the racks (which extend for approximately 178" from the pool liner) is well below the grade level.

The pool liner is 1/4" thick and is made from SA240-304 austenitic stainless material.

The foundation bedrock consists of hard limestone capable of supporting loads up to 50 tons per square foot. The foundation boring logs indicate limestone with unconfined compressive strength of 7810 psi in the vicinity of the spent fuel pool.

The structural analysis is carried out using a finite element model of representative sections of the pool. The floor and walls are modeled using shell elements, and the foundation modeled using 3-D brick elements. Two sections were analyzed, denoted as Section A-A and Section B-B, respectively, in Figure 1. Figure 3 shows a 2-D slice of the fuel pit for Section A-A and the surrounding rock foundation. Section A-A is a sectional view parallel to the widest and weakest section. This section is assumed fully populated with the heaviest racks for structural analysis purposes.

The effective depth of rock substructure is assumed as 10 feet and the centerline of the opposite walls (N/S) is assumed to be a 40' span (greater than the actual inside span of the pool at the location). The weight of concrete plus reinforcement is assumed to be such that the combined weight density is 180 lb./cu.ft. The following properties are used in the analysis:

Reinforcement strength	f. = 60000 psi
Concrete strength	$f_{2}^{y} = 3000 \text{ psi}$
Young's Modulus of Rock	E ^C = 8400000 psi

Section B-B is chosen for analysis because it contains an internal pool wall (left wall in Figure 1) which does not have the lateral foundation support. Figure 4 shows the 2-D cut away section.

In addition to the mechanical loadings, the pool structure was also subjected to the temperature induced loadings. For this purpose, the thermal boundary conditions were conservatively specified as 180°F pool water temperature and 0°F outside ambient. The thermal moments computed by the finite element analyses were combined with those due to mechanical loads as described below.

Structural Loadings on the Pool Slab and Walls

The following loadings are considered:

- (i) Dead weight of slab and walls (D1)
- Dead weight of rack modules (D_2) (ii)
- (iii) Dead weight of stored fuel assémblies (D₃)
- Dead weight of 39'-1" water in the pool (D_4) (iv)
- Hydrostatic pressure on pool walls (D_5) (v)
- Hydrodynamic pressure on the (vi) pool walls during seismic event (D₆) Tmpact loads due
- (vii) to response of racks during seismic event (D₇)
- (viii) Thermal Moment (temperature gradient loading) (D_{g})

Table 1 gives information concerning these loads.

As noted previously, in order to obtain a conservative assessment of the stresses in the pool structure, the most controlling sections in the pool were analyzed using a Finite Element Model. The Finite Element Model consists of 270 elements and 544 nodes. Figure 4 shows the concrete sections modeled by shell elements. The contribution of the surrounding rack continuum is modeled using three dimensional solid elements. The following load combinations are per SRP 3.8.4.

Consider:

1.4D + 1.9ED + E' $0.75 [1.4D + 1.9E + 1.7T_{0}]$ where, referring to Table 1,

 $\begin{array}{l} D = D_1 + D_2 + D_3 + D_4 \ (on \ pool \ slab) \\ E' = D_6 \ on \ pool \ walls \ + D_7 \ on \ slab \end{array}$

For added conservatism, we combine the two governing loading combinations into a "bounding loading condition" as

 $1.4D + 1.9E' + 1.275T_{o}$

The section moments and shears at critical locations are provided in Table 2 and 3 for Section A-A and B-B, respectively, and compared to their respective Design Strengths.

In addition to the conservative load combination, several other assumptions in the pool structural analysis produce inherent margins of safety in the computed values. The key assumptions are synopsized below:

- a) A lowered bound value of foundation modulus of the equivalent elastic foundation representing the subgrade surrounding the outside pool walls is utilized in the analysis.
- b) The lateral support provided by the "plate" effect of the wall is incorporated in the 2-D model in a conservative manner.
- c) In the temperature profile analysis of the pool walls, and the elastic continuum surrounding it, a lower bound value of the thermal conductivity is used so as to produce a most adverse temperature gradient.

It is noted from the results presented in Tables 2 and 3 that despite these conservative assumptions, there are large margins between the factored loads and corresponding design strengths.

Table 1

GROSS LOADINGS

Value in KIPS unless otherwise stated (i) Reinforced concrete and water dead weight $(D_1 + D_4)$ 5.39 KSF (ii) Dead weight of rack modules (empty) (D₂) (per Table 2.2 of Licensing 217.1 Report) (iii) Dead weight of 137 stored spent fuel assemblies (1453 lb. each rounded off 2061. to 1500 lbs) (D₃) Maximum hydrostatic pressure of water (iv) (triangular profile from top to bottom) 16.94. psi (v) Hydrodynamic pressure on walls due to 7.8 psi (on Section A-A) 5.63 psi (on Section B-B) seismic motion of water in pool (D_6) (vi) Maximum hydrodynamic+ pressure on 2 psi pool walls (constant for the bottom 178" height of the walls) due to gaps between rack and wall (D_6) (vii) Pool slab impact loading due to SSE .52 x dead load per (per spindle) (D₇) spindle (viii) Thermal gradient loading, D_g defined As in the preceding test

+ Obtained from DYNARACK simulations, assuming 1% damping for the SSE condition.

Table 2

٠

CRITICAL REGIONS OF SECTION A-A (Results given in absolute value)

Location	Calculated Factored Moment (KIP in./in.)	Limit Factored Moment (KIP in./in.)
Pool Wall (6'-3" section)	164.9	255.8
Pool Wall transition section	41.0	207.8
Pool Wall (4' section)	24.8	159.8
Pool Slab (center section) 1.9	117.1
Pool Slab (outer section)	3.8	285.1
Foundation pressure under	slab 308.9 psi	694. psi
Foundation pressure on North Wall	72.2 psi	694. psi

Table 3

.

•

CRITICAL REGIONS OF SECTION B-B (Results given in absolute value)

Location	Calculated Factored Moment (KIP in./in.) or Pressure (psi)	Limit Factored Moment (KIP in./in.) or Pressure (psi)		
Pool Wall Top Section	92.0	316.9		
Pool Wall Bottom Section	119.5	386.1		
Pool Slab Center Section	1.9	117.1		
Pool Slab Adjacent to Peo	destals 6.4	117.1		
Foundation Pressure Under	r Slab 302.2 psi	694		

36'-0"

В

N



FIGURE 1 PLAN VIEW OF IP-2 POOL



and the second second

····

FIGURE 2 HALF SECTION (VIEW A-A ON FIGURE 1) SHOWING REINFORCEMENT

T. Sur





.





•











FIGURE 5

2D FINITE ELEMENT MODEL FOR IP-2 SLAB (SECTION B-B) · .

I. SPENT FUEL POOL ANALYSIS

3. Provide information on the locations of the rack pedestals with respect to the leak-chases and other embedments.

RESPONSE

In order to provide a complete description of the rack pedestals with respect to embedments in the spent fuel pool, Drawing 531 entitled "Support ID & Bearing Pads" is being provided. This drawing shows the support pads that the rack pedestals will be placed on. The various embedments in the pool floor are shown as well as the pool liner weld seams (dashed lines running N-S and E-W). It should be noted that the Indian Point 2 spent fuel pool was built and licensed without a leak chase, since the pool structure rests on bedrock.

II. SEISMIC INPUT MOTION

1. The plant FSAR (Table 1.11-1) requires that 1% damping be used for steel welded structures such as the rack. Provide justification for using 2% (LAR Section 6.2.4) damping for the rack analyses.

RESPONSE

All governing loading cases reported in Section 6 of the Licensing Report have been re-run with 1% structural damping. The responses, as expected, have increased slightly. The results are presented in Tables II.1 and II.2. There is no effect on the rack structural integrity conclusions presented in the licensing submittal.

Table II.1

STRESS FACTORS AND RACK TO FUEL IMPACT LOAD (1% DAMPING)

Run		Rack/Fuel Impact Load (lb.)		STRESS FACTORS		
I.D.	Remarks	(Per Ce	í1) 	R ₁	R ₂	R ₃
DOb	Rack D	252.9	*	.013	.014	.152
	Cof = .8, SSE Filled with Regular Fuel		**	.183	.031	.122
DOd	Rack D Cof - 2 SSF	252.7		.013	.014	.152
	Full load Regular Fuel			.182	.030	.124
G2a	Rack G2 (11x12)	330.8		.013	.014	.097
	Full load Regular Fuel			.147	.015	.042
B02	Rack B (9x12) Cof - 8 SSE	328.0	*	.008	.010	.069
	Full load Regular Fuel			.167	.034	.097
в03	Rack B	328.0		.008	.010	.068
	Full load Regular Fuel			.166	.032	.106

* Upper values are for rack cell just above baseplate.

** Lower values are for support foot cross section (upper part). See last page of this table for stress factors R_4-R_7 .

Table II.1 (continued)

Run	Stress Factors				
I.D.	R ₄	R ₅	R ₆	R ₇	
DOb	.095	.181	.212	.024	
	.070	.292	.312	.051	
DOd	.095	.180	.210	.023	
	.070	.290	.309	.050	
G2a	.083	.139	.162	.016	
	.034	.183	.190	.018	
B02	.073	.097	.114	.013	
	.058	.246	.259	.040	
B03	.074	.095	.111	.012	
	.066	.247	.263	.040	

•

.

Table II.2

Run I.D.	Floor Load (sum of all support feet)	Ma: Suj Lo:	ximum pport ad	Vertical Load*	Shear Load**	DX*** (in.)	DY (in.)
DOP	2.465x10 ⁵	1 2 3 4	115000. 105900. 100700. 113900.	114960. 112052.	13973. 23368.	.1801 .0007	.1854 .0009
DOd	2.465x10 ⁵	1 2 3 4	114400. 105900. 100200. 113400.	114398. 113165.	17408. 22633.	.1803 .0011	.1853 .0038
G2a	2.292x10 ⁵	1 2 3 4	87790. 91740. 90720. 92410.	92343. 42684.	7890. 8241.	.1330 .0006	.1285 .0006
B02	1.953x10 ⁵	1 2 3 4	105000. 96960. 81130. 98520.	104955. 49529.	16371. 17541.	.1767 .0013	.0884 .0009
B03	1.953x10 ⁵	1 2 3 4	104700. 93860. 80660. 98130.	104667. 104667.	20935. 20935.	.1761 .0016	.0884 .0026

RACK DISPLACEMENTS AND SUPPORT LOADS (1% DAMPING) (all loads are in lbs.)

* The first line in any set of data is near the maximum vertical load and the second line reported is the vertical load when the net horizontal shear at the liner is maximum.

** The first line is the net horizontal liner shear when the vertical load is near the maximum; the second line is the maximum value of the net horizontal shear on any single support foot.

*** The first line reports results at the top of the rack; the second line reports results at the baseplate. The times at which these maximums occur may be different.

II. SEISMIC INPUT MOTION

 Provide information on how the statistical independence (LAR Section 6.1) of the three components of earthquake was established.

RESPONSE

The statistical independence of the three components of synthetic time histories was established by computing the normalized cross covariance of each pair of time histories (a total of three pairs). An effective technique to obtain the desired level of non-correlation between the time histories involves changing the random seed number, and the enveloping function for the time history profile. The time history generation techniques permit the use of different envelope functions. Trapezoidal, exponential decay, and sinusoidal envelopes are some of the commonly used bounding functions. It is found that using a different genre bounding function for two time histories results in a lower level of covariance between them. This statistical correlation function was found to be less than 0.1 in all the cases.

The synthetic time histories in the N-S, E-W and vertical directions may be labeled as a; (γ) ; i = 1,2,3 respectively (γ is time coordinate). If γ ij represents the normalized statistical correlation function between a and a, then the computed values of γ_{ij} are as follows:

 $\gamma_{12} = .02933$ $\gamma_{13} = .02155$ $\gamma_{23} = .01550$

III. ANALYSIS AND DESIGN OF HDRs

- A. RACK ANALYSIS
- 1. Provide justification for the use of five rattling masses (to represent fuel assemblies) instead of rattling masses at every grid locations. How is the impact on fuel grid computed? (LAR Section 6.2.1a)

RESPONSE

The grid straps are only on the order of a few mils thick, and therefore cannot be postulated as definitively designated impact locations. The low flexural stiffness of the fuel assembly and fluid force contribution of water further ensure that the assembly will undergo various curved contours, and the rattling impacts will occur at non-grid strap locations. Our model, therefore, discretizes the assembly into five discrete masses, which are equispaced along the assembly length. This is in contrast to seven grid strap locations. Therefore, the number of lumped masses used in our analysis is less than the number of grid strap locations. Consequently. each lumped mass in our model is bigger than the discretized mass if the lumped masses were provided at each grid strap locations. A larger lumped mass implies a greater impact load due to rattling of the mass in the storage cell. Consequently, the impact force at each of the five mass locations in our model bounds the value that one would obtain from the model employing a lumped mass at each grid strap location. However, to be conservative, the maximum impact load obtained from the dynamic analysis is assumed to be applicable to the grid strap, as well. In summary, the impact force computed at a mass node point in our analysis would exceed that calculated for each grid strap location. Therefore, our analysis is conservative. The maximum values of the fuel assembly-to-cell wall impact load are given in Table II.1 (see response to Question II.1), and impact capacities of the fuel assembly are provided in the response to Question III.A.2.

III. ANALYSIS AND DESIGN OF HDRs

- A. RACK ANALYSIS
- 2. Provide calculations showing how the impact capacity (LAR Section 6.9.1) of cell-walls are estimated. Are the concurrent longitudinal stresses considered in combination with the stresses due to impact? What is the impact capacity of fuel assemblies?

RESPONSE

The maximum fuel assembly-cell wall impact loads are calculated by DYNARACK and compared with the limit capacity of the section. Since these impact loads are localized, the only criteria is that collapse of the section does not occur. A beam section having length equal to the unsupported cell width and subject to two concentrated loads applied where the corners of the assembly would impact is analyzed for the limit state. The thickness of the beam section is .075". The actual impact load is compared to the limit load (with a safety factor of 2 built into the limit calculation). Figure 6 shows the configuration used for the impact load calculation.

The worst impact load on a cell is obtained from the DYNARACK computer code simulations as 424 lbs. Limit analysis applied to the configuration of Figure 6 yields

$$Q_{L} = \sigma_{y} \frac{L}{C} t^{2} \times \frac{1}{SF}$$
(1)

where σ_{y} = 25000 psi, L = 21.125" (1/8 of rack height)

t = .075" (cell wall thickness)

If we know the inside cell dimension (8.75") and the outside dimension of the impacting assembly (taken as 8.3"), then for calculation purposes

$$c = \frac{8.75 - 8.3}{2} = .225"$$

Assuming a factor of safety SF = 2 on the bending limit load yields

 $Q_{I} = 6602$ lbs. per cell

Assuming a failure in shear of the cell wall over a length L, and a yield stress in shear equal to $\sigma/2$, the corresponding limit load for pure shear failure of the cell wall (with a safety factor of 2.0) is

$$Q_s = \sigma_y^{-1} (a + L) = 2.759 \times 10^4 \text{ lbs.} (a = 8.3")$$

L = 21.125")

It is noted that the actual maximum impact load is a small fraction of the cell capacity.

Concurrent longitudinal stresses are not considered in combination with impact load since these longitudinal primary stresses decrease with distance above the baseplate and are small in the region where maximum impacts occur.

The impact capacity of the fuel assemblies is approximately 5000 lbs. at each grid location, and an order of magnitude greater at other locations.



FIGURE 6 CELL-WALL IMPACT CAPACITY (UNIT DEPTH)

III. ANALYSIS AND DESIGN OF HDRs

- A. RACK ANALYSIS
 - 3. It is not clear (LAR Section 6.2.1b) whether the entire fuel mass is modeled to vibrate in phase under the seismic event or a portion of it. If it is the later, provide justification for such assumption.

RESPONSE

The entire fuel mass is assumed to vibrate in phase under the seismic event.

III. ANALYSIS AND DESIGN OF HDRs

- A. RACK ANALYSIS
- 4. With respect to the cross-coupling effects (LAR Section 6.2.1m), provide the following information:
 - (a) What is the nominal gap-multiplier for IP-2?
 - (b) How much is the cross-coupling consideration contributed to the resistance to the rack movement under the SSE?

RESPONSE

- (a) Nominal gaps of 50% of water-rack spacing and 100% of rack-wall spacing are used. Each rack is assumed to move out of phase with any adjacent rack so as to maximize impact potential. Hydrodynamic flow around each rack is assumed to occur from the alternate squeezing and opening of channels transverse to local seismic wall motion which forces the fluid along the sides of the rack to the opposing channel. There is no "nominal gap multiplier" in single rack 3-D analysis. This term is meaningful only in the context of a 2-D multi-rack analysis. Paragraph 6.2.1 (m) of our licensing report is intended to explain how the physical effect of fluid coupling is mathematically simulated in the context of fuel rack movements.
- (b) The DYNARACK output does not permit separation of the effects of different components of the hydrodynamic effect. Therefore, we cannot quantify the "cross coupling component".
III. B. RACK DESIGN

1. Provide rack drawings (or sketches) showing the details of inter-box welding and separation elements for Region I and Region II racks.

RESPONSE

The following drawings and information are provided in response to the above request:

Drawings

14	Region 1 Typical Elevation Spent Fuel Storage Racks
15	Region 2 Typical Elevation Spent Fuel Storage Racks
1-A 1-C 1-D	Region 1 Rack A Spread Sheet Detailing QA Check List Requirements
1-A 1-D	Region 2 Rack D Spread Sheet Detailing QA Check List Requirements

Information

Region	1	Shop	Check	Lists		
Region	2	Shop	Check	Lists		
Use of	tł	ne Sho	op Che	ck List	System	Procedure









پ۲۰

Region 1

Shop Check Lists



SPECIAL CHECK LIST - SPENT FUEL RACK

		QA INSF	ECTOR
. *		The listed of Exams & che Performed)PERATIONS ECKS WERE
NO.	OPERATIONS, INSPECTIONS & CHECKS TO BE PERFORMED	INITIALS	DATE
1	INSPECT BASEPLATE SIZE & STENCILING AT CM 150		
2	INSPECT BASEPLATE HOLE SIZE , HOLE SPACING & GRID LAYOUT AT HBM		
3	INSPECT BASEPLATE ALIGNMENT ON FIXTURE		
4	INSPECT BASEPLATE FLATNESS ON FIXTURE		
5	SURVEILLANCE OF CELL PLACEMENT ON BASEPLATE TO TEMPLATE BEAM		
6	SCRIBE BENCH MARKS AT FOUR CORNERS OF RACK		
7	INSPECT LOCATION OF SUPPORT FEET & I.D.'S		
8	RANDOM INSPECT LEAD IN ANGLE AT TOP OF CELLS (REGION 1 RACKS ONLY)		
9	RE-LEVEL RACK IN GAGING STATION		
10	GAGE RACK PER IGT1N - RECORD RESULTS ON IGTR		
11	RECORD OVERALL DIMENSIONS OF BOUNDARY CELLS ON RACK/ PRISMATIC ENVELOPE OF RACK		
12	PERFORM CHECK OF TRAVEL RANGE ON SUPPORT FEET		
13	INSPECT RACK STENCILS (POST ASSEMBLY)		
14	INSPECT RACK CLEANLINESS		
15	ALL REQUIRED RECORDS RELATED TO THIS FUEL RACK ARE COMPLETE AND ARE ON FILE		······
16			<u> </u>
17			
18			
Pack	K MADE BY APP'D BY Y MADE CONTRACT	vo.	
A	DATE DATE SHI'D BBIIG	/ SHEET	

CCM #14



CCM GE 516 REV Jun 87

	T	hese examina	tions & oper	ations were p	erformed, res	ults evaluate	ed and accept	ed to applica	ble procedure		<u>.</u>		<u>-</u> ,	· · ·	1
REF. MARK	VI4X FIT UP CHECKED	<u>2</u> MATERIAL ID RECORDED	3 Weld Proced. AND Repair	4 RECORD WELDERS ID ON SPREAT	5 VI4X WELDING	6 VT5X	7	8	9	10	11	Witness Hold ANI		COL NO.	See Nor conforn ance Control
	REV.1	(TUBE)	PROCED.	SHEET	REV.1		<u>.</u>								List No.
A			A 2 53	N SHEET		X						N/A			
B	X		X 0 50	RECORD ON SHEET		×					<u> </u>	N/A N/A		· · ·	
С	× –		X Q	1D RECORD	8	8						N/A			
<u> </u>	× –		53 X 2	1C FECORD		x	 	<u> </u>	<u> </u>	 		N/A			
U			63	ON SHEET									┼╌┼		
]											N/A		<u> </u>	
												N/A N/A	┼─┼		
ACK												N/A N/A			
<u> </u>	· · · · · · · · · · · · · · · · · · ·					· · · ·			 			N/A			
												N/A N/A	┨╌┨		•
					┉┛╴╷┟]						N/A			
		·										N/A N/A			
												N/A			
lade By	Chkd By	By										N/A	, , , , , , , , , , , , , , , , , , ,		
			\succ	\geq	\rightarrow	1 A		VONELI	CONTRA	CT NO.	NO. RAC	<u>ж -А</u>		4 17 1	
	Date	Date	ł			•			881	161	SHT 2	of 3			

- 1972 - 1	. 97	•			;		~		·						
ing si ∎	(* *	•		·	C	EL S	HOP C	CHECK	LIST						
	SUF BAS	SEAM E PORT TO	E1.	27-1									Œ	<u>-</u> - 2	27-1
	F		·	•	$ \Theta $	$\bigcirc ($	$) \bigcirc ($		\mathbb{O})(-)
	N	ORTH			Q	ŎČ	\dot{O}	ŽŎ	Q	\mathcal{T}	$\langle \zeta \rangle$	$\sum_{i=1}^{n}$			
-		-		ал — . А	K	SC	$) \bigcirc ($	38					,	•	
					$ \Theta $	\bigcirc	$) \bigcirc ($	20		$\left\{ \right\} \in$	$) \subset$		6	- 27	1
			E2- 27-		Ŏ	<u>Č</u> Č	\overline{OO}	20	30	50			(-		
	1 3 19 N	SEC	CTIO	NA-	• A		•	RAC	K - ,	A					
	SEQ.	0	PERATIC	N.	SE	20	OPE	RATION		SEQ		0	PERA		1
•		REVIEW	CHECKL	ST	2	D INSPE	CT FINAL	SEAM		_					
	1B FO	REMAN F	REVIEW CI	HECKLIST	2	E VISUA	LEXAMS	SEAM			-				
		ECK FIT	UP SEAN	1 <u>E</u>	2	FPTEX	AM SEA	M		_					
			DPHOCEL	JURE											
	ZU RE		ELDER I.D.	tions & on								,		·	· · · ·
		1			4		6	7	and accep	19	pplicab	le proce	dures.	\sim	See Non-
	REF.	Fit	Mati	Weld	Becord	VI4X	VT5X	DTEV				Hold	H	NO	conform-
	MARK	Up	ID	Spec.and	Welder	' Welding	REV.1					ANI	CUS	TOM.	Control
		Checked	Record	Repair Proced.	ID	REV. 1		REV.I		1		·			List No.
	E 1		X	DIX					\vdash	F		/ A			
		ly			V 1				ļ		<u> </u>	/ A			
	E2				لم			لم			N				• •
	E 3		X	XIQ	X	X	XI			\mathbb{P}	N	A			
					XI	- <u> x</u>	XI		<u> </u>	<u> -</u>		/ A			
	E4								 		N	γ Α / Δ			
	CB	I	I				1	Review	red with A	NI befo	re use:	1			
	ASSEM			ACCEDT				l r			N	I / A		5 -1	+ C +
	ACCEM		CUIED&	AUGEPI	יז מ ט:	•		ļ	ANI			Date	100	<u> </u>	101
	MODEO	TOP						Review	ved by QA	Mana	ger		NO.	RACI	<u><- A</u>
	INSPEC	IUH			DA	1E		·	Jamo			Data	SHT	. 3	OF <u>3</u>
	Made E	y Chkd	By	Ву			$\overline{\}$	Review	ed By:	FORE	MAN	Uale			
	Date	Date		PP'D] ·	•				1		
	5415	Jaie		Date	ľ	ř		1				• •			
3. j.			L			<u> </u>									

Region 2 Shop Check Lists

,



SPECIAL CHECK LIST - SPENT FUEL RACK

		QA INSPE	CTOR
		THE LISTED OPI EXAMS & CHECI PERFORMED	ERATIONS, KS WERE
NO.	OPERATIONS, INSPECTIONS & CHECKS TO BE PERFORMED	INITIALS	DATE
1	INSPECT BASEPLATE SIZE & STENCILING AT CM 150		
2 .	INSPECT BASEPLATE HOLE SIZE , HOLE SPACING & GRID LAYOUT AT HBM		
3	INSPECT BASEPLATE ALIGNMENT ON FIXTURE		
4	INSPECT BASEPLATE FLATNESS ON FIXTURE	······································	
5	SURVEILLANCE OF CELL PLACEMENT ON BASEPLATE TO TEMPLATE BEAM	·····	
6	SCRIBE BENCH MARKS AT FOUR CORNERS OF RACK		
7	INSPECT LOCATION OF SUPPORT FEET & I.D.'S		
× 8	RANDOM INSPECT LEAD IN ANGLE AT TOP OF CELLS (REGION 1 RACKS ONLY)		
9	RE-LEVEL RACK IN GAGING STATION		
10	GAGE RACK PER IGT1N - RECORD RESULTS ON IGTR		
11	RECORD OVERALL DIMENSIONS OF BOUNDARY CELLS ON RACK/ PRISMATIC ENVELOPE OF RACK		
12	PERFORM CHECK OF TRAVEL RANGE ON SUPPORT FEET		
13	INSPECT RACK STENCILS (POST ASSEMBLY)		
14	INSPECT RACK CLEANLINESS		
15	ALL REQUIRED RECORDS RELATED TO THIS FUEL RACK ARE COMPLETE AND ARE ON FILE		
16			
17			
18		ļ	
RACK	MADE BY APP'D BY 20 MADE CONTRACT APP'D BY 20 APP'D CONTRACT APP'D BY 20 APP'D CONTRACT APP'D CO	ю.	
<i>D</i>	DATE DATE DATE B81/6		



CCM GE 516 REV Jun 87

	۰.				CB	SHO	P CHEC	к						
	T1	iese examinat	ions & opera	ations were p	erformed, res	ults evaluate	d and accepte	ed to applicat	ole procedures	3.				1
REF. ARK	1 VI4X FIT UP CHECKED	2 MATERIAL ID RECORDED	3 Weld Proced. AND BEPAIR	4 RECORD WELDERS ID ON SPREAT	5 VI4X WELDING CHECKED	6 VT5X BEV 1	7	8	9	10		Witness Hold ANI	W COL. H NO.	See Non- conform- ance Control
	REV.1	(TUBE)	PROCED.	SHEET	REV.1								<u> </u>	List No.
4		×I*	⊠ 2 5 3	RECORD ON SHEET	X	\bowtie						N/A N/A		
3	X		⊠ 2 53	RECORD ON SHEET	X	×						Ν/Α		
			60	RECORD ON SHEET										
D	×		X 2 63	FECORD CN SHEET	X	X I								
]										N/A N/A		
						 ·						N/A N/A		
CK									· · ·					
· .		·				_						N/A		
in	`											N/A N/A		
·]											N/A N/A		
		·]					·]		N/A N/A		
de By	Chkd By	Ву				* RECORD) ON SPREA	AD SHEET	CONTRA	CT NO.	NO. RAC	N/ A		
te	Date	APP'D							881	161	SHT. 2	OF <u>3</u>		

CCM GO 1258 REV JUN 87



Se

CCM GE 515 REV JUN 89

. . .

a the second		· .					
		•				DOC. ID REV. NO. CONTRACT	AP 7-2 2
	USE OF	THE	SHOP	CHECK	LIST SYSTEM	PAGE NO. 1	OF 14

		Corp	Corp				 	BY	DATE
	Engr	Weld	QA	Const	Mfg	•,	 PREPARED	PTC	7-7-87
PPROVI		LRS	REK		RRW		REVISED AUTHORIZED	RGL	7-11-89 8-7-8 4
×	· · · · ·	· .				1	STANDARD	REV	NO.

1.0 <u>SCOPE</u>

This procedure describes the check list system in a shop for process control. When using the Shop Check List System, control per this procedure is mandatory for Type A material and welds thereto (including repairs) on all classes of work and for the following additional areas on specific classes:

Class 1 - repairs to Type B and C material.

Class MC - welds of Type B material together (including repair of such welds) within 16t of Type A material.

Class 2 & 3 Tanks - welds of bottom plates together and nozzle-to-bottom plates. For roofs made from Type B material - welds of roof plates together and nozzle to roof plates. Includes repairs of these welds.

2.0 <u>REFERENCES</u>

2.1

AP 2-8, Classification of Materials

- AP 9-15, Welder I.D. Requirements
- AP 11-1, Handling of Nonconformances
- AP 14-1, General Procedure for Quality Assurance Records
- 2.2 Reference to the above procedures includes equivalent FAP's, AP Addenda or contract procedures.

3.0 <u>RESPONSIBILITIES</u>

3.1 The Production Superintendent shall prepare the Shop Check Lists and distribute them to the Production Foremen.

C								•	• •	DOC. REV.	ID NO.			AP 2	7-2	·
 TITLE	2	USE	OF	THE	SHOP	CHECK	LIST	SYSTEM	·.	PAGE	NO.	2	OF	14		-

3.2 The QA Coordinator, who reports to the QA Manager, shall review the Shop Check Lists before use, assign QA witness and/or hold points, present the Shop Check Lists to the ANI, and review and file completed process control documents.

3.3 The Production Foreman, who reports to the Production Superintendent, shall review the Shop Check Lists prior to performing any operations and obtain the required signoffs on the Shop Check Lists.

4.0 <u>DEFINITIONS</u>

None

- 5.0 <u>SHOP CHECK LIST SYSTEM</u>
- 5.1 This system is designed for use on items for which sequencing of operations is not important.
- 5.2 This system includes the following:
- 5.2.1 Check List (Attachments 1, 2 and 3)
- 5.2.2 Control List (Attachment 4)
- 5.2.3 Repair Check List (Attachment 5)
 - 6.0 <u>CHECK LISTS</u>

6.1

6.2

Process control for welding, heat treating, NDE and forming operations requiring procedures shall be outlined on the check lists. Contract drawings and the Contract QA Handbook are used for information. The Production Superintendent is responsible for preparation of the check lists. (See paragraph 6.6 for contents of check lists.)

Prior to use, the check lists shall be reviewed by the QA Coordinator for inclusion of QA requirements, using the contract drawings and Contract QA Handbook. QA hold points shall be indicated on the check lists by the QA Coordinator. His approval of the check lists shall be documented by signoff on the check lists.



	CE	E							DOC. REV. CONTI	ID NO. RACT			AP 2	7-2
مرومانوم ار ا ^{ر مرد}	TITLE	USE	OF	THE	SHOP	CHECK	LIST	SYSTEM	PAGE	NO.	3	OF	14	

6.3

6.4

The QA Coordinator shall present the check lists and associated contract drawings to the ANI for his review. The ANI may place witness and/or hold points on the check lists for the listed operations. The ANI's review shall be documented by the ANI's initials and date on the check lists.

After review by the ANI, the check lists are returned to the Production Superintendent for use. Working copies of the check lists may be used to control operations. When working copies are used, the Production Superintendent shall complete the official check lists (check lists containing the original ANI and QA approval) from the working copies.

6.5 Following distribution by the Production Superintendent, the Production Foreman shall initial and date the check lists before starting any operations, signifying that he has reviewed and understands the listed requirements.

6.6 Entries on the check lists shall include:

6.6.1 Identification with a contract number and check list number.

6.6.2 A listing of required operations. The "Seq. Operation", "Weld Procedure Spec and Repair Procedure", and "Proc & Rev." columns shall be used for this purpose. Sequence numbers need not be assigned provided that witness and/or hold points are not bypassed. An "X" shall be placed in the small box within the signoff square to indicate each required operation. For temporary attachments and plate cleanup, documentation may be by groups and columns for "Fit Up Checked" and "Material ID Recorded" are not applicable.

6.6.2.1 Per AP 9-15, specify the requirements for and provide a place to record welder I.D.

6.6.2.2 When required in AP 2-8 for Type A material, provide a place for the Production Superintendent to record item location by identification information (piece mark, or piece mark and heat serial code, or piece mark and serial number) from the item.

	CBD		DOC. ID REV. NO. CONTRACT		AP 7-2 2
Carlo The Area	TITLE	OF THE SHOP CHECK LIST SYSTEM	PAGE NO.	⁴ OF	14
en e			· · · · · · · · · · · · · · · · · · ·		
	6.6.3	A sketch, when needed for clarit entered in the "Ref. Mark" colum items such as weld seams or piece	y. Sketc n to iden surfaces.	h ID s tify s	hall be pecific
	6.6.4	"Hold" and "Witness" points, w customer's inspector, ANI, or QA required, the customer inspect completed form. "Hold" and "Wit controlled in accordance with para	here requ Manager. or's sig ness" poi agraph 10.	Also Also noff ints sh 0.	by the b, when on the hall be
	6.6.5	Signoffs by QA Inspectors under "F: ing that fit-up was checked prior	it-Up Chec to weldin	ked" co g.	ertify-
	6.6.6	For Type A material, when required signoffs by QA Inspectors under certifying that material identific	by AP 2-8 "Material ation was	, prov: ID Rec record	ide for corded" led.
	6.6.7	Signoffs by QA Inspectors und certifying that requirements of the met, welders were qualified and, attachments, surface and configura weld meet applicable requirements.	er "Weld he referen except f ation of	ing Ch oced WP for ten the com	necked" 'S were nporary pleted
	6.6.8	Signoffs under "Proc & Rev" by ND) that:	g personne	el cert	ifying
		 A. Examinations were completed B. Reports were made and are tra list C. Nonconformities have been corr 	ceable fr ected.	om the	check
•	6.6.9	Signoffs under "Proc & Rev" by in for performance of other required (and dimensional checks requiring p that the operation was performed pe	ndividuals operations rocedures) er require	respo (e.g. , cert ments.	nsible , PWHT ifying
	6.6.10	References by the QA Coordinator Control List No." for applicable no 11-1).	under "No onconformi	nconfo ties (rmance see AP
_	,			• •	•

CB		DOC. ID REV. NO. CONTRACT	AP 7-2 2
USE	OF THE SHOP CHECK LIST SYSTEM	PAGE NO. 5 OF	14
	r		
6.6.11	Unit acceptance for the assem whose signoff on a completed ch tion that:	bly by the QA] eck list is his c	Inspector, certifica-
	A. All items were identified serialization or heat codi required.	on the check ng was accompli	list and shed when
	B. Assemblies were properly ma	rked.	
,	C. Fabrication workmanship m requirements.	eets Code and	customer
6.6.12	A final review by the QA Coordi completed check list, certifying been completed and signed off, completed in accordance with refe and that related required record	nator, and signo that all operat that repairs h erenced repair pr ds are on file.	ff on the ions have have been ocedures,
6.7	The Production Foreman is res required signoffs for all open inspection, and maintaining cus until they are completed. Th (containing the original signof office of the Production Form	sponsible to ob rations, includi stody of the che e "official" ch fs) shall be kep	tain the ng final eck lists eck list ot in the
	current operations or in anothe the Production Superintendent.] offices as required; however, sibility of the Production Fore of check lists removed.	man responsible r location desig It may be removed it shall be the man to know the	for the gnated by to other respon- location
6.8	The Production Foreman shall be a QA Coordinator of upcoming witne a timely manner so the QA Coor witness and/or hold points and ca notice in advance of his witness	responsible to no ss and/or hold p dinator can sig n give the ANI re and/or hold poi	otify the ooints in noff his asonable nts.
6.9	Completed check lists are sent t final review and acceptance. T given to the ANI for his final rev is documented on the check list.	o the QA Coordin he check lists view and acceptan	ator for are then ace which
		· · · ·	

•

.

CBD		DOC. ID REV. NO. CONTRACT	AP 7-2 2
TITLE USE	OF THE SHOP CHECK LIST SYSTEM	PAGE NO. 6 OF	14
••• <u></u>		· · ·	

- approved in the same manner as the original check lists.
- 7.0 <u>CONTROL LISTS</u>
- 7.1 Control Lists (Attachment 4) are maintained by the QA Coordinator as a summary of the check lists that have been issued. They provide space for recording the dates that the check lists were issued and completed.
- 8.0 <u>REPAIR CHECK LIST</u>
- 8.1 Repair Check Lists (Attachment 5) shall be used to control the repair of nonconformities (see AP 11-1). Repair Check Lists shall be initiated and maintained by the Production Superintendent.
- 8.2 Initial entries shall include:
- 8.2.1 The nonconformance number
 - 8.2.2 A description of the nonconformity (size, depth and location of nonconformity for base metal defects and as may be necessary for control) unless included in a repair procedure.
- 8.2.3 Reference to applicable repair procedure and revision.
 - 8.2.4 Reference to other applicable procedure and revision numbers or, if there is no written procedure, a complete description using as many lines or spaces as necessary to fully describe repair steps.
 - 8.2.5 Under "Hold or Witness", designation of the proper releasing authority for established "hold" and "witness" points.
 - 8.2.6 The ANI's initials in the ANI column to indicate that the foregoing entries were reviewed with him prior to repair.
 - 8.3 Additional entries during the progress of work shall include:



			•			
	CBD		•	DOC. ID REV. NO. CONTRACT		AP 7-2 2
TITL	E / USE	OF THE SHOP CHECK LI	ST SYSTEM	PAGE NO. 7	OF	14
د بعد الم			• •	-		
•	8.3.1	Under "NDE Rept. I (not required when plished by process	D", the identi traceability control docume	fication of to the repo nt and seque	NDE rtai nce	report saccom number)
	8.3.2	Under "Welder ID", ing work per AP 9-1	the identifica	tion of weld	ers	perform
	8.3.3	At the completion the applicable QA I "CBI QA" certifying	of each listed nspector (Weld) g that:	operation, ing, NDE or	sign othe:	noffs b r) unde
		A. Welders were qu met and surfac weld meet appli	a lified, requi e and configur icable requirem	rements of ation of tl ents.	the W ne co	IPS wer omplete
		B. Required NDE wa are traceable f	s completed, and from the check	nd reports w list.	ere n	nade an
•		C. The operation performed per r	(other than equirements.	welding of	r NE	E) was
	3.3.4	The ANI may initial examinations witnes witness points").	under "ANI" to sed. (See para	indicate og graph 10.0 f	perat or "}	ions on hold and
8	3.3.5	The last column may or others to indic nessed.	y be used by the state operations	ne customer' or examin	s in atio	spector os wit-
S	9.0	WELDED CORRECTIONS	•	· ·		
g	1.1	Welded corrections	made to welde	during th		

Welded corrections made to welds during the course of deposition (prior to submittal for NDE acceptance examination) are handled as part of the welding operation.

9.2

Correction of welds found unacceptable due to visual inspection after final acceptance (welding checked signed off and/or NDE signed off) and prior to PWHT shall be performed to a correction procedure and documented in the same manner as required for repairs. Typical unacceptability is due to improperly sized butt welds, improper length or size of fillet welds or undercut.

		DOC. ID REV. NO. CONTRACT		AP 7-2 2
TITLE	OF THE SHOP CHECK LIST SYSTEM	PAGE NO.	8 OF	14
тана улика. <u>— — — — — — — — — — — — — — — — — — —</u>		•		
9.3	Each repair (or group of repair Shop Check List shall be entered applicable check list. The foll	s) to be co l on a separ owing shall	ntrolle rate lin be doc	ed on the ne of the umentéd:
9.3.1	Identification of repair procedu welder I.D. per AP 9-15.	ure, weldin	g proce	dure and
9.3.2	Signoffs for NDE of repair cavit of repair weld and NDE of compl	y (if requ eted repair	ired), r.	checking
9.3.3	Signoffs by the ANI for repairs	he has wi	tnessed	•
10.0	"HOLD" AND "WITNESS" POINT CONT	ROL		•
10.1	Work shall not proceed beyond a until the "hold" point is signed placed it or he has had it void	designate off by the ed.	d "hold e autho	d" point rity who
	The authority voiding a "hold" po such action on the Check List.	oint must i	nitial	and date
10.3	Inspectors placing "hold" point notification (per local arrange reaching of the "hold" point.	s shall bo ment) of t	e given he anti	timely
10.4	Work may proceed past a "witne individual placing it has been g (per local arrangement) of the the "witness" point.	ss" point, iven timel anticipate	provi y notif ed reac	ded the lication hing of
11.0	RECORDS			
11.1	The following records completed Quality Assurance records and sha l:	l by this all be hand	proced led per	ure are AP 14-
11.1.1	Shop Check Lists	•		
11.1.2	Repair Check Lists			
11.1.3	Control Lists		• • •	
	•			•

	GBD	DOC. ID REV. NO. CONTRACT	AP 7-2 2
TI	TLE JUSE OF THE SHOP CHECK LIST SYSTEM	M PAGE NO. 9 OF	14
	12.0 <u>ATTACHMENTS</u>		
	12.1 Attachment 1 - Shop Check I	List, Form GE515	en e
	12.2 Attachment 2 - Shop Check'I	List, Form GE516	
.*	12.3 Attachment 3 - Shop Check L	ist, Form GO1258	
	12.4 Attachment 4 - Control List	, Form GE518	
	12.5 Attachment 5 - Repair Check	List. Form GO1002	

• :

•

	C		•						DOC. REV. CONTR	ID NO. RACT		AP 2	7-2
the state of the s	TITLE	USE	OF	THE	SHOP	CHECK LI	STSYSI	EM	PAGE	NO.	10 OF	14	

SHOP CHECK LIST 「おうちょう」というななななないとない。「おおんない」など、「おおんない」など、たちになっていたのであるので、このないない sco OPERATION ۰. 210 ۰. . OPERATION 520 OPERATION These or and accepted to applicable proced 15 81 3 Weld Procedure Spec. and Repair Procedure Ū 2 IJ 1.4 Fit . Up Checked Nold Matt 10 Recorded Record Welders 1D REF. MARX 11 Weidung ance Canavai List No. 1 J ┛ Ц L * J \square ÷ J · 1 \square 國家主要出版 化酸盐 化水香油 CIII CONTRACT NO. ASSEMBLY DISPECTED & ACCEPTED BY: **, 11** W QA Ma NO. Made By App'd By 8, GE 315 PEV J

ATTACHMENT 1

	C	3)				<u></u>				DOC REV CON	. ID . NO. TRACT		AP 2	7-2
T. S. S. S.	'ITLE 🗹	USE	OF	THE	SHOP	CHECK	LIST	SYSTEM	1	PAG	e no.	11 OF	14	
1. 1.67 . 0. <u></u>			• . •									-		
		• . •	· .		т. х . 		ATTA	CHMENI	2					
· · · · · ·		United	- 449 - 1		des stati	an a sa a	·					*		
						C	E SHOP	CHECK LIS	т				er tres etc.	
				-										
				•						· .				
	· ·						•	• • •	· -	• .	• .			
				×	••••	×	•	•						
						•	•							
			•		•		•			•				
·			•		•			2	•	•				
		SEC		OPERA	TION	SEO	OPERAT	10N	SEO	OPERA	TION			
							· · · · · · · · · · · · · · · · · · ·							
•		CB AS: Insi	SEMBLY I	SPECTED	& ACCEPTED) 87: `Date		lewed with ANI	before use:	Date	CONTRACT	NO.	· .	
		Mad	e By A	p'd By	By			Name iewed By:		Date	NO of		*	•
		Di		Pate V	App'd			•	•		•		·.	

ż

	CED			, ,		· .					DOC REV CON	АР 2	7-2						
- 19+ 44 Jaury	TITLE	أهر	USE	OF	THE	SHOP	CHEC	K L	IST	SYS	TEM			PAG	E NO.	12	OF	14	
ومعهاد والمراجر والم	·					· · · · · ·	·,												
									ATTA	СНМ	ENT	3							
	~ -				• _• _							·.··						مرتبع فرخش م	™÷
				Nov				<u> </u>		<u> </u>	<u> </u>						a MUL VIA		
				II Pola													11102		
			•	H	ANI						<u> </u>						4.6 SA		·
•			• 4 • 7	3 5 1	<u>. </u>									┼╼┸╸					
		1.44					1 <u> </u>	_Π_	_Π_	<u></u>	Π	<u>ρ</u>	Π_	Π.	Π				
		1 A A .				h	<u>ı þ</u>	h	<u>h</u> _	<u>þ</u>	<u>h</u> _	<u>h</u>	<u>h</u> _	<u>þ</u>	<u>h</u>	TACT N			
• • •				1- 1-		h		h	h		<u>h</u>	<u> </u>	<u>h</u>	<u>h</u> _	<u>h</u>	20 9			
		1. 1. 1.		0 Proc 4									h	h			Sec.		
			LIST	9101 F	6 74.						<u> </u>		Ŀ			- ,		¥	
			CHECK	5000 F								1							
· .			SHOP	(1 1 P				<u>h</u>	<u> </u>	<u>þ</u>	<u>h</u> _	<u>h</u> _	<u>h</u>	<u>h</u>	<u>þ</u> _				
••••		1	B		i		Lh_	<u> </u>	<u> </u>	<u>h</u>	<u>h</u> _	<u>h</u> _	<u>h</u> _	<u>h</u>	<u>þ</u>				
÷				AVC 1				<u> </u>	h		<u> </u>	h	<u>h</u> .	<u>h</u>	<u>h</u> _				
		「日本のたい			Welding Chacked						L			L		$ \uparrow $			•
•		•		Performe												Щ		•	
		1 + 25 4 4	,	-	*3 						<u> </u>	Π_		<u>n</u> 	Γ			• •	
•						<u>þ</u>	LÞ.	<u>þ</u> _	<u>h</u> _	<u>h</u>	<u>h</u>	<u>h</u>	<u>h</u> _	<u>h</u> _	<u>þ.</u>				
				L L	Net 10	╞╌┝	Lh.	<u>h</u>	<u>þ</u> _	<u>h</u>	<u>h</u> _	<u>h</u> _	<u>þ</u> _	<u>h</u>	<u>þ</u> _				
· · · · · ·		1. A. A. A.			E S S					ŀ	h	h	h	h		App'd By Date			• •
	• • • •,	調整を行い			ternes.		······································									Date By			
	ماد عرب به م م		<u>p-asig</u>	Lordan	2							Sec. 1							

.

		C																•		· .			De Ri Ce	DC. EV.	I N TRA	D IO.			4	AP 2	7-2
	 T	ITLE		USE	OF	THI	E 5	SHO	P	СН	EC	K	L	IS	Т	S	YS	TE	M				P	AGE	: N	0.	1	3	OF	14	
. 3	• • • <u></u>	•																					•						-		
		.*								· .			ł	\T!	TA	CH	IMI	BN	T	4											
	. •						• • • •																				-			بر الارز	
																			2.8		2. 7. ⁷ .	• • •			1	-					:
						DATE OMPLETED																							anathtan Anathtan		
					DATE OF	0 			╉				+	+	+	+	+	+	╀					╉		╀		+	_		
	•	· .		CONT. NO	SHEET	ISSUE						·																	100		
:						_			-				· -		. 	$\frac{1}{1}$		-										$\frac{1}{1}$			
	• .																														
		•																ĺ						.							
						z																									
			·			DESCRIPTIC																							. N. 200		
	· ,	· ·		DL LIST	ECK LISI	2																									
				CONTRO	нор сн						Ļ		ľ	ŀ															44.5		
				ā																									X. L.		
				e						+	╎									+						-		$\frac{1}{1}$			
•			et na Linnette en		ASSEM												·														
			a an		LIST	5					_	<u> </u>				_		_			-					-				. •	
		۰.		5	CHECK																								10 M M		• •
				L	L	<u> </u>	_1	·ł			1	<u>.</u>						[<u> </u> ;•	1			 L	<u>. 1</u>		. 1	<u>.</u>			: • • :

	3							· ·				•		· · · · · · · ·			DO RE CO	C. V. NTF	ID NO RAC	Г			AP 2	7-2
TITLE	USE	OF T	HE SH	OP	C	HEC	K	LI	ST	S	YS	ΤE	M	•			PA	GE	NO	•	14	OF	14	
1. T. C. P.	<u> </u>	· · · · · · · · · · · · · · · · · · ·											· .											
	-		• .		•			A	ΤT	AC	HM	EN	T	5				•	•					·
	8, 827 87. 51 14	Sar Switter	Strange Start		м.н.		· 245				<u>.</u>		àn C	• • •				-4-1					t neitenes Hun Louis	5 (s). • -
		tipe clor	A litted ons or Nations	Date						1.2												10 M/F / 10		
		ar W ands Nuclear Is	Windth	Initials											1.38							56 100		
All and the second s		Authorized Cutomer	ANI Led Trad	Date							-		_		·			_				- - -		
		A N N N N N N N N N N N N N N N N N N N	N N N N N N N N N N N N N N N N N N N	Initele						_	-		_						_			12.8.24		
			Checking Checking Checks Friumed										_				•							
			E LEAN	Initial									1		13. YA									
			- Di			<u> </u> .					_		· ,			•		_						
			Milne See						_								_					4. 64 P.2.2		
		כא רוצו	00 8 00 8 00 8							<u>.</u>						_		-				1.00		-
		REPAIR CHI	e er Operation Required	- 	h ANI before use	,				h ANI before use					h ANI belere ui					L acarlan	Contract		A	.'
	14. 14.	8			Reviewed with Exam Cavity	or Filwp Weld	Redrom			Reviewed wit Exam Cavity	or Fit-up	RM			Reviewed wi	Erem Coult	Pi•M	Rotem				14 F 13 - 1490		
		•.	Entered By and Date			-																		
		•										•			•									
		•	beleet besechtlag	Argab Procedure No		•					•		•			•					•	1		·
			× ,				•						•								•			•

B. RACK DESIGN

2. Explain the sentence (LAR Section 3.1.4): "The extent of welding is selected to 'detune' the racks from the ground motion (OBE and SSE)."

RESPONSE

III.

The extent of cell-to-cell welding determines the "beam mode" stiffness of the rack. Although the response of a rack to seismic loadings is extremely non-linear, the maximum displacements (including sliding, tilting, twist, etc.) are found to be sensitive to the beam mode stiffness of the module. At the rack module design stage, some parametric studies of module response for the specified seismic loadings helps establish a rack design which is not apt to experience large kinematic response under the postulated loadings.

The volume of material associated with these parametric studies is quite large (8-10,000 pages). If further details of this methodology and it's application to the proposed Indian Point 2 racks is desired by the NRC, a technical audit of this material at Con Edison's rack designer's office can be provided.

B. RACK DESIGN

3. For weld stresses between the baseplate and support leg, justify the use of limit analysis when there is a partial penetration grove weld joining the components. Provide information on how two directional bending and shear at the junction are considered in constructing the interaction diagram. Also, provide 'R' factor if only elastic analysis (instead of limit analysis) were used.

RESPONSE

The weld joint between the baseplate and the internally threaded member of the support leg assembly is a partial penetration groove weld reinforced by a covering fillet weld. The weld wire is also of austenitic stainless steel stock (ER308). Even though the material yield strength of the weld wire is considerably greater than that of the base material, its yield strength is conservatively taken equal to that of the base material.

The governing code for the stress analysis of the weld structure is Section III subsection NF of the ASME Code which, at the present time, contains no stress limits for welds section under Level D loadings (which corresponds to the SSE condition). Even for normal and upset conditions the Code prescribes stress limits for equivalent static loads. The dynamic analysis of the rack provides the peak values of reactions produced by the interaction of inertia and fluid forces. In the interest of conservatism, these peak values, rather than equivalent static loads, are used for computing the weld section stresses.

In the absence of a uniquely prescribed stress limit in the Code, the stress analysis of the weld section has followed the practice of strength evaluation of reinforced concrete section. SRP 3.8.4 of NUREG 0800 provides for calculating "Design Strength" of reinforced concrete procedures Following the same design approach, the "Design Strength" of structures. the weld section is calculated assuming that the stress distribution is fully plastic across the cross-section. Recalling that the yield strength of 304 stainless steel is only 35.2% of its ultimate strength, it is concluded that the computed "Design Strength" of the weld cross-section has an inherent factor of safety against failure equal to 2.84. In other words, if the applied loads are found to reach the limit of Design Strength of the weld section based on the rectangular stresses distribution assumption, then the inherent factor of safety against failure at that point is equal to 2.84. This is totally consistent with definition of Level D condition which postulates that permanent deformation is acceptable but total structure collapse is not.

A comparison of the factor of safety corresponding to the weld Design Strength approach, and that used in base materials points up the added conservatism in this method. Section F.1332 seeks to limit the base metal stress for Level D condition to 0.7Su (Su = ultimate strength), which implies a factor of safety of 1.428 against failure. As stated above, the inherent factor of safety in the weld analysis using the Design Strength approach is much greater (= 2.84).



The governing codes, mentioned above, do not require combination of shear loads with two bending moments. However, the interaction analysis is performed using the vectorial resultant of the two moments and direct thrust on the support pedestal-baseplate interface.

In the following, we present the results assuming a linear elastic stress distribution in the welds.

The results for 1% damping (case DOB) in Table II.1, II.2, provided in response to question II.1, give stress factors $R_1 = .183$ and $R_6 = .312$ for the spindle cross-section. Since R_6 is the sum of direct and bending effects for the spindle, and R_1 is the stress factor for direct compression, we can calculate the stress factor for bending as:

$$R_{\rm b} = R_{\rm c} - R_{\rm 1} = .129$$

Since the allowable stress is $.6\sigma_y = 15000$ psi, the actual direct stress on the spindle is

 $\sigma_1 = 15000 R_1 = 2745 psi$

The bending stress at the extreme fiber of the spindle is

 $\sigma_{\rm B}$ = 15000 R_B = 1935 psi

Because of the relatively low value of bending moment, there is no tension acting on any cross-section of the spindle at the baseplate spindle interface. Thus, when the additional fillet weld area is accounted for, the maximum normal stress at the extreme fiber will be less than 4680 psi which translates to a throat shear stress of 6619 psi. Note that this result occurs for the SSE seismic event.



B. RACK DESIGN

4. The stress factors (Ri) only addresses stresses in the support feet and base plate. Provide stresses in the cell walls under an SSE considering the longitudinal (overall rack behavior), transverse compressive (due to hydrodynamic load between the racks) and impact loads from the fuel assemblies.

RESPONSE

The governing code for rack structural design as mandated by the OT Position Paper (USNRC c' 1978) is ASME Section III Subsection NF for Class 3 structures. This Code places strict limits on all "primary stresses" which are subdivided into seven categories. These are reported in Table 6.5 of the SAR as dimensionless factors (R_i , i = 1,2...7). The contribution of the hydrodynamic loads and fuel assembly impact on the overall rack behavior is included in the above stress factors. The Code prescribes no limit on the local stresses which develop in the baseplate or the cell. These stresses are defined as "local bending" or "secondary" stresses in the Code. The governing ASME Code (Section III NF Class 3) places no limit on the "local" stresses.

The stresses reported in the top line of Table 6.5 for each run are the stresses in the cell walls considering overall rack behavior. The transverse compressive stresses due to hydrodynamic loads and impact loads due to fuel assemblies do not have a prescribed Code stress limit, and therefore are not required to be evaluated and combined with the primary stresses.



III.

IV. OTHER ACCIDENT CONSIDERATIONS

1. Provide calculation which demonstrates the assertions in the submittal (LAR Sections 7.1.1 a and b) that the structural integrity of the rack and subcriticality of the stored fuel is assured.

RESPONSE

The LAR contains statements on results of certain accident scenarios which are postulated. Here we enclose results of bounding calculations which demonstrate that the postulated accident conditions do not cause unacceptable conditions in the fuel racks.

Detailed calculations are provided here for

- 1. Dropping of a fuel assembly
 - a. from a height of 36" above the top of the rack and have it hit the top plate
 - b. from a height of 36" above the top of the rack and have it hit the baseplate

In the case of accident 1a, permanent deformation would be confined to the top region of the rack above the active fuel region. This is an area where no other postulated conditions would result in a continuing high stress. We therefore do not consider any other loading acting in concert with the above postulated accident.

For the case of accident conditions 1b, the concern would be to maintain the integrity of the pool floor liner plate and to maintain the center-to-center distance between adjacent storage locations.

The center-to-center distance between adjacent storage cells is not dependent on the presence or absence of support from the baseplate. The purpose of the above calculation is only to show that there would be no danger to the liner. In the event of a dropped fuel assembly, it is correct to say that the baseplate may separate from the tube in the immediate vicinity of the affected tube. While this would result in baseplate plastic bending, it would not affect center-to-center spacing since there would be no effect on the welds between adjacent tubes nor on the baseplate-to-tube welds away from the immediate vicinity of the dropped assembly.

Accident #1a - A Mass (assumed weight = 20001b) drops 36" in water and hits the top of the rack.

When a rigid body moves with velocity V and strikes the edge of an elastic rod or plate, it may be shown (Timoshenko and Goodier, 1951, pp. 441-442) that an impact stress develops of magnitude

= EV/C; $C^2 = E/$; = mass density



Based on a drop velocity of 135.22 in/sec at impact at the top of the rack, we show that the wave propagation stress at the point of impact is below yield:

$$\sigma = (E\rho)^{1/2} V = 19330 \text{ psi}$$

We also examine the depth of propagation down the cell should local bucking occur causing the cell wall to have to support the impact load by shear alone.

Let the impact be spread over the width W of one fuel assembly. Let d be the depth (toward the active fuel region) that is capable of carrying shear and resisting the impact. Then, if σ is the impact stress, we have

$$W\sigma t = 2d \tau_y t$$

Where τ_y is the shear yield stress. Since $\tau_y = .577 \sigma_y$ the depth of cell required to support σ is

 $\sigma_{\rm W}$ d = _____ = 5.127" (Note: $\sigma_{\rm y}$ increased by 15% for dynamic loading)

That is, in the worst case, yielding may occur to a depth of 5.127" below the top of the rack. This is above the active fuel region so there is no safety concern for this condition.

Accident 1b - A Fuel Assembly drops to the baseplate

As noted, the major concern is with the integrity of the pool liner. In the dry condition, damage to the liner is not a safety concern since there is no water to contend with. The design analysis simply shows that while welds may break, the baseplate structure has sufficient strength to prevent the dropped fuel assembly from hitting the liner. We examine only the wet condition where there is a potential safety concern.

Considerations of a fuel assembly dropping through a narrow channel filled with water lead to the result that the impact velocity at the rack base of a 2000 lbs assembly is

VF = 257 in./sec

To check maximum baseplate deformation after local weld damage, we treat the baseplate deforming section as a circular plate and wish to show that maximum baseplate deformation h is less than the minimum distance from the baseplate to the liner. The energy to be absorbed is

$$U = \frac{1}{2} \frac{W}{g} VF^2$$

We consider the plate absorbing this energy by stretching as a membrane. Thus

$$\frac{1}{2} ((\mathcal{O}_{r} \in_{r}^{+} \mathcal{O}_{\Theta} \in_{\Theta}) \cap \mathbb{R}^{2} \mathbb{T}) = \mathbb{U} \qquad \mathbb{R} = \text{radius, } \mathbb{T} = \text{thickness}$$
of circular
plate

For the simple case considered here, $\epsilon_r = \epsilon_{\Theta} = \frac{\delta_r}{R}$

where δ is the stretch of the plate.

Assuming that the failure stress is Y_F , then $\sigma_r = \sigma_{\Theta} = Y_F$ yields

$$\mathcal{S} = \frac{U}{\frac{Y_{F} \mathcal{T} R T}{}}$$

Since

$$\int = [R^2 + h^2]^{1/2} - R = \frac{h^2}{2R}$$

an estimate of h is

$$h^{2} = \frac{2 U}{\frac{Y_{F} T}{T} T}$$

In terms of VF

$$h^{2} = \frac{W}{g} \frac{VF^{2}}{Y_{F} \gamma T}$$

Using the conservative estimate leads to the conclusion that the baseplate will contain the drop with the possibility of some local baseplate to cell weld damage occurring adjacent to the cell in question. This does not affect the ability of the rack to withstand any concurrent seismic loadings.

h = 2.752" if
$$Y_F = \sigma_Y$$



IV. OTHER ACCIDENT CONSIDERATIONS

2. Provide information on the procedures for removing the existing racks and installing new racks including the possibility of rack drop on the pool floor or a wall.

RESPONSE

The removal of old racks and installation of new racks will be carried out using written procedures which will be reviewed and approved in accordance with the Indian Point 2 review process before use. A list of activities that will be covered by procedures is provided below along with brief explanatory notes, where necessary, for clarification.

(i) Receipt Inspection Procedure:

Includes receipt inspection of transit damage, dummy gage test and "dimensional overchecks.

- (ii) Horizontal Lift and Upending of Racks.
- (iii) Vertical Lift and Preliminary Leveling of Racks.
- (iv) Purpose and Scope of Removal of Existing Racks and Installation of New Racks.
- (v) New Racks Installation

This procedure will contain the following information:

- o Materials and equipment o Safe rigging practice o NUREG 0612 requirements o Load travel path well defined Note: The path specified will preclude movement of racks over fuel assemblies at any time. o Sketches of lifting fixtures o Sketches of remote tooling o QA hold points o Fuel shuffles
- (vi) New Rack Leveling
- (vii) Underwater Diving (if necessary)
- (viii) Vacuum Box Testing for Leak Detection Procedure

(ix) Underwater Vacuum Cleaning

(x) Site Free Path Gauge Test

(xi) Cell Rework

The detailed procedures for the above activities are currently under preparation and review by Con Edison. The removal and installation of the racks involves a carefully planned sequence of fuel assembly relocation followed by old rack removal and new rack placement. Figures 1 through 6 show the sequence of rack regions occupied by fuel, racks removed and racks installed in the pool. Old racks are indicated by numerals 1 through 12. New racks are designated by alphanumeric identifications used in the Licensing Report. The dimension x (with subscripts where necessary) indicates the shortest distance between the fuel and the new racks at each reracking stage. These figures provide proposed fuel shuffles which meet the objective of maintaining a minimum distance of four feet between stored fuel and a rack being installed. The final reshuffling plan may differ somewhat from Figure 1 through 6, but the objective of maintaining the minimum distance of four feet will be met.

In the unlikely event that a rack was dropped, a thorough inspection of the affected area including but not limited to the pool liner, potentially damaged racks, and the spent fuel cooling system would be done with remote inspection equipment such as underwater cameras. If necessary, divers would be utilized to augment and/or verify the remote inspection. Based on the inspection results an action plan and associated procedures would be developed to correct any deficiencies identified.




FIGURE 1

INDIAN POINT UNIT II

INSTALLATION AND REMOVAL SEQUENCE AND PROPOSED FUEL SHUFFLE STEPS:

- Shuffle all fuel assemblies to locate them as shown in this Figure.
- 2. Remove Racks 11 and 12 for disposal.

Install Racks G1 and G2.

Note: 5' < x'





FIGURE 2 INDIAN POINT UNIT II

INSTALLATION AND REMOVAL SEQUENCE AND PROPOSED FUEL SHUFFLE STEPS:

 Shuffle fuel to obtain the configuration shown in this Figure. The following net movements from racks are involved.

<u>Rack ID</u>	Assemblies Added (+) <u>or Removed (-)</u>
1 5 6 7 9 10	+ 5 -30 -55 -48 -20 - 8
G1	+96
G2	+60

Remove Racks 9 and 10.

Note: 4 1 x



. .

.



Note: 4' < x





V. MISCELLANEOUS ITEMS

1. Provide details of the proposed installation procedures indicating how the elevations of the racks and designated gaps between the racks will be maintained and monitored.

RESPONSE

A brief description of the procedure indicating how control of rack elevations and inter-rack gaps will be realized during installation is given below:

- a. Equipment Required:
 - o 50' transit pole
 - o Optical level
 - o Shim plates
 - o Hydraulic jacks
 - o Stainless steel shims
- b. Floor Elevation Readings
 - o Using 50' transit pole and optical level record the elevation readings of the locations of the four-corner shim plates where the rack is to be installed.
- c. Rack Installation and Leveling in Spent Fuel Pool
 - o Prior to lowering rack into pool, adjust four-corner feet to account for the differences in elevations of the four-corner shim plates.
 - o Set the new rack in its designated location. Using leveling tool, ensure all four-corner feet are in contact with shim plates.
 - o Record rack height elevations using optical level and 35' transit pole in each of the four corners.
 - o If the differences in elevation are within $\pm 1/16$ " then the rack is acceptable.
 - o If the differences are not within <u>+1/16</u>" using hydraulic jacks, raise rack just enough to make the proper amount of turns for the necessary adjustments to bring elevation differences to within the acceptable tolerance +1/16".
 - o Check all four-corner feet with leveling tool to ensure they are still in contact with the shim plates.



d. Rack Position

- o The rack is placed on the pool bearing pad locations as illustrated in Drawing 531 provided in response to question I.3. Minor adjustment of the rack location may be required to satisfy the inter-rack gap and rack-to-wall gap requirements. For this purpose, the "go-no-go" gage blocks are used to determine whether the rack location criterion is satisfied. If necessary, hydraulic jacks along with the crane are used to nudge the bearing pad or the rack to its final designated location.
- <u>NOTE</u>: Rack leveling readings and measurements between racks will be verified by Contractor's Q.C. using remote camera and an optical level.

MISCELLANEOUS ITEMS

- 2. Provide a summary of plant safety procedure for the following cases:
 - (a) Fuel drop (or rack drop) accident.
 - (b) A seismic event.
 - (c) Loss-of-water from the pool detected by leak chases.

RESPONSE

All of the procedures referenced below are available at Indian Point 2 for review.

a) In the event of a fuel drop (or rack drop) accident, damage to fuel would be assumed until proven otherwise. Therefore the procedure that would be used for a fuel or rack drop accident would be Abnormal Operating Instruction 17.0.2 entitled "Irradiated Fuel Damage in Fuel Storage Building". This procedure requires evacuation of all personnel if radiation monitor alarms are received. All fuel handling would be suspended and fuel movement would not be permitted until further evaluation is performed and permission is obtained from the Operations Manager. After evaluation by Health Physics personnel, re-entry to the Fuel Storage Building to perform damage assessment will occur.

Coincident with the above actions the required Emergency Plan actions will be evaluated. The event would be classified using the graded classification system for emergencies and actions would be taken to protect the safety of the public, plant personnel and property both onsite and offsite.

In the case of a seismic event, Abnormal Operating Instruction 28.0.8 b) entitled "Earthquake Emergency" would be utilized. The procedure requires an inspection of plant equipment and structures which includes an inspection of the spent fuel pool for possible water leakage following a seismic event. If the water level in the pool is dropping, actions are to be taken to restore normal level. If the normal makeup system to the pool is unavailable, actions are to be taken to utilize available water sources such as the fire protection system. In addition, this procedure requires notification of Con Edison's Plant Structures Engineer and Field Engineering if the seismic event was greater than 0.10g horizontal or 0.05g vertical or if damage to plant structures has occurred. Once this notification occurs, the Structures Engineer and Field Engineering must recommend that further action is not necessary or specify repair procedures for damaged equipment or The spent fuel pool and the racks are designed for a structures. design basis seismic I earthquake (also called a safe shutdown

٧.

earthquake) which is a 0.15g horizontal and 0.10 g vertical seismic event. Therefore, the condition of the spent fuel pool and racks after a safe shutdown earthquake or less would be within the analysis for safe storage of fuel in the storage racks. This procedure requires Engineering evaluation at a much lower level of seismic event than the pool and racks are designed to withstand. Therefore, this procedure addresses seismic events of concern to the spent fuel pool and racks.

In addition to the procedure discussed above, the severity of the seismic event would be evaluated for activation of the Emergency Plan if necessary.

Attachment II contains page revisions to the Consolidated Edison June c) 20. 1989 request for a license amendment to expand spent fuel storage. As discussed in Attachment II, revision of page 2-2 of Attachment B of the submittal, the Indian Point 2 spent fuel pool was constructed without a leak chase. Loss-of-water from the spent fuel pool is detected by level instrumentation. The level instrumentation has an alarm in the control room which activates when a variation of + 6" from normal level occurs. The Alarm Response Procedure for control room panel SGF window 2-2 is for spent fuel pool level. When a spent fuel pool level alarm is received, a direct visual observation of the spent fuel pool level is required. If the water level is low, restoration of normal level using the makeup system is required. The procedure provides two alternative makeup water sources in the event the first choice is not available. The procedure directs that an investigation be initiated to determine the cause of the low water level which includes: refueling cavity leakage, spent fuel pool and purification piping leakage, spent fuel pool building foundations evaporation, and spent fuel pool cooling system line-up. leakage.

ATTACHMENT II

PAGE REVISIONS TO LICENSE AMENDMENT REQUEST FOR INCREASE IN SPENT FUEL STORAGE CAPACITY DATED JUNE 20, 1989

CONSOLIDATED EDISON COMPANY OF NEW YORK, INC. INDIAN POINT UNIT NO. 2 DOCKET NO. 50-247 JANUARY, 1990



Summary of Page Changes

1. Page 2-2

This revision deletes the reference to a leak chase in the spent fuel pool. The Indian Point 2 spent fuel pool was built and licensed without a leak chase.

2. Page 3-8

This revision provides the materials for the support leg and failed fuel canister that are now going to be used in rack fabrication.

3. Page 3-13, Figure 3.5

This revision provides the updated dimensions for the adjustable support.

The racks will be arranged in two regions in the spent fuel pool. Region I will have 269 locations capable of storing unirradiated fuel of up to 5.0 wt% U-235 initial enrichment. Region I has enough locations to store a full core discharge and one-third core of unirradiated fuel. Region II will have 1105 locations for storage of fuel which meets enrichment and burnup criteria developed as part of the rack design. Section 4 of this report addresses this in more detail. In addition, there are two locations for storage of failed fuel canisters. The total number of storage locations, as detailed above, is 1376.

Table 2.3 gives the essential storage cell data for all racks. As noted, the storage cells are 8.75" (internal dimension) for Region I and 8.80" for Region II which accommodates the standard Westinghouse fuel assembly or equivalent fuel.

The module's four support legs are remotely adjustable. Thus, the racks can be made vertical and the top of the racks can easily be made co-planar with each other. The rack module support legs are engineered to accommodate variations of the pool floor. The placement of the racks in the spent fuel pool has been designed to preclude any support legs from being located on the liner welds. Support pads have been provided to bridge any obstructions which could potentially interfere with placement of a rack support leg.

2.1.2 Poison Material

Boraflex has been selected as the neutron absorber material for the new high density spent fuel storage racks.

2-2

e. <u>Other References</u>

- (1) NRC Regulatory Guides 1.13, Rev. 2 (proposed); 1.29, Rev. 3; 1.31, Rev. 3; 1.61, Rev. 0; 1.71, Rev. 0; 1.85, Rev. 22; 1.92, Rev. 1; 1.124, Rev. 1; and 3.41, Rev. 1.
- (2) General Design Criteria for Nuclear Power Plants, Code of Federal Regulations, Title 10, Part 50, Appendix A (GDC Nos. 1, 2, 61, 62, and 63).
 - (3) NUREG-0800, Standard Review Plan, Sections 3.2.1, 3.2.2, 3.7.1, 3.7.2, 3.7.3, 3.8.4.
 - (4) "OT Position for Review and Acceptance of Spent Fuel Storage and Handling Applications," dated April 14, 1978, and the modifications to this document of January 18, 1979.

(anti-

3.5 <u>MATERIALS OF CONSTRUCTION</u>

Storage Cell:	SA240-304
Baseplate:	SA240-304
Support Leg:	SA479-304
Support Leg (male):	Ferritic stainless (ar galling material) SA564-630
Poison:	Boraflex
Failed Fuel Canister	SA312-304



FIGURE 3.5



3-13

n antare e arrae.

ATTACHMENT III

REPORT ON ANALYSIS OF AN ISOLATED 5 W/O FUEL ASSEMBLY IN WATER

CONSOLIDATED EDISON COMPANY OF NEW YORK, INC. INDIAN POINT UNIT NO. 2 DOCKET NO. 50-247 JANUARY, 1990

I. INTRODUCTION

After completion of the analysis for the licensing report in Attachment B to the June 20, 1989 letter to the NRC requesting a license amendment to modify spent fuel storage requirements, an additional case involving a 5 w/o fuel assembly was identified as requiring further analysis. This case involved the keff, including uncertainties, of a 5 w/o fuel assembly in pure water in the spent fuel pool when not located in a storage rack. Upon review of other spent fuel storage modifications at other facilities, it became apparent that this case had not been addressed before. Therefore, Con Edison proceeded with the analysis for the fuel used at Indian Point 2, Westinghouse 15x15. This report provides the analytical methodology and results and the subsequent conclusions.

II. ANALYTICAL METHODOLOGY

A. Reference Fuel Assembly

The design basis fuel assembly is a 15x15 array of fuel rods with 21 rods replaced by 20 control rod guide tubes and 1 instrument thimble. Table 1 summarizes the design specifications and the expected range of significant variations. The fuel assembly grid spacers and miscellaneous hardware were neglected and are considered to have only a minor and conservative effect on reactivity.

B. Calculational Models

The primary criticality analyses were performed with a two-dimensional multi-group transport theory technique, using the CASMO-2E⁽¹⁾ computer code. Independent verification calculations were made with a Monte Carlo technique utilizing the AMPX-KENO IV computer package⁽²⁾, with the 27-group SCALE* cross-section library⁽³⁾ and the NITAWL subroutine for U-238 resonance shielding effects (Nordheim integral treatment). These codes have previously been benchmarked and determined to have a bias of 0.0013 with an uncertainty of \pm 0.0018 for CASMO-2E and 0.0106 \pm 0.0048 (95%/95%) for NITAWL-KENO. In addition, a check calculation was run with KENO Va to independently confirm the KENO IV calculation.

Casmo-2E was also used to evaluate the reactivity consequences of temperature and the tolerances on fuel density and enrichment.

In the geometric model used in the calculations, each fuel rod and its cladding were described explicitly and reflecting boundary conditions (zero neutron current) were used in the axial direction and at the centerline of the water space between assemblies. The model assumed fuel assemblies on a 21 inch lattice spacing. Diffusion theory calculations (with constants edited from CASMO-2E) confirmed that the model adequately represents an isolated fuel assembly. Because of the high scattering and low absorption crossections of the large volume of water, it was necessary to use a large number of neutron histories (75,000) to obtain acceptable statistics in the KENO calculation.

*"SCALE" is an acronym for <u>Standardized</u> <u>Computer</u> <u>Analysis</u> for Licensing <u>Evaluation</u>, a standard cross-section set developed by ORNL for the USNRC.

III. ANALYTICAL RESULTS

A. Reference Calculations

Calculations for a single isolated fuel assembly in pure water at 20° C gave the following results:

CODE	CALCULATED k	BIAS CORRECTED k 🥪
CASMO-2E	0.9552	0.9565 ± 0.0018
KENO-IV	0.9426 <u>+</u> 0.0047	0.9532 <u>+</u> 0.0067
KENO-Va	0.9428 + 0.0071	0.9534 + 0.0086

Including the effect of fuel tolerance uncertainties and a small temperature correction, the maximum, k_{∞} for both CASMO-2E and KENO IV becomes 0.961 (see Table 2).

B. Tolerance Uncertainties

The reactivity effect of fuel tolerances were determined from differential CASMO-2E calculations. These uncertainties were found to be \pm 0.0028 for fuel density (\pm 2% in density) and \pm 0.0011 for fuel enrichment (+ 0.05 in % enrichment).

C. Temperature Effect

Calculations were made at several temperatures by CASMO-2E, with the following results:

TEMPERATURE	<u>k</u> ~
20 °C	0.9552
40 °C	0.9558
65 ⁰ C	0.9538

Although the reactivity is nearly insensitive to temperature over the expected range of pool water temperatures, the maximum value at 40 $^{\circ}$ C was used to determine a small correction (+ 0.0006 k) to the base calculations at 20 $^{\circ}$ C. Above 40 $^{\circ}$ C, the temperature coefficient of reactivity is negative and higher temperatures will therefore result in lower reactivities.

IV CONCLUSIONS

Results of the analysis confirm that a single assembly of 5w/o enrichment, immersed in clean unborated water, would exceed a k_{eff} of 0.95 when not in storage. As summarized in Table 2, the maximum calculated reactivity (k_{∞}) was 0.961, including uncertainties at the 95% probability, 95% confidence level. Independent calculations by CASMO-2E and by KENO (both versions IV and Va) were in agreement and confirmed the maximum k_{∞} of 0.961.

Although a k_{eff} of 0.95 is exceeded, no immediate criticality safety concern exists since (1) there is a substantial subcriticality margin (-0.04 Δ k) and (2) the soluble boron actually present in the pool water will assure reactivity limits will be met (a concentration of only 100 ppm boron is estimated to be adequate to reduce the reactivity below 0.95). The proposed Indian Point 2 Technical Specification page revisions that were submitted to the NRC in Attachment A to the June 20, 1989 letter from Con Edison contain a requirement for a minimum boron concentration in the spent fuel pool at all times. Proposed Technical Specification 3.8.D.2 states "At all times the spent fuel storage pit boron concentration shall be at least 1500 ppm." The required 1500 ppm far exceeds the approximately 100 ppm required to reduce the keff to less than 0.95. Therefore, with the proposed Technical Specification 3.8.D.2 in effect, the reactivity of the spent fuel pool for this case will be well below a k_{eff} of 0.95.

REFERENCES

1. A. Ahlin, M. Edenius, H. Haggblom, "CASMO - A Fuel Assembly Burnup Program," AE-RF-76-4158, Studsvik report (proprietary).

A. Ahlin and M. Edenius, "CASMO - A Fast Transport Theory Depletion Code for LWR Analysis," <u>ANS Transactions</u>, Vol. 26, p. 604, 1977.

M. Edenius et al., "CASMO Benchmark Report," Studsvik/ RF-78-6293, Aktiebolaget Atomenergi, March 1978.

- Green, Lucious, Petrie, Ford, White, Wright, "PSR-63/AMPX-1 (code package), AMPX Modular Code System for Generating Coupled Multigroup Neutron-Gamma Libraries from ENDF/B", ORNL-TM-3706, Oak Ridge National Laboratory, March 1976.
- 3. R.M. Westfall et al., "SCALE: A Modular Code System for performing Standardized Computer Analyses for Licensing Evaluation," NUREG/CR-0200, 1979.

V

Table 1DESIGN BASIS FUEL ASSEMBLY SPECIFICATIONS

 10.31 ± 0.21

FUEL ROD DATAOutside diameter, in.0.422Cladding thickness, in.0.0243Cladding inside diameter, in.0.3734Cladding materialZr-4Pellet density, % T.D.95Pellet diameter, in.0.3659Maximum enrichment, wt % U-2355.00 ± 0.05

Maximum stack density, g U0₂/cc

FUEL ASSEMBLY DATA

Fuel rod array	15x15
Number of fuel rods	204
Fuel rod pitch, in.	0.563
Number of control rod guide and	21
instrument thimbles	
Thimble O.D., in. (nominal)	0.546
Thimble I.D., in. (nominal)	0.512

Table 2 CRITICALITY ANALYSIS OF AN ISOLATED FUEL ASSEMBLY IN WATER

ι.	CASMO-2E	AMPX-KENO IV
Fuel Enrichment, wt% U-235	5	5
Temperature for analysis	20 ⁰ C (68 ⁰ F)	20 ⁰ C (68 ⁰ F)
Calculated k	0.9552	0.9426
Temperature correction (40 ⁰ C)	+0.0006	+0.0006
Calculational bias, k	0.0013	0.0106
Sum	0.9571	0.9538
Uncertainties		
Bias	<u>+</u> 0.0018	<u>+</u> 0.0048
Monte Carlo Statistics	NA	<u>+</u> 0.0047
Fuel enrichment	<u>+</u> 0.0011	<u>+</u> 0.0011
Fuel density	<u>+</u> 0.0028	<u>+</u> 0.0028
Statistical combination of uncertainties	<u>+</u> 0.0035	<u>+</u> 0.0074
Reference k Maximum Reactivity (k)	0.9571 <u>+</u> 0.0035	0.9538 <u>+</u> 0.0074

Ģ



SEE APERTURE CARDS

14

NUMBER OF OVERSIZE PAGES FILMED ON APERTURE CARDS

APERTURE CARD/HARD COPY AVAILABLE FROM

RECORDS AND REPORTS MANAGEMENT BRANCH