CONSOLIDATED EDISON COMPANY OF NEW YORK, INC.
4 IRVING PLACE
NEW YORK, N.Y.

INDIAN POINT GENERATING STATION
UNIT NO. 2

CENTRAL ENGINEERING DEPARTMENT
SPECIFICATION NO. MP – 88 – 002

INDIAN POINT 2 SIMULATOR
PHASES III & IV UPGRADE

PREPARED BY: Robert F. McVetty
Robert F. Mc Vetty
Senior Engineer

REVIEWED BY: Thomas Magnani
Thomas Magnani
Process Computer Engineer

APPROVED BY:
Rex J. Helfant
Generation Programs & Controls Engineer

DATE: MARCH 15, 1988

REVISION NO. 0

9410030233 920326
PDR ADOCK 05000247
P PDR

10/3 233

TECHNICAL SPECIFICATION

CONSOLIDATED EDISON OF NEW YORK, INC.

INDIAN POINT UNIT 2
SIMULATOR
PHASES III & IV - UPGRADE

REV 0
3-11-88

prepared
for
CONSOLIDATED EDISON
by
EXITECH CORPORATION
Columbia, Maryland

Table of Contents

1.0 SCOPE 1-1
1.1 Project Description 1-1
1.2 Scope of Project 1-1
1.3 Work Supplied by Seller 1-1
1.3.1 General Requirements 1-1
1.3.2 Control Room Simulation Scope 1-4
1.4 Work Supplied by Con Edison 1-4
1.5 Table of Compliance 1-5
Figures 1-1 & 1-2 Simulator Layout

2.0 DEFINITIONS 2-1

3.0 CODES AND STANDARDS 3-1
3.1 Required Codes And Standards 3-1
3.1.1 ANSI/ANS 3.5 3-1
3.1.2 ANSI MC8.1 3-1
3.1.3 ANSI/NFPA 70* 3-1
3.1.4 ANSI/NFPA 75 3-1
3.1.5 ANSI N413 3-1
3.1.6 ANSI/UL 478 3-1
3.1.7 ANSI X3.9 3-1
3.1.8 ANSI Y14.1 3-1
3.1.9 ANSI Y 32.16 3-1
3.1.10 ASTM D635 3-1
3.1.11 IEEE STD 730 3-1
3.1.12 IEEE STD 802.3 3-1
3.1.13 IEEE STD 828 3-2
3.1.14 IPCEA 5-61-402-73 3-2
3.1.15 ISA-S61.1 3-2
3.1.16 MIL STD 1644B 3-2
3.1.17 NUREG CR1482 3-2
3.1.18 NUREG CR2353 3-2
3.1.19 NUREG/CR-4640 3-2
3.1.20 NUREG-1258 3-2
3.1.21 PNL-4674, March 1983 3-2
3.1.22 Reg Guide 1.8 3-2
3.1.23 Reg Guide 1.149 3-2
3.1.24 TRAD No. 3, Rev. 4 3-2
3.1.25 TRAD No. 5, Rev. 3 3-2
3.1.26 UL 83-1980 3-2
3.1.27 10 CFR parts 50 and 55 3-2
3.2 Other Codes and Standards for Reference 3-3
3.2.1 ANSI/ANS 10.3 3-3
3.2.2 ANSI/ASME N45.2.23 3-3
3.2.3 ANSI/IEEE-ANS-7.4.3.2 3-3
3.2.4 ANSI/IEEE Std 91 3-3
3.2.5 ANSI/IEEE STD 315 3-3
3.2.6 ANSI N45.2.11 3-3

3.2.7 ANSI X3.1 3-3
3.2.8 ANSI X3.12 3-3
3.2.9 ANSI X3.24 3-3
3.2.10 ANSI X3.4 3-4
3.2.11 ANSI Y14.15 3-4
3.2.12 Bulletins 1-10 3-4
3.2.13 EIA Std RS-232-C 3-4
3.2.14 EIA Std RS-363 3-4
3.2.15 EIA Std RS-404 3-4
3.2.16 EIA Std RS-422 3-4
3.2.17 EIA Std RS-423 3-4
3.2.18 EIA Std RS-425 3-4
3.2.19 EIA Std RS-449 3-4
3.2.20 EL-3089 EPRI 3-4
3.2.21 EPRI NP-783 3-4
3.2.22 EPRI NP-4243 3-5
3.2.23 EPRI NP-4977 3-5
3.2.24 IEEE Std 352 3-5
3.2.25 IEEE STD 729 3-5
3.2.26 IEEE STD 829 3-5
3.2.27 IEEE Std 830 3-5
3.2.28 IEEE Std 983 3-5
3.2.29 INPO TQ-504 3-5
3.2.30 Mil Std MIL-HDBK-217 3-5
3.2.31 Mil Std 471 3-5
3.2.32 MIL-STD-483A 3-5
3.2.33 MIL-STD-1521 3-5
3.2.34 NASC-39 3-5
3.3 Compliance to the Codes and Standards 3-5

4.0 TESTING, DOCUMENTATION AND SUBMITTAL REQUIREMENTS 4-1
4.1 Testing Requirements 4-1
4.1.1 Inspections and Tests 4-1
4.1.2 Factory Acceptance Test 4-2
4.1.2.1 Preparation of Test Procedures 4-2
4.1.2.2 Prerun of the Factory Acceptance Test 4-3
4.1.2.3 Beginning of Factory Acceptance Tests 4-3
4.1.2.4 Conduct of Factory Acceptance Test 4-3
4.1.2.5 Completion of Factory Acceptance Tests 4-4
4.1.3 Continuing Onsite Testing 4-4
4.1.3.1 Availability Demonstration 4-4
4.1.3.2 Warranty Period Testing 4-5
4.1.4 Completion of Seller Responsibility 4-6
4.2 Documentation Requirements 4-6
4.2.1 General Hardware Documentation 4-6
4.2.2 Computer System Hardware Documentation (all computers) 4-7
4.2.3 Software Documentation 4-8
4.2.3.1 Support Software Documentation 4-9
4.2.3.1.1 Seller Operating System Software 4-9
4.2.3.1.2 Seller Utility, Engineering Support, Simulator Executive, and Instructor System Software 4-10
4.2.3.1.3 Seller Supplied Diagnostic, Test and Maintenance Software 4-10

4.2.3.2 Plant Simulation Software 4-11
4.2.3.2.1 Modeling Techniques Handbook 4-11
4.2.3.2.2 Nomenclature Dictionary 4-13
4.2.3.2.3 System Design Reports. 4-14
4.2.4 Test Reports 4-16
4.2.5 Maintenance Manual 4-16
4.2.6 Instructor's Manual 4-16
4.2.7 Administrative Manual 4-16
4.2.8 Drawings 4-16
4.3 Documentation Submittal Requirements 4-17
4.3.1 Preliminary Design Documentation Submittals and Reviews 4-17
4.3.2 Interim Design Documentation Submittals and Reviews 4-18
4.3.3 Final Documentation Submittals 4-19
Table 4.1-1 ATP Outline
Attachment 4.A ATP Development

5.0 QUALITY ASSURANCE/QUALITY CONTROL REQUIREMENTS 5-1
5.1 General Requirements 5-1
5.2 Software Requirements 5-3
5.2.2.1 ANSI/ANS 10.3-1986 5-3
5.2.2.2 ANSI N45.2.11-1974 5-4
5.2.2.3 ANSI X3.9-1978 5-4
5.2.2.4 ANSI/ASME N45.2.23-1978 5-4
5.2.2.5 ANSI/IEEE STD 91-1973 5-4
5.2.2.6 ANSI/IEEE STD 315-1975 5-4
5.2.2.7 ANSI/IEEE-ANS-7-4.3.2-1982 5-4
5.2.2.8 EL-3089 EPRI 5-4
5.2.2.9 EPRI NP-4977 5-4
5.2.2.10 IEEE STD 730 5-4
5.2.2.11 IEEE STD 983-1986 5-4
5.2.2.12 IEEE STD 830-1984 5-4
5.2.2.13 IEEE STD 829 5-4
5.2.2.14 IEEE STD 828 5-4
5.2.2.15 IEEE STD 729 5-4
5.2.2.16 INPO TQ-504 5-4
5.2.2.17 MIL-STD-1644B 5-4
5.2.2.18 MIL-STD-483A 5-5
5.2.2.19 MIL-STD-1521 5-5
5.2.2.20 NASC-39 5-5
5.2.2.21 NUREG-1258 5-5
5.2.2.22 NUREG/CR-2353 5-5
5.2.2.23 NUREG/CR-4640 5-5
5.3 Hardware & Associated Peripheral Requirements 5-5
5.3.2.1 ANSI ISA RP 55.1 5-6
5.3.2.2 ANSI Y14.1 5-6
5.3.2.3 ANSI/NFPA 70* 5-6
5.3.2.4 ANSI/NFPA 75 5-6
5.3.2.5 ASTM D635 5-6
5.3.2.6 IPCEA 5-61-402-73 5-6
5.3.2.7 Mil-STD/Mil-HDBK-217 5-7
5.4 Panels, Wiring & Instrumentation 5-7
5.5 Quality Assurance Records & Documentation 5-8

6.0 PACKING, SHIPPING AND INSTALLATION 6-1
6.1 Packing Requirements 6-1
6.2 Shipping Requirements 6-1
6.3 Installation Requirements 6-2
6.3.1 Proposal Details 6-2
6.3.2 General 6-2
6.4 Other Shipment Requirements 6-3

7.0 UTILIZATION OF EXISTING SIMULATED HARDWARE AND SOFTWARE 7-1
7.1 Hardware Requirements 7-1
7.1.1 Panels 7-2
7.1.2 Instrumentation & Controls 7-2
7.1.3 Input/Output Interface Equipment 7-2
7.1.4 Power, Ground and Signal Wiring 7-2
7.1.5 Computers and Peripherals 7-3
7.1.6 Instructor Station 7-3
7.2 Software Requirements 7-3
7.2.1 Real Time Simulation 7-4
7.2.1.1 NSSS Models 7-4
7.2.1.2 Electrical Generator and Distribution 7-4
7.2.1.3 Balance of Plant Systems 7-4
7.2.1.4 Instructor Station 7-5
7.2.2 The DEC Operating System, Diagnostic and Utility Software 7-5
7.2.2.1 DEC System Software 7-5
7.3 Documentation Requirements 7-5

8.0 SPARE PARTS, EXPENDABLES AND MAINTENANCE 8-1
8.1 Simulator Equipment Spare Parts 8-1
8.1.1 Spare Parts List 8-1
8.2 Expendables 8-2
8.3 Maintenance 8-2
8.3.1 Manuals and Procedures 8-2
8.3.2 Tools and Test Equipment 8-2
8.3.3 I/O Tester 8-2

9.0 PROJECT ORGANIZATION 9-1
9.1 Project Manager 9-1
9.2 Project Team 9-1
9.3 Project Schedule 9-2
9.4 Project Reports 9-3
9.4.1 Monthly Report 9-4
9.4.2 Project Meetings 9-5
9.4.3 Correspondence 9-5
9.4.4 Meeting and Telephone Conversation Minutes 9-5
9.5 Project Team Information 9-5
9.6 Project Monitoring 9-6

10.0 CONFIGURATION MANAGEMENT 10-1
10.1 Configuration Management System functions 10-3
10.2 Functional Requirements 10-3
10.3 Supporting Reports and Data Bases 10-6

11.0 REQUIRED TRAINING 11-1
11.1 General 11-1
11.1.1 Cross Training 11-1
11.1.2 Schedule 11-1
11.1.3 Number of Students 11-2
11.1.4 Documentation 11-2
11.1.5 Course Content 11-2
11.1.6 Training Materials 11-2
11.1.7 Instructor Qualifications 11-3
11.2 Hardware Maintenance Training 11-3
11.2.1 General 11-3
11.2.2 Objectives 11-4
11.2.3 Course Structure 11-4
11.2.4 Course Topics 11-5
11.2.5 Student Material 11-6
11.3 Software Training 11-6
11.3.1 General 11-6
11.3.2 Student Materials 11-6
11.3.3 Objectives 11-6
11.3.4 Course Topics 11-7
11.4 Instructor Training 11-9
11.4.1 General 11-9
11.4.2 Student Materials 11-9
11.4.3 Objectives 11-9
11.4.4 Course Topics 11-10

12.0 DATA 12-1
12.1 Simulator Design Data 12-1
12.1.1 Con Edison Review and Acceptance 12-1
12.1.3 Data Base Report 12-1
12.1.4 Con Edison Supplied Data 12-2
12.2 Design Data Freeze 12-3
12.3 Data Not Used by the Seller 12-3
12.4 Specification Data 12-3

13.0 SIMULATOR HARDWARE 13-1
13.1 General Requirements 13-1
13.1.1 Building Services 13-2
13.1.2 Building Design Constraints 13-2
13.1.3 General Wiring and Electrical 13-2
13.2 Protection 13-4
13.2.1 Emergency Alarm Panel 13-4
13.2.2 Emergency Alarm and Protection Systems 13-5
13.2.2.1 Manual Emergency Power Off Switches 13-5
13.2.2.2 Fire Detection System 13-5
13.2.2.3 Water Detection and High Humidity System 13-5
13.2.2.4 Primary Power Source Monitoring 13-6
13.2.3 Automatic Simulator Shutdown 13-6
13.2.4 Emergency Simulator Shutdown 13-7
13.3 Simulator Control Room 13-8
13.3.1 Panel Hardware 13-8

13.3.2 Control Room Boards and Panels 13-9
13.3.2.1 Structure 13-9
13.3.2.2 Lighting 13-9
13.3.2.3 Finish 13-9
13.3.2.4 Design Constraints 13-10
13.3.3 General Electrical 13-10
13.3.3.1 Stimulated Instrumentation and Equipment 13-10
13.3.3.2 Wiring Terminations 13-10
13.3.3.3 Physical Protection 13-11
13.3.3.4 Wire Runs 13-11
13.3.3.5 Terminal Blocks 13-11
13.3.3.6 Ground Bus 13-12
13.3.3.7 Breakers 13-12
13.3.3.8 Keep-Alive Voltage 13-12
13.3.3.9 Relays 13-13
13.4 Maintenance Accessibility 13-13
13.5 Hardware Design Reviews 13-13

14.0 SIMULATOR ELECTRICAL AND ELECTRONIC EQUIPMENT 14-1
14.1 Simulation Computer Complex 14-1
14.1.1 Computer Complex Functional Requirements 14-1
14.1.2 Computer Complex Hardware, Development and Programmer Terminals 14-2
14.1.3 Instructor Station Hardware 14-4
14.1.3.1 Main Instructor Station 14-4
14.1.3.2 Remote Instructor Station 14-5
14.1.2.3 Wireless Remote Control Device 14-6
14.1.3.4 Instructor's Station Program Development System 14-6
14.1.4 Spare Capacities 14-7
14.1.4.1 Processor Time 14-7
14.1.4.2 Main Memory 14-7
14.1.4.3 Secondary Memory - On-line 14-8
14.2 System Interface Equipment 14-8
14.2.1 Real Time I/O 14-8
14.2.1.1 Digital Inputs 14-9
14.2.1.2 Digital Outputs 14-9
14.2.1.3 Analog Inputs 14-9
14.2.1.4 Analog Output 14-9
14.2.1.5 Synchroscope Output 14-10
14.2.1.6 Other Special I/O Devices 14-10
14.2.2 Display Interfaces 14-10
14.2.3 Distributed System Interface Spare (Analog & Digital Input and Output) 14-10
14.2.4 Computer Peripheral Device Interface (Printers, CRTs, Etc.) 14-11
14.3 Communications Equipment 14-11
14.4 Power Equipment 14-11
14.4.1 Power Source 14-11
14.4.2 AC Power Distribution 14-12
14.4.3 DC Power Supply 14-12
14.4.4 DC Power Distribution 14-12
14.4.5 Fault Interrupt Protection 14-12
14.4.6 Equipment Energized Indication 14-12
14.5 Protection of Equipment 14-13

15. PLANT COMPUTER SYSTEMS 15-1
15.1 General 15-1
15.1.1 Proteus/DRMS Simulation 15-1
15.1.2 Plant Proteus 15-2
15.1.2.1 General 15-2
15.1.2.2 Configuration 15-2
15.1.2.3 Software 15-3
15.1.2.4 Data Base 15-3
15.1.3 Plant Digital Radiation Monitoring System 15-3
15.1.3.1 General 15-3
15.1.3.2 Configuration 15-3
15.1.3.3 Software 15-4
15.2 Proteus Simulation 15-5
15.2.1 Data Acquisition and Input Processing 15-5
15.2.2 Dedicated Push Button Tasks 15-8
15.2.3 Trends/Logs/Groups 15-10
15.2.3.1 Real-Time Trends 15-10
15.2.3.2 History Trending 15-11
15.2.3.3 Group Display/Assign/Review 15-11
15.2.3.4 Logging 15-11
15.2.3.5 Group Logs 15-12
15.2.4 Point Details and Review 15-12
15.2.5 Alarm Monitoring 15-12
15.2.6 Miscellaneous Functions 15-13
15.2.6.1 Update Time/Date/Rods 15-13
15.2.6.2 Change Transform Time Constants 15-13
15.2.6.3 Redundant Measurements Check 15-13
15.2.6.4 Rod Position Supervision 15-14
15.2.6.5 Primary Plant Performance 15-14
15.2.6.6 Delta flux 15-14
15.2.6.7 Boron Follow 15-15
15.2.6.8 Watch Load Follow 15-15
15.2.6.9 Xenon Follow 15-15
15.2.6.10 Xenon Predict 15-16
15.2.6.11 Heatup/Cooldown Rate Review 15-16
15.2.6.12 Reactor Coolant System Leak Rate 15-16
15.2.6.13 Set point Monitoring 15-17
15.2.6.14 Incore Thermocouple Map 15-17
15.2.7 Historical Data Storage & Retrieval 15-17
15.2.8 CRT Colors 15-17
15.2.8.1 Color Definitions 15-18
15.2.8.2 Color System Differences 15-18
15.2.8.3 Proteus/DRMS Colors 15-18
15.2.9 Proteus Database 15-20
15.3 DRMS Simulation 15-21
15.3.1 DRMS Operator Console Interface Functions 15-21
15.3.1.1 DRMS Channel Data and Alarm Displays 15-21
15.3.1.1.1 Plant Overview Display 15-22
15.3.1.1.2 Bar-Graph Time Trend Display 15-22
15.3.1.1.3 Line-Graph Time Trend Display 15-23
15.3.1.1.4 Group Monitoring Display 15-23
15.3.1.1.5 Monitor Information Display 15-24

15.3.1.1.6 Channel Information Display 15-24
15.3.1.1.7 Alarm Listing Display 15-25
15.3.1.2 DRMS Remote Control Operations 15-26
15.3.1.2.1 Monitor Remote Control Functions 15-26
15.3.1.2.2 Manual 8-Hour Shift Turnover and Review 15-26
15.3.1.3 DRMS System Database Examine/Modify Functions 15-27
15.3.1.3.1 Historical Channel Average Data 15-27
15.3.1.3.2 Add/Delete Monitor 15-28
15.3.2 DRMS Support Software 15-28
15.3.2.1 DRMS Historical Data Storage 15-29
15.3.2.1.1 Initial Conditions 15-29
15.3.2.1.2 Real Time Data Storage and Retrieval 15-29
15.3.2.2 DRMS Alert, Alarm, and Return Message Generation 15-29
15.3.2.2.1 Messages to CRTs and Line printers 15-30
15.3.2.2.2 Interface to Annunciators 15-30
15.3.2.3 DRMS System Error and Recovery Messages 15-30
15.3.2.4 DRMS Database 15-31
15.4 Simulator Application Software 15-32
15.4.1 Introduction of Malfunctions 15-32
15.4.2 Establishing Initial Conditions 15-32
15.4.3 Backtrack 15-32
15.4.4 Freeze 15-33
15.4.5 Fast Time and Slow Time Operation 15-33
15.5 Man/Machine Interface 15-34
15.6 General Software 15-36
15.6.1 Executive Software 15-36
15.6.2 System Maintenance Software 15-37
15.6.2.1 Data Base Generator/Editor 15-37
15.6.2.2 CRT Display Generator/Editor 15-38
15.7 System Resource Utilization 15-38
15.8 Additional Hardware 15-39
15.9 Safety Assessment System Stimulation 15-39

16.0 SYSTEMS AND SUPPORT SOFTWARE 16-1
16.1 Computer Seller Operating System Software Requirements 16-1
16.2 Executive Software Requirements 16-3
16.3 Computer Seller's Utility Software 16-4
16.4 Computer Seller Supplied Diagnostics 16-5
16.5 Test and Maintenance Program Requirements 16-6
16.6 Engineering Support and Data Processing Programs 16-7
16.7 Instructor Station Applications Programs 16-8

17.0 PLANT SIMULATION SOFTWARE 17-1
17.1 General Requirements 17-1
17.2 Exclusions 17-5
17.2.1 General Exclusions 17-5
17.2.2 Software Exclusions 17-5
17.3 Performance Criteria and Modeling Approach 17-6
17.3.1 General Performance Criteria and Software Organization 17-6
17.3.2 Overall Simulation Requirements 17-7
17.3.3 Fluid Systems Modeling Requirements 17-9
17.3.4 Turbine and Electrical Equipment Simulation Requirements 17-11

17.3.5 Reactor Core and Related Systems Criteria 17-13
17.3.5.1 Reactor Core Physics 17-14
17.3.5.2 Reactor Core Fuel Failure 17-15
17.3.5.3 Reactor Thermal-hydraulics 17-15
17.3.5.4 Reactor Coolant System and Steam Generator 17-16
17.3.6 Primary Containment System 17-17
17.3.7 Steady-State and Transient Operation Criteria 17-17
17.3.7.1 Steady-State Operation 17-17
17.3.7.2 Transient Operation 17-19
17.4 Simulation Fidelity 17-20
17.4.1 General 17-20
17.4.2 Component Fidelity 17-20
17.4.3 Operational Fidelity 17-20
17.4.4 Retuning Fidelity 17-22

18.0 SIMULATOR CONTROL SYSTEM 18-1
18.1 General 18-1
18.2 Physical Characteristics of the Main Instructor Station 18-1
18.3 Functional Features of the Main Instructor Station 18-2
18.3.1 General 18-3
18.3.2 Specific 18-4
18.3.2.1 Startup and shutdown of the simulator: 18-4
18.3.2.2 Hardware Operability Test Control: 18-5
18.3.2.3 Reset/Initial Condition Control: 18-5
18.3.2.4 Freeze/Run Control: 18-6
18.3.2.5 Snapshot Feature: 18-7
18.3.2.6 Backtrack Feature: 18-7
18.3.2.7 Replay Feature: 18-8
18.3.2.8 Malfunction Control: 18-8
18.3.2.9 Instructor Directed Actions Control: 18-12
18.3.2.10 Annunciator and Alarm Control: 18-13
18.3.2.11 Computer-Aided Exercise Program (CAEP): 18-13
18.3.2.12 Trainee Performance Review (TPR): 18-14
18.3.2.13 Simulator Time Modes Control (slow time, fast time, real t 18-15
18.3.2.14 Control Room Device Override: 18-15
18.3.2.15 Transient Plot Capability: 18-15
18.3.2.16 Time Mark Control: 18-16
18.3.2.17 Monitor Parameter Control: 18-16
18.3.2.18 Instrument Noise Disable: 18-16
18.3.2.19 Computer Fault Alarm: 18-16
18.3.2.20 Master Simulator Control Room Audible Alarm Disable, Test, Acknowledge, and Reset: 18-16
18.3.2.21 Emergency Power Off: 18-17
18.3.2.22 Instructor Station Video Hard Copy: 18-17
18.3.2.23 Telephone and Communications Equipment as defined in Section 14. 18-17
18.3.2.24 Re-boot and program load function for the SAS computer(s) after loss of power, as explained in Section 15. 18-17
18.3.2.25 Recorder Power Off. 18-17
18.3.2.26 Rod Control Reset Bypass. 18-17
18.4 Instructor Hand Held Remote Control Device 18-17
18.5 Support Functions 18-18
18.6 Configuration Management System 18-19

18.7 Auto-Testing 18-19

19.0 SIMULATOR INITIAL CONDITIONS 19-1
19.1 General Information 19-1
19.2 Initial Condition Generation 19-1
19.3 Special IC's 19-2
19.4 Initial Conditions To Be Generated For Testing 19-2
19.5 Initial Condition Procedures 19-2
19.6 Initial Condition Reset Capability 19-2

20.0 MALFUNCTIONS AND INSTRUCTOR DIRECTED ACTIONS 20-1
20.1 Malfunction Philosophy 20-1
20.2 Malfunction Requirements 20-3
20.2.1 Preliminary Identification of Component Level Failures 20-3
20.2.2 Preliminary Identification of System Level Failures 20-8
20.3 Instructor Directed Actions 20-9
20.3.1 Local Operator Actions 20-9
20.3.2 Environmental Effects 20-9
20.3.3 Plant Performance Changes 20-10
20.3.4 Lineup Function 20-10

21.0 OPTIONS 21-1
21.1 Take Out Options 21-1
21.1.1 Take Out Option 1 - Con Edison Supplied Simulation Computer Complex 21-1
21.2 Add-on Options 21-1
21.2.1 Add-on Option 1 - Training of Additional Personnel 21-1
21.2.2 Add-on Option 2 - Spare Simulation Computer 21-1
21.2.3 Add-on Option 3 - Recorder Pen Lift Feature 21-1
21.2.4 Add-on Option 4 - Control Room Communications System 21-2
21.2.5 Other add-on options as recommended by the Seller 21-2

ATTACHMENT E2-B

Physical Fidelity Procedure
&
Sample Data Sheets