Table 4.1-3

Frequencies for Equipment Tests

		Check	Frequency	Maximum Time Between Tests
1.	Control Rods	Rod drop times of all control rods	Refueling # Interval	*
2.	Control Rods	Movement of at least 10 steps in any one direction of all control rods	Every 31 days during reactor critical operations	*
3.	Pressurizer Safety Valves	Setpoint	Refueling # Interval	*
4.	Main Steam Safety Valves	Setpoint	Refueling # Interval	*
5.	Containment Isolation System	Automatic Actuation	Refueling Interval	*
6.	Refueling System Interlocks	Functioning	Each refueling shutdown prior to refueling operation	Not Applicable
7.	Diesel Fuel Supply	Fuel Inventory	Weekly	10 days
8.	Turbine Steam Stop, Control Valves	Closure	**	**
9.	Cable Tunnel Ventilation Fans	Functioning	Monthly	45 days

* See Specification 1.9.

** The turbine steam stop and control valves shall be tested at a frequency determined by the methodology presented in WCAP-11525 "Probabilistic Evaluation of Reduction in Turbine Valve Test Frequency", and in accordance with established NRC acceptance criteria for the probability of a missile ejection incident at IP-2. In no case shall the test interval for these valves exceed one year.

9402140164 940125
PDR ADOCK 05000247
P PDR

Table 4.1-1

Minimum Frequencies for Checks, Calibrations and Tests of Instrument Channels

	Channel Description	Check	Calibrate	Test	Remarks
20.	Boric Acid Make-up Flow Channel	N.A.	R	N.A.	
21a.	Containment Sump and Recirculation Sump Level (Discrete)	S	R#	R#	Discrete Level Indication Systems.
21b.	Containment Sump, Recirculation Sump and Reactor Cavity Level (Continuous)	S	R#	R#	Continuous Level Indication Systems.
21c.	Reactor Cavity Level Alarm	N.A.	R#	R#	Level Alarm System
21d.	Containment Sump Discharge Flow	S	R	M	Flow Monitor
21e.	Containment Fan Cooler Condensate Flow	S	R#	M*	
22a.	Accumulator Level	S	R#	N.A.	
22b.	Accumulator Pressure	S	R#	N.A.	
23.	Steam Line Pressure	S	R#	Q	
24.	Turbine First Stage Pressure	S	R#	Q	
25.	Reactor Trip Logic Channel Testing	N.A.	N.A.	M[1]	
26.	Deleted				

* Monthly visual inspection of condensate weirs only.