


GSI-191
PWROG Resolution Efforts

April 15, 2010

Amir Shahkarami
Chairman PWROG Executive Committee
Senior VP Exelon, Site VP Braidwood
Exelon Nuclear



GSI-191 Timeline



Resolution Actions

- A highly conservative, deterministic approach was developed to address GSI-191
- Plant modifications were based on the application of conservative tests and methods
- All PWR licensees have replaced their strainers and implemented numerous design and operational enhancements
- GSI-191 is no longer a safety issue for PWRs

Summary of Actions

- Median size of new screens is 4,000 ft²
 - On average, 32 times larger than original screens
- Additional design modifications include:
 - Replacement of fibrous insulation with Reflective Metallic
 - Changes to alternate buffering agents
 - Flow diversions and debris interceptors
 - Downstream modifications
- Enhanced operational and emergency procedures

Current Status

- Actions in last 24 months focused on attempts to respond to NRC review questions
- Efforts to remove overly conservative assumptions and view holistically have been unsuccessful
- A determination of reasonable assurance of compliance with current regulations is possible now
- Further plant modifications will not improve safety

Recommended Actions

- Permit application of GDC-4 exclusion of Leak-Before-Break qualified piping to local debris generation
- Industry margin recovery efforts will continue
- Continue efforts to develop models and analysis methods based on prototypical tests and research

NRC Commissioner Briefing on GSI-191 Resolution Status

April 15, 2010

David A. Heacock

President and Chief Nuclear Officer
Dominion Nuclear

Dominion GL 04-02 Status

- North Anna
- Project complete
- Surry
- RAI response complete; minor modifications pending
- Millstone
- RAI response ongoing
- Kewaunee
- RAI response ongoing


GSI-191 / North Anna Timeline

- 2003/4 Containment walkdowns
- 07/05 Decision to abandon active strainer - install passive strainer
- 09/05 Response to GL 2004-02 due
- 11/05 AECL chosen as strainer vendor

GSI-191 / North Anna Timeline

- 2005-07 Containment reanalysis/LAR
- 2007-08 Chemical effects testing
- 2007/08 NRC corrective action and chemical effects audits
- 05/2009 NRC NAPS acceptance letter
- ~07/2010 NRC SER for in-vessel effects

NAPS-1 GSI-191 Containment Sump Strainer



Comparison of Before/After NAPS Strainer Surface Area

Unit/System	Original Design Strainer Area (approximate)	Newly Installed Strainer Area (approximate)	Percent Increase
NAPS Unit 1 RS	168 ft ² (common)	4400 ft ²	~3800 %
NAPS Unit 1 LHSI		2000 ft ²	
NAPS Unit 2 RS	168 ft ² (common)	4400 ft ²	~3750 %
NAPS Unit 2 LHSI		1900 ft ²	

Obstacles to Success

- Evolving, plant-specific R&D effort
- Multiple licensees - few vendors
- Lack of / ill-defined and evolving acceptance criteria
- Unrealistic regulatory schedules
- Unrealistic regulatory resource impact estimate

Keys to Success

- Commitment of project team
- Insights from NRC audits
- Selection of research-oriented vendor
- Adequate containment floor space

Conclusions

- Generic issues are R&D projects and rarely adhere to pre-ordained regulatory schedules
- Implementation of requirements prior to specification of acceptance criteria is counterproductive and ineffective
- Reasonable levels of conservatism provide reasonable assurance of safety

The Southern Nuclear GSI-191 Perspective


April 15, 2010

Jeff Gasser


Executive VP & CNO – Southern Nuclear

The SNC GSI-191 Perspective


New Screens - Fall 2006 Spring 2007



The SNC GSI-191 Perspective



Vogtle GSI-191 Timeline



The SNC GSI-191 Perspective

Where We Stand Today

- News sump screens 1250% - 1400% increase
- New injection needle valves and/or flow orifices to increase flow reliability (downstream effects)
- Removed problematic micro-porous insulation
- Reasonable assurance of safety exists

The SNC GSI-191 Perspective

Summary

- Required to design, build and test simultaneously before acceptance criteria established
- Cumulative effect of conservative assumptions
- Reasonable Assurance
- Further modifications result in significant worker radiation dose with no appreciable safety benefit
- GDC-4 allows closure now and maintains consistency with current design assumptions

GSI-191 Resolution Actions

- Industry Actions have resolved safety implications of GSI-191
- Commission action is needed to attain closure with no further undue worker exposure
- Current regulations (GDC-4) provide means to resolve remaining issues without further delay
- Commission action to direct the staff to allow licensee use of GDC-4 as one of the acceptable means of closing GSI-191



Generic Safety Issue 191, PWR Sump Performance

Michael Scott

Chief, Safety Issue Res. Branch

Office of Nuclear Reactor Regulation

April 15, 2010

Agenda

- **GSI-191 – Status of Completion**
- **Path Forward**
- **BWR Strainer Activities**
- **Conclusions**

GSI-191 – Status of Completion

- **Purpose – demonstrate compliance with 10 CFR 50.46(b)(5), long-term core cooling**
- **Many safety improvements**
- **Much larger ECCS strainers**
- **Some removing fibrous insulation**
- **Strainer test protocols generally acceptable**

NRC Staff Actions

- **Executed multi-year integrated plan - frequent revisions**
- **Issued guidance in 2004 and 2008**
- **Detailed reviews of submittals - some issues largely resolved**
- **Resolved all strainer performance issues for over half of PWRs**

Actions Remaining

- **Goal is issue closure in 2010**
- **Need to resolve issues for remaining plants**
- **In-vessel effects**
- **Some licensee test/evaluation methods not technically justified**
- **Additional modifications possible**

Path Forward

- **Test strainer performance using approach acceptable to staff**
- **Make plant configuration match tested one within two cycles**
- **Open to proposed alternatives, not to delay final completion**

Improvements Implemented

- **Enhanced communication among NRC staff, licensees, and vendors**
- **New review approach to balance conservatisms and uncertainties or potential nonconservatism**
- **Facilitated sharing of lessons learned among licensees**

BWR Strainer Activities

- **BWR ECCS strainer performance evaluated in 1990s**
- **Enlarged strainers**
- **So BWRs in better place now than PWRs were at start of GSI-191**
- **But some subjects need work and regulatory review**

BWR Strainer Activities (Continued)

- **Owners Group implementing evaluation plan**
- **Starting to see some slips in dates for planned actions**
- **Staff monitoring carefully for need to take additional measures**
- **Lessons learned from GSI-191**

Conclusions

- **PWR licensees have made many safety improvements**
- **Some challenges remain**
- **Goal is issue closure in 2010**
- **Implementing GSI-191 lessons learned in evaluating BWR strainer performance**

Acronyms

- **BWR – boiling water reactor**
- **ECCS – emergency Core Cooling System**
- **GL – generic letter**
- **GSI – generic safety issue**
- **PWR – pressurized water reactor**