

Facility: BRUNSWICK		Date of Exam: APRIL 2010															
Tier	Group	RO K/A Category Points											SRO-Only Points				
		K 1	K 2	K 3	K 4	K 5	K 6	A 1	A 2	A 3	A 4	G *	Total	A2	G*	Total	
1. Emergency & Abnormal Plant Evolutions	1	4	3	3	N/A			4	3	N/A			3	20	3	4	7
	2	1	1	1	N/A			2	1	N/A			1	7	1	2	3
	Tier Totals	5	4	4	N/A			6	4	N/A			4	27	4	6	10
2. Plant Systems	1	3	2	3	2	2	3	3	3	2	1	2	26	2	3	5	
	2	1	1	1	1	1	1	2	1	1	1	1	12	0	1	2	3
	Tier Totals	4	3	4	3	3	4	5	4	3	2	3	38	3	5	8	
3. Generic Knowledge and Abilities Categories		1		2		3		4		10		1	2	3	4	7	
		3		3		2		2				2	2	1	2		

1. Ensure that at least two topics from every applicable K/A category are sampled within each tier of the RO and SRO-only outlines (i.e., except for one category in Tier 3 of the SRO-only outline, the "Tier Totals" in each K/A category shall not be less than two).
2. The point total for each group and tier in the proposed outline must match that specified in the table. The final point total for each group and tier may deviate by ± 1 from that specified in the table based on NRC revisions. The final RO exam must total 75 points and the SRO-only exam must total 25 points.
3. Systems/evolutions within each group are identified on the associated outline; systems or evolutions that do not apply at the facility should be deleted and justified; operationally important, site-specific systems that are not included on the outline should be added. Refer to ES-401, Attachment 2, for guidance regarding the elimination of inappropriate K/A statements.
4. Select topics from as many systems and evolutions as possible; sample every system or evolution in the group before selecting a second topic for any system or evolution.
5. Absent a plant-specific priority, only those K/As having an importance rating (IR) of 2.5 or higher shall be selected. Use the RO and SRO ratings for the RO and SRO-only portions, respectively.
6. Select SRO topics for Tiers 1 and 2 from the shaded systems and K/A categories.
7. *The generic (G) K/As in Tiers 1 and 2 shall be selected from Section 2 of the K/A Catalog, but the topics must be relevant to the applicable evolution or system.
8. On the following pages, enter the K/A numbers, a brief description of each topic, the topics' importance ratings (IRs) for the applicable license level, and the point totals (#) for each system and category. Enter the group and tier totals for each category in the table above; if fuel handling equipment is sampled in other than Category A2 or G* on the SRO-only exam, enter it on the left side of Column A2 for Tier 2, Group 2 (Note # 1 does not apply). Use duplicate pages for RO and SRO-only exams.
9. For Tier 3, select topics from Section 2 of the K/A catalog, and enter the K/A numbers, descriptions, IRs, and point totals (#) on Form ES-401-3. Limit SRO selections to K/As that are linked to 10 CFR 55.43.

KA	NAME / SAFETY FUNCTION:	IR		K1 K2 K3 K4 K5 K6 A1 A2 A3 A4 G												TOPIC:					
		RO	SRO																		
295001AK1.03	Partial or Complete Loss of Forced Core Flow Circulation / 1 & 4	3.6	4.1	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Thermal limits.....
295003AA2.05	Partial or Complete Loss of AC / 6	3.9	4.2	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Whether a partial or complete loss of A.C. power has occurred.....
295004AA1.02	Partial or Total Loss of DC Pwr / 6	3.8	4.1	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Systems necessary to assure safe plant shutdown.....
295005AA1.07	Main Turbine Generator Trip / 3	3.3	3.3	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	A.C. electrical distribution.....
295006AK1.02	SCRAM / 1	3.4	3.7	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Shutdown margin.....
295016G2.4.1	Control Room Abandonment / 7	4.6	4.8	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	Knowledge of EOP entry conditions and immediate action steps.
295018AA1.02	Partial or Total Loss of CCW / 8	3.3	3.4	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	System loads.....
295019G2.2.37	Partial or Total Loss of Inst. Air / 8	3.6	4.6	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Ability to determine operability and/or availability of safety related equipment
295021AA2.02	Loss of Shutdown Cooling / 4	3.4	3.4	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	RHR/shutdown cooling system flow
295023AK3.03	Refueling Acc Cooling Mode / 8	3.3	3.6	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Ventilation isolation.....
295024G2.2.37	High Drywell Pressure / 5	3.6	4.6	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Ability to determine operability and/or availability of safety related equipment

KA	NAME / SAFETY FUNCTION:	IR	K1	K2	K3	K4	K5	K6	A1	A2	A3	A4	G	TOPIC:
		RO	SRO											
295025EA2.05	High Reactor Pressure / 3	3.4	3.6	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Decay heat generation.....
295026EA1.01	Suppression Pool High Water Temp. / 5	4.1	4.1	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Suppression pool cooling.....
295028EK3.05	High Drywell Temperature / 5	3.6	3.7	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Reactor SCRAM.....
295030EK2.09	Low Suppression Pool Wtr Lvl / 5	2.5	2.8	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	SPDS/ERIS/CRIDS/GDS: Plant-Specific.....
295031EK3.03	Reactor Low Water Level / 2	4.1	4.4	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Spray cooling.....
295037EK1.03	SCRAM Condition Present and Power Above APRM Downscale or Unknown / 1	4.2	4.4	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Boron effects on reactor power (SBLC).....
295038EK2.12	High Off-site Release Rate / 9	3.5	3.8	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Feedwater leakage control: BWR-6.....
600000AK2.01	Plant Fire On Site / 8	2.6	2.7	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Sensors / detectors and valves
700000AK1.02	Generator Voltage and Electric Grid Disturbancecs	3.3	3.4	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Over-excitation

KA	NAME / SAFETY FUNCTION:	IR		K1 K2 K3 K4 K5 K6 A1 A2 A3 A4 G											TOPIC:				
		RO	SRO																
295008AK1.01	High Reactor Water Level / 2	3.0	3.2	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Moisture carryover.....
295014AA2.03	Inadvertent Reactivity Addition / 1	4.0	4.3	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Cause of reactivity addition.....
295015AK3.01	Incomplete SCRAM / 1	3.4	3.7	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Bypassing rod insertion blocks.....
295020G2.4.1	Inadvertent Cont. Isolation / 5 & 7	4.6	4.8	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	Knowledge of EOP entry conditions and immediate action steps.
295032EK2.02	High Secondary Containment Area Temperature / 5	3.6	3.7	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Secondary containment ventilation.....
295033EA1.05	High Secondary Containment Area Radiation Levels / 9	3.9	4.0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Affected systems so as to isolate damaged portions....
295035EA1.01	Secondary Containment High Differential Pressure / 5	3.6	3.6	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Secondary containment ventilation system.....

KA	NAME / SAFETY FUNCTION:	IR		K1 K2 K3 K4 K5 K6 A1 A2 A3 A4 G													TOPIC:							
		RO	SRO																					
203000K1.01	RHR/LPCI: Injection Mode	2.8	2.8	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Condensate storage and transfer system: Plant-Specific
205000G2.4.21	Shutdown Cooling	4.0	4.6	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	Knowledge of the parameters and logic used to assess the status of safety functions
206000K4.02	HPCI	3.9	4	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	System isolation: BWR-2,3,4
209001K3.01	LPCS	3.8	3.9	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Reactor water level
209001K3.03	LPCS	2.9	3.0	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Emergency generators
211000K1.01	SLC	3.0	3.3	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Core spray line break detection: Plant-Specific
211000K1.09	SLC	3.2	3.4	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Core spray system: Plant-Specific
212000K2.01	RPS	3.2	3.3	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	RPS motor-generator sets
215003A2.02	IRM	3.5	3.7	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	IRM inop condition
215004K5.03	Source Range Monitor	2.8	2.8	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Changing detector position
215005A2.05	APRM / LPRM	3.5	3.6	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Loss of recirculation flow signal

KA	NAME / SAFETY FUNCTION:	IR	K1	K2	K3	K4	K5	K6	A1	A2	A3	A4	G	TOPIC:
		RO	SRO											
215005A2.07	APRM / LPRM	3.2	3.4	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Recirculation flow channels flow mismatch
217000A1.01	RCIC	3.7	3.7	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	RCIC flow
217000A1.04	RCIC	3.6	3.6	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Reactor pressure
218000K3.01	ADS	4.4	4.4	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Restoration of reactor water level after a break that does not depressurize the reactor when required
223002A3.03	PCIS/Nuclear Steam Supply Shutoff	2.5	2.8	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	SPDS/ERIS/CRIDS/GDS: Plant-Specific
239002A4.04	SRVs	4.3	4.3	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	Suppression pool temperature
259002K6.04	Reactor Water Level Control	3.1	3.1	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Reactor feedwater flow input
261000A3.01	SGTS	3.2	3.3	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	System flow
262001K6.01	AC Electrical Distribution	3.1	3.4	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	D.C. power
262001K6.02	AC Electrical Distribution	3.6	3.9	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Off-site power
262002G2.4.3	UPS (AC/DC)	3.7	3.9	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Ability to identify post-accident instrumentation.

KA	NAME / SAFETY FUNCTION:	IR		K1 K2 K3 K4 K5 K6 A1 A2 A3 A4 G											TOPIC:				
		RO	SRO																
263000K2.01	DC Electrical Distribution	3.1	3.4	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Major D.C. loads
264000A1.01	EDGs	3.0	3.0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Lube oil temperature
300000K5.13	Instrument Air	2.9	2.9	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Filters
400000K4.01	Component Cooling Water	3.4	3.9	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Automatic start of standby pump

KA	NAME / SAFETY FUNCTION:	IR	K1	K2	K3	K4	K5	K6	A1	A2	A3	A4	G	TOPIC:
		RO	SRO											
201001A1.03	CRD Hydraulic	2.9	2.8	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	CRD system flow
201002K6.01	RMCS	2.5	2.6	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Select matrix power
201006K5.01	RWM	3.3	3.7	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Minimize clad damage if a control rod drop accident (CRDA) occurs: P-Spec(Not-BWR6)
214000A3.04	RPIS	3.5	3.8	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	RCIS: Plant-Specific
216000K2.01	Nuclear Boiler Inst.	2.8	2.8	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Analog trip system: Plant-Specific
230000A1.06	RHR/LPCI: Torus/Pool Spray Mode	3.3	3.3	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Suppression pool level
234000A4.02	Fuel Handling Equipment	3.4	3.7	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	Control rod drive system
259001A2.06	Reactor Feedwater	3.2	3.2	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Loss of A.C. electrical power
272000K3.05	Radiation Monitoring	3.5	3.7	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Offgas system
288000K1.04	Plant Ventilation	2.6	2.6	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Applicable component cooling water system: Plant-Specific
290002G2.4.46	Reactor Vessel Internals	4.2	4.2	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Ability to verify that the alarms are consistent with the plant conditions.

KA NAME / SAFETY FUNCTION: IR K1 K2 K3 K4 K5 K6 A1 A2 A3 A4 G TOPIC:

RO SRO

290003K4.01 Control Room HVAC 3.1 3.2 System initiations/reconfiguration: Plant-Specific

KA	NAME / SAFETY FUNCTION:	IR		K1 K2 K3 K4 K5 K6 A1 A2 A3 A4 G												TOPIC:			
		RO	SRO																
G2.1.27	Conduct of operations	3.9	4	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Knowledge of system purpose and or function.
G2.1.31	Conduct of operations	4.6	4.3	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Ability to locate control room switches, controls and indications and to determine that they are correctly reflecting the desired plant lineup.
G2.1.39	Conduct of operations	3.6	4.3	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Knowledge of conservative decision making practices
G2.2.15	Equipment Control	3.9	4.3	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Ability to determine the expected plant configuration using design and configuration control documentaion
G2.2.25	Equipment Control	3.2	4.2	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Knowledge of the bases in Technical Specifications for limiting conditions for operations and safety limits.
G2.2.39	Equipment Control	3.9	4.5	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Knowledge of less than one hour technical specification action statements for systems.
G2.3.14	Radiation Control	3.4	3.8	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Knowledge of radiation or contamination hazards that may arise during normal, abnormal, or emergency conditions or activities
G2.3.6	Radiation Control	2.0	3.8	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Ability to approve release permits
G2.4.1	Emergency Procedures/Plans	4.6	4.8	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Knowledge of EOP entry conditions and immediate action steps.
G2.4.9	Emergency Procedures/Plans	3.8	4.2	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Knowledge of low power / shutdown implications in accident (e.g. LOCA or loss of RHR) mitigation strategies.

KA	NAME / SAFETY FUNCTION:	IR		K1 K2 K3 K4 K5 K6 A1 A2 A3 A4 G											TOPIC:				
		RO	SRO																
295006G2.2.22	SCRAM / 1	4.0	4.7	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Knowledge of limiting conditions for operations and safety limits.
295021AA2.03	Loss of Shutdown Cooling / 4	3.5	3.5	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Reactor water level		
295023G2.4.46	Refueling Acc Cooling Mode / 8	4.2	4.2	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Ability to verify that the alarms are consistent with the plant conditions.		
295026EA2.03	Suppression Pool High Water Temp. / 5	3.9	4.0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Reactor pressure.....			
295028EA2.05	High Drywell Temperature / 5	3.6	3.8	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Torus/suppression chamber pressure: Plant-Specific...			
295038G2.2.42	High Off-site Release Rate / 9	3.9	4.6	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Ability to recognize system parameters that are entry-level conditions for Technical Specifications			
600000G2.2.37	Plant Fire On Site / 8	3.6	4.6	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Ability to determine operability and/or availability of safety related equipment			

KA	NAME / SAFETY FUNCTION:	IR	K1	K2	K3	K4	K5	K6	A1	A2	A3	A4	G	TOPIC:
		RO	SRO											
295008AA2.05	High Reactor Water Level / 2	2.9	3.1	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Swell.....
295014G2.1.19	Inadvertent Reactivity Addition / 1	3.9	3.8	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Ability to use plant computer to evaluate system or component status.
295029G2.1.7	High Suppression Pool Wtr Lvl / 5	4.4	4.7	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Ability to evaluate plant performance and make operational judgments based on operating characteristics, reactor behavior and instrument interpretation.

KA	NAME / SAFETY FUNCTION:	IR		K1 K2 K3 K4 K5 K6 A1 A2 A3 A4 G											TOPIC:				
		RO	SRO																
212000A2.12	RPS	4.0	4.1	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Main turbine stop control valve closure		
217000G2.4.8	RCIC	3.8	4.5	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Knowledge of how abnormal operating procedures are used in conjunction with EOPs.		
239002G2.2.25	SRVs	3.2	4.2	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Knowledge of the bases in Technical Specifications for limiting conditions for operations and safety limits.			
262002G2.1.23	UPS (AC/DC)	4.3	4.4	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Ability to perform specific system and integrated plant procedures during all modes of plant operation.			
300000A2.01	Instrument Air	2.9	2.8	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Air dryer and filter malfunctions			

KA	NAME / SAFETY FUNCTION:	IR	K1	K2	K3	K4	K5	K6	A1	A2	A3	A4	G	TOPIC:
		RO	SRO											
204000G2.2.3	RWCU	3.8	3.9	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	(multi-unit license) Knowledge of the design, procedural and operational differences between units.
214000A2.03	RPIS	3.6	3.9	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Overtravel/in-out
233000G2.4.34	Fuel Pool Cooling/Cleanup	4.2	4.1	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Knowledge of RO tasks performed outside the main control room during an emergency and the resultant operational effects

KA	NAME / SAFETY FUNCTION:	IR		K1 K2 K3 K4 K5 K6 A1 A2 A3 A4 G												TOPIC:		
		RO	SRO	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>		<input type="checkbox"/>	<input type="checkbox"/>
G2.1.42	Conduct of operations	2.5	3.4	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Knowledge of new and spent fuel movement procedures
G2.1.5	Conduct of operations	2.9	3.9	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Ability to locate and use procedures related to shift staffing, such as minimum crew complement, overtime limitations, etc.
G2.2.15	Equipment Control	3.9	4.3	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Ability to determine the expected plant configuration using design and configuration control documentaion
G2.2.22	Equipment Control	4.0	4.7	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Knowledge of limiting conditions for operations and safety limits.
G2.3.11	Radiation Control	3.8	4.3	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Ability to control radiation releases
G2.4.17	Emergency Procedures/Plans	3.9	4.3	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Knowledge of EOP terms and definitions.
G2.4.35	Emergency Procedures/Plans	3.8	4.0	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Knowledge of local auxiliary operator tasks during emergency and the resultant operational effects

DRAFT

ES-301

Administrative Topics Outline

Form ES-301-1

Facility: <u>Brunswick</u>		Date of Examination: <u>April 2010</u>
Examination Level: RO <input type="checkbox"/> SRO-I <input checked="" type="checkbox"/>		Operating Test Number: <u>DRAFT</u>
Administrative Topic (see Note)	Type Code*	Describe activity to be performed
Conduct of Operations	R, M, D	Core Performance Check - APRM parameter check
Conduct of Operations	R, M, P R, P	Drywell Average Air Temperature Calculation (SRO-I only) Refueling Technical Specifications
Equipment Control	R, D	RCC Clearance
Radiation Control	R, M	Calculation of Stay Times
Emergency Procedures/Plan	R, M	(SRO-I only) Emergency Action Level Determinations
NOTE: All items (5 total) are required for SROs. RO applicants require only 4 items unless they are retaking only the administrative topics, when all 5 are required.		
* Type Codes & Criteria: (C)ontrol room, (S)imulator, or Class(R)oom (D)irect from bank (≤ 3 for ROs; ≤ 4 for SROs & RO retakes) (N)ew or (M)odified from bank (≥ 1) (P)revious 2 exams (≤ 1 ; randomly selected)		

DRAFT

1126

Conduct of Operations

Core Performance Check RO/SROI R, M, D

K/A 2.1.7 Ability to evaluate plant performance and make operational judgments based on operating characteristics, reactor behavior, and instrument interpretation

This is a banked modified Administrative JPM that will require the examinee perform 1PT-01.11 recognizing APRM GAF adjustment required. Modified to allow performance in a classroom setting.

Conduct of Operations

Drywell Average Air Temperature Calculation (RO Only) R, M, P

K/A 2.1.20 Ability to interpret and execute procedure steps

This is a modified classroom Administrative JPM that will require the examinee perform OPT-16.2. Modified to allow performance in a classroom setting and values changed resulting in different answer. This JPM was used on one of the last two NRC exams (November 08) and was randomly selected for this exam.

Conduct of Operations

Evaluate Refueling Technical Specifications (SRO-I Only) R, P

K/A 2.1.40 Knowledge of refueling administrative requirements

This is a banked classroom Administrative JPM that requires the examinee to evaluate Technical Specifications to allow removal of Shutdown Cooling from operation during Refueling operations. This JPM was used on one of the last two NRC exams (April 08) and was randomly selected for this exam.

Equipment Control

RCC Clearance R, D

K/A 2.2.13 Knowledge of tagging and clearance procedures

This is a banked classroom Administrative JPM that will require the examinee identify Clearance Boundaries for RBCCW Pump 2C by completing Attachment 4 of OPS-NGGC-1301.

Radiation Control

Calculation of Stay Times R, M

K/A 2.3.7 Ability to comply with radiation work permit requirements during normal and abnormal conditions

This is a modified banked classroom Administrative JPM that will require the examinee to determine the total dose accumulated for two workers and if any Brunswick administrative dose limitations will be exceeded. Modified the values and area resulting in a different answer.

Emergency Procedures/Plan

Emergency Action Level Determinations (SRO-I Only) R, M

K/A 2.4.29 Knowledge of the Emergency Plan

This is a modified banked classroom Administrative JPM that will require the examinee to classify an emergency per PEP-02.1. Modified to incorporate NEI 99-01 EALs.

Facility: <u>Brunswick</u>		Date of Examination: <u>April 2010</u>
Exam Level: RO <input checked="" type="checkbox"/> SRO-I <input checked="" type="checkbox"/>		Operating Test No.: <u>DRAFT</u>
Control Room Systems [@] (8 for RO); (7 for SRO-I)		
System / JPM Title	Type Code*	Safety Function
a. Bypass a LPRM	S, D	7
b. Restart RBHVAC with Failure to Isolate	S, A, D	9
c. Place B Loop RHR in SPC IAW hard card – NSW header failure	S, A, P	5
d. Place HPCI in Pressure control	S, A, P	3
e. 230 kV Bus in Service	S, D	6
f. Secure Main Turbine with failure of PCB to open	S, A, N	4
g. SULCV in service after scram	S, L, D	2
h. (RO only) Restart CRD	S, D	1
In-Plant Systems [@] (3 for RO/SRO-I)		
i. LEP-01 Alternate Coolant Injection, SLC w/ Fire Water	R, M, E	2
j. Fire Pump power supply to alternate	D	8
k. SAMA DG	R, P, M, E	6
<p>[@] All RO and SRO-I control room (and in-plant) systems must be different and serve different safety functions; all 5 SRO-U systems must serve different safety functions; in-plant systems and functions may overlap those tested in the control room.</p>		
* Type Codes	Criteria for RO / SRO-I / SRO-U	
(A)lternate path	4-6 / 4-6 / 2-3	
(C)ontrol room		
(D)irect from bank	≤ 9 / ≤ 8 / ≤ 4	
(E)mergency or abnormal in-plant	≥ 1 / ≥ 1 / ≥ 1	
(EN)gineered safety feature	- / - / ≥ 1 (control room system)	
(L)ow-Power / Shutdown	≥ 1 / ≥ 1 / ≥ 1	
(N)ew or (M)odified from bank including 1(A)	≥ 2 / ≥ 2 / ≥ 1	
(P)revious 2 exams	≤ 3 / ≤ 3 / ≤ 2 (randomly selected)	
(R)CA	≥ 1 / ≥ 1 / ≥ 1	
(S)imulator		

a. Bypass a LPRM

215005 A2.02

Ability to predict impacts on APRM and based on those predictions, use procedures to correct, control or mitigate consequences of those abnormal conditions.

This is a banked simulator JPM that will require the examinee to bypass an LPRM.

b. Restart RBHVAC with Failure to Isolate

288000 A3.01

Ability to monitor Plant Ventilation System automatic isolation/initiation signals in the control room

This is a modified banked simulator JPM that will require the examinee to restart the RB Ventilation system. As an alternate path when the fans are started the high radiation condition alarm re-occur and the examinee will have to isolate the system.

c. Place B Loop RHR in SPC IAW hard card – NSW header failure

219000 A4.12

Ability to manually operate and/or monitor in the control room: suppression pool temperature.

This is a banked simulator JPM that will require the examinee to place the B loop of RHR into SPC. As an alternate path they will have to use the conventional service water header. This is an engineered safety feature JPM. This JPM was used on one of the last two NRC exams (Nov. 08) and was randomly selected for this exam.

d. Place HPCI in Pressure Control

295025 EA1.04

Ability to operate and/or monitor the following as they apply to High Reactor Pressure: HPCI (plant specific)

This is a banked simulator JPM that will require the examinee to place HPCI into pressure control mode of operation. As an alternate path there is a exhaust diaphragm failure. This JPM was used on one of the last two NRC exams (Nov. 08) and was randomly selected for this exam.

e. 230 kV Bus in Service

262001 A4.01

Ability to manually operate and/or monitor in the control room: All breakers and disconnects (including available switchyard)

This is a banked simulator JPM that will require the examinee energize 230 kV Bus 2B.

f. Main Turbine Shutdown

245000 A2.01

Ability to predict impacts of a turbine trip on the Main Turbine Generator and Auxiliary Systems; and based on those predictions, use procedures to correct, control or mitigate consequences of those abnormal conditions.

This is a new simulator JPM that will require the examinee to shutdown the turbine. As an alternate path one of the PCBs will fail to auto open and the examinee will have to open the PCB manually.

g. SULCV in service after scram

295001 A4.02

Ability to manually start/control a RFP in the control room.

This is a banked low power simulator JPM that will require the examinee to place the Startup Level Control Valve in service, restart a Reactor Feed Pump and restore RPV water level.

h. (RO only) Restart CRD

201001 A2.01

Ability to predict the impact of a CRD pump trip on the CRD Hydraulic System and use procedures to correct, control or mitigate the consequences.

This is a banked simulator JPM that will require the examinee to restart the CRD system.

i. LEP-01 Alternate Coolant Injection, SLC w/ Fire Water

295031 EA1.08

Ability To Operate/Monitor Alternate Coolant Injection Systems.

This is an in-plant JPM that will require the examinee to simulate aligning Fire Water to the SLC pumps for alternate coolant injection per LEP-01. This JPM is performed in the RCA. This JPM was modified due to a plant modification incorporating a new connector to the fire water hose.

j. Fire Pump power supply to alternate

286000 A1.05

Ability to predict and/or monitor changes in parameters associated with operating the Fire Protection System controls including: System lineups.

This is a banked in-plant JPM that will require the examinee to simulate the transfer of the Electric Fire Pump to its alternate power supply and start the Electric Fire Pump locally.

k. SAMA DG

295003 AA1.02

Ability to Operate and/or Monitor Emergency Generators as it applies to a Station Blackout

This is a banked in-plant JPM that will require the examinee to simulate aligning the SAMA Diesel to a battery charger. This JPM is performed in the RCA. This JPM was modified due to a plant modification to the equipment. This JPM contains actions for a Station Blackout.