

# BWROG ECCS SS Resolution Plan

#### Steve Scammon, Committee Chairman

#### June 3, 2010 NRC Bethesda, MD



June 3, 2010

# Introductions

BWROG Executive Committee Vice Chairman: Dave Czufin BWROG Chairman: Ted Schiffley Committee Chairman: Steve Scammon GEH: Craig Nichols, Program Manager Rob Whelan, ECCS SS Project Manager Alion Science and Technology: Rob Choromokos

# Background

NRC requested that BWROG address new ECCS suction strainer concerns (April 10, 2008 letter from John A. Grobe)

BWROG formed ECCS Suction Strainer Committee to address:

- NRC issues for BWRs not previously addressed by URG
- Lessons learned from PWROG response to GSI-191

#### **Recent Activities**

Fuel test planning – concurrence from GEH, AREVA, and Westinghouse

Walkdowns – results being processed from at least ten walkdowns

GEH LOCA analysis – switching to SAFER methodology

# **Recent Activities (continued)**

- Based on PWROG lessons learned, initiated development of comprehensive Project Plan
- Project plan final review complete May 5, 2010
- Industry executive review and funding approved May 18, 2010

# **Overall Philosophy**

- 1. Communicate closely with NRC and obtain confirmation before attempting major work
- 2. Complete most testing and analysis at a generic level
- 3. Update URG and complete any plantspecific follow-up after generic work is done

# **Four Technical Areas**

Debris Source Term Strainer Headloss Downstream Effects – Components Downstream Effects – Fuel

# Plan: Source Term (1 of 3)

Current methodology to be validated:

- 1. Debris characteristics (3Q 2011)
- 2. ZOI adjustment for air jet testing (4Q 2010)
- 3. Debris transport / erosion characteristics (3Q 2011)
- 4. Near-field effects and scaling (4Q 2011)
- 5. Spherical ZOI (2Q 2011)

# Plan: Source Term (2 of 3)

To be developed using plant-specific inputs:

- 1. Assessment of coatings (2Q 2011)
- 2. Assessment of ZOI for Protective Coatings (1Q 2011)
- 3. Latent debris
  - a. Debris characteristics "85/15" (3Q 2011)
  - b. Debris Load (3Q 2011)

# Plan: Source Term (3 of 3)

- To be developed via testing and analysis Chemical Effects
  - 1. Material dissolution correlations and verification (4Q 2011)
  - 2. Headloss testing in chemical environment (2Q 2013)

# **Plan: Strainer Headloss**

- 1. Review previous testing dataset (3Q 2012)
- 2. Perform additional vendor-specific tests or revise correlations if needed (3Q 2012)
- 3. Validate original thin bed assumptions through testing and report results (1Q 2014)

#### Plan: Downstream Effects -Components

- Develop debris bypass source term (4Q 2010)
- 2. Utilize methods similar to WCAP 16406 on components (1Q 2012)
- 3. Perform generic component evaluations (2Q 2014)
- 4. Provide plant-specific follow-up actions if needed (1Q 2015)

# **Plan: Downstream Effects - Fuel**

- 1. Establish fuel test parameters (GEH LTR1, 3Q 2010; AREVA / Westinghouse 1Q 2012 LTR2-3)
- 2. Single facility and procedures to be used by all fuel vendors for testing (4Q 2012)
- 3. Conduct testing with 3 fuel vendors (3Q 2013)
- 4. Share final results of testing with formal submittal (Addendum to LTR1,2,3, 2Q 2014)

# **Final Resolution**

#### URG Supplement (1Q 2015)

- Incorporates all generic work
- Provides guidance for plant-specific work

Plant-specific follow-up as required 2015+

# Conclusion

BWROG has re-planned the project Funding has been committed Executive backing for project plan Continued interaction with NRC is essential