



# **Construction Reactor Oversight Process Development**

Tom Kozak

Construction Assessment  
and Enforcement Branch  
Office of New Reactors

# **cROP Development**

- **The NRC cROP WG's interaction with the NEI cROP Task Force and other stakeholders has resulted in substantive agreement on the following:**
  - **Issue Screening**
  - **cROP framework, including cornerstone objectives, attributes, and areas to measure**
  - **Two Significance Determination Process Approaches**
    - **Risk Matrix and Flowchart (details still need to be developed)**

# **cROP Development**

- **Issue Screening**
  - **Inspection Manual Chapter (IMC) 0613 provides issue screening guidance**
  - **cROP WG will recommend to modify the issue screening process by incorporating applicable portions of the IMC 0612 approach for operating reactors**
  - **Recommendations will include the use of the terms ‘issue of concern’ and ‘performance deficiencies’ and the use of the traditional enforcement screening tool**

# cROP Development

**Draft Significance Determination Process Matrix**

<b>Degree of Non-Conformance</b>	<b>High</b>	White	Yellow	Red
	<b>Medium</b>	Green	White	Yellow
	<b>Low</b>	Green	Green	White
	<b>Minimal</b>	Green	Green	Green
		<b>Insignificant</b>	<b>Significant</b>	<b>Very Significant</b>
		<b>Risk Significance</b>		

## **Degree of Non-conformance**

- Evaluate the finding using the following factors
  - Quality of Construction
  - Extent of Onsite Review Prior to Identification
  - Corrective Actions

## Degree of Non-conformance

### Quality of Construction

#### 3 points

- Major repairs, replacement or rework needed to meet AC
- Reanalysis involving reduction of margin to design limits
- Failure on retest or re-inspection due to same failure mode

#### 2 points

- Limited repair, replacement or rework needed to meet AC
- Reanalysis needed to meet AC
- Acceptable on retest or re-inspection

#### 1 point

- No repair, replacement or rework needed to meet AC
- Program or process corrective actions sufficient

## **Degree of Non-conformance**

### Extent of Onsite Review Prior to Identification

3 points

- ITAAC Closure Letter Submitted to NRC
- ITAAC acceptance criteria reviewed and accepted by 1<sup>st</sup> line QA/QC

2 points

- Turned over for ITAAC testing or pre-op testing
- In process work has been completed to determine AC met

1 point

- Identified during fabrication, installation, or QC phase
- Fabrication/QC test completed successfully

## Degree of Non-conformance

### Corrective Actions

3 points

- Recurrence of similar significant problem due to ineffective corrective actions
- Recurrence of SCAQ due to ineffective corrective actions

2 points

- Untimely corrective actions for similar problem
- Recurrence of a similar, less significant problem
- Problem caused by repetitive personnel error

1 point

- Problem not previously identified
- Problem identified by planned tests, inspections, or reviews



# Degree of Non-conformance

## Determination of Degree of Non-conformance

### Summary of points

High: 9 points

Medium: 7 - 8 points

Low: 5 - 6 Points

Minimal: 4 points or less

# Risk Significance

- Very Significant
  - Finding associated with targeted ITAAC in a risk significant system
- Significant
  - Finding associated with remaining targeted ITAAC
- Insignificant
  - All other applicable findings

# Risk Significant System


- To be determined for each design based on Fussel-Vessely and Risk Achievement Worth Values
- Possible Systems for AP1000
  - PMS (Protection and Safety Monitoring System)
  - DC (DC Power)
  - IRWST (In Containment Refueling Water Storage Tank)
  - CMT (Core Makeup Tank)
  - ACC (Accumulators)

# cROP Development

## Draft Significance Determination Process Matrix

<b>Degree of Non-Conformance</b>	<b>High</b>	White	Yellow	Red
	<b>Medium</b>	Green	White	Yellow
	<b>Low</b>	Green	Green	White
	<b>Minimal</b>	Green	Green	Green
		<b>Insignificant</b>	<b>Significant</b>	<b>Very Significant</b>
		<b>Risk Significance</b>		

# Draft Construction SDP Flow Chart



## **cROP Development**

- IMC 2505 Provides Construction Assessment Program Guidance including Construction Action Matrix
- cROP Working Group Will Recommend Some Changes to Construction Assessment Program
  - **Continuous assessment of all inspection results, including inspections conducted of applicants**
  - **Implementation of formal, semi-annual assessment program upon issuance of license and initiation of sufficient activities such that a formal assessment would be meaningful**

# cROP Development

- Next Steps
  - Performance Indicator Approach
  - Construction Action Matrix Inputs
  - Safety Culture Approach
  - Assessment Program Evaluation
  - Transition to ROP

# cROP Development

- Federal Register Notice Issued on June 24 Requesting Feedback on cROP Development
- Category II Meeting With NEI cROP Task Force on July 14 and August 5
- Internal White Paper With Working Group Recommendations August 6
- Category III Meeting on August 19
- Notation Vote SECY Paper Issued By October 29
- Commission Meeting December 9