Simulated ITAAC Closure and Verification Demonstration

NRO Public Workshop December 09, 2010

Mahmoud Jardaneh, PE NRO/DCIP/CTSB/CIT



Scope



Six ITAAC selected from AP1000 design

- ITAAC 2.1.02.07a.i, RCS Harsh Environment Type Test
- ITAAC 2.2.01.04a.ii, Containment System Impact Testing
- ITAAC 2.2.02.01, Passive Containment Cooling Functional Arrangement
- ITAAC 2.2.03.08c.i, Injection Line Flow Resistance Testing and Analysis
- ITAAC 2.6.03.08, DC System Fault Current Analysis
- ITAAC 3.7.01, Design Reliability Assurance Program

Four Stages

- ITAAC Performance and NRC Assessment
- ITAAC Closure Verification
- Exercise Workshop
- Lessons Learned

Milestones Update



• 7/29/10	Public Meeting - Kickoff		
8/19/10 8/19/	Public Meeting - Progress Update		
• 9/14/10	Simulated Inspection at Vogtle 3&4		
• 9/22/10	Simulated Inspection at Westinghouse HQ		
• 10/07/10	Public Meeting - Progress Update		
• 1 0/27/10	Region II issues Integrated Inspection Report		
• 11/03/10	Public Meeting - D-RAP ITAAC		
• 11/10/10	Closed Meeting - Surge in ITAAC evaluation		
• 11/11/10	Westinghouse/Southern submit ICL to NRC		
• 12/09/10	Public Meeting – Progress Update		
• 1/17/11	NRC Completes ITAAC Closure Verification		
• 1/27/11	Public Meeting – Demonstration Workshop		
• 3/31/11	Public Meeting – Lessons Learned		

Stage 2



- Objectives for Stage 2
 - Demonstrate the infrastructure that will be used for ITAAC closure verification
 - Demonstrate the communication paths for ITAAC closure letters (ICLs) and additional inspection requests
 - Evaluate the surge in ICL submittals expected in the last year of construction
 - Simulate the issuance of a Federal Register Notice (FRN)
- Progress for Stage 2
 - 9 simulated ICLs have been submitted
 - ICLs are being evaluated
 - Issued Technical Assistance Request (TAR) to Region II CCI for additional inspection
 - FRN template and checklist are being developed
 - Evaluated the surge in ICL submittals

ICL Review Approach



- Learning Experience for NRC and Industry
- 22 ICL examples including the generic template in Appendix D of NEI 08-01 were used
- Reviewed independently and then discussed in a group setting with OGC and some members with significant construction experience

ICL Review – Initial Feedback



- Organize IDB to match the ITA
- List the ITAAC closure package table of contents in the references instead of simply listing "ITAAC closure package"
- Include the applicable pre-op tests, drawings, etc. in the reference list
- When larger ITAAC is divided into multiple ITAAC, appropriate notification/documentation in the ICL will aid in ITAAC closure
- References did not match between ICL contents and reference lists

ITAAC 2.1.02.07a.i (10E)



- NEI 08-01 Template: D-1
- Acceptance Review: Accepted
- Closure Verification Review: Not Verified
 - Many test descriptions reside in App. 3D of AP1000, but which tests were used?
 - App 3D should be listed in the references
 - Equipment qualification reports should be included in references

ITAAC 2.2.01.04a.ii (6F)



- NEI 08-01 Template: D-7
- Acceptance Review: Accepted
- Closure Verification Review: Verified

ITAAC 2.2.02.01 (14A)



- NEI 08-01 Template: D-18
- Acceptance Review: Not Accepted
 - ICL did not list the walk down procedure in the reference list
 - Detailed check lists and observations are not referenced as indicated on D-18 template
- Closure Verification: Not Verified
 - The referenced table and figure in the IDB did not list or show all the sensors and valves as required in the acceptance criteria
 - The IDB did not indicate that each component is in its proper functional or logical (for I&C) relation to the system

ITAAC 2.2.03.08c.i-01 (6D)



- NEI 08-01 Template: D-1
- Acceptance Review: Not Accepted
 - A performance test and a calculation were performed, but not referenced
- Closure Verification Review: Not Verified
 - Letter refers to flow loss instead of head loss
 - Test methodology is not sufficiently detailed
 - Staff could not determine if the value of uncertainty adjustment for the flow resistance calculation was appropriate for test conditions

ITAAC 2.2.03.08c.i-02 (06D)



- NEI 08-01 Template: D-1
- Acceptance Review: Not Accepted
 - Missing information requires detailed test statement on accumulator for the "sub-ITA"
- Closure Verification Review: Not Verified
 - Insufficient Information ICL needs to reference pre-op testing if applicable or provide sufficient details on the "performance test" and associated QA and controls

ITAAC 2.2.03.08c.i-03 (06D)



- NEI 08-01 Template: D-1
- Acceptance Review: Accepted
- Closure Verification Review: Not Verified
 - Insufficient Information ICL needs to reference preop testing if applicable or provide sufficient details on the "performance test" and associated QA and controls

ITAAC 2.2.03.08c.i-04 (06D)



- NEI 08-01 Template: D-13
- Acceptance Review: Accepted
- Closure Verification Review: Not Verified
 - IDB should call out how the elements of the ITA coincide with the actual SSCs tested (temp. water supply, which valves were opened, etc.)
 - Level of detail is insufficient. Contrary to template,
 IDB did not call out valve numbers, drain numbers,
 specific reports, and the actual pre-operational test

ITAAC 2.6.03.08 (08F)



- NEI 08-01 Template: D-1
- Acceptance Review: Accepted
- Closure Verification Review: Verified

ITAAC 3.7.00.01 (16F)



- NEI 08-01 Template: D-10
- Acceptance Review: Not Accepted
 - References are missing
 - Headings are not consistent with template
- Closure Verification Review: Verified

Summary



- Industry should assess comments to discuss in detail on January 27
- Refer to NEI 08-01 templates when drafting ICLs
- Consider NRO project managers who will review the ICLs
- ICL must stand alone to inform the public

ICL ML Numbers



_	\sim	\mathbf{A}	$\cap 7$:
	· / /		11/21
		-(<i>) </i>	07a.i
		· · · · ·	\mathbf{o}

ML103190452

ML103190443

ML103190445

ML103190442

• 2.2.03.08c.i-02

ML103190446

• 2.2.03.08c.i-03

ML103190477

• 2.2.03.08c.i-04

ML103190448

• 2.6.03.08

ML103190450

• 3.7.00.01

ML103190451