



Entergy Nuclear Operations, Inc.  
Vermont Yankee  
320 Governor Hunt Rd  
Vernon, VT 05354  
Tel 802 257 7711

Michael J. Colomb  
Site Vice President

BVY 11-024

March 18, 2011

ATTN: Document Control Desk  
U.S. Nuclear Regulatory Commission  
Washington, DC 20555-0001

SUBJECT: Deviation from BWRVIP-25 Inspection Requirements  
Vermont Yankee Nuclear Power Station  
Docket No. 50-271  
License No. DPR-28

REFERENCES: 1. BWR Vessel and Internals Project, BWR Core Plate Inspection and Flaw Evaluation Guidelines (BWRVIP-25), EPRI Report TR-107284, December 1996

Dear Sir or Madam:

BWR Vessel and Internals Project (BWRVIP), BWR Core Plate Inspection and Flaw Evaluation Guidelines (BWRVIP-25) requires that 50% of the core plate rim hold-down bolts of BWR/2-5 plants without repair wedges be examined by enhanced visual testing (EVT-1) from below the core plate (or by ultrasonic testing (UT) from above core plate once the technique is developed). However, it was determined that the bolts cannot be inspected by UT due to configuration issues and it has been concluded that an EVT-1 exam does not provide meaningful results. Accordingly, a technical justification for deviation from the BWRVIP guidance was developed to delay implementation of the BWRVIP-25 inspection requirements until the BWRVIP-25 guidance is revised.

The Vermont Yankee Nuclear Power Station (VYNPS) technical justification included an analysis that found that the bolting has a relatively low susceptibility to cracking and a very high flaw tolerance, and that postulated flaws would not grow to a size that significantly reduces the bolt preload over the life of the plant. Even if significant cracking did occur in the bolting, redundant structural components will prevent adverse displacement of the core plate. Furthermore, even with the extremely conservative assumptions of failures of both the bolting and the redundant hardware, thereby potentially preventing all control rods from inserting into the core, the standby liquid control system could be used to bring the reactor to a safe shutdown.

The BWRVIP is currently working on developing revised guidance for the core plate bolts and expects to complete that work, including gaining NRC approval of the revised guidance, by December 31, 2015. VYNPS will implement the revised inspection guidance for the core plate bolts following NRC approval. Given the low likelihood that the function of the core plate will be compromised by bolting failures, there is little risk in postponing UT and EVT-1 inspections of the bolts until such time as the BWRVIP develops revised guidance.

A00,  
MRR

VYNPS currently inspects 25% of the top of the core plate hold down bolts every other refueling outage in accordance with the VYNPS Reactor Vessel Internals (RVI) Inspection Program using the VT-3 method. VYNPS will continue to inspect 25% of the core plate hold down bolts every other refueling outage using the VT-3 method in accordance with the RVI Program until the inspection guidance of BWRVIP-25 is revised by the Electric Power Research Institute and approved by the NRC.

This letter is being transmitted for information only and VYNPS is not requesting any action from the NRC staff.

A new regulatory commitment is provided in Attachment 1. Should you have any questions or require additional information concerning this submittal, please contact Mr. Robert Wanczyk at 802-451-3166.

Sincerely,



[MJC/PLC]

Attachment: 1. List of Regulatory Commitments

cc: Mr. William M. Dean, Regional Administrator  
U.S. Nuclear Regulatory Commission, Region 1  
475 Allendale Road  
King of Prussia, PA 19406-1415

Mr. Robert Kuntz, Senior Project Manager  
U.S. Nuclear Regulatory Commission  
One White Flint North 11F1  
11555 Rockville Pike  
Rockville, MD 20852-2738

Mr. James S. Kim, Project Manager  
Office of Nuclear Reactor Regulation  
U.S. Nuclear Regulatory Commission  
Mail Stop O8C2A  
Washington, DC 20555-0001

Mr. Jonathan G. Rowley, Project Manager  
Office of Nuclear Reactor Regulation  
U.S. Nuclear Regulatory Commission  
Mail Stop O12 G11  
Washington, DC 20555-0001

cc (cont'd):

Mr. Matthew Mitchell, Branch Chief  
Office of Nuclear Reactor Regulation  
U.S. Nuclear Regulatory Commission  
Mail Stop O9 H6  
Washington, DC 20555-0001

USNRC Resident Inspector

Ms. Elizabeth Miller, Commissioner  
VT Department of Public Service  
112 State Street – Drawer 20  
Montpelier, Vermont 05620-2601

**Attachment 1**

**Vermont Yankee Nuclear Power Station  
License No. DPR-28 (Docket No. 50-271)**

**List of Regulatory Commitments**

### List of Regulatory Commitments

This table identifies actions discussed in this letter for which Entergy commits to perform. Any other actions discussed in this submittal are described for the NRC's information and are **not** commitments.

COMMITMENT	TYPE (Check one)		SCHEDULED COMPLETION DATE (If Required)
	ONE-TIME ACTION	CONTINUING COMPLIANCE	
<p>VYNPS will continue to inspect 25% of the core plate hold down bolts every other refueling outage using the VT-3 method in accordance with the VYNPS Rector Vessel Internals Inspection Program until BWRVIP-25 is revised and approved by the NRC.</p> <p>Following NRC approval, VYNPS will implement the revised BWRVIP-25 inspection guidance for the core plate bolts.</p>	x		<p>Following NRC approval of revised BWRVIP-25 guidance in accordance with BWRVIP-94 Rev 1 guidelines.</p>