



NOTES:  
 1. FOR GENERAL NOTES, SEE 18N0700-X1  
 2. CONCRETE SHALL BE CLASS 301.5 SFM FOR WALLS AND CLASS 301.5 SFM FOR SLABS.  
 3. A MINIMUM OF 3 DAYS IS REQUIRED BETWEEN ADJACENT POURS.  
 4. FLOORS ARE TO HAVE A STEEL TROWELED MONOLITHIC FINISH. SEE CONSTRUCTION SPECIFICATION 5-22.  
 5. POOR METAL LINESUS STEEL EMBEDDED PARTS, SEE 4CW0324-X2.  
 6. CONST JT BETWEEN PADS AT EL 590.25 AND ROOF SLAB AT EL 690.0 TO BE A BONDED CONST JT, IE, THE CONTACT SURFACE AT EL 693.0 IS TO BE CLEAN AND INTENTIONALLY ROUGHENED.  
 7. PIP EMBEDDED PARTS, PIPES AND CONDUITS, SEE MECHANICAL & ELECTRICAL DRAWINGS.  
 Docket # 50-43814-99  
 Control # 820908002  
 Date 8/23/82 of Document  
 REGULATORY DOCKET FILE

| NO. | DATE    | DESCRIPTION  | BY  | CHKD |
|-----|---------|--|-----|------|
| 6   | 8/23/82 | ADDED 3 WALLS 300'-0" DIA, CUT SECT PER 21-10-82           | ... | ...  |
| 5   | 8/21/82 | DRILL 3" HOLES PER ECN 321, 322, 323 IN WALLS PER 21-10-82 | ... | ...  |
| 4   | 8/17/82 | REVISED PARAPET B/LINE WALL, ADDED SECTION CUT IN 2        | ... | ...  |
| 3   | 8/17/82 | REVISED WALL ELEVATIONS, ADDED WALLS                       | ... | ...  |
| 2   | 8/17/82 | REVISED CONST JTS & WALL ELEVATIONS, PER 21-10-82          | ... | ...  |
| 1   | 8/17/82 | RELEASED COMP DWGS, MINOR REVISIONS, ADDED CONST JT        | ... | ...  |

CONTROL BUILDING  
 UNITS 1 & 2  
 CONCRETE  
 ROOF SLAB EL 689.0  
 OUTLINE

BELLEFONTE NUCLEAR PLANT  
 TENNESSEE VALLEY AUTHORITY  
 DIVISION OF ENGINEERING DESIGN

SUBMITTED: [Signature]  
 RECOMMENDED: [Signature]  
 APPROVED: [Signature]

KNOXVILLE 12-16-75 882 4CW0472-XI-1.0

POOR ORIGINAL

820 908 00 18