



UNITED STATES
NUCLEAR REGULATORY COMMISSION
WASHINGTON, D.C. 20555-0001

May 6, 2011

Mr. David A. Heacock
President and Chief Nuclear Officer
Virginia Electric and Power Company
Innsbrook Technical Center
5000 Dominion Boulevard
Glen Allen, VA 23060-6711

SUBJECT: SURRY POWER STATION, UNIT NO. 2 (SURRY 2) - UPCOMING STEAM
GENERATOR TUBE INSERVICE INSPECTION (TAC NO. ME6146)

Dear Mr. Heacock:

Inservice inspections of steam generator (SG) tubes play a vital role in assuring SG tube integrity. A telephone conference call has been arranged for May 12, 2011, at 1:00 p.m. with members of your staff to discuss the ongoing results of the SG tube inspections to be conducted during the current Surry 2 spring refueling outage. This call will occur after the majority of the tubes have been inspected, but before the SG inspection activities have been completed. Enclosed is a list of discussion points to facilitate this call.

The U.S. Nuclear Regulatory Commission (NRC) staff will document a summary of the conference call, including any material that you provide to the NRC staff in support of the call.

Should you have any questions you can contact me at 301-415-1438.

Sincerely,

A handwritten signature in cursive script, appearing to read "Karen Cotton".

Karen Cotton, Project Manager
Plant Licensing Branch II-1
Division of Operating Reactor Licensing
Office of Nuclear Reactor Regulation

Docket No. 50-281

Enclosure:
SG Tube Inspection Discussion Points

cc w/encl: Distribution via Listserv

STEAM GENERATOR TUBE INSPECTION DISCUSSION POINTS

The following discussion points have been prepared to facilitate the conference call arranged with the licensee to discuss the results of the steam generator (SG) tube inspections to be conducted during the current Surry Power Station, Unit No. 2 spring refueling outage. This conference call is scheduled to occur towards the end of the planned SG tube inspections, but before the unit completes the inspections and repairs, May 12, 2011, at 1:00 p.m..

The U.S. Nuclear Regulatory Commission (NRC) staff plans to document a summary of the conference call as well as any material that is provided in support of the call.

1. The NRC staff requests clarification on the definition of over-expansion that was provided in your response dated April 25, 2011, Agencywide Documents Access and Management System, Accession No. ML11124A009 to a request for additional information regarding the End of Cycle 22 Steam Generator Tube Inspection.
2. Discuss any trends in the amount of primary-to-secondary leakage observed during the recently completed cycle.
3. Discuss whether any secondary side pressure tests were performed during the outage and the associated results.
4. Discuss any exceptions taken to the industry guidelines.
5. For each SG, provide a description of the inspections performed including the areas examined and the probes used (e.g., dents/dings, sleeves, expansion-transition, U-bends with a rotating probe), the scope of the inspection (e.g., 100% of dents/dings greater than 5 volts and a 20% sample between 2 and 5 volts), and the expansion criteria.
6. For each area examined (e.g., tube supports, dent/dings, sleeves, etc), provide a summary of the number of indications identified to-date for each degradation mode (e.g., number of circumferential primary water stress corrosion cracking indications at the expansion transition). For the most significant indications in each area, provide an estimate of the severity of the indication (e.g., provide the voltage, depth, and length of the indication). In particular, address whether tube integrity (structural and accident-induced leakage integrity) was maintained during the previous operating cycle. In addition, discuss whether any location exhibited a degradation mode that had not previously been observed at this location at this unit (e.g., observed circumferential primary water stress corrosion cracking at the expansion transition for the first time at this unit).
7. Describe repair/plugging plans.
8. Describe in-situ pressure test and tube pull plans and results (as applicable and if available).

Enclosure

9. Discuss the following regarding loose parts:
 - what inspections are performed to detect loose parts
 - a description of any loose parts detected and their location within the SG (including the source or nature of the loose part, if known)
 - if the loose parts were removed from the SG
 - indications of tube damage associated with the loose parts
10. Discuss the scope and results of any secondary side inspection and maintenance activities (e.g., in-bundle visual inspections, feeding inspections, sludge lancing, assessing deposit loading, etc).
11. Discuss any unexpected or unusual results.
12. Provide the schedule for steam generator-related activities during the remainder of the current outage.

May 6, 2011

Mr. David A. Heacock
President and Chief Nuclear Officer
Virginia Electric and Power Company
Innsbrook Technical Center
5000 Dominion Boulevard
Glen Allen, VA 23060-6711

SUBJECT: SURRY POWER STATION, UNIT NO. 2 (SURRY 2) - UPCOMING STEAM
GENERATOR TUBE INSERVICE INSPECTION (TAC NO. ME6146)

Dear Mr. Heacock:

Inservice inspections of steam generator (SG) tubes play a vital role in assuring SG tube integrity. A telephone conference call has been arranged for May 12, 2011, at 1:00 p.m. with members of your staff to discuss the ongoing results of the SG tube inspections to be conducted during the current Surry 2 spring refueling outage. This call will occur after the majority of the tubes have been inspected, but before the SG inspection activities have been completed. Enclosed is a list of discussion points to facilitate this call.

The U.S. Nuclear Regulatory Commission (NRC) staff will document a summary of the conference call, including any material that you provide to the NRC staff in support of the call.

Should you have any questions you can contact me at 301-415-1438.

Sincerely,

/RA/ by GKulesa for

Karen Cotton, Project Manager
Plant Licensing Branch II-1
Division of Operating Reactor Licensing
Office of Nuclear Reactor Regulation

Docket No. 50-281

Enclosure:
SG Tube Inspection Discussion Points

cc w/encl: Distribution via Listserv

DISTRIBUTION:

Public	LPL2-1 r/f	RidsNrrDorlLpl2-1 Resource	RidsRgn2MailCenter Resource
RidsAcrsAcnw_MailCTR Resource		RidsNrrLAMO'Brien Resource	RidsNrrPMSurry Resource
RidsNrrDciCsgb Resource		RidsOgcRp Resource	AJohnson, NRR

ADAMS Accession No. ML11123A285

OFFICE	NRR/LPL2-1/PM	NRR/LPL2-1/LA	NRR/LPL2-1/BC	NRR/LPL2-1/PM
NAME	KCotton (JWiebe for)	MO'Brien	GKulesa	KCotton (GKulesa for)
DATE	05/05/11	05/05/11	05/06/11	05/06/11

OFFICIAL RECORD COPY