

**AEC DISTRIBUTION FOR PART 50 DOCKET MATERIAL
(TEMPORARY FORM)**

CONTROL NO: 356
FILE: INCIDENT REPORT

FROM: Wisconsin Public Svc Cop Kewaunee, Wi unsigned		DATE OF DOC 1-14-75	DATE REC'D 1-6-75	LTR XX	TWX	RPT	OTHER
TO: Mr Boyd		ORIG none signed	CC	OTHER	SENT AEC PDR <u>XX</u> SENT LOCAL PDR <u>XX</u>		
CLASS	UNCLASS XXXX	PROP INFO	INPUT	NO CYS REC'D 1	DOCKET NO: 50-305		

DESCRIPTION:
Ltr re AO #75-1 on 1-4-75 concernng the failure of the auxiliary feedwater pump to remain in operation.....

ENCLOSURES:

**DO NOT REMOVE
ACKNOWLEDGED**

PLANT NAME: Kewaunee

FOR ACTION/INFORMATION 1-14-75 ehf

BUTLER (S) W/ Copies	SCHWENCER (S) W/ Copies	ZIEMANN (S) W/ Copies	REGAN (E) W/ Copies
CLARK (S) W/ Copies	STOLZ (S) W/ Copies	DICKER (E) W/ Copies	LEAR (S) W/ Copies
PARR (S) W/ Copies	VASSALLO (S) W/ Copies	KNIGHTON (E) W/ Copies	SPEIS (S) W/ Copies
KNIEL (S) W/ Copies	PURPLE (S) W/4 Copies	YOUNGBLOOD (E) W/ Copies	

INTERNAL DISTRIBUTION

<u>REG FILE</u> AEC PDR OGC, ROOM P-506-A MUNIZING/STAFF CASE GIAMBUSSO BOYD MOORE (S) (BWR) DEYOUNG (S) (PWR) SKOVHOLT (S) GOLLER (S) P. COLLINS DENISE REG OPR FILE & REGION T.R. WILSON	<u>TECH REVIEW</u> SCHROEDER MACCARRY KNIGHT PAWLICKI SHAO STELLO HOUSTON NOVAK ROSS IPPOLITO TEDESCO LONG LAINAS BENAROYA STEELE VOLIMER	<u>DENTON</u> GRIMES GAMMILL KASTNER BALLARD SPANGLER <u>ENVIRO</u> MULLER DICKER KNIGHTON YOUNGBLOOD REGAN PROJECT LDR HARLESS	<u>LIC. ASST.</u> DIGGS (S) GEARIN (S) GOULBOURNE (S) KREUTZER (E) LEE (S) MAIGRET (S) REED (E) SERVICE (S) SHEPPARD (S) SLATER (E) SMITH (S) TEETS (S) WILLIAMS (E) WILSON (S) INGRAM (S)	<u>A/T IND</u> BRAITMAN SALTZMAN B. HURT <u>PLANS</u> MCDONALD CHAPMAN DUBE w/input E. COUPE D. THOMPSON (2) KLEGGER F. WILLIAMS
---	---	--	---	---

EXTERNAL DISTRIBUTION

1-LOCAL PDR <u>Kewaunee, WI</u> 1-TIC (ABERNATHY) 1-NSIC (BUCHANAN) 1-ASLB 1-NEWTON ANDERSON 5-ACRS SENT TO LIC. ASST. <u>Sheppard</u>	(1) (2) (10) -NATIONAL LABS 1-W. PENNINGTON, RM E-201 G.T. 1-CONSULTANTS NEWMARK/BLUME/AGBABIAN	1-PDR SAN/LA/NY 1-BROOKHAVEN NAT LAB 1-G. ULRIKSON, ORNL 1-AGMED(RUTH GUSSMAN) RM B-127 G.T. 1-J. RUNKLES, RM E-201 G.T.
---	--	--

TELEGRAM

sent 1-7-75
0855
January 6, 1974

REGULATORY DOCKET FILE COPY

Mr. Duane Boyd
Resident Inspector - U.S. ATOMIC ENERGY COMMISSION
Directorate of Regulatory Operations - Region III
Two Rivers Municipal Hospital
Two Rivers, Wisconsin

SUBJECT: Docket 50-305
Operating License DPR - 43
Abnormal Occurrence Report



In accordance with the requirements of Technical Specifications, Paragraph 6.6.2.d and 1.0d. 1 (d), we submit the following:

Report Number: 50-305/75-1

Occurrence Date: January 4, 1975

Facility: Kewaunee Nuclear Power Plant
Kewaunee, Wisconsin

Identification of Occurrence:

Failure of Auxiliary Feedwater Pump to remain in operation.


Condition Prior to Occurrence:

Reactor Critical - 75% power
Normal Operating Temperature - 547°F
Reactor Coolant System Pressure - 2220

Description of Occurrence:

Load was being reduced on the unit to a electric gross output of 220 MW. 1A Feedwater regulating valve stuck in the partially open position and a Hi-Hi steam generator level was indicated on 1A Steam Generator. Main feedwater pump 1A tripped off with the Hi-Hi Steam generator level. 1B Main Feedwater Pump was off the line due to maintenance and the breaker was tagged open. Upon receipt of the Hi-Hi level auxiliary feedwater 1B started and remained in operation. 1A Auxiliary Feed water pump started, but did not stay in operation. The switch for 1A Auxiliary Feed Water Pump was put in the start position and the pump started and remained in operation.

The steam driven Auxiliary Feed Water Pump started on Lo-Lo level in steam generator.



CP Luma