

## WISCONSIN PUBLIC SERVICE CORPORATION



P.O. Box 1200, Green Bay, Wisconsin 54305

May 12, 1978

Office of Nuclear Reactor Regulation  
U. S. Nuclear Regulatory Commission  
Washington, D. C. 20555

Attention Mr. A. Schwencer, Chief  
Operating Reactors Branch #1  
Division of Operating Reactors

Gentlemen:

Docket 50-305  
Operating License DPR-43  
Kewaunee Reload Safety Evaluation Cycle 4

Reference: Letter to Mr. James from Mr. A. Schwencer  
dated May 3, 1978

Enclosed you will find forty (40) copies of the following attachments submitted in support of our application for Amendment to the Technical Specifications concerning the operation of Cycle 4 of the Kewaunee Nuclear Power Plant.

- (1) Figure 1, page 15, of the RSE for Cycle 4 has a typographical error in it. Please insert the attached page in place of the existing page and destroy the removed page.
- (2) Attachment No. 2 provides a listing of the currently planned Physics/Startup Tests to be performed for Cycle 4 along with the acceptance criteria for each test.
- (3) Attachment No. 3 contains the response to those questions transmitted by the referenced letter concerning the RSE for Cycle 4 submitted as supplemental information in our application for change to the Technical Specifications.

781360087

A001  
1/40 \*

C 05/16/78

REGULATORY INFORMATION DISTRIBUTION SYSTEM (RIDS)  
DISTRIBUTION FOR INCOMING MATERIAL 50-305

REC: SCHWENCER A  
NRC

ORG: JAMES E W  
WI PUB SVC

DOC DATE: 05/12/78  
DATE RCVD: 05/15/78

DOCTYPE: LETTER NOTARIZED: NO

COPIES RECEIVED  
LTR 1 ENCL 40

SUBJECT:  
FORWARDING SUPPORTING DOCUMENTS AS LISTED TO APPLICANT'S APPL FOR AMEND,  
TECH SPEC PROPOSED CHANGE CONCERNING THE OPERATION OF THE RELOAD SAFETY  
EVALUATION CYCLE 4 OF SUBJECT FACILITY.

PLANT NAME: KEWAUNEE

REVIEWER INITIAL: XJM  
DISTRIBUTOR INITIAL: *mc*

\*\*\*\*\* DISTRIBUTION OF THIS MATERIAL IS AS FOLLOWS \*\*\*\*\*

NOTES:

- 1 & E - 3 CYS ALL MATERIAL
2. LAWRENCE(OELD) - 1 COPY ALL MATERIAL

GENERAL DISTRIBUTION FOR AFTER ISSUANCE OF OPERATING LICENSE.  
(DISTRIBUTION CODE A001)

FOR ACTION: BR CHIEF ~~SCHWENCER~~\*\*W/7 ENCL

INTERNAL:

REG FILE\*\*W/ENCL  
~~I & E\*\*W/3 ENCL~~  
HANAUER\*\*W/ENCL  
EISENHUT\*\*W/ENCL  
BAER\*\*W/ENCL  
EEB\*\*W/ENCL  
J. MCGOUGH\*\*W/ENCL

NRC PDR\*\*W/ENCL  
OELD\*\*LTR ONLY  
CHECK\*\*W/ENCL  
SHAD\*\*W/ENCL  
BUTLER\*\*W/ENCL  
J COLLINS\*\*W/ENCL

EXTERNAL:

LPDR'S  
KEWAUNEE, WI\*\*W/ENCL  
TIC\*\*W/ENCL  
NSIC\*\*W/ENCL  
ACRS CAT B\*\*W/16 ENCL

DISTRIBUTION: LTR 40 ENCL 39  
SIZE: 2P+7P

CONTROL NBR: 781360087

*BP*

\*\*\*\*\*

THE END

\*\*\*\*\*

U. S. Nuclear Regulatory Commission  
May 12, 1978  
Page 2

The results of the Physics/Startup tests for Cycle 4 will be made available to the Staff 45 days after startup and a formal Physics Test Report will be docketed 90 days after Cycle 4 startup.

Very truly yours,

A handwritten signature in dark ink, appearing to read "E. W. James". The signature is fluid and cursive, with the first name "E" being particularly large and stylized.


E. W. James  
Senior Vice President  
Power Supply & Engineering

sna

Attach.

FIGURE 1

CORE LOADING PATTERN  
KEWAUNEE NUCLEAR PLANT  
UNIT 1 - CYCLE 4



Region Number

KEWAUNEE NUCLEAR POWER PLANT

CYCLE 4 PHYSICS TESTS

<u>Test</u>	<u>Acceptance Criteria</u>
Boron Endpoint	
All rods out	$\pm 50$ ppm from predicted
Reference bank in	$\pm 50$ ppm from predicted
Boron Worth	None
Temperature Coefficient - ARO	$\pm 3$ pcm/ $^{\circ}$ F from predicted
RCCA reference bank worth	$\pm 10\%$ from predicted
Rod Swap	
Individual Bank Worths	$\pm 20\%$ from predicted
Total Banks Worth	$\leq 10\%$ RMS of deviation from predicted
Power Distribution Flux Maps	
Hot Zero Power	Analyze to verify measured
$\approx 75\%$ Power	Values of $F_Q^N$ , $F_H^N$ , assembly-
$\approx 90\%$ Power	wise relative power and quadrant
Full Power	to average power tilt ratios are
	within Tech Spec limits

Kewaunee Cycle 4

Peaking Factors vs. Core Height  
Sub-Case Analysis\*

<u>Height from Core Bottom (ft.)</u>	<u>Maximum F<sub>Q</sub> x Power</u>	<u>ARO F<sub>xy</sub> (z)</u>	<u>D-In F<sub>xy</sub> (z)</u>
11.7	1.123	1.465	1.665
11.2	1.610	1.435	1.617
10.6	1.779	1.435	1.594
9.7	1.925	1.435	1.580
8.8	2.037	1.435	1.580
7.9	2.057	1.435	1.580
6.9	2.033	1.440	1.592
6.0	2.018	1.454	1.610
5.1	2.019	1.468	1.627
4.1	1.993	1.479	1.641
3.2	1.985	1.483	1.648
2.3	2.038	1.470	1.636
1.3	2.016	1.435	1.592
.7	1.838	1.435	1.608
.3	1.318	1.435	1.631

\* Letter NS-CE-1749 dated April 6, 1978 from C. Eicheldinger to  
John F. Stolz, Non-Proprietary portion of Attachment 1.

The loss of flow transient for the Kewaunee Cycle 4 reload was evaluated based on a generic study for a number of similar 2 loop plants. This study was conducted to determine the effect of using the new trip reactivity curve on the loss of flow analyses. The plants used in the generic analysis were similar in those parameters which most affect the loss of flow transient, i.e., thermal power, average temperatures and system pressure. Since the original analysis had significant margin to a DNBR of 1.3, a comparison of the decrease in margin for the worst case in the generic study to the amount of margin available was made and the results of this evaluation reported. Since the RSE was filed, a detailed analysis has been done. The results of this analysis show that the minimum DNBR still meets the design basis of 1.30.

Kewaunee Nuclear Power Plant  
List of Safety Analyses

<u>Accident</u>	<u>Latest Analysis</u>
Uncontrolled RCCA Withdrawal from a Subcritical Condition	2/78 (Core 4 - RSE)
Uncontrolled RCCA Withdrawal at Power	2/78 (Core 4 - RSE)
RCC Assembly Misalignment	1/27/71 (AM7 - FSAR) 11/76 (Core 3 - RSE - Addressed Only)
CVCS Malfunction	1/27/71 (AM7 - FSAR) (2/76 - Core 2B - RSE - Addressed Only)
Startup of an Inactive RC Loop	1/27/71 (AM7 - FSAR) (2/76 - Core 2B - RSE - Addressed Only)
Excessive Heat Removal Due to FW System Malfunctions	1/27/71 (AM7 - FSAR) (2/76 - Core 2B - RSE - Addressed Only)
Excessive Load Increase Incident	1/27/71 (AM7 - FSAR) (2/76 - Core 2B - RSE - Addressed Only)
Loss of Reactor Coolant Flow	3/73 (WCAP-8903) (2/78 - Core 4 - RSE - Addressed Only)
Locked Rotor Accident	2/78 (Core 4 - RSE)
Loss of External Electrical Load	1/27/71 (AM7 - FSAR) (2/76 - Core 2B - RSE - Addressed Only)
Loss of Normal Feedwater	8/31/73 (AM33 - FSAR) (2/76 - Core 2B - RSE - Addressed Only)



Loss of AC Power to Plant Auxiliaries	8/31/72 (AM21 - FSAR) (2/76 - Core 2B - RSE - Addressed Only)
Fuel Handling Accidents	1/27/71 (AM7 - FSAR) (2/76 - Core 2B - RSE - Addressed Only)
Accidental Release - Recycle or Waste Liquid	1/27/71 (AM7 - FSAR) (2/76 - Core 2B - RSE - Addressed Only)
Accidental Release - Waste Gas	1/27/71 (AM7 - FSAR) (2/76 - Core 2B - RSE - Addressed Only)
Steam Generator Tube Rupture	1/27/71 (AM7 - FSAR) (2/76 - Core 2B - RSE - Addressed Only)
Rupture of a Steam Pipe	4/13/73 (AM28 - FSAR) (2/78 - Core 4 - RSE - Addressed Only)
Rupture of a CR Drive Mechanism Housing	2/78 (Core 4 - RSE)
Turbine Missile Damage to Spent Fuel Pool	1/4/72 (AM14 - FSAR) (2/76 - Core 2B - RSE - Addressed Only)
RC System Pipe Rupture (LOCA)	12/10/76 (AM40 - FSAR)
Loss of RC from Small Ruptured Pipes or from Cracks in Large Pipes which Actuate ECCS	4/1/75 (AM36 - FSAR)
Major RC Pipe Ruptures (LOCA)	12/10/76 (AM40 - FSAR)
Core and Internals Integrity Analysis	5/12/72 (AM17 - FSAR)
Containment Integrity Evaluations	11/8/71 (AM12 - FSAR)
Offsite Dose Consequences	8/31/72 (AM21 - FSAR)
Effects of Containment Leakage By-Passing Shield Building Annulus	1/4/72 (AM14 - FSAR)

Effects of Leakage from Residual Heat  
Removal System

6/30/72 (AM19 - FSAR)

Charcoal Filter Ignition Hazard Due to  
Iodine Adsorption

12/1/72 (AM22 - FSAR)

Generation & Disposition of Hydrogen

1/22/73 (AM23 - FSAR)

Containment Pressure Response to LOCA

33 - 10/19/73