

ACCELERATED DISTRIBUTION DEMONSTRATION SYSTEM

REGULATORY INFORMATION DISTRIBUTION SYSTEM (RIDS)

ACCESSION NBR:8806210147 DOC.DATE: 88/06/16 NOTARIZED: NO DOCKET #
 FACIL:50-305 Kewaunee Nuclear Power Plant, Wisconsin Public Servic 05000305
 AUTH.NAME AUTHOR AFFILIATION
 HINTZ,D.C. Wisconsin Public Service Corp.
 RECIP.NAME RECIPIENT AFFILIATION
 Document Control Branch (Document Control Desk)

SUBJECT: Provides addl info re ICS sys surveillance,per Proposed
 Amend 83 submitted on 871026.

DISTRIBUTION CODE: A047D COPIES RECEIVED:LTR 1 ENCL 1 SIZE: 9
 TITLE: OR Submittal: Inservice Inspection/Testing/Relief from ASME Code

NOTES:

RECIPIENT	COPIES	RECIPIENT	COPIES
ID CODE/NAME	LTTR ENCL	ID CODE/NAME	LTTR ENCL
PD3-3 LA	1 0	PD3-3 PD	5 5
GIITTER,J	1 1		
INTERNAL: ACRS	10 10	AEOD/DOA	1 1
AEOD/DSP/TPAB	1 1	ARM/DAF/LFMB	1 0
NRR/DEST/MEB 9H	1 1	NRR/DEST/MTB 9H	1 1
NUDOCS-ABSTRACT	1 1	OGC 15-B-18	1 0
<u>REG-FILE</u> 01	1 1	RES/DE/EIB	1 1
EXTERNAL: EG&G ROCKHOLD,H	1 1	LPDR	1 1
NL 007 HEMMING	1 1	NRC PDR	1 1
NSIC	1 1		

TOTAL NUMBER OF COPIES REQUIRED: LTTR 31 ENCL 28

R
I
D
S
/
A
D
D
S

R
I
D
S
/
A
D
D
S



WISCONSIN PUBLIC SERVICE CORPORATION

600 North Adams • P.O. Box 19002 • Green Bay, WI 54307-9002

June 16, 1988

10 CFR 50.90

U. S. Nuclear Regulatory Commission
ATTN: Document Control Desk
Washington, D.C. 20555

Gentlemen:

Docket 50-305
Operating License DPR-43
Kewaunee Nuclear Power Plant
Proposed Amendment No. 83 to the Kewaunee
Internal Containment Spray System Testing

Reference: Letter from D. C. Hintz (WPSC) to Document Control Desk (NRC)
dated October 26, 1987

The referenced, proposed amendment 83 (PA-83), requested that Technical Specification 4.5.a.2 (TS 4.5.a.2) be changed to clarify its intent. TS 4.5.a.2 describes the surveillance requirements for the internal containment spray (ICS) system. TS 4.5.a.2.A states:

"System tests shall be performed once every operating cycle or once every 18 months, whichever occurs first. The test shall be performed with the isolation valves in the supply lines at the containment blocked closed. Operation of the system is initiated by tripping the normal actuation instrumentation."

The proposed change would delete the last sentence of the specification. As a result of the proposed change, Kewaunee Nuclear Regulatory Commission (NRC) Project Manager requested additional information concerning ICS system surveillance. This submittal supplies the additional information.

Presently, the requirement specified by TS 4.5.a.2 is met by conducting surveillance procedure (SP) 23-095, Containment Spray System Test. During SP 23-095 the ICS isolation valves at the containment are closed and then the ICS pumps are operated near their shutoff head. Since this can lead to excessive wear and tear on the pumps, pump run time is limited to 20 seconds. The test is initiated by simultaneously pushing the two manual initiation pushbuttons located in the control room.

8806210147 880616
PDR ADOCK 05000305
P DCD

A047
11

The NRC has questioned the adequacy of this test because the manual pushbuttons are used to actuate the system. TS 4.5.a.2.A could be interpreted to require the injection of test pressure signals into the containment pressure transmitters in order to actuate the system. If this interpretation is taken, the system would have to be started a minimum of eight times to verify the operability of all containment pressure channel combinations. The seven additional starts required by this interpretation would exacerbate the wear and tear on the pumps. The proposed change would clarify the testing requirements and preclude this interpretation.

Sufficient surveillance currently exists to adequately verify the operability of the ICS system initiation logic. Figures 1 through 5 in the attachment provide simplified schematics of the ICS system actuation logic from the containment pressure transmitters to an ICS pump or valve. The figures identify the SPs that test each component. From these figures, it can be seen that the existing procedures adequately test each component with sufficient overlap to ensure system operability.

SP 18-043, Containment Pressure Instrument Channel test, is conducted on a monthly basis in accordance with item 18c of table TS 4.1-1. This procedure calibrates the bistables associated with the containment pressure transmitters and verifies the operability of the transmitter's power supply, isolation amplifier, test point, bistables, logic relay, and control room annunciators.


SP 18-044, Containment Pressure Instrument Calibration, is conducted on a refueling basis in accordance with item 18c of table TS 4.1-1. This procedure calibrates the containment pressure transmitters, their associated bistables and control room indication. The procedure also verifies operability of the transmitter's power supply, isolation amplifier, test point, logic relay and control room annunciators.

SP 23-095, Containment Spray System Test, is conducted on a refueling basis in accordance with TS 4.5.a.2.A. This procedure verifies operability of the ICS system's pumps, valves, and actuation logic, including the master/slave relay.

SP 55-155, Engineered Safeguards Logic Channel Test, is conducted monthly in accordance with item 26 of Table TS 4.1-1 and item 3b of table TS 3.5-3. This procedure verifies operability of the ICS master/slave relays, their associated contact points and the ICS ESF actuation logic.

In conclusion, the proposed change to TS 4.5.a.2 requested by PA-83 should be approved by the NRC. The proposed change would ensure that the TS is properly interpreted to prevent excessive wear and tear of the ICS pumps. Therefore, the proposed change is safe and conservative and should be approved.

Sincerely,



D. C. Hintz
Vice President - Nuclear Power

TJW/jms
Enc.

cc - Mr. Robert Nelson, US NRC
US NRC, Region III

Attachment

To The Letter

From:

D. C. Hintz (WPSC)

To:

Document Control Desk (NRC)

Dated:

June 16, 1988

Re:

Internal Containment Spray System Testing







FIGURE 1

— — SP18-044
 - - - SP18-043
 - . . - SP55-155

Control Room
 Indication



Relay
 Contacts



[To Cntmt Press
 Logic For ICS
 Initiation]


[To Control Room
 Annunciators]

Relay Rack o Field

Ref DWGs
 XK100-623
 XK100-653
 E2709

FIGURE 1 (CON'T)


SP55-155 — . . . —
 SP23-095 — — — —



ICS ESF ACTUATION LOGIC
 FIGURE 2

Ref DWG:
 E2712


SP23-095 — —



ICS PUMP
FIGURE 3

Ref DWGS:
E1082
E1089

SP23-095 — —




ICS PUMP DISCHARGE VALVE TO CNTMT

FIGURE 4

Ref DWG:
E1419

SP23-095 — —



SV-33086 Energizes
to Open CV 31272

Ref DWG
E1545

ICS PUMP DISCHARGE VALVE TO THE RWST
FIGURE 5