

NRC FORM 195 (2-76)		U.S. NUCLEAR REGULATORY COMMISSION		DOCKET NUMBER 50-263
NRC DISTRIBUTION FOR PART 50 DOCKET MATERIAL				FILE NUMBER
TO: NRC		FROM: NSP Minneapolis, Minnesota 55401 L. O. Mayer		DATE OF DOCUMENT 09/14/77
				DATE RECEIVED 09/19/77
LETTER <input checked="" type="checkbox"/> ORIGINAL <input type="checkbox"/> COPY	<input type="checkbox"/> NOTORIZED <input checked="" type="checkbox"/> UNCLASSIFIED	PROP	INPUT FORM	NUMBER OF COPIES RECEIVED 1 signed

DESCRIPTION	Consists of corrections to the Annual Effluent Summary Data submitted by NRC's ltr. dtd. 08/26/77...w/att copy of the summary...	ENCLOSURE
	2p + 3p	
PLANT NAME: MONTICELLO		
cjm 09/19/77		1 CY ENCL Rec'd *

SAFETY		FOR ACTION/INFORMATION	
PROJECT MANAGER:	SNRIDER		
LIC. ASST. (5)**	DIGGS		
**FOR DISTRIBUTION AS FOLLOWS:			
1 EACH TO: EPA HQS, EPA REGION, NOAA, F & W & F & D			

INTERNAL DISTRIBUTION			
REG. FILES			
NRC PDR			
I & E (2)			
MIPC (2)			
HANAUER			
STELLO			
EISENHUT			
SHAO			
BAER			
BUTLER			
GRIMES			
P. CHECK			
J. COLLINS			

EXTERNAL DISTRIBUTION			CONTROL NUMBER
LPR: MINNEAPOLIS, MN.			472620079
TIC			
NSIC			
NAT LAB			
ACRS W/15 CYS SENT CATEGORY B			


NSP

NORTHERN STATES POWER COMPANY

MINNEAPOLIS, MINNESOTA 55401

REGULATORY DOCKET FILE COPY

September 14, 1977



U S Nuclear Regulatory Commission
Office of Management Information & Program Control
Operating Data Branch, 12105 MNBB
Washington, DC 20555

Gentlemen:

MONTICELLO NUCLEAR GENERATING PLANT
Docket No. 50-263 License No. DPR-22

Verification of Annual Radioactive Effluent Summary Data

In a letter dated August 26, 1977 from Mr D K Davis, Acting Chief, Operating Reactors Branch No. 2, to Mr L O Mayer, NSP, we were asked to verify the accuracy of a tabulation of radioactive effluent data for 1976 for our operating nuclear generating plants.

A copy of the summary is attached with all necessary corrections noted. The following corrections were necessary:

- 1) Gross thermal generation was corrected to clearly indicate the numbers presented are rounded to the nearest whole MWHT.
- 2) Net electrical generation was corrected to clearly indicate the numbers presented are rounded to the nearest whole MWHE.
- 3) Item D under Summary of Effluents, Airborne, should be corrected to read, "Total Particulates (half-lives longer than 8 days)."
- 4) Other corrections shown are required to correct transcription errors or to incorporate amendments dated June 3, 1977 to the Monticello Effluent and Waste Disposal Semiannual reports covering the periods January 1 - June 30, 1976 and July 1 - December 31, 1976. These amendments were not used in compiling the draft copy of the data you provided to us. In addition, the Monticello Effluent and Waste Disposal Semiannual Report for the period January 1 - June 30, 1976 was not prepared in the Regulatory Guide 1.21 format and certain information (i.e. tritium and individual particulate isotopes) was not reported. Where required, this data was obtained from plant records to correct the draft copy of the data.

Summary totals on the first page of the data can be different than the sum of isotopes on pages 2 and 3 in all cases except for "Total Noble Gases" and "Total

772620097

NORTHERN STATES POWER COMPANY

U S Nuclear Regulatory Commission
Page 2
September 14, 1977

Halogens (including I-131)." As required by Regulatory Guide 1.21, Section C.12.c, measurements of samples resulting in no measured activity are reported as less than the maximum sensitivity of the measurement. In our Effluent and Waste Disposal Semiannual Reports, summary total releases presented in Tables 1A and 2A do not include nuclides which were below minimum detectable activity (MDA). MDA values are included, however, in the individual isotopes reported in Tables 1B, 1C, and 2B. This is done to permit comparisons of releases to applicable regulatory limits to exclude nuclides which were not actually detected during sampling. Noble gas releases are reported as above MDA since they are based on continuous gross activity monitoring with individual isotope releases determined using calculated ratios. There is no regulatory limit on total halogens.

Individual halogen and particulate isotopes on the second and third pages of the data generally include a "less than" symbol. As noted above, this situation arises from reporting measurements of samples in which no measured activity was found as less than MDA. For example, if a quarterly quantity of an isotope released is based on 13 weekly samples, even one sample less than MDA can cause the total quarterly release to be expressed as "less than". Quantities are reported without the "less than" symbol only when all individual measurements are greater than MDA, or if measurements less than MDA do not contribute to the total expressed to three significant decimal places.

We believe we have taken a conservative approach in conforming to Regulatory Guide 1.21, Section C.12.c. There is a wide variation in interpretation of this section, however, and further guidance from the Commission in this area would be welcome.

If you should find it necessary to clarify the attached data, please contact the following individual at Northern States Power Company:

David Misolf
612-330-6764

Please contact us if you have any questions or require further information related to this matter.

Yours very truly,



L O Mayer, PE
Manager of Nuclear Support Services

Attachment

cc: D K Davis
J G Keppler
G Charnoff
MPCA - Attn: J W Ferman

FACILITY: MONTICELLO
 TYPE: BWR
 LOCATION: 23 MI SE ST. CLOUD MN
 COOLING WATER SOURCE: MISSISSIPPI RIVER

DOCKET NO: 50-263
 LICENSED POWER (MWT): 1670.0
 INITIAL CRITICALITY: 12/10/70

~~0.0~~ ~~0.0~~

OPERATION

GROSS THERMAL GENERATION	12343438.	12343438.0	MWHT
NET ELECTRICAL	3986380.	3986380.0	MWHE
THERMAL CAPACITY FACTOR (DURING COMMERCIAL OPERATION)		84.1	PER CENT

SUMMARY OF EFFLUENTS

AIRBORNE

A)	TOTAL NOBLE GASES	1.14E+04	CURIES
B)	TOTAL I-131	1.21E-01	CURIES
C)	TOTAL HALOGENS (INCLUDING I-131)	<1.02E+00	CURIES
D)	TOTAL PARTICULATES (half lives longer than 8 days)	2.74E-02 5.02E-02	CURIES
E)	TOTAL TRITIUM	5.02E+01 7.69E 01	CURIES

LIQUID

A)	TOTAL MIXED FISSION AND ACTIVATION PRODUCTS	0.0	CURIES
B)	TOTAL TRITIUM	0.0	CURIES
C)	DISOLVED NOBLE GASES	0.0	CURIES
D)	VOLUME OF LIQUID WASTE RELEASED	0.0	LITERS
E)	VOLUME OF DILUTION WATER	0.0	LITERS

SOLID WASTE

A)	VOLUME	2.85E+02	CUBIC METERS
B)	ACTIVITY	3.00E+02 3.79E 03	CURIES
C)	NUMBER OF SHIPMENTS	4.30E+01	

** IF SUMMARY
 VALUES ARE
 DIFFERENT THAN
 THE SUM OF
 ISOTOPES PLEASE
 EXPLAIN DISCREPANCY.*

AIRBORNE EFFLUENTS (CURIES)

NOBLE GAS

KR-83M	2.09E-01	2.81E 01
KR-85	2.69E-03	5.65E 01
KR-85M	1.74E-01	2.02E 01
KR-87	9.03E-04	1.34E 02
KR-88	5.11E-01	6.94E 01
KR-89	2.07E-03	2.70E 03
KR-90	7.09E-01	9.15E 01
XE-131M	4.91E-00	5.54E 00
XE-133	6.11E-02	6.97E 02
XE-133M	2.91E-01	2.09E 00
XE-135	1.44E-02	1.95E 02
XE-135M	1.57E-02	2.08E 02
XE-137	2.71E-03	3.53E 03
XE-138	2.50E-03	3.42E 03
XE-139	2.11E-02	2.72E 02

HALOGENS

I-131	1.21E-01	
I-133	6.21E-01	6.20E-01
I-135	<2.76E-01	

PARTICULATES

CR-51	<2.63E-03	
MN-54	8.68E-05	<3.92E-04
FE-59	1.32E-04	<1.34E-04
CO-57	3.67E-05	<7.76E-05
CO-58	1.11E-05	<9.60E-05
CO-60	9.61E-04	<1.17E-03
ZN-65	1.18E-03	<1.41E-03
SR-89	8.29E-04	4.48E-03
SR-90	8.98E-05	4.93E-04
ZR-95	1.01E-04	<1.12E-04
NB-95	2.04E-04	<2.34E-04
RU-103	5.34E-04	<5.41E-04
CS-134	1.23E-04	<1.44E-03
CS-136	2.37E-04	<2.02E-03
CS-137	1.12E-03	<2.08E-03
CE-141	8.61E-05	<1.34E-03
CE-144	3.61E-04	<6.41E-04
SB-124	1.10E-04	<8.55E-04
HA-140	2.12E-02	3.16E-02
SB-126	7.42E-05	<7.52E-05
ND-147	1.95E-04	<1.98E-04

TRITIUM

H-3	5.02E-01	7.69E 01
-----	---------------------	----------

PLEASE EXPLAIN USE OF LESS THAN NOTATION.
UNUSUALLY LARGE NUMBER OF ISOTOPES WITH
THAT NOTATION.

LIQUID EFFLUENTS (CURIES)