

# **Generic Environmental Impact Statement for License Renewal of Nuclear Plants**

## **Supplement 38**

### **Regarding Indian Point Nuclear Generating Unit Nos. 2 and 3**

#### **Draft Report for Comment**

## AVAILABILITY OF REFERENCE MATERIALS IN NRC PUBLICATIONS

### NRC Reference Material

As of November 1999, you may electronically access NUREG-series publications and other NRC records at NRC's Public Electronic Reading Room at <http://www.nrc.gov/reading-rm.html>.

Publicly released records include, to name a few, NUREG-series publications; *Federal Register* notices; applicant, licensee, and vendor documents and correspondence; NRC correspondence and internal memoranda; bulletins and information notices; inspection and investigative reports; licensee event reports; and Commission papers and their attachments.

NRC publications in the NUREG series, NRC regulations, and *Title 10, Energy*, in the Code of *Federal Regulations* may also be purchased from one of these two sources.

1. The Superintendent of Documents  
U.S. Government Printing Office  
Mail Stop SSOP  
Washington, DC 20402-0001  
Internet: [bookstore.gpo.gov](http://bookstore.gpo.gov)  
Telephone: 202-512-1800  
Fax: 202-512-2250
2. The National Technical Information Service  
Springfield, VA 22161-0002  
[www.ntis.gov](http://www.ntis.gov)  
1-800-553-6847 or, locally, 703-605-6000

A single copy of each NRC draft report for comment is available free, to the extent of supply, upon written request as follows:

Address: U.S. Nuclear Regulatory Commission  
Office of Administration  
Publications Branch  
Washington, DC 20555-0001

E-mail: [DISTRIBUTION.SERVICES@NRC.GOV](mailto:DISTRIBUTION.SERVICES@NRC.GOV)

Facsimile: 301-415-2289

Some publications in the NUREG series that are posted at NRC's Web site address <http://www.nrc.gov/reading-rm/doc-collections/nuregs> are updated periodically and may differ from the last printed version. Although references to material found on a Web site bear the date the material was accessed, the material available on the date cited may subsequently be removed from the site.

### Non-NRC Reference Material

Documents available from public and special technical libraries include all open literature items, such as books, journal articles, and transactions, *Federal Register* notices, Federal and State legislation, and congressional reports. Such documents as theses, dissertations, foreign reports and translations, and non-NRC conference proceedings may be purchased from their sponsoring organization.

Copies of industry codes and standards used in a substantive manner in the NRC regulatory process are maintained at—

The NRC Technical Library  
Two White Flint North  
11545 Rockville Pike  
Rockville, MD 20852-2738

These standards are available in the library for reference use by the public. Codes and standards are usually copyrighted and may be purchased from the originating organization or, if they are American National Standards, from—

American National Standards Institute  
11 West 42<sup>nd</sup> Street  
New York, NY 10036-8002  
[www.ansi.org](http://www.ansi.org)  
212-642-4900

Legally binding regulatory requirements are stated only in laws; NRC regulations; licenses, including technical specifications; or orders, not in NUREG-series publications. The views expressed in contractor-prepared publications in this series are not necessarily those of the NRC.

The NUREG series comprises (1) technical and administrative reports and books prepared by the staff (NUREG-XXXX) or agency contractors (NUREG/CR-XXXX), (2) proceedings of conferences (NUREG/CP-XXXX), (3) reports resulting from international agreements (NUREG/IA-XXXX), (4) brochures (NUREG/BR-XXXX), and (5) compilations of legal decisions and orders of the Commission and Atomic and Safety Licensing Boards and of Directors' decisions under Section 2.206 of NRC's regulations (NUREG-0750).

# **Generic Environmental Impact Statement for License Renewal of Nuclear Plants**

## **Supplement 38**

### **Regarding Indian Point Nuclear Generating Unit Nos. 2 and 3**

### **Draft Report for Comment**

Manuscript Completed: June 2012  
Date Published: June 2012

1 Proposed Action Issuance of renewed operating licenses DPR-26 and DPR-64 for Indian  
2 Point Nuclear Generating Unit Nos. 2 and 3, in Buchanan, NY  
3  
4 Type of Statement Supplement to Final Supplemental Environmental Impact Statement  
5  
6 Agency Contact Michael Wentzel  
7 Office of Nuclear Reactor Regulation  
8 Mail Stop O-11F1  
9 U.S. Nuclear Regulatory Commission  
10 Washington, DC 20555-0001  
11 Telephone: 301-415-6459  
12 E-mail: [michael.wentzel@nrc.gov](mailto:michael.wentzel@nrc.gov)  
13  
14 Comments Any interested party may submit comments on this supplement to the  
15 final supplemental environmental impact statement. Please specify  
16 NUREG-1437, Supplement 38, Volume 4, draft supplement to final, in  
17 your comments. Comments must be received by August 20, 2012.  
18 Comments received after the expiration of the comment period will be  
19 considered if it is practical to do so, but the NRC cannot assure that  
20 consideration of late comments will be given. Comments may be  
21 submitted electronically by searching for docket ID NRC-2008-0672 at the  
22 Federal rulemaking Web site, <http://www.regulations.gov>. Comments  
23 may also be mailed to the following address:  
24  
25 Chief, Rules, Announcements, and Directives Branch  
26 Division of Administrative Services  
27 Office of Administration  
28 Mail Stop: TWB-05-B01M  
29 U.S. Nuclear Regulatory Commission  
30 Washington, DC 20555-0001  
31  
32 Please be aware that any comments that you submit to the U.S. Nuclear  
33 Regulatory Commission will be considered a public record and entered  
34 into the Agencywide Documents Access and Management System. Do  
35 not provide information you would not want to be publicly available.

## ABSTRACT

1

2 This supplement to the final supplemental environmental impact statement (FSEIS) for the  
3 proposed license renewal of Indian Point Nuclear Generating Unit Nos. 2 and 3 incorporates  
4 new information that the U.S. Nuclear Regulatory Commission (NRC) staff has obtained since  
5 the publication of the FSEIS in December 2010.

6 This supplement includes corrections to impingement and entrainment data presented in the  
7 FSEIS, revised conclusions regarding thermal impacts based on newly available thermal plume  
8 studies, and an update of the status of the NRC's consultation under section 7 of the  
9 Endangered Species Act with the National Marine Fisheries Service regarding the shortnose  
10 sturgeon (*Acipenser brevirostrum*) and Atlantic sturgeon (*Acipenser oxyrinchus oxyrinchus*).



# CONTENTS

<b>ABSTRACT</b> .....	<b>iii</b>
<b>CONTENTS</b> .....	<b>v</b>
<b>FIGURES</b> .....	<b>vii</b>
<b>TABLES</b> .....	<b>vii</b>
<b>EXECUTIVE SUMMARY</b> .....	<b>ix</b>
<b>ABBREVIATIONS, ACRONYMS, AND SYMBOLS</b> .....	<b>xi</b>
<b>1.0 INTRODUCTION</b> .....	<b>1</b>
<b>2.0 IMPINGEMENT AND ENTRAINMENT DATA CORRECTIONS</b> .....	<b>3</b>
2.1 Corrections to Section 4.1.2, “Entrainment of Fish and Shellfish in Early Lifestages,” and Its Related Appendices .....	3
2.2 Corrections to Section 4.1.3, “Combined Effects of Impingement and Entrainment,” and Its Related Appendices .....	7
<b>3.0 ASSESSMENT OF THERMAL IMPACTS</b> .....	<b>17</b>
<b>4.0 SECTION 7 CONSULTATION</b> .....	<b>23</b>
4.1 Corrections to Section 4.6.1, “Aquatic Special Status Species” .....	23
4.2 History of Section 7 Consultation for Shortnose Sturgeon .....	24
4.3 Summary of the National Marine Fisheries Service’s Biological Opinion for Shortnose Sturgeon.....	25
4.4 Reinitiation of Consultation Due to NMFS’s Listing of Atlantic Sturgeon .....	26
<b>5.0 REFERENCES</b> .....	<b>27</b>
<b>6.0 LIST OF PREPARERS</b> .....	<b>33</b>





1 **FIGURES**

2 Figure 4-3. Percentage of entrainment composed of RIS fish and total identified  
3 fish relative to the estimated total entrainment at IP2 and IP3 combined  
4 (data from Entergy 2007b) .....4  
5 Figure H-5. Percentage of entrainment composed of RIS fish and total identified  
6 fish relative to the estimated total entrainment at IP2 and IP3 combined  
7 (data from Entergy 2007b) .....5

8 **TABLES**

9 Table I-39. Percentage of Each Life Stage Entrained by Season and the  
10 Contribution of Major Taxa Represented in the Samples.....6  
11 Table I-42 Annual Estimated Number of RIS Entrained at IP2 and IP3 (~~millions~~  
12 thousands of fish) .....7  
13 Table 4-4. Impingement and Entrainment Impact Summary for Hudson River YOY  
14 RIS.....9  
15 Table H-16. Weight of Evidence for the Strength-of-Connection Line of Evidence  
16 for YOY RIS Based on the Monte Carlo Simulation..... 10  
17 Table H-17. Impingement and Entrainment Impact Summary for Hudson River  
18 YOY RIS ..... 11  
19 Table I-40. Method for Estimating Taxon-Specific Entrainment Mortality Rate  
20 (EMR) Based on River Segment 4 Standing Crop for the Strength of  
21 Connection Analysis ..... 12  
22 Table I-41 Estimated Annual Standing Crop of Eggs, Larvae, and Juvenile RIS  
23 Within River Segment 4 (~~millions~~ thousands of fish)..... 12  
24 Table I-43. Estimate of the River Segment 4 Entrainment Mortality Rate (EMR)  
25 and the 95 Percent Confidence Limits for the Riverwide Entrainment  
26 CMR (1974-1997)..... 13  
27 Table I-46. Parameter Values Used in the Monte Carlo Simulation..... 14  
28 Table I-47. Quartiles of the Relative Difference in Cumulative Abundance and  
29 Conclusions for the Strength-of-Connection from the Monte Carlo  
30 Simulation..... 15  
31 Table 6–1. List of Preparers .....33



# EXECUTIVE SUMMARY

## BACKGROUND

By letter dated April 23, 2007, Entergy Nuclear Operations, Inc. (Entergy) submitted an application to the U.S. Nuclear Regulatory Commission (NRC) to issue renewed operating licenses for Indian Point Nuclear Generating Unit Nos. 2 and 3 (IP2 and IP3) for additional 20-year periods.

Under Title 10 of the *Code of Federal Regulations* (10 CFR) 51.20(b)(2) and the National Environmental Policy Act of 1969, as amended (NEPA), the renewal of a power reactor operating license requires preparation of an environmental impact statement (EIS) or a supplement to an existing EIS. In addition, 10 CFR 51.95(c) states that the NRC shall prepare an EIS, which is a supplement to the Commission's NUREG-1437, "Generic Environmental Impact Statement for License Renewal of Nuclear Plants," issued May 1996.

The NRC published its final supplemental environmental impact statement (FSEIS) for IP2 and IP3 in December 2010. After the NRC published the FSEIS, the staff identified new information that necessitated changes to its assessments in the FSEIS. This new information is derived from the following:

- Entergy provided comments on the FSEIS that included new information on the entrainment and impingement field data units of measure,
- Entergy provided comments on the Essential Fish Habitat Assessment that also included new information on the data units of measure, and
- Entergy completed and submitted to the New York State Department of Environmental Conservation a new study that characterizes the IP2 and IP3 thermal plume.

To address this new information, the NRC staff has prepared this supplement to the FSEIS in accordance with 10 CFR 51.92(a)(2) and (c), which address preparation of a supplement to a final environmental impact statement for proposed actions that have not been taken, under the following conditions:

- There are new and significant circumstances or information relevant to environmental concerns and bearing on the proposed action or its impacts, or
- The NRC staff determines, in its opinion, that preparation of a supplement will further the purposes of NEPA.

In addition to supplementing the FSEIS for the reasons stated above, the NRC is also taking this opportunity to document the completion of the consultation process under section 7 of the Endangered Species Act of 1973, as amended (ESA), with the National Marine Fisheries Service (NMFS) regarding the shortnose sturgeon (*Acipenser brevirostrum*) and the subsequent reinitiation of consultation due to NMFS's listing of the Atlantic sturgeon (*Acipenser oxyrinchus oxyrinchus*) population in the New York Bight as endangered.

## PROPOSED ACTION

The proposed action remains the same as that stated in the FSEIS (at pages 1-6-1-7):

The proposed Federal action is renewal of the operating licenses for IP2 and IP3 (IP1 was shut down in 1974). IP2 and IP3 are located on approximately

## Executive Summary

1 239 acres of land on the east bank of the Hudson River at Indian Point,  
2 Village of Buchanan, in upper Westchester County, New York, approximately  
3 24 miles north of the New York City boundary line. The facility has two  
4 Westinghouse pressurized-water reactors. IP2 is currently licensed to  
5 generate 3216 megawatts thermal (MW(t)) (core power) with a design net  
6 electrical capacity of 1078 megawatts electric (MW(e)). IP3 is currently  
7 licensed to generate 3216 MW(t) (core power) with a design net electrical  
8 capacity of about 1080 MW(e). IP2 and IP3 cooling is provided by water from  
9 the Hudson River to various heat loads in both the primary and secondary  
10 portions of the plants. The current operating license for IP2 expires on  
11 September 28, 2013, and the current operating license for IP3 expires on  
12 December 12, 2015. By letter dated April 23, 2007, Entergy submitted an  
13 application to the NRC (Entergy 2007a) to renew the IP2 and IP3 operating  
14 licenses for an additional 20 years.

### 15 **PURPOSE AND NEED FOR ACTION**

16 The purpose and need for action remains the same as stated in the FSEIS (at page 1-7):

17 Although a licensee must have a renewed license to operate a reactor  
18 beyond the term of the existing operating license, the possession of that  
19 license is just one of a number of conditions that must be met for the licensee  
20 to continue plant operation during the term of the renewed license. Once an  
21 operating license is renewed, State regulatory agencies and the owners of  
22 the plant will ultimately decide whether the plant will continue to operate  
23 based on factors such as the need for power or matters within the State's  
24 jurisdiction—including acceptability of water withdrawal, consistency with  
25 State water quality standards, and consistency with State coastal zone  
26 management plans—or the purview of the owners, such as whether  
27 continued operation makes economic sense.

28 Thus, for license renewal reviews, the NRC has adopted the following  
29 definition of purpose and need (GEIS Section 1.3):

30 The purpose and need for the proposed action (renewal of an  
31 operating license) is to provide an option that allows for power  
32 generation capability beyond the term of a current nuclear power  
33 plant operating license to meet future system generating needs,  
34 as such needs may be determined by State, utility, and where  
35 authorized, Federal (other than NRC) decision makers.

36 This definition of purpose and need reflects the Commission's recognition  
37 that, unless there are findings in the safety review required by the Atomic  
38 Energy Act of 1954, as amended, or findings in the NEPA environmental  
39 analysis that would lead the NRC to reject a license renewal application, the  
40 NRC does not have a role in the energy-planning decisions of State  
41 regulators and utility officials as to whether a particular nuclear power plant  
42 should continue to operate. From the perspective of the licensee and the  
43 State regulatory authority, the purpose of renewing the operating licenses is  
44 to maintain the availability of the nuclear plant to meet system energy  
45 requirements beyond the current term of the plant's licenses.

## ABBREVIATIONS, ACRONYMS, AND SYMBOLS

°C	degree(s) Celsius
°F	degree(s) Fahrenheit
ADAMS	Agencywide Documents Access and Management System
BSS	Beach Seine Survey
CFR	Code of Federal Regulations
CHGEC	Central Hudson Gas and Electric Corporation
CMR	conditional mortality rate
DPS	distinct population segment
EIS	environmental impact statement
EMR	entrainment mortality rate
Entergy	Entergy Nuclear Operations, Inc.
ESA	Endangered Species Act of 1973, as amended
FSEIS	final supplemental environmental impact statement
FSS	Fall Shoals Survey
ft	feet
GEIS	NUREG-1437, "Generic Environmental Impact Statement for License Renewal of Nuclear Plants"
IMR	impingement mortality rate
IP2 and IP3	Indian Point Nuclear Generating Unit Nos. 2 and 3
LOE	line of evidence
LRS	Long River Survey
m	meter(s)
NEPA	National Environmental Policy Act of 1969
NMFS	National Marine Fisheries Service
NRC	U.S. Nuclear Regulatory Commission
NYCRR	New York Codes, Rules, and Regulations
NYSDEC	New York State Department of Environmental Conservation
RIS	representative important species
SEIS	supplemental environmental impact statement
SOC	strength of connection
SPDES	State Pollutant Discharge Elimination System
WOE	weight of evidence
YOY	young of year



## 1.0 INTRODUCTION

The U.S. Nuclear Regulatory Commission (NRC) staff prepared this supplement to the final supplemental environmental impact statement (FSEIS) for Indian Point Nuclear Generating Units 2 and 3 (IP2 and IP3) in accordance with Title 10 of the *Code of Federal Regulations* (10 CFR) 51.92(a)(2) and (c), which address the preparation of a supplement to an FSEIS for proposed actions that have not been taken, if the following conditions apply:

- There are new and significant circumstances or information relevant to environmental concerns and bearing on the proposed action or its impacts, or
- The NRC staff determines, in its opinion, that preparation of a supplement will further the purposes of NEPA.

The NRC staff prepared this supplement to the FSEIS because it received new data, analyses, and comments from several sources that potentially changed, and in some cases did change, the staff's conclusions in the FSEIS. This supplement contains the text, tables, and figures that changed as the result of this new information.

Three sources provided information that changed the staff's conclusions in the FSEIS.

First, in comments to the NRC dated March 29, 2011, Entergy Nuclear Operations, Inc. (Entergy) (Entergy 2011b, AKRF 2011b) provided new information regarding the entrainment and impingement field data that it had previously provided to the NRC for its aquatic resource impact assessment in Entergy (2007), a December 2007 supplement to its license renewal application. In its letter dated March 29, 2011, Entergy (2011b) said that these changes would:

...not alter, but rather confirm, NRC's ultimate conclusion in the FSEIS that potential impacts to aquatic species as a result of theoretical entrainment and impingement at IPEC are no more than MODERATE.

Second, comments submitted on behalf of Entergy (Goodwin Proctor 2011, AKRF 2011a) on the FSEIS and the NRC staff's Essential Fish Habitat Assessment contained related new information. When the NRC staff considered this information, the staff found that the information necessitated some minor changes to the aquatic ecology findings in Sections 4.1.2 through 4.1.3 of the FSEIS and Appendices H and I. Chapter 2 of this supplement provides corrected tables and conclusions resulting from the NRC staff's analysis of the new information. Where specific changes or corrections to FSEIS information occur, this supplement references the affected FSEIS section, page, and line numbers.

Third, since the publication of the FSEIS, Entergy submitted to the New York State Department of Environmental Conservation (NYSDEC) a triaxial plume study (Swanson et al. 2011a) as part of its State Pollutant Discharge Elimination System (SPDES) permit renewal application. Entergy undertook this study in response to the NYSDEC's 2010 Notice of Denial (NYSDEC 2010). Based on this new information, as well as Entergy's response to the NYSDEC staff's comments on the study (Mendelsohn et al. 2011, Swanson et al. 2011b) and the NYSDEC staff's conclusions regarding its review of the study and response to comments (NYSDEC 2011), the NRC staff has revised its conclusions regarding the impacts of heat shock to aquatic species. Chapter 3 of this supplement presents these revised conclusions.

In addition to supplementing the FSEIS for the reasons stated above, the staff is also taking this opportunity to update the status of consultations under section 7 of the Endangered Species Act of 1973, as amended (ESA) with the National Marine Fisheries Service (NMFS). Chapter 4 of this supplement updates the information contained in Section 4.6.1 of the FSEIS to document

## Introduction

1 the completion of consultation regarding the shortnose sturgeon (*Acipenser brevirostrum*), and  
2 summarizes the biological opinion and associated incidental take statement (NMFS 2011e) that  
3 NMFS issued in October 2011 as a result of that consultation. Additionally, Chapter 4 of this  
4 supplement provides a summary of the reinitiation of consultation regarding the Atlantic  
5 sturgeon (*Acipenser oxyrinchus oxyrinchus*) that resulted from NMFS's February 2012 listing of  
6 Atlantic sturgeon as an endangered species under the ESA.

7 Where appropriate, **bold** text indicates specific text corrections or additions to the FSEIS and  
8 **bold strikeout** indicates deletions from the text.



## 2.0 IMPINGEMENT AND ENTRAINMENT DATA CORRECTIONS

### 2.1 Corrections to Section 4.1.2, “Entrainment of Fish and Shellfish in Early Lifestages,” and Its Related Appendices

In a letter to the NRC dated March 29, 2011 (Entergy 2011b; AKRF 2011b), Entergy provided new information supplementing the entrainment and impingement field data that it had previously provided to the NRC for its aquatic resource impact assessment. This new information appears in “Technical Review of FSEIS for Indian Point Nuclear Generating Unit Nos. 2 and 3” (AKRF 2011b). In its technical review, AKRF (2011b) stated that the units of the entrainment catch densities provided by Entergy are expressed as the number caught per 1,000 cubic meters ( $m^3$ ). Because Entergy did not originally provide the units used in the FSEIS to assess impacts, the NRC staff believed the units to be the number caught/ $m^3$  based on historical documents provided by Entergy, comments by Entergy and its consultants on the draft SEIS, and phone conversations among Entergy, Entergy’s consultants, and NRC staff. Thus, the entrainment losses the FSEIS reported for each of the representative important species (RIS) used in the NRC staff’s analysis are too large by a factor of 1,000.

In the FSEIS, the NRC staff estimated the number entrained for a given week as the product of the mean density entrained and the combined weekly flow for IP2 and IP3. The error in the entrainment catch density directly affects Figure 4-3 in Section 4.1.2, and the error is repeated in Figure H-5 in Appendix H. In these figures, the total number entrained on the right axis should be in units of numbers  $\times 10^8$  instead of numbers  $\times 10^{11}$ . The corrected Figures 4-3 and H-5 appear below. In addition, these changes affect two portions of text in the FSEIS.

**Lines 2 and 3 of page 4-14** in the FSEIS are corrected as follows:

The total number of identified fish entrained has decreased at a rate of 187 ~~billion~~ million fish per year since 1984.


**Lines 1–3 of page H-22** in the FSEIS are corrected as follows:

Linear regression ( $n=6$ ;  $p<0.01$ ) indicated that the number of identified fish entrained decreased at a rate of 187 ~~billion~~ million fish per year, a result consistent with the decrease observed in the number of fish impinged.

The change in units of the entrainment catch densities also affects the 75th percentile of the number of each life stage entrained and the annual estimate of the number entrained presented in Tables I-39 and I-42 of Appendix I. In Table I-39, the units should be numbers  $\times 10^3$  instead of numbers  $\times 10^6$ . In Table I-42, the units should be numbers in the thousands instead of numbers in the millions. The corrected tables appear below.

Impingement and Entrainment Corrections

1 **Figure 4-3 on page 4-15 in the FSEIS is corrected as follows:**




2

3 **Figure 4-3. Percentage of entrainment composed of RIS fish and total identified fish**  
4 **relative to the estimated total entrainment at IP2 and IP3 combined**  
5 **(data from Entergy 2007b)**

6

1 **Figure H-5 on page H-23** in the FSEIS is identical to Figure 4-3 in the FSEIS and is corrected  
 2 as follows:



3  
 4 **Figure H-5. Percentage of entrainment composed of RIS fish and total identified fish**  
 5 **relative to the estimated total entrainment at IP2 and IP3 combined**  
 6 **(data from Entergy 2007b)**

7  
 8

Impingement and Entrainment Corrections

1 **Table I-39 on page I-54** in the FSEIS is corrected as follows:

2 **Table I-39. Percentage of Each Life Stage Entrained by Season and the Contribution of**  
 3 **Major Taxa Represented in the Samples.**

4 Calculations are based on the 75th percentile over years (1981 and 1983–1987) of each  
 5 season's number of fish entrained. No entrainment sampling occurred in October–December.

Life Stage	Season 1 Jan–Mar	Season 2 Apr–Jun	Season 3 Jul–Sep	75th Percentile over Years
EGG	3%	20%	78%	210,801×10 <sup>6</sup> 10 <sup>3</sup>
Rainbow Smelt	99%	2%	0%	
Bay Anchovy	0%	92%	100%	
White Perch	0%	4%	<1%	
<i>Alosa</i> species	1%	2%	0%	
YOLK-SAC LARVA	8%	89%	3%	23,140×10 <sup>6</sup> 10 <sup>3</sup>
Atlantic Tomcod	100%	0%	0%	
Herring Family	0%	91%	<1%	
Bay Anchovy	0%	2%	94%	
Striped Bass	0%	5%	1%	
Hogchoker	0%	0%	3%	
POST YOLK-SAC LARVA	<1%	52%	48%	618,393×10 <sup>6</sup> 10 <sup>3</sup>
Atlantic Tomcod	100%	<1%	0%	
<i>Alosa</i> species	0%	37%	<1%	
Bay Anchovy	0%	11%	58%	
Anchovy Family	0%	2%	39%	
White Perch	0%	12%	1%	
Striped Bass	0%	17%	1%	
Herring Family	0%	20%	<1%	
JUVENILE	2%	44%	54%	10,989×10 <sup>6</sup> 10 <sup>3</sup>
White Perch	96%	10%	10%	
Atlantic Tomcod	0%	67%	2%	
Weakfish	0%	1%	50%	
Bay Anchovy	0%	1%	17%	
Rainbow Smelt	0%	9%	3%	
Striped Bass	0%	6%	5%	
Anchovy Family	0%	1%	4%	
<i>Alosa</i> species	0%	2%	2%	
White Catfish	4%	<1%	0%	
Blueback Herring	0%	<1%	3%	
UNDETERMINED STAGE	10%	77%	13%	4,469×10 <sup>6</sup> 10 <sup>3</sup>
Atlantic Tomcod	100%	<1%	0%	
<i>Morone</i> species	0%	88%	2%	
Bay Anchovy	0%	9%	83%	
Anchovy Family	0%	0%	10%	
<i>Alosa</i> species	0%	0%	4%	

1 The title of Table I-42 on page I-58 of the FSEIS is corrected as follows:

2 **Table I-42 Annual Estimated Number of RIS Entrained at IP2 and IP3**  
3 **(~~millions~~ thousands of fish)**

4 The contents of the table remain accurate and, therefore, are not duplicated in this supplement.

## 5 **2.2 Corrections to Section 4.1.3, “Combined Effects of Impingement and** 6 **Entrainment,” and Its Related Appendices**

7 In a letter to the NRC dated March 29, 2011, Entergy (2011b) provided new information (in  
8 AKRF 2011b) regarding the units associated with the catch density data from the Long River  
9 Survey (LRS) and the Fall Shoals Survey (FSS) that Entergy (2007) had previously submitted to  
10 the NRC for its aquatic resource impact assessment. In AKRF’s (2011b) technical review, the  
11 units of the catch densities are expressed as the number caught/1,000 m<sup>3</sup>. Entergy did not  
12 provide the units for these densities when it originally submitted the data to the NRC. The NRC  
13 staff based the units it used in the FSEIS to assess impacts (i.e., number caught/m<sup>3</sup>) on  
14 information in the mathematical construction of these measures provided in Central Hudson  
15 Gas and Electric Corporation (CHGEC) et al. (1999). Thus, the NRC staff overestimated the  
16 annual standing crop from the LRS and FSS in the FSEIS for each of the representative  
17 important species (RIS) by a factor of 1,000. The NRC staff then used the estimates of the  
18 annual standing crop and the estimated entrainment losses to estimate a conditional  
19 entrainment mortality rate (EMR), a parameter in the models used in the strength-of-connection  
20 (SOC) analysis.

21 The NRC staff described the calculation of the standing crop from the LRS and FSS in  
22 Appendix I, Section I.2.2, of the FSEIS. The NRC staff estimated the LRS and FSS weekly  
23 standing crop as the weekly density of fish caught multiplied by the IP2 and IP3 region river  
24 volume. The error in the density units for the LRS and FSS produced incorrect estimates of the  
25 combined standing crop used in the denominator of the estimated EMR in the FSEIS. The NRC  
26 staff also used entrainment losses as input to the numerator and the denominator of the EMR  
27 estimates. Because both the numerator and the denominator of the estimated EMR were too  
28 large by a factor of 1,000, only those estimates for two RIS (spottail shiner (*Notropis hudsonius*)  
29 and white catfish (*Ameiurus catus*)), in which the Beach Seine Survey (BSS) contributed more  
30 of the standing crop, were seriously affected. For the remaining RIS, to which the BSS  
31 contributed little, the errors in units largely cancelled because of the construction of the EMR as  
32 a ratio of the number entrained (which was 1,000 times too large) to the number at risk (number  
33 in the river plus the number entrained, both of which were 1,000 times too large). The amount  
34 and direction of change in the EMR depends on the relative contributions from the three  
35 sampling programs—BSS, FSS, and LRS.

36 The NRC staff used the EMR in its assessment of the SOC and, ultimately, to determine the  
37 final weight-of-evidence (WOE) assessment of the combined effects of impingement and  
38 entrainment from IP2 and IP3. The unit of measure error affects the staff’s conclusion of High  
39 SOC for spottail shiner, but not the conclusion of Low SOC for white catfish. The NRC staff  
40 reran the SOC Monte Carlo simulations using the corrected EMRs, and, based on the corrected  
41 data, now finds a Low SOC for the spottail shiner. Further, based on the WOE assessment of  
42 the combined effects of impingement and entrainment from IP2 and IP3, the NRC staff  
43 concludes that the impacts of impingement and entrainment on the spottail shiner are SMALL  
44 rather than LARGE.

45 The changes to the SOC analysis affect FSEIS Table 4-4 (presented below) and several lines of  
46 text in Section 4.1.3.3. However, Section 4.1.3.5 is not affected by these changes.

Impingement and Entrainment Corrections

1 **Lines 41–43 on page 4-20** of the FSEIS are corrected as follows:

2 Based on the WOE assessment (Table 4-4), the NRC staff concludes that  
3 impacts to American shad, Atlantic menhaden, Atlantic sturgeon, Atlantic  
4 tomcod, bay anchovy, bluefish, gizzard shad, shortnose sturgeon, **spottail**  
5 **shiner**, striped bass, white catfish, and blue crab are SMALL.

6 **Lines 1–3 on page 4-21** of the FSEIS are corrected as follows:

7 The NRC staff concludes that impacts to alewife, rainbow smelt, and weakfish  
8 are MODERATE. The staff concludes that impacts to blueback herring,  
9 hogchoker, **spottail shiner**, and white perch are LARGE.

10 **Lines 30–41 on page 4-21** of the FSEIS are removed as follows:

11 ***Spottail Shiner***

12 ~~The NRC staff concludes that a Large impact is present for YOY spottail~~  
13 ~~shiner because a detectible population decline occurred in the river-wide (1~~  
14 ~~of 3) and river segment (1 of 1) data sets, and the strength of connection~~  
15 ~~with the IP2 and IP3 cooling system is high. The habitat for the spottail~~  
16 ~~shiner includes small streams, lakes, and large rivers, including the~~  
17 ~~Hudson. This species feeds primarily on aquatic insect larvae,~~  
18 ~~zooplankton, benthic invertebrates, and fish eggs and larvae, and is the~~  
19 ~~prey of striped bass. Spottail shiners spawn from May to June or July~~  
20 ~~(typically later for the northern populations) over sandy bottoms and~~  
21 ~~stream mouths (Smith 1985; Marcy et al. 2005); water chestnut (Trapa~~  
22 ~~natans) beds provide important spawning habitat (CHGEC 1999).~~  
23 ~~Individuals older than 3 years are rare, although some individuals may live~~  
24 ~~4 or 5 years (Marcy et al. 2005). Spottail shiner is not a marine or~~  
25 ~~anadromous species, so coastal population trend data are not available.~~

26

1 **Table 4-4 on page 4-23** of the FSEIS is corrected as follows:

2 **Table 4-4. Impingement and Entrainment Impact Summary for Hudson River YOY RIS**

Species	Population Trend Line of Evidence	Strength of Connection Line of Evidence	Impacts of IP2 and IP3 Cooling Systems on YOY RIS
Alewife	Variable	High	Moderate
American Shad	Detected Decline	Low	Small
Atlantic Menhaden	Unresolved <sup>(a)</sup>	Low <sup>(b)</sup>	Small
Atlantic Sturgeon	Unresolved <sup>(a)</sup>	Low <sup>(b)</sup>	Small
Atlantic Tomcod	Detected Decline	Low	Small
Bay Anchovy	Undetected Decline	High	Small
Blueback Herring	Detected Decline	High	Large
Bluefish	Detected Decline	Low	Small
Gizzard Shad	Unresolved <sup>(a)</sup>	Low <sup>(b)</sup>	Small
Hogchoker	Detected Decline	High	Large
Rainbow Smelt	Variable	High	Moderate-Large <sup>(c)</sup>
Shortnose Sturgeon	Unresolved <sup>(a)</sup>	Low <sup>(b)</sup>	Small
Spottail Shiner	Detected Decline	<b>High Low</b>	<b>Large Small</b>
Striped Bass	Undetected Decline	High	Small
Weakfish	Variable	High	Moderate
White Catfish	Variable	Low	Small
White Perch	Detected Decline	High	Large
Blue Crab	Unresolved <sup>(a)</sup>	Low <sup>(b)</sup>	Small

(a) Population trend could not be established because of a lack of river survey data.

(b) Monte Carlo simulation could not be conducted because of the low rate of entrainment and impingement; a Low Strength of connection was concluded.

(c) Section 4.1.3.3 provides supplemental information.

3 Because of the new information regarding the units of the data for entrainment density and the  
 4 density of fish caught during the LRS and FSS, the NRC staff corrected the estimates of EMR  
 5 for American shad (*Alosa sapidissima*), bay anchovy (*Anchoa mitchilli*), hogchoker (*Trinectes*  
 6 *maculatus*), white catfish, and white perch (*Morone americana*) reported in Appendices H and I.  
 7 The staff's conclusions of the SOC for these RIS, however, remain unchanged. These changes  
 8 affect several lines of text in Sections H.1.3.2 and H.1.3.3 and Tables H-16 and H-17, as  
 9 described below.

10 **Lines 11–12 on page H-47** in Section H.1.3.2 of the FSEIS are corrected as follows:

11 The results of this analysis indicated a High strength of connection for **nine eight**  
 12 species (Table H-16).

13 **Lines 15–16 on page H-47** in Section H.1.3.2 of the FSEIS are corrected as follows:

14 For **four five** RIS, the strength of connection was Low (minimal evidence of  
 15 connection).

16 **Lines 5–10 on page H-49** in Section H.1.3.3 of the FSEIS are corrected as follows:

17 Based on the WOE assessment (Table H-17), the NRC staff concludes that the  
 18 impact levels are Small for **eleven-12** species: American shad, Atlantic  
 19 menhaden, Atlantic sturgeon, Atlantic tomcod, bay anchovy, bluefish, gizzard  
 20 shad, shortnose sturgeon, **spottail shiner**, striped bass, white catfish, and blue  
 21 crab. Further, the staff concludes that the impacts are Moderate for three  
 22 species: alewife, rainbow smelt, and weakfish. Finally, the staff concludes that

Impingement and Entrainment Corrections

1 the impacts are Large for **four three** species: blueback herring, hogchoker,  
 2 **spottail shiner**; and white perch.

3 **Lines 26–38 on page H-50** in Section H.1.3.3 of the FSEIS are removed as follows:

4 ***Spottail Shiner***

5 ~~The NRC staff concludes that a Large impact is present for YOY spottail~~  
 6 ~~shiner because a detectible population decline occurred in the river-wide (1~~  
 7 ~~of 3) and river segment (1 of 1) data sets, and there was a high strength of~~  
 8 ~~connection with the IP2 and IP3 cooling system. The habitat for the spottail~~  
 9 ~~shiner includes small streams, lakes, and large rivers, including the~~  
 10 ~~Hudson. This species feeds primarily on aquatic insect larvae,~~  
 11 ~~zooplankton, benthic invertebrates, and fish eggs and larvae, and is the~~  
 12 ~~prey of striped bass. Spottail shiners spawn from May to June or July~~  
 13 ~~(typically later for the northern populations) over sandy bottoms and~~  
 14 ~~stream mouths (Smith 1985; Marcy et al. 2005); water chestnut (Trapa~~  
 15 ~~natans) beds provide important spawning habitat (CHGEC 1999).~~  
 16 ~~Individuals older than 3 years are rare, but there is evidence of individuals~~  
 17 ~~living four or five years (Marcy et al. 2005). Coastal population trend data~~  
 18 ~~were not available for this species.~~

19 **Table H-16 on page H-48** of the FSEIS is corrected as follows:

20 **Table H-16. Weight of Evidence for the Strength-of-Connection Line of Evidence for YOY**  
 21 **RIS Based on the Monte Carlo Simulation**

RIS	Strength of Connection	RIS	Strength of Connection
Alewife	High	Hogchoker	High
American Shad	Low	Rainbow Smelt	High
Atlantic Menhaden	Cannot be Modeled <sup>(a)</sup>	Shortnose Sturgeon	Cannot be Modeled <sup>(a)</sup>
Atlantic Sturgeon	Cannot be Modeled <sup>(a)</sup>	Spottail Shiner	<b>High Low</b>
Atlantic Tomcod	Low	Striped Bass	High
Bay Anchovy	High	Weakfish	High
Blueback Herring	High	White Catfish	Low
Bluefish	Low	White Perch	High
Gizzard Shad	Cannot be Modeled <sup>(a)</sup>	Blue Crab	Cannot be Modeled <sup>(a)</sup>

<sup>(a)</sup> Estimates for model parameters were unavailable or information was lacking. Strength of connection assumed to be Low based on review of impingement and entrainment data.



1 **Table H-17 on page H-49** of the FSEIS is corrected as follows:

2 **Table H-17. Impingement and Entrainment Impact Summary for Hudson River YOY RIS**

Species	Population Trend Line of Evidence	Strength of Connection Line of Evidence	Impacts of IP2 and IP3 Cooling Systems on YOY RIS
Alewife	Variable	High	Moderate
American Shad	Detected Decline	Low	Small
Atlantic Menhaden	Unresolved <sup>(a)</sup>	Low <sup>(b)</sup>	Small
Atlantic Sturgeon	Unresolved <sup>(a)</sup>	Low <sup>(b)</sup>	Small
Atlantic Tomcod	Detected Decline	Low	Small
Bay Anchovy	Undetected Decline	High	Small
Blueback Herring	Detected Decline	High	Large
Bluefish	Detected Decline	Low	Small
Gizzard Shad	Unresolved <sup>(a)</sup>	Low <sup>(b)</sup>	Small
Hogchoker	Detected Decline	High	Large
Rainbow Smelt	Variable	High	Moderate-Large <sup>(c)</sup>
Shortnose Sturgeon	Unresolved <sup>(a)</sup>	Low <sup>(b)</sup>	Small
Spottail Shiner	Detected Decline	<b>High Low</b>	<b>Large Small</b>
Striped Bass	Undetected Decline	High	Small
Weakfish	Variable	High	Moderate
White Catfish	Variable	Low	Small
White Perch	Detected Decline	High	Large
Blue Crab	Unresolved <sup>(a)</sup>	Low <sup>(b)</sup>	Small

<sup>(a)</sup> Population LOE could not be established using WOE; therefore, population LOE could range from small to large.

<sup>(b)</sup> Strength of connection could not be established using Monte Carlo simulation; therefore, strength of connection was based on the rate of entrainment and impingement.

<sup>(c)</sup> Section 4.1.3.3 provides supplemental information.

3 In addition to Tables I-39 and I-42, presented earlier, the new information about the units of  
 4 measure affects tables in Appendix I. The corrected Table I-40, Table I-41, Table I-43,  
 5 Table I-46, and Table I-47 in Appendix I of the FSEIS appear on the following pages.

6

Impingement and Entrainment Corrections

1 **Table I-40 on page I-56** of the FSEIS is corrected as follows:

2 **Table I-40. Method for Estimating Taxon-Specific Entrainment Mortality Rate (EMR)**  
 3 **Based on River Segment 4 Standing Crop for the Strength of Connection**  
 4 **Analysis**

Property of Method		Number Entrained	River Segment 4 Standing Crop
Input Data	Variables	mean density organisms entrained by IP2 and IP3 <b>(# per 1000 m<sup>3</sup>)</b>  Volume of cooling water withdrawn by IP2 and IP3 (1000 m <sup>3</sup> /min)	LRS density (by life stage) FSS density of YOY <b>(# per 1000 m<sup>3</sup>)</b> BSS density of YOY <b>(# per haul)</b>  River Segment 4 volume (m <sup>3</sup> ) River Segment 4 shorezone surface area (m <sup>2</sup> )
	Frequency	Per week of sampling	Per week of sampling
Summary Statistics	Seasonal (Year specific)	Sum of weekly estimates of number of organisms entrained by IP2 and IP3	Sum of weekly standing crop estimates
	Annual	Sum of Season 1, 1986 with each year's totals from Season 2 and Season 3	Sum of seasonal standing crop estimates for River Segment 4
	EMR	$\frac{75^{\text{th}} \text{ Percentile Annual Number Entrained}}{75^{\text{th}} \text{ Percentile (Annual Number Entrained} + \text{Annual Standing Crop)}}$	
	Units of numerator and denominator of EMR	# of organisms	
Years of Data		1981 and 1983-1987	1981 and 1983-1987
Life Stages		Eggs, Larvae, and Juveniles	Eggs, Larvae, and Juveniles (YOY)
Taxonomic Substitutions		Alewife, blueback herring, and unidentified alosids treated collectively as river herring	
		Unidentified anchovy spp. (species, plural) allocated to bay anchovy  Unidentified <i>Morone</i> spp. allocated proportionally to striped bass and white perch	

5  
 6 **The title of Table I-41 on page I-57** of the FSEIS is corrected as follows:

7 **Table I-41 Estimated Annual Standing Crop of Eggs, Larvae, and Juvenile RIS Within**  
 8 **River Segment 4 (millions thousands of fish)**

9 The contents of the table remain accurate and, therefore, are not duplicated in this supplement.

10

Impingement and Entrainment Data Corrections

1 **Table I-43 on page I-59** of the FSEIS is corrected as follows:

2 **Table I-43. Estimate of the River Segment 4 Entrainment Mortality Rate (EMR) and the 95**  
 3 **Percent Confidence Limits for the Riverwide Entrainment CMR (1974-1997)**

Taxa	75th Percentile Annual Number Entrained (number x 10 <sup>9</sup> 10 <sup>6</sup> )	75th Percentile of Number at Risk (number x 10 <sup>9</sup> 10 <sup>6</sup> )	EMR	Riverwide CMR for Entrainment at IP2 and IP3	
				Lower 95% Confidence Limit	Upper 95% Confidence Limit
Alewife and Blueback Herring	94.9	1003	0.095	0.00747	0.0324
American Shad	0.357	<del>8.43</del> 9.26	<del>0.042</del> 0.039	0	0.016696
Atlantic Menhaden	0	NA	NA	Not Modeled	
Atlantic Sturgeon	0	NA	NA	Not Modeled	
Atlantic Tomcod	7.65	210	0.036	0.152	0.234
Bay Anchovy	439	<del>2064</del> 2065	<del>0.213</del> 0.212	0.0925	0.140
Bluefish	0.00291	1.13	0.003	Not Modeled	
Gizzard Shad	0	NA	NA	Not Modeled	
Hogchoker	1.87	<del>4.83</del> 4.84	<del>0.386</del> 0.385	Not Modeled	
Rainbow Smelt	7.07	27.4	0.258	Not Modeled	
Shortnose Sturgeon	0	NA	NA	Not Modeled	
Spottail Shiner	0.00295	<del>0.00838</del> 0.0937	<del>0.352</del> 0.031	0.0802	0.104
Striped Bass	71.4	676	0.106	0.181	0.276
Weakfish	3.90	7.17	0.544	Not Modeled	
White Catfish	0.00965	<del>0.0848</del> 0.0388	<del>0.114</del> 0.249	Not Modeled	
White Perch	63.5	<del>840</del> 841	<del>0.076</del> 0.075	0.0568	0.108

4

5

Impingement and Entrainment Corrections

1 **Table I-46 on page I-61** of the FSEIS is corrected as follows:

2 **Table I-46. Parameter Values Used in the Monte Carlo Simulation**

RIS	Survey Used	Linear Slope (r)	Upper 95% Confidence Limit of the Slope	Error Mean Square from Regression	CV of Density Data (1979-1990)	EMR	IMR
Alewife	BSS	-0.030	-0.014	0.570	1.245	0.095	0.0020
American Shad	BSS	-0.069	-0.059	0.350	0.744	<del>0.042</del> 0.39	0.0005
Atlantic Tomcod	FSS	-0.040	-0.026	0.490	1.035	0.036	0.0300
Bay Anchovy	FSS	-0.075	-0.061	0.505	0.598	<del>0.213</del> 0.212	0.0040
Blueback Herring	BSS	-0.024	-0.009	0.530	1.488	0.095	0.0040
Bluefish	BSS	-0.038	-0.022	0.580	0.692	0.003	0.0005
Hogchoker	FSS	-0.034	-0.018	0.580	1.679	<del>0.386</del> 0.385	0.0005
Rainbow Smelt	FSS	0.012	0.041	0.576	1.452	0.258	0.0005
Spottail Shiner	BSS	-0.017	-0.005	0.430	1.293	<del>0.352</del> 0.031	0.0070
Striped Bass	BSS	0.040	0.052	0.420	0.528	0.106	0.0080
Weakfish	FSS	-0.047	-0.031	0.560	1.085	0.544	0.0005
White Catfish	FSS	0.007	0.010	0.100	3.520	<del>0.144</del> 0.249	0.0005
White Perch	BSS	-0.062	-0.045	0.610	0.848	<del>0.076</del> 0.075	0.0320

3

1 Table I-47 on page I-63 of the FSEIS is corrected as follows:

2 Table I-47. **Quartiles of the Relative Difference in Cumulative Abundance and**  
 3 **Conclusions for the Strength-of-Connection from the Monte Carlo Simulation**

Taxa	Number of Years	N <sub>0</sub> = 1000				N <sub>0</sub> = 1 x 10 <sup>8</sup>			Strength of Connection Conclusion
		Median	Q1	Q3		Median	Q1	Q3	
Alewife	20	0.33	0.11	0.59		0.32	0.06	0.55	High
	27	0.36	0.15	0.56		0.33	0.14	0.53	
American Shad	20	<del>0.07</del> <b>0.08</b>	<del>-0.04</del> <b>-0.03</b>	<del>0.18</del> <b>0.20</b>		<del>0.09</del> <b>0.08</b>	<del>-0.02</del> <b>-0.03</b>	<del>0.20</del> <b>0.19</b>	Low
	27	<del>0.08</del> <b>0.07</b>	-0.01	<del>0.16</del> <b>0.15</b>		<del>0.08</del> <b>0.07</b>	<del>0.00</del> <b>-0.01</b>	0.16	
Atlantic Tomcod	20	0.14	-0.04	0.32		0.17	-0.01	0.38	Low
	27	0.18	0.04	0.32		0.18	0.02	0.33	
Bay Anchovy	20	<del>0.21</del> <b>0.19</b>	<del>0.09</del> <b>0.08</b>	<del>0.32</del> <b>0.31</b>		0.20	0.08	0.31	High
	27	<del>0.18</del> <b>0.19</b>	0.10	<del>0.26</del> <b>0.28</b>		0.18	<del>0.10</del> <b>0.09</b>	<del>0.27</del> <b>0.28</b>	
Blueback Herring	20	0.30	0.02	0.60		0.28	0.02	0.60	High
	27	0.43	0.16	0.67		0.40	0.14	0.64	
Bluefish	20	0.13	-0.04	0.29		0.14	-0.03	0.30	Low
	27	0.14	0.02	0.29		0.16	0.01	0.30	
Hogchoker	20	<del>0.71</del> <b>0.72</b>	<del>0.39</del> <b>0.37</b>	<del>1.05</del> <b>1.06</b>		<del>0.74</del> <b>0.76</b>	<del>0.41</del> <b>0.42</b>	<del>1.10</del> <b>1.09</b>	High
	27	<del>0.81</del> <b>0.76</b>	<del>0.53</del> <b>0.50</b>	<del>1.10</del> <b>1.09</b>		<del>0.77</del> <b>0.84</b>	<del>0.46</del> <b>0.56</b>	<del>1.06</del> <b>1.13</b>	
Rainbow Smelt	20	0.77	0.33	1.25		0.81	0.35	1.34	High
	27	0.93	0.52	1.38		1.03	0.63	1.46	
Spottail Shiner	20	<del>0.59</del> <b>0.20</b>	<del>0.33</del> <b>-0.07</b>	<del>0.88</del> <b>0.43</b>		<del>0.58</del> <b>0.18</b>	<del>0.23</del> <b>-0.06</b>	<del>0.90</del> <b>0.42</b>	High Low
	27	<del>0.61</del> <b>0.22</b>	<del>0.36</del> <b>0.01</b>	<del>0.88</del> <b>0.42</b>		<del>0.62</del> <b>0.23</b>	<del>0.35</del> <b>0.01</b>	<del>0.87</del> <b>0.46</b>	
Striped Bass	20	0.45	0.09	0.76		0.45	0.12	0.78	High
	27	0.62	0.27	1.02		0.66	0.31	1.01	
Weakfish	20	0.62	0.39	0.87		0.66	0.42	0.90	High
	27	0.63	0.43	0.84		0.64	0.43	0.83	
White Catfish	20	<del>0.19</del> <b>0.40</b>	<del>-0.36</del> <b>-0.20</b>	<del>0.76</del> <b>0.98</b>		<del>0.05</del> <b>0.37</b>	<del>-0.46</del> <b>-0.18</b>	<del>0.66</del> <b>1.00</b>	Low
	27	<del>0.09</del> <b>0.39</b>	<del>-0.44</del> <b>-0.15</b>	<del>0.58</del> <b>0.91</b>		<del>0.09</del> <b>0.37</b>	<del>-0.43</del> <b>-0.19</b>	<del>0.58</del> <b>0.99</b>	
White Perch	20	<del>0.16</del> <b>0.18</b>	<del>0.01</del> <b>0.03</b>	<del>0.32</del> <b>0.35</b>		<del>0.20</del> <b>0.19</b>	<del>0.04</del> <b>0.03</b>	<del>0.35</del> <b>0.34</b>	High
	27	<del>0.18</del> <b>0.19</b>	<del>0.06</del> <b>0.07</b>	<del>0.34</del> <b>0.30</b>		<del>0.20</del> <b>0.17</b>	<del>0.07</del> <b>0.06</b>	<del>0.34</del> <b>0.30</b>	



### 3.0 ASSESSMENT OF THERMAL IMPACTS

In the FSEIS, the NRC staff concluded that the potential impacts of the cooling water discharge from IP2 and IP3 on aquatic species could range from SMALL to LARGE because the staff did not have enough information to quantify the extent and magnitude of the IP2 and IP3 thermal plume. Since publication of the FSEIS, the NRC has obtained additional information from Entergy regarding the thermal plume that enables the staff to make a more informed conclusion regarding thermal impacts.

In January 2011, Entergy submitted to the NYSDEC a preliminary report on a triaxial plume study (Swanson et al. 2011a) as part of its SPDES permit renewal application. Entergy undertook this study in response to the NYSDEC's 2010 Notice of Denial (NYSDEC 2010), which noted that Entergy's previous thermal study (Swanson et al. 2010) did not directly address the period of highest river temperatures, and as such, would require additional confirmatory monitoring to determine whether any modeled results accurately show compliance with thermal standards. The NYSDEC provided Entergy with comments on the new Swanson et al. (2011a) study in March 2011. Within the same month, Mendelsohn et al. (2011) and Swanson et al. (2011b) prepared responses to the NYSDEC staff's review of the study. In a letter dated May 16, 2011, NYSDEC (2011) notified NYSDEC Judges M.E. Villa and D.P. O'Connell that it had finished reviewing the data and information contained in both the study and the response to NYSDEC's comments and that, based on this information and applicable regulations, the NYSDEC staff had determined the following:

... a thermal mixing zone in the Hudson River near Indian Point not to exceed a maximum of seventy-five (75) acres in total size during any time of a given year (6 NYCRR §704.3) will provide reasonable assurance of compliance with water quality standards and criteria for thermal discharges set forth in 6 NYCRR §§704.1 and 704.2, respectively.

Based on Swanson et al.'s (2011a) triaxial thermal plume study, Mendelsohn et al. (2011) and Swanson et al.'s (2011b) responses to NYSDEC staff comments on the study, and NYSDEC staff's (2011) conclusions regarding the study, the NRC staff has revised its discussion of and conclusions regarding thermal impacts to aquatic species, which appear in Section 4.1.4 of the FSEIS.

Lines 16–26 on page 4-30 in Section 4.1.4.3 of the FSEIS are changed as follows:

~~Entergy has been engaged in discussions with the NYSDEC concerning the thermal impacts of IP2 and IP3 cooling water system operation. As a result of those discussions, the NRC staff notes that Entergy recently performed a triaxial thermal study of the Hudson River from September 9 to November 1 of 2009 (Entergy 2010). Given the months involved in this study, the study period did not include days with the highest average annual water temperature. Entergy has indicated that it will perform modeling of the river based on its field data in order to determine whether the power plant is in compliance with conditions of its permit; it also indicated that it may conduct additional monitoring in 2010. The NYSDEC, in its recent Notice of Denial of Water Quality Certification, indicated that additional verification of any modeled results would be necessary (NYSDEC 2010). Entergy did conduct additional studies in 2010. This issue continues to be subject to NYSDEC authority and review.~~

## Assessment of Thermal Impacts

1 In February 2010, Entergy submitted to NYSDEC a preliminary report  
2 (Swanson et al. 2010) on a triaxial thermal study of the Hudson River  
3 performed during the period of September 9 to November 1, 2009.  
4 Because the study did not directly address the period of highest river  
5 temperatures, the NYSDEC directed Entergy to perform additional  
6 confirmatory monitoring to determine whether any modeled results  
7 accurately show compliance with thermal standards (NYSDEC 2010). In  
8 January 2011, Entergy submitted to the NYSDEC a new triaxial plume  
9 study (Swanson et al. 2011a).

10 In the new study, Swanson et al. (2011a) reported that the extent and  
11 shape of the thermal plume varied greatly, primarily in response to tidal  
12 currents. For example, the plume (illustrated as a 4°F (2.2°C)  
13 temperature increase or  $\Delta T$  isotherm in Figure 5-6 of Swanson et al.  
14 2011a) generally followed the eastern shore of the Hudson River and  
15 extended northward from IP2 and IP3 during flood tide and southward  
16 from IP2 and IP3 during ebb tide. Depending on tides, the plume can be  
17 reasonably easily identified and can reach a portion of the near-shore  
18 bottom or be largely confined to the surface of the river.

19 Temperature measurements reported by Swanson et al. (2011a)  
20 generally show that the warmest water in the thermal plume is close to  
21 the surface, and plume temperatures tend to decrease with depth. A  
22 cross-river survey conducted in front of IP2 and IP3 captured one such  
23 incident during spring tide on July 13, 2010 (Figure 3-28 in Swanson et  
24 al. 2011a). Across most of the river, water temperatures were close to  
25 82°F (28°C), often with warmer temperatures near the surface and  
26 cooler temperatures near the bottom. The IP2 and IP3 thermal plume at  
27 that point was clearly defined and extended about 1,000 feet (ft)  
28 (300 meters (m)) from shore on a cross-river transect of about 3800 ft  
29 (1150 m) (interpreted from the figure). Surface water temperatures in  
30 the plume reached about 85°F (29°C). Maximum river depth along the  
31 measured transect is approximately 50 ft (15 m).

32 A temperature contour plot at a cross-river transect at IP2 and IP3  
33 illustrates a similar condition on July 11, 2010, during slack before flood  
34 tide (Figure 1-10 in Swanson et al. 2011b). Here, the thermal plume is  
35 evident to about 2,000 ft (600 m) from the eastern shore (the location of  
36 the IP2 and IP3 discharge) and extends to a depth of about 35 ft (11 m)  
37 along the eastern shore. The river here is more than 4,500 ft (1,400 m)  
38 wide. Bottom temperatures above 82°F (28°C) were confined to about  
39 the first 250 ft (76 m) from shore. In that small area, bottom water  
40 temperatures might also exceed 86°F (30°C); elsewhere, bottom water  
41 temperatures were about 80°F (27°C). The NRC staff notes, however,  
42 that these limited-area conditions would not last long, as they would  
43 change with the tidal cycle.

44 In response to NYSDEC's review of the IP2 and IP3 thermal studies  
45 (Swanson et al. 2011a), Mendelsohn et al. (2011) modeled the maximum  
46 area and width of the thermal plume (defined by the 4°F (2.2°C)  $\Delta T$   
47 isotherms) in the Hudson River. Mendelsohn et al. (2011) reported that  
48 for four cross-river transects near IP2 and IP3, the maximum cross-river  
49 area of the plume would not exceed 12.3 percent of the river cross-



1 section, and the maximum cross-river width of the plume would not  
 2 exceed 28.6 percent of the river width (Table 3-1 in Mendelsohn et al.  
 3 2011).

4 Swanson et al. (2011a) concluded that IP2 and IP3 are in compliance  
 5 with NYSDEC water quality standards set forth at 6 NYCRR Part 704.

6 After line 43 on page 4-31 of Section 4.1.4.4 of the FSEIS, the following text is to be added:

7 In response to the NYSDEC’s 2010 Notice of Denial (NYSDEC 2010),  
 8 Entergy submitted a new triaxial plume study (Swanson et al. 2011a) to  
 9 the NYSDEC in January 2011. NYSDEC provided Entergy with  
 10 comments on the new study (Swanson et al. 2011a) in March 2011.  
 11 Within the same month, Mendelsohn et al. (2011) and Swanson et al.  
 12 (2011b) prepared responses to the NYSDEC staff’s review of the study.  
 13 In a May 2011 letter (NYSDEC 2011), NYSDEC staff notified NYSDEC  
 14 Judges M.E. Villa and D.P. O’Connell that NYSDEC staff had finished  
 15 reviewing the data and information contained in both the study and the  
 16 response to NYSDEC’s comments and that, based on this information  
 17 and applicable regulations, NYSDEC staff had determined the following:

18 a thermal mixing zone in the Hudson River near Indian Point not  
 19 to exceed a maximum of seventy-five (75) acres in total size  
 20 during any time of a given year (6 NYCRR §704.3) will provide  
 21 reasonable assurance of compliance with water quality  
 22 standards and criteria for thermal discharges set forth in 6  
 23 NYCRR §§704.1 and 704.2, respectively.

24 Lines 2–26 on page 4-32 in Section 4.1.4.5 of the FSEIS are corrected as follows:

25 ~~In the absence of a completed thermal study proposed by NYSDEC (or~~  
 26 ~~an alternative proposed by Entergy and accepted by NYSDEC), existing~~  
 27 ~~information must be used to determine the appropriate thermal impact~~  
 28 ~~level to sensitive life stages of important aquatic species. Since~~  
 29 ~~NYSDEC modeling in the FEIS (NYSDEC 2003a) indicates that~~  
 30 ~~discharges from IP2 and IP3 could raise water temperatures to a level~~  
 31 ~~greater than that permitted by water quality criteria that are a~~  
 32 ~~component of existing NYSDEC permits, the staff must conclude that~~  
 33 ~~adverse impacts are possible. Cold water fish species such as Atlantic~~  
 34 ~~tomcod and rainbow smelt may be particularly vulnerable to~~  
 35 ~~temperature changes caused by thermal discharges. The population of~~  
 36 ~~both species has declined, and rainbow smelt may have been extirpated~~  
 37 ~~from the Hudson River. The NYSDEC’s issuance of a SPDES permit~~  
 38 ~~provides a basis to conclude that the thermal impacts of IP2 and IP3~~  
 39 ~~discharges could meet applicable regulatory temperature criteria. The~~  
 40 ~~NYSDEC’s recent pronouncements and its ongoing re-examination of~~  
 41 ~~this issue create uncertainty, and this issue is currently being~~  
 42 ~~addressed in NYSDEC administrative proceedings. Accordingly, in the~~  
 43 ~~absence of specific studies, and in the absence of results sufficient to~~  
 44 ~~make a determination of a specific level of impact, the NRC staff~~  
 45 ~~concludes that thermal impacts from IP2 and IP3 potentially could range~~  
 46 ~~from SMALL to LARGE depending on the extent and magnitude of the~~  
 47 ~~thermal plume, the sensitivity of various aquatic species and life stages~~  
 48 ~~likely to encounter the thermal plume, and the probability of an~~

## Assessment of Thermal Impacts

~~encounter occurring that could result in lethal or sublethal effects. This range of impact levels expresses the uncertainty accruing from the current lack of studies and data. Either additional thermal studies or modeling and verification of Entergy's 2009 thermal study might generate data to further refine or modify this impact level. For the purposes of this Final SEIS, the NRC staff concludes that the impact level could range from SMALL to LARGE. This conclusion is meant to satisfy NRC's NEPA obligations and is not intended to prejudice any determination the NYSDEC may reach in response to new studies and information submitted to it by Entergy.~~

NRC regulations for license renewal environmental reviews establish the primary role of the U.S. Environmental Protection Agency (EPA) (or States, when applicable) in water quality regulations as they relate to impacts on aquatic species. As such, the assessment of impacts from heat shock is within the purview of the responsible government agency. In the case of IP2 and IP3, NYSDEC is the responsible agency.

NYSDEC regulations at 6 NYCRR Part 704 establish specific standards that apply to thermal discharges within the State of New York. The standards are set to “assure the protection and propagation of a balanced, indigenous population of shellfish, fish, and wildlife in and on the body of water” to which heated water is discharged (6 NYCRR 704.1(a)). Section 4.1.4.4 of this FSEIS supplement describes the thermal plume studies (Swanson et al. 2010, 2011a) that Entergy submitted to NYSDEC and NYSDEC's (2011) conclusions regarding these studies. NYSDEC concluded that the results of the thermal plume studies provide reasonable assurance that the IP2 and IP3 discharge is in compliance with NYSDEC's water quality standards and criteria for thermal discharges.

Based on Entergy's thermal plume studies and NYSDEC's conclusions, the NRC staff concludes that the impacts from heat shock to aquatic resources of the lower Hudson River would be SMALL.

This change in the NRC staff's conclusion regarding thermal impacts (heat shock) also affects the Abstract, Executive Summary, Alternatives, and Summary sections of the FSEIS. The NRC staff has revised parts of these sections, as described below.

**Line 37 on page iii through line 2 on page iv** of the FSEIS Abstract are changed as follows:

Overall effects from entrainment and impingement are likely to be MODERATE, and impacts from heat shock are likely to be SMALL. ~~Impacts from heat shock potentially range from SMALL to LARGE depending on the conclusions of thermal studies proposed by the New York State Department of Environmental Conservation (NYSDEC).~~

**Lines 33–39 on page xviii** of the FSEIS Executive Summary are changed as follows:

The NRC staff concludes that the potential environmental effects for most of these issues are of SMALL significance in the context of the standards set forth in the GEIS with ~~three two~~ exceptions—~~entrainment, and impingement, and heat shock from the facility's heated discharge~~. The NRC staff jointly assessed the impacts of entrainment and impingement to be MODERATE based on NRC's analysis of representative important species. ~~Impacts from~~

1 ~~heat shock potentially range from SMALL to LARGE depending on the~~  
2 ~~conclusions of thermal studies conducted by Entergy and submitted to~~  
3 ~~the NYSDEC.~~

4 **Line 43 on page 8-8 through line 3 on page 8-9** of Section 8.1.1.2 are changed as follows:

5 Because the closed-cycle cooling system discharges a smaller volume of  
6 water, and because the water is cooler than in a once-through system, the  
7 extent of thermal impacts ~~—which could range from SMALL to LARGE for~~  
8 ~~the current once-through system, given uncertainty in the facility's~~  
9 ~~thermal impacts— would remain SMALL be reduced. Thus, the effects~~  
10 ~~of thermal shock also decline.~~

11 **Lines 35–40 on page 9-4** of Section 9.1 are changed as follows:

12 The NRC staff concludes that the potential environmental effects for **9 10** of  
13 the 12 categorized issues are of SMALL significance in the context of the  
14 standards set forth in the GEIS. The NRC staff concludes that the combined  
15 impacts from impingement and entrainment (each a separate issue) are  
16 MODERATE. ~~Impacts from heat shock could range from SMALL to~~  
17 ~~LARGE, based on the large uncertainties discussed in Chapter 4.~~

18 **Lines 8–13 on page 9-5** of Section 9.1 are changed as follows:

19 For issues of MODERATE ~~or LARGE~~ significance (i.e., issues related to aquatic ecology),  
20 mitigation measures are addressed both in Chapter 4 and in Chapter 8 as alternatives based on  
21 determinations in the draft New York State Department of Environmental Conservation  
22 (NYSDEC) State Pollutant Discharge Elimination System (SPDES) permit proceeding, Clean  
23 Water Act Section 401 proceeding, and in draft policy statements published by the State.



## 4.0 SECTION 7 CONSULTATION

At the time the NRC staff published the FSEIS, the NRC and NMFS had not completed section 7 consultation under the Endangered Species Act of 1973, as amended (ESA) for the shortnose sturgeon (*Acipenser brevirostrum*). During the course of the section 7 consultation, the NRC staff obtained more studies and information on the thermal plume (previously discussed in Chapter 3 of this document). As a result, the NRC staff has revised its conclusions regarding thermal impacts to the shortnose sturgeon based on this new thermal modeling information. Section 2.2.5.5 of the FSEIS, which includes the shortnose sturgeon's life history, remains unchanged. The staff identified one correction to Section 4.6.1 of the FSEIS, shown below.

In addition to supplementing the FSEIS for the reasons stated in Chapter 1 of this supplement, the staff is also taking this opportunity to provide an update on the status of its consultation with NMFS related to Indian Point Nuclear Generating Unit Nos. 2 and 3 (IP2 and IP3). This chapter provides an update on the section 7 consultation history provided in Section 4.6.1 of the FSEIS, as well as a summary of the biological opinion that NMFS issued in October 2011 as a result of consultation. This chapter also provides a summary of the reinitiation of consultation regarding the Atlantic sturgeon (*Acipenser oxyrinchus oxyrinchus*). Consultation with NMFS regarding the Atlantic sturgeon was reinitiated as a result of NMFS's February 2012 listing of Atlantic sturgeon as an endangered species under the ESA.

### 4.1 Corrections to Section 4.6.1, "Aquatic Special Status Species"

In the FSEIS, the NRC staff concluded that the potential impacts of heated discharge from IP2 and IP3 on shortnose sturgeon could not be determined because the staff did not have enough information to quantify the extent and magnitude of the IP2 and IP3 thermal plume. Since publication of the FSEIS, the NRC staff has obtained additional information on the IP2 and IP3 thermal plume. Chapter 3 of this document describes the new thermal plume information. Based on Swanson et al.'s (2011a) triaxial thermal plume study, Mendelsohn et al. (2011) and Swanson et al. (2011b)'s responses to NYSDEC staff comments on the study, and NYSDEC staff's (2011) conclusions regarding the study, the NRC staff has revised its discussion regarding thermal impacts to shortnose sturgeon, which appears in Section 4.6.1 of the FSEIS.

Lines 40–43 on page 4-58 in Section 4.6.1 of the FSEIS are changed as follows:

~~The potential impacts of thermal discharges on shortnose and Atlantic sturgeon cannot be determined at this time because additional studies are required to quantify the extent and magnitude of the thermal plume, as discussed in Section 4.1.4 of this SEIS.~~

**In July 2011, the NRC (2011c) supplemented its analysis of the thermal effects from IP2 and IP3 on the shortnose sturgeon that was presented in NRC's (2010) December 2010 revised biological assessment. The NRC staff's (2011c) supplement to the revised biological assessment considered newly available thermal plume information (Swanson et al. 2011a, 2011b; Mendelsohn et al. 2011; NYSDEC 2011) as well as various studies on shortnose sturgeon biology and thermal preferences (Dadswell 1979; Dadswell et al. 1984; Heidt and Gilbert 1978; Ziegeweid et al. 2008a, 2008b). In its July 2011 supplement, the NRC (2011c) concluded that the proposed license renewal of IP2 and IP3 is not likely to adversely affect the Hudson River population of shortnose sturgeon.**

**NMFS issued its biological opinion in October 2011 (NMFS 2011e). In its biological opinion, NMFS concluded that shortnose sturgeon are likely to avoid the small area of water elevated above the species' preferred temperature range and that—**

## Section 7 Consultation

1 **it is extremely unlikely that these minor changes in behavior will**  
2 **preclude shortnose sturgeon from completing any essential behaviors**  
3 **such as resting, foraging or migrating or that the fitness of any**  
4 **individuals will be affected.**

5 **Based on the NRC's (2011c) previous analysis and NMFS's (2011e) biological opinion,**  
6 **the NRC staff concludes that the heated discharge resulting from the proposed IP2 and**  
7 **IP3 license renewal would have SMALL impacts on the shortnose sturgeon.**

### 8 **4.2 History of Section 7 Consultation for Shortnose Sturgeon**

9 Under section 7 of the ESA, the NRC staff (2008b) initiated consultation with NMFS in a letter  
10 dated December 22, 2008, upon publication of the draft supplemental environmental impact  
11 statement (SEIS) and the staff's (NRC 2008a) original biological assessment, which found that  
12 the relicensing of IP2 and IP3 could adversely affect the shortnose sturgeon, which had been  
13 listed as endangered under the ESA in 1967. In response to that biological assessment, on  
14 February 24, 2009, NMFS (2009) requested additional information from the NRC. NMFS stated  
15 that it required this information before it could begin formal consultation. On July 1, 2009, the  
16 NRC staff obtained the relevant information from Entergy (2009). On August 10, 2009, the NRC  
17 (2009) provided that information (including revised impingement data) to NMFS and stated that  
18 the data would be addressed in the FSEIS and in a revised biological assessment. The NRC  
19 staff published its FSEIS in December 2010 and transmitted its revised biological assessment to  
20 NMFS on December 10, 2010 (NRC 2010b).

21 On February 16, 2011, NMFS (2011) formally responded to the NRC staff's letter of  
22 December 10, 2010, and stated that (1) NMFS currently has all the information it needs to  
23 complete a formal consultation, (2) NMFS considers formal consultation to have begun on  
24 December 16, 2010, (3) NMFS expects the consultation will conclude within 90 days after it  
25 began (i.e., by March 16, 2011) unless extended, and (4) NMFS expects to issue its biological  
26 opinion by April 30, 2011. On March 1, 2011, Entergy (2011a) formally notified the NRC staff  
27 that it will participate in the consultation process and requested a 45-day extension of the  
28 consultation conclusion date in accordance with 50 CFR 402.14(e).

29 In teleconferences on March 9 and March 11, 2011, NMFS and the NRC staff discussed  
30 extending the consultation to allow time for Entergy to submit additional information on the  
31 shortnose sturgeon pertinent to the consultation (NRC 2011h). NMFS formally extended the  
32 consultation period in a March 16, 2011, letter (NMFS 2011a) for a period of 60 days until June  
33 29, 2011, in accordance with 50 CFR 402.14(e). On April 18, 2011, the NRC staff (2011a) held  
34 a Category 1 public meeting during which Entergy presented a data synthesis on the shortnose  
35 sturgeon updated with the most recent annual Hudson River monitoring reports. On April 28,  
36 2011, Entergy (2011c) formally submitted to the NRC the information it had presented during  
37 this public meeting.

38 On June 16, 2011, the NRC staff learned that Entergy had submitted a final, verified triaxial  
39 thermal model to NYSDEC concerning aquatic conditions at IP2 and IP3. The staff also learned  
40 that NYSDEC had relied on that model and Entergy's associated information to reach  
41 conclusions about thermal conditions at Indian Point for inclusion in a draft SPDES permit  
42 (NYSDEC 2011). The NRC staff (2011b) brought this information to NMFS's attention in an e-  
43 mail to NMFS on June 16, 2011.

44 The NRC staff held three teleconferences with NMFS and Entergy during the weeks of June 20  
45 and June 27, 2011 (NRC 2011d). On June 20, 2011, the NRC staff and NMFS discussed the  
46 NRC's statutory authority to implement terms and conditions or reasonable and prudent

1 measures identified in a biological opinion. On June 22, 2011, the NRC staff, NMFS, and  
 2 Entergy discussed NMFS's outstanding questions on thermal impacts, impingement, and  
 3 entrainment of prey species and the design of the IP2 and IP3 cooling system. The NRC staff  
 4 also requested that Entergy formally submit to NRC the thermal modeling information that  
 5 Entergy had given to NYSDEC. By letter dated June 29, 2011, Entergy (2011d) formally  
 6 submitted to the NRC various documents related to the thermal studies it had conducted.  
 7 During a teleconference on June 29, 2011, the NRC staff, NMFS, and Entergy addressed  
 8 questions that had arisen during the teleconference on June 22, 2011, and the parties agreed to  
 9 a revised consultation schedule in which the consultation would end by September 20, 2011,  
 10 provided that Entergy and the NRC staff would supply NMFS with the information related to  
 11 NMFS's outstanding questions in a timely manner. The NRC staff (2011c) supplemented its  
 12 revised biological assessment on July 26, 2011, as a result of the information that Entergy  
 13 submitted to the staff on June 29, 2011.

14 NMFS (2011b) issued a draft biological opinion on August 26, 2011. In an e-mail dated  
 15 September 6, 2011, the NRC staff provided NMFS with Entergy's comments on the draft  
 16 biological opinion (NRC 2011f). In a separate e-mail on the same day, the staff submitted its  
 17 comments on the draft biological opinion (NRC 2011e). The NRC staff stated that its comments  
 18 on the draft biological opinion were complete and that it would respond to the procedural issues  
 19 raised in NMFS's cover letter to the draft biological opinion in a separate letter. On  
 20 September 19, 2011, NMFS (2011c) requested more time to complete the final biological  
 21 opinion. On September 20, 2011, the NRC staff (2011g) sent its letter addressing the issues  
 22 NMFS had raised in the cover letter to its draft biological opinion.

23 NMFS (2011d, 2011e) issued its final biological opinion for shortnose sturgeon on  
 24 October 14, 2011, which concluded the section 7 consultation for the IP2 and IP3 license  
 25 renewal. The NMFS biological opinion is discussed below.

### 26 **4.3 Summary of the National Marine Fisheries Service's Biological Opinion for** 27 **Shortnose Sturgeon**

28 NMFS's (2011d, 2011e) biological opinion includes an incidental take statement for shortnose  
 29 sturgeon and stipulates a number of reasonable and prudent measures, as well as terms and  
 30 conditions with which the NRC and Entergy must comply to be exempt from prohibitions of  
 31 section 9 of the ESA.

32 Under the biological opinion, IP2 and IP3 may take up to the following numbers of shortnose  
 33 sturgeon during the terms of their renewed operating licenses, which NMFS assumed would not  
 34 begin before the completion of the initial operating licenses for IP2 and IP3:

- 35 • 6 shortnose sturgeon at Unit 1,
- 36 • 104 shortnose sturgeon at Unit 2, and
- 37 • 58 shortnose sturgeon at Unit 3

38 NMFS included Unit 1, even though it is not in operation, because Unit 2 uses water from the  
 39 Unit 1 intake as service water.

40 The biological opinion stipulates four reasonable and prudent measures that require Entergy to  
 41 (1) implement an NMFS-approved monitoring program, (2) release all live sturgeon back to the  
 42 Hudson River, (3) transfer any dead sturgeon to NMFS for necropsy, and (4) report all  
 43 shortnose sturgeon impingements or sightings to NMFS. The terms and conditions provide  
 44 NRC and Entergy with more specific details on how the reasonable and prudent measures must  
 45 be carried out. The terms and conditions can be found on pages 64–67 of the biological

## Section 7 Consultation

1 opinion. If the NRC renews the IP2 and/or IP3 licenses, compliance with the terms and  
2 conditions of the biological opinion will be required, as appropriate<sup>1</sup>.

### 3 **4.4 Reinitiation of Consultation Due to NMFS's Listing of Atlantic Sturgeon**

4 On February 6, 2012, the NMFS listed five distinct population segments (DPSs) of the Atlantic  
5 sturgeon (*Acipenser oxyrinchus oxyrinchus*) under the ESA (77 FR 5880; 77 FR 5914). In the  
6 Hudson River near Indian Point, Atlantic sturgeon belong to the New York Bight DPS, which  
7 NMFS listed as endangered. The NRC staff had previously addressed the environmental  
8 impacts of license renewal on the Atlantic sturgeon in the final SEIS and had requested that  
9 NMFS conduct a section 7 conference with the staff regarding the Atlantic sturgeon, which was  
10 proposed for listing at that time. On May 16, 2012, in response to the listing, the NRC  
11 staff (2012) prepared and submitted a biological assessment to NMFS, along with a request to  
12 reinitiate section 7 consultation for the newly-listed Atlantic sturgeon. The NRC staff expects to  
13 continue consultation with NMFS in 2012 regarding Atlantic sturgeon at IP2 and IP3, and will  
14 consider the results of that consultation, as appropriate.

---

<sup>1</sup> The biological opinion states: "This [incidental take statement] ITS applies to the extended operating period, beginning at the date that the facility begins to operate under the terms of a new license and extending through the expiration date of that license." (NMFS 2011e)



## 5.0 REFERENCES

- 1
- 2 *References that appear with an Agencywide Documents Access and Management System*  
3 *(ADAMS) accession number can be accessed through NRC's web-based ADAMS at the*  
4 *following URL: <http://adams.nrc.gov/wba/>.*
- 5 77 FR 5880. National Oceanic and Atmospheric Administration. "Endangered and Threatened  
6 Wildlife and Plants; Final Listing Determinations for Two Distinct Population Segments of  
7 Atlantic Sturgeon (*Acipenser oxyrinchus oxyrinchus*) in the Northeast." *Federal Register*  
8 77(24):5880-5912. February 6, 2012.
- 9 77 FR 5914. National Oceanic and Atmospheric Administration. "Endangered and Threatened  
10 Wildlife and Plants; Final Listing Determinations for Two Distinct Population Segments of  
11 Atlantic Sturgeon (*Acipenser oxyrinchus oxyrinchus*) in the Southeast." *Federal Register*  
12 77(24):5914-5982. February 6, 2012.
- 13 *Endangered Species Act of 1973. 16 U.S.C. 1531, et seq.*
- 14 [AKRF] AKRF, Inc. 2011a. Review of Estimates of Numbers Entrained Presented in NRC 2009  
15 EFH Assessment and 2010 FSEIS. ADAMS Accession No. ML11286A140.
- 16 [AKRF] AKRF, Inc. 2011b. *Technical Review of FSEIS for Indian Point Nuclear Generating*  
17 *Unit Nos. 2 and 3; Sections 4.1.1–4.1.3 and Appendices H and I.* Prepared for Entergy Nuclear  
18 Operations, Inc. Hanover, MD: AKRF, Inc. March 28, 2011. ADAMS Accession No.  
19 ML110980163.
- 20 [CHGEC et al.] Central Hudson Gas and Electric Corporation, Consolidated Edison Company  
21 of New York, Inc., New York Power Authority, and Southern Energy New York. 1999. *Draft*  
22 *Environmental Impact Statement for State Pollutant Discharge Elimination System Permits for*  
23 *Bowline Point, Indian Point 2 and 3, and Roseton Steam Electric Generating Stations.*  
24 December 1999. ADAMS Accession No. ML083400128.
- 25 Dadswell, MJ. 1979. Biology and population characteristics of the shortnose sturgeon,  
26 *Acipenser brevirostrum* LeSueur 1818 (Osteichthyes: Acipenseridae), in the Saint John River  
27 estuary, New Brunswick, Canada. *Canadian Journal of Zoology* 57:2186–2210.
- 28 Dadswell MJ, BD Taubert, TS Squiers, D Marchette, and J Buckley. 1984. Synopsis of  
29 biological data on shortnose sturgeon, *Acipenser brevirostrum* LeSueur 1818. NOAA Technical  
30 Report NMFS-14. Washington, DC: National Marine Fisheries Service. October 1984. 45 pp.  
31 Available at <[http://www.nmfs.noaa.gov/pr/pdfs/species/shortnosesturgeon\\_biological\\_](http://www.nmfs.noaa.gov/pr/pdfs/species/shortnosesturgeon_biological_data.pdf)  
32 [data.pdf](http://www.nmfs.noaa.gov/pr/pdfs/species/shortnosesturgeon_biological_data.pdf)> (accessed January 12, 2012).
- 33 [Entergy] Entergy Nuclear Operations, Inc. 2007. Letter from F. Dacimo, Vice President of  
34 Operations License Renewal, Entergy, to NRC Document Control Desk. Subject: Supplement  
35 to License Renewal Application—Environmental Report References. December 20, 2007.  
36 ADAMS Accession Nos. ML080080199. Long River Survey: ML11279A044 and Fall Shoals  
37 Survey: ML080080291, ML080080298, ML080080306.
- 38 [Entergy] Entergy Nuclear Operations, Inc. 2009. Letter from F. Dacimo, Vice President of  
39 License Renewal, to Document Control Desk, NRC. Subject: Transmission of additional  
40 requested information regarding sturgeon impingement data. July 1, 2009. ADAMS Accession  
41 No. ML091950345.
- 42 [Entergy] Entergy Nuclear Operations, Inc. 2011a. Letter from F. Dacimo, Vice President of  
43 License Renewal, Entergy, to A. Stuyvenberg, Project Manager, NRC. Subject: Endangered

## References

- 1 Species Act consultation for Indian Point Nuclear Generating Unit Nos. 2 and 3. March 1, 2011.  
2 ADAMS Accession No. ML110670270.
- 3 [Entergy] Entergy Nuclear Operations, Inc. 2011b. Letter from F. Dacimo, Vice President of  
4 Operations License Renewal, to B. Holian, Division Director, NRC. Subject: Comments on final  
5 supplemental environmental impact statement for Indian Point Nuclear Generating. March 29,  
6 2011. ADAMS Accession No. ML110980073.
- 7 [Entergy] Entergy Nuclear Operations, Inc. 2011c. Letter from F. Dacimo, Vice President of  
8 License Renewal, Entergy, to A. Stuyvenberg, Project Manager, NRC. Subject: Endangered  
9 Species Act consultation for Indian Point Nuclear Generating Unit Nos. 2 and 3. April 28, 2011.  
10 ADAMS Accession No. ML11125A071.
- 11 [Entergy] Entergy Nuclear Operations, Inc. 2011d. Letter from F. Dacimo, Vice President of  
12 License Renewal, Entergy, to NRC Document Control Desk. Subject: License renewal thermal  
13 study documents for Indian Point Unit Nos. 2 and 3. June 29, 2011. ADAMS Accession No.  
14 ML11189A026.
- 15 [Goodwin Proctor] Goodwin Proctor LLP. 2011. Letter from Elise N. Zoli, Goodwin Proctor LLC  
16 to David Wrona, Chief, Projects Branch 2, Division of License Renewal, U.S. Nuclear  
17 Regulatory Commission. Subject: Indian Point License Renewal - Entergy's Comments on  
18 NMFS' Essential Fish Habitat Consultation Correspondence. September 30, 2011. ADAMS  
19 Accession No. ML11286A140.
- 20 Heidt AR, and RJ Gilbert. 1978. The shortnose sturgeon in the Altamaha River drainage,  
21 Georgia. In: RR Odum and L Landers, editors. *Proceedings of the Rare and Endangered*  
22 *Wildlife Symposium*. Georgia Department of Natural Resources, Game and Fish Division,  
23 Technical Bulletin WL-4. p 54–60.
- 24 Mendelsohn D, C Swanson, and D Crowley. 2011. *Part 1 of Response to the NYSDEC Staff*  
25 *Review of the 2010 Field Program and Modeling Analysis of the Cooling Water Discharge from*  
26 *the Indian Point Energy Center*. Prepared for Entergy Nuclear Indian Point 2, LLC and Entergy  
27 Nuclear Indian Point 3, LLC. South Kingstown, RI: Applied Science Associates, Inc. March 31,  
28 2011. 13 p. Available at <[http://www.dec.ny.gov/docs/permits\\_ej\\_operations\\_pdf/](http://www.dec.ny.gov/docs/permits_ej_operations_pdf/indnptpart1resp.pdf)  
29 [indnptpart1resp.pdf](http://www.dec.ny.gov/docs/permits_ej_operations_pdf/indnptpart1resp.pdf)> (accessed January 11, 2012).
- 30 [NMFS] National Marine Fisheries Service. 2009. Letter from M. Colligan, Northeast Assistant  
31 Regional Administrator for Protected Resources, NMFS, to D. Wrona, Branch Chief, NRC.  
32 Subject: Biological assessment for license renewal of Indian Point Nuclear Generating Unit Nos.  
33 2 and 3. February 24, 2009. ADAMS Accession No. ML090820316.
- 34 [NMFS] National Marine Fisheries Service. 2011. Letter from P. Kurkul, Northeast Regional  
35 Administrator, to D. Wrona, Branch Chief, NRC. Subject: Reply to biological assessment for  
36 license renewal of the Indian Point Nuclear Generating Unit Nos. 2 and 3. February 16, 2011.  
37 ADAMS Accession No. ML110550751.
- 38 [NMFS] National Marine Fisheries Service. 2011a. Letter from P. Kurkul, Northeast Assistant  
39 Regional Administrator for Protected Resources, NMFS, to D. Wrona, Branch Chief, NRC.  
40 Subject: Extension of consultation period—license renewal of the Indian Point Nuclear  
41 Generating Plant, Unit Nos. 2 and 3. March 16, 2011. ADAMS Accession No. ML110830578.
- 42 [NMFS] National Marine Fisheries Service. 2011b. Letter from P. Kurkul, Northeast Assistant  
43 Regional Administrator for Protected Resources, NMFS, to D. Wrona, Branch Chief, NRC.  
44 Subject: Draft biological opinion for license renewal of Indian Point Nuclear Generating Unit  
45 Nos. 2 and 3. August 26, 2011. ADAMS Accession No. ML11249A012.

- 1 [NMFS] National Marine Fisheries Service. 2011c. E-mail from J. Crocker, Fisheries Biologist,  
2 to A. Stuyvenberg, Project Manager, NRC. Subject: Schedule for biological opinion (revised  
3 proposal). September 19, 2011. ADAMS Accession No. ML11300A037.
- 4 [NMFS] National Marine Fisheries Service. 2011d. Letter from P. Kurkul, Northeast Assistant  
5 Regional Administrator for Protected Resources, NMFS, to D. Wrona, Branch Chief, NRC.  
6 Subject: Biological opinion for relicensing of Indian Point Nuclear Generating Unit Nos. 2 and 3.  
7 October 14, 2011. ADAMS Accession No. ML11290A232.
- 8 [NMFS] National Marine Fisheries Service. 2011e. *Biological Opinion for Relicensing—Indian*  
9 *Point Nuclear Generating Station F/NER/2009/00619*. October 14, 2011. ADAMS Accession  
10 No. ML11290A231.
- 11 [NRC] U.S. Nuclear Regulatory Commission. 2008a. *Biological assessment for License*  
12 *Renewal of Indian Point Nuclear Generating Unit Nos. 2 and 3*. Appendix E to draft NUREG-  
13 1437, Supplement 38. 16 p. ADAMS Accession No. ML083540614.
- 14 [NRC] U.S. Nuclear Regulatory Commission. 2008b. Letter from D. Wrona, Branch Chief,  
15 NRC, to M. Colligan, Northeast Assistant Regional Administrator for Protected Resources,  
16 NMFS. Subject: Biological assessment for license renewal of Indian Point Nuclear Generating  
17 Unit Nos. 2 and 3. December 22, 2008. ADAMS Accession No. ML083450723.
- 18 [NRC] U.S. Nuclear Regulatory Commission. 2009. Email from D. Logan, Aquatic Ecologist,  
19 NRC, to J. Crocker, NMFS. Subject: Indian Point Section 7—new data from Entergy. August  
20 10, 2009. ADAMS Accession No. ML092220524.
- 21 [NRC] U.S. Nuclear Regulatory Commission. 2010a. Generic Environmental Impact Statement  
22 for License Renewal of Nuclear Plants: Supplement 38, Regarding Indian Point Nuclear  
23 Generating Unit Nos. 2 and 3. Washington, DC: NRC. NUREG–1437, Supp. 38. December  
24 2010. ADAMS Accession No. ML103270072.
- 25 [NRC] U.S. Nuclear Regulatory Commission. 2010b. Letter from D. Wrona, Branch Chief,  
26 NRC, to M. Colligan, Northeast Assistant Regional Administrator for Protected Resources,  
27 NMFS. Subject: Revised biological assessment for license renewal of the Indian Point Nuclear  
28 Generating Unit Nos. 2 and 3. December 10, 2010. ADAMS Accession No. ML102990043.
- 29 [NRC] U.S. Nuclear Regulatory Commission. 2011a. Summary of public meeting held on Apr.  
30 18, 2011, between NRC and Entergy to discuss Entergy’s shortnose sturgeon and Atlantic  
31 sturgeon data at Indian Point Nuclear Generating Unit Nos. 2 and 3. April 22, 2011. ADAMS  
32 Accession No. ML111090905.
- 33 [NRC] U.S. Nuclear Regulatory Commission. 2011b. E-mail from A. Stuyvenberg, Project  
34 Manager, NRC, to J. Crocker, Fisheries Biologist, NMFS. Subject: Indian Point thermal  
35 information available on New York DEC website. June 16, 2011. ADAMS Accession No.  
36 ML11167A108.
- 37 [NRC] U.S. Nuclear Regulatory Commission. 2011c. Letter from L. Bauer, Acting Branch Chief,  
38 NRC, to M. Colligan, Northeast Assistant Regional Manager for Project Resources, NMFS.  
39 Subject: Supplement to revised biological assessment for license renewal of Indian Point  
40 Nuclear Generating Unit Nos. 2 and 3. July 26, 2011. ADAMS Accession No. ML11203A100.
- 41 [NRC] U.S. Nuclear Regulatory Commission. 2011d. Summary of telephone conference calls  
42 held on Jun. 20, 22, and 29, 2011, regarding the ongoing Endangered Species Act consultation  
43 for the proposed Indian Point Nuclear Generating Unit Nos. 2 and 3 license renewal.  
44 July 29, 2011. ADAMS Accession No. ML11201A306.

## References

- 1 [NRC] U.S. Nuclear Regulatory Commission. 2011e. E-mail from A. Stuyvenberg, Project  
2 Manager, NRC, to J. Crocker, Fisheries Biologist, NMFS. Subject: NRC staff comments on  
3 draft BO for proposed Indian Point license renewal. September 6, 2011. ADAMS Accession  
4 No. ML11249A210.
- 5 [NRC] U.S. Nuclear Regulatory Commission. 2011f. E-mail from A. Stuyvenberg, Project  
6 Manager, NRC, to J. Crocker, Fisheries Biologist, NMFS. Subject: FW: Entergy comments on  
7 draft BO. September 6, 2011. ADAMS Accession No. ML11249A145.
- 8 [NRC] U.S. Nuclear Regulatory Commission. 2011g. Letter from D. Wrona, Branch Chief,  
9 NRC, to P. Kurkul, Northeast Assistant Regional Administrator for Protected Resources, NMFS.  
10 Subject: NMFS Letter dated August 26, 2011, regarding the Endangered Species Act, section 7  
11 consultation for the proposed license renewal of Indian Point Nuclear Generating Unit Nos. 2  
12 and 3. September 20, 2011. ADAMS Accession No. ML11259A018.
- 13 [NRC] U.S. Nuclear Regulatory Commission. 2011h. Summary of telephone conference calls  
14 held on Mar. 8 and Mar. 11, 2011, regarding the ongoing Endangered Species Act consultation  
15 for the proposed Indian Point Nuclear Generating Unit Nos. 2 and 3 license renewal. April 14,  
16 2011. ADAMS Accession No. ML11089A031.
- 17 [NRC] U.S. Nuclear Regulatory Commission. 2012. Letter from J.J. Susco, Acting Chief,  
18 Environmental Review and Guidance Update Branch, Division of License Renewal to Patricia A.  
19 Kurkul, Northeast Regional Administrator, National Marine Fisheries Service. Subject: Request  
20 to Reinitiate Section 7 Consultation for the Indian Point Nuclear Generating Unit Nos. 2 and 3  
21 Due to Listing of Atlantic Sturgeon. May 16, 2012. ADAMS Accession No. ML12100A082.
- 22 [NYSDEC] New York Department of Environmental Conservation. 2010. Letter from W.R.  
23 Adriance, Chief Permit Administrator, NYSDEC to D. Gray, Entergy. Subject: Joint Application  
24 for CWA §401 Water Quality Certification, NRC License Renewal—Entergy Nuclear Indian Point  
25 Units 2 and 3, DEC Nos.: 3-5522-00011/00030 (IP2) and 3-5522-00105/00031 (IP3), Notice of  
26 Denial. April 2, 2010. Available at <[http://www.dec.ny.gov/docs/permits\\_ej\\_operations\\_pdf/  
27 ipdenial4210.pdf](http://www.dec.ny.gov/docs/permits_ej_operations_pdf/ipdenial4210.pdf)> (accessed January 11, 2012).
- 28 [NYSDEC] New York Department of Environmental Conservation. 2011. Letter from M.D.  
29 Sanza, Assistant Counsel, NYSDEC to Administrative law Judges M. Villa and D.P. O'Connell,  
30 NYSDEC Office of Hearings and Mediation Services. Subject: Entergy Indian Point Nuclear  
31 Units 2 and 3 SPDES Permit Renewal/401 WQC Application Proceedings; DEC Staff's Review  
32 of Thermal Information. May 16, 2011. Available at <[http://www.dec.ny.gov/docs/  
33 permits\\_ej\\_operations\\_pdf/indnptsanzaltr.pdf](http://www.dec.ny.gov/docs/permits_ej_operations_pdf/indnptsanzaltr.pdf)> (accessed January 4, 2012).
- 34 Swanson C, Y Kim, D Mendelsohn, D Crowley, and M Mattson. 2010. *Preliminary Analysis of*  
35 *Hudson River Thermal Data*. South Kingstown, RI: Applied Sciences, Inc. and Bedford, NH:  
36 Normandeau Associates, Inc. February 10, 2010. 20 p. Available at <[http://www.dec.ny.gov/  
37 docs/permits\\_ej\\_operations\\_pdf/elecbrdrexhj-k.pdf](http://www.dec.ny.gov/docs/permits_ej_operations_pdf/elecbrdrexhj-k.pdf)> (accessed January 11, 2012).
- 38 Swanson C, D Mendelsohn, N Cohn, D Crowley, Y Kim, L Decker, and L Miller. 2011a. *2010*  
39 *Field Program and Modeling Analysis of the Cooling Water Discharge From the Indian Point*  
40 *Energy Center*. Prepared for Indian Point Entergy Center, Buchanan, NY. South Kingstown,  
41 RI: Applied Science Associates, Inc. January 31, 2011. 132 p. Available at:  
42 <[http://www.dec.ny.gov/docs/permits\\_ej\\_operations\\_pdf/indnpthrmlrpt.pdf](http://www.dec.ny.gov/docs/permits_ej_operations_pdf/indnpthrmlrpt.pdf)> (accessed  
43 January 11, 2012). ADAMS Accession No. ML11189A026.
- 44 Swanson C, D Crowley, Y Kim, N Cohn, and D Mendelsohn. 2011b. *Part 2 of Response to the*  
45 *NYSDEC Staff Review of the 2010 Field Program and Modeling Analysis of the Cooling Water*  
46 *Discharge from the Indian Point Energy Center*. Prepared for Entergy Nuclear Indian Point 2,

## References

- 1 LLC and Entergy Nuclear Indian Point 3, LLC. South Kingstown, RI: Applied Science
- 2 Associates, Inc. March 31, 2011. 27 p. Available at <[http://www.dec.ny.gov/docs/permits\\_ej\\_](http://www.dec.ny.gov/docs/permits_ej_operations_pdf/indnptpart2resp.pdf)
- 3 [operations\\_pdf/indnptpart2resp.pdf](http://www.dec.ny.gov/docs/permits_ej_operations_pdf/indnptpart2resp.pdf)> (accessed January 11, 2012).
- 4 Ziegeweid JR, CA Jennings, and DL Peterson. 2008a. Thermal maxima for juvenile shortnose
- 5 sturgeon acclimated to different temperatures. *Environmental Biology of Fish* 3:299–307.
- 6 Ziegeweid JR, CA Jennings, DL Peterson, and MC Black. 2008b. Effects of salinity,
- 7 temperature, and weight on the survival of young-of-year shortnose sturgeon. *Transactions of*
- 8 *the American Fisheries Society* 137:1490–1499.



1

## 6.0 LIST OF PREPARERS

2 Members of the NRC’s Office of Nuclear Reactor Regulation prepared this SEIS with assistance  
3 from other NRC organizations, as well as contract support from the Pacific Northwest National  
4 Laboratory. Table 6-1 identifies each contributor’s name, affiliation, and function or expertise.

5 **Table 6–1. List of Preparers**

<b>Name</b>	<b>Affiliation</b>	<b>Function or Expertise</b>
<b>NRC</b>		
Jeremy Susco	Nuclear Reactor Regulation	Branch Chief
Michael Wentzel	Nuclear Reactor Regulation	Project Manager
Kimberly Green	Nuclear Reactor Regulation	Project Manager
Dennis Logan	Nuclear Reactor Regulation	Ecology
Briana Balsam	Nuclear Reactor Regulation	Ecology
<b>Contractor</b>		
Valerie Cullinan	Pacific Northwest National Laboratory	Statistics, Ecology
Jeffrey Ward	Pacific Northwest National Laboratory	Ecology





**[Placeholder for NRC Form 335–Bibliographic Data Sheet]**



Federal Recycling Program





**UNITED STATES  
NUCLEAR REGULATORY COMMISSION**  
WASHINGTON, DC 20555-0001  
-----  
OFFICIAL BUSINESS

**NUREG-1437,  
Supplement 38, Vol. 4**

**Generic Environmental Impact Statement for License Renewal of Nuclear  
Plants: Regarding Indian Point Nuclear Generating Unit Nos. 2 and 3**

**June 2012**